Section 401 Water Quality Certification Public Notice

The Central Coast Water Board is currently reviewing an application for the following project for water quality certification under Section 401 of the Clean Water Act. We encourage public comments on the proposed work, which will be considered in the decision on certification. You may submit written comments on this project to:

Central Coast Regional Water Quality Control Board
895 Aerovista Place, Suite 101
San Luis Obispo, CA 93401
Attention: 401 Coordinator
OR
centralcoast@waterboards.ca.gov
Attention: 401 Coordinator

| | |
|---|---|
| **Project Applicant** | Monterey County Water Resources Agency-David E. Chardavoyne |
| **Applicant's Agent** | Monterey County Water Resources Agency-Mark Foxworthy |
| **Project Name** | Moss Landing Tide Gate Permanent Repairs |
| **Receiving Water** | Moro Cojo Slough |
| **City/County** | Moss Landing/Monterey |
| **Public Notice** | May 15, 2017 – June 5, 2017 |
| **Project Description** | The purpose of this project is to restore the leaking Moss Landing Tide Gates facility to its original functionality and prevent any uncontrolled inflow of seawater into the Moro Cojo Slough through the tide gates.<br><br>The project activities include:<br>• Slip lining three existing facility culverts;<br>• Removing gabion rock baskets and sewn geotextile sand bags, both part of January 2017 temporary repairs;<br>• Constructing two concrete end walls;<br>• Placing compacted class 2 base rock behind the tide gate headwall and between the culvert pipes;<br>• Grouting between the existing culvert pipes and the slip line pipes; and<br>• Placing riprap behind the tide gate head wall, over the three culvert pipes.<br><br>Proposed mitigation consists of preserving 50 acres of jurisdictional wetland.<br><br>The County of Monterey filed a Categorical Exemption. |

R:\RB3\Shared\401\Public Notices\Public Notices Monterey Co\2017\PN_R3_MossLandingTideGatePermRepairs_32717WQ14.doc