

**RESOLUTION NO. R3-2002-0051**

**ATTACHMENT—PROPOSED BASIN PLAN AMENDMENTS**

1. Revise the September 8, 1994 Basin Plan, Chapter Four, as follows:

Add the following to chapter 4 under IX TOTAL MAXIMUM DAILY LOADS:

**IX.A MORRO BAY TOTAL MAXIMUM DAILY LOAD FOR SEDIMENT (INCLUDING CHORRO CREEK, LOS OSOS CREEK AND THE MORRO BAY ESTUARY)**

This TMDL was adopted by the Regional Water Quality Control Board on May 16, 2003.

This TMDL was approved by:

The State Water Resources Control Board on September 16, 2003.

The California Office of Administrative Law on December 3, 2003.

The U.S. Environmental Protection Agency on January 20, 2004.

**TMDL ELEMENTS**

| <b>Element</b>           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|--------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Problem Statement</b> | Over time, all estuaries eventually fill with sediment due to the natural processes of erosion and sedimentation. In Morro Bay these natural processes have been accelerated due to anthropogenic watershed disturbances, resulting in impairment of Beneficial Uses, principally biological resources, but also recreational uses, including: RARE, MIGR, SPWN, WILD, EST, MAR, BIOL, REC1, REC2, NAV. This impairment indicates an exceedance of the Basin Plan narrative objective for sediment, which states that: “the suspended sediment load and suspended sediment discharge rate of surface waters shall not be altered in such a manner as to cause nuisance or adversely affect beneficial uses.” |

| Element                                                |                                                                              |                                                                                                         |  |
|--------------------------------------------------------|------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|--|
| Numeric Targets                                        | <b>Parameter</b>                                                             | <b>Numeric Target</b>                                                                                   |  |
|                                                        | <b>Chorro and Los Osos Creeks and Tributaries Streambed Sediment</b>         |                                                                                                         |  |
|                                                        | Residual Pool Volume <sup>1</sup>                                            | V* (a ratio) =<br>Mean values ≤ 0.21 (mean of at least 6 pools per sampling reach)<br>Max values ≤ 0.45 |  |
|                                                        | Median Diameter (D <sub>50</sub> ) of Sediment Particles in Spawning Gravels | D <sub>50</sub> =<br>Mean values ≥ 69 mm<br>Minimum values ≥ 37 mm                                      |  |
|                                                        | Percent of Fine Fines (< 0.85 mm) in Spawning Gravels                        | Percent fine fines ≤ 21%                                                                                |  |
|                                                        | Percent of Coarse Fines (all fines < 6.0 mm) in Spawning Gravels             | Percent coarse fines ≤ 30%                                                                              |  |
|                                                        | <b>Morro Bay and Estuary</b>                                                 |                                                                                                         |  |
|                                                        | Tidal Prism Volume                                                           | 4,200 acre-feet                                                                                         |  |
|                                                        |                                                                              |                                                                                                         |  |
| Loading Allocations<br>(TMDL expressed as annual load) | <b>Watershed</b>                                                             |                                                                                                         |  |
|                                                        |                                                                              | <b>Total<br/>(tons/year,<br/>rounded to nearest ton)</b>                                                |  |
|                                                        |                                                                              |                                                                                                         |  |
|                                                        | Chorro Creek at Reservoir                                                    | 6,541                                                                                                   |  |
|                                                        | Dairy Creek                                                                  | 440                                                                                                     |  |
|                                                        | Pennington Creek                                                             | 966                                                                                                     |  |
|                                                        | San Luisito Creek                                                            | 7,315                                                                                                   |  |
|                                                        | San Bernardo Creek                                                           | 10,269                                                                                                  |  |
|                                                        | Minor Tributaries                                                            | 4,489                                                                                                   |  |
|                                                        | <b>Chorro Creek</b>                                                          | 30,020                                                                                                  |  |
|                                                        | Los Osos Creek                                                               | 3,052                                                                                                   |  |
|                                                        | Warden Creek and Tributaries                                                 | 1,812                                                                                                   |  |
|                                                        | <b>Los Osos Creek</b>                                                        | 4,864                                                                                                   |  |
|                                                        | <b>Morro Bay Watershed</b>                                                   | 34,885                                                                                                  |  |

<sup>1</sup> Residual Pool Volume refers to the portion of a pool in a stream that is available for fish to occupy. Pool habitat is the primary habitat for steelhead in summer. Overwintering habitat requirements include deeper pools, undercut banks, side channels, and especially large, unembedded rocks, which provide shelter for fish against the high flows of winter. V\* gives a direct measurement of the impact of sediment on pool volume. It is the ratio of the amount of pool volume filled in with fine, mobile sediment, to total scour pool volume. Qualifying pools are those having a gradient less than 5%, a minimum depth twice the riffle-crest depth, a fairly even spacing between tributaries, and are located on streams fifth order or smaller.

|                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|-------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Implementation</b>   | <p>The sediment load to Morro Bay, Los Osos Creek and Chorro Creek derives from nonpoint sources (NPS) and point sources. As such, implementation will rely on the State's Plan for NPS pollution control (CWC §13369) and continued implementation of existing regulatory controls as appropriate for point sources, including storm water pursuant to NPDES surface water discharge regulations and Waste Discharge Requirements (Porter Cologne).</p> <p>At this time, implementation emphasizes the activities of the Morro Bay National Estuary Program, Coastal San Luis Resources Conservation District, and other public and private groups that are not currently identified as dischargers responsible for sediment loading, to implement self-determined activities (see Table: Trackable Implementation Actions). Other actions, currently required because of another program, will be evaluated to make sure progress is taking place (see Table: Trackable Implementation Actions identifying Responsible Dischargers). Regional Board Staff will meet annually with the implementing parties identified in the list of Trackable Implementation Actions to provide technical assistance and to evaluate and track progress (see Implementation Schedule for details). If at the end of year three, implementing parties fail to complete these self-determined activities or resulting management practices fail to reduce sediment loads, then Regional Board staff may conduct inspections and investigations to identify individual responsible dischargers (e.g., landowners or public agencies). Regional Board staff may rely on Section 13267 of the California Water Code for investigation and identification of individual responsible dischargers. Regional Board staff will also rely on Section 13267 of the California Water Code to require reporting and/or monitoring to determine the level of implementation of identified activities to reduce erosion and sediment. If necessary, the Regional Board may rely on enforcement authority, pursuant to California Water Code Section 13304, to require dischargers to clean-up and abate sediment discharges and/or prevent the threat of discharges on a case-by case basis. Additionally, Implementation Actions (in the Table of Implementation Actions) may be identified as conditions of compliance with storm water permits and Waste Discharge Requirements.</p> <p>The Implementation Actions identified do not identify the specific management practices that will result in reduced sediment loads. As such, the management practices developed through pursuit of the Implementation Actions are not intended to be independently enforceable by the Regional Board. Therefore, the Regional Board will rely on scheduled 3-year reviews to track Implementation Actions and the effectiveness of management practices to determine whether to continue with self-determined implementation. If progress towards erosion and sedimentation reduction is not satisfactory, staff will develop a regulatory approach (rather than a self-determined approach) and present it to the Regional Board as a revised Basin Plan Amendment, or establish requirements on a case-by-case basis.</p> <p>Direct measurement of sediment loading is not proposed for this TMDL. Numeric Targets, which characterize the effect of loading are to be measured in lieu of loadings. The 50-year schedule for achieving the TMDL acknowledges that implementation actions taken in the near term are expected to take years to produce a response as measured through Numeric Target monitoring.</p> <p>Numeric targets and other parameters will be monitored to ensure that numeric targets are met. The Regional Board will rely on existing or planned efforts for this monitoring (e.g., Morro Bay National Estuary Program, Central Coast Ambient Monitoring Program).</p> |
| <b>Margin of Safety</b> | <p>An implicit margin of safety has been incorporated into this TMDL through the use of conservative assumptions throughout the source analysis and characterization of beneficial use impacts. The margin of safety is required due to uncertainty in calculations of sediment loading and of the effects of this loading on beneficial uses of the Morro Bay Estuary, Chorro Creek and Los Osos Creek.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |

Trackable Implementation Actions

| PROJECT NAME |                                                        | ACTION                                                                                                                                                      | SCHEDULE                        | IMPLEMENTING PARTY                                                                                |
|--------------|--------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|---------------------------------------------------------------------------------------------------|
| 1            | Hollister Ranch Acquisition                            | Design and construct floodplain restoration project                                                                                                         | January 2002-May 2005           | CSLRCD and MBNEP                                                                                  |
| 2            | Los Osos Creek Wetland Restoration Project             | Design and construct Los Osos Creek wetland restoration project                                                                                             | Fall 2000-Spring 2004           | CSLRCD and MBNEP                                                                                  |
| 3            | Watershed Crew Curriculum                              | Develop a curriculum that will provide training for a year-round crew of Civilian Conservation Corps                                                        | Winter 2001-Fall 2001           | CCC                                                                                               |
| 4            | Catalogue of Erosion Control Projects                  | Develop a list of areas in need of erosion control projects                                                                                                 | Spring 2001-Fall 2001; on-going | MBNEP                                                                                             |
| 5            | Project Clearwater                                     | Provide technical assistance and cost sharing to install BMPs                                                                                               | 2001-June 2004; on-going        | CSLRCD                                                                                            |
| 6            | Agricultural Water Quality Program                     | Develop and implement a voluntary, cost-effective, and landowner/manager-directed program                                                                   | 2001-2002; on-going             | Farm Bureau                                                                                       |
| 7            | Land Acquisitions and Conservation Easements           | Acquire or otherwise protect lands in cooperation with willing land owners                                                                                  | 2000-2010; on-going             | MBNEP                                                                                             |
| 8            | Fire Management Plan                                   | Develop and implement a Fire Management Plan                                                                                                                | 2001-2006; on-going             | CDF                                                                                               |
| 9            | Maintenance of Sediment Basins Above Chorro Reservoir  | Continue maintenance of the sediment basins above Chorro Reservoir                                                                                          | on-going                        | California Army National Guard                                                                    |
| 10           | Road Maintenance                                       | Increase the use of management measures for road maintenance and construction                                                                               | 2001-2006; on-going             | County of San Luis Obispo, Public and Private Landowners; California Department of Transportation |
| 11           | Sediment Traps                                         | Install sediment traps                                                                                                                                      | 2000-2007; on-going             | CSLRCD; Natural Resource Conservation Service; DFG; Public and Private Land Owners                |
| PROJECT NAME |                                                        | ACTION                                                                                                                                                      | SCHEDULE                        | RESPONSIBLE DISCHARGERS                                                                           |
| 12           | Primera Mine Rehabilitation and Erosion Control        | Remediation of Primera Mine                                                                                                                                 | 2003                            | California Army National Guard                                                                    |
| 13           | Stormwater Sediment Control on Roads                   | Include specific road sediment control measures in County stormwater management plan prior to enrollment in Stormwater Permit; track implementation of BMPs | Prior to March 2003; on-going   | County of San Luis Obispo                                                                         |
| 14           |                                                        | Track implementation of BMPs in Stormwater Permit                                                                                                           | On-going                        | Caltrans                                                                                          |
| 15           | Water Quality Management Plans on Chorro Creek Ranches | Implement Waste Discharge Requirements to address Chorro Creek Ranches                                                                                      | Fall 2002-Fall 2003             | California Polytechnic State University                                                           |

**Implementation Schedule**

| At End of Implementation Year: | IMPLEMENTATION MILESTONE                                                                                                                                                                                    |                       |                                                           | MONITORING ACTIVITY                                    |                       |                   |
|--------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|-----------------------------------------------------------|--------------------------------------------------------|-----------------------|-------------------|
|                                | <i>Chorro Creek</i>                                                                                                                                                                                         | <i>Los Osos Creek</i> | <i>Morro Bay</i>                                          | <i>Chorro Creek</i>                                    | <i>Los Osos Creek</i> | <i>Morro Bay</i>  |
| 1                              | RB and MBNEP Staff meet to review progress.<br>RB and County Staff meet to review inclusion of road erosion control measures in Stormwater Management Plan.                                                 |                       |                                                           | Baseline Streambed Parameters <sup>2</sup> , Turbidity |                       |                   |
| 2                              | <i>As above</i>                                                                                                                                                                                             |                       |                                                           |                                                        |                       |                   |
| 3                              | RB and MBNEP Staff meet to review progress;<br>RB requests implementation tracking report from Implementing Parties if not provided;<br>RB staff consider modifications to Trackable Implementation Actions |                       |                                                           | Baseline Streambed Parameters, Turbidity               |                       |                   |
| 4                              | RB and MBNEP Staff meet to review progress                                                                                                                                                                  |                       |                                                           | Baseline Streambed Parameters, Turbidity               |                       |                   |
| 5                              | RB and MBNEP Staff meet to review progress                                                                                                                                                                  |                       | RB Staff calculate: 5-year changes to Bay area and volume | Baseline Streambed Parameters, Turbidity               |                       | Bathymetry survey |
| 6                              | RB and MBNEP Staff meet to review progress;<br>RB request implementation tracking report from Implementing Parties if not provided;<br>RB staff consider modifications to Trackable Implementation Actions  |                       |                                                           | Baseline Streambed Parameters, Turbidity               |                       |                   |
| 7                              | RB and MBNEP Staff meet to review progress                                                                                                                                                                  |                       |                                                           | Baseline Streambed Parameters, Turbidity               |                       |                   |
| 8                              | <i>As above</i>                                                                                                                                                                                             |                       |                                                           |                                                        |                       |                   |
| 9                              | RB and MBNEP Staff meet to review progress;<br>RB request implementation tracking report from Implementing Parties if not provided;<br>RB staff consider modifications to Trackable Implementation Actions  |                       |                                                           | Baseline Streambed Parameters, Turbidity               |                       |                   |
| 10                             | RB and MBNEP Staff meet to review progress;<br>RB Staff calculate 10-year rolling average of Streambed Sediment data                                                                                        |                       | RB Staff calculate: 5-year changes to Bay area and volume | Baseline Streambed Parameters, Turbidity               |                       | Bathymetry survey |
| 11                             | RB and MBNEP Staff meet to review progress;<br>RB Staff calculate 10-year rolling average of Streambed Sediment data                                                                                        |                       |                                                           | Streambed Parameters, Turbidity                        |                       |                   |

<sup>2</sup> Streambed Parameters include: Residual Pool Volume; Median Diameter of Sediment Particles; Percent Fine Sediment; Percent Coarse Sediment. (See discussion of Numeric Targets).

| At End of Implementation Year: | IMPLEMENTATION MILESTONE                                                                                                                                                                                                                                                             |                                                           | MONITORING ACTIVITY             |                   |
|--------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------|---------------------------------|-------------------|
| 12                             | RB and MBNEP Staff meet to review progress;<br>RB Staff calculate 10-year rolling average of Streambed Sediment data;<br>RB request implementation tracking report from Implementing Parties if not provided;<br>RB staff consider modifications to Trackable Implementation Actions |                                                           | Streambed Parameters, Turbidity |                   |
| 13                             | RB and MBNEP Staff meet to review progress;<br>RB Staff calculates 10-year rolling average of Streambed Sediment data                                                                                                                                                                |                                                           | Streambed Parameters, Turbidity |                   |
| 14                             | <i>As above</i>                                                                                                                                                                                                                                                                      |                                                           |                                 |                   |
| 15                             | RB and MBNEP Staff meet to review progress;<br>RB Staff calculate 10-year rolling average of Streambed Sediment data;<br>RB request implementation tracking report from Implementing Parties if not provided;<br>RB staff consider modifications to Trackable Implementation Actions | RB Staff calculate: 5-year changes to Bay area and volume | Streambed Parameters Turbidity  | Bathymetry survey |
| 16-49                          | <i>Repeat as above with 3-, 5- and 10-year milestones.</i>                                                                                                                                                                                                                           |                                                           |                                 |                   |
| 50                             | <b>Numeric targets achieved; load reduction achieved</b>                                                                                                                                                                                                                             |                                                           |                                 |                   |