

Berths 302 to 306 [APL] Container Terminal Project

Final Environmental Impact Statement/ Environmental Impact Report



May 2012

Prepared by:

Los Angeles Harbor Department
Environmental Management Division
425 S. Palos Verdes Street
San Pedro, CA 90731

With assistance from:



ADP No. 081203-131
SCH No. 2009071031



US Army Corps
of Engineers

1
2

3 **1.1 Final EIS/EIR Organization**

4 This chapter presents background and introductory information for the proposed Project,
5 Berths 302-306 [APL] Container Terminal Project, located in the industrial area of the
6 Fish Harbor region of Terminal Island, within the Port of Los Angeles (Port).
7 Additionally, this chapter discusses general changes and modifications made to the Draft
8 Environmental Impact Statement/ Environmental Impact Report (EIS/EIR), which are
9 mostly editorial in nature. Chapter 2, “Responses to Comments,” presents information
10 regarding the distribution of and comments on the Draft EIS/EIR, and the responses to
11 these comments. Chapter 3, “Modifications to the Draft EIS/EIR,” presents the
12 modifications to the Draft EIS/EIR.

13 This Final EIS/EIR has been prepared in accordance with the requirements of the
14 National Environmental Policy Act (NEPA) (42 United States Code [USC] 4341 et seq.),
15 and in conformance with the Council for Environmental Quality (CEQ) Guidelines and
16 the United States Army Corps of Engineers (USACE) NEPA Implementing Regulations.
17 The document also fulfills the requirements of the California Environmental Quality Act
18 (CEQA) (California Public Resources Code [PRC] 21000 et seq.), the State CEQA
19 Guidelines (California Code of Regulations [CCR] 15000 et seq.). The USACE is the
20 NEPA lead agency for this proposed Project, and the Los Angeles Harbor Department
21 (LAHD) is the CEQA lead agency.

22 **1.2 Project Background**

23 This section describes the proposed Project. A description of alternatives to the proposed
24 Project is provided in Section 2 of the Draft EIS/EIR. The proposed Project is the
25 improvement and expansion of an existing container terminal that would facilitate the
26 transfer of shipping containers between ocean-going vessels and ground transportation
27 modes such as trucks and trains.

28

1 The proposed Project area (see Figure 1-1) encompasses approximately 347 acres at the
2 Pier 300 area of Terminal Island, including the 291-acre existing APL Terminal area and
3 a 56-acre expansion area.¹ Forty-one of the 56 acres of expansion area constitute the fill
4 area described above, that resulted from the Channel Deepening Project.

5 Physical improvements proposed at the existing APL Terminal include adding cranes,
6 modifying the main gate (conversion of existing outbound lanes to inbound lanes and the
7 relocation of out gates), converting a portion of the existing dry container storage unit
8 area to a refrigerated container storage area with a permanent distributed electrical power
9 source, replacement of the existing roadability inspection facility where container
10 transport trucks are inspected after arriving containers are attached to the trailer,
11 expanded power shop facilities to facilitate tractor maintenance and marine office space,
12 and installation of necessary infrastructure improvements.


13 The proposed expansion of the terminal includes usage of 41 acres of new terminal
14 container backlands on previously constructed (but currently unimproved and unused)
15 landfill, nine acres at the former Los Angeles Export Terminal (LAXT) site, two acres of
16 existing land northeast of the main gate, and four acres of new wharf area to create Berth
17 306. Improvements within the expansion areas would include: extension of the existing
18 concrete wharf to the east by 1,250 linear feet (lf) with Alternative Maritime Power
19 (AMP) facilities and new cranes, paving and infrastructure to support traditional/diesel-
20 powered equipment operations, electric equipment operations, and potential automated
21 operations within the new Berth 306 backlands; development of a new out-gate location;
22 and additional parking area in Berth 301 backlands.

23 The proposed Project includes dredging at the new Berth 306, which is at various depths
24 in the low fifties, to a depth of -55 feet (ft) mean lower-low water level (MLLW) plus
25 two ft of overdredge. Depending upon the quality of the dredge sediments and site
26 availability, dredged material would be beneficially reused and/or disposed of at an
27 approved disposal site (such as the Confined Disposal Facility [CDF] at Berths 243-245
28 and/or Cabrillo shallow water habitat). If these sites are unavailable or impracticable, an
29 ocean disposal site (LA-2) could be considered assuming the material was approved for
30 such use by the Los Angeles Regional Dredged Material Management Team (DMMT).

31 Currently Eagle Marine Services, LTD (EMS) operates the existing 291 acre APL
32 Terminal. The Terminal includes 261 acres covered by an existing lease (LAHD Permit
33 No. 733) and an additional approximately 30 acres of adjacent backlands authorized for
34 use under a month-to-month space assignment (Non-Exclusive Berth Assignment
35 No. 01-31). The proposed Project would make available an additional 56 acres which
36 would be operated by EMS under an amendment to the existing LAHD Permit No. 733.
37 In addition, EMS would continue to utilize the 30 acres currently authorized for use
38 under the month to month Non-Exclusive Berth Assignment No. 01-31. The term of the
39 amended permit would remain unchanged (1998 to 2027), but the permit would be
40 amended to include the additional 56 acres.

41


¹ Unless otherwise noted, all project areas, lengths and volumes are approximates.



**CDM
Smith**

Legend

 Existing Terminal



**Port of Los Angeles
Berths 302 - 306 [APL]
Container Terminal Project
Project Site and Vicinity**

Figure 1-1

1.3 Existing Conditions

1.3.1 Regional Context



The Port Complex, located in the San Pedro Bay approximately 20 miles south of downtown Los Angeles, serves as one of the Nation's primary gateways for international trade (Figure 1-2). International trade is a key economic engine for the local region and the country. The Port Complex serves as a vital link in the goods movement chain delivering goods for our local market as well as those shipped by truck and rail throughout the country. The Port Complex serves as the country's primary gateway for Asian-based trading partners. Approximately half of the cargo coming through the Ports is delivered by truck to the regional market, which is an area roughly 500 to 700 miles from the Port (refer to Section 1.2.2.2.1.1 and Figure 1-5 in Chapter 1, Introduction, of the Draft EIS/EIR for additional information). The local freeways that directly serve the Port are the I-110, I-710, SR-47, and SR-103. Goods destined for national markets beyond this area are delivered primarily by rail. The Alameda Corridor is the primary rail line between the Port and downtown railyards. Other rail lines extend from the Downtown area north and east.

1.3.2 Project Setting

The Port consists of 28 miles of waterfront, approximately 300 commercial berths, and 7,500 acres of land and water. The Port is administered under the California Tidelands Trust Act of 1911 by the LAHD. The LAHD is chartered to develop and operate the Port to benefit maritime uses, and it functions as a property owner by leasing Port properties to more than 300 tenants. The Port contains 27 major cargo terminals, including facilities to handle automobiles, containers, dry bulk products, liquid bulk products, and cruise ships, as well as extensive transportation infrastructure for cargo movement by truck and rail. The Port accommodates commercial fishing, canneries, shipyards, and boat repair yards; provides slips for 6,000 pleasure craft, sport fishing boats, and charter vessels; and supports community and educational facilities such as a public swimming beach, the Boy/Girl Scout Camp, the Cabrillo Marine Aquarium, and the Maritime Museum.

1.3.3 Project Site and Surrounding Uses

The proposed Project site is located on Terminal Island, within an industrial area in the vicinity of Fish Harbor. The site is within the Port of Los Angeles Community Plan area of the City of Los Angeles, which is adjacent to the communities of San Pedro and Wilmington. Four bridges provide vehicular and rail access to Terminal Island from the mainland: the Vincent Thomas Bridge, the Schuyler Heim Bridge, the Gerald Desmond Bridge, and the Badger Avenue Railroad Lift Bridge. The existing APL Terminal is located on Pier 300. It occupies approximately 291 acres and includes: 4,000 ft of wharf with four labeled berths (Berths 302 through 305); an on-dock railyard that can accommodate up to 64 five-platform double-track railcars (equivalent to nearly three full trains); two dedicated lead rail tracks with flexible entrance/exit points off the main rail line within the Alameda Corridor; a transloading dock; a gate complex that includes an intermodal control tower; 10 inbound and 10 outbound lanes; automobile parking facilities; two marine buildings; 600 refrigerated container plugs; a washdown facility for refrigerated container units and trucks; and maintenance and repair facilities consisting of



1 a chassis shop (approximately 30,000 square feet [sf]) and a Power Shop (approximately
2 22,000 sf). Existing equipment and facilities on the proposed Project site include: 12 A-
3 frame 100'-gauge cranes along the south-facing wharves, along with mobile equipment
4 used to handle containers. Current cargo-handling equipment consists of approximately
5 36 forklifts, 7 side picks, 19 top handlers, 8 Rubber Tire Gantry (RTG) cranes, 10 Rail
6 Mounted Gantry (RMG) cranes, and 195 yard tractors. Figure 1-3 shows key features of
7 the existing container terminal.

8 With respect to surrounding uses, the proposed Project site is generally bounded as
9 follows:

- 10 ▪ On the north by Terminal Way, Seaside Avenue, the Terminal Island Water
11 Reclamation Plant, the vacant former LAXT facility, Mobil Oil Corp facilities, the
12 U.S. Custom House, the Port Fire Station 40, the Terminal Island Container Transfer
13 Facility and associated rail tracks, and a dry bulk terminal remote storage area;
- 14 ▪ On the east by the Pier 300 Shallow Water Habitat, Navy Way, and Sea Plane
15 Lagoon;
- 16 ▪ On the west by Earle Street, the Los Angeles Yacht Club, Starkist Foods Inc., Pan
17 Pacific Fisheries, Tri-Union Fish Company Fish Harbor, and the Main Channel; and
- 18 ▪ On the south by the Pier 300 Channel and the Outer Los Angeles Harbor.

19 Slightly farther to the south is the 484-acre APM Terminals/Pier 400 area, which hosts
20 six berths, backland operations, and on-dock rail operations. Heavy port industries also
21 occur to the north, east, and west. Farther to the north and west are the communities of
22 Wilmington, Harbor City, and San Pedro, respectively.

23 **1.3.4 Historic Use of the Project Site**

24 Most of the proposed Project site is part of landfill created by the placement of dredge
25 material removed from the Los Angeles Harbor for the Los Angeles Harbor Deepening
26 Project in 1981-1983. Since then, the container terminal site has been the subject of
27 several improvement projects to consolidate landfill material.

28 Prior to development of the site as a commercial marine terminal, the general area was
29 under the control of the U.S. Navy and used for the Naval Reserve Training Center. A
30 Naval Air Station, known as Reeves Field, was also established on the site. Reeves Field
31 was decommissioned in 1947. Following use by the Navy, the area was used to store dry
32 bulk goods (including petroleum coke), and used to support institutional and industrial
33 uses (Port of Los Angeles [POLA], 1979). Other uses included sludge-drying beds (22
34 acres) by the City of Los Angeles Department of Public Works' Bureau of Sanitation and
35 use by the Los Angeles Police Department for police driver training. A large portion of
36 the proposed Project site was created as the 190-acre fill area after the Port Master Plan
37 was certified in 1980. Dredge material from the Harbor Deepening Project was used to
38 create the 190-acre fill area that underlies the majority of the existing APL Terminal.
39 The proposed Project site was subsequently developed as the APL Terminal, which
40 opened in 1997.


41



- Legend**
- ① Guard Booth
 - ② Chassis Shop
 - ③ Gatehouse
 - ④ Reefer Wash
 - ⑤ Compressed Air Plant
 - ⑥ Transload Office and Dock
 - ⑦ Roadability Canopy
 - ⑧ Genset Building
 - ⑨ Secondary Marine Building
 - ⑩ Primary Marine Building
 - ⑪ Security Office
 - ⑫ Power Shop
 - ⑬ Fuel Facility



Legend
 Existing Terminal



**Port of Los Angeles
 Berths 302 - 306 [APL]
 Container Terminal Project
 Project Site - Existing Conditions
 Buildings
 Figure 1-3**

1 In 1998, the Port approved the Channel Deepening Project, which removed millions of
2 cubic yards (cy) of sediment from the Los Angeles Main Channel, West Basin, East
3 Channel, and East Basin, and disposed of it in various locations. In 2000, the Port
4 approved additional disposal sites for sediments associated with the Channel Deepening
5 Project. Approximately 1.6 million cy of the dredge materials was used to expand a
6 number of areas in the Port, including the approximate 41 acre landfill expansion of Pier
7 300.

8 To the west of the APL Terminal are portions of the former LAXT facility. The former
9 LAXT facility at the Port opened in 1997 for the purpose of loading petroleum coke and
10 coal onto ships bound for power plants in Asia. Coal from the western United States was
11 transported by rail to LAXT and stored in large hemispherical silos constructed at the
12 north end of the Port. The coal would then be transported approximately 1.25 miles by a
13 covered conveyor, generally parallel to Terminal Way and Earle Street, to a specialized
14 conveyor crane that loaded the coal on to ships at Berth 301. LAXT operations within
15 the backlands area at Berth 301 included a large metal silo that provided short-term
16 storage of coal to be loaded on an arriving ship. This facility could also receive and store
17 coal delivered by truck. The backlands area also included two warehouse/maintenance
18 buildings, an administrative/operations office, a power substation, a surface water
19 impoundment area, and an open area for equipment/container storage. Based on a change
20 in the global market for coal (i.e., increased availability of coal from Australia and other
21 places in Asia closer to where the coal was needed) and other business issues, LAXT
22 operations at the Port ceased in Fiscal Year 2003. In late 2006, LAXT's permit to lease
23 and operate at the Port was relinquished and the miscellaneous former LAXT structures
24 and enclosed conveyer were removed from the area adjacent to the proposed Project site.
25 However, various former LAXT paved areas and a settling pond remain on the
26 approximately 7-acre upland area behind Berth 301, as does the power substation. As
27 part of the proposed Project, the Berth 301 backlands would be used for parking and
28 miscellaneous storage.

29 1.4 Project Purpose

30 The LAHD operates the Port under the legal mandates of the Port of Los Angeles
31 Tidelands Trust (Los Angeles City Charter, Article VI, Section 601) and the California
32 Coastal Act (PRC Division 20 Section 30700 *et seq.*), which identify the Port and its
33 facilities as a primary economic and coastal resource of the State of California and an
34 essential element of the national maritime industry for the promotion of commerce,
35 navigation, fisheries, and Harbor operations. Activities should be water dependent and
36 the LAHD must give highest priority to navigation, shipping, and necessary support and
37 access facilities to accommodate the demands of foreign and domestic waterborne
38 commerce. The LAHD is chartered to develop and operate the Port to benefit maritime
39 uses, and it functions as a landlord by leasing Port properties to more than 300 tenants.

40 The proposed Project is needed to meet a portion of the Port's projected container
41 throughput demand for the year 2035. In 2007, studies projected Port container
42 throughput demand within the San Pedro Bay Ports Complex of Los Angeles and Long
43 Beach (Port Complex) would be constrained at 43.2 million twenty-foot equivalent units
44 (TEUs) by 2023; however, this projection was revised in 2009 to take into account a
45 prolonged economic downturn, which negatively impacted global trade and resulted in
46 dramatically reduced actual container throughput and future growth projections. As a
47 result, current projections now estimate that, assuming planned capacity expansions and

1 handling efficiency improvements occur, the Port Complex throughput capacity
2 constraints would be experienced in 2035 at 43.2 million TEUs, twelve years later than
3 expected in the 2007 study. The revised projection assumes completion of planned
4 physical and operational improvements to terminals within the Port Complex, including
5 the proposed Project.

6 Providing the capacity needed to manage the projected level of cargo throughput is
7 critical for the Port to fulfill its role of facilitating trade along the Pacific Rim, which is
8 expected to grow with anticipated increases in population and foreign trade. The Port
9 also is instrumental to the regional and national markets.²

10 Additionally, a purpose of the proposed Project is to optimize and expand the cargo
11 handling capacity at the APL Terminal to accommodate the increased throughput demand
12 expected at the Port, including at the APL Terminal, in the long-term, while also
13 maintaining consistency with established Port policies pertaining to the environment.
14 This objective would be accomplished through expansion and improvement of the
15 existing Berths 302-305 marine terminal from the current 291 acres to approximately 347
16 acres, including extension of the existing wharf by 1,250 ft (creating Berth 306), to
17 accommodate an annual throughput of approximately 3.2 million TEUs by 2027.

18 The expansion and optimization of Pier 300 has been contemplated and analyzed in
19 evaluations prepared for the Port, including Port Plan, Port Master Plan (as amended),
20 and the *Channel Deepening Supplemental EIS/EIR*.

21 1.4.1 CEQA Objectives

22 The LAHD's overall goal for the proposed Project is threefold: (1) provide a portion of
23 the facilities needed to accommodate the projected long-term growth in the volume of
24 containerized cargo through the Port and at the APL Terminal; (2) implement the Port's
25 green growth strategy, which includes growing core operations while greening to mitigate
26 the environmental impacts of that growth on the local communities and the Los Angeles
27 region; and (3) carry out the Port Strategic Plan to maximize the efficiency and capacity
28 of terminals while raising environmental standards through application of all feasible
29 mitigation measures. The Port's green growth strategy relies on utilizing pollution
30 control measures included in the Clean Air Action Plan (CAAP), sustainable lease
31 agreements, and other sustainability measures.

32 To meet the overall Project purposes, the following objectives need to be accomplished:

- 33 ■ Optimize the use of existing land at Berths 302-305, the proposed Berth 306
34 backlands, and associated waterways in a manner that is consistent with the LAHD's
35 public trust obligations;

² It should be noted that the previously cited forecast and capacity studies are Port-wide studies and do not consider the market conditions of individual shipping companies and terminal operators. There are competitive differences between container terminals within the Ports, and each terminal's market share will reflect these differences at any given point in time.

- 1 ▪ Improve the container terminal at Berths 302-306 to more efficiently work larger
2 ships and to ensure the terminal’s ability to accommodate increased numbers and
3 sizes of container ships;
- 4 ▪ Increase accommodations for container ship berthing, and provide sufficient
5 backland area and associated improvements for optimized container terminal
6 operations, at Berths 302-306;
- 7 ▪ Incorporate modern backland design efficiencies into improvements to the existing
8 vacant landfill area at Berth 306; and
- 9 ▪ Improve the access into and out of the terminal and internal terminal circulation, at
10 Berths 302-306 to reduce the time for gate turns and to increase terminal efficiency.

11 **1.4.2 NEPA Purpose and Need**

12 As discussed above and in Chapter 1 of the Draft EIS/EIR, implementation of the
13 proposed Project is needed to provide the terminal capacity to accommodate the long-
14 term future cargo demand projected for the Port. The proposed Project would meet a
15 public need for economic growth in trade and import/export of goods, as well as a need
16 for efficiency in cargo handling at the Port.

17 The overall purpose of the proposed Project is to optimize the cargo handling efficiency
18 and capacity at the APL Terminal to accommodate projected long-term increases in
19 volume of containerized goods shipped through the Port. As the proposed Project is
20 water dependent, optimizing the terminal’s efficiency would improve marine shipping
21 and maritime trade. The overall project purpose serves as the foundation of the USACE
22 Section 10 and Section 103 analyses. Under Section 10, the USACE will conduct public
23 interest review (per 33 CFR 320.4).

24 In general, the scope of federal review for evaluating the potential impacts of a proposed
25 project is focused on those aspects of the project that the affected federal agency has
26 jurisdiction over. The USACE has jurisdiction over activities affecting navigable waters
27 and other waters of the U.S., as well as any ocean transport and disposal activities
28 involving dredged material. As such, the primary focus of USACE’s review of the
29 proposed Project is on those activities that directly or indirectly affect the aquatic
30 environment, such as dredging and any associated in-water reuse or ocean transport and
31 disposal activities, and construction of new wharf/pier facilities. The scope of USACE
32 review does, however, include other related aspects, including some activities in upland
33 (non-water) areas, such as staging and storage of materials along the shoreline required to
34 complete in-water and over-water activities, and operations. Following is a summary of
35 how the USACE’s scope of federal review is typically defined, and Figure 1-4 illustrates
36 the scope for this Project.

37 **1.4.3 Federal Scope of Analysis**

38 Under federal law, “the [USACE] district engineer should establish the scope of the
39 NEPA document to address the impacts of the specific activity requiring the Department
40 of the Army (DA) permit and those portions of the entire project over which the district
41 engineer has sufficient control and responsibility to warrant Federal review” (33 C.F.R.
42 Part 325 Appendix B). The four factors considered in determining “sufficient control and
43 responsibility” include:

- 1) Whether or not the regulated activity comprises merely a link in a corridor-type project
- 2) Whether there are aspects of the upland facility in the immediate vicinity of the regulated activity that affect the location and configuration of the regulated activity
- 3) The extent to which the entire project will be within USACE jurisdiction
- 4) The extent of cumulative federal control and responsibility

Therefore, determining the federal scope of analysis for the proposed Project involves evaluating all four factors. The “impacts of the specific activity requiring the DA permit” are the direct impacts (i.e., those regulated impacts occurring in, over, and/or under waters of the U.S.); while indirect impacts are those impacts occurring in the upland portions of the project area over which there is sufficient federal control and responsibility to warrant inclusion in the federal scope of analysis.

With respect to the first factor, the proposed Project is a container terminal expansion project, which consists of wharves, associated cranes, backlands/container yard, and entry/exit infrastructure. Thus, it is not “merely a link” in a corridor-type project, such as a highway or a utility line crossing.

Considering the second factor, as an existing container terminal in the Port of Los Angeles, there is a physical link between the upland container yard/backlands and the adjacent wharves and associated cranes in and over waters of the U.S. that service APL’s approved third-party ships, which move containers into and out of the port. While this consideration might suggest expanding the scope of analysis to include the upland container yard/backlands, the existing APL Terminal is a fully functioning, approximately 300-acre container terminal that has been operating at this location for many years, and, as such, many of the upland impacts that would occur at the site under the proposed Project represent continuations of impacts that are already occurring and would occur regardless of whether the USACE regulated activities are implemented, as well as growth in operations at the existing terminal up to the point at which the terminal reaches its capacity. The exception is the improvement of the 41-acre landfill adjacent to the southeast corner of the existing terminal which was created by the Channel Deepening Project in 2005. While this area could be used for temporary storage of containers without federal action, the proposed Project includes developing it as a permanent backland feature, as well as developing the adjacent new Berth 306.

Because the existing APL Terminal is a fully functional, operating terminal with previous and ongoing air, traffic, biological resource, water resource, and other impacts occurring over the majority of the terminal site, it is unlike the new shipping terminal example provided in 33 CFR 325 Appendix B Section 7(b)(3) (“...a shipping terminal normally requires dredging, wharves, bulkheads, berthing areas and disposal of dredged material in order to function. Permits for such activities are normally considered sufficient Federal control and responsibility to warrant extending the scope of analysis to include the upland portions of the facility”).

In evaluating the third factor, the extent of waters of the U.S. that would be affected by the proposed Project it was concluded that the proposed Project would affect a relatively

1 small portion (approximately 5 acres to create Berth 306, including construction dredging)
2 of the approximately 350-acre project area.

3 For the fourth factor, other than the requirement to obtain a USACE permit, there is no
4 other federal involvement on this site, such as use, transfer, or sale of federal property;
5 federal funding including cost sharing, guarantee, or financial assistance; or the
6 involvement of federally listed historic resources, threatened or endangered species,
7 designated critical habitat, or other federally recognized natural resource areas, which
8 would suggest that broadening the federal scope of analysis is warranted. Other federal
9 agencies exert no control over the environmental effects of land development on the
10 upland portions of the proposed Project area. Furthermore, the federal and non-federal
11 portions of the proposed project could exist independently of each other. State and local
12 regulations primarily control the design of the proposed project, and this project is being
13 subject to extensive state environmental review. In short, the environmental
14 consequences of the larger project are not essentially products of the federal action.
15 Rather, they are primarily the product of non-federal interests and designs.

16 Considering all four factors, the USACE has determined that the federal direct and
17 indirect scope of analysis should consist of: 1) work (including construction dredging)
18 and placement of structures in or over waters of the U.S., 2) impacts to the adjacent
19 upland area expected to be used temporarily for staging and storage of equipment and
20 materials to complete the in-water and over-water activities (i.e., an approximately
21 100-foot-wide strip of upland area adjacent to the shoreline), and 3) development and use
22 of the 41-acre landfill constructed as part of the Channel Deepening Project for container
23 terminal operations (shown in Figure 1-4). The federal analysis would also include any
24 ocean transport and disposal of the dredged material to designated ocean disposal site(s),
25 as well as any beneficial reuse of dredged material in waters of the U.S.


26 The USACE has no authority or responsibility to regulate activities, such as upland
27 operations, that are presently occurring or could occur absent a USACE permit. These
28 activities and resulting conditions, therefore, comprise the NEPA Baseline, which is
29 discussed above.

30 **1.5 Proposed Project**

31 This section describes the proposed redevelopment and expansion of the APL Terminal,
32 the anticipated construction phasing, and the anticipated terminal operations once the
33 improvements are completed.

34 Figure 1-3 presents a map of the existing conditions at the proposed Project site, while
35 Figure 1-5 locates the site improvements of the proposed Project at full build-out and
36 optimal capacity (2027).

37



USACE Scope of Federal Review*

- 41 Acres
- New Wharf/Berth 306
- Installation and Operation of 12 New Cranes (Berths 302 to 306)
- 100 Feet from Waters Edge

*Cumulative impact analysis associated with 41 acre backland development and new crane operations extends beyond the delineated direct and indirect impact areas under Federal jurisdiction/review for some issues, such as air quality and traffic.


**Port of Los Angeles
Berths 302 - 306 [APL]
Container Terminal Project
USACE Scope of Federal Review**

Figure 1-4



Legend

- New 41 acres
- New 2 acres
- New 4 acres
- New 2 acres
- New 7 acres
- Existing Terminal



**Port of Los Angeles
Berths 302 - 306 [APL]
Container Terminal Project
Proposed Project**

Figure 1-5

1.5.1 Project Elements

1.5.1.1 Overview

The proposed Project encompasses approximately 347 acres and includes improvements to the existing 291-acre APL Terminal and an expanded area of 56 acres. This section presents a summary of the improvements that would occur within each area, followed by a more detailed description.

Improvements to the existing terminal would:

- Modify the outbound gates associated with the main gate;
- Modify the terminal entrance lanes;
- Modify the Earle Street gate;
- Install up to 4 new cranes at Berths 302-305;
- Convert a portion of the existing dry container storage unit area to a refrigerated container unit (reefer) storage area equipped with plug-in electric power;
- Demolish and re-construct the Roadability facility;
- Expand the Power Shop facilities by constructing and operating a separate two-story Power Shop Annex building (just north of the existing Power Shop), which would include tractor maintenance bays (first floor) and Marine Offices (second floor); and
- Install utility infrastructure at various areas in the existing backlands (including the removal and installation of new light poles, utilities for a new “Meet and Greet” booth on backlands behind Berth 301, etc.).

Proposed expansion-area components would:


- Construct approximately 1,250 lf (4 acres) of concrete wharf to create Berth 306;
- Install up to 8 new cranes on the new wharf at Berth 306;
- Install AMP along the new wharf at Berth 306;
- Dredging at Berth 306; the dredge material (approximately 20,000 cy) will be beneficially reused (as fill), or disposed of at an approved CDF site. If these options are unavailable or impracticable, an existing ocean disposal site could be considered (i.e., LA-2);
- Improve approximately 41 acres of already constructed but unimproved fill as container terminal backland with infrastructure that could support traditional operations, electric equipment operations, as well as potentially automated operations on the Berth 306 backlands (a majority of the new infrastructure would be located adjacent to existing stations or substations near the reefer area of the existing backlands);
- Redevelop approximately 2 acres of the former LAXT conveyor right of way and approximately 7 acres of former LAXT backland behind Berth 301 into container terminal backland; and
- Develop approximately 2 acres of existing land northeast of the current main gate for a new out gate location.

1 **Operation of the Berth 306 Backlands.** The existing APL Terminal operates using
 2 “traditional” methods. Once containers have been off-loaded from a ship or received
 3 through the gates on trucks and trains, the containers are stored and moved around the
 4 backlands area of the terminal using mostly diesel-powered cargo-handling equipment. It
 5 is foreseeable that a technology change could result in replacement of some of the
 6 traditional backland operations at the APL Terminal through the use of an automated
 7 container handling system on the 41-acre backland area adjacent to proposed Berth 306.
 8 If installed, such a system would involve the use of semi-automatic dual hoist electric
 9 shore side gantry cranes, Automated Guided Vehicles (AGVs), electric automated
 10 stacking cranes (ASCs), and semi-automated electric Landside Transfer Cranes (LTCs).
 11 Because it is not certain as to whether or when use of an automated system would
 12 commence, for the purposes of environmental review, the EIS/EIR assumes that either
 13 (1) the terminal would continue to operate using traditional operation throughout the
 14 lease term; or (2) the operation of the 41-acre backland would transition from a
 15 traditional operation (i.e., transport of containers by mostly diesel-powered equipment) to
 16 an automated operation with mostly electric equipment during the lease term. More
 17 discussion of the potential design of the proposed Berth 306 backlands can be found
 18 below in Section 1.5.2.7 Terminal Operations.

19 1.5.1.2 **Shoreline Improvements**

20 **Wharf Area Expansion Improvement**

21 The proposed Project would include construction of approximately 1,250 lf of new wharf
 22 area, encompassing approximately 4 acres that would extend eastward from the existing
 23 Berths 302-305 wharf. Photograph 1 shows a typical berth on the existing wharf at the
 24 APL Terminal.




25
26 **Photograph 1: View of existing wharf, cranes, and berthed vessel**

27 Photograph 2 shows the shoreline area along Berth 306 where the new wharf would be
 28 constructed. No new rock dike or fill would be required, as this area was previously
 29 constructed as part of the Channel Deepening Project, which created the 41-acre
 30 undeveloped fill area along Berths 305 and 306. New wharf construction would,
 31 however, require the placement of approximately 515 new 24-inch-diameter concrete
 32 piles to support the new wharf. These piles would be placed by barge-mounted pile

1 drivers that would be brought to the site by tugboat and temporarily supported by a wharf
2 boat. Construction would also involve the operation of concrete trucks, and heavy-duty
3 over-the-road trucks for the delivery of structural materials, cranes, and other fabrication
4 equipment.

5 When completed, the concrete wharfs of Pier 300 (Berths 302-306) would total
6 approximately 5,250 ft. The existing wharf was designed to accommodate the largest
7 ships in the current transpacific fleet, which can each carry up to 10,000 TEUs. The new
8 wharf extension would be similarly designed. The existing wharf currently has four (4)
9 berths based on the existing average vessel size. Once the new wharf along Berth 306 is
10 completed (approximately 2014), the number of berths serving the terminal would
11 increase to approximately 4.5. However, as fleet changes occur and larger vessels are
12 used over time, the number of useable berth space along the Berths 302 to 306 wharf
13 would decrease to 3.5 berths by 2027.

14 The crane models, currently operating at the existing wharf are not able to span the width
15 of vessels capable of carrying more than 10,000 TEUs. The new wharf extension and
16 cranes would have the capacity to accommodate larger ships. The largest vessel that is
17 expected to operate as part of the transpacific fleet through year 2027 is the 10,000 to
18 10,999 TEU vessel. This analysis assumes the operation of a range of TEU vessels that
19 includes the 10,000 to 10,999 TEU vessels.



20
21 **Photograph 2: Area of new wharf along Berth 306**


22 AMP infrastructure would be installed along the new wharf at Berth 306. AMP is the
23 technique of utilizing shoreside electrical power from the power grid to operate the
24 container ships when they are berthed at an appropriately equipped wharf. AMP
25 connection voltage would be 6.6 kilovolts (kV), 3-phase, 60 Hertz (Hz). The proposed
26 Project would assist visiting fleets (in this case, APL and third party shipping lines) to

1 comply with the California Air Resources Board (CARB) adopted schedule for
2 implementing AMP power.³

3 In addition to electricity, the standard ship services at wharf include other utilities, such
4 as telephone and water hook-up facilities at each berth.

5 **New Shore-Side Gantry Cranes**

6 Under the proposed Project, up to 12 new A-frame cranes (also known as shore side
7 gantry cranes) would be installed on the wharves at Berths 302 to 306 (four new cranes
8 would be added to the 12 existing cranes on the existing wharf along Berths 302-305, and
9 eight new cranes would be installed at the new Berth 306 wharf). With the existing
10 12 cranes and the installation of the proposed 12 new cranes at Project completion, the
11 APL Terminal would have a total of 24 cranes. A-frame cranes at the existing terminal
12 have fixed towers that are approximately 245 ft high. When stowed (at a 45-degree
13 angle), the articulated booms on these cranes normally extend to a height of about 280 ft
14 and, for maintenance, are capable of being extended up to 360 ft in the vertical position.
15 Photograph 1 shows existing A-frame cranes at the APL Terminal and Photograph 3
16 shows a crane in the stowed position.



17
18 **Photograph 3: A-Frame crane in the stowed position.**
19

20 The 12 new cranes would function in a similar manner to the existing cranes but have a
21 longer outreach and higher lift capabilities than the existing cranes in order to

³ As provided for under Title 17, California Code of Regulations section 93118.3, a fleet's vessels — including container vessels, passenger vessels, and refrigerated container (reefer) vessels — must shut down their auxiliary engines (not including 3 or 5 permissible hours of total operation, as specified in the regulation) as follows: (a) In 2014, at least 50 percent of a fleet's visit to the port must meet these operational time limits, and the fleet must reduce its fleet's onboard auxiliary-diesel engine power generation at a given berth by 50 percent from its baseline power generation; (b) in 2017, at least 70 percent of a fleet's visit to the port must meet the aforementioned operational time limits, and the fleet must reduce its fleet's onboard auxiliary-diesel engine power generation at a given berth by 70 percent from its baseline power generation; and (c) in 2020, at least 80 percent of a fleet's visit to the port must meet the aforementioned operational time limits, and the fleet must reduce its onboard auxiliary-diesel engine power generation at a given berth by 80 percent from its baseline power generation.

1 accommodate larger ships. When stowed, the height of the new cranes is estimated to
2 extend to approximately 340 ft, and while operating, the A-frame structure of the cranes
3 is estimated to stand at approximately 260 ft.

4 The new cranes would be outfitted with semi-automatic dual trolley equipment so that
5 they could support an automated backland behind the new Berth 306 if such a system is
6 used (see Section 1.5.1.5 below for a detailed description of the proposed automated
7 system).

8 **1.5.1.3 Dredging**

9 The portion of the channel adjacent to the new wharf at Berth 306 would be dredged to
10 restore a depth of -55 ft MLLW plus an additional two ft of overdredge. New ships in the
11 world container vessel fleet and pending ship orders indicate that container vessels with a
12 draft of -52 ft are being planned, which would require a channel as deep as -55 ft MLLW
13 plus an additional two ft of overdredge during construction dredging (tolerance). The
14 area along Berth 306 is at various depths within the low fifties and currently less than
15 55 ft deep. Approximately 20,000 cy of marine sediments would be removed alongside
16 Berth 306 to achieve the desired design depth (POLA, 2009).

17 **1.5.1.4 Berths 302 – 305 Backlands Redevelopment**

18 Redevelopment of the backlands at the existing APL Terminal involves existing
19 buildings, backlands, and gates. Figure 1-5 shows the general location of the buildings
20 and gate structures.

21 **Buildings.** The proposed Project would include demolition and reconstruction of the
22 Roadability Facility, including approximately 4,160 sf of new building space and
23 approximately 10,000 sf for two new canopies (see Photograph 4). In addition, the
24 proposed Project would expand the Power Shop facilities to add tractor maintenance bays
25 and Marine Offices, including approximately 10,158 sf for the maintenance bays, and
26 approximately 10,150 sf of second floor space for offices (see Photograph 5). The
27 redevelopment of the Marine Office facility would meet Leadership in Energy and
28 Environmental Design (LEED) standards and are expected to achieve, at minimum,
29 LEED silver certification, consistent with the LAHD Green Building Policy.

30 **Backlands.** The proposed Project would convert a portion of dry container storage unit
31 area to a refrigerated container storage unit (reefer) area with use of electric power
32 (Photograph 6 shows refrigerated storage containers - reefers). Terminal lighting and fire
33 hydrants would be installed within the improved backland areas. The additional backland
34 improvements would require construction activities such as grading, drainage, paving,
35 striping, lighting, fencing, and the addition of utility facilities and equipment.

36 **Gates.** The proposed Project includes the construction of a new Meet and Greet booth
37 (approximately 400 sf) on backlands behind Berth 301, modifications to the Earle Street
38 Gate, and modifications to the northeast entrance (Photograph 7 shows the existing in-
39 gate and out-gate at the APL). Development in the northeast entrance area would include
40 construction of a new out-gate on two acres of undeveloped land northeast of the current
41 main gate, coupled with reconfiguration of the old out-gate.

1
2
3
4



Photograph 4: Roadability canopy

5
6
7



Photograph 5: Powershop



Photograph 6: Refrigerated containers



Photograph 7: Existing in-gate and out-gate

In addition, within the existing backlands behind Berths 302-305, the proposed Project includes the installation of a new Los Angeles Department of Water and Power (LADWP) industrial station (adjacent to the existing industrial station and new AMP substation, which is located near the existing Roadability Canopy/Genset Building), as well as various substations to support either traditional or electric-powered automated operations on the 41 acres of backlands adjacent to proposed Berth 306. If the new Berth 306 backlands are used to support an automated operation in the future, an area approximately 12 acres in size within the existing backland area adjacent to the new backlands would need to be converted to a Landside Transfer Area (a delineated area where drivers and trucks wait for containers held within the Berth 306 backlands).

1
2
3

4
5

6
7
8
9
10
11
12
13
14
15

1.5.1.5 Development of Berth 306 41-acre Backlands

Development of the Berth 306 backlands on the 41-acres of undeveloped fill adjacent to the existing terminal would include grading; paving and striping; as well as installation of smaller substations and underground electrical lines; water lines; light poles (Photograph 8 shows an example of terminal light poles); conduits to support electrical, data and phone connections; sewers; gas lines; and drainage infrastructure. This infrastructure would be adequate to support either traditional or electric-powered automated operations (or some combination of the two).



**Photograph 8:
Example of light poles**

In addition, other infrastructure elements would be built as part of the initial Project construction that would support either a traditional or an automated 41-acre backland at a later date, such as approximately 7,100 lf of rail sets that would support RMGs or the electric Automated Stacking Cranes (ASCs), and any additional corresponding electrical distribution system.⁴ The rail sets would be oriented parallel to the berth (refer to Figure 1-6 and Figure 1-7 for the preliminary conceptual design associated with the automated container operations and Photograph 9 shows an existing RMG at the on-dock railyard; the new ASCs, if installed, would likely be larger, with a cantilever on one side and sized to span a stack that is six containers high and 12 containers wide.

⁴ Although additional electrical distribution would be required to operate an automated 41-acre backland, the additional power infrastructure needed to support automated operations is proposed as part of initial Project construction.

1 Construction for the rails and installation of the ASCs would involve excavation,
2 installing concrete beams that would later support steel rails, paving, and installing
3 conduits for electrical power and data connectivity.

4



5
6 **Photograph 9: Rail-mounted gantry crane at the existing on-dock railyard**

7

8

9

10

11

12

13

14

15

16


17

18

19

20

If EMS determines that automated operations are feasible and cost effective for the Berth 306 backlands, additional infrastructure specific to the automated operation would need to be installed. Future installation of the automated equipment would be less complex than installation of the supporting infrastructure that has been included in the initial construction plans for the backland area. This additional work would include some asphalt grinding to flatten the finished grade and to expose the concrete beams, installation of steel rails, and installation of reefer racks (foundations with plug-in electric power) along the edge of the 41-acre area (these racks would allow refrigerated container units to be stored). Improvements to delineate and support operation of the Landside Transfer Area would also be installed adjacent to the Berth 306 backlands, including some excavation and installation of concrete rail beams to support the LTCs, pavement striping, waiting booths for drivers, and concrete curbing.





Storage yard cross section

Waterside transfer and transport area

Source: APL/Moffat & Nickel, 2011

Note: These elements and their size and arrangement are for discussion purposes only



Landside transfer crane

AGV transfer lanes

Container buffer

AGV transfer lanes

Source: APL/Moffat & Nicket, 2011

Note: These elements and their size and arrangement are for discussion purposes only

1.5.2 Project Construction

Construction of the proposed Project is anticipated to commence in 2012 and extend for approximately two years. The proposed Project would be constructed in two phases. Phase I consists of dredging, constructing the Berth 306 wharf extension, installing AMP at Berth 306, and improving the 41-acre fill site. Phase II consists of all other project modifications (Table 1-1). Construction would take place 6 days per week (Monday through Saturday) with no construction occurring on Sundays or national holidays. In general construction would occur from 6:00 a.m. to between 4:00 to 6:00 p.m., although some night construction may occur. Table 1-1 shows the estimated construction schedule for each component of the proposed Project, by phase.

Table 1-1: Berths 302-306 [APL] Container Terminal Construction Phasing

| Activity | Duration ¹ | Period |
|---|-----------------------|---------------------|
| Phase I (Package 1) | | |
| Construct 1,250-foot Wharf and AMP at Berth 306 ² | 22 months | Q4 2012 to Q2 2014 |
| Dredge Channel along Berth 306 | 1 month | Q3 2012 |
| Crane Delivery & Installation for Berths 302-306 ³ | 1 month per event | Q3 2012 and Q3 2014 |
| Develop 41-acre Backlands at Berths 305-306 | 18 months | Q1 2013 to Q2 2014 |
| Phase II (Package 2) | | |
| Demolish the Roadability Facility | 6 months | Q3 2014 to Q4 2014 |
| Construct the Roadability and Genset Facilities | 18 months | Q1 2013 to Q2 2014 |
| Expand Power Shop facilities for Tractor Maintenance bays and a Marine Office (separate annex building) | 18 months | Q1 2013 to Q2 2014 |
| Develop 9 acres Backlands behind berth 301 (former LAXT site) | 9 months | Q1 2013 to Q3 2013 |
| Develop New Out-Gate (2 acres) | 3 months | Q4 2013 |
| Modify existing outbound lanes to inbound | 3 months | Q1 2014 |
| Modify Terminal Entrance | 3 months | Q2 2014 |
| Modify Earle St. Gate | 3 months | Q1 2013 |
| Conversion of Dry Container Storage Area to Refrigerated-Container Storage Area (to include Use of Electric Source Power) | 6 months | Q1 2013 to Q3 2013 |
| Install Infrastructure throughout Backlands | 9 months | Q1 2013 to Q3 2013 |

Notes:

Q1, Q2, Q3, and Q4 signify the respective quarters of the year.

¹Durations provided in this table are only for the construction period. The bid and award period is not included in the provided durations.

²The new wharf would add 4 acres of area to the terminal area.

³Eight cranes would be added to the new wharf and four to the existing wharves (Berths 302-305). Initially, four cranes would be installed in Year 2012 at Berths 302-305, with two more cranes installed in 2014 or at some point thereafter, and the remaining cranes installed after 2015, when throughput volume dictates need.

1 Implementation of automated container-handling operations at the 41-acre expansion area
2 would depend largely on market demand and cost. For the purpose of the environmental
3 analysis, the miscellaneous construction activity and construction-related emissions
4 required to install the automated system (which includes installation of reefer racks,
5 striping, curbing, etc.), and delivery, installation and operation of the automated
6 equipment, is assumed to occur during year 2020. However, it is unknown whether
7 installation and use of such equipment would be cost-effective in 2020 or at any other
8 time.

9 **1.5.2.1 Dredging of Berth 306**

10 The existing depth along Berth 306 is less than 55 ft deep. The proposed Project includes
11 dredging at the new Berth 306 to restore the depth of -55 ft MLLW plus two ft of
12 overdredge. Dredging of Berth 306 to the proper depth would occur using an electric
13 dredge with a clamshell dredge (derrick barge) or a crane mounted on a barge with a
14 clamshell bucket. The barge would be maneuvered into proper position using a tug, and
15 held in place with anchor lines. A second barge would be anchored next to the derrick
16 barge to hold excavated dredge material. The clamshell bucket would be lowered to the
17 sea floor, and then it would scoop and lift sediments, and place them on the storage barge.
18 As the dredging progresses, the derrick barge would be repositioned as needed, and the
19 dredging would continue. Once a storage barge is filled, it would be hauled by tug to an
20 approved disposal site (such as the CDF at Berths 243-245 and/or Cabrillo Shallow
21 Water Habitat Area). If these sites are unavailable or impracticable, an ocean disposal
22 site (LA-2) could be considered assuming the material was approved for such use by the
23 DMMT.

24 **1.5.2.2 Wharf Construction**

25 Construction of the new wharf would occur sequentially and involve pile driving,
26 formwork and wharf casting, and finish work. Once dredging has been completed,
27 construction of the new wharf at Berth 306 would commence by driving piles in the
28 water and on the land adjacent to the water's edge. Pile driving would occur by using a
29 crane-mounted pile hammer, which attaches to the top of a pile. The pile would be
30 driven into the ground by the automated hammer until it is placed at the proper depth in
31 the underlying bedrock. For piles driven from the water, the crane would be mounted on
32 a barge. Pile driving would proceed from one end of the new wharf area to the other.

33 Once a suitable number of piles have been placed, in a designated section according to
34 design specifications, wharf construction would begin while the pile driving activity
35 continues in the next section. Formwork for a portion of the wharf deck would be
36 installed, and the tops of the piles cut to the proper height. Steel reinforcement would be
37 placed in the formed area, and appropriate utility conduits and structures (such as vaults,
38 AMP, etc.) would be placed. The formed wharf area would then be filled with concrete
39 and allowed to cure.

40 A second finish pour would occur after placement of the first concrete pour. Prior to the
41 second pour, the power trench and rail trenches required for operation of the cranes
42 would be formed. After the second concrete layer is cured, the forms would be removed,
43 and the crane rails installed. Power infrastructure for the cranes would also be installed.

1 The wharf construction process would occur in approximately 100 to 300-foot long
2 segments and would follow the pile driving process.

3 **1.5.2.3 Crane and Equipment Delivery**

4 A-frame cranes would be delivered to the proposed Project site by vessel (they are
5 constructed overseas), with approximately four cranes per ship. Once the vessel is at
6 berth, it would be ballasted so the ship deck is at the appropriate height to off-load the
7 cranes. A temporary ship-to-shore ramp would be constructed so that the cranes could be
8 rolled off the vessel directly onto the wharf rail system.

9 Delivery and installation of proposed automated equipment would be similar to the
10 delivery process for the cranes, which would involve delivery by vessel, placement of the
11 equipment on the rails followed by the necessary commissioning. It is assumed that an
12 additional six vessels within a one year period would be required to deliver the ASCs and
13 LTCs for automated operations at the Berth 306 backlands. Due to their size, the AGVs
14 are assumed to be delivered using regularly scheduled container ships (i.e., no additional
15 ships would be required to deliver the AGVs).

16 **1.5.2.4 Backlands Construction**

17 Development of the 41-acre vacant area as backlands would be a multi-step process. The
18 area is currently rough graded. Underground infrastructure such as utility lines, storm
19 drains, water lines, sewers, power substation and vaults, electrical conduits, and other
20 infrastructure would first be installed. The site would then be graded and balanced.
21 Caissons for light structure foundations would be placed, as would electrical connectors
22 for refrigerated units. Crushed miscellaneous base (CMB) rock would then be placed
23 over the backland area. In addition formwork for rails (to support ASCs) would be
24 installed, and pavement placed over the base in two layers. Pavement would be Asphalt
25 Concrete (AC), Roller Compacted Concrete (RCC), or Portland Cement Concrete (PCC).
26 Following paving, infrastructure would be installed or finished.

27 **1.5.2.5 Construction of Other Improvements**

28 Construction of other improvements such as the new gates, buildings, canopies, etc.
29 would be accomplished using traditional building methods in the following general order:
30 construction of foundations, installation of utilities, placement of structures, and
31 completion of finish work. Standard demolition, trenching, paving, and construction
32 methods would be used to construct the other terminal improvements.

33 **1.5.2.6 Permit Conditions**

34 As part of the approvals needed for the proposed Project, EMS's existing lease would be
35 modified to include the expanded terminal acreage. The modified lease would extend, as
36 does the present one, to 2027. The lease would continue to require that the premises be
37 used for activities, operations, and purposes incidental to and related to the operation of a
38 container terminal. Specifically, the lease would prohibit the tenant from any use of the
39 premises other than those stated above without prior approval of the Port. The existing
40 lease would be modified after certification of the EIS/EIR. It would require compliance
41 with all applicable laws and regulations and certain Port policies, including feasible
42 environmental controls that are not part of the current lease. For instance, the lease
43 would incorporate those measures adopted as mitigation based on the Final EIS/EIR, as

1 well as measures arising from the Clean Air Action Plan, Port environmental policies,
2 and the Port Real Estate Leasing Policy (POLA, 2006), as applicable. The USACE has
3 the authority to place special conditions in USACE permits (requirements for mitigation)
4 for areas within the USACE jurisdiction, and based on this, the USACE permits also
5 would require specific mitigation measures specific to USACE permitting jurisdiction.
6 Section 1.6 below describes various environmental plans and programs at the Port to
7 reduce the environmental effects associated with operations at the Port, such as standards
8 for terminal equipment, participation in the vessel speed reduction program, fuel
9 requirements, AMP for a proportion of marine vessels, clean truck requirements, and
10 other environmental measures such as storm water management, and dredging
11 restrictions.

12 **1.5.2.7 Terminal Operations**

13 For purposes of evaluation, the EIS/EIR assumes the APL Terminal would operate at
14 optimal throughput capacity by 2027. At optimal throughput capacity, the improved APL
15 Terminal could handle approximately 3.2 million TEUs per year, which represents
16 approximately 1,832,000 containers using a conversion factor of 1.75.⁵ EMS might
17 operate the terminal at lower TEU volumes than those described; however, an estimation
18 of throughput based on optimal terminal capacity ensures a conservative analysis in that
19 all reasonably foreseeable Project operations are included. Additionally, ships not
20 belonging to APL (third-party invitees) occasionally might use the terminal. By
21 estimating throughput based on optimal terminal capacity, the potential for such
22 third-party ship calls is accounted for in the analysis assumptions.

23 Anticipated Throughput: The proposed Project would be designed to accommodate
24 3.2 million TEUs by 2027. This compares to an existing throughput of approximately
25 1.1 million TEU's in 2009 (CEQA baseline) and a design capacity of the APL Terminal
26 of 2.2 million TEUs (NEPA baseline and No Project Alternative). While the total design
27 capacity would be available upon completion of proposed Project construction activities,
28 actual throughput in interim study years (2012, 2015, 2020, and 2025), would be much
29 lower. Table 2-3 summarizes the throughput levels for the proposed Project by study
30 year, and also includes throughput activity at the proposed Project site during the CEQA
31 baseline year (July 2008 through June 2009) and throughput under the NEPA baseline
32 conditions during the study years (2012, 2015, 2020, 2025, and 2027).⁶

33 If automated operations occur in the Berth 306 backlands, the TEU volumes for the
34 APL Terminal in 2027 would be the same as they would be under traditional container
35 terminal operations. The Port has prepared a white paper to assess the capacity of the
36 terminal under automated conditions in the Berth 306 backland area. The white paper
37 can be found in Appendix C2 of the Draft EIS/EIR. The main difference between
38 traditional terminal operations and automated terminal operations is that with a traditional

⁵ The throughput conversion factor used here represents an APL specific conversion factor and is discussed in more detail in Chapter 1, Section 1.1.2.1 of the Draft EIS/EIR.

⁶ The NEPA baseline represents the set of conditions that would occur without Federal action, such as a permit from the USACE. Under the NEPA baseline, terminal throughput is expected to grow over time to accommodate future projected containerized throughput, and therefore, different levels of terminal operation would occur at each study year (2012, 2015, 2020, 2025, and 2027). The NEPA baseline in 2027 is equal to the capacity of the existing APL Terminal.

1 terminal, containers are moved to and from the dock at shipside and to from the
2 backlands by diesel equipment driven by human operators whereas with automated
3 operations the containers would be transported to and from the dock at shipside to and
4 from the backlands by computer operated electric vehicles.

5 **Ship Operations:** The operation of container vessels, their loading and unloading, and
6 the handling of containers in the terminal are described in Section 1.2.2.1.1 in Chapter 1,
7 Introduction, of the Draft EIS/EIR. Normally, no more than three of the largest vessels
8 would be berthed at the terminal wharf at one time; however, after construction of Berth
9 306, up to four vessels could be berthed at the same time. By intent and design, shipping
10 companies deploy vessel strings (schedules) that are spread to avoid berth overlaps. This
11 method allows the ship to be processed faster while in port because the maximum number
12 of cranes and gangs can be dedicated to each ship.

13 To accommodate an annual throughput of approximately 3.2 million TEUs in 2027,
14 390 annual ship calls and associated tugboat operations would be required. For the APL
15 Terminal, one tug generally is required for ship docking and undocking, for a total of two
16 tugs per call, or 780 tugs operations annually. In less than one percent of cases, two tugs
17 are needed during docking/undocking due to equipment malfunction or by request of the
18 ship's pilot. In these rare instances, up to four tugboat operations would be required for a
19 single ship call. As occurs today, tugboats would be able to dock at terminal facilities in
20 between trips, reducing tug emissions associated with travel back to their docking
21 facilities. Table 1-2 summarizes the anticipated ship calls for the Project by study year,
22 and for the CEQA and NEPA baselines.

23 **Truck Operations:** Currently about 24 percent of Port-wide cargo throughput passes
24 through on-dock rail facilities, 8 percent through near-dock rail facilities, and the
25 remaining 68 percent via truck to the local and regional markets (and off-dock facilities).
26 However, the mode split at individual terminals can vary. Mode splits differ from
27 terminal to terminal on the basis of the existence and capacity of a terminal's on-dock rail
28 facility, as well as the demands of shipping lines, which are sensitive to the downstream
29 market. The existing APL Terminal transports a relatively high percentage of the
30 containers handled at the site via on-dock rail compared to the Port as a whole. Mode
31 splits at the APL Terminal are presently 35 percent through on-dock facilities, 11 percent
32 through near-dock facilities, and 54 percent by truck. Table 1-2 summarizes the
33 anticipated mode split percentages for the Project by study year, and for the CEQA and
34 NEPA baseline years.

35 Port-wide, by 2027, between 30 to 33 percent of the TEUs are expected to travel to and
36 from terminals by on-dock rail, between 7.5 to 12.5 percent are expected to travel to and
37 from the terminal via truck to near-dock and off-dock railyards, and the remaining cargo
38 volumes are anticipated to travel by truck to the local and regional market (i.e. markets
39 within an approximately 700-mile radius from the Port). As previously explained, the
40 percentage of TEUs expected to travel by on-dock rail verses by truck differ from
41 terminal to terminal because each terminal has different on-dock rail capacities, in
42 addition, each shipping line is subject to different market pressures and logistics.

43 Under the proposed Project, mode splits at the APL Terminal after year 2020 are
44 expected to change slightly as throughput via the on-dock facility reaches its maximum
45 capacity. The percentage of cargo passing through the on-dock facility at the APL
46 Terminal is expected to decrease to approximately 32 percent by 2027. The maximum

1 annual capacity of the current on-dock facility at the APL Terminal is estimated to be
2 1.04 million TEUs; and given rising levels of throughput expected at the terminal in years
3 2025 and 2027 (see Table 1-2), on-dock throughput splits in years 2025 and 2027 would
4 be slightly less than 35 percent. Specifically, the on-dock/near- dock/truck distribution
5 delivery splits anticipated to occur at the terminal is 33/12/55 percent respectively in year
6 2025, and 32/13/55 percent respectively in year 2027.

7 Based on the anticipated mode splits for the proposed Project, the design capacity
8 throughput of 3.2 million TEUs in 2027 would require a total of 11,361 peak daily truck
9 trips and 2,953 annual one-way-rail trip movements. Those trips would include cargo
10 hauled entirely by truck (principally within southern California, with some trips to and
11 from northern California, Arizona, Nevada, and Utah), and intermodal cargo bound for,
12 or coming from, locations farther east. Table 1-2 summarizes the anticipated truck trips
13 and rail trips associated with the proposed Project by study year, and for the CEQA and
14 NEPA baselines. Of the approximately 2.17 million TEUs transported by trucks in 2027,
15 approximately 405,000 TEUs (approximately 23 percent) would be intermodal cargo
16 trucked to nearby dock railyards. Draying containers to near- and off-dock facilities
17 could become necessary because all the containers on a train that is assembled in the
18 on-dock railyards are bound for the same destination, meaning containers bound for other
19 locations are hauled to nearby dock facilities to be grouped with containers from other
20 terminals bound for that same destination. Trucks would haul those containers on public
21 highways to and from off-site railyards, including the Union Pacific Carson ICTF, the
22 Burlington Northern Santa Fe Hobart Yard in Vernon, and the Union Pacific East Los
23 Angeles Yard. Local and national (minimal long-haul trips) containers would be hauled
24 to and from the terminal gates by trucks.

25 In addition to the above assumptions regarding transportation mode splits, assumptions
26 regarding the timing distribution of truck trips were developed based on on-going
27 Port-area transportation studies. Truck traffic throughout the Port in 2008 was distributed
28 as follows: 80 percent day shift (8:00 a.m. to 5:00 p.m.), 10 percent night shift (5:00 p.m.
29 to 3:00 a.m.), and 10 percent “hoot shift” (3:00 a.m. to 8:00 a.m.). The overall
30 80/10/10 percent split assumption was determined jointly by the Ports of Long Beach and
31 Los Angeles staff, based on operational reports. However, each terminal has distinct
32 operating characteristics, which may differ from the Port-wide composite. While EMS
33 anticipates loading and unloading vessels during the hoot shift in 2027, it does not
34 anticipate operating the gate or railyard during this shift. Truck traffic through the APL
35 Terminal gate in 2008 was distributed as follows: 60 percent day shift (8:00 a.m. to
36 5:00 p.m.), 40 percent night shift (5:00 p.m. to 3:00 a.m.), and no activity during the hoot
37 shift (3:00 a.m. to 8:00 a.m.). In year 2027, the split is expected to be 55/45/0. For
38 purposes of environmental review, this assumed future distribution (55 percent day,
39 45 percent night) is conservative in that it would tend to result in higher traffic impacts
40 than a 50/50 day/night distribution.

Table 1-2: Project Throughput Comparison

| | NEPA Baseline | | | | | CEQA Baseline ^a | Proposed Project | | | | |
|---|---------------|-----------|-----------|-----------|-----------|-------------------------------|------------------|-----------|-----------|-----------|-----------|
| | 2012 | 2015 | 2020 | 2025 | 2027 | July 08- June 09 | 2012 | 2015 | 2020 | 2025 | 2027 |
| Terminal Acreage | 291 | 291 | 291 | 291 | 291 | 291 | 291 | 347 | 347 | 347 | 347 |
| TEUs per Acre | 6,550 | 6,695 | 6,988 | 7,281 | 7,399 | 3,877 | 6,550 | 7,787 | 8,392 | 8,997 | 9,239 |
| Total Annual TEUs ^b | 1,906,000 | 1,948,201 | 2,033,536 | 2,118,871 | 2,153,000 | 1,128,080 | 1,906,000 | 2,702,000 | 2,912,000 | 3,122,000 | 3,206,000 |
| Annual Ship Calls | 234 | 234 | 234 | 286 | 286 | 247 | 234 | 286 | 338 | 364 | 390 |
| Daily Truck Movements (peak) | 6,438 | 6,581 | 6,869 | 7,157 | 7,273 | 5,093 | 6,438 | 9,127 | 9,836 | 10,892 | 11,361 |
| Annual Truck Trips ^c | 1,701,940 | 1,739,620 | 1,815,820 | 1,892,020 | 1,922,500 | 998,728 | 1,701,940 | 2,412,720 | 2,600,240 | 2,879,170 | 3,003,160 |
| Annual Rail Movements ^d | 2,197 | 2,221 | 2,270 | 2,317 | 2,336 | 1,676 | 2,197 | 2,627 | 2,831 | 2,876 | 2,953 |
| % TEUs by Truck ^e | 55 | 55 | 55 | 55 | 55 | 54 | 55 | 55 | 55 | 55 | 55 |
| % TEUs to Near/Off Dock Rail ^f | 10% | 10% | 10% | 10% | 10% | 11% | 10% | 10% | 10% | 12% | 13% |
| % TEUs by On-Dock Rail | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 33% | 32% |
| Number of Cranes ^g | 12 | 12 | 12 | 12 | 12 | 12 | 16 | 18 | 24 | 24 | 24 |
| # Terminal Employees ^h | 1,161 | 1,188 | 1,231 | 1,275 | 1,292 | 1,041 | 1,161 | 1,733 | 1,908 | 2,083 | 2,152 |

a The CEQA Baseline is the period from July 2008 through June 2009.

b Throughput forecasts conservatively estimate maximum capacity will be reached by 2027 so as to ensure environmental impacts are not underestimated.

c Annual truck trips were determined by the QuickTrip port terminal truck trip generation model, which uses truck trip generation rates from the Port of Los Angeles Baseline Transportation Study (2004) to determine a terminal's truck trips based on its TEU throughput by regional truck, on-dock rail intermodal and off-dock rail intermodal.

d Estimated annual rail one-way trips. Includes both on- and near-dock rail. Calculation extrapolated from annual TEU figures specified by Rail Master Plan and actual on-dock railyard projections. Assumes 414 TEUs per outbound trip and 114 TEUs per in-bound trip, and 1.75 TEUs per container or 302 TEUs per round train trip.

e Truck trips distribution based on current percentage rounded and projected forward. Assumes 10% to near dock rail, 55% are local/regional delivery, and 35% are on-dock

f Appendix C1 of the Draft EIS/EIR.

g This schedule represents a conservative but likely assumption regarding the phasing of cranes.

h Information for existing and future direct employees were provided or projected by EMS, 2010.

1 **Rail Operations.** The on-dock railyard at the existing terminal would handle a portion
 2 of the increased cargo from the expanded APL Terminal. According to the Ground
 3 Transportation analysis done for the proposed Project, as well as the Port Rail Master
 4 Plan, the existing railyard at the APL Terminal could handle approximately 1.04 million
 5 TEUs annually.

6 As occurs under existing conditions, containers would be hauled by yard tractors between
 7 the vessel berths and the on-dock railyard (Photograph 10 shows a yard tractor at the
 8 existing APL Terminal). At the railyard, containers would be lifted on and off railcars by
 9 mobile cranes or RMG cranes. The railyard would operate 24 hours per day; 365 days
 10 per year, as it does now, and could accommodate two double-stack unit trains each day.
 11 Although each train, both inbound and outbound, could carry a maximum of 250
 12 containers (with each container measuring 40 ft long), the trains usually carry a mix of
 13 containers, including those 20-ft long, and fewer than the maximum number of containers
 14 due to weight considerations. A more realistic estimate is that each inbound train trip
 15 (into the Port) transports an average of 65 containers (114 TEUs) plus empty railcars,
 16 while each outbound train trip (to inland locations) transports an average of
 17 237 containers (415 TEUs), for an average of 151 containers (264 TEUs) per round trip.⁷



18
 19 **Photograph 10: Yard Tractor**

20 Rail operations at on-dock railyards involve a number of entities. The terminal operator
 21 moves containers to and from the on-dock facility. Containers are off-loaded and loaded
 22 directly from and onto train components known as wells, with each well capable of
 23 carrying two 40-foot containers (Photograph 11 shows containers stacked on wells
 24 beneath an RMG at the existing on-dock railyard). Five wells make up a railcar, and each
 25 railcar is then coupled with other railcars traveling to the same destination. The coupled
 26 railcars are called a unit train. Unit trains vary in length between 21 and 28 railcars
 27 (105 and 140 wells). The average on-dock train length at the APL Terminal is 15 railcars
 28 (75 wells), or 4,725 ft, and this figure would not change under the proposed Project.

⁷ The conversion of containers to TEUs is based on an APL Terminal-specific factor of 1.75. In other words, 65 containers being sent via rail multiplied by the 1.75 factor equals approximately 114 TEUs.

1 These unit trains are usually built by Pacific Harbor Line (PHL). PHL is a third party,
2 independent rail company that provides rail transportation, yard switching, maintenance
3 and dispatching services to the Port Complex. PHL manages all rail dispatching and
4 switching functions at the on-dock railyards at the two ports, including:

- 5 ■ Scheduling and overseeing all train movements;
- 6 ■ Organizing railroad cars carrying containers of imported goods and switching them
7 onto various tracks to form unit trains;
- 8 ■ Breaking down unit trains arriving at the ports, switching railroad cars onto various
9 tracks and distributing them to nine marine terminals where containers are loaded
10 onto ships for export;
- 11 ■ Maintaining 60 miles of railroad tracks within the Port Complex; and
- 12 ■ Breaking and storing railroad cars awaiting dispatch.



13
14 **Photograph 11: Stacked containers in rail car wells**

15 The Port is served by two Class 1 railroads, Burlington Northern Santa Fe (BNSF) and
16 Union Pacific (UP), often referred to as the ‘main line’ or ‘line-haul’ rail companies.
17 After PHL has built a unit train, BNSF or UP will hook up their line-haul locomotive(s)
18 to the train and pull the train out of the on-dock railyard on to the main-line tracks to the
19 eventual destination. PHL locomotives will occasionally pull portions of a unit train out
20 of the on-dock facility to one of the near dock ICTFs. A loaded double-stack train is
21 typically pulled by three or four line-haul locomotives, although, if PHL pulls the train, it
22 would be hauled by two or three smaller locomotives.

23 PHL contracts with the Ports of Los Angeles and Long Beach to operate the centralized
24 traffic control (signaling) system. Agreements with BNSF and UP for international cargo
25 are usually handled by the shipping lines. Many shipping lines have a contract with both
26 BNSF and UP.

1 **Cargo-handling Equipment.** Under the proposed Project, an increase in the number of
2 some pieces of cargo-handling equipment would be required to process the increased
3 throughput. The current and future equipment inventory is described by the following:

- 4 ▪ Forklifts (36 in 2008, 46 in 2027);
- 5 ▪ RMG cranes (10 in 2008, 10 in 2027);
- 6 ▪ Rubber-tired Gantry Crane (8 in 2008, 8 in 2027);
- 7 ▪ Side picks (7 in 2008, 7 in 2027);
- 8 ▪ Top handlers (19 in 2008, 27 in 2027); and
- 9 ▪ Yard tractors (195 in 2008, 285 in 2027).

10 Cargo-handling equipment have useful operating lives, which correspond to the period
11 during which continued operation, with routine maintenance and periodic retrofits, is still
12 cost-effective. At the expiration of useful operating lives, items of equipment would be
13 replaced. EMS has adopted a schedule for equipment replacement consistent with the
14 retrofit schedule adopted by CARB. Specifically:

- 15 ▪ Forklifts would be replaced approximately every twelve years;
- 16 ▪ RMG cranes would be replaced approximately every thirty years;
- 17 ▪ A-frame cranes would be replaced every 30 years;⁸
- 18 ▪ Rubber-tired gantry cranes (see Photograph 12) would be replaced every twenty-five
19 years;
- 20 ▪ Side picks (see Photograph 13) would be replaced every twelve years;
- 21 ▪ Top handlers (see Photograph 14) would be replaced every twelve years;
- 22 ▪ Yard tractors (see Photograph 10 above) would be replaced every seven years; and
- 23 ▪ Miscellaneous diesel equipment would be replaced every twelve years.

⁸ RMGs and A-frames are not expected to be replaced as a normal course of business during the length of the lease



Photograph 12: Rubber Tire Gantry Crane

1
2
3



Photograph 13: Side pick

4
5
6



Photograph 14: Top pick or handler

1
2
3
4
5
6
7
8
9
10

Operation of the 41-acre Backland Area Adjacent to Berth 306. Because it is not certain as to whether or when use of an automated system would commence, for the purposes of environmental review, the EIS/EIR assumes that either (1) the terminal would continue to operate using traditional operations throughout the lease term; or (2) the operation of the 41-acre backland would transition from a traditional operation (i.e., transport of containers by mostly diesel-powered equipment) to an automated operation with mostly electric equipment during the lease term. Following is a description of traditional and automated backland operations:

11

Traditional Backlands

12
13
14
15
16
17
18
19
20
21
22
23
24
25

The existing APL Terminal operates using “traditional” methods for container terminal operations. As detailed in Section 1.2.2.1.1 in Chapter 1, Introduction, of the Draft EIS/EIR under the traditional operations, 1 to 10 cranes (depending on the size of the ship and availability of the cranes) operating simultaneously unload or load one ship. Once containers have been off-loaded from the ship or received through the gates on trucks and trains, the containers are stored and moved around the backlands area of the terminal (the storage yards) using cargo-handling equipment that may include electric- or diesel-powered RMGs, diesel-powered RTGs, and/or diesel-powered sidepicks, toppicks, and yard tractors. Through the use of this handling equipment, containers are stored by stacking containers on top of each other, up to five containers high, with the bottom container placed directly on the ground, or with a container stored directly on a chassis (trailer). All of the unloading/loading equipment used in the traditional backland operations is performed and operated by workers. A majority of the equipment used in the traditional operations is diesel-powered.

26

Automated Backlands

27
28
29
30

The Ports of Los Angeles and Long Beach have developed a roadmap for moving forward with the identification, evaluation, and integration of zero emission technologies for goods movement. It is foreseeable that a technology change could result in replacement of some of the traditional backland operations at the APL Terminal through

1 the use of an automated container handling system on the 41-acre backland area
2 adjacent to the proposed Berth 306. If installed, such a system would involve the use of
3 semi-automatic dual hoist electric shore side gantry cranes, AGVs, electric ASCs, and
4 semi-automated electric LTCs. Figure 1-6 and the following Figure 1-7 show a
5 preliminary conceptual design associated with the potential automated container
6 operations.

7 Once the vessel arrives at the berth, the cranes would begin unloading containers from
8 the vessel. Each crane would have a dual trolley with spreaders - a ship trolley and a
9 shore trolley. The ship trolley would lift the container from the vessel to a platform on
10 the crane where the Inter-Box-Connectors (IBCs) would be removed from the container.
11 The shore trolley would then lift the container from the coning platform to an AGV that
12 is positioned directly to the rear of the crane. The AGV would receive wireless
13 instructions and proceed through the use of sensors below the ground surface to a
14 pre-assigned location in the backlands area. Once the AGV arrives at the correct location,
15 an ASC would lift the container from the AGV and place it in the appropriate location.

16 When a customer's truck arrives at the terminal to pick up an import container, the truck
17 would proceed to the Landside Transfer Area adjacent to the backlands area. The
18 Landside Transfer Area would be comprised of parking stalls for the trucks delivering or
19 receiving of containers from the 41-acre backland area adjacent to Berth 306, LTCs for
20 the delivery and receiving of containers, and parking stalls on the backland area for
21 AGVs to park. A truck would back into a stall with a chassis, and the driver would exit
22 the truck and enter a booth. An AGV would then proceed to the appropriate grounded
23 location of the container and an ASC would lift the container from the grounded location
24 to the AGV. The AGV would proceed to the Landside Transfer Area and arrive at an
25 AGV stall. The LTC would then lift the container from the AGV and move it by trolley
26 to a position near the chassis, then land the container onto the chassis. The driver of the
27 truck would re-enter the truck and proceed to the Out Gate. The container handling
28 process for loading export containers would be handled in the same manner but in the
29 reverse direction.

30 With the exception of the operator of the A-frame/shore side gantry crane, the automated
31 backlands would be unmanned and fully automated. The automated system would be
32 operated from a remote facility (such as the remodeled/expanded Power Shop). With the
33 exception of the diesel/electric AGVs, all or part of the equipment used would be electric.

34 While infrastructure to support electric and automated equipment would be installed as
35 part of the initial proposed Project improvements by 2013, the timing of the installation,
36 integration, and operation of the automated equipment on the 41-acre backlands area
37 would depend largely on market demand and cost.

38 Although no date is certain, for this environmental analysis, the construction effects of
39 the installation of additional infrastructure and equipment necessary for automated
40 operations on the 41-acre are assumed to occur around 2020. However, it is unknown
41 whether installation and use of such equipment would be cost-effective in 2020 or at any
42 other time.

43 The potential environmental impacts associated with the operations of the Berth 306
44 backlands as a traditional container terminal are quantified under each environmental
45 resource area. This is the most conservative approach for estimating the environmental

1 impacts associated with the proposed Project operations. Where impacts associated with
2 automated operations could differ from impacts associated with traditional operations, the
3 impacts of automated operations at the backland area adjacent to Berth 306 also are
4 addressed at full build-out in 2027, based on the information available from the
5 conceptual designs.

6 **Terminal Operating Hours**

7 Currently, APL Terminal operations occur 360 days per year in two 8-hour shifts and one
8 5-hour shift per day, 7 days a week. The two 8-hour shifts can be extended to two
9 10-hour, overlapping shifts if operations so demand. For the 5 days of the year where the
10 marine terminal does not operate, rail operations and mechanics at the on-dock railyard
11 continue to operate 24 hours per day. The unloading and loading of ships (and
12 supporting operations in backland areas) follows the schedule described above except
13 that, during the hoot shift, only mechanics and security personal are working. Meanwhile,
14 gate operations do not occur on Friday nights, Saturday nights, Sunday days, and Sunday
15 nights, and not at all during the hoot shift. To facilitate these operations, the terminal
16 directly employed up to 599 workers during the day, up to 407 at night, and 35 in the
17 hoot shift in the CEQA baseline period July 2008 – June 2009.

18 In 2027, terminal operating hours are expected to change from those existing in 2008.
19 Along with other terminals in the Port, EMS expects to load and unload ships and operate
20 their gates during all three shifts in the future.

21 By 2027, terminal employees are expected to increase from a peak daily total of up to
22 1,041 in the CEQA baseline period to approximately 2,152 in 2027 (926 workers during
23 the day, up to 849 at night, and up to 377 in the hoot shift). The terminal is run as a
24 continuous operation, in which more employees are hired to supplement operations as
25 needed. Thus, the terminal is expected to operate 24 hours a day (*i.e.*, with cargo
26 operations occurring 24 hours per day) at a fairly consistent level of services.

27 **1.6 Port of Los Angeles Environmental Initiatives**

28 The Environmental Management Policy of the Port, as described in this section, was
29 approved by the Harbor Commission on April 27, 2003. The purpose of the
30 Environmental Management Policy is to provide an introspective, organized approach to
31 environmental management; further incorporate environmental considerations into
32 day-to-day Port operations; and achieve continual environmental improvement.

33 The Environmental Management Policy includes existing environmental initiatives for
34 the Port and its customers, such as the voluntary Vessel Speed Reduction Program
35 (VSRP), Source Control Program, Least Tern Nesting Site Agreement, Hazardous
36 Materials Management Policy, and the Clean Engines and Fuels Policy. In addition, the
37 Policy encompasses initiatives such as the Environmental Management System (EMS)
38 with the Construction and Maintenance Division of the Port, and a Clean Marina
39 Program. These programs are Port-wide initiatives to reduce environmental pollution.
40 Many of the programs relate to the proposed Project. The following discussion includes
41 details on a number of the programs and their goals.

1.6.1 Port Environmental Policy

The Port is committed to managing resources and conducting Port developments and operations in an environmentally and fiscally responsible manner. The Port strives to improve the quality of life and minimize the impacts of its development and operations on the environment and surrounding communities. This is done through the continuous improvement of its environmental performance and the implementation of pollution-prevention measures, in a feasible and cost-effective manner that is consistent with the overall mission and goals of the Port and with those of its customers and the community.

To ensure this policy is successfully implemented, the Port will develop and maintain an Environmental Management Program that will:

- Ensure that environmental policy is communicated to Port staff, its customers, and the community
- Ensure compliance with all applicable environmental laws and regulations
- Ensure that environmental considerations include feasible and cost-effective options for exceeding applicable regulatory requirements
- Define and establish environmental objectives, targets, and best management practices (BMPs), and monitor performance
- Ensure the Port maintains a Customer Outreach Program to address common environmental issues
- Fulfill the responsibilities of each generation as trustee of the environment for succeeding generations through environmental awareness and communication with employees, customers, regulatory agencies, and neighboring communities

The Port is committed to the spirit and intent of this policy and the laws, rules, and regulations, which give it foundation.

1.6.2 Environmental Plans and Programs

The Port has implemented a variety of plans and programs to reduce the environmental effects associated with operations at the Port. These programs include the San Pedro Bay Port Complex Clean Air Action Plan (CAAP), Water Resources Action Plan (WRAP), deepening the channels of the Port to accommodate larger and more efficient ships, and converting to electric and alternative-fuel vehicles. All of these efforts ultimately reduce environmental effects.

1.6.2.1 Clean Air Action Plan

The Ports of Los Angeles and Long Beach, with the participation and cooperation of the staff of the USEPA, CARB and SCAQMD, the San Pedro Bay Ports CAAP, a planning and policy document that sets goals and implementation strategies to reduce air emissions and health risks associated with port operations while allowing port development to continue. In addition, the CAAP sought the reduction of criteria pollutant emissions to the levels that assure Port-related sources decrease their “fair share” of regional emissions to enable the Basin to attain state and federal ambient air quality standards. Each individual CAAP measure is a proposed strategy for achieving these emissions reductions

1 goals. The Ports approved the first CAAP in November, 2006. Specific strategies to
2 significantly reduce the health risks posed by air pollution from port-related sources
3 include:

- 4 ▪ Aggressive milestones with measurable goals for air quality improvements
- 5 ▪ Specific goals set forth as standards for individual source categories to act as a
6 guide for decision-making
- 7 ▪ Recommendations to eliminate emissions of ultrafine particulates
- 8 ▪ Technology advancement programs to reduce greenhouse gases
- 9 ▪ Public participation processes with environmental organizations and the business
10 communities

11 The CAAP focuses primarily on reducing diesel particulate matter (DPM), along with
12 nitrogen oxide (NOx) and sulfur oxides (SOx). This reduces emissions and health risk
13 and thereby allows for future port growth while progressively controlling the impacts
14 associated with growth. The CAAP includes emission control measures as proposed
15 strategies that are designed to further these goals expressed as Source-Specific
16 Performance Standards which may be implemented through the environmental review
17 process, or could be included in new leases or Port-wide tariffs, Memoranda of
18 Understanding (MOU), voluntary action, grants or incentive programs.

19 The CAAP Update, adopted in November, 2010 includes updated and new emission
20 control measures as proposed strategies which support the goals expressed as the
21 Source-Specific Performance Standards and the Project-Specific Standards. In addition,
22 the CAAP Update includes the recently developed San Pedro Bay Standards which
23 establish emission and health risk reduction goals to assist the ports in their planning for
24 adopting and implementing strategies to significantly reduce the effects of cumulative
25 port-related operations.

26 The goals set forth as the San Pedro Bay Standards are the most significant addition to
27 the CAAP and include both a Bay-wide health risk reduction standard and a Bay-wide
28 mass emission reduction standard. Ongoing Port-wide CAAP progress and effectiveness
29 will be measured against these Bay-wide Standards which consist of the following
30 reductions as compared to 2005 emissions levels:

- 31 ▪ Health Risk Reduction Standard: 85 percent reduction in DPM by 2020
- 32 ▪ Emission Reduction Standards:
 - 33 ○ By 2014, reduce emissions by 72 percent for DPM, 22 percent for NOx, and
34 93 percent for SOx
 - 35 ○ By 2023, reduce emissions by 77 percent for DPM, 59 percent for NOx, and
36 92 percent for SOx

37 The Project-Specific Standard remains as adopted in the original CAAP in 2006, that new
38 projects meet the 10 in 1,000,000 excess residential cancer risk threshold, as determined
39 by health risk assessments conducted subject to CEQA statutes, regulations and
40 guidelines, and implemented through required CEQA mitigations and/or lease
41 negotiations. Although each Port has adopted the Project Specific Standard as a policy,
42 the Boards of Harbor Commissioners retain the discretion to consider and approve

1 projects that exceed this threshold if the Board deems it necessary by adoption of a
2 statement of overriding considerations at the time of project approval.

3 This EIS/EIR analysis assumes compliance with the CAAP. Proposed Project-specific
4 mitigation measures applied to reduce air emissions and public health impacts are
5 consistent with, and in some cases exceed, the emission-reduction strategies of the
6 CAAP.

7 **1.6.2.2 Water Resources Action Plan (WRAP)**

8 Both the LAHD and Port of Long Beach face ongoing challenges from contaminants that
9 remain in Port sediments, flow into the harbor from port land, and flow from upstream
10 sources in the watershed, well beyond the ports' boundaries. Therefore, the Ports
11 undertook a collaborative, scientific effort to address existing and potential sources of
12 water and sediment pollution. Building on the collaborative model developed by the
13 CAAP, the Port Complex under the WRAP will continue to work together and with other
14 stakeholders to achieve further progress in water and sediment quality improvement. The
15 WRAP establishes a program of water quality improvement measures necessary to
16 achieve the goals and targets that will be established by the Los Angeles RWQCB in
17 upcoming regulations. The WRAP targets the four basic types of potential sources of
18 pollutants to harbor waters (land use discharges, on-water discharges, sediments and
19 watershed discharges) and includes control measures zeroing in on known and potential
20 sources of water and sediment contamination in the harbor area (POLA and
21 POLB, 2009).

22 **1.6.2.3 Port of Los Angeles Sustainable Construction Guidelines**

23 The Port adopted the Port of Los Angeles Sustainable Construction Guidelines in
24 February 2008. The guidelines will be used to establish air emission criteria for inclusion
25 in bid specifications for construction. The guidelines will reinforce and require
26 sustainability measures during performance of the contracts, balancing the need to protect
27 the environment, be socially responsible, and provide for the economic development of
28 the Port. Future resolutions are anticipated to expand the guidelines to cover other
29 aspects of construction, as well as planning and design. These guidelines support the
30 forthcoming Port Sustainability Program.

31 The intent of the Guidelines is to facilitate the integration of sustainable concepts and
32 practices into all capital projects at the Port and to phase in the implementation of these
33 procedures in a practical, yet aggressive, manner (LAHD, 2008). These guidelines will
34 be made a part of all construction specifications advertised for bids.

35 Significant features of these Guidelines include, but are not limited to:

- 36 ■ All ships and barges used primarily to deliver construction-related materials for
37 LAHD construction contracts shall comply with the VSRP and use low-sulfur fuel
38 within 40 nautical miles of Point Fermin,
- 39 ■ Harbor craft shall meet USEPA Tier-2 engine emission standards, and the
40 requirement will be raised to USEPA Tier-3 engine emission standards by
41 January 1, 2011,
- 42 ■ All dredging equipment shall be electric,

- 1 ▪ On-road heavy-duty trucks shall comply with USEPA 2004 on-road emission
2 standards for inhalable particulate matter (PM₁₀) and NO_x and shall be equipped with
3 a CARB-verified Level 3 device. Emission standards will be raised to USEPA 2007
4 on-road emission standards for PM₁₀ and NO_x by January 1, 2012,
- 5 ▪ Construction equipment (excluding on-road trucks, derrick barges, and harbor craft)
6 shall meet Tier 2 emission off-road standards. The requirement will be raised to
7 Tier 3 by January 1, 2012, and to Tier 4 by January 1, 2015. In addition, construction
8 equipment shall be retrofitted with a CARB-certified Level 3 diesel emissions control
9 device,
- 10 ▪ Comply with SCAQMD Rule 403 regarding fugitive dust, and other fugitive dust
11 control measures, and
- 12 ▪ Additional Best Management Practices, based largely on Best Available Control
13 Technology (BACT), will be required on construction equipment (including on-road
14 trucks) to reduce air emissions further.

15 1.6.2.4 Other Environmental Programs

16 1.6.2.4.1 Air Quality

17 **Alternative Maritime Power.** AMP reduces emissions from container vessels docked at
18 the Port. Normally, ships shut off their propulsion engines when at berth, but use
19 auxiliary diesel generators to power electrical needs such as lights, pumps, and
20 refrigerator units. These generators emit an array of pollutants, primarily NO_x, SO_x, and
21 particulate matter (PM₁₀ and PM_{2.5}). The Port is beginning to provide shore-based
22 electricity as an alternative to running the generators (a process also referred to as cold
23 ironing). The AMP program allows ships to “plug-in” to shoreside electrical power while
24 at dock instead of using on-board generators, a practice that will dramatically reduce
25 emissions. Before being used at the Port, AMP was used commercially only by the
26 cruise ship industry in Juneau, Alaska. Now, AMP facilities have been installed and are
27 currently in use at China Shipping and the Yusen Terminals with plans for additional
28 facilities at the Evergreen Terminal, TraPac Terminal, and Cruise Ship Terminal, among
29 others. AMP has been incorporated into the CAAP as a project-specific measure.

30 **Off-Peak Program.** Extending cargo terminal operations by five night and weekend
31 work shifts, the Off-Peak Program, managed by PierPASS (an organization created by
32 marine terminal operators) has been successful in increasing cargo movement, reducing
33 the waiting time for trucks inside port terminals, and reducing truck traffic during peak
34 daytime commuting periods.

35 **On-Dock Rail and the Alameda Corridor.** Use of rail for long-haul cargo is
36 acknowledged as an air quality benefit. Four existing on-dock railyards at the Port,
37 including the existing on-dock facility on the proposed Project site (another two
38 on-dock yards are proposed), significantly reduce the number of short-distance truck trips
39 (the trips that normally would convey containers to and from off-site railyards).
40 Combined, these intermodal facilities eliminate an estimated 1.4 million truck trips per
41 year, and the emissions and traffic congestion that go along with them. A partner in the
42 Alameda Corridor project, the Port is using the corridor to transport cargo to downtown
43 railyards at 10 to 15 miles per hour faster. Use of the Alameda Corridor allows cargo to
44 travel the 20 miles to downtown Los Angeles at a faster pace and promotes the use of rail

1 versus truck. In addition, the Alameda Corridor eliminates 200 rail/street crossings and
2 emissions produced by cars with engines idling while the trains pass.

3 **Tugboat Retrofit Project.** The engines of several tugboats in the Port were replaced
4 with ultra-low-emission diesel engines. This was the first time such technology had been
5 applied to such a large engine. Emissions testing showed a reduction of more than
6 80 tons of NO_x per year, nearly three times better than initial estimates. Under the Carl
7 Moyer Program,⁹ the majority of tugboats operating in the Port Complex have been
8 retrofitted.

9 **Electric and Alternative Fuel Vehicles.** The Port has converted more than 35 percent
10 of its fleet to electric or alternative-fuel vehicles. These include heavy-duty vehicles and
11 passenger vehicles. The Port proactively has embarked on the use of emulsified fuels
12 that are verified by CARB to reduce diesel particulates by more than 60 percent
13 compared to diesel-powered equipment.

14 **Electrified Terminal Operating Equipment.** The 57 ship-loading cranes currently in
15 use at the Port operate under electric power. In addition, numerous other terminal
16 operations equipment has been fitted with electric motors.

17 **Yard Equipment Retrofit Program.** Over the past 5 years, DOCs have been applied to
18 nearly all yard tractors at the Port. This program has been carried out with Port funds and
19 funding from the Carl Moyer Program.

20 **Vessel Speed Reduction Program.** Under this voluntary program, oceangoing vessels
21 slow to 12 knots when within 20 nautical miles of the entrance to Los Angeles Harbor,
22 thus reducing emissions from main propulsion engines. Currently, approximately
23 70 percent of ships comply with the voluntary program.

24 **Greenhouse Gas Reduction.** Under a December 2007 agreement with the Attorney
25 General's office, the Port will conduct a comprehensive inventory of port-related
26 greenhouse gas (GHG) emissions, tracking these emissions from their foreign sources to
27 domestic distribution points throughout the United States. The Port will report this data
28 annually to the California Climate Action Registry. The annual report will include
29 emissions of all ships bound to and from the Port terminals, encompassing points of
30 origin and destination; emissions of all rail transit to and from Port terminals,
31 encompassing major rail cargo destination and distribution points in the United States;
32 and emissions of all truck transit to and from Port terminals, encompassing major truck
33 destinations and distribution points. The Port-wide inventory will be conducted annually
34 until Assembly Bill (AB) 32 regulations become effective.¹⁰ Under the agreement, the
35 Port will also construct a 10-megawatt photovoltaic solar system to offset approximately
36 17,000 metric tons of carbon dioxide equivalent annually. In addition to the recent
37 agreement with the Attorney General, many of the environmental programs described in

⁹ The Carl Moyer Program is a grant program implemented by CARB and administered by the SCQAMD to fund the incremental cost of cleaner-than-required engines.

¹⁰ The California Global Warming Solutions Act of 2006, also known as Assembly Bill (AB) 32, requires CARB to adopt regulations to require the reporting and verification of statewide GHG emissions and to monitor and enforce compliance with the program. In general, the bill requires CARB to reduce statewide GHG emissions to the equivalent of those in 1990 by 2020.

1 this section such as the Green Terminal Program, the Recycling Program, the Green Ports
2 Program, and all of the air quality improvement programs described above, will serve to
3 reduce GHG emissions.

4 **1.6.2.4.2 Water Quality**

5 **Clean Marinas Program.** To help protect water and air quality in the Harbor, the Port is
6 developing a Clean Marinas Program. The program advocates that marina operators and
7 boaters use BMPs - environmentally friendly alternatives to some common boating
8 activities that could cause pollution or contaminate the environment. The program also
9 includes several innovative clean water measures unique to the Port. The Clean Marinas
10 Program features voluntary components and measures required through Port leases,
11 CEQA mitigation requirements, or established federal, state, and local regulations.

12 **Water Quality Monitoring.** The Port has been monitoring water quality at
13 31 established stations in San Pedro Bay since 1967, and the water quality today at the
14 Port is among the best of any industrialized port in the world. Samples are tested on a
15 monthly basis for dissolved oxygen (DO), biological oxygen demand (BOD), and
16 temperature. Other observations are noted, such as odor and color, as well as the
17 presence of oil, grease, and floating solids. The overall results of this long-term
18 monitoring initiative show the tremendous improvement in Harbor water quality that has
19 occurred over the last four decades.

20 **Inner Cabrillo Beach Water Quality Improvements.** The Port is one of the few
21 industrial ports in the world to have a swimming beach. Inner Cabrillo Beach provides
22 quiet water for families with small children. However, in recent years, upland runoff has
23 resulted in high levels of bacteria in shoreline waters. The Port has invested hundreds of
24 thousands of dollars in water circulation/quality models and studies to investigate the
25 problem. Recently, the Port repaired storm drains and sewer lines, replaced poor quality
26 beach sand with clean sand, removed the groin at the north end of the beach, and installed
27 a bird exclusion device, all as part of its commitment to make sure that Inner Cabrillo
28 Beach continues to be an important regional recreational asset, but more importantly –
29 improve water quality.

30 **1.6.2.4.3 Habitat Management and Endangered Species**

31 **California Least Tern Site Management.** The federal- and State-endangered California
32 least tern (a species of small sea bird) nests from April through August on Pier 400 in the
33 Port adjacent to the Pier 400 container terminal. Through an interagency nesting site
34 agreement, the Port maintains, monitors, and protects the approximately 15-acre nesting
35 site on Pier 400.

36 **Interagency Biomitigation Team.** As part the development of mitigation for the
37 Deep-Draft Navigation Improvements, including the Pier 400 Landfill, the Port Complex
38 helped establish an interagency mitigation team to evaluate and provide solutions for
39 impacts of landfill and terminal construction on marine resources in the ports. The
40 primary agencies involved include the USACE, USFWS, NMFS, and the CDFG. A
41 number of mitigation agreements have been established through this coordination, and it
42 continues to meet as necessary to address environmental issues associated with Port
43 development and operations.

1.6.2.4.4 General Port Environmental Programs

Green Building Policy. In August 2007, the Port adopted a Green Building Policy, which outlines the environmental goals for newly constructed and existing buildings, dictates the incorporation of solar power and technologies that are efficient with respect to the use of energy and water, dedicates staffing for the advancement and refinement of sustainable building practices, and maintains communication with other City Departments for the benefit of the community. The policy incorporates sustainable building design and construction guidelines based on the United States Green Building Council - Leadership in Energy and Environmental Design (USGBC - LEED) Green Building Rating System (POLA, 2007).

Recycling. The Port incorporates a variety of innovative environmental ideas into its construction projects. For example, when building an on-dock rail facility, the Port saved nearly \$1 million and thousands of cubic yards of landfill space by recycling existing asphalt pavement instead of purchasing new pavement. The Port also maintains an annual contract to crush and recycle broken concrete and asphalt. In addition, the Port successfully has used recycled plastic products, such as fender piles and protective front-row piles, in many wharf construction projects.

1.6.3 Port of Los Angeles Leasing Policy

On February 1, 2006, the Harbor Commission approved a comprehensive Leasing Policy for the Port that not only establishes a formalized, transparent process for tenant selection but also includes environmental requirements as a provision in Port leases (POLA, 2006).

Specific emission-reducing provisions contained in the Leasing Policy that apply to the proposed Project as specific to cargo-handling equipment purchases, which must meet one of the following standards:

- Cleanest available NO_x alternative-fueled engine, meeting 0.01 g/bhp-hr PM; or
- Cleanest available NO_x diesel-fueled engine, meeting 0.01 g/bhp-hr PM, or, if 0.01 g/bhp-hr PM engines are unavailable;
- Cleanest available engine (either fuel type) and install cleanest Verified Diesel Emissions Controls (VDEC) available.
- Compliance with VSRPs;
- Use of clean AMP or cold-ironing technology, plugging into shore side electric power while at dock, where appropriate;
- Use of low sulfur fuel in main and auxiliary engines while sailing within the boundaries of the South Coast Air Basin; and
- Use of clean, low-emission trucks and locomotives to service the terminal.

1.6.4 Port Community Advisory Committee

The Port Community Advisory Committee (PCAC) was established in 2001 as a standing committee of the Harbor Commission. The purposes of the PCAC are to:

- Assess the impacts of Port developments on the Harbor area communities and recommend suitable mitigation measures to the Board for such impacts;

- 1 ▪ Review past, present, and future environmental documents in an open public process
2 and make recommendations to the Board to ensure that impacts to the communities
3 are mitigated appropriately in accordance with federal and California law; and
- 4 ▪ Provide a public forum and make recommendations to the Board to assist the Port in
5 taking a leadership role in creating balanced communities in Wilmington, Harbor
6 City, and San Pedro so that the quality of life is maintained and enhanced by the
7 presence of the Port.

8 The role of the PCAC in Port environmental documents is described in Appendix B of
9 the Draft EIS/EIR.

10 **1.7 Changes to the Draft EIS/EIR**

11 This section of the Final EIS/EIR discusses general changes and modifications that have
12 been made to the Draft EIS/EIR. Actual changes to the text, organized by Draft EIS/EIR
13 chapters and sections, can be found in Chapter 3, “Modifications to the Draft EIS/EIR,”
14 of this Final EIS/EIR. The changes to the Draft EIS/EIR are primarily editorial in nature
15 and have been made for the purpose of correcting and clarifying information contained
16 within the Draft EIS/EIR based on comments received from the public.

17 Changes noted in Chapter 3 are identified by text strikeout and underline. These changes
18 are referenced in Chapter 2, “Responses to Draft EIS/EIR Comments,” of this Final
19 EIS/EIR, where applicable. The project description is presented above and summarized in
20 the Executive Summary, incorporating the editorial changes noted in the Responses to
21 Comments and other minor corrections.

22 The changes and clarifications presented in Chapter 3 were reviewed to determine
23 whether or not they warranted recirculation of the Draft EIS/EIR prior to certification of
24 the EIS/EIR according to CEQA and NEPA Guidelines and Statutes. The changes would
25 not result in any new significant environmental impacts or a substantial increase in the
26 severity of an existing environmental effect. In response to public comments, changes
27 and clarifications have been made throughout the Draft EIS/EIR.

28 The above changes are consistent with the findings contained in the environmental
29 impact categories in Chapter 3, “Environmental Analysis,” of the Draft EIS/EIR, as
30 amended. There would be no new or increased significant effects on the environment due
31 to the proposed project changes, and no new alternatives have been identified that would
32 reduce significant effects of the proposed Project. Therefore, the Draft EIS/EIR does not
33 need to be recirculated, and the EIS/EIR can be certified without additional public
34 review, consistent with PRC Section 21092.1 and CEQA Guidelines Section 15088.5,
35 and NEPA regulations in 40 Code of Federal Regulations (CFR) 1502 and 1503.

36 **1.8 References**

37 **1.8.1 Printed References**

38 Los Angeles Harbor Department (LAHD). 2008. *Los Angeles Harbor Department*
39 *Sustainable Construction Guidelines for Reducing Air Emissions.*

- 1 Port of Los Angeles and Port of Long Beach. 2009. *Water Resources Action Plan*
2 (WRAP). August. Available at: <
3 http://www.portoflosangeles.org/DOC/WRAP_Final.pdf>. Last accessed May 2011.
- 4 Port of Los Angeles (POLA). 2006. *Port of Los Angeles Real Estate Leasing Policy*.
5 Available at
6 <http://www.portoflosangeles.org/Publications/POLA_Leasing_Policy_020106.pdf>. Last
7 accessed September 2011.
- 8 _____ . 2007. *Green Building Policy*. Available at
9 <[http://www.portoflosangeles.org/newsroom/2007_releases/news_082907green_building_po](http://www.portoflosangeles.org/newsroom/2007_releases/news_082907green_building_policy.pdf)
10 [licy.pdf](http://www.portoflosangeles.org/newsroom/2007_releases/news_082907green_building_policy.pdf)>. Last accessed September 2011.
- 11 _____ . 2009. *Port of Los Angeles Channel Deepening Project, Final*
12 *Supplemental Environmental Impact Statement/Supplemental Environmental Impact*
13 *Report*. State Clearinghouse No. 1999091029.
- 14 _____ .1979. *Port of Los Angeles Master Plan with Amendments*. Last revised
15 November 2009.

Chapter 2

Response to Comments

2.1 Distribution of the Draft EIS/EIR

The Draft EIS/EIR prepared for the LAHD and USACE was distributed to the public and regulatory agencies on December 16, 2011, for a 60-day review period. Approximately 224 printed and digital copies (CD) of the Draft EIS/EIR were distributed to various government agencies, organizations, individuals, and Port tenants. The USEPA and USACE also published a Notice of Availability (NOA) of the Draft EIS/EIR in the Federal Register (Volume 76, No. 247 pages 80367 and 80346, respectively), and the USACE published a Public Notice on December 23, 2011. LAHD, in cooperation with the USACE, conducted a public hearing regarding the Draft EIS/EIR on January 19, 2012, to provide an overview of the proposed Project and alternatives and to accept public comments on the proposed Project, alternatives, and environmental document.

Printed and digital copies of the Draft EIS/EIR were available for review at the following locations:

- Los Angeles Harbor Department, 425 South Palos Verdes Street, San Pedro, CA, 90731
- Los Angeles Public Library - Central Branch, 630 West 5th Street, Los Angeles, CA 90071
- Los Angeles Public Library - San Pedro Branch, 931 South Gaffey Street, San Pedro, CA 90731
- Los Angeles Public Library - Wilmington Branch, 1300 North Avalon, Wilmington, CA 90744

In addition to printed copies of the Draft EIS/EIR, digital copies were made available in response to specific requests. Due to the size of the document, the digital copies were prepared as a series of PDF files to facilitate downloading and printing. Members of the public were also invited to request a CD containing the EIS/EIR. The Draft EIS/EIR was available in its entirety on the Port web site at <http://www.portoflosangeles.org/environmental/publicnotice.htm>, with the public notice available online at www.spl.usace.army.mil/regulatory/POLA.htm. Digital copies of the Draft EIS/EIR on CD were available free of charge to interested parties. The USEPA and USACE NOAs and USACE Public Notice were also made available online at www.federalregister.gov, and www.spl.usace.army.mil/Missions/CivilWorks/Regulatory, respectively.

2.2 Comments on the Draft EIS/EIR

The public comment and response component of the NEPA/CEQA process serves an essential role. It allows the respective lead agencies to assess the impacts of a project based on the analysis of other responsible, concerned, or adjacent agencies and interested parties, and it provides an opportunity to amplify and better explain the analyses that the lead agencies have undertaken to determine the potential environmental impacts of a project. To that extent, responses to comments are intended to provide complete and thorough explanations to commenting agencies and individuals, and to improve the overall understanding of the Project for the decision-making bodies.

The USACE and LAHD received 25 comment letters and comments through the public hearing transcript on the Draft EIS/EIR during the public review period. Table 2-1 presents a list of those agencies, organizations, and individuals who commented on the Draft EIS/EIR.

Table 2-1: Public Comments Received on the Draft EIS/EIR

| Letter Code | Date | Individual/Organization | Page |
|---------------------------|----------|--|----------------|
| Federal Government | | | |
| USEPA | 02/23/12 | U.S. Environmental Protection Agency, Region IX | 2-5 to 2-32 |
| FEMA | 12/22/11 | U.S. Department of Homeland Security, FEMA Region IX | 2-33 to 2-35 |
| NMFS | 02/16/12 | US Dept of Commerce National Oceanic and Atmospheric Admin National Marine Fisheries Service | 2-36 to 2-47 |
| DOI | 02/17/12 | U.S. Department of the Interior | 2-48 to 2-49 |
| State Government | | | |
| NAHC | 12/21/11 | Native American Heritage Commission | 2-50 to 2-57 |
| SCAQMD | 2/24/12 | South Coast Air Quality Management District | 2-58 to 2-91 |
| DTSC | 01/17/12 | Department of Toxic Substances Control | 2-92 to 2-99 |
| DOT | 02/15/12 | Caltrans District 7 | 2-100 to 2-104 |
| Local Government | | | |
| BOS1 | 03/14/12 | City of Los Angeles, Bureau of Sanitation, Wastewater Engineering Services Division | 2-105 to 2-107 |

| | | | |
|-------------------------------------|------------|--|----------------|
| BOS2 | 03/29/12 | City of Los Angeles, Bureau of Sanitation, Wastewater Engineering Services Division | 2-108 to 2-111 |
| Organizations | | | |
| PCAC | 02/15/12 | Port of Los Angeles Community Advisory Committee, Past EIR Subcommittee | 2-112 to 2-124 |
| CFASE | 02/17/12 | Coalition for a Safe Environment | 2-125 to 2-210 |
| Individuals/Companies | | | |
| RSF | 12/18/11 | RSF9873 | 2-211 to 2-212 |
| Crable | 01/12/12 | Arthur (Dennis) Crable | 2-213 to 2-214 |
| RNLDS | 02/17/12 | William ("Bill") Reynolds | 2-215 to 2-216 |
| TM | 02/16/12 | Ty McMichael | 2-217 to 2-218 |
| RH | 02/17/12 | Richard Havenick | 2-219 to 2-223 |
| MMI | 02/14/12 | Marine Mechanical Inc. | 2-224 to 2-226 |
| MTS | 02/14/12 | Maintenance Turnaround Services | 2-227 to 2-229 |
| HI | 02/14/12 | Harbor Industrial | 2-230 to 2-232 |
| JM | 02/16/12 | Jesse Marquez | 2-233 to 2-234 |
| PFP | 02/15/12 | PF Properties | 2-235 to 2-236 |
| MTSI | 02/15/12 | Marine Technical Services Inc. | 2-237 to 2-238 |
| DMSR | 02/16/12 | Dockside Machine & Ship Repair | 2-239 to 2-241 |
| JT | 12/24/2011 | Joseph Towers | 2-246 to 2-247 |
| Draft EIS/EIR Public Hearing | | | |
| APLPH | 01/19/12 | Draft EIS/EIR Public Hearing Transcript | 2-248 to 2-271 |

1

2 2.3 Responses to Comments

3 In accordance with NEPA (23 CRR Part 771) and CEQA (Guidelines Section 15088), the
4 USACE and LAHD have evaluated the comments on environmental issues received from
5 agencies and other interested parties and have prepared written responses to each comment
6 pertinent to the adequacy of the environmental analyses contained in the Draft EIS/EIR. In
7 implementing regulations 23 CFR Part 771 of NEPA and specific compliance with CEQA
8 Guidelines Section 15088(b), the written responses address the environmental issues raised.

1 In addition, where appropriate, the basis for incorporating or not incorporating specific
2 suggestions into the proposed Project is provided. In each case, the USACE and LAHD
3 have expended a good faith effort, supported by reasoned analysis, to respond to comments.

4 This section includes responses not only to the written comments received during the 60-
5 day public review period of the Draft EIS/EIR, but also verbal comments made at the
6 public hearing for the Draft EIS/EIR. Some comments have prompted revisions to the text
7 of the Draft EIS/EIR, which are referenced and shown in Chapter 3, Modifications to the
8 Draft EIS/EIR. A copy of each comment letter is provided, and responses to each comment
9 letter immediately follow.

10



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION IX

75 Hawthorne Street
San Francisco, CA 94105-3901

February 23, 2012

Theresa Stevens
U.S. Army Corps of Engineers
Los Angeles District – Regulatory Division, North Coast Branch
2151 Alessandro Drive, Suite 110,
Ventura, California 93001

Subject: Draft Environmental Impact Statement/Environmental Impact Report for Proposed Berths 302-306 (APL) Container Terminal Project, at the Port of Los Angeles, Los Angeles County, CA (CEQ # 20110428)

The U.S. Environmental Protection Agency (EPA) is providing comments on the Draft Environmental Impact Statement (DEIS) for Proposed Berths 302-306 American President Lines (APL) Container Terminal Project, at the Port of Los Angeles. Our comments are provided pursuant to the National Environmental Policy Act (NEPA), Council on Environmental Quality regulations (40 CFR Parts 1500-1508), and our NEPA review authority under Section 309 of the Clean Air Act. Our comments are also prepared under the authority of, and in accordance with, Section 103 of the Marine Protection, Research and Sanctuaries Act (MPRSA) and Section 10 of the Rivers and Harbors Act (RHA), and the provisions of the Federal Guidelines promulgated at 40 CFR 230 under Section 404(b)(1) of the Clean Water Act. We appreciate the Corps of Engineers' willingness to accept this letter as timely, after the close of the comment period, as discussed in your email of February 8, 2012, to Tom Kelly, of my staff.

The project proponent, the Port of Los Angeles, along with Port of Long Beach, continues to demonstrate environmental leadership in reducing air pollution, especially diesel particulate matter, yet the APL container terminal project still imposes added burdens on the local community. The local effects include significant emissions of volatile organic compounds, carbon monoxide, nitrogen oxides (NO₂), particulate matter, both 10 microns or less (PM₁₀) and 2.5 microns or less (PM_{2.5}), and exceedences of federal, state and local standards for nitrogen dioxide and particulate matter. Numerous scientific studies have linked particulate pollution exposure to a range of health problems, including premature death, increased hospital and emergency room visits for cardiovascular and respiratory effects, and development of chronic respiratory disease. Likewise, exposure to NO₂ has been correlated with increased visits to emergency rooms and hospital admissions for respiratory issues, especially asthma. Because the community impacted by this project is predominantly minority and low income, these impacts constitute a disproportionate high and adverse effect on minority and low income populations.

The Department of Defense is signatory to the August 4, 2011 Memorandum of Understanding (MOU) on Environmental Justice and Executive Order 12898. In addition to reinforcing the federal government's commitment to environmental justice, the MOU is relevant to actions such as the APL Container Terminal Project through its focus on goods movement, NEPA, and Title VI of the Civil Rights Act. In light of this renewed commitment and focus, we recommend that the Corps consider changes to alternatives and mitigation measures, as proposed in this letter and by other stakeholders, to avoid or further mitigate the project's disproportionately high and adverse impacts. Further efforts to reduce environmental justice impacts could assist the Port and the City of Los Angeles, as recipients of Federal funds, to meet their potential obligations under Title VI of the Civil Rights Act.

The Ports, and its partners such as EPA and the South Coast Air Quality Management District, are also working to accelerate the commercial feasibility of new clean air strategies to reduce air pollution through

USEPA-1

USEPA-2

USEPA-3

the Technology Advancement Program or TAP. The TAP is evaluating and demonstrating zero tailpipe emission trucks, locomotives, cargo-handling equipment and retrofit technologies for ocean-going vessels and harbor craft. While the APL DEIS mitigation measures are consistent with the Clean Air Action Plan, the DEIS lacks a clear plan to transition to technologies being demonstrated through the TAP.

USEPA-3
Cont.

APL, the terminal operator and primary shipping line using the terminal, has participated in multiple TAP projects to retrofit existing ships to reduce emissions. Additionally, APL announced the purchase of 12 new, and cleaner, container ships in 2011. Despite these and other fleet-wide environmental improvements by APL, the DEIS does not include a commitment to retrofit older ships with emission reduction technologies demonstrated through the TAP or a commitment to bring new cleaner ships to the Port of Los Angeles.

USEPA-4

Based on our review of the DEIS, we are rating the action alternatives as *Environmental Objections - Insufficient Information (EO-2)* (please see the enclosed "Summary of EPA Rating Definitions"). Please see the enclosed detailed comments for a more thorough discussion of the comments provided above, as well as additional comments on, air quality and water quality and sediment.

USEPA-5

We appreciate the opportunity to review this DEIS. When the FEIS is released for public review, please send one hard copy and one electronic copy to the address above (mail code: CED-2). If you have questions, please contact me at (415) 972-3856 or Tom Kelly of my staff at kelly.thomasp@epa.gov.

Sincerely,



Enrique Manzanilla, Director
Communities and Ecosystems Division

Enclosures: EPA's Detailed Comments
Summary of EPA's Rating Definitions

cc: Christopher Cannon, Port of Los Angeles
Cindy Miscikowski, Los Angeles Board of Harbor Commissioners
Rick Cameron, Port of Long Beach
Susan E. Anderson Wise, Port of Long Beach Harbor Commissioners
Susan Nakamura, South Coast Air Quality Management District
Cynthia Marvin, California Air Resources Board
Hassan Ikrhata, Southern California Association of Governments
David Seep, BNSF Railway
Lanny Schmid, Union Pacific Railroad
Martin Tuttle, Caltrans
Bimla Rhinehart, California Transportation Commission
Alan Hicks, U.S. Department of Transportation, Maritime Administration
Gene Seroka, APL

Air Quality

Environmental Justice

The EJ analysis and conclusions in the DEIS state that there will be disproportionately high and adverse effects on minority and low-income populations due to air quality impacts. We recognize the considerable level of analysis in the DEIS, but we note that the proposed mitigation does not fully offset the significant project-related impacts to the local community. The local community is already heavily impacted¹, a condition likely to be exacerbated by the many projects currently planned at and around the Port, such as the Cop of Engineers Pier S project, the Southern California International Gateway, and perhaps the expansion of Interstate 710. Therefore, all impacts, even seemingly small ones, are important to consider and mitigate in order to fully offset the adverse Project-related impacts to the local community.

EPA is helping to develop a growing body of evidence that environmental justice communities are more vulnerable to pollution impacts than other communities². As discussed in EPA's *Framework for Cumulative Risk*³ and *Integrated Science Assessment for Oxides of Nitrogen – Health Criteria*⁴ (July 2008), disadvantaged, underserved, and overburdened communities are likely to come to the table with pre-existing deficits of both a physical and social nature that make the effects of environmental pollution more, and in some cases, unacceptably, burdensome. Thus, certain subpopulations may be more likely to be adversely affected by a given stressor than is the general population.

In the past, EPA has recommended using a Health Impact Assessment (HIA) or an HIA type approach as a means to more creatively mitigate project impacts. While we are not seeking an HIA for this project, we do encourage the Port to identify additional community-supported mitigation, as a means to better address disproportionate and adverse health impacts of the proposed project.

As stated by the Council on Environmental Quality (CEQ)⁵, the identification of disproportionately high and adverse human health or environmental effects on a low-income or minority population does not preclude a proposed agency action from going forward nor compel a finding that a proposed project is environmentally unacceptable. Instead, the identification of such effects is expected to encourage agency consideration of alternatives, mitigation measures, monitoring needs, and preferences expressed by the affected community or population.

Recommendations:

Considering the magnitude of potential cumulative health impacts, the FEIS should vigorously consider all feasible mitigation strategies, monitoring measures, and the

¹ Final Report, Multiple Air Toxics Exposure Study in the South Coast Air Basin, MATES-III, September 2008, South Coast Air Quality Management District.

² Symposium on the Science of Disproportionate Environmental Health Impacts, March 17 - 19, 2010, see the fourteen scientific reviews commissioned by EPA and published in the American Journal of Public Health at: <http://www.epa.gov/compliance/ej/multimedia/albums/epa/disproportionate-impacts-symposium.html> ,

³ Available at: <http://cfpub.epa.gov/ncea/raf/recordisplay.cfm?deid=54944>.

⁴ Available at: <http://cfpub.epa.gov/ncea/cfm/recordisplay.cfm?deid=194645#Download>.

⁵ Environmental Justice Guidance Under the National Environmental Policy Act, Council on Environmental Quality, 10 December 1997.

preferences expressed by the local community. Examples of mitigation measures to reduce the community's exposure and reduce community vulnerability are:

- Fund proactive measures to improve air quality and general health in neighboring homes, schools, and other sensitive receptors;
- Provide public education programs about environmental health impacts to better enable residents to make informed decisions about their health and community; and
- Engage in proactive measures to train and hire local residents for construction or operation of the project to improve their economic status and access to health care.
- Expansion and improvement of local community parks and recreation system, in areas where air quality is highest, in order to provide increased access to open space and exercise opportunities.

USEPA-6
Cont.

As an element of the Corps Pier S project, the proponent, the Port of Long Beach, offered grant funds for impacts that could not be fully mitigated. We recommend that Corps discuss this option with the Port of Los Angeles, the proponent for the current Corps project, and include consideration of a similar program to implement these examples in the FEIS

USEPA-7

Ocean Going Vessels

Ships represent the largest category of NOx emissions (Table 3.2-29). Mitigation measure AQ-9 (i.e. shore power) substantially reduces ship hoteling emissions (at port) by more than 85%. The reductions would also be achieved by the California Air Resources Board (CARB) regulation, but MM AQ-9 slightly accelerates implementation of shore power. In contrast to the decreasing hoteling emissions, the ship transit and anchoring emissions subcategory not only increases by 51% by 2027, it exceeds truck and locomotive emissions combined, representing 48% of all project (annual) emissions (Table 3.2-29).

USEPA-8

The DEIS proposes three operational mitigation measures for ocean going vessels: AQ-10: Vessel Speed Reduction Program, MM AQ-11: Cleaner OGV Engines; and OGV Engine Emission Reduction Technology Improvements. We support vessel speed reduction as a measure to minimize air impacts and reduce whale strikes. We acknowledge that the Ports of Los Angeles and Long Beach are working with Agency partners, including EPA, to develop corresponding Clean Air Action Plan (CAAP) measures (OGV5 and 6), which correspond to MM AQ-10 and 11. Further development of the CAAP measures and revision of the DEIS mitigation measures is necessary to achieve emission reductions for ocean-going vessels.

Terminal operators, railroads and the trucking industry have been investing in the expedited turnover to cleaner equipment, often at the urging of the Port of Los Angeles. The FEIS should discuss the contribution of APL to a strategy for expedited turnover. We note that the APL website states the company plans to purchase 32 new ships, a 22% increase when compared to its current fleet. At a minimum, these ships must comply with International Maritime Organizations Tier II standards, but Tier III engines, which are not required until 2016, are available now. APL can readily share their plans to bring cleaner ships and retrofit older ships with demonstrated emissions control technologies. The project's significant impacts and disproportionately high and adverse effects to minority and low income communities call for the best efforts of all sectors in the chain of goods movement, particularly the entity that, along with the Port itself, stands to benefit from the project.

USEPA-9

Recommendations:

The FEIS should revise mitigation measures AQ-10 and 11, consistent with the developing Clean Air Action Plan measures OGV5 and OGV6, to ensure that cleaner ocean-going vessels will use the APL terminal.

USEPA-10

Include in the FEIS a discussion of expedited delivery of cleaner equipment and how APL and the Port of Los Angeles are investing in the commitment for cleaner equipment.

USEPA-11

Terminal Operations

The DEIS states that the proposed action would not increase capacity, or throughput, by automating the new 41 acres of backlands (Appendix C2). The berth capacity limits the APL terminal throughput, not the processing capacity of the backlands or container yard. Consequently, the proposed action does not fully automate the terminal, but (as stated on p. 2-42) the infrastructure necessary to support an electric automated terminal will be installed. The DEIS discusses a grounded or "stacked" system (containers stacked in high-density arrays) and chassis or "wheeled" system (containers stored on individual wheeled chassis and not stacked), or a combination of the two (p. 1-32).

While the APL terminal may not need to adopt modern high density stacking to maximize throughput, we note that stacking and a higher density system would minimize on-site tailpipe emissions from cargo handling equipment. Direct air emissions from terminal equipment are estimated at 10% of the project emissions initially, but decline to just over 1% by 2027; Automating Berth 306 would reduce these emissions and the need for backlands at Berth 302 to 305, providing more area for on-dock rail. Lease measure LM AQ-2, Substitution of New Technology, if applied on an aggregate basis, appears to require automation. The DEIS notes automated equipment is mostly electric (p. 2-18), while the proposed project includes diesel equipment.

USEPA-12

Recommendations:

Consistent with lease measure LM AQ-2, the proposed project should require automated container handling equipment at Berth 306. Should the proposed project allow expansion of traditional diesel operations at Berth 306, the FEIS should quantify emission benefits of maximizing backland automation and on-dock rail.

The DEIS considered, but did not further evaluate, a fully electrified container terminal, expanded rail lines and increased technology to increase efficiency. Because the terminal is "berth-constrained", these options were dismissed, as they do not increase terminal capacity. While adding rail lines to the APL terminal will not increase its throughput, it will reduce the air quality and traffic impacts of the increased trucks used to haul containers to off dock rail yards. For that reason, we support measures to maximize backland automation and on-dock rail throughout the low-density APL backlands (i.e. behind berths 302-305). Alternative 6 is a step in the right direction, as it would increase on dock rail by 100,000 TEU, converting 10 acres of backlands to railyard. Alternative 6 would reduce peak daily truck trips for the project at full throughput by 531 per day (4.7%), cutting NOx emissions by more than 40 pounds per day (3.3%). At a minimum, this concept should be increased so that near-dock rail is no longer necessary for the APL terminal, reducing nearly 1500 truck trips per day and 115 pounds per day of NOx. The proposed project would allow APL to avoid adding on-dock rail and continue business as usual until economic and space considerations dictate stacking is necessary.

USEPA-13

In many respects, the container terminals are underutilizing land at the Port of Los Angeles. A 2005 APL press release notes "nearly every container at the GGS [Global Gateway South a.k.a APL]

USEPA-14

terminal is on a chassis” meaning containers are not stacked. This is confirmed by a recent Google Earth aerial photo showing almost no stacked containers behind berths 302-305⁶.

The DEIS recognizes that stacking will be needed for the terminal to reach its full throughput, but even three-high stacking, described as “relatively low” in Appendix C2, is sufficient to meet APL’s future need. In contrast, modern terminals like Euromax are designed to stack containers 5-high⁷. In light of the Harbor Commission’s recent proposal to locate a new rail yard, the Southern California International Gateway, close to residents, schools, day care centers and senior facilities, we urge recognition of the current underutilization of port property at the APL terminal, and a commitment to create additional space for on-dock rail through high density stacking. Alternative 5 proposes to relinquish 30 acres on current space assignment and electrify a portion of the backlands infrastructure, while Alternative 6 would expand on-dock rail. An alternative that combines and expands on these elements of Alternatives 5 and 6 would better optimize the cargo-handling efficiency and capacity than the proposed project, and better meeting the purpose and need for the project.

USEPA-14
Cont.

Recommendations:

Because the backland behind Berth 302-306 is capable of supporting APL’s needs using stacked containers over a much smaller footprint, the FEIS include an alternative with minimized backland footprint and a maximized on-dock rail system.

Should the on-dock rail be larger than necessary to serve APL, it could be made available to nearby container terminals to avoid trucking containers to near and off-dock rail yards (e.g. the Evergreen Container Terminal).

USEPA-15

Health Effects

The DEIS concludes that NO₂ emissions are significant and unavoidable, because it exceeds the NO₂ 1-hour NAAQS. The DEIS does not include any additional information on the extent of the exceedence. As the DEIS notes, NO₂ has the potential to aggravate chronic respiratory disease and respiratory difficulties in sensitive groups, but it does not evaluate health data to assess the health status of the community, such as asthma rates and asthma-related hospitalization or emergency room visits.

The DEIS concludes that the acute hazard index for occupational acute exposures is significant for industrial exposures, but not significant for residential exposures (3.2-145 and Table 3.2-38b). In both cases, the acute incremental or project-related hazard index is compared to the significance threshold of 1.0. This is consistent with South Coast Air Quality Management District’s Air Quality Significance Thresholds; however, the significance level is an effect/no effect threshold. Much like the NO₂ significance level, the relative (or project increment) of the hazard index is less important than the total hazard index (background plus project exposure). Additional mitigation, such as altering the construction schedule or using high emitting equipment only when emissions would otherwise be low, may sufficiently change the timing of emissions to avoid an acute residential hazard.

USEPA-16

⁶ Imagery date March 7, 2011.

⁷ Euromax: A New Standard in Container Handling, undated,

<http://www.tba.nl/uploads/files/euromax,_a_new_standard_in_container_handling.pdf>

Recommendations:

The FEIS should map the results of NO₂ dispersion modeling, and consider the health status of the local community. The FEIS should identify mitigation measures to reduce emissions causing the acute hazard index to exceed 1.0.

USEPA-16
Cont.

Drayage Trucks

The DEIS summarizes the Clean Truck Program, a key element of the Clean Air Action Plan, that has substantially reduced port-related air emissions, especially diesel emissions, from both San Pedro Bay ports (p. 3.2-34). While we acknowledge the success of the current program, and the challenges that the Port undertook to implement it, the FEIS needs to incentivize and require continuous improvement for drayage trucks. Additionally, the Port of Los Angeles needs to fulfill its promise “to accelerate the verification or commercial availability of new, clean technologies, through evaluation and demonstration, to move towards an emissions free port⁸.”

The DEIS offers lease measure LM AQ-1, Periodic Review of New Technology and Regulations, as a means to incorporate the Port’s Technology Assistance Program and Zero Emissions Technology Program. This measure could be dramatically improved with a schedule for implementation of zero tailpipe emission trucks, following the Ports determination that a zero tailpipe emission technology is feasible. The Los Angeles Harbor Commission proposed a lease measure that would require low-emission drayage trucks from 2016 to 2026 for the Southern California International Gateway. That requirement could be met by natural gas powered trucks, which we are not suggesting for this project, as it does not fully mitigate the project’s high and disproportionate impacts; however, that schedule could serve as a basis for a zero emission drayage truck schedule. Following successful demonstration of zero emissions drayage truck by the Port, the schedule could be adjusted to account for current uncertainties, such as capital and operating costs, incentives and other differences between zero emissions and natural gas trucks.

USEPA-17

Recommendations: The FEIS should describe zero and near zero emission tailpipe demonstration and deployment projects. The FEIS should include lease measure AQ-3 providing a schedule for phase-in of zero emission drayage trucks by the leaseholder, following successful demonstration by the Port. The lease measure could include adjustment criteria to account for current uncertainties.

Mitigation measure AQ-16, Truck Idling Reduction Measure, limits idling to 30 minutes total and 10 minutes at any one time. Many vehicles are commonly limited to 5 minutes or less of idling, such as school busses and sleeper berth heavy duty trucks. Even Mitigation Measure AQ-4, Fleet Modernization for Construction Equipment, limits idling to 5 minutes when not in use. EPA sees no need to justify ten minute idling for trucks at the APL terminal.

USEPA-18

Recommendation:

The FEIS should limit diesel truck idling at the APL terminal to 5 minutes.

Rail

The DEIS analysis appears to have used Tier 2 locomotives for the APL on-dock terminal (Table 3.2-7b), but the DEIS also notes that the Pacific Harbor Line will transition to a cleaner, Tier 3, diesel fleet by the end of 2011 if grant funds are available (p. 3.2-32). We congratulate the Ports and

USEPA-19

⁸ Technology Advancement Program, San Pedro Bay Ports, accessed November 18, 2011 < <http://www.cleanairactionplan.org/programs/tap/default.asp> >.

Pacific Harbor Line on the receipt of California's Carl Moyer grant funds⁹ to retrofit 16 locomotives to meet the Tier 3+ standard. As we noted earlier, stacked backland operation offers an opportunity to create additional space for on-dock rail. New rail lines could offer an opportunity to demonstrate zero emission rail transportation systems.

Recommendation:

The FEIS should discuss the potential for zero emission and hybrid rail transportation systems and evaluate layouts that increase the use of on-dock rail.

USEPA-19
Cont.

General Conformity:

General conformity requires federal agencies to demonstrate that the direct and indirect emissions from both the construction and the operational phases of the project conform to the approved State Implementation Plan and do not cause or contribute to violations of the National Ambient Air Quality Standards. While the DEIS estimated (NEPA) construction emissions for the project (Appendix E1), it did not estimate operational emissions.

The emissions associated with reasonably foreseeable action-related activities occurring during the operational phase of the project may be excluded from the general conformity evaluation only if the applicable Federal Agency lacks the authority to practically control these emissions (such as through conditions on permits) or the agency lacks continuing program responsibility for such emissions; however, the DEIS does not make this assertion.

USEPA-20

Recommendation:

The FEIS should include direct and indirect operational emissions as part of the general conformity evaluation.

Emissions Related to Transloaded Goods

The DEIS estimates emissions associated with goods movement for the APL terminal throughout Section 3.2 and Appendix E. These sections do not include an estimate of emissions following transloading of goods from marine shipping containers to domestic containers or trailers for re-shipping. The *Port and Modal Elasticity Study, Phase II*¹⁰ estimates that 36% of the goods shipped into the Ports of Los Angeles and Long Beach were transloaded.

USEPA-21

Recommendation:

The FEIS should include truck and locomotive emissions that occur in the South Coast Air Basin after transloading.

Diesel Emission Standards for Mitigation Measures

DEIS mitigation measures frequently cite compliance with EPA 2007 on-road and Tier 4 non-road emission standards (e.g., MM AQ-13, p. 3.2-110). Some but not all mitigation measures provide PM_{2.5} and NO_x emission levels. As the DEIS notes, EPA on-road standards allowed manufacturers to phase-in compliance with the NO_x emission standard of 0.2 grams per brake horsepower-hour (g/bhp-hr) and non methane hydrocarbons or NMHC (p. 3.2-22). EPA is also phasing-in Tier 4 standards for non-road engines beginning in 2008 to 2014; however engines from 75 to 750

USEPA-22

⁹ In the News: New Less Polluting Locomotives Arrive at Ports Complex, Anacostia and Pacific Company. (Pacific Harbor Line) accessed 11/21/2011, <<http://www.anacostia.com/latestnews/phl110929.html>>

¹⁰ Port and Modal Elasticity Study, Phase II, Final Report, Southern California Association of Governments

horsepower, are now available that meet the Tier 4 NOx standard, 0.3 g/bhp-hr. Larger mobile engines (greater than 750 horsepower) have one year of additional flexibility to meet their emissions standard¹¹.

Mitigation measure AQ-3, Fleet modernization for on-road trucks used during construction, commits to compliance with 2007 on-road standards for NOx, 1.2 g/bhp-hr or better, for on-road trucks. It commits to complying with 2004 on-road emission standards, 2.0 g/bhp-hr, for earth movers and import haulers. Mitigation measures AQ-13, AQ-14 and AQ-15 do not provide a NOx emission level. In view of the significant impacts to the air basin and residents, and the high and adverse impacts to environmental justice communities, the cleanest achievable NOx emission control is justified for trucks and equipment used on this project.

USEPA-22
Cont.

Recommendation:

Mitigation measures AQ-3, AQ-13, AQ-14 and AQ-15 should commit to meeting the cleanest available Tier 4 non-road diesel emission standard for NOx (e.g., 0.3 g/bhp-hr for engines from 75 to 750 horsepower) or the 2010 on-road standard for heavy-duty highway compression-ignition (diesel) engines (0.2 g/bhp-hr).

Reasonably Foreseeable Future Actions

The DEIS states the purpose and need for the proposed project “is to optimize the cargo handling efficiency and capacity at the APL Terminal to accommodate projected long-term increases in volume of containerized goods shipped through the port.” (p. 2-11) The proposed project would incorporate 7 acres behind Pier 301 as backlands, specifically for parking and storage (p. 2-16); however, none of the action alternatives include a fifth berth at Pier 301. A fifth berth would require the fill of a small channel separating Pier 301 from the 7 acres of backlands. Because the terminal is “berth constricted” as explained in Appendix C-2, an additional berth at Pier 301 could dramatically increase the throughput of the APL terminal. Adding a fourth berth would increase the terminal’s throughput more than 1 million TEUs per year in 2027. While the DEIS does not consider a fifth berth, the Port of Los Angeles’ *Terminal Island Land Use Plan, Summary Report (1/11/2012)* states¹², “[a] fifth berth at Pier 300 was decided to be a part of all options.” All three options also consider filling the channel behind Pier 301 and the Southeast corner of Fish Harbor¹³.

USEPA-23

Recommendation:

The FEIS should consider a fifth berth at Pier 300 as a reasonably foreseeable action and evaluate the air, water quality and other cumulative impacts resulting from it.

Refrigerated Container Storage Area

The proposed project includes creating a refrigerated container (reefer), storage area with plug-in electric power (p. ES-10). While the current APL terminal has an area of white-roofed containers, which we assume are reefers, in one area, the DEIS does not consider the benefit of a roof over the reefer storage area, to keep the containers cool. The roof might even include photovoltaic solar array to partially off-set the power use of the containers.

USEPA-24

¹¹ For more details and limits appropriate to smaller non-road diesel engines, see <http://www.epa.gov/nonroad-diesel/2004fr.htm>.

¹² See page 8, *Terminal Island Land Use Plan, Summary Report*, Port of Los Angeles, Planning and Economic Development Division, 1/11/2012

¹³ See page 13, *Terminal Island Land Use Plan, Summary Report*, Port of Los Angeles, Planning and Economic Development Division, 1/11/2012

Recommendation:

The FEIS should consider a roof over the reefer storage area for cooling and/or renewable energy generation purposes.

USEPA-24
Cont.

Harbor Craft Used During Construction

Mitigation measure AQ-1, Harbor Craft Used During Construction, contains practical measure to ensure clean, Tier 3, harbor craft are used during construction. The mitigation measure does not consider new Tier 4 standards applicable to harbor craft in 2015. The mitigation measure makes allowances in the event that the contractor can provide proof that harbor craft are unavailable for leasing in California, but equipment in Oregon and Washington would seem to be available at relatively minor transportation cost.

USEPA-25

Recommendation:

Mitigation Measure AQ-1 should be revised to require Tier 4 harbor craft in construction as of January 2015. It should also be revised to so that the contractor is required to provide proof that the cleanest Tier is unavailable in California, Oregon or Washington, before allowing the use of a lower Tier harbor craft.

Periodic Review of New Technology and Regulations

Lease measure LM AQ-1, Periodic Review of New Technology and Regulations, would require the ports tenant to consider new emissions reduction technologies. If the technology is determined by the Port to be feasible, the tenant will work with the Port to implement it (p. 3.2-111 and 112). This requirement would be required at the time of any lease amendment or facility modification, but "not less frequently than once every 7 years following the effective date of the permit."

USEPA-26

Recommendations:

The FEIS should commit to reviewing new technologies every five years from the date of the most recent facility lease. Additionally, technology reviews and any resulting recommendations should be made available to the public.

Water Quality

Sediment

The DEIS presents three options for disposal of sediment from dredging at Berth 306. Suitable sediment could be used as fill for the Cabrillo shallow water habitat or disposed at the LA-2 Ocean Dredged Materials Disposal Site. Sediment unsuitable for unconfined aquatic disposal would be placed at Port Berths 243-245 (p. 3.3-3). The DEIS also states that the majority of sediments off Berth 306 are unsuitable for unconfined aquatic disposal due to heavy metals and amphipod toxicity (p. 3.14-17); however, the easternmost portion of Berth 306 could qualify for placement at the Cabrillo shallow water habitat or disposal at LA-2.

USEPA-27

On July 27, 2011, the interagency Southern California Dredged Material Management Team (SC-DMMT; agencies include: EPA, Army Corps of Engineers, National Oceanic and Atmospheric Administration, Los Angeles Regional Water Quality Control Board, California Coastal Commission and the California Department of Fish and Game) reviewed the sampling and analysis report for this project (Appendix K) and concurred on several determinations:

- the eastern half of the proposed dredging area off Berth 306 is suitable for aquatic disposal (unconfined ocean disposal) or beneficial reuse placement;
- the western half of the proposed dredging area off Berth 306 contains potential contamination hotspots which requires further specific delineation to minimize the volume to dispose in the Pier 243-245 landfill.
- clean sediments may be too fine for beneficial reuse placement at the Port of Los Angeles Cabrillo Shallow Water Habitat Area; therefore this area needs standards and performance criteria as well as a monitoring plan

Recommendations:

The FEIS should discuss submissions of the following plans to the SC-DMMT:

- standards and sediment placement criteria for the Cabrillo shallow water habitat area
- a dredging plan including specific engineering specifications for the management of the suitable and unsuitable sediments, as well as cap placement over the unsuitable sediments after they are placed in confined aquatic site (Pier 243-245).

Ballast Water Treatment

The DEIS does not discuss the requirement for Vessel General Permits (VGP), under EPA's National Pollution Discharge Elimination System, authorized by the Clean Water Act. The VGP applies to discharges incidental to the normal operation of all non-recreational, non-military vessels of 79 feet or greater in length which discharge in waters of the United States. It requires vessel owners and operators to meet certain requirements, including seeking coverage for most vessels, assuring their discharges meet effluent limits and related requirements, corrective action process for fixing permit violations, and requirements for inspections, monitoring, recordkeeping and reporting. For more information, please see <http://cfpub.epa.gov/npdes/vessels/vgpermit.cfm#2008>.

The DEIS discusses a shipboard ballast water treatment system that APL is testing, in collaboration with the Ports of Los Angeles and Long Beach and the California State Lands Commission, but also prefaces this discussion with, "no feasible mitigation is currently available to totally prevent introduction of invasive species via vessel hulls or even ballast water, due to the lack of proven technology." (p. 3.3-59) On the contrary, as stated in the federal register notice for EPA's Draft 2013 VGP¹⁴:

The SAB [EPA's Science Advisory Board] found, among other things, that at least five types of ballast water treatments systems are available which treat to the limits found in the International Maritime Organization (IMO) Ballast Water Convention and proposed in today's permit.

As EPA noted in the *Proposed 2013 Vessel General Permit (VGP) Fact Sheet*¹⁵, the ballast water treatment system industry is relatively young and currently and has a limited production capacity, but Lloyd's Register estimated that 119 ballast water treatment systems had been installed worldwide by February 2010, and 200 systems installed by June 2011.

USEPA-27
Cont.

USEPA-28

¹⁴ 76 FR 76720, Thursday, December 8, 2011, <http://www.epa.gov/npdes/pubs/vgp_draft_federalregister2011.pdf>
¹⁵ See http://www.epa.gov/npdes/pubs/vgp_draft_factsheet2011.pdf

Recommendation:

The FEIS should include the requirements of the applicable VGP. The FEIS should also consider expedited implementation of ballast water treatment as a mitigation measure to reduce the significant impact of introducing non-native species into the Harbor.

USEPA-28
Cont.

2.3.1 Federal Government

United States Environmental Protection Agency (USEPA)

Response to Comment USEPA-1

Thank you for providing comments on the Draft EIS/EIR. Chapter 5, Environmental Justice, of the Draft EIS/EIR discusses the significant and unavoidable impacts from the proposed Project associated with air quality on minority and low income populations. Responses to specific comments on the proposed Project's air quality impacts from construction and operations to minority and low income populations are provided in more detail below. As stated on page 5-18 of the Draft EIS/EIR (Chapter 5, Environmental Justice), the maximum off-site ambient NO₂ concentrations associated with the proposed Project operations would remain significant and unavoidable after mitigation under NEPA. Since residential areas closest to the proposed Project are predominantly minority and have a higher concentration of low-income population relative to the County of Los Angeles, the elevated ambient concentrations of NO₂ would constitute a disproportionately high and adverse effect on minority and low-income populations. Adverse respiratory and pulmonary human health effects have been linked to exposure to NO₂. In addition, as also discussed on page 5-18 of the Draft EIS/EIR, the proposed Project would have significant effects on acute noncancer risks (i.e. an acute hazard index of 1.0 or greater) relative to the NEPA baseline. Because the populations closest to the proposed Project site are predominantly minority and low income, this elevated acute noncancer risk would represent a disproportionately high and adverse impact on minority and low-income populations. Mitigation to minimize significant NEPA impacts related to air quality during construction and operations is identified in the Draft EIS/EIR, and some mitigation measures were strengthened and are included in Chapter 3, Modifications to the Draft EIS/EIR, of the Final EIS/EIR. Other mitigation measures recommended by the Commenter and others have been determined to be infeasible, as discussed in other responses in this Chapter.

Please note that environmental justice impacts are based on the NEPA impact determination, not the CEQA impact determination, consistent with Executive Order 12898 (Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations) and the Council on Environmental Quality (CEQ) Guidance for Environmental Justice Under NEPA (CEQ 1997). For the proposed Project, cancer risk would be below the significance threshold before and after mitigation, under NEPA. For acute hazard risks, the threshold would be exceeded at occupational receptors located on Terminal Island and would not extend to the mainland (the location of the adjacent communities of San Pedro and Wilmington, which have designated environmental justice populations).

The unavoidable significant impacts related to cancer risk under CEQA identified for the proposed Project would apply to live-aboards at the marina west of Terminal Island Freeway and to a lesser extent, the marina in Fish Harbor. The cancer risk increment would not exceed the threshold at residential receptor locations on the mainland (e.g. the communities of San Pedro and Wilmington). Exceedence of the cancer risk threshold for occupational receptors would be confined to terminal Island and would not extend to the mainland. Unavoidable acute hazard risks under CEQA for occupational receptors on Terminal Island would remain, but these would not extend to the mainland. Mitigation to minimize significant CEQA impacts is identified in the Draft EIR.

Response to Comment USEPA-2

The Commenter's recommendations to add additional mitigation to address impacts to Environmental Justice are noted, and responses to specific comments are provided below.

1 The LAHD and USACE have prescribed a number of mitigation measures in the Draft EIS/EIR that
2 together would substantially reduce impacts associated with the proposed project and alternatives on
3 minority and low income populations, in particular to air quality. Additional mitigation was not considered
4 available or feasible.

5 In addition, the LAHD is implementing various other beneficial measures to the surrounding community.
6 Harbor Department Agreement No. 09-2764 (also known as the TraPac Memorandum of Understanding or
7 MOU) requires the establishment of a Port Communities Mitigation Trust Fund (Fund) to fund mitigation
8 and grant projects to help offset past, present, and future impacts from Port Projects on off-port areas in the
9 communities of Wilmington and San Pedro. If the proposed Project were approved, the deposit to this Fund
10 is anticipated to be over \$4.2 million. Additional information on the Fund can be found in Response to
11 Comment USEPA-6.

12 LAHD and the USACE has carefully considered all mitigation measures proposed as part of the public
13 comment period, including those proposed as part of this comment letter, and has added all mitigation that
14 was found feasible and appropriate to mitigate identified impacts to the Final EIS/EIR.

15 **Response to Comment USEPA-3**

16 As highlighted by the Commenter, the Port of Los Angeles is an active partner in the Technology
17 Advancement Program (TAP) Program, along with the Port of Long Beach (POLB), the USEPA (Region 9),
18 California Air Resources Board (CARB), and South Coast Air Quality Management District (SCAQMD).
19 Consistent with the Clean Air Action Plan (CAAP), the TAP seeks to reduce emissions from the five source
20 categories through evaluation and demonstration of emerging technologies. The Draft EIS/EIR includes
21 lease measure LM AQ-1, which requires that the terminal operator to periodically implement new emissions
22 reduction technologies. As new technologies that are proven to be effective in reducing emissions and in
23 serving key functional requirements in the goods movement process in the Ports become commercially
24 available and are applicable to terminal operations, those would be adopted via LM AQ-1. As shown in
25 Chapter 3, Modifications to the Draft EIS/EIR, lease measure LM AQ-1 has also been revised to reflect a
26 revision of the 7 year lease reopener to a more stringent 5 year reopener. It should also be noted many of
27 the technologies being demonstrated under the TAP are more suited to Port-wide implementation once the
28 technologies are ready for production. Because the timing for proving the technical and operational
29 feasibility of the technologies, commercial production, and the ability of other parties in the goods
30 movement chain to fund equipment purchases to implement the new technologies cannot be provided or
31 forecasted at this time with any degree of specificity, the Draft EIS/EIR includes LM AQ-1 to allow for new
32 technologies to be adopted after they become feasible in the future.

33 **Response to Comment USEPA-4**

34 In regards to APL's new ships, as noted in the comment letter, APL is testing the effectiveness of other
35 emission reducing technologies (see the Response to Comment USEPA-8 below) on several of its newest
36 vessels, and is implementing various operational measures to further reduce emission.

37 With the exception of 10 new-build vessels (described in Response to Comment USEPA-8 (below)), the
38 newest ships purchased by APL are the very largest ships in APL's fleets. These large ships are designated
39 for the Asia-Europe routes. Ships on the Asia-Europe routes travel west between Asia and Europe,
40 typically stopping at over 14 ports along their routes (these vessels generally stop at 5 to 6 port calls in the
41 Far East, 3 to 4 port calls in the Mid-East, and 6 to 8 port calls in Europe). This is an effective use of a
42 these sized vessels because it is feasible to filled each ship to capacity. Further, the size of the ship allows
43 for faster port turnarounds because the ship is not fully unloaded or loaded at each individual port. On the
44 Asia-Europe routes, the time in port is approximately 24 hours.

1 The Transpacific route (Asia –West Coast U.S.) operates quite differently from the Asia-Europe routes and
2 is focused on regular weekly services transporting goods between a few ports. On the Transpacific route, a
3 ship leaves from an Asian port and typically stops at 1-2 ports on the west coast, and then returns to its
4 beginning destination. Fewer port stops means that it is more difficult to fill the largest ships to capacity,
5 while maintaining a schedule that enables weekly deliveries. More importantly, if the largest ships were
6 filled to capacity, then they would need to be in port for more time than the smaller ships, which would
7 make it impossible to operate a weekly service due to the combined time in port and time in transit.

8 A liner's deployment of particular container vessels is driven by market demand, rates, and fuel prices.
9 Requiring deployment of the newest ships to the Port of Los Angeles would not be considered feasible due
10 to operating cost considerations and would place APL at a severe competitive disadvantage.

11 In regards to retrofitting older ships, APL has already installed slide valves on all APL owned vessels with
12 MAN B&W engines. However, APL has committed to upgrades to reduce emissions which are detailed in
13 the Draft EIS/EIR and will be required as part of the lease. As an example, ships calling at the Port of Los
14 Angeles will be retrofitted to plug into shore side power (representing a \$13.1 million capital investment)
15 and include necessary upgrades to enable low sulfur fuel switching. More detailed information is included
16 in Response to Comment USEPA-8.

17 **Response to Comment USEPA-5**

18 Comment noted. Responses to detailed comments on the Draft EIS/EIR are provided below. The LAHD
19 and Corps respectfully disagree with the USEPA's findings that the Draft EIS/EIR contained insufficient
20 information. A hard copy and electronic copy of the Final EIS/EIR will be sent as requested.

21 **Response to Comment USEPA-6**

22 The Draft EIS/EIR includes a full analysis on Environmental Justice in Chapter 5 based on guidance from
23 CEQ. Regarding health risk impacts from exposure to toxic air contaminants, a complete discussion is
24 provided in the Draft EIS/EIR on pages 3.2-132 – 3.2-149 related to the proposed Project.

25 The cumulative impact analysis in Chapter 4 and Chapter 5 consider the effects of other related projects in
26 the Port Complex in addition to the proposed Project, on the surrounding community. Cumulative projects
27 include the Port of Long Beach's Pier S Project, the Southern California International Gateway Project, and
28 I-710 project.

29 As discussed in Response to Comment USEPA-1, the Draft EIS/EIR identifies a disproportionately high
30 and adverse impact on minority and low income populations related to air quality and noise, including
31 cumulative air quality impacts. The maximum off-site ambient NO₂ concentrations associated with the
32 proposed project operations would remain significant and unavoidable after mitigation under NEPA. As the
33 Draft EIS/EIR discusses, adverse respiratory and pulmonary human health effects have been linked to
34 exposure to NO₂. The mitigation measures in the Draft EIS/EIR have been developed to address significant
35 impacts identified in the technical analysis related to the proposed Project. Additional mitigation was not
36 found to be feasible based on technical availability, operational issues and prohibitive costs. However,
37 LAHD has been engaged in numerous Port-wide activities to contribute to the improvement of the
38 Wilmington and San Pedro communities. To help offset past, present, and future impacts from Port projects
39 on off-port areas in the communities of Wilmington and San Pedro, where the majority of low income and
40 minority populations near the Port are located, the Port is implementing Harbor Department Agreement No.
41 09-2764, to fund mitigation and grant projects (via the Port Communities Mitigation Trust Fund). As
42 discussed above in Response to Comment USEPA-2, if approved, LAHD would deposit approximately \$4.2
43 million in the Fund.
44

1 Approximately \$11 million has already been allocated to fund mitigation and grant projects identified in the
2 Fund. As detailed in the TraPac MOU, approximately \$6 million has been allocated for air filtration
3 systems in schools, and \$5 million has been allocated for the following uses: installation of double-paned
4 windows in schools and residences in the Wilmington community, funds to local clinics, health service
5 providers, and other organizations aimed at addressing health impacts that result from air quality impacts
6 from port operations, and job training and hiring programs.

7
8 Regarding the suggestion that LAHD invest in the improvement of local community parks and a recreation
9 system, in June 2011, the LAHD opened the Wilmington Waterfront Park, a new 30-acre open space with
10 walking and bike paths, plazas, playing fields, event spaces, and a playground for the Wilmington
11 community. Previously the parcel had been planned as a container terminal expansion area. However,
12 through a multi-year community planning process, the 30 acres became a dedicated open space, one that
13 complements an additional adjacent 90-acre area to provide improved public access and recreational
14 activities at the Wilmington Waterfront. For more details please refer to the Wilmington Waterfront Project
15 EIR that was approved by the LAHD in 2009.

16
17 Additional LAHD efforts to address other impacts to the surrounding community include projects
18 completed under the Mitigation Trust Fund related to the Amended Stipulated Judgment for the China
19 Shipping Project. Approximately \$34 million has been set aside for various community improvements,
20 including community health measures. As part of this fund, the LAHD has contributed \$1 million to the
21 Robert F. Kennedy Health Institute to provide health education and social services in the Wilmington Area.
22 Eight health workshops and two health fairs have already been held through December 2011. The health
23 workshops included topics such as air pollution and health effects, asthma, heart health care, breast cancer,
24 chronic respiratory disease, and emphysema. The two health fairs (held in May and October 2011) were
25 attended by 356 persons.

26
27 Regarding the comment to engage in proactive measures to train and hire local residents, the LAHD has
28 entered into a five-year Port-wide Project Labor Agreement (Port-wide PLA) with the building and trade
29 unions affiliated with the Los Angeles/Orange Counties Building and Construction Trade Council (Building
30 Trades). The Port-wide PLA will serve as a blanket agreement between the Harbor and Building Trades
31 hired to work on selected Capital Improvement Program (CIP) projects for a term of five years. The Port-
32 wide PLA seeks to address unemployment and underemployment in concentrated poverty neighborhoods,
33 particularly near to Port, and seeks to advance the skills of the local labor pool. To this end, the Port-wide
34 PLA requires a hiring minimum of local resident workers and disadvantaged workers. The PLA has a goal
35 of at least 30 percent of total work hours to be performed by local residents residing within the targeted
36 areas of the City using a two-tier approach. The first tier includes residents within approximately 10 miles
37 of the Port, and the second tier includes residents of high unemployment zip codes throughout the
38 remainder of the City of Los Angeles. The implementation mechanism for the PLA is the construction
39 contract documents.

40 **Response to Comment USEPA-7**

41 As discussed in the Response to Comment USEPA-2 and USEPA-6, the Port is currently funding
42 community mitigation and grant projects (via the Port Communities Mitigation Trust Fund and the China
43 Shipping Mitigation Trust Fund) to help offset past, present, and future impacts from Port projects on off-
44 port areas in the communities of Wilmington and San Pedro, where the majority of low income and
45 minority populations near the Port are located. These trust funds are mechanisms for moving forward and
46 support the collaborative efforts to grow and sustain the Port in a manner that provides a concrete way to
47 reduce cumulative environmental impacts on the community while creating jobs and economic prosperity to
48 the surrounding region.

1 **Response to Comment USEPA-8**

2 As the Commenter notes, the use of shoreside power during hoteling greatly reduces Port area emissions by
3 allowing the ships' main and auxiliary engines to be turned off. During transit, current main and auxiliary
4 engine emission reduction strategies are more limited and have not matched the effectiveness of AMP. As
5 shown in the Draft EIS/EIR, even with cleaner fuels and other emissions improvements over time, ship
6 transit emissions will not be reduced to a similar extent as shore-side vessel emissions.

7 Regarding the Commenter's request to further develop CAAP measures and include such measures in the
8 Draft EIS/EIR, the Draft EIS/EIR has identified a process to implement future technology. The CAAP is
9 not a static plan and as the Commenter has noted, LAHD is working on advancing emission reduction
10 strategies through the TAP and regular updates to the CAAP. LAHD is also working with the International
11 Association of Ports and Harbors (IAPH) to develop incentive program strategies to participate in the
12 Environmental Ship Index (ESI) Program. ESI is an international web-based ship-rating system ports can
13 use to promote clean ships by rewarding operators whose vessels exceed current environmental
14 performance standards and regulations. The ESI identifies voluntary engine, fuel and technology
15 enhancements ships can use to exceed current environmental performance standards. The ESI targets
16 primary pollutants, which include nitrogen oxides (NOx), sulfur oxides (SOx), and diesel particulate matter
17 (DPM). The program also contains a component to help reduce greenhouse gases. While future technology
18 identified by these efforts cannot specifically be added to the Draft EIS/EIR, as detailed in Response to
19 Comment USEPA-3, the Draft EIS/EIR includes lease measure LM AQ-1, which requires the terminal
20 operator to periodically implement new emissions reduction technologies, such as those for ocean-going
21 vessels. As shown in Chapter 3, Modifications to the Draft EIS/EIR, lease measure LM AQ-1 has also been
22 revised to reflect a revision of the 7 year lease reopener to a more stringent 5 year reopener.

23 In addition, APL is a leader in the testing and installation of retrofits to reduce ship emissions. The
24 following are a few examples of APL's commitment to reducing air emissions (the technologies are
25 consistent with the TAP):

- 26 ▪ APL retrofitted five vessels for cold ironing almost three years in advance of regulations requiring
27 use of AMP. These retrofits, and improvements to the terminal to accommodate the vessels,
28 represented a \$13.1 million capital investment. The five APL AMP-capable vessels, which had 41
29 cold iron events in Oakland in 2011, also call at the Port of Los Angeles and therefore will be
30 available to use AMP facilities once installed (AMP installation at Berths 302-305 would occur in
31 phases from September 2013 through February 2014). By plugging APL's ships in at Oakland three
32 year prior to regulations, APL has eliminated nearly 3,600 pounds of VOC's, 70,000 pounds of CO,
33 140,000 pounds of NOx, 4,000 pounds of PM, and 425,000 pounds of SOx emissions. It should be
34 noted that LAHD and APL developed plans to install AMP at Berths 302-305 before the Draft
35 EIS/EIR was prepared and the CARB rule became effective (AMP at Berths 302-305 is a related
36 project included in Chapter 4 of the Draft EIS/EIR).

- 37 ▪ APL is currently testing a state-of-the-art seawater scrubber aboard the APL England. This \$3.6
38 million project was funded in part by a \$1.65 million grant from the TAP. The scrubber features an
39 advanced emission control technology in which seawater is used to scrub, or filter, contaminants
40 from a ship's auxiliary engines and boiler before exiting the exhaust stack of a ship. Once solid
41 carbon contaminants are removed, the seawater used during the scrubbing process is then treated
42 and cleansed before being discharged. A hydro cyclone removes carbons and any liquids that are
43 not water soluble and returns the seawater to a clean, discharge-safe state. This water is then
44 pumped overboard and the solids removed by the hydro cyclone are stored in a plastic container
45 and are offloaded ashore for proper disposal. If it proves to be effective, the scrubber could result

- 1 in air emission reductions of approximately 80 – 85 percent PM, 99.9 percent SO_x, more than a 90
2 percent decrease in VOCs and 10 percent NO_x from the auxiliary engines and boiler.
- 3 ■ APL has installed slide valves on all APL owned vessels with MAN B&W engines. APL slide
4 valves reduced almost 29 tons of NO_x emissions from 2002 – 2011.
 - 5 ■ Several ships' auxiliary engines use Constant Water Injection to humidify the scavenge air and
6 lower exhaust gas temperatures thereby reducing NO_x emissions by over 20 percent.
 - 7 ■ APL is also installing a fuel cavitation system for main and auxiliary engines to produce a fuel
8 emulsification with 20 percent water. This is expected to generate a fuel savings of 10 percent for
9 the main engine and 18 percent for auxiliaries. Less fuel used translates directly into fewer
10 emissions.
 - 11 ■ APL participates in the Port's voluntary vessel speed reduction program which resulted in the
12 following annual emission reductions: (2011- 11.08 tons PM₁₀, 11.37 tons DPM, 166.14 NO_x,
13 118.62 tons of SO_x, and 6369.81 tons of CO₂), (2010- 11.19 tons PM₁₀, 11.47 tons DPM, 166.44
14 NO_x, 118.21 tons of SO_x, and 6369 tons of CO₂), (2009- 8.8 tons PM₁₀, 9.0 tons DPM, 133 tons
15 NO_x, 94.8 tons of SO_x, and 5106 tons of CO₂),
 - 16 ■ APL vessels slow steam (reduced vessels speeds during transit), which further reduce CO₂, CO,
17 SO_x, NO_x, and PM₁₀ and DPM emissions.
 - 18 ■ APL will introduce approximately 10 new build vessels into the Transpacific service that will call
19 at the Port. These vessels will be AMP capable, they will have an electronic main engine to
20 optimize low load operation with reduced fuel consumption and emissions, they will come
21 equipped with a full spade twisted rudder and propeller with pre-swirl stator for improved
22 performance and efficiency, they will have an optimized hull form and trim for optimized fuel
23 consumption and emissions, as well as self-polishing environmental friendly paint which reduces
24 fuel consumption and emissions.

25 **Response to Comment USEPA-9**

26 Comment noted. Please see Response to Comment USEPA-4 above; APL has been investing significant
27 funds in new ships and ship-board technology. It should also be noted that in 2009, APL's parent company,
28 NOL Group, operated at a net loss of \$741 million and in 2011, NOL Group lost \$478 million. Losses at
29 APL made up the entirety of this loss.. In 2011, APL's earnings before interest and taxes totaled negative
30 \$466 million. Meanwhile, cargo throughput at Pier 300 has fallen as compared to the baseline year, such
31 that 2011 volumes (1,403,845 TEUs) remain below the volumes handled in 2008-2009 (1,128,080 TEUs)
32 and peak volumes handled in 2004(1,644,062 TEUs) (see Response to Comment USEPA-12). Due to
33 market conditions, it is unlikely that APL will have the ability to purchase additional new ships beyond
34 those described in the Response to USEPA-8, before market conditions improve.

35 **Response to Comment USEPA-10**

36 The Commenter incorrectly identified MM AQ-10 as a mitigation measure related to OGV engine
37 technologies when in fact it is a measure associated with the vessel speed reduction program. As it relates
38 to the OGV mitigation measures associated with the proposed Project (MM AQ-11 and MM AQ-12), as the
39 Commenter noted, the OGV5 and OGV6 measures are “developing” CAAP measures. The Draft EIS/EIR
40 analysis assumes compliance with the CAAP. In fact, proposed Project-specific mitigation measures
41 applied to reduce air emissions and public health impacts are consistent with, and in some cases exceed, the

1 emission-reduction strategies of the CAAP. The mitigation measures prescribed for the proposed Project or
2 alternative would be required in construction contracts or become part of the tenant's lease and would no
3 longer be tied to implementation of the CAAP; however, should the CAAP be strengthened in the future,
4 lease measures LM AQ-1 and LM AQ-2 provides a mechanism for additional measures to be incorporated
5 into the tenant's lease.

6 **Response to Comment USEPA-11**

7 Please see the Response to Comments USEPA-8, USEPA-9, and USEPA-10.

8 **Response to Comment USEPA-12**

9 As the Commenter notes, an automated system is discussed in the Draft EIS/EIR. It should be clarified that
10 the infrastructure that is proposed for installation to support an electronic automated terminal is only for
11 potential automation of Berth 306 backlands. Both wheeled and stacked container management is used at
12 the existing terminal, and both such methods would continue into the future with or without automation at
13 Berth 306. An automated stacking system on the backlands behind Berth 306 is a potential project
14 component that could be implemented if and when the terminal operator determines that the underlying
15 economics and market conditions can support such a capital intensive system. Given that 2011 cargo
16 volumes remain far below the volumes handled at the height of operations in 2004, market conditions will
17 have to improve before such a component can be implemented.

18 The comment that an automated stacking system could result in more land being made available for on-
19 dock rail is not a correct premise for the Berths 302-206 terminal. The current area allocated for the on-
20 dock railyard is adequate to support terminal operations in the near term. Longer term, an expansion of the
21 on-dock railyard could occur independent of whether an automated stacking system is implemented at Berth
22 306 as identified in the Terminal Island Plan. LAHD is currently examining ways to increase on-dock rail
23 capacity Port-wide including on Terminal Island. Increasing Terminal Island rail capacity would
24 necessitate a coordinated effort as there are a number of external constraints in the rail system between the
25 Terminal Island and the Alameda Corridor, such as capacity limits on the Badger Bridge (the only rail
26 bridge connecting terminal island to the mainland) and the configuration of main track crossovers and leads
27 to CP Mole.

28 Regarding the comment that an automated stacking system should be required under the proposed Project to
29 further reduce on-terminal emissions, as noted, terminal emissions would only represent 1 percent of future
30 emissions based on mitigation identified in the Draft EIS/EIR. As discussed in the Draft EIS/EIR, because
31 automation is planned for the backlands behind Berth 306, not the entire terminal, implementing automation
32 would not decrease any remaining significant air quality impacts. Table 1.6-44 in Appendix E1 of the Draft
33 EIS/EIR shows that automation would decrease emissions by approximately 4 percent. As such,
34 automation would not represent an effective mitigation measure to reduce emissions to a less than
35 significant level. In addition, implementation of such a system would require a significant capital
36 investment for EMS, the terminal operator. The decision to implement an automated container handling
37 system is based on market conditions, capital availability, technical feasibility, and acreage. All four
38 elements need to be aligned for the automated container handling system to be feasible. In addition to a
39 large equipment capital investment, dedicated terminal acreage is required with the understanding that once
40 automation is in place the likelihood of reverting is very small. EMS requires the flexibility to weigh all
41 these variables in order to make a decision at the right time based on the business need and ability.

42 Therefore, the automated stacking system is a potential Project component that is included in the Draft
43 EIS/EIR because it could be implemented in the future. Because the automated stacking system represents a
44 project component and not a lease or mitigation measure, it is disclosed in the Draft EIS/EIR as an option,
45 not a requirement of lease measure LM AQ-2.

1
 2 EMS estimates that the capital cost of automation will be in the hundreds of millions of dollars (recent
 3 reports on the OOCL automated terminal at the Port of Long Beach indicate the capital costs for that
 4 terminal will be approximately \$1 billion). By contrast, traditional yard operations would require no new
 5 equipment in the short term, with the exception of new shore side cranes, which would be required under
 6 either an automated or a traditional operation. Recent volatility in liner profitability and container
 7 throughput makes it impossible for EMS to commit to a capital expenditure of this magnitude in the near
 8 term. In 2009, APL's parent company, NOL Group, operated at a net loss of \$741 million and in 2011,
 9 NOL Group lost \$478 million. The entirety of this loss was due to APL. In 2011, APL's earnings before
 10 interest and taxes totaled negative \$466 million. Meanwhile, as shown below, cargo throughput at Pier 300
 11 has risen and fallen, such that 2011 volumes remain far below the volumes handled in 2004.

| 12 | <u>Year</u> | <u>Annual Lifts</u> |
|----|-------------|--------------------------|
| 13 | 2004 | 931,188 (1,644,062 TEUs) |
| 14 | 2005 | 744,856 (1,289,136 TEUs) |
| 15 | 2006 | 866,064 (1,507,265 TEUs) |
| 16 | 2007 | 924,107 (1,613,098 TEUs) |
| 17 | 2008 | 789,976 (1,381,303) |
| 18 | 2009 | 597,448 (1,050,656) |
| 19 | 2010 | 873,797 (1,558,975) |
| 20 | 2011 | 792,179 (1,403,845) |

21 As a result, EMS intends to move forward with capital expenditures for new cranes at Berth 306 and will
 22 not accept a lease that requires installation of automated equipment. Such a lease requirement is therefore
 23 not a currently economically feasible component of the proposed Project, but may be so in the future if and
 24 when market conditions support such an option.

25 **Response to Comment USEPA-13**

26 The Commenter is correct that a fully electrified terminal was not considered to be a viable alternative at
 27 this time, in part, due to the berth constrained nature of the terminal. In addition, the Draft EIS/EIR provides
 28 additional reasons why such a terminal was not carried forward for a co-equal evaluation; namely, although
 29 several test projects are underway that are intended to demonstrate the feasibility and reliability of the zero-
 30 emission trucks and cargo-handling equipment, full electrification of the Berths 302-306 Container
 31 Terminal is not considered to be operationally feasible at this time, and therefore was not considered to be a
 32 viable or feasible alternative to the proposed Project.

33 The comment that “Alternative 6 is a step in the right direction but that more on-dock rail is needed so that
 34 drayage trucks to near dock yards can be eliminated” appears to be based on a premise that on-dock rail
 35 capacity can replace the need for near-dock capacity. If so, that premise is incorrect. Both types of railyards
 36 are needed and are complimentary to each other, as described in greater detail below and in Chapters 1 and
 37 2 of the Draft EIS/EIR.

38 Over the last ten years, on-dock volumes have increased steadily in the Ports of Los Angeles and Long
 39 Beach (Ports) for a variety of reasons, including the provision of additional on-dock capacity. Additionally,
 40 the total direct (on-dock and off-dock volume, excluding transloading) intermodal volume share has
 41 remained fairly constant, at around 40 percent of total Port TEUs. Historically, the APL Terminal total
 42 direct intermodal and on-dock shares have been higher than the aggregate Ports proportions (see following
 43 information).

| | | | | | | | | |
|-----------------------------|------|------|-------|-------|-------|-------|-------|-------|
| On-Dock Rail | 2001 | 2002 | 2003 | 2004 | 2005 | 2006 | 2007 | 2008 |
| % of Vessel Lifts (APL) | 22% | 20% | 16% | 17% | 22% | 27% | 30% | 38% |
| % of vessel Lifts (POLA/LB) | n/a | n/a | 15.9% | 18.1% | 20.7% | 24.1% | 23.0% | 23.7% |

1

2 To help accommodate the anticipated cargo volumes, the Ports plan to expand existing and construct new
 3 on-dock railyards and supporting infrastructure over the next 10 to 15 years. In addition, the Ports will seek
 4 to maximize the on-dock operations at the marine terminals by encouraging tenants to schedule round-the-
 5 clock shifts and optimize labor rules.

6 Despite the efforts by the Ports to develop additional on-dock capacity and by the railroads to increase
 7 utilization of on-dock rail, however, a number of factors will continue to limit the overall percentage of on-
 8 dock rail use. First, not all intermodal cargo can be handled at on-dock railyards. As described in Chapter
 9 1, cargo at a marine terminal is sorted by destination. If there are enough cargo containers bound for the
 10 same destination, a unit train to that destination will be built at the on-dock facility. If, however, there are
 11 containers bound for different destinations, they must be either stored in the terminal, resulting in delays
 12 and congestion, or trucked to a near/off-dock facility to be combined with cargo from other marine
 13 terminals bound for that same destination. Other limiting factors include shipper and steamship line
 14 logistics (e.g. transloading, transportation costs, etc.) and railroad operations (equipment availability, train
 15 schedules, and contracts/arrangements with shippers).

16 Second, as discussed in Chapter 1, detailed rail simulation analyses have determined that even with billions
 17 of dollars of rail infrastructure improvements planned/proposed in the POLA/POLA, the projected on-dock
 18 volumes for the APL Terminal and all other terminals in the POLA/POLB used in the Draft EIS/EIR is the
 19 maximum amount that can be accommodated. Accordingly, there will always be a need for off-dock
 20 loading of containers. This detailed rail system simulation has also determined that even the movement of
 21 containers on trains via “block swap” and “unsorted” operations will not yield higher capacities or greater
 22 use of the on-dock facilities. Accordingly, of the 17.3 million TEUs of intermodal cargo projected by the
 23 Year 2035 (see Table 1-5 in Chapter 1 of the Draft EIS/EIR), only 12.9 million TEUs will be handled by
 24 existing and planned on-dock railyards. The on-dock railyard capacities accounted for in this data (as well
 25 as the SCIG Draft EIR), were updated from what is contained in the *San Pedro Bay Ports Rail Study*
 26 *Update (2006)*.

27 Consequently, the assumption that 35 percent of the containers would move via on-dock rail, while 10
 28 percent would move via off-dock rail is reasonable. Furthermore, it should be noted that under Year 2027
 29 proposed Project conditions, the existing APL Terminal on-dock railyard capacity (and used for all project
 30 alternatives except Alternative 6), would be reached, and could only handle 32.4 percent of the total
 31 terminal TEU. It should also be noted that the estimated capacity of the existing and expanded on-dock
 32 railyard were updated from what is contained in the *San Pedro Bay Ports Rail Study Update (2006)*.
 33 Therefore, by not assuming more than 35 percent for on-dock movements, the Draft EIS/EIR analysis yields
 34 conservative results as more truck trips are projected.

35 **Response to Comment USEPA-14**

36 Please see Response to Comment USEPA-13. The comment appears to be based on the premise that
 37 operating the APL Terminal using wheeled or low stack heights is impeding the expansion of the on-dock
 38 yard, which if implemented, would eliminate the need for drayage trucks to haul containers to near dock
 39 yards. The area allocated for container management on the backlands is not preventing the on-dock yard
 40 from being expanded. As described in USEPA-13, expanding on-dock capacity will not substantively result
 41 in a greater proportion of on-dock rail usage.
 42

1 The percentage of wheeled versus stacked containers on a terminal is related to many factors, including the
2 cargo origin/destination mix, land availability, and vessel schedules. The Euromax Terminal (Rotterdam)
3 the commenter references handles a broader mix of cargo, meaning it serves as a point where cargo is
4 transferred from very large Asia-Europe route-ships for transport to smaller ships for short sea shipping
5 through Europe. Therefore, the cargo does not need to be sorted much while on Terminal and stacking is an
6 efficient mode of cargo management. Terminals at the Port are receiving ports and must sort cargo for
7 transport to individual destinations, therefore wheeled operations are generally favored over stacked as
8 wheeled operations are more efficient (the exception is for empty cargo containers; empties do not need to
9 be sorted and therefore are stacked up to 5 high at the Port). EMS's current mode of operation is to have as
10 many containers on a chassis as possible so the terminal operator touches the container the fewest number
11 of times. As an example, a container can be discharged from the vessel to a chassis, and a street trucker
12 then can hook up to the container and leave the terminal. The terminal operator will have touched the
13 container only once, minimizing labor cost¹ and terminal equipment usage. As a second example, a
14 container can be discharged to the ground and then stacked, and then delivered to the street trucker. The
15 terminal operator will have touched the container three times: discharge, deck to the ground, delivery from
16 the ground. The second example increases not only labor expense but also potential air emissions.
17 Finally, for the reasons stated in Response to Comment USEPA-13, the on-dock infrastructure for the entire
18 Port Complex has been maximized in the analyses, and more on-dock rail use cannot be assumed.
19 Moreover, detailed rail simulation analyses have determined that even with billions of dollars of rail
20 infrastructure planned/proposed in the Port Complex, the projected on-dock volumes for the APL Terminal
21 and all other terminals in the Port Complex used in the Draft EIS/EIR is the maximum amount that can be
22 accommodated.

23
24 The Commenter also recommends combining Alternative 5 and 6 into a single alternative to optimize
25 terminal operations. Because both of those alternatives would have the same throughput and have the same
26 option for an automated staking system behind Berth 306, such a combined alternative would not represent
27 a substantial change from the range of alternatives (or their impacts) analyzed in the Draft EIS/EIR.

28 **Response to Comment USEPA-15**

29 As stated in Response to Comments USEPA-12 and USEPA-13, the on-dock infrastructure for the entire
30 Port Complex has been maximized in the analyses, and more on-dock rail use cannot be assumed. Until the
31 APL Terminal railyard and POLA/POLB rail system reaches capacity, using the APL Terminal on-dock
32 railyard for other terminals containers would result in additional cargo handling which translates to
33 additional air emissions and expenses. The additional revenue from third party terminals necessary to
34 cover these increased expenses would result in an uncompetitive high on-dock rail rate versus alternate
35 transportation modes for near-dock rail yard customers. As detailed above under Response to Comment
36 USEPA-14, EMS's current mode of operation is to have as many containers on a chassis as possible so the
37 terminal operator touches the container the fewest number of times. A decked operation adds \$50 per lift
38 compared to a wheeled operation. The current market rate for a rail lift is \$100 per lift. If EMS were to
39 handle third party business, it would need to add \$50 per lift to cover the increased cost for decking its own
40 containers due to reduced container yard acreage to handle additional on-dock containers, plus another \$50
41 per lift for a gate move into the facility. A fee of \$200 per rail move would not be competitive versus a
42 competing terminal operator using its own on-dock rail or draying to a near dock rail facility at a cost of
43 approximately \$75 per lift. Based on this, the recommendations to expand the on-dock rail yard and utilize
44 excess capacity as a near -dock yard to other Terminal Island container terminals is neither economically
45 feasible nor an effective means of reducing overall Project impacts.

¹ As a note, fewer times a terminal operator touches a container generally translate to fewer air quality emissions being emitted.

1 **Response to Comment USEPA-16**

2 USEPA's request for additional mitigation is noted. LAHD and USACE are committed to applying all
3 feasible mitigation measures to minimize impacts. The Draft EIS/EIR air quality analysis was conducted
4 based on LAHD protocols and Port-specific methods of environmental analysis used for Port projects over
5 the last several years. These protocols and Port-specific methods are intended to report the maximum
6 potential impacts so a comprehensive set of mitigation requirements can be applied. In addition, the
7 analysis conducted for the Draft EIS/EIR is very conservative. The impacts simply add the future
8 concentrations to the existing background, even though the existing (CEQA baseline) operations contribute
9 to the existing background. The existing background NO₂ concentration is assumed to be uniform
10 throughout the analysis area and consumes almost 80 percent of the NAAQS, therefore the modeled extent
11 of the NO₂ concentrations, when added to the background, exceed the NAAQS in most of the study area.
12

13 Regarding the suggestion that the construction schedule could be altered to reduce the potential for acute
14 hazard risks, as described in the Draft EIS/EIR, the proposed Project would emit certain emissions whether
15 constructed over a short or longer period of time. These risks are driven by a combination of operational
16 ship maneuvering and docking, construction cargo ship hoteling, maneuvering, and docking, and the
17 construction equipment active on the APL Terminal. Because acute risks are developed from 1-hour
18 exposure periods, it is unlikely that changing the construction schedule would actually reduce the acute risk.
19 With mitigation, the peak acute risk impact was 1.1, just over the threshold of 1.0, and the impacts occur in
20 a very limited area on Pier 400, directly across the channel from the proposed Project (as shown on Figure
21 E3.2-8 in Appendix E3 of the Draft EIS/EIR). No other locations in the Port or beyond were above the
22 threshold. Given the type of the required major construction components (backlands, wharf, and dredging),
23 shifting periods of heavy work would likely just shift the period of heavy emission generation in time,
24 without reducing the acute hazard risk. Furthermore, alternating construction with other projects would
25 effectively lengthen the total construction schedule, thereby extending other environmental impacts, such as
26 noise. Finally, altering the construction schedule could delay the construction schedule beyond a
27 reasonable amount of time and result in increased construction costs due to escalation of material and labor
28 costs over time. Because of these factors, this measure is not considered practical or feasible.

29 **Response to Comment USEPA-17**

30 The Commenter recommends that the Final EIS/EIR should describe zero and near zero emission
31 demonstration projects and deployment projects. For a zero-emission technology to be considered a good
32 candidate for advancement by the Ports, it must be capable of being implemented successfully and within a
33 reasonable period of time, taking into account economic, environmental, legal, operational, and
34 technological factors. LAHD has funded numerous zero emission projects through the TAP including plug-
35 in battery electric yard tractors and drayage trucks, and a hydrogen fuel cell yard tractor and drayage truck.
36 The LAHD intends to expand these demonstration projects on a larger scale, pending the results of the
37 initial testing. The LAHD will also continue to seek and potentially fund new technologies as they emerge
38 and are evaluated and approved by the TAP. The current roadmap for developing and demonstrating new
39 technologies includes near-term (1-3 years) activities to facilitate on-road drayage, cargo handling, and
40 locomotive technology development and demonstrations through the TAP, as well as longer-term activities
41 (greater than 3 years) that include further technology proving and collaboration with stakeholders and
42 partners in developing implementation strategies. None of the zero emission options considered to date is
43 ready for full-scale implementation; however, the Ports will move forward with demonstration and
44 collaboration efforts that advance promising technologies towards real world implementation.

45 The Commenter also recommends that the Final EIS/EIR require a phase-in schedule for zero emission
46 trucks. At this time no zero emission truck technologies have been proven feasible. As stated above the
47 LAHD has funded several demonstration projects; however none of the technologies have been thoroughly

1 tested to large-scale application. The study titled, “Technology Status Report - Zero Emission Drayage
2 Trucks” prepared for the Ports of Los Angeles and Long Beach by TIAX LLC, outlines the anticipated
3 demonstration steps needed for a technology to reach commercial viability. Steps include the completing
4 an in-use demonstration, followed by a large scale demonstration consisting of ten or more units. The
5 technology projects LAHD has funded are either beginning or about to begin the in-use demonstration. It
6 would be only after a successful in-use demonstration that a large-scale demonstration would be pursued.
7 With the current amount of completed testing the LAHD is unable to commit or require a phase-in schedule
8 of zero emission technologies for drayage trucks.

9 Additionally, once technologies prove to be feasible, LAHD intends to deploy them using a Port-wide
10 strategy rather than a terminal-by-terminal approach. This allows LAHD to develop coordinated, more
11 comprehensive, Port-wide program using a variety of implementation strategies. This also allows the
12 technologies to be deployed uniformly so to not place unbalanced financial burdens or economic
13 disadvantages to single terminals. In addition, please see the Response to Comment SCAQMD-8 below.

14 For instance, several factors would create a competitive disadvantage for APL if it were required to use zero
15 emission drayage trucks, which render such a requirement economically infeasible:

- 16 ▪ Recharge time for an electric battery truck. EMS understands that the current recharge time for an
17 electric battery truck is 4 to 5 hours, and the charge is good for up to 8 hours. These time limits
18 would be insufficient for a truck to be utilized over two contiguous gate shifts. Either the truck
19 would need to be recharged during open gate hours, resulting in reduced utilization or additional
20 trucks would need to be purchased to keep the cargo moving. EMS conservatively estimates that
21 30 percent more trucks would be needed to provide drayage service to transport containers between
22 Pier 300 and ICTF if electric battery trucks were used to eliminate delays in cargo movement while
23 electric trucks are recharged.
- 24 ▪ Increased cost of zero emission truck versus commercially available diesel engine trucks. The
25 companies providing drayage service to the Port recently converted their fleets to 2007 USEPA
26 clean trucks (in accordance with USEPA standards codified under 40 CFR 86.007-11). Under the
27 Port's Clean Truck Program, all trucks had to be replaced by January, 2012. These trucks are not
28 near the end of their useful lives. The near-term cost to replace the 2007 USEPA clean trucks with
29 a truck equipped with zero emissions technology would be equal to the entire cost of the new zero-
30 emissions truck- not the differential cost between a zero-emissions truck and a 2007 USEPA clean
31 truck. In addition, a company providing drayage service to Pier 300 would have to bear the
32 additional cost to provide 30 percent more trucks due to the need to take trucks out of service for 4
33 to 5 hour periods to recharge batteries.
- 34 ▪ Increased rates and lost business. Higher truck costs incurred by the companies providing drayage
35 service would result in higher rates charged by such companies to the liner companies doing
36 business at EMS. These increased rates would drive intermodal business away from EMS, to other
37 liner companies doing business at terminals that are not required to use zero-emission drayage
38 trucks.

39 Therefore, the best approach to implementing zero emission technologies, such as drayage trucks, is by a
40 Port-wide approach which would allow implementation without creating competitive disadvantages
41 between terminals and Ports.

42 **Response to Comment USEPA-18**

43 Regarding examples cited (i.e., construction activity and school buses), terminal operations are not
44 comparable. The proposed mitigation in the Draft EIS/EIR regarding truck idling during operation (MM

1 AQ-16) is appropriate for the safe and efficient operation of the container terminal. In addition to the
2 mitigation measure, the APL terminal operator already limits idling from trucks calling at the terminal.
3 Policies such as requiring all on-road trucks being processed at the main gate to shut down their engines
4 before they will be processed and use of control devices on yard equipment that automatically shuts down
5 the engine after being in park and idling for 15 minutes (which would indicate equipment is not in use) are
6 measures that limit unnecessary idling while maintaining safety and efficiency within the terminal.

7 **Response to Comment USEPA-19**

8 Please see Response to Comment USEPA-13 regarding the ability to eliminate the need for near-dock
9 railyard usage by increasing on-dock rail capacity. It should also be noted that under the TAP, new
10 measures to reduce air pollution from locomotives are under evaluation. These measures address emissions
11 from switching, which comprises short movements of rail cars, such as in the assembling and disassembling
12 of trains at various locations in and around the ports (including on-dock yards). As part of the switching
13 fleet modernization under the TAP, all Class 1 line haul and switcher locomotives must meet the emissions
14 reductions associated with the California Air Resources Board's Class 1 railroads Memorandum of
15 Understanding and the 2008 USEPA locomotive engine standards, including:

- 16 ▪ By 2007, phase-out all non-essential idling and maximize use of ULSD fuel
- 17 ▪ By 2010, all Class 1 locomotives entering the ports will meet emissions equivalent to Tier 2
18 locomotive standards
- 19 ▪ By 2023, all Class 1 locomotives entering the ports will meet emissions equivalent to Tier 3
20 locomotive standards

21 On-dock railyard management will be a part of the Terminal Island planning process, which is a more
22 appropriate planning vehicle (than the Final EIS/EIR) for the Commenter's on-dock rail recommendations.

23 **Response to Comment USEPA-20**

24 As detailed in Section 3.2.3.2 of the Draft EIS/EIR, each Federal agency (including USACE) must
25 determine that any action that is proposed by the agency and that is subject to the regulations implementing
26 the conformity requirements will, in fact, conform to the applicable State Implementation Plan (SIP) before
27 the action is taken. According to USEPA guidance, before any approval is given for a Federal action to go
28 forward, the regulating Federal agency must apply the applicability requirements found at 40 CFR Section
29 51.853(b) to the Federal action and/or determine the regional significance of the Federal action pursuant to
30 40 CFR Section 51.853(j) to evaluate whether, on a pollutant-by-pollutant basis, a determination of general
31 conformity is required. The guidance states that the applicability analysis can be (but is not required to be)
32 completed concurrently with any analysis required under the NEPA. If the regulating Federal agency
33 determines that the general conformity regulations do not apply to the Federal action, no further analysis or
34 documentation is required. If the general conformity regulations do apply to the Federal action, the
35 regulating Federal agency must next conduct a conformity evaluation in accord with the criteria and
36 procedures in the implementing regulations, publish a draft determination of general conformity for public
37 review, and then publish the final determination of general conformity.

38 As part of the environmental review of the Federal action, the USACE conducted a general conformity
39 evaluation pursuant to SCAQMD Rule 1901 and 40 CFR Part 51 Subpart W. The general conformity
40 regulations apply at this time to those actions at the Port requiring USACE approval, because the South
41 Coast Air Basin (SCAB) (which includes the Port) is a nonattainment area for O₃, PM₁₀, and PM_{2.5}; and a
42 maintenance area for NO₂ and CO. The USACE began the general conformity evaluation by conducting
43 the applicability analysis in which the calculated Federal action emissions are compared to the general
44 conformity *de minimis* thresholds. This applicability analysis is presented in Appendix E1.2 of the Draft

1 EIS/EIR. Following USACE guidance, the Federal actions for this evaluation included construction
2 emissions for the following project elements:

- 3 ▪ Dredging and disposal of 20,000 cubic yards of sediment to build Berth 306.
- 4 ▪ Berth 306 wharf construction including support pile and wharf deck installation.
- 5 ▪ Development of new 41 acres of backlands adjacent to Berth 306.
- 6 ▪ Installation of AMP at Berth 306.
- 7 ▪ Installation of wharf cranes at Berths 302-306.
- 8 ▪ Construction worker commute trips to one from the project site.

9 Based on the general conformity evaluation performed for the proposed Project, the USACE determined
10 that the Federal action (i.e., those Project elements listed above) as designed will conform to the approved
11 SIP since the Federal action is not subject to a general conformity determination for CO, VOC (as an O₃ and
12 PM_{2.5} precursor), NO_x (as an O₃ and PM_{2.5} precursor), PM₁₀, PM_{2.5}, or SO_x (as a PM_{2.5} precursor) because
13 the net emissions associated with the Federal action are less than the general conformity *de minimis*
14 thresholds.

15 Finally, the operational emissions associated with Port operations would be considered “indirect emissions”
16 under the general conformity regulations. In addition, these indirect emissions are specifically not covered
17 by the general conformity rule:

18 *Preamble III.C.3.j.(3) - ...The indirect emissions from development activities related to [USACE]*
19 *permit actions are not covered where such emissions are not subject to the continuing program*
20 *responsibility of the [USACE], or cannot be practicably controlled by the [USACE].²*

21 **Response to Comment USEPA-21**

22 Regarding the comment that the Final EIS/EIR should include emissions within the SCAB from trips that
23 would occur after transloading, the LAHD estimates emissions generation to the point of first delivery (e.g.
24 to the transloading company) because once a container is delivered to the transloading company, cargo is
25 reorganized for subsequent transport. During cargo reorganization, cargo from other terminals, other ports,
26 and other suppliers (foreign and domestic) are combined and loaded onto other trucks or containers for
27 subsequent delivery and redelivery to many other common point destinations. The subsequent destinations
28 of the cargo are unknown and are subject to change depending on the cargo and intermediate and end users,
29 as well as changing market conditions. Due to the speculative nature and logistic variables associated with
30 transloaded cargo shipments, including a lack of LAHD jurisdiction and control, the LAHD intends to
31 continue estimating emissions to the first point of delivery.

32 **Response to Comment USEPA-22**

33 Operational mitigation measures MM AQ-13, MM AQ-14, and MM AQ-15, as well as construction
34 mitigation measure MM AQ-3, require Tier 4 or Tier 3 compliance, depending on measure’s timing or the
35 presence of other emissions controls. There is a range of emissions allowed under these standards, and
36 rather than focusing on specific emission levels, these mitigation measures implement represent an overall
37 approach to reducing emissions without unnecessarily micromanaging the operations a specific terminal.

² 58 FR 63224, Determining Conformity of General Federal Actions to State or Federal Implementation Plans; Final Rule (November 30, 1993).

1 APL and EMS do not own or operate an on-road fleet of trucks. Any additional phasing in of Tier 4
2 standards needs to be associated with a Port-wide strategy, such as part of the effort to reduce emissions
3 though implementation of the CAAP, which allows such technologies to be demonstrated, developed, and
4 implemented uniformly and in a more coordinated manner without creating competitive disadvantages
5 between terminals and Ports.

6 **Response to Comment USEPA-23**

7 The Commenter recommends that the Final EIS/EIR include another alternative with a fifth berth at Pier
8 300 because the *Terminal Island Land Use Plan, Summary Report* identifies a fifth berth at Pier 300 (along
9 Berth 301). The *Terminal Island Land Use Plan* is in draft planning level document which has not been
10 finalized, approved, or been the subject of environmental clearance. There is currently no foreseeable
11 market demand that a fifth berth (along Berth 301) would accommodate, and because of this, the proposed
12 Project and alternatives in the Draft EIS/EIR do not include a new Berth 301. In essence, proposed Project
13 goals can be met by the existing reasonable range of alternatives. In addition, neither the proposed Project
14 nor the Project alternatives would preclude a future Berth 301 should market conditions later require its
15 addition (however, adding Berth 301 would require additional environmental analysis)

16 The referenced draft *Terminal Island Land Use Plan* includes features that are possible, but may not be
17 likely in the near or intermediate term. Once the *Terminal Island Land Use Plan is finalized*, the potential
18 improvements at various locations on Terminal Island, including the alternatives presented in the Plan
19 would be subject to environmental evaluation under both CEQA and NEPA. In addition, please see Related
20 Project No. 31 in Table 4-1 of the Draft EIS/EIR. LAHD is in the process of preparing the Port of Los
21 Angeles Master Plan Update, and if a new wharf at Berth 301 is included, it would be evaluated as an
22 anticipated project if considered reasonably foreseeable at that time.

23 **Response to Comment USEPA-24**

24 Regarding the comments that the Final EIS/EIR should consider a roof over the reefer storage area for
25 cooling or renewable energy generation, such a roof is not considered feasible as it would prevent access to
26 the containers, which occurs from above using toppicks. Additionally, even if such a roof could be high
27 enough to accommodate yard equipment, the roof structure would necessitate new lighting beneath the
28 structure for use during nighttime, as the roof would block lighting from fixtures throughout the backlands.

29 **Response to Comment USEPA-25**

30 Regarding the recommendation to change mitigation measure MM AQ-1 to require the contractor to import
31 if available Tier 4 equipment from Oregon or Washington, LAHD respectfully declines this
32 recommendation as infeasible. LAHD would ensure that construction contractors comply with CAAP
33 measures, Project-specific mitigation, and LAHD Sustainable Construction Guidelines through the
34 environmental compliance plan. While LAHD uses restrictions and requirements geared at requiring
35 construction contractors working within its jurisdiction to use the cleanest feasible construction equipment,
36 LAHD does not overly burden the contractors by requiring construction equipment not readily available
37 (such as requiring the leasing of out-of-state equipment) as it would pose an undue economic burden on
38 contractors in California, as well as result in additional emissions associated with transportation of such
39 equipment from those states. The LAHD has performed a screening level calculation of the
40 recommendation by estimating emissions associated with bringing two Tier 4-compliant tugs to the Port
41 from Seattle, and found that the associated transportation emissions substantially outweigh any benefit of
42 using these Tier 4 compliant tugs in the Port (refer to Section 2.4 for an estimate of the tugboat emissions).

1 **Response to Comment USEPA-26**

2 Regarding the recommendation to change the lease reopener period from 7 years to 5 years under lease
3 measure LM AQ-1, LAHD will make the change as requested in the Final EIS/EIR (refer to Chapter 3 –
4 Modifications to the Draft EIS/EIR).

5 **Response to Comment USEPA-27**

6 LAHD has coordinated with the Southern California Dredged Material Management Team (SC-DMMT)
7 regarding placement of the dredge material at Berths 243-245, an approved confined disposal facility. The
8 management of sediment at this facility and the appropriate confinement specifications was established
9 through the Channel Deepening Project.

10 **Response to Comment USEPA-28**

11 *Vessel General Permit*

12 The requirements of the Vessel General Permit (VGP), and other ballast water management regulations,
13 will be added in the Final EIS/EIR (refer to Chapter 3 – Modifications to the Draft EIS/EIR), as follows:

14
15 The USEPA VGP was released on December 19, 2008, and applies to all non-military and non-
16 recreational vessels of 79 feet or greater in length. Requirements for the VGP include:

- 17
- 18 ▪ Submission of a Notice of Intent for vessels over 300 gross tons (or vessels with a
19 capacity to hold or discharge 2,113 gallons (8 cubic meters) or more of ballast water;
- 20 ▪ Corrective actions for violations of VGP limits;
- 21 ▪ Requirements for visual and annual inspections; and
- 22 ▪ Reporting requirements, which vary by vessel class.

23 In addition to general VGP regulations, states with authority to implement the CWA may add
24 specific provisions, including performance standards, for vessel discharges in state waters through
25 the Section 401 Water Quality Certification process. The state of California has issued additional
26 conditions for vessels while in state waters. The VGP expires in December 2013, and the USEPA
27 recently solicited public comment on a new draft VGP that would take effect upon expiration of the
28 original VGP. The proposed VGP includes numeric criteria for discharged ballast water, and would
29 impose several ballast water management (BWM) best management practices (BMPs) substantially
30 similar to those in the 2008 VGP.

31

32 In July 2010, the Ports of Los Angeles and Long Beach published a guidance manual (*Port of Long*
33 Beach and Port of Los Angeles Vessel Discharge Rules and Regulations) that provides interested
34 parties with relevant information on allowable and prohibited maintenance activities and discharges
35 within the Ports. The manual applies to large commercial vessels generally over 79 feet in length.
36 This manual summarizes federal, state, and local provisions governing the management and
37 discharge of ballast water, and has been distributed directly to terminal operators and facility
38 managers, among other parties. Los Angeles Port Pilots have also been distributing the manual to
39 vessel operators as they board inbound vessels. The guidance manual is available at the Port of Los
40 Angeles' web site, and will be updated as necessary.

1 *Shipboard Ballast Water Treatment*

2 USEPA has requested the Final EIS/EIR consider expedited treatment of ballast water treatment to reduce
3 the significant impact resulting from the introduction of aquatic invasive species (AIS) into the Harbor.
4 Treatment of ballast water to reduce or eliminate potential AIS is an emerging field.

5 As discussed above, states are allowed to include additional conditions under the VGP. The state of
6 California has issued the most stringent requirements related specifically to ballast water and such
7 requirements are more stringent than those issued by the USEPA in the draft 2013 VGP., California has
8 regulations in place to eliminate the introduction of AIS via ballast water discharge by the year 2020.³
9 California's ballast water discharge performance standards consist of "no detectable" organisms >50 mm in
10 dimension, <0.01 organisms per milliliter (ml) for organisms in the 10–50 µm range, 10 organisms per ml
11 for living bacteria, and 100 organisms per ml for living viruses within State waters. There are also
12 performance standards for organisms <10 µm in diameter, and vary depending on the type of organism (i.e.,
13 virus or bacteria). California's performance standards for new vessels went into effect in January 1, 2010
14 and January 1, 2012 (depending on ballast water capacity), and will go into effect for existing vessels on
15 January 1, 2014 and January 1, 2016 (depending on ballast water capacity). California's current regulations
16 include the interim performance standards described above, the final discharge standard of zero detectable
17 living organisms discharged by 2020, and reporting requirements. California's current BWM regulations,
18 including the performance standards, are currently more stringent than the Regulation D-2 limits of the
19 International Maritime Convention (IMO), also referred to as the IMO D-2 standards, and proposed 2013
20 VGP.

21 The Commenter noted that the USEPA's Science Advisory Board (SAB) determined five types of ballast
22 water treatment systems are available that treat to the Regulation D-2 limits of the International Maritime
23 Convention (IMO), and these same limits (referred to as the D-2 limits) are proposed in the proposed VGP.⁴
24 Although the USEPA's SAB determined there were several types of systems capable of treating to the
25 limits of the IMO D-2 and proposed VGP standards, they also determined:

26 "The detection limits for currently available test methods preclude a complete statistical assessment of
27 whether BWMS (ballast water management systems) can meet standards more stringent than IMO-
28 D2/Phase I"⁵ (page 4).

29 The Panel also concluded "that it is not reasonable to assume that BWMS are able to reliably meet or
30 closely approach a "no living organisms" standard" (page 4). The California State Lands Commission
31 recently came to a similar conclusion—the inherent uncertainty regarding BWMS performance "is likely to
32 persist over the next several years."⁶ The State Lands Commission staff is working with industry experts to
33 develop compliance protocols to ensure that vessel discharges into California waters will be compliant with
34 California law.

35

³ Final discharge standard for California is zero detectable living organisms in all size classes beginning January 1, 2020.

⁴ U.S. Environmental Protection Agency, Science Advisory Board (USEPA SAB). 2011. *Efficacy of Ballast Water Treatment Systems: a Report by the EPA Science Advisory Board*. July 12, 2011.

⁵ Phase I refers to the Phase I of the U.S. Coast Guard proposed ballast water regulations (74 FR 44632), which are also identical to the IMO D-2 standards. The proposed standards were published on August 28, 2009, but have not been finalized.

⁶ Dobroski, N., C. Scianni, and L. Takata. 2011. *2011 Update: Ballast Water Treatment Systems for Use in California Waters*. Prepared for the Calif. State Lands Comm. by the Marine Inv. Sp. Progr. Sept. 1, 2011

1 California's interim performance standards are extremely stringent, and the technology to effectively treat
2 to such low levels is still in development. Once a specific treatment system shows promise for removing
3 the target organisms from the ballast water, integrating this system onto vessels and training ship crews to
4 effectively operate a new system will take additional time. Therefore, the existing compliance schedule
5 should be considered extremely aggressive.

6 The U.S. Coast Guard's Shipboard Technology Evaluation Program (STEP) is intended to facilitate the
7 development of effective BWMS technologies, to create more options for vessel owners seeking
8 alternatives to ballast water exchange. The program was established to alleviate concerns regarding the
9 investment in, installation, and operation of an experimental treatment system that might not meet discharge
10 standards mandated by future regulations. Vessels accepted into the STEP may be granted an equivalency
11 to future ballast water discharge standard regulations, for up to the life of the vessel or the system, while
12 their BWM system operates satisfactorily. As summarized in the Draft EIS, the Port of Los Angeles, Port
13 of Long Beach, California State Lands Commission, and University of Maryland are collaborating with
14 APL to test a shipboard ballast water treatment system designed to eliminate AIS from ballast water. The
15 vessel APL England is one of only five ships currently enrolled in the STEP⁷.

16 Vessels currently calling at the APL Terminal are subject to: (1) the BWM provisions of the current VGP;
17 (2) the BWM provisions of the U.S. Coast Guard's Ballast Water Management for the Control of
18 Nonindigenous Species in Waters of the U.S.⁸; (3) the provisions and numeric limits of the State's BWM
19 regulations; and (4) Port Tariff Number 4, which prohibits the discharge of ballast water within the Port
20 without permission from the Executive Director. While the USEPA, the U.S. Coast Guard, and other states
21 consider new or revised BWM regulations, California's numeric limitations are currently among the most
22 stringent in the United States, and for many classes and sizes of organisms, are much more stringent than
23 the IMO D-2 standard.

24 USEPA's request to consider an expedited BWMS implementation schedule is not supported due to (1) the
25 aggressive compliance schedule for vessels operating in California's waters, (2) the lack of ballast water
26 treatment systems that can meet the stringent standards, and (3) the lack of approved compliance
27 verification protocols at both the state and federal levels. Based on past accomplishments, there will be
28 several advances in the field of BWMS technology in the next decade. At this time, however, it could be
29 counterproductive to require vessels to install technologies that may not meet state or federal standards.

30

⁷ See: <http://www.uscg.mil/hq/cg5/cg522/cg5224/step.asp>

⁸ 33 *CFR* 151. See: <http://www.uscg.mil/hq/cg5/cg522/cg5224/bwm.asp>

U.S. Department of Homeland Security
FEMA Region IX
1111 Broadway, Suite 1200
Oakland, CA. 94607-4052



FEMA

RECEIVED

DEC 27 2011

Regulatory Branch

December 22, 2011

Theresa Stevens, PhD
U. S. Army Corps of Engineers
Los Angeles District Regulatory Division
Ventura Field Office
2151 Alessandro Drive, Suite 110
Ventura, California 93001

Dear Ms. Stevens:

This is in response to your request for comments on Public Notice No. SPL-2009-00226-TS, Port of Los Angeles Berths 302-306 (APL) Container Terminal Project.

Please review the current effective countywide Flood Insurance Rate Maps (FIRMs) for the City (Community Number 060137) and County (Community Number 065043) of Los Angeles, Maps revised September 26, 2008. Please note that the City of Los Angeles, Los Angeles County, California is a participant in the National Flood Insurance Program (NFIP). The minimum, basic NFIP floodplain management building requirements are described in Vol. 44 Code of Federal Regulations (44 CFR), Sections 59 through 65.

A summary of these NFIP floodplain management building requirements are as follows:

- All buildings constructed within a riverine floodplain, (i.e., Flood Zones A, AO, AH, AE, and A1 through A30 as delineated on the FIRM), must be elevated so that the lowest floor is at or above the Base Flood Elevation level in accordance with the effective Flood Insurance Rate Map.
- If the area of construction is located within a Regulatory Floodway as delineated on the FIRM, any *development* must not increase base flood elevation levels. **The term *development* means any man-made change to improved or unimproved real estate, including but not limited to buildings, other structures, mining, dredging, filling, grading, paving, excavation or drilling operations, and storage of equipment or materials.** A hydrologic and hydraulic analysis must be performed *prior* to the start of development, and must demonstrate that the development would not cause any rise in base flood levels. No rise is permitted within regulatory floodways.

FEMA-1

Theresa Stevens, PhD

Page 2

December 22, 2011

- All buildings constructed within a coastal high hazard area, (any of the "V" Flood Zones as delineated on the FIRM), must be elevated on pilings and columns, so that the lowest horizontal structural member, (excluding the pilings and columns), is elevated to or above the base flood elevation level. In addition, the posts and pilings foundation and the structure attached thereto, is anchored to resist flotation, collapse and lateral movement due to the effects of wind and water loads acting simultaneously on all building components.
- Upon completion of any development that changes existing Special Flood Hazard Areas, the NFIP directs all participating communities to submit the appropriate hydrologic and hydraulic data to FEMA for a FIRM revision. In accordance with 44 CFR, Section 65.3, as soon as practicable, but not later than six months after such data becomes available, a community shall notify FEMA of the changes by submitting technical data for a flood map revision. To obtain copies of FEMA's Flood Map Revision Application Packages, please refer to the FEMA website at <http://www.fema.gov/business/nfip/forms.shtm>.


FEMA-1
Cont.

Please Note:

Many NFIP participating communities have adopted floodplain management building requirements which are more restrictive than the minimum federal standards described in 44 CFR. Please contact the local community's floodplain manager for more information on local floodplain management building requirements. The Los Angeles County floodplain manager can be reached by calling Gary L. Moore, City Engineer, at (213) 485-4935. The Los Angeles County floodplain manager can be reached by calling George De La O, Senior Civil Engineer, at (626) 458-7155.

If you have any questions or concerns, please do not hesitate to call Cynthia McKenzie of the Mitigation staff at (510) 627-7194.

Sincerely,



Gregor Blackburn, CFM, Branch Chief
Floodplain Management and Insurance Branch

cc:

Gary L. Moore, City Engineer, City of Los Angeles

George De La O, Senior Civil Engineer, Los Angeles County, Department of Public Works,
Los Angeles County

Garret Tam Sing/Salomon Miranda, State of California, Department of Water Resources,
Southern Region Office

Cynthia McKenzie, Senior NFIP Planner, DHS/FEMA Region IX

Alessandro Amaglio, Environmental Officer, DHS/FEMA Region IX

1 **United States Department of Homeland Security, FEMA**

2 **Region IX (FEMA)**

3 **Response to Comment FEMA-1**

4 Thank you for your comment. The comment letter has been forwarded to LAHD's Engineering Division
5 for their consideration during the design process. As described in Section 3.14 of the Draft EIS/EIR, the
6 majority of Pier 300 is mapped by FEMA as Flood Zone X (defined as areas of 0.2 percent annual chance
7 flood; areas of one percent annual chance flood with average depths of less than one foot or with drainage
8 areas less than one square mile; and, areas protected by levees from one percent annual chance flood). A
9 portion of the pier (Berth 301 area) in the vicinity of Earle and Bass Streets is mapped as Flood Zone AE
10 (defined as special flood hazard areas that are subject to inundation by the one percent annual chance flood).
11 The land planned for the proposed Berth 306 wharf extension and backland uses, and the Pier 300 Shallow
12 Water Habitat area have not been mapped for flood risk by FEMA. However, waters of the Harbor near
13 land, plus some of the landfill margins in other areas of the Harbor, are mapped within the 100-year flood
14 zone. Adjacent areas on the landfills are generally within the 500-year flood zone. The Project site is not
15 within a Regulatory Floodway as delineated on the FIRM; therefore, the area of construction and
16 development would not cause any rise in base flood levels. The Project site is also not within a delineated
17 "V" Flood Zone and the proposed Project would not involve development that changes an existing Special
18 Flood Hazard Area. As determined in the impact analysis (Section 3.14 of the Draft EIS/EIR), although the
19 proposed Project would develop the existing 41-acre undeveloped area that has not been mapped for flood
20 risk by FEMA, it is at the same level as the existing terminal. Most of the terminal is designated by FEMA
21 as Flood Zone X (defined as areas of 0.2 percent annual chance flood; areas of one percent annual chance
22 flood with average depths of less than one foot or with drainage areas less than one square mile; and, areas
23 protected by levees from one percent annual chance flood); therefore, the impact would be less than
24 significant.

25



UNITED STATES DEPARTMENT OF COMMERCE
National Oceanic and Atmospheric Administration
NATIONAL MARINE FISHERIES SERVICE
Southwest Region
501 West Ocean Boulevard, Suite 4200
Long Beach, California 90802-4213

FEB 16 2012

Colonel R. Mark Toy
U.S. Army Corps of Engineers
Los Angeles District, CESPL-CO-R
P.O. Box 2711
Los Angeles, California 90053-2325

Dear Colonel Toy:

NOAA's National Marine Fisheries Service (NMFS) has reviewed the Draft Environmental Impact Statement (DEIS) and the U.S. Army Corps of Engineers' (Corps) Public Notice (SPL-2009-00226-TS) for upgrades to Berths 302-306 in the Port of Los Angeles (POLA), California. NMFS offers the following comments pursuant to section 305(b)(4)(A) of the Magnuson-Stevens Fishery Conservation and Management Act (MSA) and the Fish and Wildlife Coordination Act (FWCA).

Proposed Action

For purposes of this consultation, the proposed action is to expand the existing terminal by constructing a 1,250 linear foot concrete wharf at Berth 306 adjacent to the wharf at Berths 302-305. To support the wharf, approximately 515 24-inch concrete piles would be driven using impact hammers with the soft-start technique. According to the written materials provided by the Corps, the new wharf would increase overwater coverage by approximately four acres. However, a recent telephone conversation with the Corps and POLA staff clarified that the overwater coverage would be increased by 2.7 acres. The applicant would also dredge 20,000 cubic yards of material from Berth 306 to a depth of -55 feet Mean Lower Low Water with a two foot overdredge. Dredging would last approximately three months, whereas wharf construction and pile driving would occur over a 22-month period. Dredge material would be disposed of at the Corps-approved Berths 243-245 confined disposal facility (CDF), the Cabrillo Shallow Water Habitat Area (CSWHA) and/or in the open ocean at the LA-2 site.

Magnuson-Stevens Fishery Conservation and Management Act Comments

Action Area

The proposed project occurs within essential fish habitat (EFH) for various federally managed fish species within Coastal Pelagic Species and Pacific Coast Groundfish Fishery Management Plans (FMPs). In addition, the project occurs in the vicinity of eelgrass habitat, which is designated as a habitat area of particular concern (HAPC) for various federally managed fish species within the Pacific Groundfish FMP. HAPC are described in the regulations as subsets of EFH which are rare, particularly susceptible to human-induced degradation, especially



ecologically important, or located in an environmentally stressed area. Designated HAPC are not afforded any additional regulatory protection under MSA; however, federal projects with potential adverse impacts to HAPC will be more carefully scrutinized during the consultation process.

Effects of the Action

The adverse effects of dredging on EFH may include 1) direct removal/burial of organisms; 2) turbidity/siltation effects, including light attenuation from turbidity; 3) contaminant release and uptake, including nutrients, metals and organics; 4) release of oxygen consuming substances; 5) entrainment; 6) noise disturbance; and 7) alteration to hydrodynamic regimes and physical habitat. NMFS expects the waste discharge requirements imposed by the Regional Water Quality Control Board will adequately address the adverse effects of dredging.

NMFS-1

Another potential project concern is the spread of the invasive alga *Caulerpa taxifolia* from project activities. This alga was introduced to the southern California coastline in 2000. Evidence of harm that can ensue as a result of an uncontrolled spread of the alga has already been seen in the Mediterranean Sea where it has destroyed local ecosystems, impacted commercial fishing areas, and affected coastal navigation and recreational opportunities. Although it is not known to be present within the Port, it was detected and eradicated in two other locations in Southern California. It is worth noting that the intensive six-year eradication effort cost approximately \$7 million. If the invasive alga is present within the project area, the sediment disturbing activities would adversely affect EFH by promoting its spread and increasing its negative ecosystem impacts. According to the DEIS, an underwater survey for *Caulerpa* would be conducted to ensure that no *Caulerpa* is present. If *Caulerpa* is detected, an eradication program would be implemented per the requirements of the *Caulerpa* Control Protocol. NMFS believes this environmental commitment adequately addresses our *Caulerpa* concerns.

NMFS-2

The construction activities associated with this project may generate substantial underwater noise. For example, pile driving can generate intense underwater sound pressure waves that may adversely affect the ecological functioning of EFH. These pressure waves have been shown to injure and kill fish. Injuries associated directly with pile driving are poorly studied, but include rupture of the swim bladder and internal hemorrhaging. Of the reported fish kills associated with pile driving, all have occurred during use of an impact hammer on hollow steel piles. In addition, increased noise frequency is a determining factor in lethal and sublethal impacts on fishes. This project requires the driving of 515 24-inch concrete piles. The applicant has proposed using soft-start techniques to minimize effects from sound. NMFS expects that the pile type and driving technique will minimize lethal and sub-lethal impacts to fish. However, NMFS believes that sufficient noise will be generated to elicit avoidance responses that may preclude or reduce use of the project area during pile driving operations. Thus, in consideration of likely avoidance responses associated with dredging and construction, NMFS expects the habitat quality to be diminished over the 25-month period of dredging and pile driving activities.

NMFS-3

Wharf development will result in a large overwater structure that will permanently limit light availability to the marine environment. Light is the single most important factor affecting

NMFS-4

aquatic plants. Light levels underneath overwater structures have been found to fall below threshold levels for photosynthesis of diatoms, benthic algae, eelgrass, associated epiphytes and other autotrophs. These photosynthesizers are an essential part of nearshore habitat and the estuarine and nearshore food webs that support many species of marine and estuarine fishes.

In addition, fishes rely on visual cues for spatial orientation, prey capture, schooling, predator avoidance and migration. Juvenile and larval fish are primarily visual feeders with starvation being the major cause of larval mortality in marine fish populations. Early life history stages are likely critical determining factors for recruitment and survival, with survival linked to the ability to locate and capture prey and to avoid predation (Britt 2001). The reduced light conditions found under an overwater structure limit the ability of fishes, especially juveniles and larvae, to perform these essential activities. For example, Able and Duffy-Anderson (2005) examined the impacts of man-made structures, especially large piers, on fishes and selected invertebrates in the lower Hudson River over a number of years. They concluded that under-pier areas are poor quality habitats because they support low fish abundances, inhibit feeding, and suppress growth. They attributed the poor habitat quality to the low light levels under piers.

NMFS-4
Cont.

Given the lack of natural hard bottom habitat in estuaries, the addition of artificial hard structures may provide an invasion opportunity for non-indigenous hard substratum species (Glasby et al. 2007; Wasson et al. 2005; Tyrell and Byers 2007). For example, Glasby et al. (2007) argue that artificial structures provide entry points for invasion and increase the spread and establishment of non-indigenous species (NIS) in estuaries. In the Ports of Los Angeles and Long beach, Silva et al. (2002) documented the presence of the Asian kelp, *Undaria pinnatifida*, a non-native algae. It was discovered in southern California in the spring of 2000, and by the summer of 2001 had been collected at several California sites from Los Angeles to Monterey Harbor. With the exception of one site, all observations were found on floating docks, piers, pilings, or other artificial substrate in a protected environment. More recent observations made by various site-specific surveys in southern California continue to observe this trend. For example, a site-specific survey conducted at POLA Berths 145-147 indicated that the dominant flora in the project vicinity was *U. pinnatifida*, which was found exclusively on pilings (Merkel and Associates 2009). The most recent biological baseline survey conducted in the Ports of Los Angeles and Long Beach documented *Undaria* at all eight inner harbor sites and at 7 of 12 outer harbor locations, indicating an expanded distribution since 2000 (SAIC 2010). Another example in the Port of Long Beach is the non-native brown seaweed, *Sargassum horneri*. It was first found in 2003, but by 2004 it had moved to both sides of the harbor's back channel. Since then, the non-native species has been found in Orange County, the Channel Islands, and as far south as San Diego Bay. Thus, NMFS believes that artificial substrate in estuaries may contribute to further proliferation of NIS. Some researchers have recommended that coastal managers should consider limiting the amount of artificial hard substrates in estuarine environments (Wasson et al. 2005, Tyrell and Byers, 2007).

NMFS-5

The hard substrate associated with overwater structures has been reported as a habitat benefit based upon the assumption that these artificial structures mimic natural hard substrate habitat. While some structures are inhabited by invertebrates and fishes similar to those found in rocky reef habitat (Merkel and Associates 2008), an increasing body of evidence is showing significant differences between the biota associated with artificial structures and those on natural reefs

(Bulleri and Chapman 2010). Within southern California, the majority of the overwater structures occur within protected embayments comprised of primarily soft bottom habitats. The novel habitat provided by overwater structures appears to harbor species that are either non-native or native to reef habitats generally found along open coasts. Consequently, while providing an artificial hard substrate within a soft bottom habitat will increase habitat heterogeneity, the habitat will be altered from its original function.

As a result of Southern California's large population and intense economic and recreational activity, there is very little coastal space that has not been subject to construction, mineral extraction, or other forms of resource utilization and habitat alteration. Dredging, fill, shoreline armoring, and overwater structures are the primary causes of habitat alteration within southern California embayments. At the ports of Long Beach and Los Angeles, increasing global economic pressures have resulted in the need for larger, deeper draft ships to transport cargo. This has led to a demand for new construction dredging to widen and deepen channels, turning basins, and slips to accommodate these larger vessels. These activities have led to permanent loss of shallow water habitats and chronic effects on water quality. In addition to the ports, other bays and harbors of Southern California have experienced significant adverse impacts associated with shoreline, intertidal, and shallow subtidal development.

The Corps concludes in your December 16, 2011, letter that shade impacts are not considered cumulatively considerable because shade does not preclude use of the water or substrate by motile, encrusting or benthic species. NMFS does not concur with this assertion. Light is a fundamental, physical factor that regulates the functioning of nearshore ecosystems. As described above, intense shading may preclude primary productivity, which forms the basis of nearshore marine food webs. In addition, there is strong evidence that changes in the lighting regime can cause changes in fish behavior and predator-prey interactions. Over-water structures create a light/dark interface which allows ambush predators to hold in the darkened areas and watch for prey against a bright background. Prey can not see into the dark shadow and therefore are less successful at avoiding predators. Protected embayments are generally acknowledged as nursery areas for fish. Altering ecosystem structure in such a way to confer additional advantages to predators will reduce the nursery function of these systems. Although shading may not preclude use by certain fish species, it results in the permanent reduction in light, a fundamental regulating factor of ecosystem function in nearshore habitat. Moreover, emerging evidence suggests that introducing novel hard substrate into embayments may adversely affect native biodiversity by facilitating the proliferation of non-native species. Therefore, NMFS believes the best available scientific information suggests that overwater structures adversely affect EFH and the ecological functions provided by nearshore waters of the U.S.

As defined in 33 CFR Part 332, riparian areas are lands adjacent to streams, rivers, lakes, and estuarine-marine shorelines. Riparian areas provide a variety of ecological functions and services and help improve or maintain local water quality. Continued modification of estuarine-marine shorelines as a result of overwater structures further reduces the ecological functions and services provided by these unique habitats. In addition, the cumulative impacts associated with reduced tidal circulation and expanded vessel use may degrade water quality. Without compensation for the degradation of aquatic resources, the proposed activity may be contrary to public interest.

NMFS-5
Cont.

EFH Conservation Recommendations

As described in the above effects analysis, NMFS has determined that the proposed action would adversely affect EFH for various federally managed fish species within Coastal Pelagic Species and Pacific Coast Groundfish FMPs. Therefore, pursuant to section 305(b)(4)(A) of the MSA, NMFS offers the following EFH conservation recommendations to avoid, minimize, mitigate, or otherwise offset the adverse effects to EFH.

1) Given the significant modification of estuarine-marine shorelines within Southern California's embayments, NMFS believes additional reductions in habitat quality should be offset via compensatory mitigation. The proposed project will permanently reduce the quality of 2.7 acres of nearshore embayment habitat. Therefore, the POLA should develop, in consultation with the Corps, NMFS, and other relevant resource agencies, a plan to compensate for this reduction in habitat quality. The plan should be approved by the Corps prior to project construction.

NMFS-6

2) The POLA should notify NMFS of the date of commencement of dredging and disposal operations not less than 14 calendar days prior to commencing work, and shall notify NMFS of the date of completion of operations at least five calendar days prior to such completion. Such notification would provide NMFS the opportunity to monitor impacts to EFH.

NMFS-7

Statutory Response Requirement

Please be advised that regulations at section 305(b)(4)(B) of the MSA and 50 CFR 600.920(k) of the MSA require your office to provide a written response to this letter within 30 days of its receipt and at least 10 days prior to final approval of the action. A preliminary response is acceptable if final action cannot be completed within 30 days. Your final response must include a description of measures to be required to avoid, mitigate, or offset the adverse impacts of the activity. If your response is inconsistent with our EFH conservation recommendations, you must provide an explanation of the reasons for not implementing those recommendations. The reasons must include the scientific justification for any disagreements over the anticipated effects of the proposed action and the measures needed to avoid, minimize, mitigate, or offset such effects.

NMFS-8

If the Corps determines that compensatory mitigation for overwater coverage is not warranted, NMFS believes the Corps should provide a detailed response explaining the rationale for not requiring compensation. NMFS recommends that, at a minimum, such a response would include the Corps' scientific opinion as to whether shading results in unavoidable adverse impact to waters of the U.S. Also, if the Corps acknowledges an unavoidable adverse impact, then the Corps should describe the threshold for which an exceedance would trigger the need for compensation.

Supplemental Consultation

Pursuant to 50 CFR 600.920(l), the Corps must reinstate EFH consultation with NMFS if the proposed action is substantially revised in a way that may adversely affect EFH, or if new

information becomes available that affects the basis for NMFS' EFH conservation recommendations.

Fish and Wildlife Coordination Act Comments

The purpose of the FWCA is to ensure that wildlife conservation receives equal consideration, and is coordinated with other aspects of water resources development [16 U.S.C. 661]. The FWCA establishes a consultation requirement for Federal departments and agencies that undertake any action that proposes to modify any stream or other body of water for any purpose, including navigation and drainage [16 U.S.C 662(a)]. Consistent with this consultation requirement, NMFS provides recommendations and comments to Federal action agencies for the purpose of conserving fish and wildlife resources. The FWCA allows the opportunity to offer recommendations for the conservation of species and habitats beyond those currently managed under the MSA. NMFS has determined that nearshore habitat will be negatively impacted by proposed project activities. As such, EFH Conservation Recommendations provided above also serve as FWCA recommendations to compensate for these negative impacts.

Thank you for consulting with NMFS. Please contact me at (562) 980-4037 or Bryant.Chesney@noaa.gov if you have any questions concerning this EFH consultation or require additional information.

Sincerely,



W. Bryant Chesney
Acting Assistant Regional Administrator
for Habitat Conservation

Works Cited

Able, K. W., Duffy-Anderson, J.T., 2005. A synthesis of impacts of piers on juvenile fishes and selected invertebrates in the lower Hudson River. Report to the Rutgers Institute of Marine and Coastal Sciences, IMCS Contribution #2005-13. 29 p.

Britt, Lyle L. 2001. "Aspects of the vision and feeding ecology of larval lingcod (*Ophiodonelongatus*) and Kelp Greenling (*Hexagrammos decagrammus*)." M.Sc. Thesis, University of Washington.

Bulleri, F., Chapman, M.G., 2010. The introduction of coastal infrastructure as a driver of change in marine environments. *Journal of Applied Ecology*, 47: 26-35.

Glasby, T.M., Connell, S.D., Holloway, M.G., Hewitt, C.L., 2007. Nonindigenous biota on artificial structures: Could habitat creation facilitate biological invasions? *Marine Biology*, 151: 887-895.

Merkel and Associates, Inc. 2008. Commercial fisheries revitalization and coastal public access plan. Existing Marine Biological Resources at Driscoll's wharf and Tuna harbor. Technical Report prepared for Lisa Wise Consulting LLC.

Merkel and Associates, Inc. 2009. Visual photo observations of leopard sharks in Seaplane Lagoon, Port of Los Angeles.

Silva, P.C., R.A. Woodfield, A.N. Cohen, L.H. Harris, and J.H.R. Goddard. 2002. First report of the Asian kelp *Undaria pinnatifida* in the northeastern Pacific Ocean. *Biological Invasions*, 4: 333-338.

Science Applications International Corporation (SAIC). 2010. Final 2008 Biological Surveys of Los Angeles and Long Beach Harbors. Report submitted to the Ports of Los Angeles and Long Beach.

Tyrell, M.C., Byers, J.E., 2007. Do artificial substrates favor nonindigenous fouling over native species? *Journal of Experimental Marine Biology and Ecology*, 342: 54-60.

Wasson, K., Fenn, K., Pearse, J.S., 2005. Habitat differences in marine invasions of central California. *Biological invasions*, 7: 935-948.

1 **United States Department of Commerce, National** 2 **Oceanic and Atmospheric Administration, National** 3 **Marine Fisheries Service (NMFS)**

4 **Response to Comment NMFS-1**

5 As discussed in Section 3.3 and Appendix F3 of the Draft EIS/EIR, the proposed Project is located in an
6 area of the Port designated as Essential Fish Habitat (EFH) for federally managed species described in the
7 Coastal Pelagic Species Management Plan and the Pacific Coast Groundfish Management Plan. The status
8 of federally-managed fish species and effects of the proposed action on them and other marine species as
9 well as EFH are discussed below.

10 The LAHD and the POLB conduct regular biological surveys of the Los Angeles and Long Beach Harbor
11 (Harbor), with the 2008 survey completed most recently⁹. Of the 95 species included under the Coastal
12 Pelagic and Pacific Coast Groundfish management plans, 19 adult species have been observed within the
13 Harbor during biological surveys, although most have been collected sporadically and in low numbers. Of
14 the 19 species, only two (2) are likely to occur in the proposed Project vicinity: *Engraulis mordax* (northern
15 anchovy) and *Sardinops sagax* (Pacific sardine). In the 2008 survey, the northern anchovy was the most
16 abundant species in both the Inner and Outer Harbor areas; Pacific sardine was less abundant. These
17 surveys also showed a stable incidence of non-indigenous species (NIS), and increased diversity and
18 abundance of native marine species since the prior survey.

19 *Dredging*

20
21 As stated in the comment letter and described in the Appendix F3 of the Draft EIS/EIR, state-issued waste
22 discharge requirements (WDRs) and best management practices (BMPs) implemented during construction
23 and operations would result in less than significant impacts to water quality and EFH. The proposed in- and
24 over-water construction requires a permit from the USACE, and WDRs and section 401 water quality
25 certification from the Los Angeles Regional Water Quality Control Board (Los Angeles RWQCB). During
26 construction and dredging, a water quality monitoring program would be implemented by LAHD with
27 oversight by the USACE and Los Angeles RWQCB, and as required by special conditions of the USACE
28 permit. Over the life of the Project, WDRs would be implemented and monitored by LAHD through
29 LAHD-required lease measures for the APL Terminal.

30 **Response to Comment NMFS-2**

31 As discussed in Section 3.3 of the Draft EIS/EIR and consistent with NMFS requirements in the *Caulerpa*
32 Control Protocol, the LAHD will conduct an underwater survey for *Caulerpa* prior to construction. If any
33 *Caulerpa* is found, an eradication plan will be developed and implemented in conjunction with NMFS and
34 the California Department of Fish and Game (CDFG), and construction will be delayed until subsequent
35 surveys demonstrate full eradication has been achieved. In addition, maintenance dredging in later project
36 years would be evaluated and permitted separately from the proposed Project. The USACE's permit would
37 include special conditions requiring *Caulerpa* surveys in advance of those actions.

⁹ Science Applications International Corporation (SAIC).2010. *Final 2008 Biological Surveys of Los Angeles and Long Beach Harbors*. In association with Seaventures, Keane Biological Consulting, Tenera Environmental, ENCORP Consulting Inc. and Tierra Data Inc.

1 **Response to Comment NMFS-3**

2 As discussed in Section 3.3 of the Draft EIS/EIR, SC BIO-1 and the USACE’s permit special conditions
3 will require the use of a “soft-start” pile driving technique, to further reduce noise impacts by encouraging
4 fish and marine mammals to avoid the area at the onset of pile driving, and also calls for an observer to be
5 present prior to pile driving to ensure no marine mammals are seen within the area before pile driving
6 commences. In addition, the Project proposes use of concrete rather than hollow steel piles to dampen over-
7 and under water noise levels during pile driving. In addition, the Project proposes use of concrete rather
8 than hollow steel piles which should dampen over- and under water noise levels during pile driving.
9 Therefore, it is the USACE’s determination noise due to pile driving is expected to result in a less than
10 significant impact on biological resources.

11 **Response to Comment NMFS-4**

12 The USACE respectfully disagrees with NMFS’s conclusions related to permanent impacts to EFH due to
13 shade associated with the proposed wharf at Berth 306. The wharf (including the deck and concrete support
14 piles) at Berth 306 would be oriented in a northeast/southwest configuration and would not extend over any
15 soft-bottom habitat, but would extend over existing artificial substrate consisting of artificial fill and rock
16 riprap placed in 2005 as part of the Channel Deepening Project. Space between the piles would range from
17 10 to 22 feet, allowing circulation of water and mixing of phytoplankton during tidal exchange (i.e., the
18 proposed piles would not have the effect of fill or impair circulation). The wharf deck would extend over
19 an approximately 2.7-acre area of water, and would be approximately 10-12 feet above the water surface
20 elevation of +4.8, which would not preclude light penetration below the wharf deck. Sand sediment at a
21 depth of -55 feet mean lower low water (MLLW) occurs at the toe of the rock riprap and would not be
22 disturbed or shaded by the proposed concrete piles or wharf deck.

23
24 As discussed in Section 3.3 of the Draft EIS/EIR, following wharf construction, shade upon the existing
25 riprap may alter the epifaunal community by selecting for aquatic organisms adapted to shade and locally
26 reduce photosynthesis. However, this potential change does not represent a substantial loss of ecosystem
27 function or a disruption of marine biological communities in the Project area or the Harbor as a whole.
28 Therefore, it is the USACE’s determination the potential impact would be localized and less than significant.
29

30 The San Pedro Bay Port Complex is highly industrialized with the biggest contributor to improved
31 ecological health and EFH being water quality, which has improved steadily since the 1970s. As stated
32 above, the area under the proposed wharf at Berth 306 is primarily artificial fill and rock riprap placed
33 during construction of the Pier 300 41-acre fill in 2005. Modification to this area following wharf
34 construction is not expected to affect the abundance or diversity of federally-managed species in the Harbor.
35

36 The LAHD operates the Port under the legal mandates of the Port of Los Angeles Tidelands Trust (Los
37 Angeles City Charter, Article VI, Section 601; the California Tidelands Trust Act of 1911) and the
38 California Coastal Act (CCA) (PRC Division 20 Section 30700 *et seq.*), which identify the Port and its
39 facilities as a primary economic and coastal resource of the state of California and an essential element of
40 the national maritime industry for promotion of commerce, navigation, fisheries, and harbor operations.
41 These mandates indicate activities should be water dependent and give highest priority to navigation,
42 shipping, and necessary support and access facilities to accommodate the demands of foreign and domestic
43 water-borne commerce. Specifically, the CCA sought to identify and limit areas for industrial activities
44 along the California coast as a way to provide trade opportunities while protecting remaining coastal areas
45 from industrial development. Since its inception, the Port has been a highly engineered harbor. The first
46 dredging events took place in the late 1800s, followed by the construction of an approximately five-mile
47 long jetty in the early 1900s. With industrialization came poor water quality and degraded marine habitat.

1 For example, as recently as the late 1960s, dissolved oxygen levels at some locations in the Harbor were so
2 low that little or no marine life could survive.¹⁰

3
4 Over the last 40 years, a combination of federal and state regulations restricted industrial and stormwater
5 discharges to the Harbor. LAHD-led sediment remediation and habitat restoration projects have greatly
6 improved water quality and in turn, marine biological resources. For example, in the Pier 300/Seaplane
7 Lagoon area, both shallow water and eelgrass (*Zostera marina*) habitat have been created. The Pier
8 300/Seaplane Lagoon eelgrass site is comprised of suitable dredged material (fill) with rock revetment and
9 very shallow water habitat (-2 to -6 feet MLLW). Eelgrass was introduced to the site in 2003 and
10 supplemental planting occurred in 2007. Since 2007, eelgrass coverage has remained fairly stable, with
11 approximately 30.6 acres of eelgrass observed at this site during the 2008 biological survey.

12
13 The LAHD, in conjunction with POLB, recently released the *Port of Los Angeles and Port of Long Beach*
14 *Water Resources Action Plan* (WRAP), which included 14 measures aimed at attaining full beneficial uses
15 of Harbor waters and sediments. The WRAP addresses the impacts of past, present, and future Port
16 operations, and provides a framework to prevent Port operations from further degrading water and sediment
17 quality in the Harbor. WRAP implementation will facilitate LAHD's ongoing efforts to improve water
18 quality and restore native marine biological communities throughout the Harbor. The Harbor is also listed
19 for sediment impairments in the recently approved Dominguez Channel and Greater Los Angeles and Long
20 Beach Harbor Water Toxic Pollutants Total Maximum Daily Load (TMDL). Efforts by the LAHD to
21 address these impairments and achieve TMDL compliance will result in further improvement to harbor
22 water and sediment quality.

23 **Response to Comment NMFS-5**

24 As discussed in the comment letter, man-made hard substrates may not support native fish, invertebrate, and
25 algal species. Federally managed species, including Pacific sardine and northern anchovy, are pelagic
26 species and not associated with hard substrates; therefore, these species are not expected to be impaired by
27 the proposed Project. The comment letter also notes that shaded areas and artificial structures may favor
28 NIS populations; however, data from the biological surveys do not support this conclusion. In the 2008
29 survey, NIS in the Harbor included one (1) species of fish (of 69 species collected), approximately 15
30 percent of total infauna and macroinvertebrates, and two (2) species of algae (of 22 species collected).
31 Since 1988, NIS populations have remained stable in the Harbor (SAIC, 2010). Such stability is likely due
32 in part to ballast water discharge regulations and improvements in water quality, which have supported
33 recovery of native species populations. Since biological survey data show native fish and algal species have
34 increased and the proportion of NIS has remained relatively constant during a time of significant terminal
35 development and Port expansion, the proposed terminal development at Berth 306 and the resultant shade
36 from the proposed new wharf deck and concrete support piles would not likely result in a significant
37 project-related impact or have a cumulatively considerable impact on marine biological resources in the
38 Harbor.

39
40 As discussed previously, the LAHD conducts periodic Harbor-wide studies which inventory and track
41 marine species diversity and abundance and trends of biological communities, water quality, and marine
42 habitat. Over the 20 years since regular surveys began, there has been a measurable improvement in water
43 and sediment quality, abundance and diversity of marine biological communities, and eelgrass and kelp
44 cover within Harbor boundaries, despite extensive expansion of Port-related landfills and terminal

¹⁰ Anderson, J.W., D.J. Reish, R.B. Spies, M. E. Brady, and E.W. Segelhorst. 1993. *Human Impacts*. Ch. 12 in: *Ecology of the Southern California Bight: A Synthesis and Interpretation* (M.D. Dailey, D.J. Reish, and J.W. Anderson [Eds.]). Univ. Calif. Press, Los Angeles, CA. 926 pages

1 developments, including the 500-acre Pier 400 fill project, a 232-acre container terminal on Pier 300, and
2 the 41-acre Pier 300 fill project. In total, over 600 acres of new Port-related fill and nine (9) new berths
3 within the Outer Harbor have been created in this time period. Meanwhile, between 1988 and 2008,
4 federally managed northern anchovy populations have increased within the Harbor and these population
5 increases have persisted. While the USACE acknowledges that NIS populations have persisted within the
6 Harbor and the distribution of some algal species has increased, limits on the amount of hard substrate in a
7 location specifically dedicated to maritime commerce is impracticable. Moreover, measures to assess the
8 impact and control the spread of non-indigenous algal species are better addressed through a Harbor-wide
9 initiative, such as through existing measures in the WRAP, than on a project-specific basis.

10
11 The USACE and LAHD administrative records of Port development also show the proposed Project has
12 been previously mitigated. In 1998, LAHD and USACE approved the Channel Deepening EIS/EIR project,
13 which proposed discharges of dredged material to create uplands facilitating terminal expansion within the
14 Port. In 2000, the USACE and LAHD prepared a supplemental EIS/EIR and identified the specific area
15 east of Pier 300 as a disposal site for 1.6 million cubic yards of dredged material. This supplemental
16 EIS/EIR also disclosed that the fill at Pier 300 would be developed and used as a marine industrial terminal.
17 As part of this action, the LAHD committed 71.5¹¹ credits from the NMFS-approved Bolsa Chica
18 Mitigation Bank for the Pier 300 fill. The 71.5 credits included 60 credits for the fill, plus an additional
19 11.5 credits to address potential degradation of the shallow water habitat in the Seaplane Lagoon. As
20 described above, eelgrass was established for the Pier 300 41-acre fill within the very shallow water habitat
21 ¹² in the Seaplane Lagoon as part of the eelgrass mitigation project. Eelgrass was planted at this site in May
22 and August of 2003. Monitoring over the first 36 months post-introduction determined that a portion to the
23 north was not performing to standards, and additional eelgrass was planted in July 2007. This supplemental
24 planting extended the monitoring period to 96 months (from initial planting in 2003), which was completed
25 in August of 2011. Monitoring efforts indicate that performance goals have been met.¹³ It is important to
26 note that a reduction in habitat quality and eelgrass cover in Seaplane Lagoon following placement of the
27 Pier 300 41-acre fill has not been observed.

28 **Response to Comment NMFS-6**

29 As discussed above, the USACE has determined further compensatory mitigation for marine biological
30 resources/EFH as described in Conservation Recommendation No. 1 is not warranted because potential
31 impacts to EFH would be localized and less than significant. In addition, LAHD completed the Pier 300
32 41-acre fill at Berth 306 in 2005, committed 71.5 acres of NMFS-approved Bolsa Chica Mitigation Bank
33 credits to compensate for marine habitat impacts at and near Berth 306, established eelgrass habitat in the
34 Seaplane Lagoon, and in accordance with NEPA and CEQA identified long-term uses at the APL Terminal
35 including Berth 306 as a maritime industrial terminal supporting shipping and terminal operations
36 consistent with the provisions of the Port of Los Angeles Tidelands Trust (Los Angeles City Charter,
37 Article VI, Section 601; the California Tidelands Trust Act of 1911) and the CCA (PRC Division 20
38 Section 30700 *et seq.*).

¹¹ The 71.5 credit value may be adjusted based on final fill acreages as determined by as-built drawing and post construction surveys. All 71.5 credits are Outer Harbor credits from the Bolsa Chica mitigation bank.

¹² The initial shallow water habitat was created years earlier as a result of a previous Port-related development. For the eelgrass mitigation component, this shallow water was filled to create “very shallow water” (-2 to -6) to support eelgrass.

¹³ Merkel & Associates. 2011. 96-Month Post-Transplant Survey at the Eelgrass Mitigation Site in Support of the Pier 300 Expansion Project at the Port of Los Angeles, California. Prepared for the Port of Los Angeles.

1 **Response to Comment NMFS-7**

2 With respect to notification, as described in Conservation Recommendation No. 2, the USACE and LAHD
3 agree to NMFS's request. LAHD will notify NMFS no less than 14 calendar days prior to commencing
4 construction, dredging, and disposal operations associated with the proposed Project. LAHD will also
5 notify NMFS no less than five calendar days prior to completion of construction, dredging, and disposal
6 operations. This notification requirement will be included as a special condition of the USACEs permit,
7 added to the Final EIS/EIR (refer to Chapter 3, Modifications to the Draft EIS/EIS for specific details) and
8 included in all construction contracts via the Mitigation Monitoring and Reporting Program. The
9 notification requirement will be added as a new standard condition of approval – SC BIO-2 under Impact
10 BIO-2a. The new standard condition of approval will be as follows:

11
12 “SC BIO-2: The Los Angeles Harbor Department (LAHD) will notify the National Marine
13 Fisheries Service (NMFS) no less than 14 calendar days prior to commencing construction,
14 dredging, and disposal operations associated with the proposed Project. LAHD will also notify
15 NMFS no less than five calendar days prior to completion of construction, dredging, and disposal
16 operations”

17 **Response to Comment NMFS-8**

18 As discussed in Section 3.3 of the Draft EIS/EIR and this response to comments section, it is the USACEs
19 determination that the construction and operation of the proposed wharf at Berth 306 would not result in
20 substantial adverse project-related or cumulative impacts to marine biological resources/EFH due to
21 shading of and placement of artificial structures (concrete piles and wharf deck) in the Harbor. Moreover,
22 through voluntary efforts such as the WRAP, and compliance with regulatory programs such as the
23 National Pollutant Discharge Elimination System and TMDL programs, LAHD is working to improve
24 marine habitat within the Harbor to build upon the improvements in water and sediment quality and
25 biological resources observed during the past 20 or more years. WRAP efforts are routinely monitored by
26 several state and federal resource agencies and non-governmental organizations including NMFS, the
27 USACE, the U.S. Environmental Protection Agency, U.S. Fish and Wildlife Service, California Coastal
28 Commission, CDFG, the Los Angeles RWQCB, and Heal the Bay.



United States Department of the Interior

OFFICE OF THE SECRETARY
Office of Environmental Policy and Compliance
Pacific Southwest Region
333 Bush Street, Suite 515
San Francisco, CA 94104

IN REPLY REFER TO:
(ER 11/1172)

Filed Electronically

17 February 2012

Ms. Theresa Stevens
U.S. Army Corps of Engineers
Los Angeles District, Regulatory Division
2151 Alessandro Drive, Suite 110
Ventura CA 93001

Subject: Draft Environmental Impact Statement/Environmental Impact Report (DEIS/EIR) for a Permit Application for the Proposed Berths 302-306 Container Terminal Improvements Project at the Port of Los Angeles, Los Angeles County, CA

Dear Ms Stevens:

The Department of the Interior has received and reviewed the subject document and has the no comments to offer.

DOI-1

Thank you for the opportunity to review this project.

Sincerely,

Patricia Sanderson Port
Regional Environmental Officer

cc:
Director, OEPC

1 **U.S. Department of the Interior (DOI)**

2 **Response to Comment DOI-1**

3 Thank you for your review and comment on the Draft EIS/EIR.

4

NATIVE AMERICAN HERITAGE COMMISSION

915 CAPITOL MALL, ROOM 364
 SACRAMENTO, CA 95814
 (916) 653-6251
 Fax (916) 657-5390
 Web Site www.nahc.ca.gov
 ds_nahc@pacbell.net



December 21, 2011

Ms. Jan Green Rebstock

City of Los Angeles City Harbor Department

425 S. Palos Verdes Street
 San Pedro, CA 90731

Re: SCH#2009071031 CEQA Notice of Completion; draft Environmental Impact Report (DEIR) for the "Berths 302-306 [APL] Container Terminal Project;" located in the San Pedro area; Los Angeles County, California

Dear Ms. Green Rebstock:

The Native American Heritage Commission (NAHC) is the State of California 'Trustee Agency' for the protection and preservation of Native American cultural resources pursuant to California Public Resources Code §21070 and affirmed by the Third Appellate Court in the case of EPIC v. Johnson (1985: 170 Cal App. 3rd 604). The court held that the NAHC has jurisdiction and special expertise, as a state agency, over affected Native American resources, impacted by proposed projects including archaeological, places of religious significance to Native Americans and burial sites. The NAHC wishes to comment on the proposed project.

This letter includes state and federal statutes relating to Native American historic properties of religious and cultural significance to American Indian tribes and interested Native American individuals as 'consulting parties' under both state and federal law. State law also addresses the freedom of Native American Religious Expression in Public Resources Code §5097.9.

The California Environmental Quality Act (CEQA – CA Public Resources Code 21000-21177, amendments effective 3/18/2010) requires that any project that causes a substantial adverse change in the significance of an historical resource, that includes archaeological resources, is a 'significant effect' requiring the preparation of an Environmental Impact Report (EIR) per the CEQA Guidelines defines a significant impact on the environment as 'a substantial, or potentially substantial, adverse change in any of physical conditions within an area affected by the proposed project, including ... objects of historic or aesthetic significance.' In order to comply with this provision, the lead agency is required to assess whether the project will have an adverse impact on these resources within the 'area of potential effect (APE), and if so, to mitigate that effect.

The NAHC Sacred Lands File (SLF) search resulted as follows: **Native American cultural resources were not identified** within the project area identified. Also, the absence of archaeological resources does not preclude their existence. . California Public Resources Code §§5097.94 (a) and 5097.96 authorize the NAHC to establish a Sacred Land Inventory to record Native American sacred sites and burial sites. These records are exempt from the provisions of the California Public Records Act pursuant to California Government Code §6254 (r). The purpose of this code is to protect such sites from vandalism, theft and destruction. The NAHC "Sacred Sites," as defined by the Native American Heritage Commission and the California Legislature in California Public Resources Code §§5097.94(a) and 5097.96. Items in the NAHC

NAHC-1

Sacred Lands Inventory are confidential and exempt from the Public Records Act pursuant to California Government Code §6254 (r).

Early consultation with Native American tribes in your area is the best way to avoid unanticipated discoveries of cultural resources or burial sites once a project is underway. Culturally affiliated tribes and individuals may have knowledge of the religious and cultural significance of the historic properties in the project area (e.g. APE). We strongly urge that you make contact with the list of Native American Contacts on the list of Native American contacts, to see if your proposed project might impact Native American cultural resources and to obtain their recommendations concerning the proposed project. Special reference is made to the *Tribal Consultation* requirements of the California 2006 Senate Bill 1059: enabling legislation to the federal Energy Policy Act of 2005 (P.L. 109-58), mandates consultation with Native American tribes (both federally recognized and non federally recognized) where electrically transmission lines are proposed. This is codified in the California Public Resources Code, Chapter 4.3 and §25330 to Division 15.

NAHC-2

Furthermore, pursuant to CA Public Resources Code § 5097.95, the NAHC requests that the Native American consulting parties be provided pertinent project information. Consultation with Native American communities is also a matter of environmental justice as defined by California Government Code §65040.12(e). Pursuant to CA Public Resources Code §5097.95, the NAHC requests that pertinent project information be provided consulting tribal parties. The NAHC recommends *avoidance* as defined by CEQA Guidelines §15370(a) to pursuing a project that would damage or destroy Native American cultural resources and Section 2183.2 that requires documentation, data recovery of cultural resources.

NAHC-3

Consultation with tribes and interested Native American consulting parties, on the NAHC list, should be conducted in compliance with the requirements of federal NEPA and Section 106 and 4(f) of federal NHPA (16 U.S.C. 470 *et seq*), 36 CFR Part 800.3 (f) (2) & .5, the President's Council on Environmental Quality (CSQ, 42 U.S.C 4371 *et seq.* and NAGPRA (25 U.S.C. 3001-3013) as appropriate. The 1992 *Secretary of the Interiors Standards for the Treatment of Historic Properties* were revised so that they could be applied to all historic resource types included in the National Register of Historic Places and including cultural landscapes. Also, federal Executive Orders Nos. 11593 (preservation of cultural environment), 13175 (coordination & consultation) and 13007 (Sacred Sites) are helpful, supportive guides for Section 106 consultation. The aforementioned Secretary of the Interior's *Standards* include recommendations for all 'lead agencies' to consider the historic context of proposed projects and to "research" the cultural landscape that might include the 'area of potential effect.'

NAHC-4

Confidentiality of "historic properties of religious and cultural significance" should also be considered as protected by California Government Code §6254(r) and may also be protected under Section 304 of the NHPA or at the Secretary of the Interior discretion if not eligible for listing on the National Register of Historic Places. The Secretary may also be advised by the federal Indian Religious Freedom Act (cf. 42 U.S.C., 1996) in issuing a decision on whether or not to disclose items of religious and/or cultural significance identified in or near the APEs and possibility threatened by proposed project activity.

NAHC-5


Furthermore, Public Resources Code Section 5097.98, California Government Code §27491 and Health & Safety Code Section 7050.5 provide for provisions for accidentally discovered archeological resources during construction and mandate the processes to be followed in the event of an accidental discovery of any human remains in a project location other than a 'dedicated cemetery'.

NAHC-6

To be effective, consultation on specific projects must be the result of an ongoing relationship between Native American tribes and lead agencies, project proponents and their contractors, in the opinion of the NAHC. Regarding tribal consultation, a relationship built around regular meetings and informal involvement with local tribes will lead to more qualitative consultation tribal input on specific projects.

If you have any questions about this response to your request, please do not hesitate to contact me at (916) 653-6251.

Sincerely,



Dave Singleton
Program Analyst

Cc: State Clearinghouse

Attachment: Native American Contact List

California Native American Contacts

Los Angeles County
December 21, 2011

LA City/County Native American Indian Comm
Ron Andrade, Director
3175 West 6th St, Rm. 403
Los Angeles , CA 90020
randrade@css.lacounty.gov
(213) 351-5324
(213) 386-3995 FAX

Ti'At Society/Inter-Tribal Council of Pimu
Cindi M. Alvitre, Chairwoman-Manisar
3098 Mace Avenue, Aapt. D Gabrielino
Costa Mesa, , CA 92626
calvitre@yahoo.com
(714) 504-2468 Cell

Tongva Ancestral Territorial Tribal Nation
John Tommy Rosas, Tribal Admin.
Private Address Gabrielino Tongva
tattnlaw@gmail.com
310-570-6567

Gabrieleno/Tongva San Gabriel Band of Mission
Anthony Morales, Chairperson
PO Box 693 Gabrielino Tongva
San Gabriel , CA 91778
GTTribalcouncil@aol.com
(626) 286-1632
(626) 286-1758 - Home
(626) 286-1262 -FAX

Gabrielino Tongva Nation
Sam Dunlap, Chairperson
P.O. Box 86908 Gabrielino Tongva
Los Angeles , CA 90086
samdunlap@earthlink.net
(909) 262-9351 - cell

Gabrielino Tongva Indians of California Tribal Council
Robert F. Dorame, Tribal Chair/Cultural Resources
P.O. Box 490 Gabrielino Tongva
Bellflower , CA 90707
gtongva@verizon.net
562-761-6417 - voice
562-761-6417- fax

Gabrielino-Tongva Tribe
Bernie Acuna
1875 Century Pk East #1500 Gabrielino
Los Angeles , CA 90067
(619) 294-6660-work
(310) 428-5690 - cell
(310) 587-0170 - FAX
bacuna1@gabrieinotribe.org

Gabrielino-Tongva Tribe
Linda Candelaria, Chairwoman
1875 Century Park East, Suite 1500
Los Angeles , CA 90067 Gabrielino
lcandelaria1@gabrielinoTribe.org
626-676-1184- cell
(310) 587-0170 - FAX
760-904-6533-home

This list is current only as of the date of this document.

Distribution of this list does not relieve any person of the statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 5097.94 of the Public Resources Code and Section 5097.98 of the Public Resources Code.

This list is applicable for contacting local Native Americans with regard to cultural resources for the proposed SCH#2009071031; cEQA Notice of Completion; draft Environmental Impact Report (DEIR) for the Berths 302 - 306 {APL} Container Terminal Project; located in the San Pedro Area; Los Angeles County, California.

California Native American Contacts
Los Angeles County
December 21, 2011

Gabrieleno Band of Mission Indians
Andrew Salas, Chairperson
P.O. Box 393 Gabirelino
Covina , CA 91723
(626) 926-4131
gabrielenoindians@yahoo.
com

This list is current only as of the date of this document.

Distribution of this list does not relieve any person of the statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 5097.94 of the Public Resources Code and Section 5097.98 of the Public Resources Code.

This list is applicable for contacting local Native Americans with regard to cultural resources for the proposed SCH#2009071031; cEQA Notice of Completion; draft Environmental Impact Report (DEIR) for the Berths 302 - 306 {APL} Container Terminal Project; located in the San Pedro Area; Los Angeles County, California.

2.3.2 State Government

Native American Heritage Commission (NAHC)

Response to Comment NAHC-1

Thank you for your review and comment on the Draft EIS/EIR. As described in Section 3.4.2 and Appendix G of the Draft EIS/EIR, the Native American Heritage Commission (NAHC) was contacted by letter on November 4, 2009, during the Notice of Intent/Notice of Preparation (NOI/NOP) phase of the Draft EIS/EIR, to request information about traditional cultural properties such as cemeteries and sacred places that might exist in the proposed Project area. As with your current letter, the record search of the Sacred Lands file failed to indicate the presence of Native American cultural resources in the immediate Project area. As you noted, the absence of archaeological resources does not preclude their existence; therefore, as detailed in Section 3.4.4.3 of the Draft EIS/EIR, SC CR-1 would be applied as a standard condition of approval involving surface soil disturbing activities on the proposed Project site.

SC CR-1: Stop Work in Area if Prehistoric and/or Archaeological Resources are Encountered. In the unlikely event that any artifact, or an unusual amount of bone, shell, or non-native stone is encountered during construction, work shall be immediately stopped, the area secured, and work relocated to another area until the found materials can be assessed by individuals competent to assess their value. Examples of such cultural materials might include concentrations of grinding stone tools such as mortars, bowls, pestles, and manos; chipped stone tools such as projectile points or choppers; flakes of stone not consistent with the immediate geology such as obsidian or fused shale; historical trash pits containing bottles and/or ceramics; or structural remains. The contractor shall stop construction within 10 meters (30 feet) of the exposure of these finds until a qualified archaeologist can be retained by the Port to evaluate the find (see 36 CFR 800.11.1 and California Code of Regulations, Title 14, Section 15064.5(f)). If the resources are found to be significant, they shall be avoided or shall be mitigated consistent with Section 106 or State Historic Preservation Officer Guidelines. All construction equipment operators shall attend a preconstruction meeting presented by a professional archaeologist retained by the Port that shall review types of cultural resources and artifacts that would be considered potentially significant, to ensure operator recognition of these materials during construction.

Prior to beginning construction, the Port shall meet with applicable Native American Groups, including the Gabrieliño/Tongva Tribal Council, to identify areas of concern. A trained archaeologist shall monitor construction at identified areas. In addition to monitoring, a treatment plan shall be developed in conjunction with the Native American Groups to establish the proper way of extracting and handling all artifacts in the event of an archaeological discovery.

Response to Comment NAHC-2

As with your current letter, the 2009 letter received from the NAHC contained a list of nine Native American tribes and individuals interested in consulting on development projects. As detailed in Section 3.4.2 and Appendix G of the Draft EIS/EIR, LAHD contacted the Native American tribes and individuals previously provided by the NAHC. Letters were sent via U.S. mail to the nine Native American contacts on December 16, 2009, requesting information regarding potential cultural resources that may be located within the proposed Project vicinity. Three responses were received. A follow-up attempt was made to

1 contact each of these individuals/groups by phone in January 2010. Of those contacted, none provided
2 information about traditional cultural properties in the proposed Project area. In addition, standard
3 condition of approval for the proposed Project, SC CR-1 (above), includes a provision that ... *“Prior to*
4 *beginning construction, the Port shall meet with applicable Native American Groups, including the*
5 *Gabrielino/Tongva Tribal Council, to identify areas of concern. A trained archaeologist shall monitor*
6 *construction at identified areas. In addition to monitoring, a treatment plan shall be developed in*
7 *conjunction with the Native American Groups to establish the proper way of extracting and handling all*
8 *artifacts in the event of an archaeological discovery.”*
9

10 Furthermore, in accordance with USACE regulations at 33 CFR 325 Appendix C, and 36 CFR 800, Subpart
11 B, 800.3(a)(1), the USACE requested a sacred lands file search from the NAHC on December 7, 2011. The
12 NAHC responded on December 8, 2011 and indicated no sacred lands or Native American cultural
13 resources were identified from their inventory, and provided contact information for nine (9) Native
14 American representatives; these individuals were contacted by letter dated December 12, 2011, and given
15 30 days to respond. No responses from Native American representatives were received. To complete the
16 USACE’s cultural resources consultation process requirements, the USACE contacted the State Historic
17 Preservation Officer (SHPO) by letter dated February 22, 2012 with a determination that the proposed
18 Project would have no potential to cause effects to historic properties and a request for concurrence within
19 30 days. On May 2, 2012, the USACE received a letter from the SHPO with their concurrence that there
20 will be no historic properties affected by the proposed Project (refer to Section 2.4 of this chapter for a copy
21 of the SHPO letter). This concludes the USACE’s cultural resources consultation process.

22 **Response to Comment NAHC-3**

23 As described in Response to Comments NAHC-1 and NADC-2, and detailed in Appendix G of the Draft
24 EIS/EIR, on November 4, 2009, Native American coordination was initiated for the proposed Project in
25 compliance with Section 106 of the National Historic Preservation Act. Letters were sent to the nine Native
26 American contacts in December 2009, requesting information regarding potential cultural resources that
27 may be located within the Project vicinity. The letters included pertinent project information, such as
28 location maps and a description of the proposed Project and its related Area of Potential Effect. Follow-up
29 phone calls and emails were sent in January 2010, and subsequent follow-ups via telephone or email, or
30 both, were made as necessary. Of those contacted, none provided information about traditional cultural
31 properties in the proposed Project area. The results of the Native American coordination and the letters
32 describing the proposed Project are in Attachment A of Appendix G of the Draft EIS/EIR. Regarding the
33 recommendation of avoiding cultural resources, the comment is noted.

34 **Response to Comment NAHC-4**

35 As described in Response to Comment NAHC-3 above, consultation with tribes and interested Native
36 American consulting parties on the NAHC list has occurred in compliance with the National Environmental
37 Policy Act and Section 106. As detailed throughout Section 3.4 of the Draft EIS/EIR (specifically Sections
38 3.4.2 and 3.4.4.3) the geologic formation within the proposed Project area consists of imported/modern fill
39 material placed in the early 20th century. Specifically, the landform that makes up Pier 300 (location of the
40 current APL Terminal) was created in the early 1980s by material dredged from the inner and outer Los
41 Angeles harbors during the Channel Deepening Project. Additional expansions to Pier 300 have occurred
42 from harbor and channel deepening projects; including the 41-acre expansion area in 2005 (details on the
43 background of the site can be found in Section 2.2 of Chapter 2 of the Draft EIS/EIR). Therefore, the site
44 was created using imported/modern fill dredged material placed within the ancestral San Pedro Bay and no
45 intact prehistoric or historical archaeological resources would be expected to exist in soils. In addition, any
46 soil excavation on the existing terminal site (which began operating in 1997) would be in a previously
47 disturbed area, and therefore, would not be expected to adversely impact archaeological or paleontological

1 resources or unique geologic features. Based on the timeframe that the site was created (1980s and 2005),
2 material that the landform was created from (imported/modern fill from harbor and channel deepening
3 projects), and the sites disturbed condition, the “cultural landscape” of the Project site or vicinity was
4 considered in the analysis performed in Section 3.4.4.3 of the Draft EIS/EIR, which led to a finding of a less
5 than significant impact on historic resources.

6 **Response to Comment NAHC-5**

7 LAHD and USACE understand that the confidentiality of “historic properties of religious and cultural
8 significance” should be considered and will make every attempt to ensure confidentiality.

9 **Response to Comment NAHC-6**

10 As detailed in Response to Comment NAHC-1 above, the proposed Project includes a standard condition of
11 approval (SC CR-1) that provides for the accidental discovery of archaeological resources during
12 construction (i.e., surface disturbing activities).



South Coast
Air Quality Management District

21865 Copley Drive, Diamond Bar, CA 91765-4182
(909) 396-2000 • www.aqmd.gov

E-Mailed: February 24, 2012
ceqacomment@portla.org

February 24, 2012

Chris Cannon
Director of Environmental Management
Port of Los Angeles
425 South Palos Verdes Street
San Pedro, CA 90731

Dear Mr. Cannon:

**Review of the Draft Environmental Impact Report/Statement (Draft EIR/EIS)
for the Proposed Berths 302-306 (APL) Container Terminal Project**

The South Coast Air Quality Management District (AQMD) staff appreciates the opportunity to comment on the Draft EIR/EIS for the Proposed Berths 302-306 (APL) Container Terminal Project, and thanks the Port of Los Angeles (POLA) for accommodating our request on an extension past the comment deadline until February 24, 2012.

The proposed Project involves the expansion of the existing marine terminal from 291 to 347 acres and an increase of 1,250 linear feet of available wharf space. At completion, the projected container annual capacity will increase from 2.15 million TEUs to 3.20 million TEUs. As discussed in the Draft EIR/EIS, the proposed project would result in 390 annual vessel calls, 2,953 annual train trips, and 3.0 million annual truck trips or 8,342 truck trips per day at full operation. Based on the Draft EIR/EIS, the proposed Project will cause significant impacts after mitigation for construction and operation.

SCAQMD-1

Under the proposed Project, the on-dock railyard capacity will be unchanged. The existing on-dock railyard consists of 8 sets of double track with a capacity of 1.04 TEUs per year (pg. 2-56). The proposed Project is inconsistent with the future expansion scenarios envisioned in the San Pedro Bay Ports Rail Study. The San Pedro Bay Ports Rail Study Update (Rail Enhancement Program) included an enhancement to Pier 300 (APL Terminal) which specified the addition of an extra set of rail tracks¹. According to the San Pedro Bay Ports Rail Study Update, this enhancement will increase the on-dock rail capacity by approximately 600,000 TEUs per year. Maximizing use of on-dock rail

SCAQMD-2

¹ San Pedro Bay Ports Rail Study Update, December, 2006.

can reduce the number of drayage truck trips. The proposed Project will result in a significant increase in the number of drayage trucks. If the proposed Project increases on-dock rail capacity, off-site drayage truck trips (and the resulting emission and health impacts) to near and off-site railyards can be decreased.

**SCAQMD-2
Cont.**

While Alternative 6 is projected to increase the capacity of the existing on-dock railyard, its projected capacity is still below what was predicted in the San Pedro Bay Ports Rail Study. In order to address impacts from drayage trucks, the proposed Project should include the expansion of the on-dock railyard as envisioned in the San Pedro Bay Ports Rail Study.

The localized NO₂ and health risk significant impacts from the proposed Project will impact residents and local workers that surround the proposed Project site and necessitate the lead agency to mandate additional mitigation measures. These findings of significance show that all feasible mitigation measures including zero emission technologies are necessary, and should be incorporated as enforceable project requirements.

SCAQMD-3

In Attachment A, the SCAQMD staff has provided a discussion of changes to existing mitigation measures and some additional mitigation measures which the lead agency should implement. Attachment B includes a description of zero-emission container transport systems (ZECMS) with supporting evidences that zero-emission transport between the APL Terminal and near dock railyards is feasible early in the life of the proposed Project, specifically, between 2016 and 2020. The proposed Project should incorporate a mitigation measure or alternative to mitigate significant localized NO₂ health risk impacts to the surrounding community using zero-emission container movement between the marine terminals and the near-dock railyard.

SCAQMD-4


The proposed Project is one of several major port projects that have either recently been approved or are currently going through the approval process that will more than double the current number of containers flowing through the ports. It is important that these projects are developed in a complementary and coordinated manner to achieve the long-term goal of reducing the significant air quality impacts the Ports of Los Angeles and Long Beach create in the South Coast Air Basin.

SCAQMD-5

Pursuant to Public Resources Code Section 21092.5, please provide the SCAQMD staff with written responses to all comments contained herein prior to the adoption of the Final EIR/EIS. Further, staff is available to work with the lead agency to address these issues and any other questions that may arise. Please contact me, at (909) 396-3105, if you have any questions regarding the enclosed comments.

SCAQMD-6

Sincerely,



Susan Nakamura
Planning Manager

SN:EE
Attachment

ATTACHMENT A**CEQA Baseline**

- The Draft EIR/EIS should include a realistic baseline which accurately reflects the improvements in air quality that will occur, independent of the proposed project. The Draft EIR/EIS uses a CEQA baseline for determination of air quality impacts from criteria pollutants based on a 12-month period from July 2008 to June 2009 which corresponds to the release of the Notice of Preparation (NOP) for the proposed Project. For analysis purposes under Air Quality Impacts AQ-1 through AQ-5, and AQ-9, this baseline is held constant and compared to future years under the proposed Project. However, this approach uses a comparison between the proposed Project impacts and a baseline that is not reflective of future emission reductions from existing air quality rules and regulations. As mentioned in previously submitted comment letters², the SCAQMD staff believes that CEQA not only allows but actually requires a determination of significant impacts that does not credit the project with unrelated improvements in air quality that will occur anyway. The lead agency did take this baseline approach when determining significance for cancer and other health risks of the proposed Project, and for consistency, this approach should be used when determining significance for regional criteria emissions.

The purpose of CEQA is to give the public and government agencies the information needed to make informed decisions. Not taking into account future emission reductions from existing air quality rules in the baseline results in the appearance that the proposed Project benefits air quality, while in fact the effect of existing rules and regulations is contributing most of the air quality benefits. CEQA's intent is to provide the public and decision makers the actual changes to the environment from the proposed Project.

SCAQMD-7

Zero Emission Container Transport System

- The on-dock rail yard will not be large enough to handle all the containers imported at this terminal, and the number of annual truck trips which will be trucked to near or off-dock rail yards will increase by 250% (Appendix E1 - Table 1.7.3). Because of the significant NO₂ and health risk impacts from the proposed Project operations (including trucking activities) identified in the Draft EIR/EIS, CEQA requires the lead agency to implement all feasible mitigation (CEQA Guidelines 15126.4). As is described in Attachment B, the proposed project can include a measure that requires transport of containers using a zero-emission technology that does not create tailpipe emissions from the vehicle or system that is transporting containers. Zero-emission container transport technologies can be implemented beginning 2016 as follows:
 - By 2016, at least 25% of container transport between the APL terminal and the near-dock railyards shall be by zero-emission technology.
 - By 2020, 100% of container transport between the APL terminal and the near-dock railyards shall be by zero-emission technology.

SCAQMD-8

² SCAQMD letters dated November 30, 2011 and January 19, 2012, to Mr. Christopher Cannon on the Draft Environmental Impact Report: Southern California International Gateway

Considering the current levels of product development, it is clear that, if the lead agency provides a clear message to technology providers that zero emission will be needed and when, zero-emission container transport technologies can be commercialized in sufficient time to begin operational deployment between the APL terminal and the near-dock railyards between by 2016, with 100% deployment for such transport by 2020. (See Attachment B - Zero-Emission Container Transport). The measure described above will send a clear market signal to technology developers and allow this schedule to be met.

SCAQMD-8
Cont.

Project Alternatives

- Under Alternative 6 – Proposed Project with Expanded On-Dock Railyard, all elements of the proposed Project will be developed with the addition of a redeveloped and expanded on-dock railyard. The existing on-dock railyard consists of 8 sets double track with a capacity of 1.04 TEUs per year (pg. 2-56). Under Alternative 6, one additional set of double tracks will be added increasing the capacity to 1.14 million TEUs per year (pg.2-56). SCAQMD staff considers this alternative to have benefits over the proposed Project because of the increase in on-dock rail capacity. However, the projected on-dock rail capacity of Alternative 6 still falls short of the expansion scenarios envisioned in the San Pedro Bay Ports Rail Study Update³ for the Pier 300 on-dock railyard (APL Terminal).

The San Pedro Bay Ports Rail Study Update (Rail Enhancement Program) included an enhancement to Pier 300 which specified the addition of an extra set of rail tracks. According to the San Pedro Bay Ports Rail Study Update, this enhancement increased the on-dock rail capacity by approximately 600,000 TEUs per year. According to the Draft EIR/EIS, the increase in capacity under Alternative 6 is projected to be 100,000 TEUs per year (1.14 million minus 1.04 million TEUs).

SCAQMD-9

Another area where Alternative 6 is inconsistent with the San Pedro Bay Ports Rail Study Update is that the Rail Study Update projects the on-dock rail utilization to be 38% once the planned enhancements are completed, while the on-dock rail utilization of Alternative 6 is estimated to be 32% (Appendix E1, Table 1.4-21). The lead agency needs to explain why there is a discrepancy between the San Pedro Bay Ports Rail Study Update planned enhancements to Pier 300 and the projections for Alternative 6 in Draft EIR/EIS, and if necessary re-evaluate the operational profile of Alternative 6.

³ San Pedro Bay Ports Rail Study Update, December, 2006.

Mitigation Measures

- *MM AQ-3: Fleet Modernization for On-road Trucks (used during construction)*

MM AQ-3 requires that all on-road heavy-duty diesel trucks used during construction should comply with the EPA 2007 on-road PM and NOx emission standards. MM AQ-3 specifies exceptions from this requirement for import haulers and earth movers. SCAQMD sees no reason for these exceptions. It has been five years since the 2007 on-road standards went into effect and even with the known slow turn-over of these trucks, it is very likely that trucks used for import haulers and earth movers, meeting the 2007 on-road standards are in service. The lead agency should remove these exceptions and require as part of this mitigation measure, use of the cleanest available trucks. Specifically, trucks used during construction should operate on engines with the lowest certified NOx emissions levels, and if the cleanest available truck does not meet the EPA 2007 on-road PM emission standards, then the lead agency shall require all trucks be equipped with CARB certified Level 3 DECS. Mitigation Measure MM AQ-3 should also apply during circumstances where a piece of compliant equipment becomes available during the timeframe of construction.

SCAQMD-10

- *MM AQ-4: Fleet Modernization for Construction Equipment*

MM AQ-4 requires that prior to January 1, 2015, all off-road diesel-powered construction equipment greater than 50 horsepower meet Tier 3 non-road emission standards and be equipped with CARB certified Level 3 diesel emission control system (DECS). Beginning in January 1, 2015, the mitigation measure requires all off-road diesel-powered construction equipment greater than 50 horsepower meet Tier 4 non-road emission standards with CARB certified Level 3 DECS. This mitigation measure does not represent the cleanest technology available since Tier 3 certified construction equipment has been available since 2006, and construction equipment meeting Tier 4 non-road emission standards became available beginning 2011. Mitigation Measure MM AQ-4 should be revised to require all construction equipment to meet the cleanest off-road engine emission standard available, and be equipped with Level 3 CARB verified DECS.

SCAQMD-11

- *MM AQ-11: Cleaner OGV Engines*

MM AQ-11 seeks to maximize the number of vessels calling at the APL terminal meeting the International Maritime Organization (IMO) January 1, 2016, NOx limit of 3.4 g/kW-hr (Tier 3). The SCAQMD staff supports this goal since it has a significant potential to decrease NOx emissions from ships, but the mitigation measure lacks any real commitment from the shipping line to actually reroute or purchase ships that meet the new IMO emission standard. Because the project will have significant regional and localized air quality impacts, the lead agency must implement additional feasible mitigation measures for all sources, including vessels. Additional vessel strategies should be incorporated into MM AQ-11 which includes incentives or requirements to preferentially route IMO-compliant Tier 3 vessels to the APL terminal. Mitigation measure MM AQ-11 should also be amended to include a minimum commitment on the percentage of ships calling at the proposed Project site which meet the new emissions standard.

SCAQMD-12

- *MM AQ-12: OGV Engine Emissions Reduction Technology Improvements*

MM AQ-12 requires that the Tenant determine the feasibility of incorporating advanced emissions reduction technologies and/or design options when using or retrofitting existing ships bound for the proposed Project terminal. Similar to mitigation measure MM AQ-11, this measure lacks any real implementation commitment on the part of the Tenant to actually perform any retrofits on existing ships. In order for the proposed Project to benefit from this measure, mitigation measure MM AQ-12 should be amended to include a detailed schedule for operators to perform a feasibility study on retrofitting their existing ships, including a requirement to contact engine manufacturers, and a commitment on the percentage of ships calling at the proposed Project site which would be retrofitted to use the advance emission reduction technologies, once they are deemed feasible.

SCAQMD-13

- *MM AQ-13: Yard Tractors at Berths 302-306 Terminal*
MM AQ-14: Yard Equipment at Berths 302-306 Railyard
MM AQ-15: Yard Equipment at Berths 302-306 Terminal

Mitigation measures MM AQ-13, MM AQ-14, and MM AQ-15 require yard tractors and other yard equipment to meet the most stringent U.S. EPA emissions standards by a specified date. Unfortunately, this would still result in diesel-powered equipment being used at the proposed Project site. Under Air Quality Impacts AQ-4: *Would the Operations Result in Off-site Ambient Air Pollutant Concentrations that Exceed a SCAQMD Threshold*, the lead agency concluded that NO₂ concentrations exceeded significant thresholds after mitigation. In addition, for Air Quality Impact AQ-7: *Would the Proposed Project Expose Receptors to Significant Levels of TACs*, the residential and occupational cancer risk remain significant after mitigation. Electric battery yard tractors are currently being tested at the Ports and if successful could reduce emissions NO_x and DPM emissions (as compared to diesel-powered yard tractors) from the proposed Project. Other yard equipment such as existing diesel-powered rubber tire gantry cranes could be replaced with electric rail-mounted gantry cranes as a means of further reducing NO_x and PM emissions (as compared to diesel-powered yard equipment). In order to reduce the impacts of Air Quality Impacts AQ-4 and AQ-7, mitigation measures MM AQ-13, MM AQ-14, and MM AQ-15 should contain a zero-emission yard tractor/yard equipment component.

SCAQMD-14

- *Rail Mitigation Measure*

The Draft EIR/EIS does not contain any mitigation measures for rail operations. Instead the lead agency relies on existing CAAP measure RL-2 to further reduce emissions from Class 1 locomotives operating at the APL terminal. The CAAP control measure RL-2 relies on the existing CARB MOUs and the existing U.S. EPA 2008 locomotive engine rulemaking to achieve emission reductions from rail operations. While most of the switching and building of trains under the proposed Project is done by PHL, line haul locomotives do operate at the proposed Project site and total rail emissions represent the third highest contributor to NO_x and PM_{2.5} emissions, after mitigation. In order to reduce the impacts under Air Quality Impacts AQ-4 and AQ-7, the lead agency should add mitigation that requires accelerated introduction of Tier 4 line haul locomotives used at the APL on-dock railyard.

SCAQMD-15

Proposed Project Emission Quantification Analysis and Assumptions

- *Locomotive Emission Factors*

The Draft EIR/EIS references the U.S. EPA Technical Highlights Document from the 2008 locomotive emission standard rulemaking as being the source of emission factors used in the emission calculations for rail operations.⁴ SCAQMD staff is very familiar with this document and our understanding is that the emission factors for future Tiers are not based on actual engine testing but are projections based on what the future locomotive Tiers are likely to achieve. These projections are not appropriate for estimating locomotive emissions when determining impacts under CEQA and can underestimate potential impacts from locomotives. The emission factors in future years should be based on the locomotive emission standards and a projected fleet mix based on natural turnover. Locomotive emission standards represent the “not to exceed level” and are more conservative than projected emission rates. The lead agency should re-calculate the locomotive emissions for future years using emission standards rather the projections provided by U.S. EPA.

SCAQMD-16

- *Ocean Going Vessel Fuel Sulfur Content*

In the Draft EIR/EIS, the lead agency assumes in the unmitigated scenario for general cargo and container ships, a sulfur content of 0.1 percent out to 24 nm and 0.2 percent from 24 nm to 40 nm during the construction period (2012 to 2014) when shore-side cranes are delivered (pages 3.2-39 and 3.2-42). However, the SCAQMD staff considers this assumption to be less than conservative since there is no requirement that fuels with these sulfur contents be used by container or general cargo ships operating within California state waters. Beginning August 1, 2012, both CARB’s marine diesel fuel rule for ocean going vessels and the IMO fuel sulfur requirements under the federal Emission Control Area (ECA) specifications, limit the maximum fuel sulfur content to 1.0 percent. CARB’s regulation applies out to a distance of 24 nm, while the IMO requirements apply out to 200 nm. It isn’t until January 2014, when CARB requires ocean going vessels to use a maximum sulfur content of 0.2 percent that assumptions for lower sulfur content marine fuels are justified.

Therefore, there is no reason to believe that all general cargo or container vessels will be using 0.2 percent sulfur when they are allowed a maximum limit of up to 1.0 percent. The unmitigated emission calculations for ocean going vessels during the construction period (i.e., 2012 to 2014) should be revised to reflect the higher conservative sulfur limits.

SCAQMD-17

⁴ U.S. EPA “Technical Highlights: Emission Factors for Locomotives” EPA-420-F-09-025, 2009

- *AMP Construction Emissions*

In calculating operational emissions from hotelling, the lead agency assumes container ships will use AMP in the percentages and time frames which are required under CARB's Shore-side Power Regulation. In order to meet these percentages all or most of the berths at the proposed Project site must have AMP infrastructure installed. However, according to Appendix E1 Table 1.1-6, construction emissions were only calculated for the newly constructed Berth 306. In addition, the 2010 CAAP Update describes that the POLA will install AMP infrastructure for all berths at Pier 300 by the end of 2013 (page 92). This implies that the lead agency is only attributing the construction of AMP infrastructure at Berth 306 to the proposed Project, while in fact the infrastructure construction improvements for all the other berths (which are integral to the proposed Project) are going on at the same time as the construction activities for the proposed Project. This underestimates the construction emissions of the proposed Project and the lead agency should include the remaining berth AMP upgrades in the emission quantification analysis for the proposed Project.

SCAQMD-18

- *Quantifying Mortality and Morbidity*

On page 3.2-60 of the DEIR, the lead agency describes the methodology that was used to determine when a mortality and morbidity analysis would be conducted for the proposed Project. Mortality is a measure of the number of deaths in a population, scaled to the size of that population, per unit time. Morbidity refers to the number of individuals who have contracted a disease during a given time period (the incidence rate) or the number who currently have that disease (the prevalence rate), scaled to the size of the population. The lead agency specifies that the POLA has determined that mortality and morbidity will be calculated when the incremental operational emissions would result in off-site 24-hour PM_{2.5} concentrations that exceed the SCAQMD significance criterion of 2.5 µg/m³."

The SCAQMD staff does not agree with the use a screening threshold of 2.5 µg/m³ for determining mortality and morbidity. The SCAQMD's PM_{2.5} significance threshold of 2.5 µg/m³ is designed to determine the significance of localized impacts on nearby receptors. The PM_{2.5} significance threshold of 2.5 µg/m³ was not intended to be used as a screening tool to further analyze mortality and morbidity impacts and is too high. With a screening threshold this high, it is unlikely that any project would conduct a mortality and morbidity analysis.

SCAQMD-19

The lead agency set precedent for conducting mortality and morbidity analyses in three of its own previous EIRs: TraPac, China Shipping, and San Pedro Waterfront EIRs. In all three cases there was no threshold used to determine if an analysis for mortality and morbidity would be done. The SCAQMD staff considers this to be sufficient precedent for the POLA to continue this practice for the proposed Project.

- *NO₂/NO_x ratio*

In the dispersion modeling files for NO_x impacts, the analysis appears to be based on two different in-stack NO₂/NO_x ratios: 0.5 and 0.1. The U.S. EPA recommends a default ratio of 0.5 for stationary sources. It is also not clear whether this ratio applies to mobile sources. The SCAQMD staff recommends that the lead agency provide further clarification regarding this choice of in stack ratios.

SCAQMD-20

- *Use of SIL as a significance threshold*

In determining the potential significance of annual PM 2.5 concentrations, the lead agency used the Significant Impact Level (SIL) of 0.3 ug/m³. Although the most recent SCAQMD guidance on CEQA thresholds does not list a value for PM_{2.5} annual impacts, SCAQMD staff recommends that the ambient air quality standards be used rather than the SIL to determine significance under CEQA.

SCAQMD-21

ATTACHMENT B
SCAQMD COMMENTS ON DRAFT EIR/EIS FOR THE PROPOSED BERTHS
302-306 (APL) CONTAINER TERMINAL PROJECT
ZERO-EMISSION CONTAINER TRANSPORT:
NEEDS AND TECHNOLOGIES

SCAQMD-22

Overview

SCAQMD comments regarding the Draft EIR/EIS for the Proposed Berths 302-306 (APL) Container Terminal Project propose a commitment by the lead agency to require deployment of zero-emission technologies to move containers between ports and the near-dock railyards. The specific technology or technologies used to implement this alternative would be determined by the lead agency. This alternative would be implemented according to the schedule set out in the comment, with deployment beginning by 2016. By 2020, all container moves between the APL Terminal and near-dock railyards would be by zero emission technologies.

Any of several types of zero-emission container movement systems could be used to implement this measure. As is described below, these include, but are not limited to, on-road technologies such as battery-electric trucks, fuel cell trucks, hybrid-electric trucks with all-electric range (AER) and zero-emission hybrid or battery-electric trucks with "wayside" power (such as electricity from overhead wires). The measure could also be implemented by fixed-guideway systems such as maglev or linear synchronous motor propulsion.

Such systems are not currently in use for full-scale port operations and, depending on the technology, may require different levels of additional development and optimization. But, as is described below, a variety of these technologies are being demonstrated, and there is substantial evidence that they can be made commercially available within a few years after commencement of proposed Project operation, particularly if the lead agency sends a market signal to technology developers by requiring the use of zero-emission technologies. In addition, many of these zero-emission technologies are expected to be operationally feasible to serve the APL Terminal. For example, electric trucks with adequate range, power and reliability -- such as are being developed and demonstrated at the Ports -- could fit into current operating procedures as a replacement for fossil fuel-powered trucks, and their implementation could be required and co-funded through mechanisms similar to those employed to implement the ports' Clean Truck Program (see below). Drayage service to the proposed Project is particularly conducive to implementation of zero-emission trucking technologies because of the relatively short distance involved and because the near-dock railyards could be served by a relatively limited number of trucks compared to the total number serving the ports and region.

Reasons for Zero-Emission Transport

As is described in the SCAQMD comment letter regarding the Draft EIR/EIS for the Proposed Berths 302-306 (APL) Container Terminal Project, deployment of zero-emission technologies for transport between the APL Terminal and the proposed Project will mitigate significant project impacts as required by CEQA.

In addition, zero emission transport is important for the following reasons:

- In the 2010 Update to the San Pedro Bay Ports Clean Air Action Plan, the ports underscored their commitment to air quality improvement by adopting San Pedro Bay Standards. These targets for port air quality programs are comprised of two components: 1) reduction in health risk from port-related diesel particulate matter (DPM) emissions in residential areas surrounding the ports, and 2) “fair share” reduction of port-related air emission to assist the region in achieving federal air quality standards. These components reflect the ports’ stated goals of reducing health risks to local communities from port-related sources, and reducing emissions to support the attainment of health-based ambient air quality standards on a regional level.

Specifically, the ports’ Health Risk Reduction Standard is to reduce the population-weighted cancer risk of ports-related DPM emissions by 85% by 2020, relative to 2005 conditions, in highly impacted communities located near port sources and throughout the residential areas in the port region. The San Pedro Bay Emission Reduction Standards are to, by 2014, reduce emissions by 22% for nitrogen oxides, 93% for sulfur oxides, and 72% for DPM; and to, by 2023, reduce emissions by 59% for nitrogen oxides, 93% for sulfur oxides and 77% for DPM.

While the ports have made significant progress toward meeting these goals, as reflected in each port’s annual emission inventories, emissions forecasts indicate that CAAP measures and existing emissions control regulations will not be adequate to achieve and maintain the San Pedro Bay Standards. Implementation of zero-emission technology options would provide significant benefits to the ports, bringing them closer to achieving the San Pedro Bay Standards, addressing community concerns about pollution from port operations and projects, and assisting the region in attaining National Ambient Air Quality Standards. The South Coast Air Quality Management District and the California Air Resources Board have determined that, in order to attain currently-adopted federal ozone standards, zero-emission technologies will need to be broadly deployed in transportation sources. Absent timely adoption of sufficient plans and measures to attain the national standards as required by the Clean Air Act, federal transportation funds for infrastructure projects will be jeopardized, and restrictions on construction of stationary sources will be imposed.

- Deployment of zero-emission technologies for the transport corridor between the APL Terminal and the near-dock railyards is particularly important for the following reasons:

- Emissions in this transport corridor occur relatively close to locations where people live, work and go to school.
 - These areas are also impacted by cumulative emissions from other port-related sources: ships, harbor craft, cargo handling equipment, locomotives and trucks.
 - Achieving emission reductions beyond current regulations and CAAP measures, as needed to attain the San Pedro Bay Standards, will be relatively challenging in the case of some port-related sources (e.g. vessel main engines) compared to further reducing emissions from other sources such as trucks.
 - The transport corridor to near dock rail yards is in an area where existing regulations and CAAP measures are projected to achieve a lower percentage level of risk reduction than other areas. *See* 2010 CAAP Update, Figure 2.2: Percent Reduction in DPM-Related Health Risk Between 2005 and 2020 for Areas Located Closest to the Ports (p.35).
 - The transport corridor to near dock rail yards--as a high volume, relatively short (approximately five mile)--route, is particularly suited to deployment of new technologies such as electric trucks, which ultimately could be deployed by the ports, and then in broader areas as technologies evolve.
- In addition to air quality benefits, utilization of zero-emission technologies could be a significant strategy for reducing greenhouse gas (GHG) emissions. Each port, in cooperation with their respective cities, has initiated a process to quantify, evaluate and implement strategies to reduce GHG emissions from their administrative operations as well as from port-related activities of their tenants and customers.
 - Finally, energy security (i.e. reducing dependence on foreign oil) is also a significant consideration as the ports transition into the future. Uncertainty about potential future supplies of oil and rising costs provide another reason for moving away from technologies that rely on petroleum to technologies that are powered by electricity, ideally produced using renewable energy sources.

Zero-Emission Container Transport Technologies

A variety of zero-emission technologies can be available for deployment early in the life of the proposed Project if the port requires them. The following is a discussion of key technology options.

Zero-Emission Trucks

Zero-emission trucks can be powered by grid electricity stored in a battery, by electricity produced onboard the vehicle through a fuel cell, or by “wayside” electricity from outside sources such as overhead catenary wires, as is currently used for transit buses and heavy mining trucks (discussed below). All technologies eliminate fuel combustion and utilize

electric drive as the means to achieve zero emissions and higher system efficiency compared to conventional fossil fuel combustion technology. Hybrid-electric trucks with all electric range can provide zero emissions in certain corridors and flexibility to travel extended distances (e.g. outside the region) powered from fossil fuels or fuel cells.

Vehicles employing electrified drive trains have seen dramatic growth in the passenger vehicle market in recent years, evidenced by the commercialization of various hybrid-electric cars, and culminating in the sale of all-electric, plug in, and range extended electric vehicles in 2011. A significant number of new electric light-duty vehicles will come on the market in the next few years. The medium- and heavy-duty markets have also shown recent trends toward electric drive technologies in both on-road and off-road applications, leveraging the light-duty market technologies and component supply base. Indeed, the California-funded Hybrid Truck and Bus Voucher Incentive Project (HVIP) website' currently lists more than 75 hybrid-electric on-road trucks and buses available for order from eight manufacturers.

Battery-Electric Trucks

Battery-electric vehicles operate continuously in zero-emissions mode by utilizing electricity from the grid stored on the vehicle in battery packs. Battery-electric technology has been tested, and even commercially deployed for years in other types of heavy-duty vehicles (e.g., shuttle buses). Technologically mature prototypes have recently become available to demonstrate in drayage truck applications. (TIAX, *Technology Status Report - Zero Emission Drayage Trucks*, 1 (June 2011)).

The Port of Los Angeles is testing the Balqon Nautilus XE30 battery-electric truck prototype. Early tests of the Balqon E-30 began in 2008 with a lead-acid battery pack. In subsequent manufacturer tests the truck was equipped with a larger and more advanced lithium-ion battery pack, and the port has stated it will demonstrate this upgraded vehicle commencing in fall of 2011. Manufacturer's tests of the upgraded vehicle have shown a maximum range of between 125 – 150 miles loaded, and dynamometer results indicate ability to climb a 15% grade while fully loaded for two hours. (TIAX, 7). The port demonstration will test performance in actual operations against these and other metrics.

The performance metrics being targeted by the manufacturer would be sufficient to meet the needs of service between near dock rail yards and the APL Terminal. These needs are relatively limited, primarily due to the short distance between the APL Terminal and near dock rail yards: approximately 10 miles round trip. This limits the required number of trucks, as well as their needed range and charging time.

Number of Trucks. Regarding number of trucks needed, at full build out, at least 2,100,000 annual round trip truck trips are anticipated between proposed near dock rail yards and the ports -- an average of 5,753 per day. TIAX assumed that a Balqon truck would make 12 round trips per day, assuming three shifts per day (TIAX, 14). This would total 120 miles per day per truck (within the loaded range estimated by the manufacturer for a single charge), and would indicate a need for 480 trucks to fully serve the rail yards. Adding 8% to account for seasonal variation (TIAX, 9) indicates a need for 518 trucks to serve the near-dock yards. Balqon has estimated that it could produce as many as three trucks per day due to modular truck design, which would enable it to deliver more than 750 trucks per year. This would, in one year and for one manufacturer,

be well in excess of the fleet size needed to serve proposed near-dock railyards.

Charging Time. Regarding charging time, Balqon offers a 60kW charger that would require 4.5 hours for a full charge. Balqon is working on a 100kW charger that would reduce charging time, as well as the number of required chargers and peak electrical demand. (TIAX, 14). In addition, quick charge technologies are now being manufactured, e.g. by AeroVironment which are in use by Foothill Transit electric buses to allow continuous service for a set route. Such technologies could be adapted to allow charging of trucks in much less than one hour. In addition, various charging strategies are available that could further reduce time dedicated to charging. These include battery swapping and “opportunity charging.” (TIAX at 13). Even assuming a 4.5 hour charging time every day, however, would allow 12 round trips to near dock rail yards per day (TIAX at 14; assuming round-trip duration of 1.6 hours. (Id. at 15)).

Implementation Time. TIAX recommends 6 to 12 months of tests in real world drayage operations, followed by an assessment and an additional larger scale demonstration of 12 to 18 months duration. (TIAX, 20-21).

To the extent that in-use performance testing indicates a need for improvements such as greater range or gradability for a battery-electric truck such as Balqon, resolving such technical issues is, in general, a matter of appropriately sizing and engineering key components—notably the battery. A variety of battery sizes are feasible, although there are trade-offs such as weight and cost. The limited range requirements of service to near dock rail yards will, however, minimize the impact of any such trade-offs.

Given these factors, it is expected that battery-electric trucks can be developed and manufactured in sufficient time and quantities to fully serve near dock rail yards by 2016, even if modifications in response to demonstration tests are required.

Costs. As with most new technologies, capital costs are higher for electric-drive trucks compared to conventional diesel trucks. However, operating and maintenance (O&M) costs of electric-drive trucks can be significantly lower, due to higher vehicle fuel economy (reduced fuel costs per energy used) and lower maintenance costs. TIAX calculated a ten-year cost for the Balqon truck, including capital cost of truck, operation and maintenance, at \$363,841 - \$391,233, about \$30,000 - \$60,000 more than the \$335,041 cost for a diesel truck. This differential cost is, however, well within the amount of government incentive funding for relatively clean technologies that has been provided in the past for vehicles such as LNG trucks, and which is currently available (see below). Cost of charging infrastructure would vary greatly based on conventional or quick charging, and charging strategy (e.g. whether battery swapping and opportunity charging occur). TIAX estimated costs of one approach at between \$26.4 and 30.4 million for a fleet of 720 trucks (TIAX, 14) -- well in excess of the number needed to serve near-dock railyards. Again, various government funding programs have been and continue to be available for installation of charging infrastructure.

Since the electric drayage truck is still in its early commercialization phase, the costs are expected to come down as the technology matures, unit volumes increase and economies of scaled production and supply take effect. Balqon estimates that with large scale

purchase commitments and its partnership with Winston Battery Limited, the largest heavy-duty lithium battery manufacturer in China, battery costs will come down to half their current costs.

Operational Issues. The ports have devoted substantial resources to developing and demonstrating electric trucks in part because they would fit well into current operating modes, with minimal or no need for new transportation infrastructure such as roads or new fixed guideway systems. Operational issues thus are expected to be manageable.

It should also be noted that the successful deployment of nearly 900 natural gas drayage trucks since 2008 indicates that the drayage industry can adapt to operational changes and adapt to new fueling procedures and limitations. Most of these natural gas drayage trucks are routinely being refueled at a small number of public stations located near the ports, although some motor carriers are installing onsite natural gas refueling stations. Refueling can take longer than diesel, and during peak times, the waiting time at the limited number of natural gas fueling stations can exceed one hour. Motor carriers have been able to make adjustments to this process. Weight and payload considerations significantly restrict the amount of onboard energy that LNG drayage trucks can carry compared to diesel trucks. However, in a local delivery application such as drayage, LNG trucks can provide plenty of driving range to meet daily operational requirements. In these ways and others, drayage truckers using natural gas rigs have been able to accommodate fuel-related changes in operational requirements. (TIAX, 16).

Implementation Mechanisms. The ports have shown ability to craft programs to transition on-road trucks to new technologies. The successful Clean Trucks Program provides one model of a feasible mechanism to do this for the near-dock railyards related drayage. Through progressive bans of older vehicles and funding and fee mechanisms to provide incentives, the ports succeeded in transitioning from relatively old diesel truck drayage to thousands of new diesel trucks, and nearly 900 LNG trucks. The number of vehicles needed in connection with near-dock railyards is far less. In addition, through approval conditions on the marine terminal project, the lead agency has the ability to ensure cooperative actions by the applicant to assist in the transition.



Figure 1 Balqon Electric Battery Truck

Fuel Cell Battery-Electric Trucks

Fuel cell vehicles utilize an electrochemical reaction of hydrogen and oxygen in fuel cell “stacks” to generate electricity onboard a vehicle to power electric motors. Fuel cells are typically combined with battery packs, potentially with plug-in charging capability, to extend the operating range of a battery-electric vehicle. Because the process is combustion free, there are no emissions of criteria pollutants or CO₂.

Fuel cell vehicles are less commercially mature than battery-electric technologies, but have been successfully deployed in transit bus applications, and are beginning to be deployed in passenger vehicles. The Port of Los Angeles recently awarded Vision Motor Corporation (Vision) of El Segundo, California a contract to outfit fifteen battery electric trucks with fuel cells for demonstration purposes. Total Transportation Services, Inc. (TTSI), a port drayage company, has stated an intent to buy 100 “Tyranos” fuel cell Class 8 trucks from Vision for \$27 million, subject to an initial vehicle (which was delivered on July 22, 2011) performing as expected. TTSI also stated it may acquire an additional 300 vehicles. TTSI intends to test the initial truck for 18 months by using it to haul containers between the ports, rail yards and distribution facilities.

Vision estimates that its fuel cell electric battery trucks would have an operating range of 200 miles on a single charge, with the proposed 20 kg of hydrogen storage and 130 kWh battery pack, while at the same time lowering operating and maintenance costs as compared to diesel-powered trucks. The company’s engineers report the vehicle has a rated gradability of 13% when fully loaded at 80,000 GVWR; this should enable it to meet all grades that will be encountered in short-haul drayage. (TIAX, 7).

TIAX recommends an 18 month demonstration period in drayage operations, followed by an assessment and a further large scale demonstration for 12 to 18 months. (TIAX, 21). Given these factors, it is expected that fuel cell battery-electric trucks can be developed and manufactured in sufficient time and quantities to fully serve near-dock railyards before 2016, even if modifications in response to demonstration tests are required.

The discussions above regarding number of vehicles needed, operational issues and implementation mechanisms are generally applicable to fuel cell trucks, although hydrogen fueling time would be less than Balqon truck charging time, and would be similar to fueling time for current LNG trucks. (TIAX, 17). Per vehicle combined capital and operating costs, as well as fueling infrastructure costs, are projected by TIAX to be higher than for the Balqon truck, although costs could be below the TIAX projections if certain cost reductions expected by Vision are realized, and if cost of fueling infrastructure is recovered through revenue sales. (TIAX, 12, 15). In addition, as noted above, Vision does have a private purchaser with a potential sale of at least 100 units.



Figure 2 Vision Zero-Emission Fuel Cell Battery Electric Truck

Hybrid-Electric with All-Electric Range (AER) Trucks

Hybrid vehicles combine a vehicle's traditional internal combustion engine with an electric motor. Hybrid-electric heavy-duty trucks that improve fuel mileage are in commercial operation today. Hybrid-electric technologies can also be designed to allow all electric propulsion for certain distances, similar to the Chevrolet Volt passenger automobile which is currently being marketed. The large vehicle drive-train manufacturer Meritor has developed such a heavy-duty truck and it is being demonstrated by Walmart Inc. in the Detroit area. This "dual mode" vehicle was developed as part of a U.S. Department of Energy program. Besides the advantages of increased range flexibility, dual-mode hybrid trucks can incorporate smaller battery packs as compared to those for all-battery electric trucks. This saves weight and cost while increasing range.

The Meritor truck is powered solely by battery power (i.e. produces zero emissions) at speeds less than 48 mph. (<http://walmartstores.com/sustainability/9071.aspx>). This speed is likely sufficient to serve proposed near-dock railyards drayage needs. The vehicle can maintain zero-emission operation for 20 miles, sufficient for two round trips to near dock rail yards with zero emissions, but the vehicle could be coupled with plug-in charging capability. The latter would open the potential for 24-hour zero-emission operation using existing quick-charge technologies. Battery capacity could also be augmented in production units, based on specific needs.



Figure 3: Dual-Mode Hybrid (Meritor)

The discussions above regarding number of vehicles needed, operational issues and implementation mechanisms are generally applicable to hybrid AER trucks. Costs for commercially available units are unknown at this time, but would likely be slightly more than conventional hybrids as larger battery packs would be needed for the electric only mode. The incremental cost of a hybrid AER truck compared to a diesel truck is anticipated to be approximately \$50,000-70,000 depending on the capacity of the battery pack. This incremental cost is similar for LNG trucks which were successfully funded through a combination of grants for the Ports' Clean Truck Program (see below).

Since this technology is currently being demonstrated and is similar to hybrid electric technologies that are currently being marketed, it is expected that hybrid AER trucks could be deployed in a similar timeframe as full battery-electric trucks. As with the other zero-emission technologies described here, a key need to ensure timely deployment is a clear message from the ports to technology developers that such technologies will be required.

Trucks With Wayside Power (e.g. "Trolley Trucks")

As noted above, given the relatively short distance between the ports and near dock rail yards, several types of zero-emission trucks can feasibly be made available in coming years. One largely existing technology that could be used to serve this need, as well as move trucks regionwide, is wayside power to power motors and/or charge vehicle batteries. Wayside power from overhead catenary wires is commonly provided to on-road transit buses, and has been used for heavy mining trucks. Other potential wayside power technologies that serve the same purpose include linear induction, which can charge batteries from electromagnetic systems in roadbeds without a physical connection or exposed wires.

An example of how wayside power is feasible would be to outfit a battery-electric or hybrid AER truck with a connection to overhead catenary wires. Many cities operate electric transit buses that drive on streets with overhead wires, as well as streets without them. In such cities, "dual-mode" buses have capability to disconnect from the overhead wire and drive like a conventional bus. In Boston and other cities, such buses are propelled "off wire" by diesel engines. In Rome, such buses are propelled off wire by battery power to the same electric motors used on wire. The batteries are charged as the

bus operates on the wired roadways. Figure 4 shows a dual-mode electric and battery-electric transit bus with detachable catenary connection in Rome, Italy.⁵



Figure 4 Dual-Mode Battery Electric Transit Bus (Rome)

The global technology manufacturer Siemens has developed a prototype truck to catenary wire connection for this purpose. Figure 5 shows a photo of this system on a prototype roadway in Germany. The truck is a hybrid electric with zero emission all electric operation when operated under the overhead wire. The truck automatically senses the wire which allows the driver to raise the pantograph connection while driving at highway speeds. The pantograph automatically retracts when the truck leaves the lane with catenary power. The powered lane can be shared by cars and traditional trucks. The truck may be operated off the powered lane propelled by a diesel engine, or could be configured with battery or fuel cell power sources.



Figure 5 Truck Catenary (Siemens)

As applied to hybrid AER trucks, wayside power could provide zero-emission operation and battery charging on key transport corridors, allowing the vehicle to operate beyond such corridors in zero-emission mode. As the battery is depleted, the vehicle would have the flexibility for extended operation on fossil fuel power.

As existing technologies long used in the transit bus sector, an application of wayside power for trucks would be technologically feasible and could be implemented relatively soon. Siemens retrofitted existing trucks for its prototype road in Germany.

⁵ Other proposals have been evaluated and awarded by the SCAQMD and the CEC to develop catenary trucks and hybrid trucks with AER. Similarly, in 2010, Volvo announced an award by the Swedish Energy Agency to develop a “slide in” technology for both automobiles and trucks which would provide wayside power from the road to the vehicle using a connection from the bottom of the vehicle to a slot in the roadway (<http://www.energimyndigheten.se/en/Press/Press-releases/New-initiatives-in-electrical-vehicles/>).

The key feasibility and cost issues presented by wayside power are associated with need for power infrastructure such as overhead catenary wires. Rights of way must have room for such infrastructure, although they could be limited to key corridors and still provide the battery charging benefits described above. Cost of overhead catenary wires would have to be estimated by corridor as it varies by circumstance, e.g. based on available space, but would likely be from one to a few million dollars per mile. Operational cost benefits due to reduced fuel and maintenance costs for electric technologies would offset a portion of these costs. Based on communications with Siemens and other equipment manufacturers, AQMD technology advancement staff concludes it would be feasible to deploy catenary electric trucks within a few years and early in the life of the near-dock railyards.

Fixed-Guideway Systems

Fixed guideway systems, as the name implies, are mechanisms that move the containers on rails, magnetic levitation tracks, or other fixed structures. An example of a fixed guideway zero-emission container movement system in use today is an electric locomotive pulling a train of containers. Such electric locomotives receive power from overhead catenaries or electric third rails, and are used for freight transport in Europe, Asia and other locations, but not in the United States. Figure 6 shows an electric freight locomotive in Europe.



Figure 6 European Electric Freight Locomotive

The fixed guideway approach would consist of development of infrastructure to move containers between the APL Terminal and the near-dock railyards using magnetic levitation, linear motor technologies, or catenary/third rail power. Unless existing rail lines could be utilized without impeding other operations, the guideways would be purpose-built, which would likely require right-of-way acquisition. Several technology developers have proposed to the ports to use linear motors to propel containers on purpose-built fixed guideway systems, including maglev systems. Under this approach, containers would be loaded onto specialized shuttles conveyed between port terminals and the near-dock railyards. In another variation, electric or diesel trucks would interact with ports and rail terminals as conventional trucks do today, but would be propelled on certain roads by linear synchronous motors in the roadbed. Linear motors propel vehicles using electromagnetic force created by a wire coil embedded in the road.

Light rail train and subway lines have operated for years using linear motor technology, and it is expected that, given sufficient resources, this technology can technologically be adapted for freight movement. The staffs of the two ports have, however, focused their zero-emission technology development and demonstration efforts on truck technologies and, recently, technologies to move line-haul rail. (*See, Roadmap for Moving Forward with Zero Emission Technologies*, presented by port staffs on July 7, 2011 at a joint meeting of the Harbor Commissions of the Ports of Long Beach and Los Angeles). The port staffs have stated concerns about (1) congestion on existing rail lines if they are used to move containers between the ports and near-dock railyards, and (2) about cost and operational feasibility of creating new types of fixed guideway systems. Regarding the latter, the port staffs have cited the results of a "Request for Concepts and Solutions" (RFCS) the ports issued in conjunction with the Alameda Corridor Transportation Authority to design, build, finance and operate a zero emission container movement system (ZECMS). The seven responses to the RFCS included six fixed-guideway systems and one truck-based system (hybrid truck with all electric range).

The responses to the RFCS were reviewed by a panel chosen by the Keston Institute at USC, which determined that none of the proposals demonstrated that the intended ZECMS objectives would be achieved. The Keston panel stated that, prior to selection and deployment of any system, additional testing needs to be carried out in an environment that simulates actual container handling operations. The panel also concluded that a ZECMS would have difficulty competing economically with conventional truck drayage.

It should be noted, however, that the Keston panel did not conclude that zero-emission transport is infeasible, and, indeed, concluded that it is technologically feasible. As the panel stated:

"(T)he panel believes that the submissions illustrate that the concept of a ZECMS is well within the realm of technological feasibility and that potentially viable technologies either already exist or could believably be available within a relatively short timeframe. In other words, a ZECMS is, or could be shortly, technically feasible."

(The panel also noted that the one truck technology proposed—hybrid trucks with all electric range—had achieved the target level of technology readiness for selection and deployment.⁶)

A key issue found by the Keston panel for fixed guideway systems was that the solicitation prohibited any public funding of, or government requirement for, zero-emission technologies, even during the initial development and startup phase. The panel said:

In light of the capital intensive nature of fixed guideway systems and the best case assumptions regarding growth in container volume, market share, capital costs,

⁶ The panel stated: "*Although not strictly a 'zero emission' technology in all operational modes, the panel believes that the hybrid truck has achieved the equivalent of TRL 8. Under the assumption that hybrid trucks would be operating in the electric mode in the port environs, this technology would be viewed as compliant with the goal of removing combustion emissions from port operations.*"

and system availability used in many of the proposers' analyses, the panel believes that, absent other drivers (e.g., environmental regulations or a subsidy provided by the Ports or others), a ZECMS will have difficulty competing economically with conventional truck drayage, particularly given the rapid advances being made in hybrid-electric vehicles and their inherent flexibility and scalability. . . . The RFCS was quite clear that a ZECMS would be in direct competition with the existing system of truck drayage, so that it had to match or improve the total economic value it offered compared to the existing system—the Ports would not provide any subsidy nor would they compel port users to use the ZECMS.

It should be noted, however, that public funding has in the past been considered appropriate to develop and deploy new clean technologies, including by the ports, and such funding is and will likely continue to be available in the future (see below). In addition, the JPA and ports have clear authority, which they have exercised in the past, to require and incentivize use of new technologies.

Rail

In addition to implementing zero-emission technologies such as electric trucks to move containers between the APL Terminal and the near-dock railyards, the measure proposed by SCAQMD would require the ports to take actions to evaluate and demonstrate zero-emission technologies for line-haul locomotives. Zero-emission electric locomotives are an existing technology in use around the world for freight and passenger transport. One issue to be addressed in implementing such technology in Southern California would be the transition to non-electrified track outside of the region. One potential solution is to switch between electric and diesel locomotives at the edge of the region. It should be noted, however, that the railroads have in the past objected to the time, expense and railyard space needed to switch to cleaner locomotives when trains enter this region. A second major issue is the expense of electrification infrastructure such as overhead catenary wires, and the cost of electric locomotives.

Among the technologies to be evaluated under this alternative would be technologies that could eliminate the need for catenary wires, or to switch locomotives at the edge of the electrified region. These include dual-mode locomotives, such as are currently in use for passenger trains; battery tender cars to provide power to locomotives in certain areas; and hybrid-electric locomotives with all electric range. Finally, linear synchronous motor (LSM) technology has the potential to move trains on existing rail lines that are retrofitted with such technology.

Zero Emission Implementation Timeline Overview

A Gantt chart of the likely zero-emission technologies is shown in Figure 7, which illustrates expected timeframes for development, validation and evaluation of technologies. The timeframes are based on status of the specific technologies, and on typical timeframes for the referenced actions. These timeframes are based on proposals received for such technologies as well as technical experience by the Technology

Advancement Office at the SCAQMD. Although each technology provider and manufacturer may describe these phases differently, the cycles are all on the order of five to seven years from development to commercialization. The development phase includes design and non-recurring engineering activities for the prototype technology. This phase also typically includes limited testing or simulation in preparation for field trials. The validation phase is testing and demonstration of the technology in the field, including data collection for design changes and optimization. During this phase, the technology design is tested to the actual performance standards (e.g., towing capability, gradability, speed, etc.). The final fleet evaluation phase includes multiple units in actual fleet or real-world use with potential for accelerated durability testing to gauge maintenance and reliability issues. During this phase, testing is conducted to ensure safety as well as working with the appropriate agencies for commercial certification.

It should be noted that the development phases for many of the truck projects were already initiated in 2008-2009 through efforts at the Ports, the SCAQMD and the DOE. The last phase of “evaluation” includes durability and certification activities, which may lengthen the phase depending on the field-trial experiences. Timeframes could also be shortened if sufficient funding is applied to increase resources toward that effort by the manufacturer. However, considering the current levels of product development and uncertainty, it is clear that, given sufficient clarity of purpose, all described technologies can be commercialized by 2016-2020, with some at earlier dates.




Figure 7: Commercialization Timeframes For Zero Emission Truck Technologies

Financing Support for Zero-Emission Technologies

A key aspect of technology development and commercialization is initiating and ensuring activities by technology manufacturers. Government can play a critical role by ensuring a market for the end product (e.g. by adopting emission control requirements), and by offsetting the typically high cost of technology development and initial deployment through funding incentives. This strategy has been used in Europe for zero-emission technologies, which is why manufacturers are working on zero-emission trucks, namely Siemens and Volvo. State and local governments in California have a long history of

successfully requiring and incentivizing deployment of new technologies. Actions by the ports to require and incentivize clean technologies are thus of critical importance.

As noted above, the ports have implementation mechanisms such as project approval conditions and port rulemaking that can require transition to new technologies. In addition, a variety of sources exist for development and incentive funding. Potential sources of funding for air quality technologies include, but are not limited to, the ports, AQMD, and the future tenant. State and local governments have a long history of incentivizing cleaner technologies through collaborative efforts. A recent example is the partnership with CARB, the Port of Los Angeles, the Port of Long Beach, U.S. Department of Energy, California Energy Commission and U.S. EPA for the buydown of the cleaner but more expensive natural gas trucks as part of the Ports Clean Truck Program. The AQMD utilized the existing Proposition 1B incentive of \$50,000 per truck but augmented this with an additional \$50,000 through grants from the U.S. Department of Energy, California Energy Commission and U.S. EPA as well as AQMD funds and the Ports. With the \$100,000 incentive, fleets and independent operators were able to offset the higher cost of natural gas trucks which are approximately \$150,000 – 170,000. Through this collection of incentives, the AQMD was successfully able to purchase over 690 natural gas trucks as part of the Ports' Clean Truck Program.

Other funding examples include the Hybrid Voucher Incentive Program (HVIP), which provides \$20,000 per hybrid truck, including all-electric technologies. The AQMD further supplemented the HVIP by adding \$1.5M for vehicles deployed in the South Coast Region. In May 2011, the California Energy Commission added an additional \$4M to the HVIP to further incentivize electric vehicles making the per-truck funding \$40,000 to \$50,000. A list of currently available incentives for heavy-duty zero-emission trucks is included in the table below.

Although some of these programs may not be in place at the time of the project initiation, it is anticipated that, given market demand, similar or renewed funding will be available.

Conclusion

Based on the above, there is substantial evidence to conclude that zero emission technologies can be deployed in the 2016 to 2020 timeframe (or earlier) to move containers between the APL Terminal and near-dock railyards — if the port requires such deployment.

| Incentive Program | Sunset Date | Project Category | Current Maximum Potential Funding/Credit Amounts |
|---|------------------------------|------------------|--|
| Carl Moyer Program | 2015 | New Purchase | 25% of Total Purchase Price (Up to Cost-Effectiveness Limit of \$16,640 per ton) |
| | | Repower | \$30,000 per truck |
| Proposition 1B | 2013 | Replacement | \$60,000 per truck |
| | | Repower | \$30,000 per truck |
| HVIP | 2015 | New Purchase | \$25,000 per truck (33 - 38K GVWR) |
| | | | \$30,000 per truck (>38K GVWR) |
| Hybrid and Electric Trucks and Infrastructure Act (S. 1285) | Proposed to end by Dec. 2015 | New Purchase | \$24,000 per truck |

1 **South Coast Air Quality Management District** 2 **(SCAQMD)**

3 **Response to Comment SCAQMD-1**

4 Comment noted.

5 **Response to Comment SCAQMD-2**

6 Comment noted. Please see Response to Comment USEPA-13 for details regarding the APL Terminals on-
7 dock rail capacity and the San Pedro Bay Ports Rail Study. It should be noted that the study, which was
8 based on planned capacity and did not take into consideration market demand or specific company or lease
9 holder (like APL) business needs, estimated 1.24 million TEUs at the Pier 300 on-dock. In contrast, site-
10 and proposed Project-specific information estimated 1.04 million TEUs at the Pier 300 on-dock.

11 **Response to Comment SCAQMD-3**

12 Comment noted. Please see Response to Comment USEPA-17 regarding the Port's Technology
13 Advancement Program (TAP) and use of zero emission technologies. In addition, lease measure LM AQ-1
14 is being revised in the Final EIS/EIR (refer to Chapter 3, Modifications to the Draft EIS/EIR) to reflect a 5-
15 year lease reopener for new technologies (from 7-years).

16 **Response to Comment SCAQMD-4**

17 Comment noted. Responses to the Commenter's Attachment A are made in specific responses (Response to
18 Comments SCAQMD-2 through SCAQMD-21). The response to the Commenter's Attachment B is also
19 provided below (Response to Comment SCAQMD-22).

20 **Response to Comment SCAQMD-5**

21 Comment noted. Cumulative impacts are discussed in Chapter 4 of the Draft EIS/EIR and there is a Port-
22 wide (including both Ports of Los Angeles and Long Beach) effort at working to implement improvements
23 on a Port-wide scale via the CAAP.

24 **Response to Comment SCAQMD-6**

25 Comment noted.

26 **Response to Comment SCAQMD-7**

27 The Commenter suggests that the Draft EIS/EIR should include a future baseline under CEQA for air
28 quality impact analysis. LAHD has followed the same methodology in developing the CEQA baseline on
29 the APL Draft EIS/EIR as it has on all of its EIR documents over the last decade.¹⁴⁻¹⁵⁻¹⁶⁻¹⁷⁻¹⁸⁻¹⁹⁻²⁰ The
30 approach used is consistent with State CEQA Guidelines:

¹⁴ Los Angeles Harbor Department (LAHD). 2003. *Final Supplemental Environmental Impact Report for the West Channel/Cabrillo Marina Phase II Development Project (Cabrillo Way Marina)*. State Clearinghouse No. 98041086.

1 ... In assessing the impact of a proposed project on the environment, the lead agency should
2 normally limit its examination to changes in the existing physical conditions in the affected area as
3 they exist at the time the notice of preparation is published, ... [State CEQA Guidelines, 15126.2
4 (a)]

5 LAHD believes that the analysis, as conducted in the Draft EIS/EIR appropriately characterizes the
6 proposed Project impacts. The LAHD also notes that it has imposed numerous mitigation measures both on
7 the individual Project and on Port-wide activities to reduce environmental impacts of construction and
8 operation activities associated with the proposed Project and with Port-operations as a whole. The LAHD
9 continues to lead U.S. maritime facilities in developing and installing technologies and approaches to
10 reduce of these activities. Where feasible, the LAHD has required acceleration of compliance with
11 regulations that have future compliance dates, and has invested over \$189 million to reduce air pollution in
12 the San Pedro and Wilmington communities through technology advancement projects and emissions
13 reduction programs like the Clean Truck Program, Alternative Maritime Program, Low Sulfur Fuel
14 Switching Program, Vessel Speed Reduction Program, and others. Please also see Responses to Comments
15 USEPA-6 and USEPA-8.

16 One of the statements in the Comment SCAQMD-7 is incorrect. In the last sentence of the first paragraph,
17 the following statement is made:

18 “The lead agency did take this baseline approach when determining significance for cancer and
19 other health risks of the proposed Project, and for consistency, this approach should be used when
20 determining significance for regional criteria emissions.”

21 The statement suggests that a future CEQA baseline was used for the cancer and non-cancer health risk
22 assessment. However, the future baseline concept was only used for the calculation of cancer risk because
23 cancer risk is the only impact that assumes 70-year or 40-year exposure durations²¹ for the effect (cancer)
24 to occur. Due to the uniquely long-range nature of cancer risk impacts, LAHD determined that comparison
25 of those impacts to future CEQA baseline would provide a realistic disclosure of those impacts. LAHD
26 further determined, however, that comparison to a 2008-2009 CEQA baseline adequately discloses relevant
27 information about other health risk impacts that would be experienced more immediately after the Project is
28 implemented. The other health risks (chronic non-cancer and acute non-cancer) were based on the peak
29 annual concentrations and peak hourly concentrations, respectively, which occurred between 2012 and 2027,
30 the proposed Project horizon years. The peak CEQA baseline concentrations (annual and hourly) that
31 occurred during the baseline period (July 2008-June 2009) were subtracted from the future proposed Project
32 concentrations to determine the incremental proposed Project non-cancer risk impacts. This approach is the

15 Los Angeles Harbor Department (LAHD). 2009. *Final Environmental Impact Report for the Wilmington Waterfront Development Project*. State Clearinghouse No. 2008031065.

16 U.S. Army Corps of Engineers (USACE) and Los Angeles Harbor Department (LAHD). 2007. *Final Environmental Impact Statement/Environmental Impact Report for the Berth 136-147 [TraPac] Container Terminal Project*.

17 USACE and LAHD. 2008. *Final Supplemental Environmental Impact Statement/Final Subsequent Environmental Impact Report for the Pacific LA Marine Terminal LLC, Pier 400, Berth 408 Project*. State Clearinghouse No. 1992102975.

18 USACE and LAHD. 2008. *Final Environmental Impact Statement/Environmental Impact Report for the Berth 97-109 [China Shipping] Container Terminal Project*. State Clearinghouse No. 2003061153.

19 USACE and LAHD. 2009. *Final Environmental Impact Statement/Environmental Impact Report for the Port of Los Angeles Channel Deepening Project*. State Clearinghouse No. 1999091029.

20 USACE and LAHD. 2009. *Final Environmental Impact Statement/Environmental Impact Report for the San Pedro Waterfront Project*. State Clearinghouse No. 2005061041.

21 The 70-year exposure period is assumed for residential receptors. Off-site workers are assumed to be exposed for 40 years, and an appropriate 40-year exposure concentration is used for off-site worker receptors.

1 same used for analysis of criteria pollutant impacts, which likewise will be experienced on a more
2 immediate basis than cancer-risk impacts. Therefore, only the cancer risk estimate used a future CEQA
3 baseline approach, which is warranted because the impact being considered is assumed to be associated
4 with very long exposure periods, beyond the build-out year of the Project. This practice is consistent with
5 the approach taken in prior LAHD environmental documents.

6 If the future CEQA baseline approach were to be used as a standard methodology for projects with long-
7 term horizon years, such as the 25-year period for the proposed Project, then that approach should
8 incorporate growth of population, goods movement and traffic into the future baseline where such growth is
9 unrelated to the proposed Project. Such an approach was used in developing the NEPA baseline included in
10 the Draft EIS/EIR, and related impacts have already been disclosed in the document.

11 **Response to Comment SCAQMD-8**

12 The on-dock railyard under the proposed Project and alternatives is not intended to handle all of the
13 containers managed by the APL Terminal. Rather, it is intended to assemble unit trains comprised of
14 containers that would travel to a single destination. Other containers that are destined to other locations are
15 consolidated into unit trains at the near-dock yards. The Response to Comment USEPA-13 provides
16 additional detail regarding the use splits between on-dock and off-dock (including near dock) railyards.
17

18 Regarding the recommended schedule for implementing zero emission drayage trucks, the LAHD intends to
19 utilize a Port-wide approach to implementing zero-emission drayage trucks. In taking a wider approach, the
20 LAHD can consider the relative effectiveness and readiness of zero emission drayage trucks, and how they
21 can be implemented without creating competitive disadvantages between terminals and Ports. Such an
22 approach has the advantage of ensuring that appropriate policies are developed for consistent
23 implementation rather than forcing an early direction in the marketplace that may not be the best solution
24 for the LAHD to support from a Port-wide implementation perspective. The LAHD also notes numerous
25 mitigation measures have been imposed on individual Port projects and on Port-wide activities to reduce
26 environmental impacts of construction and operation activities. The Port continues to lead U.S. maritime
27 facilities in developing and installing technologies and approaches to reduce of these activities. Where
28 feasible the LAHD has required acceleration of compliance with regulations that have future compliance
29 dates, and has invested over \$189 million to reduce air pollution in the San Pedro and Wilmington
30 communities through technology advancement projects and emissions reduction programs like the Clean
31 Truck Program, Alternative Maritime Program, Low Sulfur Fuel Switching Program, Vessel Speed
32 Reduction Program, and others.
33

34 In evaluating zero emission drayage options and implementation, the LAHD must also consider the
35 substantial improvements that the Clean Truck Program and the investment that both ports and private
36 partners have made in upgrading the trucking fleet that serves the two Ports. Over the last several years, the
37 LAHD provided \$44 million in payments to licensed motor carriers in order to incentivize their purchase of
38 2,200 Clean Trucks. Another \$12.5 million was approved for incentive payouts on the purchase of 500
39 natural gas fueled trucks. These incentives, coupled with the effect of the truck ban schedule and associated
40 fees, have led to over \$1 billion in private investment toward the purchase or lease of approximately 7,000
41 more Clean Trucks, making a total of more than 9,800 Clean Trucks currently operating at the Ports of Los
42 Angeles and Long Beach.
43

44 Given that private companies that serve the Ports have recently invested over \$1 billion in upgrading their
45 trucking fleets, time is required for those firms to adequately recoup their investment. The Commenter
46 recommends establishing a schedule for implementing zero-emission drayage trucks as part of the proposed
47 Project; however, the technology is not commercially available at this time, and once the technology is
48 demonstrated as feasible, commercial production and fleet turnover feasibility must also be considered.

1 Although a schedule to implement zero emission drayage trucking may be desirable by the Commenter,
 2 because of the factors above, the LAHD must take a Port-wide approach that considers not just the
 3 demonstration of zero emission technologies, but their commercial feasibility and implementation options
 4 and incentives.

5
 6 However, the LAHD has made policy statements to send clear messages to various market participants that
 7 zero-emissions technologies are indeed needed via the CAAP and the TAP, and continues to reiterate and
 8 support that message. Specifically, the Port's recently adopted 2012 – 2017 Strategic Plan includes an
 9 initiative to increase the number of zero emission trucks in the Port drayage fleet, focusing on trips to and
 10 from rail yards. An action plan to address this initiative will be completed by 2014.

11
 12 The Response to Comments USEPA-17 and USEPA-22 also contains additional information on this subject.

13 **Response to Comment SCAQMD-9**

14 Please see Response to Comments USEPA-9 and USEPA-13. Regarding the comment that Alternative 6 is
 15 inconsistent with the 2008 San Pedro Bay Ports Rail Study Update, the LAHD has since prepared a more
 16 thorough analysis of on-dock rail capacity, throughput projections, and modal mix with the tenant. Those
 17 assumptions for Berths 302-306 are reflected in the throughput assumptions table (Table 2-1) in Draft
 18 EIR/EIS and convey the most current information. It should be noted that the 2008 rail study represented a
 19 snapshot in time, and the current projections utilize for the proposed Project are more representative of
 20 current and future modal mix conditions.

21 **Response to Comment SCAQMD-10**

22 Comment noted. Mitigation measure MM AQ-3 has been revised to remove the exceptions for import
 23 haulers and earth moving equipment (refer to Chapter 3, Modifications to the Draft EIS/EIR). Revised MM
 24 AQ-3 is as follows:

25 **MM AQ-3: Fleet Modernization for On-Road Trucks Used During Construction**

26 1. Trucks hauling material such as debris or any fill material will be fully covered
 27 while operating off Port property.

28 2. Idling will be restricted to a maximum of 5 minutes when not in use.

29 3. USEPA Standards:

30 a. For On-road trucks with a gross vehicle weight rating (GVWR) of at least 19,500
 31 pounds (~~except for Import Haulers and Earth Movers~~): Comply with USEPA 2007
 32 on-road emission standards for PM₁₀ and NO_x (0.01 grams per brake horsepower-
 33 hour (g/bhp-hr) and 1.2 g/bhp-hr or better, respectively).

34 ~~b. For Import Haulers with a GVWR of at least 19,500 pounds used to move dirt and~~
 35 ~~debris to and from the construction site via public roadways: Comply with USEPA~~
 36 ~~2004 on-road emission standards for PM₁₀ and NO_x (0.10 g/bhp-hr and 2.0 g/bhp-hr,~~
 37 ~~respectively).~~

38 ~~e. For Earth Movers with a GVWR of at least 19,500 pounds used to move dirt and~~
 39 ~~debris within the construction site: Comply with USEPA 2004 on-road emission~~
 40 ~~standards for PM₁₀ and NO_x (0.10 g/bhp-hr and 2.0 g/bhp-hr, respectively).~~

1 **Response to Comment SCAQMD-11**

2 The comment is noted. Mitigation measure MM AQ-4 has been revised (refer to Chapter 3, Modifications
3 to the Draft EIS/EIR). Revised MM AQ-4 is as follows:

4 **MM AQ-4: Fleet Modernization for Construction Equipment (except Vessels, Harbor 5 Craft and On-Road Trucks)**

- 6 1. Construction equipment will incorporate, where feasible, emissions-savings
7 technology such as hybrid drives and specific fuel economy standards.
- 8 2. Idling will be restricted to a maximum of 5 minutes when not in use.
- 9 3. Equipment Engine Specifications:
 - 10 a. Tier 4 equipment shall be considered based on availability at the time the
11 construction bid is issued.
 - 12 b. At a minimum, prior to January 1, 2015, All off-road diesel-powered
13 construction equipment greater than 50 hp will meet Tier 3 off-road emission
14 standards at a minimum. In addition, this equipment will be retrofitted with a
15 CARB-verified Level 3 DECS.
 - 16 c. From January 1, 2015 on: All off-road diesel-powered construction equipment
17 greater than 50 hp will meet Tier 4 off-road emission standards at a minimum.

18 **Response to Comment SCAQMD-12**

19 As described in the response to USEPA-4, the APL planned vessel routes to and from the Port is based on
20 their global fleet needs and specific routing and throughput considerations. Although rerouting the newest
21 ships to the Port may seem at first glance to be a viable solution to reduce vessel emissions, this is not
22 feasible. The Port primarily serves as a terminus for APL cargo shipped from other locations. As a result,
23 the ships calling at the Port are smaller than the ships serving ports in several countries, where a vessel will
24 call at multiple ports over a longer period of time before making its return trip. The newest ships in the
25 APL fleet are larger than current ships and are designed to serve markets outside of the United States (refer
26 to Response to Comment USEPA-4 for additional information). It should be noted that APL has already
27 installed slide valves on all APL owned vessels with MAN B&W engines. The slide valves reduced NOx
28 emissions from 2002 – 2011 by almost 29 tons (credit for these reductions have not been taken and
29 therefore, the evaluation in the Draft EIS/EIR is conservative). APL is also testing the effectiveness of
30 other emission reducing technologies (see the Response to Comment USEPA-8) on several vessels, and is
31 implementing various operational measures to further reduce emission.

32 **Response to Comment SCAQMD-13**

33 The Commenter recommends establishing a specific schedule for implementing emission –reducing vessel
34 retrofits through MM AQ-12. One of the primary purposes of MM AQ-12 is to serve as a mechanism to
35 implement vessel retrofit improvements that are demonstrated to be feasible through the TAP. As discussed
36 above, APL has been a leader is testing and installing retrofits designed to reduce emissions, including
37 installation of slide valves that call at the Port. Because the technology evaluations are on-going, and
38 feasibility determination cannot be predicted in advance, no schedule for implementation has been provided,
39 as to do so would be considered speculative. In addition, developing a detailed schedule to perform
40 feasibility studies would similarly be speculative prior to technologies becoming feasible.

1 **Response to Comment SCAQMD-14**

2 The Commenter recommends replacing diesel powered cargo handling equipment at the terminal with
3 electric equipment, and requiring mitigation measures MM AQ-13, MM AQ-14, and MM AQ-15 to include
4 zero-emission component. As discussed in Response to Comments USEPA-17 and SCAQMD-8, zero
5 emission yard equipment is being tested but has not yet been determined to be feasible. Although the three
6 specific mitigation measures do not specifically require zero emission equipment, they are not precluded
7 from requiring such technology if and when they become technologically, operationally and economically
8 feasible.

9 Currently, electric rail mounted gantry (RMG) cranes are in use at the terminal. Also in use at the terminal
10 are diesel powered rubber tire gantry (RTG) cranes; however, it is not feasible to replace these with electric
11 rail mounted gantry cranes due to the need to maintain flexibility at the locations those crane operate.
12 RMG cranes run on rails, which are in a fixed position within the terminal. The acreage that an RMG
13 covers is dedicated to the RMG and not easily converted to alternate methods of container storage, such as
14 storage on chassis. RTG cranes are more versatile since they can gantry from one stacking row to another
15 and can move aside to free up acreage for alternate methods of container storage solutions market
16 conditions fluctuate. In addition, the infrastructure for RTGs is much less expensive since RTGs do not
17 require an external power source such as an electrical grid and rails for RMGs.

18 At the on-dock railyard at Pier 300, the tracks are in a fixed position, making it feasible to run rails parallel
19 to the tracks for the electric RMGs. By contrast, on the container yard, the configuration is not fixed,
20 making RMGs impractical. For this reason, the operational flexibility of being able to switch operations
21 between wheeled chassis and RTGs throughout the container yard was part of the original design criteria for
22 the terminal.
23

24 In addition, EMS has been replacing their existing equipment with cleaner running equipment to comply
25 with state requirements. EMS already has replaced 125 yard tractors at Pier 300 in order to comply with
26 CARB rules. EMS plans to replace 16 top-handlers/side-handlers and 70 additional tractors in the next two
27 years, pursuant to CARB regulations and the proposed mitigation measure identified in the Draft EIS/EIR.

28 The same time-related disadvantages outlined in the discussion of zero emission trucks in Response to
29 Comment USEPA-17 apply to electrical yard tractors. The runtime of 8 hours does not permit the use of
30 one tractor for two connecting shifts. The 4 to 5 hour battery charge time would necessitate purchase of
31 additional yard tractors to maintain the same cargo velocity or operation at a reduced velocity, which would
32 result in a competitive disadvantage compared to other terminals that can stevedore vessels faster, maintain
33 on-time trains schedules, and timely availability of local cargo.

34 Because all of the cargo equipment on the terminal, including yard tractors is undergoing replacement with
35 cleaner equipment meeting state law requirements, all of the equipment has a remaining useful life. As a
36 result, if zero emission equipment were to be required in the near-term, the cost to EMS would equal the
37 entire cost of the equipment, not the differential cost between zero emission equipment and diesel
38 equipment. Purchase of additional yard tractors to use while tractors are recharging would add even more
39 cost.

40 **Response to Comment SCAQMD-15**

41 Although the Commenter may desire early implementation of Tier 4 standards for locomotives in the
42 project area, the USEPA has jurisdiction on the implementation schedule. As a note, the Port does not have
43 control over main line locomotives, which enter the South Coast Air Basin from all parts of the U.S.
44 (although CARB has had some success in reducing locomotive emissions through their MOU with the rail
45 lines). The railroads are a federal source and controlled by federal regulation under the purview of USEPA.
46 The Ports, therefore, defer speeding up implementation of emission controls on main line locomotives to the

1 USEPA. In the meantime, the Port will continue to negotiate with Class 1 railroads to work toward
2 reducing emissions from line-haul locomotives using on-dock rail yards. Based on this, the LAHD
3 respectfully declining the recommendation to implement Tier 4 standards to line haul locomotives at the on-
4 dock railyard.

5 **Response to Comment SCAQMD-16**

6 The Commenter suggests that emission factors for locomotives should be recalculated for future years,
7 based on emission standards rather than USEPA projections. The LAHD used the locomotive emission
8 factors developed by USEPA. These emission factors account for the penetration of various Tier
9 technologies into the market over time. Since the emission standard tiers typically apply to newly
10 manufactured or rebuilt engines, it will be some time before a given tier standard is incorporated into the
11 fleet. The LAHD believes that the USEPA methodology for estimating future locomotive emission factors
12 is appropriate and more conservative. These emission factors have been used in the LAHD's 2009 and
13 2010 Emission Inventories, and in the 2010 CAAP Update.

14 **Response to Comment SCAQMD-17**

15 The comment suggests that the unmitigated emission calculations for ocean going vessels during the
16 construction period (2012-2014) be revised to reflect the higher allowed fuel sulfur content during this
17 period. The LAHD has revised the cargo ship emission calculation to use a fuel sulfur content of 1.0
18 percent, but notes that when the study was initially conducted, the lower limits were anticipated to be in
19 place by 2012. The revised construction emissions are presented in Chapter 3, Modifications to the Draft
20 EIS/EIR, of this Final EIS/EIR. Construction emissions of sulfur dioxide (SO₂) remain less than significant
21 after changing the ship fuel sulfur content to 1.0 percent.

22 **Response to Comment SCAQMD-18**

23 Comment noted. The installation of AMP at Berths 302-305 is planned to occur as a separate but related
24 project (see "Alternative Marine Power" in Table 4-1 in Chapter 4, Cumulative Analysis, of the Draft
25 EIS/EIR), and is included in the cumulative impact discussions in Chapter 4. Because AMP will be
26 installed at Berths 302-305 as a related project regardless if the proposed Project is approved or denied,
27 AMP facilities at Berths 302-305 have "independent utility" compared to the proposed Project. Because of
28 this, AMP at Berths 302-305 and its associated construction emissions are not included in the emission
29 estimates in the Draft EIS/EIR.

30 **Response to Comment SCAQMD-19**

31 All recent LAHD and USACE CEQA/NEPA documents have assessed criteria pollutant impacts both
32 regionally and locally. Regional impacts are assessed by comparing peak daily project emissions to
33 emission thresholds set by the SCAQMD. Local impacts are assessed by performing air dispersion
34 modeling of project emissions and comparing the predicted concentrations to the AAQS set by CARB and
35 USEPA, and ambient concentration thresholds set by the SCAQMD. Because mortality and morbidity
36 effects were considered by these agencies while establishing the standards and thresholds, mortality and
37 morbidity are already implicitly accounted for in CEQA air quality impact analyses by virtue of comparing
38 modeled concentrations against the standards and thresholds set by these regulatory agencies.

39 Recently, various citizens, environmental groups, and regulatory agencies (CARB and OEHHA, among
40 others) have requested that a quantitative analysis of mortality be included in several recent LAHD CEQA
41 documents. In response to their request, and without specific or formal guidance from OEHHA,
42 quantitative mortality analyses were developed and included in the TraPac, China Shipping, and San Pedro
43 Waterfront environmental documents. It should be noted that CARB's mortality methodology was

1 primarily developed for and applied to large populations (statewide and air basins) exposed to relatively
2 high concentrations. Notwithstanding the three mortality evaluations conducted previously, going forward
3 the LAHD does not believe that it is appropriate to apply these methods to project-level analyses with
4 relatively small populations and concentrations significantly lower than those analyzed in the studies CARB
5 used to develop its methodology.

6 For the APL CEQA document, CARB also requested that, for the first time, morbidity effects be quantified.
7 Therefore, the LAHD developed a protocol to describe the approaches and techniques that will be used to
8 develop quantitative mortality and morbidity impact analyses in future LAHD CEQA documents. The
9 protocol provides general descriptions of the overall approach to addressing mortality and morbidity in
10 LAHD CEQA documents, the threshold for quantifying mortality and morbidity impacts, the geographic
11 scope of the analyses, and the references and equations used to calculate mortality and morbidity impacts.
12 The protocol was submitted to CARB, SCAQMD and OEHHA for review and comment. Formal
13 comments were not received from SCAQMD.

14 In general, the threshold was set to be equal to the SCAQMD PM_{2.5} daily concentration threshold for
15 operational impacts, or 2.5 micrograms per cubic meter ($\mu\text{g}/\text{m}^3$). This value is less than one-tenth (1/10) of
16 the current daily national ambient air quality standard (NAAQS), 35 $\mu\text{g}/\text{m}^3$, and is one-sixth (1/6) of the
17 annual NAAQS, 15 $\mu\text{g}/\text{m}^3$, and is approximately one-fifth (1/5) of the state annual ambient air quality
18 standard, 12 $\mu\text{g}/\text{m}^3$. Therefore, it is considered a reasonable threshold for defining the geographic extent
19 mortality and morbidity calculations since this value is lower (more stringent) than any of the standards, and
20 the methods for calculating mortality and morbidity are those previously reviewed by CARB and USEPA to
21 set the PM_{2.5} standards.

22 **Response to Comment SCAQMD-20**

23 The comment recommends clarifying the choice of in-stack NO₂/NO_x ratios used in calculating ambient
24 NO₂ concentration impacts from project sources. A review of the air dispersion modeling input files for all
25 alternatives indicates that the in-stack NO₂/NO_x ratio used for all combustion sources was 0.1. The
26 selection of this value was based on the following:

- 27
- 28 ▪ Ships transiting, maneuvering, and hoteling represent the largest NO_x emission source
29 category. Ship NO_x emissions contribute 55 to 72 percent of the proposed project peak daily
30 total facility NO_x emissions in the unmitigated case (Section 3.2 of the Draft EIS/EIR, pages
31 3.2-94 to 3.2-96). The typical NO₂/NO_x ratio for ships has been reported by USEPA to be
32 0.06.²²
 - 33 ▪ Trucks represent the next largest source category of facility NO_x emissions. Previous studies
34 of heavy duty diesel truck emissions indicate that the NO₂/NO_x ratio could be as low as 0.02,
35 and average values would be less than 0.1.²³⁻²⁴ While several studies suggest that installation
36 of control devices may increase this ratio, the magnitude of this increase varies widely, with

²² U.S Environmental Protection Agency, 2000. *Analysis of Commercial Marine Vessels Emissions and Fuel Consumption Data*, EPA420-R-00-002 (February).

²³ Jimenez, J.L., G.J. McRae, D.D. Nelson, M.S. Zahniser, and C.E. Kolb, 2000. *Remote Sensing of NO and NO₂ Emissions from Heavy-Duty Diesel Trucks Using Tunable Diode Lasers*, Environmental Science and Technology, Vol. 34, No. 12, pp. 2380-2387.

²⁴ Yao, X., N.T. Lau, C.K. Chan, and M. Fang, 2005. *The Use of Tunnel Concentration Profile Data to Determine the Ratio of NO₂/NO_x Directly Emitted From Vehicles*, Atmospheric Chemistry and Physics Discussions, Vol. 5, pp. 12723-12740

1 heavy-duty diesel motor vehicle engine NO₂/NO_x ratios ranging from 0.05 to ~0.50²⁵⁻²⁶
 2 Shortly after the publication of the Draft EIS/EIR, a study was released which examined
 3 emissions, including the NO₂/NO_x ratio, from container trucks leaving the Port of Los
 4 Angeles.²⁷ This study indicated that trucks built before 2008 had NO₂/NO_x ratios around 0.1.
 5 The newer model year trucks (those built between 2008 and 2010) had ratios around 0.2 when
 6 measured in 2009; but after these trucks aged a year, the ratios had dropped to less than 0.15
 7 when measured again in 2010.

- 8 ■ The Localized Significance Threshold (LST) Methodology developed by SCAQMD to
 9 analyze NO₂ concentrations near construction sites indicates that near-field (within 20 meters
 10 of the site) NO₂/NO_x ratios are roughly 0.05.²⁸ This was assumed to be representative of all
 11 offroad equipment, including construction and cargo handling equipment.

12 Taken together, this information led modelers to select an NO₂/NO_x ratio of 0.1 and apply this value as the
 13 default ratio for all combustion sources. The dispersion analysis included in the Draft EIS/EIR provides
 14 reasonable impact estimates of all Project-related air pollutants, including NO₂.

15 **Response to Comment SCAQMD-21**

16 The comment recommends the PM_{2.5} annual ambient air quality standard be used to determine significance
 17 under CEQA rather than the PM_{2.5} Significant Impact Level (SIL) developed by USEPA. The significance
 18 of PM_{2.5} concentration impacts under CEQA were determined solely by comparison to the SCAQMD
 19 significance threshold for 24-hour average PM_{2.5} concentrations. This approach follows the methodology
 20 used in a number of recent LAHD EIS/EIRs, as well as in SCAQMD-produced CEQA EIRs and MNDs.

21 The use of the USEPA-developed SIL was only applied to determine significance under NEPA. The
 22 project area is designated non-attainment for the PM_{2.5} national ambient air quality standards (NAAQS),
 23 and the measured background annual PM_{2.5} concentration was approximately equal to the annual PM_{2.5}
 24 NAAQS (Section 3.2 of the Draft EIS/EIR, Table 3.2-2, page 3.2-10). Therefore, a Project-specific,
 25 appropriate threshold was selected to use which, if exceeded, could contribute to an exceedance of the
 26 standard.

27 **Response to Comment SCAQMD-22**

28 The LAHD appreciates the SCAQMD providing a status of the demonstration projects for zero emission
 29 container hauling technologies, including the fixed guideway systems included in the July 2010 Keston
 30 report on Zero Emission Container Movement Systems. As discussed in the Response to Comments
 31 SCAQMD-8, above, and Response to Comment USEPA-17, in considering implementation of zero
 32 emission container transport options, the LAHD is utilizing a Port-wide approach that considers not only
 33 whether a given technology is expected to prove suitable for container hauling, but also includes the ability
 34 of the technologies to be commercially produced, the ability of fleet businesses to finance higher cost

25 Hesterberg, T.W., .C.A. Lapin, and W.B. Bunn, 2008. *A Comparison of Emissions from Vehicles Fueled with Diesel or Compressed Natural Gas*, Environmental Science and Technology, Vol. 42, No. 17, pp. 6437-6445.

26 Shorter, J.H., S. Herndon, M.S. Zahniser, D.D. Nelson, J. Wormhoudt, K.L. Demerjian and C.E. Kolb, 2005. *Real-Time Measurements of Nitrogen Oxide Emissions from In-Use New York City Transit Buses Using a Chase Vehicle*, Environmental Science and Technology, Vol. 39, No. 20, pp. 7991-8000.

27 Bishop, G.A., B.G. Schuchmann, and D.H. Stedman, 2012. *Emission Changes Resulting from the San Pedro Bay, California Ports Truck Retirement Program*, Environmental Science and Technology, Vol. 46, pp. 551-558.

28 South Coast Air Quality Management District, 2008. *Final Localized Significance Threshold Methodology* (July).

1 vehicles and fleet turnover phasing, available incentive options, and whether or not such requirements can
2 result in competitive disadvantages between terminals or ports.

3
4 Appendix A of the comment letter concludes that zero emission technologies for trucks and rail will be
5 available between 2016 and 2020. This conclusion is based primarily on documents that assess the current
6 commercial availability and technology readiness levels of zero emission technologies. The studies stated
7 that the technologies may be feasible in the future, however noted that no technologies are currently
8 available. The prediction of when any of the technologies may be available is speculative and the timelines
9 outlined in Appendix B of the comment letter represent a best-case scenario and accelerated time frame.
10 Without further in-use and large scale testing, a determination of when a technology will be viable cannot
11 be made with a high level of confidence.

12
13 There are many factors that enter into a program to transition to zero emission container hauling (using
14 either truck or rail), and the majority of these factors are not in a state of readiness for commercial
15 implementation. The availability of financing and the ability of partners to finance new technologies once
16 they are technologically feasible is of critical importance. Because of this, the LAHD does not agree that
17 there is yet substantial evidence to conclude that zero emission technologies can be deployed within the
18 time frames provided. The LAHD also believes that it is not appropriate to immediately require the APL
19 Terminal (or any other container terminal in either Port) to comply with presumed zero emission
20 technologies without the benefit of an overall Port-wide approach to zero emissions technologies.

21
22 In addition, as noted in the Response to Comment USEPA-17, requiring zero emission drayage trucks
23 (assuming they are determined to be technically and commercially feasible) in the absence of a Port-wide
24 program would create a competitive disadvantage for APL, which would render it economically infeasible.
25 However, the LAHD has made policy statements to send clear messages to various market participants that
26 zero-emission technologies are indeed needed via the CAAP and the TAP, and continues to reiterate and
27 support that message. Specifically, the Port's recently adopted 2012 – 2017 Strategic Plan includes an
28 initiative to increase the number of zero emission trucks in the Port drayage fleet or increase the number of
29 zero emission trucks serving existing or future near-dock rail yards. An action plan to address this initiative
30 will be completed by 2014.

31



Department of Toxic Substances Control



Matthew Rodriguez
Secretary for
Environmental Protection

Deborah O. Raphael, Director
5796 Corporate Avenue
Cypress, California 90630

Edmund G. Brown Jr.
Governor

January 17, 2012



Ms. Jan Green Rebstock
City of Los Angeles, Los Angeles Harbor Department
425 S. Palos Verdes Street
San Pedro, California 90731

NOTICE OF AVAILABILITY OF A DRAFT IMPACT STATEMENT/ENVIRONMENTAL IMPACT REPORT FOR THE BERTHS 302 TO 306 AMERICAN PRESIDENT LINES CONTAINER TERMINAL PROJECT, (SCH #2009071031), LOS ANGELES COUNTY

Dear Ms. Rebstock:

The Department of Toxic Substances Control (DTSC) has received your submitted Draft Environmental Statement/ Environmental Impact Report (EIS/EIR) for the above-mentioned project. The following project description is stated in your document: "The proposed Project consists of expansion and redevelopment of the existing American President Lines (APL). The proposed project encompasses approximately 347 acres and includes improvements to the existing 291-acre APL Terminal and an expanded area of 56 acres. The proposed Project would be constructed in two phases. The proposed Project is located at Pier 300 on Terminal Island, within the Port of Los Angeles Community Plan area within the City of Los Angeles which is adjacent to the communities of San Pedro and Wilmington. The APL Terminal site encompasses the majority of Pier 300 within Los Angeles Harbor Department (LAHD) property, and is generally bounded by Terminal Way to the north, Pier 300 Shallow Water Habitat and Sea Plane Lagoon to the east, Earle Street to the west, and the Pier 300 Channel to the south. The proposed Project area is largely surrounded by industrial activities associated with the Port Complex as well as harbor water".

Based on the review of the submitted document DTSC has the following comments:

- 1) The EIS/EIR should evaluate whether conditions within the Project area may pose a threat to human health or the environment. Following are the databases of some of the regulatory agencies:
 - National Priorities List (NPL): A list maintained by the United States Environmental Protection Agency (U.S.EPA).

DTSC-1

- Envirostor (formerly CalSites): A Database primarily used by the California Department of Toxic Substances Control, accessible through DTSC's website (see below).
 - Resource Conservation and Recovery Information System (RCRIS): A database of RCRA facilities that is maintained by U.S. EPA.
 - Comprehensive Environmental Response Compensation and Liability Information System (CERCLIS): A database of CERCLA sites that is maintained by U.S.EPA.
 - Solid Waste Information System (SWIS): A database provided by the California Integrated Waste Management Board which consists of both open as well as closed and inactive solid waste disposal facilities and transfer stations.
 - GeoTracker: A List that is maintained by Regional Water Quality Control Boards.
 - Local Counties and Cities maintain lists for hazardous substances cleanup sites and leaking underground storage tanks.
 - The United States Army Corps of Engineers, 911 Wilshire Boulevard, Los Angeles, California, 90017, (213) 452-3908, maintains a list of Formerly Used Defense Sites (FUDS).
- 2) The EIS/EIR should identify the mechanism to initiate any required investigation and/or remediation for any site within the proposed Project area that may be contaminated, and the government agency to provide appropriate regulatory oversight. If necessary, DTSC would require an oversight agreement in order to review such documents.
- 3) Any environmental investigations, sampling and/or remediation for a site should be conducted under a Workplan approved and overseen by a regulatory agency that has jurisdiction to oversee hazardous substance cleanup. The findings of any investigations, including any Phase I or II Environmental Site Assessment Investigations should be summarized in the document. All sampling results in which hazardous substances were found above regulatory standards should be clearly summarized in a table. All closure, certification or remediation approval reports by regulatory agencies should be included in the EIS/EIR.

DTSC-1
Cont.

DTSC-2

DTSC-3

- 4) If buildings, other structures, asphalt or concrete-paved surface areas are being planned to be demolished, an investigation should also be conducted for the presence of other hazardous chemicals, mercury, and asbestos containing materials (ACMs). If other hazardous chemicals, lead-based paints (LPB) or products, mercury or ACMs are identified, proper precautions should be taken during demolition activities. Additionally, the contaminants should be remediated in compliance with California environmental regulations and policies. **DTSC-4**
- 5) Future project construction may require soil excavation or filling in certain areas. Sampling may be required. If soil is contaminated, it must be properly disposed and not simply placed in another location onsite. Land Disposal Restrictions (LDRs) may be applicable to such soils. Also, if the project proposes to import soil to backfill the areas excavated, sampling should be conducted to ensure that the imported soil is free of contamination. **DTSC-5**
- 6) Human health and the environment of sensitive receptors should be protected during any construction or demolition activities. If necessary, a health risk assessment overseen and approved by the appropriate government agency should be conducted by a qualified health risk assessor to determine if there are, have been, or will be, any releases of hazardous materials that may pose a risk to human health or the environment. **DTSC-6**
- 7) If the site was used for agricultural, livestock or related activities, onsite soils and groundwater might contain pesticides, agricultural chemical, organic waste or other related residue. Proper investigation, and remedial actions, if necessary, should be conducted under the oversight of and approved by a government agency at the site prior to construction of the project. **DTSC-7**
- 8) If it is determined that hazardous wastes are, or will be, generated by the proposed operations, the wastes must be managed in accordance with the California Hazardous Waste Control Law (California Health and Safety Code, Division 20, Chapter 6.5) and the Hazardous Waste Control Regulations (California Code of Regulations, Title 22, Division 4.5). If it is determined that hazardous wastes will be generated, the facility should also obtain a United States Environmental Protection Agency Identification Number by contacting (800) 618-6942. Certain hazardous waste treatment processes or hazardous materials, handling, storage or uses may require authorization from the local Certified Unified Program Agency (CUPA). Information about the requirement for authorization can be obtained by contacting your local CUPA. **DTSC-8**
- 9) DTSC can provide cleanup oversight through an Environmental Oversight Agreement (EOA) for government agencies that are not responsible parties, or a Voluntary Cleanup Agreement (VCA) for private parties. For additional information on the EOA or VCA, please see **DTSC-9**

Ms. Jan Green Rebstock
January 17, 2012
Page 4

www.dtsc.ca.gov/SiteCleanup/Brownfields, or contact Ms. Maryam Tasnif-Abbasi, DTSC's Voluntary Cleanup Coordinator, at (714) 484-5489.

- 10) Also, in future CEQA document, please provide your e-mail address, so DTSC can send you the comments both electronically and by mail.

If you have any questions regarding this letter, please contact Rafiq Ahmed, Project Manager, at rahmed@dtsc.ca.gov, or by phone at (714) 484-5491.

DTSC-10

Sincerely,



Greg Holmes
Unit Chief
Brownfields and Environmental Restoration Program

cc: Governor's Office of Planning and Research
State Clearinghouse
P.O. Box 3044
Sacramento, California 95812-3044
state.clearinghouse@opr.ca.gov.

CEQA Tracking Center
Department of Toxic Substances Control
Office of Environmental Planning and Analysis
P.O. Box 806
Sacramento, California 95812
Attn: Nancy Ritter
nritter@dtsc.ca.gov

CEQA # 3448

California Department of Toxic Substances Control (DTSC)

Response to Comment DTSC-1

Thank you for your review and comment on the Draft EIS/EIR. Section 3.7.2, Groundwater and Soils, and Section 3.8.2, Hazards and Hazardous Materials, of the Draft EIS/EIR provides details on the historic uses of the Project site, as well as a summary of known and potential contamination due to those prior uses. The Commenter listed several databases that could provide information for the EIS/EIR to evaluate whether conditions within the Project area may pose a threat to human health and the environment. Appendix I of the Draft EIS/EIR includes the results of the database search conducted by Environmental Data Resources Inc. (EDR) for the Project site and vicinity. The EDR searched approximately 22 standard and 50 additional environmental records associated with federal, state and local databases, including the National Priority List (NPL), Comprehensive Environmental Response Compensation and Liability Information System (CERCLIS), two Resource Conservation and Recovery Act (RCRA) databases, and the Cortese list (the DTSC compiled list pursuant to Government Code Section 65962.5). The Solid Waste Information System (SWIS) database was consulted in the preparation of the solid waste analysis of Section 3.11, Public Services and Utilities, of the Draft EIS/EIR. In addition, as the Commenter suggested, we have reviewed the Envirostor, GeoTracker, and Formerly Used Defense Sites (FUDS) databases, and no new or additional information was found related to the Project site or vicinity.

The Commenter does not give any indication as to what these additional databases might provide different or beyond the information from the approximately 72 reviewed as part of the EDR. As described in Section 3.7.4.3 of the Draft EIS/EIR, during proposed Project construction, if potentially hazardous materials are found, any remediation would be performed in accordance with applicable federal, state and local laws, regulations, and rules. Furthermore, the following lease measures (in Section 3.7 of the Draft EIS/EIR), LM GW-1 and LM GW-2, would further reduce potential impacts:

LM GW-1: Site Remediation Lease Requirement. Unless otherwise authorized by the lead regulatory agency for any given site, the Tenant (i.e., APL) shall address all contaminated soils within proposed Project boundaries discovered during demolition and grading activities. Contamination existing at the time of discovery shall be the responsibility of the past and/or current property owner. Contamination as a result of the construction process shall be the responsibility of the Tenant and/or Tenant contractors. Remediation shall occur in compliance with local, state, and federal regulations, as described in Section 3.7.3 and Section 3.8.3, and as directed by the lead regulatory agency for the site (such as the Los Angeles RWQCB or DTSC).

Soil removal shall be completed such that remaining contamination levels are below risk-based health screening levels for industrial sites established by OEHHA and/or applicable action levels (e.g., Environmental Screening Levels, Preliminary Remediation Goals) established by the lead regulatory agency with jurisdiction over the site. Soil contamination waivers may be acceptable as a result of encapsulation (i.e., paving) and/or risk-based soil assessments for industrial sites, but are subject to the review of the lead regulatory agency and LAHD. Excavated contaminated soil shall be properly disposed of off-site unless use of such material on-site is beneficial to construction and approved by the agency overseeing environmental concerns. All imported soil to be used as backfill in excavated areas shall be sampled to ensure that it is suitable for use as backfill at an industrial site.

1 **LM GW-2: Contamination Contingency Plan Lease Requirement.** The following contingency
2 plan shall be implemented to address contamination discovered during demolition,
3 grading, and construction.

- 4 a) All trench excavation and filling operations shall be observed for the presence of
5 free petroleum products, chemicals, or contaminated soil. Soil suspected of
6 contamination shall be segregated from other soil. In the event soil suspected of
7 contamination is encountered during construction, the contractor shall notify the
8 LAHD's environmental representative. The LAHD shall confirm the presence of
9 the suspect material and direct the contractor to remove, stockpile or contain, and
10 characterize the suspect material. Continued work at a contaminated site shall
11 require the approval of the LAHD Project Engineer.
- 12 b) Excavation of VOC-impacted soil may require obtaining and complying with a
13 South Coast Air Quality Management District Rule 1166 permit.
- 14 c) The remedial option(s) selected shall be dependent upon a suite of criteria
15 (including but not limited to types of chemical constituents, concentration of the
16 chemicals, health and safety issues, time constraints, cost, etc.) and shall be
17 determined on a site-specific basis. Both off-site and on-site remedial options may
18 be evaluated.
- 19 d) The extent of removal actions shall be determined on a site-specific basis. At a
20 minimum, the impacted area(s) within the boundaries of the construction area shall
21 be remediated to the satisfaction of the LAHD and the lead regulatory agency for
22 the site. The LAHD Project Manager overseeing removal actions shall inform the
23 contractor when the removal action is complete.
- 24 e) Copies of hazardous waste manifests or other documents indicating the amount,
25 nature, and disposition of such materials shall be submitted to the LAHD Project
26 Manager within 60 days of project completion.
- 27 f) In the event that contaminated soil is encountered, all on-site personnel handling or
28 working in the vicinity of the contaminated material must be trained in accordance
29 with USEPA and Occupational Safety and Health and Administration (OSHA)
30 regulations for hazardous waste operations or demonstrate they have completed the
31 appropriate training. Training must provide protective measures and practices to
32 reduce or eliminate hazardous materials/waste hazards at the work place.
- 33 g) When impacted soil must be excavated, air monitoring will be conducted as
34 appropriate for related emissions adjacent to the excavation.
- 35 h) All excavations shall be backfilled with structurally suitable fill material that is free
36 from contamination.

37 **Response to Comment DTSC-2**

38 Sections 3.7 and 3.8 of the Draft EIS/EIR identify the applicable soil and groundwater contamination and
39 hazardous materials regulations associated with the proposed Project. In addition, Section 3.7 of the Draft
40 EIS/EIR includes two lease measures that will be required in the lease to address the mechanisms to initiate
41 remediation and oversight if contamination is present (refer to Response to Comment DTSC-1 above for
42 detailed description of the lease measures). As described in Section 3.7.4.3 of the Draft EIS/EIR, during
43 proposed Project construction, if potentially hazardous materials are found, any remediation would be
44 performed in accordance with applicable federal, state and local laws, regulations, and rules.

1 In addition, lease measure LM GW-1 specifically requires the handling, treatment, and disposal of
2 contaminated material in accordance with oversight agency requirements, including but not limited to the
3 Regional Water Quality Control Board, Department of Toxic Substances Control, and the Office of
4 Environmental Health Hazard Assessment.

5 **Response to Comment DTSC-3**

6 Section 3.7.2.3 of the Draft EIS/EIR summarizes the existing soil and groundwater investigations associated
7 with the Project site and vicinity. In addition, should contamination be discovered during construction,
8 remediation would be performed in accordance with applicable federal, state and local laws, regulations,
9 and rules. In addition, lease measure LM GW-2 would reduce potential impacts (refer to Response to
10 Comments DTSC-1 above for detailed description of the lease measure). It should be noted that an
11 approved workplan, if applicable, is inherent in the remediation requirements contained in the regulations
12 and LM GW-2.

13 **Response to Comment DTSC-4**

14 The proposed Project includes demolition and relocation of the Roadability Facility, as well as the expansion
15 of the existing Power Shop Building. Due to the age of the buildings (both buildings were built in 1995), it
16 is not anticipated that asbestos containing material or lead-based paint were used in their construction.
17 During proposed Project construction, if potentially hazardous materials are found, any remediation would
18 be performed in accordance with applicable federal, state and local laws, regulations, and rules. In addition,
19 lease measure, LM GW-1: Site Remediation Lease Requirement, would further reduce potential impacts
20 (refer to Response to Comment DTSC-1 above for detailed description of the lease measure).

21 **Response to Comment DTSC-5**

22 As detailed in Section 3.7.4.3 of the Draft EIS/EIR, although significant impacts related to the potential for
23 exposure to underlying contaminants would not occur, lease measures LM GW-1 and LM GW-2 would
24 further reduce potential impacts (refer to Response to Comments DTSC-1 above for detailed description of
25 the lease measures).

26 **Response to Comment DTSC-6**

27 As detailed in Section 3.2 of the Draft EIS/EIR, a human health risk assessment (HRA) was prepared by a
28 qualified health risk assessor to address the potential impacts of the proposed Project on sensitive receptors.
29 Please refer to Section 3.2.4.1.3 for the HRA methodology, Section 3.2.4.3, Impact AQ-7 for the detailed
30 HRA analysis (including Figures 3.2-4 through 3.2-11 for residential and occupational cancer risks under
31 CEQA and NEPA baselines for the unmitigated and mitigated Project), and Appendix H3 of the Draft
32 EIS/EIR. In addition, lease measure LM GW-2: Contamination Contingency Plan Lease Requirement
33 (detailed in Section 3.7.4.3 of the Draft EIS/EIR and provided in Response to Comment DTSC-1 above)
34 includes provisions (“f” and “g”) that in the event contaminated soil is encountered, all on-site personnel
35 handling or working in the vicinity of the contaminated material must be trained in accordance with USEPA
36 and OSHA regulations for hazardous waste operations or demonstrate they have completed the appropriate
37 training. Training must provide protective measures and practices to reduce or eliminate hazardous
38 materials/waste hazards at the work place. When impacted soil must be excavated, air monitoring will be
39 conducted as appropriate for related emissions adjacent to the excavation. Comment noted.

1 **Response to Comment DTSC-7**

2 The historical uses of the Project site are included in Section 3.7.2 of the Draft EIS/EIR and do not include
3 agricultural, livestock or related activities or uses.

4 **Response to Comment DTSC-8**

5 As detailed in Section 3.8.1.1 of the Draft EIS/EIR (and specifically in Table 3.8-2), the proposed Project
6 site includes several facilities that contain small amounts of hazardous material and/or hazardous wastes.
7 Section 3.8.1.6 of the Draft EIS/EIR describes in detail the regulations applicable to the proposed Project or
8 alternatives are designed to regulate hazardous materials and hazardous wastes. These regulations also are
9 designed to limit the risk of upset during the use, transport, handling, storage, and disposal of hazardous
10 materials. Regulations described in the Draft EIS/EIR include California Hazardous Waste Control Law
11 (California Health and Safety Code, Division 20, Chapter 6.5), the Hazardous Waste Control Regulations
12 (California Code of Regulations, Title 22, Division 4.5), as well as the requirements associated with the
13 local Certified Unified Program Agency (CUPA).

14 **Response to Comment DTSC-9**

15 Thank you for your comment and information regarding clean-up oversight by DTSC.

16 **Response to Comment DTSC-10**

17 Thank you for your comment. E-mail addresses for submittal of comments on the Draft EIS/EIR to the
18 USACE and LAHD were provided in the public notice enclosed with the CD of the document you received,
19 the Reader's Guide (which was provided on the CD), as well as listed on both the USACE and LAHD
20 websites for the Draft EIS/EIR. Also note that the contact persons and postal mailing addresses for USACE
21 and LAHD are included at the end of Chapter 1 of the Draft EIS/EIR.
22

DEPARTMENT OF TRANSPORTATION
 DISTRICT 7, OFFICE OF REGIONAL PLANNING
 IGR/CEQA BRANCH
 100 MAIN STREET, MS # 16
 LOS ANGELES, CA 90012-3606
 PHONE: (213) 897-9140
 FAX: (213) 897-1337



*Flex your power!
 Be energy efficient!*



February 15, 2012

Ms. Jan Green-Rebstock
 Port of Los Angeles
 425 South Palos Verdes Street
 San Pedro, CA 90733

Re: Berths 302-306 American President Lines
 (APL) Container Terminal Project
 SCH# 2009071031; IGR#111230/CS
 Vic: LA-710/47/103/91/110/405/1-VAR

Dear Ms. Green-Rebstock:

Thank you for including the California Department of Transportation (Caltrans) in the environmental review process for the construction and operation of the Berths 302-306 American President Lines (APL) Container Terminal Project. The proposed project involves expansion and redevelopment of the existing 291-acre APL Terminal to approximately 347 acres to support future cargo throughput demand at the APL Terminal. Based on the information received we have the following comments:

Caltrans does not concur with the traffic report and analysis for the Port of Los Angeles Berths 302-306 Projects. Without major highway and rail improvements, we anticipate that significant project related traffic impacts will occur due to the additional truck trips generated by the APL Berths 302-306 Project, along with the cumulative impacts from all related port projects in the area. The report did not fully analyze the cumulative impacts of all port related projects in the area. When project trips contributes to saturated conditions on a highway, mitigation measures including capacity enhancement and fair-share funding contributions are warranted. Caltrans is available to discuss any mitigation measures and alternatives for necessary improvements to impacted State Highways.

DOT-1

Goods movement related highway studies in the area include the I-710 Corridor Study, the East-West Freight Corridor Study and the SR-91/I-605 Corridor Study. Two major bridge replacement projects in the area include the Gerald Desmond Bridge and the Commodore Schuyler Heim Bridge replacement projects. Freeway ramp projects are also scheduled in the vicinity of the I-110/SR-47 freeway interchange. Fair-share funding contribution may be considered towards these studies and other freight movement related highway projects.

DOT-2

To mitigate the impact of port related truck trips on the State Highway System, Caltrans strongly encourages the development and coordination of the Southern California International Gateway Project (SCIG), a near dock truck/rail intermodal container transfer facility. To minimize the impact of future truck container trips from the ports, projects within the Port of Los Angeles complex will need to contribute funding towards the development and operation of the SCIG Project in order to divert future containers from trucks to rail operations. Development of the SCIG project could

DOT-3

eliminate substantial existing and future truck trips between the ports and BNSF's Hobart Yard. Where feasible, on-dock rail facilities should be constructed to minimize port related truck operations. Diverting container cargo to rail operations could eliminate substantial truck trips throughout the region.

DOT-3
Cont.

Caltrans requests that all traffic analyses for the project be consistent with the Highway Capacity Manual (HCM) methodology And ITE trip generation rates and trip distribution used for the traffic analysis. Caltrans should be consulted in respect to calibration of micro simulation models, queue length analysis of freeway ramps, turn movement storage, geometrics and radii, level-of-service (LOS) calculations using adjusted PCE values, etc. All truck haul routes should be clearly defined in order to determine impacts to State Highway operations.


DOT-4

It is recommended that construction related truck trips on State Highways be limited to off-peak commute periods. The contractor should avoid bunching of truck trips on mainline freeways, on freeway ramps and at freeway ramp intersections. Transport of over-size or over-weight vehicles on State highways will need a Caltrans Transportation Permit.

DOT-5

If you have any questions regarding these comments, you may contact Carl Shiigi, Project Coordinator at (213) 897-1726. Please refer to record number 111230/CS.

Sincerely,



DIANNA WATSON
IGR/CEQA Program Manager
Caltrans, District 7

California Department of Transportation, Caltrans District 7 (DOT)

Response to Comment DOT-1

Comment noted. The APL Draft EIS/EIR addresses potential traffic impacts on the State Highway system (refer to Section 3.6 and Appendix H of the Draft EIS/EIR). The planning level demand-capacity methodology for the mainline freeway system is more appropriate (than the HCM analysis) for analyzing potential project-specific impacts of a development project, and as such is the prescribed methodology contained in METRO's Congestion Management Program Traffic Impact Analysis Guidelines for development project EIRs, and the planning level demand analysis is consistent with other LAHD CEQA and NEPA documents. Caltrans HCM analysis of the operational conditions of highway facilities for transportation projects in the Port area where forecasted growth at Pier 300 is included as cumulative growth are listed below. The Draft EIS/EIR evaluates the traffic impacts of the Project in the context of existing and anticipated future non-Project traffic (including anticipated future non-Project traffic related to the Port), and concludes that there would be no significant project-specific impacts or cumulatively considerable Project contributions to cumulatively significant impacts on adjacent state highways using NEPA methodology (floating baseline), CEQA methodology without cumulative projects and CEQA methodology with cumulative projects. Therefore, capacity enhancement and fair-share funding contributions are not warranted.

The LAHD has conducted numerous operational studies (using the HCM) for the State Highway system in the vicinity of the Port via other environmental impact reports consistent with the Draft EIS/EIR for the proposed Project. Each of these studies account for cumulative estimated future traffic (autos and trucks) growth of the Ports of Los Angeles/Long Beach facilities and other regional growth to the year 2035. The APL Draft EIS/EIR also includes cumulative improvements to the State Highway system that are fully funded in its analysis. The analysis of the impact of Port-related traffic on State Highway facilities has been addressed in several specific studies of the Port area transportation infrastructure, including the I-710 Corridor Project, the Southern California Association of Governments (SCAG) Comprehensive Regional Goods Movement Plan and Implementation Strategy, the Schuler Heim Bridge Replacement and SR 47 Expressway Project, the Gerald Desmond Bridge Replacement, and the I-110 Connectors: I-110 Freeway Ramp & SR 47/I-110 NB Connector Widening. In each case, forecasted growth at Pier 300 (the APL Terminal) was included as cumulative Port-related growth. These studies have identified projects to address cumulative traffic growth from all sources, and to improve traffic operating conditions on the State Highway System.

The LAHD is voluntarily constructing and/or contributing funding for several significant transportation improvement projects on the State Highway System which account for the proposed Project under study in the APL Draft EIS/EIR. These studies and improvements include:

- 1. I-710 Corridor Project:** Although the APL project would not have significant project-specific or cumulative impacts on adjacent freeways nor result in a significant, LAHD is voluntarily collaborating with the State in addressing future traffic conditions on I-710 via volumes via the I-710 Corridor Project EIR/EIS. The LAHD is a funding and technical partner to Caltrans and METRO for the Project Approval/Environmental Documentation (PA/ED) phase. The soon to be released Draft EIS/EIR identifies improvements to the entire 20-mile corridor to accommodate all Year 2035 POLA/POLB and regional traffic. The corridor area includes the mainline freeway and adjacent arterial street system. The I-710 EIS/EIR utilizes HCM methodologies (weaving, mainline, ramp diverge/merge), which is appropriate for a transportation facility environmental document and preliminary engineering. The LAHD

1 contributed \$5 million towards the PA/ED phase and participates directly and extensively by
2 providing technical guidance/input for the: preliminary engineering; Administrative, Draft, and
3 Final EIS/EIRs; and Caltrans Project Report. This input is provided on all technical studies as
4 well, that includes (but is not limited to): air quality, transportation, goods movement,
5 rail/intermodal, and alternative technology. For these studies, the LAHD provided all
6 POLA/POLB traffic volumes for direct incorporation into the I-710 EIS/EIR model (which is a
7 focus model of the SCAG RTP model). These projections are consistent with the Draft
8 EIS/EIR for the proposed Project. The LAHD also worked directly with the consultants and
9 METRO in the development of the port area transportation model, ensuring consistency with
10 the LAHD's transportation model used for transportation analysis in POLA and POLB
11 environmental documents. Additionally, the POLA/POLB jointly conducted several alternative
12 technology (zero emission container movement systems - ZECMS) studies which guided the I-
13 710 EIS/EIR studies, and ultimately led to the recommendation of a separate truckway with
14 zero emission technology.
15

16 If the entire I-710 Corridor project, or components thereof, is ultimately approved for
17 construction, the LAHD may voluntarily contribute funding in the future. This funding would
18 of course be in addition to revenue from tolls on the truck facility and funds from other public
19 sources such as METRO (e.g., Measure R, CMAQ, RTSP, etc.), the State, and/or the federal
20 government. The LAHD is also providing input to METRO's private-public partnership study,
21 which includes tolls as a fund source.
22

- 23 **2. Southern California Association of Governments (SCAG) Comprehensive Regional Goods**
24 **Movement Plan and Implementation Strategy:** Similar to the I-710 EIS/EIR, the LAHD
25 participated directly and extensively in the technical analyses and also was a member of the
26 steering committee which concurred with the East-West Corridor recommendations for
27 incorporation into the 2012 RTP. This proposed new corridor improvement program is still in
28 conceptual phase, in which extensive analysis and preliminary engineering is required even
29 before the environmental document phase can begin.
30
- 31 **3. Schuler Heim Bridge Replacement and SR 47 Expressway Project:** The traffic studies
32 prepared in 2007 for the EIS/EIR for this project were managed by the Alameda Corridor
33 Transportation Authority (ACTA), in conjunction with Caltrans, which was lead agency under
34 CEQA. The ACTA is a Joint Powers Authority of the Cities/Ports of Los Angeles/Long Beach.
35 The LAHD participated directly and extensively in the technical analyses for this EIS/EIR,
36 including providing its transportation model. Traffic micro-simulation modeling and Highway
37 Capacity Manual Operational analyses were done for the EIR/EIS, and approved by Caltrans.
38 These analyses indicated that the planned replacement Heim Bridge and SR 47 Expressway
39 Project can adequately accommodate year 2030 POLA/POLB and non-port (cumulative) traffic
40 volumes, with level of service (LOS) D or better. An analysis was done to isolate the potential
41 contribution of the proposed Project to projected cumulative traffic conditions. Given the
42 projected cumulative LOS D or better as contained in the Heim Bridge EIS/EIR, the proposed
43 Project (APL expansion) would not have an impact. Additionally, a demand-capacity analysis
44 using the APL Draft EIS/EIR for the proposed Project Year 2027 traffic projections, which are
45 in fact now projected to be lower than those contained in the Heim Bridge EIS/EIR, also
46 indicates there would be no impacts (see attached table). Finally, it should be noted that
47 ACTA/POLA/POLB are the funding agencies for the SR 47 Expressway project. The SR 47
48 Expressway project was previously contained in the POLA/POLB Infrastructure Cargo Fee
49 (ICF) program. However, it now has been reprioritized and deferred due to funding constraints
50 and the deferral of the ICF, caused primarily by the recent decline in cargo volume. The
51 decline in cargo volume and slow economic recovery also substantially defers the need for the

1 SR 47 Expressway project. This decision has been confirmed by recent detailed transportation
2 studies.

3
4 **4. Gerald Desmond Bridge Replacement:** The Desmond Bridge Replacement has been
5 designed, and will be, constructed to accommodate all Year 2035 POLA/POLB and regional
6 traffic, including the proposed Project traffic. Moreover, the LAHD collaborated with the
7 POLB and other southern California transportation agencies to obtain about \$500 million in
8 State funds as part of the State Proposition 1B Trade Corridors Improvement Fund (TCIF)
9 program.

10
11 **5. I-110 Connectors: I-110 Freeway Ramp & SR 47/I-110 NB Connector Widening:** This is a
12 LAHD TCIF project that is currently in the final design phase, and will commence construction
13 in mid-2013. This project will eliminate an existing weaving condition of slow uphill moving
14 trucks and fast downhill moving vehicles with the addition of a lane on the westbound to
15 northbound S.R. 47/I-110 connector. This additional lane will continue through the I-110 Off-
16 Ramp at John S. Gibson Boulevard. This project has been designed, and will be constructed to
17 accommodate all Year 2035 POLA/POLB and regional traffic, including the proposed Project
18 traffic.

19 **Response to Comment DOT-2**

20 Please refer to Response to Comment DOT-1, above. The Draft EIS/EIR analysis concludes that the
21 proposed Project would have no significant Project-specific or cumulative considerable impacts on adjacent
22 freeways.

23 **Response to Comment DOT-3**

24 The proposed Project would not make a cumulatively considerable contribution to a significant cumulative
25 impact that could feasibly be mitigated by contributing funding for the SCIG project. The LAHD is the
26 Lead Agency for proposed SCIG Facility EIR and the SCIG project is a separate project that is addressed
27 under Chapter 4, Cumulative Analysis of the APL Draft EIS/EIR (project #17). The LAHD owns the land
28 where the facility would be located. If the SCIG project is constructed, the BNSF railroad would pay for
29 construction and operations/maintenance of the facility. The BNSF would lease land from the LAHD. To
30 yield be conservative traffic results in the APL Draft EIR/EIS, the proposed SCIG project was included in
31 the off-dock international intermodal allocation; and some of the APL terminal off-dock trips were assumed
32 to go to/from the existing ICTF (which occurs today), the BNSF Railway Hobart yard located in the City of
33 Vernon, and the and UP Railroad ELA intermodal yards, located on Washington Boulevard in the cities of
34 Vernon and Commerce, respectively. However, if the SCIG facility were to be approved and constructed, it
35 is anticipated that cargo from the APL facility could use the new near-dock rail facility. Please indicate your
36 support for the SCIG Project by participating in the related environmental process for that project.

37 **Response to Comment DOT-4**

38 Regarding the HCM methodology and associated operational analyses see Response to Comment DOT-1.
39 Also, appropriate PCE values were utilized in the APL Draft EIS/EIRS, along with trucks routes that were
40 coded into the LAHD's transportation model, including all local truck prohibitions. Regarding the use of
41 ITE Trip Generation Manual, the Port's trip generation methodology is considered by the Port's traffic
42 analysts to be vastly more appropriate and valid, as the Port's methodology was developed specifically to
43 address circumstances unique to the Port and the transportation infrastructure that serves the Port. The
44 POLA/POLB terminals are unique trip generators which are not adequately described by ITE trip
45 generation rates. The container terminal truck trip estimates and reductions have been quantified using the

1 POLA/POLB trip generation model, termed “QuickTrip”. This model was developed in 1999 by the
2 LAHD/POLB, and since then, has been used in all POLA/POLB EIRs and all SCAG RTP modeling (and
3 subsequent corridor studies such as the I-710 Corridor and East-West Freight Corridor Study). The
4 QuickTrip model is documented in detail in the Ports of Long Beach and Los Angeles Transportation Study
5 (2001). This methodology allows for the variation of several critical independent operating parameters,
6 such as rail mode split, hours of operation, and dual truck transactions. The QuickTrip model was also
7 recognized by ITE, and received the ITE 2002 “Innovative Intermodal Solutions for Urban Transportation”
8 award. The Port auto trips assumptions were also developed with specialized rates as documented in the
9 Ports Transportation Study and the APL Draft EIS/EIR derived from extensive survey data at Port terminals.
10 Hence, the use of the Port’s methodology has been the accepted practice by the USACE, USEPA, Caltrans,
11 CARB, SCAG, SCAQMD, the City of Los Angeles, and the City of Long Beach for many years. Moreover,
12 the ITE Trip Generation Manual rate derivation yielded a poor statistical correlation ($R^2=0.58$), and only
13 based upon seven studies, none from the POLA or POLB, the largest port complex in the western
14 hemisphere.

15 **Response to Comment DOT-5**

16 Thank you for your comment.
17
18
19

CITY OF LOS ANGELES

CALIFORNIA



ANTONIO R. VILLARAIGOSA
MAYOR

March 14, 2012



DEPARTMENT OF
PUBLIC WORKS

BUREAU OF SANITATION

ENRIQUE C. ZALDIVAR
DIRECTOR

TRACI J. MINAMIDE
CHIEF OPERATING OFFICER

VAROUJ S. ABKIAN
ADEL H. HAGEKHALIL
ALEXANDER E. HELOU
ASSISTANT DIRECTORS

WASTEWATER ENGINEERING SERVICES DIV.
2714 MEDIA CENTER DRIVE
LOS ANGELES, CA 90065
FAX: (323) 342-6210 OR 342-6211

File: SC.CE.

BOARD OF
PUBLIC WORKS

COMMISSIONERS

ANDREA A. ALARCÓN
PRESIDENT

JERILYN LÓPEZ MENDOZA
VICE PRESIDENT

JOHN J. CHOI
PRESIDENT PRO TEMPORE

STEVEN T. NUTTER
COMMISSIONER

VALERIE LYNNE SHAW
COMMISSIONER

Christopher Cannon, Director
Environmental Management Division
LOS ANGELES HARBOR DEPARTMENT
425 South Palos Verdes Street
San Pedro, CA 90731

Theresa Stevens, Ph.D.
Regulatory Division
U.S. ARMY CORPS OF ENGINEERS, LOS ANGELES DISTRICT
2151 Alessandro Drive, Suite 110
Ventura, CA 93001

Dear Mr. Cannon and Mrs. Stevens:

Berths 302-306 [APL] Container Terminal Project – Draft EIR

This is in response to your December 16, 2011 letter received February 17, 2012 requesting a review of your proposed project to improve and expand the existing APL Terminal at the port of Los Angeles. The Bureau of Sanitation has conducted a preliminary evaluation of the potential impacts to the wastewater and stormwater systems for the proposed project.

WASTEWATER REQUIREMENT

The Bureau of Sanitation, Wastewater Engineering Services Division (WESD) is charged with the task of evaluating the local sewer conditions and to determine if available wastewater capacity exists for future developments. The evaluation will determine cumulative sewer impacts and guide the planning process for any future sewer improvements projects needed to provide future capacity as the City grows and develops.

Projected Wastewater Discharges for the Proposed Project:

| Type Description | Average Daily Flow per Type Description (GPD/UNIT) | Proposed No. of Units | Average Daily Flow (GPD) |
|------------------------|--|-----------------------|--------------------------|
| <i>Proposed</i> | | | |
| Office | 150 GPD/1000 SQ.FT | 52,620 SQ.FT | 7,893 |
| Industrial Uses | 80 GPD/1000 SQ.FT | 86,661 SQ.FT | 6,933 |
| Employees | 24 GPD/CAPITA | 2,152 CAPITA | 51,648 |
| Total | | | 66,474 |

BOS1-1



SEWER AVAILABILITY

The sewer infrastructure in the vicinity of the proposed project includes an existing 15-inch line on Earle St. The sewage from the existing 15-inch line feeds into an 18-inch line on Earle St before discharging into the Terminal Way Pumping Plant. According to our existing pumping data, the Terminal Way Pumping Plant appears to have sufficient capacity to handle the proposed flow. Figure 1 shows the details of the sewer system within the vicinity of the project. The current flow level (d/D) in the 15-inch and 18-inch lines cannot be determined at this time without additional gauging.

The current approximate flow level (d/D) and the design capacities at d/D of 50% in the sewer system are as follows:


| Pipe Diameter (in) | Pipe Location | Current Gauging d/D (%) | 50% Design Capacity |
|--------------------|---------------|-------------------------|---------------------|
| 15 | Earle St | * | 1.06 MGD |
| 18 | Earle St | * | 1.41 MGD |

* No gauging available

The estimated flow that would be generated from your proposed project exceeds 20,000 GPD and therefore may have a significant impact on the sewer system capacity. Thus, detailed gauging is necessary to determine whether the sewer system is capable of safely accommodating the total flow for your proposed project. We have initiated a work order to gauge the designated critical locations in the project area. This process usually takes approximately three (3) to four (4) weeks. A detailed evaluation and response will be provided to you within one (1) to two (2) weeks upon receipt of gauging data. If this schedule is not acceptable, please call us to discuss options.

If you have any questions, please call Kwasi Berko of my staff at (323) 342-1562.

Sincerely,



Ali Poosti, Acting Division Manager
Wastewater Engineering Services Division
Bureau of Sanitation

Attachments:

Figure 1 – Sewer Map

cc: Kosta Kaporis, BOS
Daniel Hackney, BOS
Rowena Lau, BOS

CITY OF LOS ANGELES

CALIFORNIA



ANTONIO R. VILLARAIGOSA
MAYOR

March 29, 2012

BOARD OF
PUBLIC WORKS

COMMISSIONERS

ANDREA A. ALARCÓN
PRESIDENT

JERILYN LÓPEZ MENDOZA
VICE PRESIDENT

JOHN J. CHOI
PRESIDENT PRO TEMPORE

STEVEN T. NUTTER
COMMISSIONER

VALERIE LYNNE SHAW
COMMISSIONER

DEPARTMENT OF
PUBLIC WORKS

BUREAU OF SANITATION

ENRIQUE C. ZALDIVAR
DIRECTOR

TRACI J. MINAMIDE
CHIEF OPERATING OFFICER

VAROUJ S. ABKIAN
ADEL H. HAGEKHALIL
ALEXANDER E. HELOU
ASSISTANT DIRECTORS

WASTEWATER ENGINEERING SERVICES DIV.
2714 MEDIA CENTER DRIVE
LOS ANGELES, CA 90085
FAX: (323) 342-6210 OR 342-6211

Christopher Cannon, Director
Environmental Management Division
LOS ANGELES HARBOR DEPARTMENT
425 South Palos Verdes Street
San Pedro, CA 90731

File: SC.CE.

Theresa Stevens, Ph.D.
Regulatory Division
U.S. ARMY CORPS OF ENGINEERS, LOS ANGELES DISTRICT
2151 Alessandro Drive, Suite 110
Ventura, CA 93001

Dear Mr. Cannon and Ms. Stevens:

FINAL RESPONSE: Berths 302-306 [APL] Container Terminal Project – Draft EIR

This is in response to your December 16, 2011 letter received February 17, 2012 requesting a review of your proposed project to improve and expand the existing APL Terminal at the port. The Bureau of Sanitation, Wastewater Engineering Services Division (WESD), has conducted a preliminary evaluation of the potential impacts to the wastewater system for the proposed project.

Projected Wastewater Discharges for the Proposed Project:

| Type Description | Average Daily Flow per Type Description (GPD/UNIT) | Proposed No. of Units | Average Daily Flow (GPD) |
|------------------------|--|-----------------------|--------------------------|
| <i>Proposed</i> | | | |
| Office | 150 GPD/1000 SQ.FT | 52,620 SQ.FT | 7,893 |
| Industrial Uses | 80 GPD/1000 SQ.FT | 86,661 SQ.FT | 6,933 |
| Employees | 24 GPD/CAPITA | 2,152 CAPITA | 51,648 |
| | Total | | 66,474 |

BOS2-1



SEWER AVAILABILITY

The sewer infrastructure in the vicinity of the proposed project includes an existing 15-inch line on Earle St. The sewage from the existing 15-inch line feeds into an 18-inch line on Earle St before discharging into the Terminal Way Pumping Plant. According to our existing pumping data, the Terminal Way Pumping Plant appears to have sufficient capacity to handle the proposed flow. Figure 1 shows the details of the sewer system within the vicinity of the project.

Since our last response on March 14, 2012 detailed gauging data has been obtained. The current approximate flow level (d/D) and the design capacities at d/D of 50% in the sewer system are as follows:


| Pipe Diameter (in) | Pipe Location | Current Gauging d/D (%) | 50% Design Capacity |
|--------------------|---------------|-------------------------|---------------------|
| 15 | Earle St | * | 1.06 MGD |
| 18 | Earle St | 29 | 1.41 MGD |

* No gauging available

Based on the estimated flows, it appears the sewer system might be able to accommodate the total flow for your proposed project. Further detailed gauging and evaluation may be needed as part of the permit process to identify a specific sewer connection point. If the public sewer has insufficient capacity then the developer will be required to build sewer lines to a point in the sewer system with sufficient capacity. A final approval for sewer capacity and connection permit will be made at that time. Ultimately, this sewage flow will be conveyed to the Terminal Island Water Reclamation Plant, which has sufficient capacity for the project.

If you have any questions, please call Kwasi Berko of my staff at (323) 342-1562.

Sincerely,



Ali Poosti, Acting Division Manager
Wastewater Engineering Services Division
Bureau of Sanitation

Attachments:
Figure 1 – Sewer Map

BOS2-1
Cont.



FIGURE 1
Berths 302-306 [APL] Container Terminal Project
Sewer Map

Wastewater Engineering Services Division
 Bureau of Sanitation
 City of Los Angeles



Thomas Brother Data reproduced with permission granted by THOMAS BROS MAP

1 **City of Los Angeles, Bureau of Sanitation, Watershed**
2 **Engineering Services Division – Letter Dated 03/29/12**
3 **(BOS2)**

4 **Response to Comment BOS2-1**

5 Comment noted. Thank you for providing detailed current flow gauging for the sewer infrastructure in the
6 vicinity of the proposed Project. Based on the gauging, it appears that the sewer system might be able to
7 accommodate the total flow from the Project. In the event that during the permit process flow gauging does
8 indicate a d/D equal to or greater than 0.5, the LAHD will coordinate with the Bureau to discuss options
9 (such as specific connection points) for ensuring adequate conveyance exists to serve the Project while
10 maintaining adequate protection from overflows.

Feb. 15, 2012

To:
Los Angeles Harbor Dept
Christopher Cannon
Director, Environmental Management Division
425 South Palos Verdes St
San Pedro, CA 90731



U.S. Army Corps of Engineers, Los Angeles District
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive Suite 110
Ventura, CA 93001

Regarding: Comments on Draft EIES/EIR for the Berths 302-306 (APL) Container Terminal Project

From: Port of Los Angeles Community Advisory Committee's EIR Subcommittee

We thank the agencies for the opportunity to comment on this DEIS/DEIR.

Health Impacts: This Committee has repeatedly called for a Health Impact Assessment (HIA) for all Port related activities. The US E.P.A. and the Los Angeles County Department have also requested that the Port carry out an HIA. To date, POLA has been unable or unwilling to perform this HIA. Once again we call for POLA to perform a HIA, not merely a health risk assessment. We request a Health Impact Assessment for the APL EIR/EIS.

PCAC-1

The Gateway Cities, which include Long Beach, Compton, Paramount, Lynwood, South Gate, Commerce, and multiple other cities along the I-710 Corridor, are at present finishing a Health Impact Assessment in conjunction with the Gateway Cities Air Quality Action Plan. This is being prepared in conjunction with I-710 Corridor Project EIR/EIS. The Gateway Cities AQAP HIA will be peer reviewed by the National Academy of Sciences as this will be a truly groundbreaking and unique study of the broad impacts of a transportation project which has become necessary as a result of growth at the twin Ports of Los Angeles and Long Beach. The HIA is scheduled for release early in the Spring of 2012, with the Peer Review to follow later in the year. A public input session will be conducted by NAS as part of the peer review process.

PCAC-2

We request that the abovementioned HIA and its Peer Review be examined in the context of the APL EIR/EIS to determine if it documents further impacts, especially health impacts that are unrecognized and unmitigated in the EIR/EIS. Further we see it as possible that the HIA and Peer Review will include ideas for mitigation measures that we have not previously considered.

We request that these documents be made a part of the Public Record on the APL EIS/EIR.

These documents may reveal significant off-Port, off the Tidelands impacts of Port related activities. Identification of these impacts would help the Port in its efforts to provide off Port mitigation measures.

PCAC-3

Mitigation Monitoring Reporting Program:

We recommend that the project not go forward until a working Mitigation Monitoring Reporting Program (MMRP) for all POLA projects is in place. The idea has been for decision makers and an apprehensive public to be able to followup on the status of mitigation measures promised in EIRs to determine if they are actually being carried out and what the real world results of these mitigation measures are. We see a functioning MMRP as a benefit both to the Port and to the community.

Many project EIRs have promised a MMRP but to date this has not been accomplished. It is this committee's understanding that Port staff are working on the software to have a working MMRP. We are asking the Port to get this done. After all , many projects promising mitigation monitoring in their EIRs have been done or are in progress. We see the MMRP as a key component of any and all expansion projects at the Port. We wonder why this system is not in place? It has been years since the public was promised the MMRP. We wonder what is causing the delay on this?

PCAC-4

The project should not go forward until the Port demonstrates to the Public that it has a functioning MMRP *for the projects that are already underway or completed*. This should include a periodic easily publicly available report on the status of mitigation measures that have been promised for these projects. For years now we have been hearing that POLA staff is "working on it" and "working on the software" but this "the dog ate my software" sort of excuse is wearing thin.

Recognition:

We appreciate and recognize the Port for the following:

- 1) Requirements applicable to Construction in MM AQ-3 that On-Road truck idling will be restricted to five minutes and in MM AQ-4 that dredging equipment be electric.
- 2) Requirement applicable to Operations in MM AQ-15 that Yard Equipment shall meet an accelerated schedule for USEPA standards compliance and a designated schedule for installation of Verified Diesel Emission Controls.
- 3) Recognition in LM AQ-1 and LM AQ-2 of the significant reduction in impacts that can result from advancing technologies.
- 4) Inclusion of the chronic non-cancer hazard index and acute non-cancer hazard index in the Health Risk Assessment.

PCAC-5

Recommendations

As the Proposed Project would increase criteria pollutants related to air quality and the resulting impacts are defined as significant and unavoidable in the area already considered a Federal non-attainment area for Air Quality, the following revisions are requested to reduce impacts as possible.

Requested Revisions:

Applicable to Construction

- | | |
|--|---------|
| 1) Revise in MM AQ-1, Harborcraft utilization of USEPA Tier 3 engines or cleaner, the exceptions #2 and #3 to clarify that such excepted equipment cannot be utilized until enhanced reduction controls (e.g., particulate trap, catalytic reduction device, etc.) are placed on the uncontrolled equipment. | PCAC-6 |
| 2) Revise MM AQ-3 # 1 to require that trucks hauling any debris or fill material will be fully-covered while operating on and off Port property and # 3 b) and c) to require that Import Haulers and Earth Movers used in construction will be required to comply with EPA 2007 or better on-road emission standards for PM10 and NOx. | PCAC-7 |
| 3) Require in MM AQ-4 that construction equipment incorporate latest emissions-saving technology without qualification for. "if feasible." or define feasibility exclusions and eliminate possibility for exceptions referenced on page 3.2-2 applicable to requirement for trucks' compliance with USEPA standards. | PCAC-8 |
| 4) Revise MM AQ-7 to require that, if a CARB-certified technology with better emission performance than MM AQ-1 through MM AQ-6 becomes available, the tenant/contractor will be required to obtain/implement the better technology within a defined schedule such as within 90 days of availability. | PCAC-9 |
| 5) Require that Off-Road Construction Equipment idling be restricted to maximum of five (5) minutes when not in use without qualification or exception. | PCAC-10 |

Applicable to Operations

- | | |
|--|---------|
| 6) Increase implementation rate for MM AQ-9 Alternative Marine Power to require 80 percent of total ship calls in 2017 and 95 percent by 2020. | PCAC-11 |
| 7) Require incorporation in MM AQ-12 of all available emission reduction technology when using or retrofitting ships bound for the Port of Los Angeles rather than allowing, "the tenant to determine the feasibility of incorporation" of such technology. | PCAC-12 |
| 8) Define specific requirements for implementation of new technologies referenced in LM AQ-1 rather than allowance for, "the tenant shall work with the Port to implement," and/or require implementation of newly identified emissions-reduction technology at a rate of incorporation such as 25 percent within one year of identification, 50 percent within two years, and 100% within five years. | PCAC-13 |

- 9) Require in LM AQ-2 the replacement of existing measure(s) with new technology proven to yield better emissions reduction performance within a defined implementation schedule without allowance for, “the technology could replace the existing measure pending approval by the Port.”

PCAC-14

LAND USE CONCERNS

We note that the bulk of land at POLA is under a “Q” overlay.

Two specific issues exist regarding the examination of land use in the EIR, policy P4 in the circulation element and failure to address methane gas:

Policy P4 in the City of Los Angeles Transportation Element calls for a review of port planning. The on-line version was adopted in 1999 <http://cityplanning.lacity.org/cwd/gnlpln/transelt/index.htm> , but the web page includes a note to check the hard copy for any changes.

Policy P4

Review the policies of current plans such as the Port of Los Angeles 2020 Plan (Pier 300/400 Implementation Program) and the LAX Master Plan and where needed, resolve any inconsistencies with the Citywide General Plan Framework and Transportation Element.

PCAC-15

Schedule

Ongoing

Responsibility:

Departments of City Planning, Transportation, Harbor, Airports and Public Works.

The LAX Master Plan has been studied and revised. Not so the Port of Los Angeles Plan. By law, all general plan amendments must be reviewed by the City Planning Commission. While BHC would no doubt be involved at some level, legal authority is invested in the Planning Commission and City Council. It is noted that for some reason the 2020 plan is viewed here as the Port of Los Angeles Plan when the 2020 Plan is actually a different animal from the Community Plan and addresses only a portion of Port land.

The need for an updated plan is reflected in Transportation Element Policy P4.

We question how this DEIR can determine that the Project conforms to relevant plans when the relevant plan was designed thirty years ago for a planning horizon long since past?

The City of Los Angeles on-line zoning information system (ZIMAS) indicates that the site is in a methane gas area. That didn't seem to be discussed anywhere in the EIR, whether under land use or hazards. (ran an electronic search for "methane".)

Background: The General Plan

Section 65300 of the California Government Code requires all cities in California, including charter cities, to prepare a comprehensive, long-term general plan for the physical development of the city. A general plan has seven mandatory elements, though other optional elements may be added.

While all elements of the general plan have equal status, with no element taking precedence over another, the land use element is often considered the core element of the general plan. The land use element is required to designate the type and extent of various land uses and to include quantifiable standards of land use intensity (Sec. 65302(a)). The specific standard is not defined, but varies with land use. For example residential development is defined in dwelling units per acre or population per acre. Commercial uses are typically defined in terms of floor area ratios, but are sometimes defined in terms of traffic generation. The last intensity standard is important in coordinating the land use element with the circulation element.

The circulation element must identify major thoroughfares and other transportation infrastructure. In accordance with Government Codes Section 65302 (b), the circulation element must be correlated with the land use element. As stated in *Concerned Citizens of Calaveras County v. Board of Supervisors* (1985) 166 Cal.App.3d 90:

“Correlated” means “closely, systematically, or reciprocally related”
[Webster’s Third New International Dictionary (1981) p. 511].

Section 65302 therefore requires that the circulation element of a general plan, including its major thoroughfares, be closely, systematically, and reciprocally related to the land use element of the plan.

In its more concrete and practical application, the correlation requirement in subdivision (b) of [Government Code] §65302 is designed to insure that the circulation element will describe, discuss and set forth “standards” and “proposals” respecting any change in demands on the various roadways or transportation facilities as a result of changes in uses of land contemplated by the plan. (See *Twain Harte Homeowners Assn. v. Tuolumne County* (1982) 138 Cal.App.3d at p. 701 and *Camp v. County of Mendocino* (1981) 123 Cal.App.3d at p. 363.) The statutory correlation requirement is evidently designed in part to prohibit a general plan from calling for unlimited population growth in its land use element, without providing in its circulation element, “proposals” for how the transportation needs of the increased population will be met. . . .

We conclude the [Calaveras County] general plan cannot identify substantial problems that will emerge with its state highway system, further report that no known funding sources are available for improvements necessary to remedy the problems, and achieve statutorily mandated correlation with its land use element (which provides for substantial population increases) simply by stating that the county will solve its problems by asking other agencies of government for money. To sanction such a device would be to provide counties with an abracadabra by which all substance in §65302's correlation requirement would be made to disappear.

Thus, if intensity of use is not defined in a manner adequate to anticipate future traffic generation and transportation demand, one is left with an "abracadabra" approach to meeting future transportation infrastructure needs. Because throughput at the Port is a major determining element for traffic generation, employment generation/housing demand, air emissions and other factors, it would be appropriate to define land use intensities in terms of throughput for planning purposes. In any case, the intensity standard must provide a quantifiable means of correlating land use with infrastructure.

All other elements of the general plan must also be consistent and coordinated (G.C. 65300.5). For example, the noise element must address sound generated along circulation corridors; the housing element must address the need for housing generated by non-residential uses as well as regional growth; and the land use element must provide adequate sites for provision of the identified housing need.

PCAC-17
Cont.

Updates

While the general plan must be stable enough to actually provide long range guidance, with amendments limited to four times per year (GC 65358(c)), the general plan must also be kept current. The housing element must be revised at least every five years (G.C. 65588). No specific schedule has been established for updating other elements of the general plan. However, in accordance with Government Code Section 65040.5 (a), the Governor's Office of Planning and Research must notify a city which has not updated its general plan in eight years that the plan may be out of date. If the plan has not been updated in ten years, the Attorney General must be notified (GC 65040.5(b)).

PCAC-18

Los Angeles General Plan

The Los Angeles General Plan consists of a Framework Element providing general city wide policies to serve as a foundation for the other elements, separate city wide elements addressing state requirements for all areas except land use, and several optional elements. State requirements for the land use element are fulfilled by thirty five community plans

for different areas of the city. The plans are prepared by the City of Los Angeles Planning Department.

Community planning areas in the vicinity of the Port of Los Angeles are San Pedro, Wilmington-Harbor City, and Port of Los Angeles. The Harbor Gateway CPA which consists primarily of the narrow strip connecting the harbor area with the remainder of the city is also considered part of the harbor area for planning purposes.

According to the Community Plans Adoption Status posted by the City of Los Angeles Planning Department, the last comprehensive revision of the San Pedro Community Plan was approved by the Planning Commission August 13, 1998 (CPC 97-0045CPU) and was approved by the City Council March 17, 1999 (CFC 98-1771). The plan is implemented through Zoning Ordinance No. 172547, adopted May 15, 1999. An update is currently underway, though progress has slowed due to budgetary constraints.

The last comprehensive revision of the Wilmington-Harbor City Community Plan was approved by the Planning Commission on July 9, 1998 (CPC 97-0050CPU) and was approved by the City Council July 14, 1999 (CF 98-1619). The plan is implemented through Zoning Ordinance 172853, adopted November 14, 1999.

The last comprehensive revision of the Port of Los Angeles Plan was adopted on September 28, 1982 (CPC 19712/CF 82-400). The City Council subsequently adopted Ordinances 165406 (CF 88-1479; January 1990) (attached) and 165862 (CF-1479; May 1990) (attached), which established a [Q] classification for most of the land within Port boundaries, but does not apply to areas north of Anaheim Street. As stated in Ordinance 165406, the [Q] classification replaces and supersedes land use standards which would normally apply in the M-2 and M-3 Districts. Ordinance 165406 specifically gives the City Planning Commission authority over planning actions at the Port.

Since 1990, City planning actions applicable to the Port have been very limited. The only Port specific action recorded on the City's Zone Information and Map Access System (<http://zimas.lacity.org/>) is Ordinance No. 169960 (CF 93-0168) which was approved in 1994 and applied to the Pier 300/400 area. Remaining ordinances consist primarily of city wide actions such as the addition of footnotes to all Community Plans (CF 90-1422) or incorporation of policies to implement the Mello Act throughout the Coastal Zone (CPC-2005-8252-CA).

Port of Los Angeles Plan

There is currently no planning vehicle which defines intensity of use in the Port of Los Angeles Community Plan Area. This renders it extremely difficult, if not impossible, to coordinate other planning programs with Port activities. This includes other general plan elements and community plans, such as the circulation element, as well as other planning efforts such as the Air Quality Management Plan (AQMP) prepared by the South Coast Air Quality Management District (SCAQMD). As a result various agencies find themselves in a catch up situation, in which, for example, transportation infrastructure is

PCAC-18
Cont.

PCAC-19

overwhelmed and air quality standards are exceeded in the basin, despite ever more stringent controls on non-port uses.

Unfortunately, there is no abracadabra solution to the problems affecting the communities around the Port, including air pollution, traffic congestion, and blight. A comprehensive update of the Port of Los Angeles Plan is well past overdue. An update including the required statements of intensity must be prepared by the City of Los Angeles.

We assert that this project should not be approved until a planning vehicle that defines intensity of use has been made for the Port of Los Angeles Community Planning Area. Additionally an up to date Port Master Plan must be in place.

Thank you again for the opportunity to comment on this DEIR.


John G. Miller, M.D. FACEP

PCAC-19
Cont.

PCAC-20

2.3.4 Organizations

Port of Los Angeles Community Advisory Committee, Past EIR Subcommittee (PCAC)

Response to Comment PCAC-1

Thank you for your comment. Because the Draft EIS/EIR discloses the health-related implications of the Project's environmental impacts, including health risk impacts, of the proposed Project and alternatives; the Draft EIS/EIR is not required to additionally include a separate HIA. Methodologies employed by HIAs may not be able to adequately differentiate health effects from the proposed project versus health effects from many of the other non-project factors that could be considered in an HIA. In addition, it does not appear that an HIA methodology has been reviewed by or approved for use in environmental documents by California Office of Environmental Health Hazards Assessment, as has the HRA methodology used in the Draft EIS/EIR. Nevertheless, the Draft EIS/EIR included a number of health assessment tools to accomplish many of the goals of an HIA. These tools include a full project-specific health risk assessment (HRA), criteria pollutant modeling, morbidity/mortality screening analysis, environmental justice analysis, and socioeconomic analysis. These analyses are presented in the Draft EIS/EIR for the proposed Project and all project alternatives (including the No-Project Alternative and the No-Federal Action Alternative), allowing the reader, and subsequently the Board of Harbor Commissioners and the USACE (the decision-makers), to compare and contrast the benefits and costs among all alternatives.

The Project-specific HRA, as presented in Section 3.2, Air Quality, Meteorology and Greenhouse Gases, and Appendix E3, Health Risk Assessment Technical Memorandum, of the Draft EIS/EIR, examines the cancer risks and the acute and chronic noncancer health risks associated with the proposed Project and all Project alternatives on the local communities. The HRA is based on procedures developed by public health agencies, most notably the California Office of Environmental Health Hazards Assessment (OEHHA).

The Draft EIS/EIR also includes a screening level particulate matter mortality analysis that assesses the incidence (as opposed to risk) of premature death that could occur as a result of the proposed Project and alternatives. The analysis is based on guidance developed with California Air Resources Board (CARB) input.

Furthermore, as part of the development of the 2010 CAAP Update, the Ports of Los Angeles and Long Beach completed a Port-wide HRA. This Port-wide HRA covered both ports and included a quantitative estimate of health risk impacts from diesel particulate matter (DPM) emissions of the Ports' overall existing and planned operations.

Response to Comment PCAC-2

Thank you for your comment. The LAHD would review the health impact assessment associated with the Gateway Cities Air Quality Action Plan and I-710 Corridor Project EIS/EIR, which are efforts and projects separate from the proposed Project. Although APL traffic could utilize I-701, the APL project would be a related but separate project to the I-710 project, as they both have independent utility and logical termini.

Response to Comment PCAC-3

The Commenter's request has been noted. As the requested documents (associated with Response to Comment PCAC-2 above) are not finalized and therefore are not available to be used in the Final EIS/EIR for the proposed Project, these documents would not be made a part of the proposed Projects administrative record.

1 **Response to Comment PCAC-4**

2 Thank you for your comment. Assembly Bill 3180 (AB 3180) codified in Section 21081.6 of the California
3 Public Resources Code, became effective January 1, 1989, and requires a Lead or Responsible Agency to
4 adopt a mitigation monitoring and reporting program (MMRP) when approving or carrying out a project.
5 The purpose of this program is to ensure that when an environmental document, either an EIR or a negative
6 declaration, identifies measures to reduce potential adverse environmental impacts to less than-significant
7 levels that those measures are implemented as detailed in the environmental document. As lead agency for
8 the proposed Project, and pursuant to AB 3180, LAHD is responsible for implementation of this MMRP.

9 An EIR²⁹ has been prepared for the proposed Project that addresses the potential environmental impacts,
10 and where appropriate, recommends measures to mitigate these impacts. As such, an MMRP is required to
11 ensure that adopted mitigation measures are successfully implemented and a monitoring strategy was
12 prepared for each mitigation measure identified in the Draft EIS/EIR for the proposed Project. As part of
13 the decision-making process, the Board of Harbor Commissioners would adopt the MMRP, and the
14 applicable LAHD division(s) will incorporate the mitigation monitoring/reporting requirements in the
15 appropriate permits (i.e., engineering specifications, engineering construction permits, real estate
16 entitlements, and/or coastal development permits). Therefore, in accordance with the aforementioned
17 requirements, this Final EIR lists each mitigation measure, describes the methods for implementation and
18 verification, and identifies the responsible party or parties as detailed below in the MMRP Implementation
19 section. The preparation and adoption of MMRPs are completed for Port projects on a project by project
20 basis, as applicable. Compliance tracking for projects performed within the Port and LAHD's jurisdiction
21 is currently being performed by designated LAHD staff. It should be noted that all LAHD EIRs approved
22 since AB 3180 have included MMRPs and project-specific MMRPs can be found on the LAHD's public
23 website for projects approved since 2003.

24 **Response to Comment PCAC-5**

25 Thank you for your comment.

26 **Response to Comment PCAC-6**

27 Please see Response to Comment USEPA-25. Regarding the recommendation to change mitigation
28 measure MM AQ-1, the comment is noted. As LAHD's Sustainable Construction Guidelines requires
29 construction contractors working within its jurisdiction to use the cleanest feasible construction equipment.
30 The mitigation measure MM AQ-1 is in compliance with the Sustainable Construction Guidelines measures
31 and appropriate as written for the proposed Project.

32 **Response to Comment PCAC-7**

33 Regarding the recommendation to change mitigation measure MM AQ-3, the comment is noted. Please see
34 the Response to Comment SCAQMD-10. The mitigation measure MM AQ-3 is in compliance with
35 LAHD's Sustainable Construction Guidelines measures and appropriate as written for the proposed Project.
36 In addition, mitigation applied to the proposed Project, such as MM AQ-3, is consistent with the LAHD's
37 Sustainable Construction.

²⁹ The proposed Project is part of a joint EIS/EIR

1 **Response to Comment PCAC-8**

2 Regarding the recommendation to change mitigation measure MM AQ-4, the comment is noted. In
3 addition, mitigation measure MM AQ-4 has been modified in response to an SCAQMD comment (please
4 see the Response to Comment SCAQMD-11). The mitigation measure MM AQ-4 is in compliance with
5 Sustainable Construction Guidelines measures and appropriate as written for the proposed Project.

6 **Response to Comment PCAC-9**

7 Regarding the recommendation to change mitigation measure MM AQ-7, the comment is noted. Because
8 LAHD enters into contracts with contractors, it cannot establish more stringent equipment requirements on
9 the contractor.

10 **Response to Comment PCAC-10**

11 Regarding the recommendation to change off-road construction equipment idling to maximum of 5 minutes,
12 the comment is noted. Mitigation measure MM AQ-4 includes an idling restriction of a maximum of 5
13 minutes that would be applied to off-road construction equipment being used at the Project site during
14 construction. In addition, please see the Response to Comment USEPA-18.

15 **Response to Comment PCAC-11**

16 Regarding the recommendation to change mitigation measure MM AQ-9, the comment is noted. The
17 mitigation measure MM AQ-9 is in compliance with CAAP measures and appropriate as written
18 considering the worldwide APL fleet and vessels anticipated under the proposed Project. Please also see
19 Response to Comment USEPA- 4.

20 **Response to Comment PCAC-12**

21 Regarding the recommendation to change mitigation measure MM AQ-12, the comment is noted. As it
22 relates to the OGV mitigation measures associated with the proposed Project (MM AQ-11 and MM AQ-12),
23 the Draft EIS/EIR analysis assumes compliance with the CAAP. In fact, proposed Project-specific
24 mitigation measures applied to reduce air emissions and public health impacts are consistent with, and in
25 some cases exceed, the emission-reduction strategies of the CAAP. The Draft EIS/EIR also includes lease
26 measures prescribed for the proposed Project or alternative that provides a means for additional measures to
27 be incorporated into the applicant's/tenant's lease should the CAAP be strengthened or new technology be
28 feasible in the future. In addition, please see the Response to Comments USEPA-4, USEPA-8, and
29 SCAQMD-13.

30 **Response to Comment PCAC-13**

31 Regarding the recommendation to change lease measure LM AQ-1, the comment is noted. LAHD's
32 approach to facilitate the demonstrations, development and implementation of new emission-reduction
33 technologies is to utilize a Port-wide strategy rather than a terminal-by-terminal approach. A Port-wide
34 approach allows such technologies to be demonstrated, developed, and implemented uniformly without
35 creating competitive disadvantages between terminals and Ports, as well as in a more coordinated manner.
36 Refer to Response to Comments USEPA-3 and USEPA-17 for additional discussion to LM AQ-1 and a
37 Port-wide strategy to future technologies to reduce air emissions. Regardless, as a company APL is a leader
38 in participating in the piloting of new technologies and is a welcome partner for the LAHD in addressing
39 future technologies (refer to Response to Comment USEPA-8 for details on commitments made by APL to
40 reduce air emissions). In addition, LM AQ-1 is structured to provide greater implementation flexibility than

1 the Commenter's suggested revisions, as timing and implementation under existing language can be added
2 once the specific technology has been identified. In addition, please see the Response to Comment
3 SCAQMD-8.

4 **Response to Comment PCAC-14**

5 Comment note. Please refer to Response to Comment PCAC-13 above.

6 **Response to Comment PCAC-15**

7 Comment noted. The proposed Project conforms to all approved land use plans. The Port of Los Angeles
8 Plan, a land use element of the City's General Plan, is the land use element that is intended to serve as the
9 official 20-year guide for the continued development and operation of the Port (City of Los Angeles, 1982
10 plus amendments). Both the Port of Los Angeles Plan and Transportation Element are under the City of
11 Los Angeles Department of City Planning domain, and the update of those plans are not within the
12 jurisdiction of the LAHD. Regardless, the LAHD Port Master Plan (PMP) is consistent with the Port of Los
13 Angeles Plan and the proposed Project is consistent with the PMP. The LAHD will be preparing a
14 comprehensive Port Master Plan Update to the original PMP certified by the California Coastal
15 Commission in April 1980. Since that date, the Coastal Commission has certified 22 amendments to the
16 PMP, addressing land use changes and new projects and landfills. Thus, the PMP is considered current.
17 While the amendments addressed changes relating to specific projects, a comprehensive review and update
18 of the PMP is being completed. This effort is a work in progress and a completion date has not been set,
19 however, the PMP update is not expected to change the overall zoning of the proposed Project area or
20 general land use mix within the Port as such use is defined by California's Coastal Act as described in
21 Chapter 1 of the Draft EIS/EIR.

22 **Response to Comment PCAC-16**

23 The Commenter is correct. Per ZIMAS, areas identified by the City of Los Angeles to be a methane buffer
24 zone have a risk of methane intrusion emanating from geologic formations. However, for such areas, the
25 City has established regulations that require compliance through the Building Code. Requirements, if
26 applicable, could include ventilation and methane gas detection systems depending on designation category.
27 Section 91.7101 of the Building Code set forth the methane buffer zone requirements within the City of Los
28 Angeles. New structures located within a methane buffer zone may have to comply with the Code's
29 methane mitigation standards, depending on site specific conditions. Per the Code, buildings located in the
30 methane buffer zone are not required to provide a methane mitigation system, if the Design Methane
31 Pressure is less than or equal to two inches of water pressure and is either of the following:

- 32
- 33 A. Areas which qualify as Site Design Level I or II; or
 - 34
 - 35 B. Areas which qualify as Site Design Level III and the utilities are installed with Trench Dams and
 - 36 Cable or Conduit Seal Fitting.
 - 37

38 As part of the design process, the applicability of methane mitigation standards will be evaluated and if
39 applicable, the relevant methane mitigation standards will be applied, as required by the Building Code.

40 **Response to Comment PCAC-17**

41 The comment is noted and has been incorporated into the Final EIS/EIR for review and consideration by the
42 decision-makers prior to any action on the proposed Project. It should be noted that land use intensities
43 throughout the City are based on zoning designations, not throughput. The proposed Project would be

1 consistent with the land use designations of the Project site. In addition, throughput projections for the APL
2 Terminal are conservative, and therefore, the traffic analysis and other analyses in the Draft EIS/EIR are
3 also considered conservative.

4 **Response to Comment PCAC-18**

5 The comment is noted and has been incorporated into the Final EIS/EIR for review and consideration by the
6 decision-makers prior to any action on the proposed Project. In addition, please see the Response to
7 Comment PCAC-15.

8 **Response to Comment PCAC-19**

9 The comment is noted and has been incorporated into the Final EIS/EIR for review and consideration by the
10 decision-makers prior to any action on the proposed Project. Refer to Response to Comment PCAC-15
11 regarding a planned comprehensive update to the PMP.

12 **Response to Comment PCAC-20**

13 The comment is noted and has been incorporated into the Final EIS/EIR for review and consideration by the
14 decision-makers prior to any action on the proposed Project. As detailed in Section 3.9.4.3 of the Draft
15 EIS/EIR and discussed in Response to Comment PCAC-15, the proposed Project would be consistent with
16 the site zoning and generalized land use designations in the Port of Los Angeles Plan. In addition, the
17 proposed Project would be consistent with the PMP's designated land uses for Area 9, and by
18 accommodating the high priority for water-dependent uses. Thus, the proposed Project would be consistent
19 with the overall intent of the PMP. In addition, the general uses of the Port are governed by the California
20 Coastal Act. The proposed Project, therefore, would not result in significant impacts because it would be
21 consistent with current site zoning and land use designations of applicable plans.

22

Coalition For A Safe Environment

P.O. Box 1918, Wilmington, California 90748
wilmingtoncoalition @ prodigy.net 310-834-1128

February 17, 2012

U.S. Army Corps of Engineers
Los Angeles District Regulatory Division
Attn: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Ste. 110
Ventura, CA 93731
theresa.stevens@usace.army.mil
805-585-2146
Public Affairs Office
213-452-3920



Port of Los Angeles (POLA)
Los Angeles Harbor Department
Christopher Cannon, Director
Environmental Management Division
425 S. Palos Verde St., San Pedro, CA 90733-0151
ccannon@portla.org
310-732-3675 Office
310-547-4643 Fax
ceqacomment@portla.org
Jan Green-Rebstock,
Environmental Project Manager
jgreenrebstock@portla.org
310-732-3949

Re: Berths 302-306 American President's Line (APL) Container Terminal Project
Draft Environmental Impact Statement (DEIS)/Draft Environmental Impact Report (DEIR)
SPL-2009-00226-TS
SCH No. 2009071021
ADP No. 081203-131

Su: Public Comments Regarding Significant Deficiencies & Unacceptability of DEIS/DEIR

The Coalition For A Safe Environment (CFASE) wishes to request the U.S. Army Corps of Engineers and Port of Los Angeles Board of Harbor Commissioners (POLABOHC) direct its management and staff to completely rewrite the DEIR or Rescind the DEIR and BNSF SCIG Project application do to significant deficiencies, errors, omissions of information, inadequate assessments, missing required assessments, misrepresentations of facts, unsubstantiated information, invalidated data, missing assessments, inappropriate assumptions, fails to eliminate where feasible all negative impacts, fails to mitigate negative impacts where feasible to less than significant and fails to include all reasonable and available feasible mitigation measures, discriminates against Environmental Justice Communities composed of people of color, high poverty and low income.

CFASE-1

The following information, data, points, concerns, references, examples, issues, recommendations and requests describe the deficiencies and inadequacies of the DEIS/DEIR:

0. **CFASE resents the fact the Port of Los Angeles intentionally and with malice intent to suppress and obstruct public participation and public comments password protected the DEIS/DEIR.**

The Port of Los Angeles in past EIS/EIR's has never password protected documents, by doing so CFASE and member of the public are unable to copy sections, paragraphs, tables, diagrams, illustrations, information etc. and include them in our public comments. This prevents the U.S. Army Corps of Engineers, Board of Harbor Commissioners, Regulatory Agencies, Decision Makers and members of the public from being able to read public comments in a more clear context DEIS/DEIR omissions, misrepresentations, discrepancies and errors. The time to retype or recopy information is significant and limits CFASE and members of the public from being able to fully comment and engage in the legally protected public participation process.

CFASE-2

CFASE Requests: The U.S. Army Corps of Engineers and the Port of Los Angeles a public agency cease and desist this practice and provide all CEQA/NEPA required documents in a unlocked, unpassword protected PDF and Microsoft Word document format. There is an extra cost to CFASE and members of the public to purchase special PDF software, pay for regular future upgrades and its is more difficult to copy and paste PDF documents and information than the standard word processing Microsoft Word program. It is also a fact that the original document is typed by the Port of Los Angeles and its consultants in Word and then converted to a PDF.

1. **Chapter ES.2.1 CEQA Introduction. References "section 15121(a) of the CEQA Guidelines," but fails to disclose state that the DEIS/DEIR does not comply with this reference.**

- a. All significant environmental impacts of the project were not disclosed.
- b. All sources of all related environmental impacts information was not identified
- c. All sources of all related environmental impacts information was not fully assessed.
- d. All possible ways to minimize the significant effects were not disclosed.
- e. Disclosed ways to minimize the significant effects were not included or dismissed.

CFASE Requests: The DEIS/DEIS:

CFASE-3

- a. Identify, disclose and include all Port known and public identified impacts, sources of impacts, source impact assessment and available mitigation.
- b. Where no assessment exists that the Port hire an independent third party to conduct an assessment and include it in the DEIS/DEIR.
- c. That all potential and alternative mitigation that has been currently been proven to be feasible and cost-effective or will be proven feasible and cost-effective in the next 12 months be required and included in the DEIS/DEIR.

2. **Chapter ES.2.3 – CEQA Purpose. States the project purposes and objectives but fails to disclose state that the DEIS/DEIR does not entirely comply with the stated purposes and objectives, because it has only included items Port staff prefers, not necessarily those which are the best, most efficient or most optimal which are also feasible and cost-effective.**

The DEIS/DEIR fails to disclose that:

- a. The most efficient and optimal way to unload and transport containers that will go to near dock railyards and non-near railyards is to have on-dock rail built dockside to ships. The DEIS/DEIR proposes to use outdated, inefficient logistics methods which will require the majority of containers to be dropped to the ground, picked-up and relocated one or two times to one or more backlands staging areas.
- b. The most efficient and optimal way to accommodate increased container throughput is to eliminate and significantly reduce travel time, idling time, cue time and staging time by having on-dock rail built dockside to ships and incorporating more efficient and faster freight transportation systems such as the American MagLev technology, Inc. Zero Emissions - Environmental Mitigation & Mobility Initiative "EMMI" MagLev Train.

CFASE-4

- c. Invest in demonstration projects for more efficient container unloading, staging and transferring systems such as the Green Rail Intelligent Development (GRID) - ON-DOCK Ship-to-Rail interface platform called "SuperDock" powered exclusively by electrification.
- d. Invest in demonstration projects for more efficient and optimal terminal designs such as unloading containers using a U-Shape Terminal Dock Design where containers can be unloaded and loaded from both sides of a ship at the same time vs the outdated technology currently being used. This design concept was previously proposed to the Port of Los Angeles for the China Shipping Terminal and unfortunately not considered.

CFASE Requests: The DEIS/DEIS: Include information and assessments of the best, most efficient or most optimal which are also feasible and cost-effective.

3. **Chapter ES.2.4 – USACE Purpose and Need.** States that the purpose of the proposed project is to "optimize the cargo-handling efficiencies and capacity," but fails to disclose that the DEIS/DEIR does not entirely comply with the stated purposes, because it has only included items Port staff prefers, not necessarily those which are the best, most efficient or most optimal which are also feasible and cost-effective and that POLA and the USACE have conducted no studies or comprehensive assessments of cargo-handling efficiencies.

The Port of Los Angeles and the USACE have conducted no comprehensive assessments of optimal cargo-handling technologies even though many have been presented to the POLA by their perspective manufacturers, have been recommended during public comments by both governmental agencies and the public, are known to exist and a simple internet search would disclose many others.

There is no emergency or urgency to build another out-dated inefficient 20th century technology terminal at this time, when new state-of-the-art 21st century alternative and zero-emission technologies have been validated, are currently undergoing validation or can be demonstrated within 1-3 years to achieve all desired purposes and objectives.

The POLA will not achieve a domestic or international leadership role in "economic growth in maritime trade," when it is using outdated 20th century technologies.

CFASE Requests: The DEIS/DEIR: Include information and assessments of the best, most efficient technologies which "optimize the cargo-handling efficiencies and capacity," and which are also feasible and cost-effective. The DEIS/DEIR include and require investment and/or demonstration of optimal cargo-handling technologies which have been proposed.

4. **Chapter ES.4.2 – Alternatives Considered.** The DEIS/DEIR included discussion on 6 alternatives but failed to consider and equally assess viable public and manufacturer recommended alternatives.

The DEIS/DEIR inadequately describes the feasibility and cost effectiveness of Alternative Technologies discussed in 2.8.2.11 Alternative Container Transport Systems. The DEIS/DEIS failed to disclose that there are in fact two Zero Emissions MagLev Train Technologies that already have on-site operating test demonstration tracks and that the only reason one has not been demonstrated at the POLA is POLA's and the Port of Long Beach's (POLB) refusal to allow them to conduct a demonstration project at an on-port site terminal location or off-port property location.

The DEIS/DEIR failed to disclose that both POLA and POLB Board of Harbor Commissioners, Regulatory Agencies and port staff have traveled to these locations and witnessed the successful on-site MagLev Train Demonstrations.

The DEIS/DEIR also failed to disclose that American MagLev Technologies, Inc. has for 4 years offered to build an on-site demonstration project at the POLA or POLB at its own expense. Questions as to its actual construction and operating costs would be further disclosed to quell any port concerns and current false

accusations. The DEIS/DEIR also failed to disclose that a POLB Terminal Operator has offered its location as a possible demonstration site and that Union Pacific Railroad has also stated it would allow a test demonstration at its ICTF Facility location. The DEIS/DEIR fails to disclose that a MagLev Train would use the exact same type of carrier as that currently used by diesel fuel locative train carriers. It would be loaded and unloaded the exact same way as it is done today. It also failed to disclose the benefits of a MagLev Train such as Zero Emissions, Near Noiseless, Less Maintenance, Lower Long Term Operating Costs, 3x-4x faster and does not need to wait 1 to 1-1/2 days to connect enough cars to form a full train length.

CFASE-6
Cont.

The public supports investment in zero emissions, near noiseless and more efficient technologies and would support a planned phase-in and integration of more cost-effective and optimal alternative technologies. The DEIS/DEIR gives the inappropriate impression that a slow phase-in is impossible when in fact it is possible. CFASE believes that the 1st phase could be from the ports to the Union Pacific ICTF Facility and/or the Alameda Corridor. The DEIS/DEIR fails to disclose the Alameda Corridor is already designed to be converted into an All-Electric Zero Emissions Freight Transportation System.

The APL Terminal can be planned to be built or converted into a Zero Emissions, Efficient and Optimized Freight Transportation System just like it can be planned to be an All-Automated Container Terminal.

The DEIS/DEIR inadequately describes the feasibility and cost effectiveness of Alternative Technologies discussed in 2.8.2.12 Fully Electrified Container Terminal. The DEIS/DEIS failed to disclose that the roadmap referenced is flawed because of the ports management and staff bias and limited vision to incorporate 21st Century Technologies asap. An All-Electric Zero Emissions MagLev Train could already be built and demonstrated while the port can continue with its research of other technologies.

The DEIS/DEIR misrepresents the facts when it states that the "electrification could, theoretically allow for marginal increases in throughput," as already stated MagLev Trains are Zero Emissions, Near Noiseless, Less Maintenance Costs, Lower Long Term Operating Costs, 3x-4x faster and does not need to wait 1 to 1-1/2 days to connect enough cars to form a full train length.

The DEIS/DEIR misrepresents the facts when it fails to disclose that the most efficient and optimal way to unload and transport containers that will go to near dock railyards and non-near railyards is to have on-dock electric rail built dockside to ships which is not proposed at the APL Terminal.

CFASE-7

The DEIS/DEIR misrepresents the facts when it fails to disclose that the Vision Motor Corp - Hydrogen Fuel Cell Electric Battery Zero Emissions Near Noiseless Tyrano a Class VIII 80,000lbs. Drayage Truck and ZETT (Zero Emission Terminal Tractor) a Class VIII 130,000 lbs. Terminal Tractor (yard dog) for off-road port terminal, rail yard and intermodal facility operations exists. POLA has purchased only 2 trucks for demonstration when in fact they are operating successfully, have a higher torque ratio, have lower maintenance costs than diesel trucks and cost less over the life-time of a comparable diesel fuel truck. The DEIS/DEIR should require that 50% of the fleet that services APL should be replaced with Vision Motor Corp trucks and the phase-in plan should be included.

The DEIS/DEIR fails to disclose that the Advanced Cleanup Technologies, Inc. - Advanced Maritime Emissions Control System (AMECS) and Advanced Locomotive Emissions Control System (ALECS) technologies have been successfully tested and not included or referenced as viable, feasible and cost-effective technologies to reduce air pollution and green house gases.

The DEIS/DEIR fails to disclose that a Fully or Near Fully Electrified Container Terminal is viable and feasible within 1-3 years, which is adequate time to meet future APL Terminal growth demands.

The DEIS/DEIR inadequately describes the feasibility and usage of expansion or improvements of rail lines discussed in 2.8.2.13 Accelerate Expansion of Rail Lines to Handle Cargo.

CFASE-8

The DEIS/DEIS failed to disclose that the Alameda Corridor is currently only being used at less than 35% of capacity because the POLA and POLB refuse to require in the Lease Agreements that Tenants maximize the use of the Alameda Corridor.

The DCESI/DEIR fails to disclose that the most efficient and optimal way to unload and transport containers that will go to near dock railyards and non-near railyards is to have on-dock rail built dockside to ships. The DEIS/DEIR proposes to use outdated, inefficient logistics methods which will require the majority of containers to be dropped to the ground, picked-up and relocated one or two times to one or more backlands staging areas.

CFASE Requests: The DEIS/DEIR: Include information, investments, demonstrations and assessments of current available and near term (1-3 years) available efficient technologies which optimize the cargo-handling, freight transportation, which are zero emissions, near noiseless and electric, which maximize land footprint capacity usage, decrease negative environmental, public health, public safety and socio-economic impacts. The DEIS/DEIR require that all feasible and cost-effective technologies be required in the project proposal.

CFASE-8
Cont.

DEIS/DEIR require the APL lease and terminal project expansion to maximize usage of the Alameda Corridor.

DEIS/DEIR require the APL Terminal design to incorporate on-dock rail built dockside to shipside.

The DEIS/DEIR inadequately describes the feasibility of expansion but increased technology to increase efficiency discussed in 2.8.2.14.

The DEIS/DEIR fails to consider the variety of alternative technologies that would facilitate more efficient and optimal cargo-handling and destination freight transportation. When considered as a whole package of solutions the following are in fact feasible and cost-effective for no expansion:

- a. The benefits of a MagLev Train such as Zero Emissions, Near Noiseless, Less Maintenance, Lower Long Term Operating Costs, 3x-4x faster and does not need to wait 1 to 1-1/2 days to connect enough cars to form a full train length.
- b. The Alameda Corridor is currently only being used at less than 35% of capacity because the POLA and POLB refuse to require in the Lease Agreements that Tenants maximize the use of the Alameda Corridor.
- c. The most efficient and optimal way to unload and transport containers that will go to near dock railyards and non-near railyards is to have on-dock rail built dockside to ships.
- e. The more efficient container unloading, staging and transferring systems such as the Green Rail Intelligent Development (GRID) - ON-DOCK Ship-to-Rail interface platform called "SuperDock" powered exclusively by electrification.
- f. The more efficient and optimal terminal designs such as unloading containers using a U-Shape Terminal Dock Design where containers can be unloaded and loaded from both sides of a ship at the same time vs the outdated technology currently being used. This design concept was previously proposed to the Port of Los Angeles for the China Shipping Terminal and unfortunately not considered.

CFASE-9

CFASE Requests: The DEIS/DEIR: Include information, investments, demonstrations and assessments of current available and near term (1-3 years) available efficient technologies which optimize the cargo-handling, freight transportation, which are zero emissions, near noiseless and electric, which maximize land footprint capacity usage, decrease negative environmental, public health, public safety and socio-economic impacts. The DEIS/DEIR require that all feasible and cost-effective technologies be required in the project proposal as described in a-f.

5. **Section ES.5.2.1 – Unavoidable Significant Impacts. The DEIS/DEIR and Table ES-3 fails to identify and list all air pollution sources, noise, traffic congestion and safety impact sources.**

The DEIS/DEIR and conclusions by port staff when they state, “No feasible mitigation measures are available that would avoid all of the potential impacts or reduce all impacts to less than significant levels,” is a lie. The DEIS/DEIR fails to include all emissions from all train and truck sources. This indicates that the traffic study data is inadequate and incomplete, the traffic projections are not accurate therefore it has underestimated the significance of emissions, the future emissions, the environmental, public health, public safety impacts and necessary mitigation. It appears that there has been no accounting for the fact that trains and trucks will age and in time release more emissions. The DEIS/DEIR fails to include all train emissions from the time the train locomotives must leave their point of origin to the Port, when they must have their maintenance and after they leave the rail facilities. The DEIS/DEIR fails to include all truck emissions from the time the trucks leave their point of origin to the Port, all other truck destinations. Off-Port Tidelands Property emissions and impact sources include:

- Off-Port Tidelands Property - Truck Transportation Corridors
- Off-Port Tidelands Property - Container Storage Yards
- Off-Port Tidelands Property - Chassis Storage Yards
- Off-Port Tidelands Property - Container Inspection Facilities
- Off-Port Tidelands Property - Fumigation Facilities
- Off-Port Tidelands Property - Truck Fuel/Gas Stations
- Off-Port Tidelands Property - Truck Maintenance Garages
- Off-Port Tidelands Property - Truck Storage Areas
- Off-Port Tidelands Property - Truck Staging Areas
- Off-Port Tidelands Property - Truck Lunch/Rest Stop Areas
- Off-Port Tidelands Property - Truck Idling Locations i.e. bridges & intersections
- Off-Port Tidelands Property - Truck Detour Locations
- Off-Port Tidelands Property - Truck & Reefer Container A/C HFC's Due to Leaking
- Off-Port Tidelands Property - Train Transportation Corridors
- Off-Port Tidelands Property - Train Idling Locations
- Off-Port Tidelands Property - Train Maintenance Yard Locations

Therefore additional new studies must be conducted such as an Off-Port Tidelands Property Community Nexus Impact Study and Health Impact Assessment to assess the impacts from the annual increase of 2,004,432 more truck trips, 1,277 more train trips and 143 more ships due to this APL expansion proposal.

The following are feasible mitigation measures:

- a. The benefits of a MagLev Train such as Zero Emissions, Near Noiseless, Less Maintenance, Lower Long Term Operating Costs, 3x-4x faster and does not need to wait 1 to 1-1/2 days to connect enough cars to form a full train length.
- b. The Alameda Corridor is currently only being used at less than 35% and at times less than 25% of capacity because the POLA and POLB refuse to require in the Lease Agreements that Tenants maximize the use of the Alameda Corridor.
- c. The most efficient and optimal way to unload and transport containers that will go to near dock railyards and non-near railyards is to have on-dock rail built dockside to ships.
- d. The more efficient container unloading, staging and transferring systems such as the Green Rail Intelligent Development (GRID) - ON-DOCK Ship-to-Rail interface platform called “SuperDock” powered exclusively by electrification.
- e. The more efficient and optimal terminal designs such as unloading containers using a U-Shape Terminal Dock Design where containers can be unloaded and loaded from both sides of a ship at the same time vs the outdated technology currently being used. This design concept was previously proposed to the Port of Los Angeles for the China Shipping Terminal and unfortunately not considered.

- f. The Vision Motor Corp - Hydrogen Fuel Cell Electric Battery Zero Emissions Near Noiseless Tyrano a Class VIII 80,000lbs. Drayage Truck and ZETT (Zero Emission Terminal Tractor) a Class VIII 130,000 lbs. Terminal Tractor (yard dog) for off-road port terminal, rail yard and intermodal facility operations exists.
- g. The Advanced Cleanup Technologies, Inc. - Advanced Maritime Emissions Control System (AMECS) and Advanced Locomotive Emissions Control System (ALECS) technologies have been successfully tested to capture 92%-98% of all emissions and is not included or referenced as viable, feasible and cost-effective technologies to reduce air pollution and green house gases. AMECS captures more emissions than what Electric Shorepower prevents.
- h. Noise suppression technologies exist for rail lines, engines, equipment, sound walls, the use of near noiseless trucks and trains, sound-proofing using a STC Rating of 90 and above for residential homes, public schools, child care centers and other sensitive receptors located adjacent and near train and truck transportation corridors.
- i. More frequent inspection and maintenance of Truck and Reefer Container A/C units to prevent fugitive HFC's emissions which are a greenhouse gases.
- j. Installation of Air Purification Systems in residential homes, public schools, child care centers and other sensitive receptors located adjacent and near train and truck transportation corridors.

CFASE Requests: The DEIS/DEIR include information and assessments of current available mitigation measure technologies and the DEIS/DEIR require that all feasible and cost-effective technologies that have been identified during the public comment period be required in the project proposal as described in a-j.

The DEIS/DEIR require the inclusion of an Off-Port Tidelands Property Community Nexus Impact Study and Health Impact Assessment in order to document all impacts and needed mitigation. That the project not be approved or the EIS/EIR certified if no study or assessment is included.

The DEIS/DEIR require the inclusion of all identified feasible mitigation measures in the APL Tenant Lease Agreement.

6. Section ES.5.2.2 – Summary of Significant Impacts that can be Mitigated, Avoided or Substantially Lessened. The DEIS/DEIR Table ES-3 fails to identify and include all impacts that were identified during the public comment period and additional impacts that would have been identified if the port had conducted an Off-Port Tidelands Property Community Nexus Impact Study and Health Impact Assessment.

The DEIS/DEIR fails to include all emissions from all train and truck sources in Table ES-3. This indicates that the traffic study data is inadequate and incomplete, the traffic projections are not accurate therefore it has underestimated the significance of emissions, the future emissions, the environmental, public health, public safety impacts and necessary mitigation. It appears that there has been no accounting for the fact that trains and trucks will age and in time release more emissions. The DEIS/DEIR fails to include all train emissions from the time the train locomotives must leave their point of origin to the Port, when they must have their maintenance and after they leave the rail facilities. The DEIS/DEIR fails to include all truck emissions from the time the trucks leave their point of origin to the Port, all other truck destinations. Off-Port Tidelands Property emissions and impact sources include:

- Off-Port Tidelands Property - Truck Transportation Corridors
- Off-Port Tidelands Property - Container Storage Yards
- Off-Port Tidelands Property - Chassis Storage Yards
- Off-Port Tidelands Property - Container Inspection Facilities
- Off-Port Tidelands Property - Fumigation Facilities
- Off-Port Tidelands Property - Truck Fuel/Gas Stations
- Off-Port Tidelands Property - Truck Maintenance Garages
- Off-Port Tidelands Property - Truck Storage Areas
- Off-Port Tidelands Property - Truck Staging Areas

Off-Port Tidelands Property - Truck Lunch/Rest Stop Areas
Off-Port Tidelands Property - Truck Idling Locations i.e. bridges & intersections
Off-Port Tidelands Property - Truck Detour Locations
Off-Port Tidelands Property - Truck & Reefer Container A/C HFC's Due to Leaking
Off-Port Tidelands Property - Train Transportation Corridors
Off-Port Tidelands Property - Train Idling Locations
Off-Port Tidelands Property - Train Maintenance Yard Locations

Therefore additional new studies must be conducted such as an Off-Port Tidelands Property Community Nexus Impact Study and Health Impact Assessment to assess the impacts from the annual increase of 2,004,432 more truck trips, 1,277 more train trips and 143 more ships due to this APL expansion proposal.

CFASE Requests: The DEIS/DEIR be required to identify and include all impacts and mitigation that were identified during past and recent public comment periods.

The DEIS/DEIR require the inclusion of an Off-Port Tidelands Property Community Nexus Impact Study and Health Impact Assessment in order to document all impacts and needed mitigation. That the project not be approved or the EIS/EIR certified if no study or assessment is included.

7. **Section ES.5.2.4 – Mitigation Measures, Standard Conditions of Approval And Lease Measures. The DEIS/DEIR needs to be updated with the information identifying other impacts and mitigation measures that have been identified in these and past public comments.**

The Air Quality, meteorology & Greenhouse Gases, Ground Transportation and Noise categories need to be updated with the information identifying other impacts and mitigation measures that have been identified in these and past public comments.

CFASE Requests: The DEIS/DEIR Air Quality, meteorology & Greenhouse Gases, Ground Transportation and Noise categories need to be updated to include information identifying other impacts and mitigation measures that have been identified in these and past public comments.

8. **Section ES.5.2.4.3 – Lease Measures. The DEIS/DEIR Lease Measures language does not guarantee that new technologies will be identified, researched, recommended or required.**

LM AQ-1 restricts new technologies to what the POLA deems feasible in terms of cost, technical and operational feasibility. It was the Port of Los Angeles in 2001 that claimed that Electric Shorepower was not feasible or cost-effective, it took a lawsuit settlement by San Pedro Homeowner Associations to force the POLA to incorporate Electric Shorepower at the China Shipping Terminal. It was CFASE a non-profit public organization as a member of the AB32 Environmental Justice Advisory Committee that first proposed that Electric Shorepower be included as an AB32 Early Action Measure which has made Electric Shorepower mandatory for all ports in the State of California by 2020. The POLA historically has been shown to be untrustworthy, unwilling to incorporate new technologies and biased in spite of scientific evidence, technical studies and successful test performances of new emerging technologies.

Historically there have been very few rare instances where a port Tenant has voluntarily adopted a new technology or mitigation measure and in most cases they were just ahead of a new law or rule making requirement.

Every current port Tenant is aware of the success of the Advanced Cleanup Technologies, Inc. - AMECS Technology but not one has volunteered to purchase the technology. AMECS reduces more emissions than Electric Shorepower from all ships and from ships which are not or cannot be retrofitted.

Every port Tenant is aware of the Vision Motor Corp - Hydrogen Fuel Cell Electric Battery Zero Emissions Near Noiseless Tyrano a Class VIII 80,000lbs. Drayage Truck and ZETT (Zero Emission Terminal Tractor) a Class VIII 130,000 lbs. Terminal Tractor (yard dog) for off-road port terminal, rail yard and intermodal

CFASE-11
Cont.

CFASE-12

CFASE-13

facility operations exists. Vision Motor Corp drayage trucks have a lower fuel costs, higher torque ratio, have lower maintenance costs than diesel trucks and cost less over the life-time of a comparable diesel fuel truck, but not one Tenant has purchased one.

CFASE Requests: The DEIS/DEIR Lease Measures language require inclusion of new technologies authorized by law, approved, validated or certified by a governmental regulatory agency or meets the requirements of a adopted national trade association standard.

CFASE-13
Cont.

9. **Section ES.5.2.7 – Socioeconomic and Growth-Inducing Impacts. The DEIS/DEIR discusses only the positive socioeconomic impacts benefits and fails to include an assessment of the numerous negative socioeconomic impacts.**

The DEIS/DEIR fails to include information of the numerous negative socioeconomic impacts such as:

- a. Cost to the state of California public for public health care from ports and goods movement air pollution. One ARB study identified a minimum cost of \$ 20 billion annually from only two air pollution sources.
- b. Cost to the state of California public for transportation infrastructure repair, maintenance and replacement from increased truck usage and weight. The typical freeway and bridge now only has a 50 year lifespan vs the 100 year life design. The public pays for 80%+ of all costs not the ports and goods movement industry.
- c. Cost to the state of California public for off-port property truck and port worker traffic accidents, increased costs of insurance, emergency response.
- d. Cost to the state of California public for loss of income and employment due to truck and port worker traffic accidents, traffic congestion, failure to report to work on time, public health illnesses & disabilities and children sick.
- e. Cost to the state of California public for utility infrastructure repair, maintenance, replacement and contract purchases of electricity from out of state. The public pays for 80%+ of all costs not the ports and goods movement industry.
- f. Cost to the state of California public for the loss of job employment. Even though the port creates jobs via its preference of container terminals it is a fact that only 1-2 jobs is created per acre for a container terminal vs other potential port site industries which create up to 50 or more jobs per acre.

CFASE-14

The POLA has never conducted a study of the number of jobs per acre a particular industry creates.

The POLA restricts other potential industries by designing a master plan that eliminates other potential industries and by not soliciting proposals for port land uses. When a non-container facility company proposes or submits an application its does everything to prevent it from occurring even if it is marine industry oriented. A recent example is the ports intentional campaign to prevent a ship repair facility on port property, because it wants the land for future container backlands.

The POLA waited over 10 year to finally build 1-mw of solar electricity and has not moved forward since then to meet its commitment to build on-site 10mw of solar electricity. The POLA has the financial capacity to take itself off-the-public grid by incorporating solar energy, fuel cells, wind and wave energy. The public has for over 10 years requested this and supports this investment of public funds.

The POLA has never conducted a comprehensive negative socioeconomic and cost impacts assessment, even though it has been requested numerous times in the past.

CFASE Requests: The DEIS/DEIR include an on-port property and off-port property comprehensive negative socioeconomic and cost impacts assessment. That the project not be approved or the EIS/EIR certified if no assessment is included. We request that POLA contract with Economist John Haveman Ph.D. for this type of study.

10. **Section 3.2 – Air Quality, Meteorology & Greenhouse Gases. The Section Summary discusses the Health Risk Impacts but fails to disclose the limited public health impacts information Health Risk**

CFASE-15

Assessment's provide and fails to disclose that all emission sources were not included in the emissions inventory

Excluded Emission Sources. The DEIS/DEIR discusses only the impacts from the APL Terminal facility but failed to include all emissions from all train and truck transportation corridor and destination sources. This indicates that the traffic study data is inadequate and incomplete, the traffic projections are not accurate therefore it has underestimated the significance of emissions, the future emissions, the environmental, public health, public safety impacts and necessary mitigation. It appears that there has been no accounting for the fact that trains and trucks will age and in time release more emissions. The DEIS/DEIR fails to include all train emissions from the time the train locomotives must leave their point of origin to the Port, when they must have their maintenance and after they leave the rail facilities. The DEIS/DEIR fails to include all truck emissions from the time the trucks leave their point of origin to the Port, all other truck destinations. Off-Port Tidelands Property emissions and impact sources include:

- Off-Port Tidelands Property - Truck Transportation Corridors
- Off-Port Tidelands Property - Container Storage Yards
- Off-Port Tidelands Property - Chassis Storage Yards
- Off-Port Tidelands Property - Container Inspection Facilities
- Off-Port Tidelands Property - Fumigation Facilities
- Off-Port Tidelands Property - Truck Fuel/Gas Stations
- Off-Port Tidelands Property - Truck Maintenance Garages
- Off-Port Tidelands Property - Truck Storage Areas
- Off-Port Tidelands Property - Truck Staging Areas
- Off-Port Tidelands Property - Truck Lunch/Rest Stop Areas
- Off-Port Tidelands Property - Truck Idling Locations i.e. bridges & intersections
- Off-Port Tidelands Property - Truck Detour Locations
- Off-Port Tidelands Property - Truck & Reefer Container A/C HFC's Due to Leaking
- Off-Port Tidelands Property - Train Transportation Corridors
- Off-Port Tidelands Property - Train Idling Locations
- Off-Port Tidelands Property - Train Maintenance Yard Locations

CFASE-15
Cont.

Therefore additional new studies must be conducted such as an Off-Port Tidelands Property Community Nexus Impact Study and Health Impact Assessment to assess the impacts from the annual increase of 2,004,432 more truck trips, 1,277 more train trips and 143 more ships due to this APL expansion proposal.

Health Risk Impacts. The DEIS/DEIR failed to include a Health Impact Assessment (HIA) that was requested by the public during the Scoping Meeting public comment period and its benefits discussed vs. HRA's. POLA has stated in previous scoping meetings that the public should ask for such a study at the earliest possible time during the scoping public comment period. POLA has once again ignored public and medical professionals' requests for an HIA to be included in all POLA project proposals. POLA has no expert medical professional on staff to base its decision making to not include an HIA.

Section 3.2 – Fails to state that CEQA requires a comprehensive analysis and discussion of health impacts.

"The environmental effects of a project will cause substantial adverse effects on human beings, either directly or indirectly." CCR§15065(a)

"The discussion should include relevant specifics of health and safety problems caused by the physical changes." CCR§15126(a)

"If the physical change causes adverse economic or social effects on people, those adverse effects may be used as a factor in determining the physical change is significant." CCR§15064

CFASE-16

The DEIR states that only a Health Risk Assessment (HRA) was performed, HRA's provide limited public health information. HRA's do not provide information as to how many people are ill, how many are ill with what illness, what is the cause of their illness, how long they have been ill, how grave their illness is, what type of health care do they have, what type of health care is available and what has been the cost of their health care. If you do not know this information how can the Port accurately determine what is the appropriate mitigation? The Port does not have a public health baseline from which to base its findings, mitigation and final decision making. The Port does not have a health professional on staff who is qualified to make appropriate public health decisions and recommendations.

HRA's only include deaths and risk factors from cancer and fails to include all categories of death such as but not limited to:

- a. Asthma
- b. COPD
- c. Premature Birth
- d. Heart Attack
- e. Port worker, truck driver or truck passenger death
- f. Public death due to an accident

The Port was requested to include a Health Impact Assessment (HIA) during the public scoping meeting and public comment period and has refused to include one in the DEIR. The International Association of Impact Assessment defines HIA as: a combination of procedures, methods and tools that systematically judges the potential and sometimes unintended effects of a policy, plan, program or project on the health of a population and the distribution of these effects within a population. HIA identifies appropriate actions to manage those effects.

CFASE has included in these public comments a Letter of Expert Witness from Dr. Jonathan Heller, PHD addressing the merits and significant new information in a HIA vs HRA. Included with his letter is his CV and a copy of the, "Minimum Elements and Practice Standards for HIA, published by the North American HIA Practice Standards Working Group. See Appendix AQ-1, AQ-2, AQ-3.

CFASE has included in these public comments our Public Health Studies List which list numerous medical health studies related to Ports and Goods Movement that the Port did not consider in their assessment of public health impacts and in their Health Risk Assessment. See AQ-4.

Container Ships. Some assumptions used are a gross misrepresentation of facts.

The DEIS/DEIR states that only ship emissions from a one-way trip were included in the inventory when they should have included a round trip. Therefore the emissions were intentionally underestimated and not mitigated.

The DEIS/DEIR states that APL will comply with CARB requirements that ships use of AMP will be 50% by 2014, 70% by 2017 and 80% by 2020 which is untrue. It is impossible for APL to retrofit 50% of its fleet by 2014 which is less than 2 years from now. In addition, the cost to retrofit a container ship ranges from \$500,000 to \$ 1 million.

The DEIS/DEIR fails to require APL to use an Alternative Emissions Control or Capture Technology mitigation method such as the Advanced Cleanup Technologies, Inc. - Advanced Maritime Emissions Control System (AMECS) which captures 92%-98% of all emissions and has been successfully tested at the Port of Long Beach on three ship. See the attached test report: Evaluation of the Advanced Maritime Emissions Control System (AMECS), AMECS Demonstration at the Port of Long Beach dated 11-19-2008 by TIAX, LLC. The DEIS/DEIR fails to disclose that he POLA was a witness and financial sponsor of the testing and has copies of all successful test results.

CFASE-16
Cont.

CFASE-17

The DEIS/DEIR further fails to require the use of Advanced Cleanup Technologies, Inc. - Advanced Maritime Emissions Control System (AMECS) technology when a ship is not retrofitted for electric shorepower or will never be retrofitted.

The DEIS/DEIR fails to disclose that AMECS reduces more emissions than Electric Shorepower from all ships and from ships which are not or cannot be retrofitted.

Trucks. Some assumptions used are a gross misrepresentation of facts.

The DEIS/DEIR states that only truck emissions from a one-way trip were included in the inventory when they should have included a round trip. Therefore the emissions were intentionally underestimated and not mitigated.

The DEIS/DEIR discusses only the emissions impacts from the APL Terminal facility but failed to include all emissions from all truck transportation corridor and destination sources. This indicates that the traffic study data is inadequate and incomplete, the traffic projections are not accurate therefore it has underestimated the significance of emissions, the future emissions, the environmental, public health, public safety impacts and necessary mitigation. It appears that there has been no accounting for the fact that trucks will age and in time release more emissions. The DEIS/DEIR fails to include all truck emissions from the time the trucks leave their point of origin to the Port, all other truck destinations. Off-Port Tidelands Property emissions and impact sources include:

- Off-Port Tidelands Property - Truck Transportation Corridors
- Off-Port Tidelands Property - Container Storage Yards
- Off-Port Tidelands Property - Chassis Storage Yards
- Off-Port Tidelands Property - Container Inspection Facilities
- Off-Port Tidelands Property - Fumigation Facilities
- Off-Port Tidelands Property - Truck Fuel/Gas Stations
- Off-Port Tidelands Property - Truck Maintenance Garages
- Off-Port Tidelands Property - Truck Storage Areas
- Off-Port Tidelands Property - Truck Staging Areas
- Off-Port Tidelands Property - Truck Lunch/Rest Stop Areas
- Off-Port Tidelands Property - Truck Idling Locations i.e. bridges & intersections
- Off-Port Tidelands Property - Truck Detour Locations
- Off-Port Tidelands Property - Truck & Reefer Container A/C HFC's Due to Leaking

Therefore additional new studies must be conducted to include a Traffic Study and an Off-Port Tidelands Property Community Nexus Impact Study to assess the impacts from the current and annual increase of 2,004,432 more truck trips due to this APL expansion proposal.

The DEIS/DEIR discusses truck idling time calculation methods but the calculations failed to include all idling circumstances such as:

- a. When the Shuyler Heim Bridge lifts idling time is 15-20 minutes.
- b. The numerous times a truck breaks down on the Vincent Thomas Bridge and Gerald Desmond Bridge.
- c. The numerous times there is an accident on the LA Harbor I-110, Long Beach I-710 and other freight transportation corridor connecting freeways.
- d. The idling time waiting for a container shipside.
- e. The idling time at container storage yards.
- f. The idling time at fumigation facilities.
- g. The idling time at inspection facilities or gates.
- h. The idling time during lunch breaks.

CFASE requests: That the DEIR disclose that it failed to include all train and truck transportation corridors and destination air emission sources, idling times and revise its data, data analysis methods and assumptions to reflect correct information. The DEIR must revise its data to reflect accurate traffic impacts studies information.

The DEIR include a Health Impact Assessment and Public Health Survey in order to establish a Public Health Baseline.

CFASE requests that the Port of Los Angeles establish a Public Health Care and Socio-Economic Mitigation Trust Fund which can provide financial assistance for immediate, short term and long term health care and other negative socio-economic impacts:

- a. Public health care & treatment.
- b. Financial assistance to pay for health care at local clinics & county hospitals.
- c. Financial assistance to pay for health insurance.
- d. Financial assistance to pay for medical equipment.
- e. Financial assistance to pay for medical supplies.
- f. Financial assistance to pay for medical prescriptions.
- g. Financial assistance for funeral expenses.
- h. Financial assistance for short & long term convalescent care.
- i. Financial assistance for rehabilitation.
- j. Financial assistance for job retraining.
- k. Financial assistance for lost income.

CFASE-19

CFASE requests that the POLA provide evidence that APL will meet the proposed CARB schedule.

11. Section 3.11 – Noise. The section only discusses noise studies that were conducted near the APL Terminal but fails to disclose that no noise studies along the freight transportation corridors and destination points were conducted and no mitigation considered.

The DEIS/DEIR fails to disclose that there are residential areas, public schools, child care centers and other sensitive receptors that border the APL freight transportation corridors and destination points which were not studied or impacts mitigated.

The DEIS/DEIR fails to identify all noise sources such as:

- Off-Port Tidelands Property - Truck Transportation Corridors
- Off-Port Tidelands Property - Container Storage Yards
- Off-Port Tidelands Property - Chassis Storage Yards
- Off-Port Tidelands Property - Container Inspection Facilities
- Off-Port Tidelands Property - Fumigation Facilities
- Off-Port Tidelands Property - Truck Fuel/Gas Stations
- Off-Port Tidelands Property - Truck Maintenance Garages
- Off-Port Tidelands Property - Truck Storage Areas
- Off-Port Tidelands Property - Truck Staging Areas
- Off-Port Tidelands Property - Truck Lunch/Rest Stop Areas
- Off-Port Tidelands Property - Truck Idling Locations i.e. bridges & intersections
- Off-Port Tidelands Property - Truck Detour Locations
- Off-Port Tidelands Property - Train Transportation Corridors
- Off-Port Tidelands Property - Train Railyards, Staging Areas, Maintenance Facilities

CFASE-20

The DEIS/DEIR fails to state that the measured sound levels fail to comply with the Los Angeles Noise Ordinance – Chapter XI Noise Regulation, Article 1 General Provisions Sec. 111.00 Declaration of Policy and Sec. 111.03 Minimum Ambient Noise Level Table II Zone A1, A2, RA, RE, RS, RD, RW1, RW2, R1, R2, R3, R4, R5 Presumed Ambient Noise Level Day dBA 50 and Night 40dBA and Article 6 General Noise Sec.116.01 Loud, Unnecessary and Unusual Noise.

The DEIS/DEIR fails to state that the measured sound levels fail to comply with the recommendations of World Health Organization – Guidelines for Community Noise, Table 1 & Table 4.1 Guidelines Values for Community Noise in Specific Environments – Specific Environment: Inside Bedrooms 30dBA, Preschool Sleep 30dBA and School Class Rooms 35dBA the American National Standards Institute (ANSI) ANSI S12.60-2002 Acoustical Performance Criteria, Design Requirements, and Guidelines for Schools. See Appendix N-1, N-2, N-6.

The DEIS/DEIR further fails to comply with the World Health Organization – Guidelines for Community Noise, 4.2.3 Sleep Disturbance Effects states, “For noise with a large proportion of low frequency sounds a still lower guideline lower than 30dBA is recommended,” and “Since A-weighting underestimates the sound pressure level of noise with low frequency components, a better assessment of health effects would be to use C-weighting.” See Appendix N-1, N-2.

CFASE-21

The Port of Los Angeles and BNSF Railway failed to establish a Community Advisory Committee (CAC) to discuss noise, noise sources, noise impacts, noise studies and noise mitigation which would have identified the deficiencies in the noise studies conducted, inadequate assumptions adopted and failure to incorporate noise mitigation measures in the DEIR.

The Port of Los Angeles and BNSF Railway failed to conduct a Community Advisory Committee Environmental Justice Community Preconstruction Noise Survey which would have revealed deficiencies in the noise studies conducted, assumptions adopted and failure to incorporate noise mitigation measures in the DEIR.

Request: CFASE requests that the DEIR include a study and assessment of long term continuous public exposure to noise, high frequency loud noise and low frequency sound levels measurement up to 3 miles from the project site, other off-site truck destinations and transportation corridors which is the normal audible distance of sound.

CFASE request that a Environmental Justice Community Fence-Line Monitoring Program be established and supervised by the Community Advisory Committee. See Appendix N-7.

CFASE requests that the DEIS/DEIR clearly state that referenced and recorded sound level measurements do not comply with the Los Angeles Noise Ordinance Standards or the World Health Organization – Guidelines for Community Noise the American National Standards Institute (ANSI) ANSI S12.60-2002 Acoustical Performance Criteria, Design Requirements, and Guidelines for Schools. See Appendix N-1, N-2, N-6.

CFASE-22

CFASE further requests that the DEIS/DEIR require the establishment of a Community Advisory Committee (CAC) made up of Wilmington, Long Beach and Carson residents and consist of 90% community residents and 10% other stakeholders. The CAC will be established prior to commencement of construction and will end at the completion of the project. The purpose of the CAC is to provide a forum to address DEIR, FEIR deficiencies, provide project statuses and address problems that may occur during construction and post operation. See Appendix N-4

CFASE further requests that the DEIS/DEIR require that an Environmental Justice Community Preconstruction Noise Survey be conducted prior to construction. See Appendix N-5

CFASE requests that the DEIS/DEIR include, identify and list the locations of the numerous off-port tidelands property truck destinations in San Pedro and Wilmington.

CFASE requests that the impact zone for noise sensitive receivers be a minimum 3 miles radius from the BNSF SCIF Facility and all train and truck transportation corridors and that a new list of sensitive receptors be established that reflects an accurate record of those within 3 miles.

CFASE requests that you mitigate all noise impacts to less than significant as required by CEQA.

CFASE requests that the following Environmental Justice Community Noise Standards be incorporated in the DEIS/DEIR to protect Wilmington, Long Beach, Carson and Transportation Corridor EJ Communities. See Appendix N-3.

In all the proposed project alternatives and mitigation, sound noise levels are high, will continue to be high in perpetuity and are unacceptable to the communities who will be impacted significantly short term during construction and long term when fully operational. The project sponsors have intentionally misled the public and decision makers by inferring that they have considered all alternatives noise abatement measures when in fact they have not. They have referenced standards that allow high noise levels and fail to disclose that standards can be adopted which provide better health protection for Environmental Justice Communities that have been historically disproportionately impacted and discriminated against. We submit the following as our EJ Community proposed Noise Standards:

Environmental Justice Community Noise Standards

| Environment | Day | Night | Night Sleep Time |
|--------------------------------|-----------------|---------------|------------------|
| | 7:00am – 5:00pm | 5:00pm-7:00am | 9:00pm – 7:00am |
| Outdoor | 50dBA | 40dBA | |
| School Indoor | 35dBA | 35dBA | |
| Preschool Sleep Time | 30dBA | | |
| Residence Indoor | 35dBA | 35dBA | |
| Residence Indoor Sleep Time | | | 30dBA |
| Residence Indoor Low Frequency | | | 25dBA |

**CFASE-22
Cont.**

CFASE-23

12. **Section 5.0 – Environmental Justice.**

The DEIS/DEIR Cumulative Impacts Assessments and Environmental Justice Assessments do not comply with the California Government Codes and California Public Resources Codes as described throughout these public comments. The DEIS/DEIR fails to demonstrate how it has complied with each code requirement.

The DEIS/DEIR fails to identify and include a discussion on CEQA requirements such as CCR§15064, CCR§15065(a), CCR§15126.2(a) and other applicable California Health & Safety Code requirements. The DEIR fails to demonstrate how it has complied with each code requirement.

The DEIS/DEIR fails to identify and include an assessment of the APL Terminal negative impacts to other Environmental Justice Communities and cities not in the City of Los Angeles, who border the project and border the Freight Transportation Corridors and Destination Point that will service the project.

The Port of Los Angeles through its decision making, actions, inactions, misrepresentations, assumptions and omissions of information has made premeditated decisions to willfully cause disproportionately higher risks, premature death, significant and permanent acute and chronic health impacts, negative socioeconomic impacts, mental and physical bodily harm, increased risk to hazards to port harbor, transportation corridor and warehouse distribution center residents, lower working-class people in general, low income, ethnic minorities, foreign language residents, the poor, children, pregnant woman, the elderly and sensitive receptors in Environmental Justice Communities without consideration, remorse, compensation, mitigation or adequate mitigation for the purpose of significant financial gain and economic benefits of others.

The Port of Los Angeles, its management, staff and APL is systemically a highly classist and racist private business interest entity because its political, business, economic and environmental decision making is structured and operates to systematically disadvantage lower working-class people in general, low income, ethnic minorities, foreign language residents, the poor, children, pregnant women, the elderly and sensitive receptors in particular and to systemically advantage a largely white upper class.

The DEIS/DEIR fails to acknowledge, address and mitigate the fact that there is no Port or Apl Project - Public Emergency, Disaster & Response Plan. The DEIR fails to discuss if there is adequate public liability and disaster insurance to protect the public and cities. The Port and APL have created no emergency funds pool, contracted no third party support services, contracted no relocation areas, contracted no food or water services etc. to assist EJ Communities that could be impacted by the APL Project, Facilities and Freight Transportation Corridors.

The Port has put every Harbor EJ Community and Freight Transportation Corridor EJ Community in extreme danger from its business operations. All planning that has been conducted has been to protect "Port Assets" not Harbor EJ Communities or Freight Transportation Corridor EJ Communities lives, livelihoods and property. If there is a Port or APL catastrophe"

- a. There are inadequate Port and City Police to protect and assist the public.
- b. There are inadequate Fire Department Personnel & Equipment to provide assistance.
- c. There are inadequate medical & hospital services & beds available.
- d. There is no relocation place for displaced families to go to.
- e. There are no emergency food & water resources for displaced families.
- f. There are no financial aid assistance programs available.

Summary of Impact Determinations, conclusion is rejected by Environmental Justice Organizations as incomplete, inaccurate assessment, fails to acknowledge and incorporate the best public health standards

CFASE-24

CFASE-25

and guidelines and fails to mitigate all noise impacts to less than significant as described in these public comments.

Mitigation Monitoring, conclusion is rejected by Environmental Justice Organizations as incomplete, inaccurate assessment, fails to acknowledge and incorporate the best public health standards and guidelines and fails to mitigate all noise impacts to less than significant as described in these public comments.

Significant Unavoidable Impacts, conclusion is rejected by Environmental Justice Organizations because it fails to acknowledge that significant unavoidable impacts will occur during both daytime and nighttime which can be mitigated to less than significant as described in these public comments.

CFASE Request. That the DEIS/DEIR identify all applicable city, county, regional, state and federal environmental, environmental justice, public health and public safety and community sustainability legal compliance requirements.

CFASE requests that the DEIS/DEIR include an assessment, discussion and matrix chart that demonstrates compliance to all legal requirements.

CFASE request that the DEIS/DEIR an assessment and discussion of other Environmental Justice Communities and cities not in the City of Los Angeles, who border the project and border the Freight Transportation Corridors that will service the project.

CFASE requests that the Port hire an Environmental Justice Attorney and Environmental Justice Consultant to advise and supervise the revision of Port policies, procedures, practices, rules, regulations, programs and projects to comply with all applicable civil rights, social justice, environmental, environmental justice, public health and public safety laws, rules, regulations, policies, programs and projects.

CFASE requests that the DEIR include an Environmental Justice Plan which includes a monitoring and compliance elements to reduce all negative individual environmental, public health, public safety, transportation and socioeconomic impacts, cumulative impacts and risks to less than significant.

CFASE requests that an Environmental Justice Advisory Committee be established with community residents and organization representatives from all impacted EJ Communities.

CFASE requests that the DEIR include a Health Impact Assessment, Public Health Survey, Off-Port Tidelands Port Property Community Impact Nexus Study, Micro-EJ Community Climate Change Impact Assessment, Negative Socio-Economic Impact Assessment and Public Emergency, Disaster & Response Plan.

CFASE requests that the DEIR include a Port and APL Project - Public Emergency, Disaster & Response Plan which has involved the proposed Environmental Justice Advisory Committee and residents.

**CFASE-25
Cont.**


CFASE-26

Coalition For A Safe Environment Mission Statement is - To protect, promote, preserve and restore our Mother Earth's delicate ecology, environment, natural resources and wildlife. To attain Environmental Justice in international trade marine ports, goods movement transportation corridors, petroleum and energy industry communities. CFASE has members in over 25 cities and every harbor city.

CFASE-27

The Coalition For A Safe Environment requests another 30 days for public comment and reserves the right to submit additional public comments as may be deemed necessary.

Respectfully Submitted,



Jesse N. Marquez
Executive Director

And

Jesse N. Marquez
A Negatively Health, Safety & Socio-Economically Impacted
Resident of Wilmington, California

Noise Appendix N - 1

Table 4.1: Guideline values for community noise in specific environments.

| Specific environment | Critical health effect(s) | LAeq [dB] | Time base [hours] | LAm _{ax} , fast [dB] |
|---|--|-----------|-------------------|-------------------------------|
| Outdoor living area | Serious annoyance, daytime and evening | 55 | 16 | - |
| | Moderate annoyance, daytime and evening | 50 | 16 | - |
| Dwelling, indoors | Speech intelligibility and moderate annoyance, daytime and evening | 35 | 16 | - |
| Inside bedrooms | Sleep disturbance, night-time | 30 | 8 | 45 |
| Outside bedrooms | Sleep disturbance, window open (outdoor values) | 45 | 8 | 60 |
| School class rooms and pre-schools, indoors | Speech intelligibility, disturbance of information extraction, message communication | 35 | during class | - |
| Pre-school bedrooms, indoors | Sleep disturbance | 30 | sleeping -time | 45 |
| School, playground outdoor | Annoyance (external source) | 55 | during play | - |
| Hospital, ward rooms, indoors | Sleep disturbance, night-time | 30 | 8 | 40 |
| | Sleep disturbance, daytime and evenings | 30 | 16 | - |
| Hospitals, treatment rooms, indoors | Interference with rest and recovery | #1 | | |
| Industrial, commercial shopping and traffic areas, indoors and outdoors | Hearing impairment | 70 | 24 | 110 |
| Ceremonies, festivals and entertainment events | Hearing impairment (patrons:<5 times/year) | 100 | 4 | 110 |
| Public addresses, indoors and outdoors | Hearing impairment | 85 | 1 | 110 |
| Music through headphones/earphones | Hearing impairment (free-field value) | 85 #4 | 1 | 110 |
| Impulse sounds from toys, fireworks and firearms | Hearing impairment (adults) | - | - | 140 #2 |
| | Hearing impairment (children) | - | - | 120 #2 |
| Outdoors in parkland and conservation areas | Disruption of tranquillity | #3 | | |

#1: as low as possible;

#2: peak sound pressure (not LAm_{ax}, fast), measured 100 mm from the ear;

#3: existing quiet outdoor areas should be preserved and the ratio of intruding noise to natural background sound should be kept low;

#4: under headphones, adapted to free-field values

GUIDELINES FOR COMMUNITY NOISE

Edited by

Birgitta Berglund
Thomas Lindvall
Dietrich H Schwela

This WHO document on the *Guidelines for Community Noise* is the outcome of the WHO-expert task force meeting held in London, United Kingdom, in April 1999. It bases on the document entitled "Community Noise" that was prepared for the World Health Organization and published in 1995 by the Stockholm University and Karolinska Institute.



World Health Organization, Geneva

Cluster of Sustainable Development and Healthy Environment (SDE)
Department for Protection of the Human Environment (PHE)
Occupational and Environmental Health (OEH)

Noise Appendix N - 3

Environmental Justice Community Noise Standard

1. Environmental Justice Community Noise Standard

| Environment | Day 7:00am – 5:00pm | Night 5:00pm-7:00am | Night Sleep Time 9:00pm – 7:00am |
|---------------------------------------|------------------------|------------------------|-------------------------------------|
| Outdoor | 50dBA | 40dBA | |
| School Indoor | 35dBA | 35dBA | |
| Preschool Sleep Time | 30dBA | | |
| Residence Indoor | 35dBA | 35dBA | |
| Residence Indoor Sleep Time | | | 30dBA |
| Residence Indoor Low Frequency | | | 25dBA |

1.1 General Ambient Noise Level

Los Angeles Noise Ordinance – Chapter XI Noise Regulation, Article 1 General Provisions Sec. 111.00 Declaration of Policy and Sec. 111.03 Minimum Ambient Noise Level Table II Zone A1, A2, RA, RE, RS, RD, RW1, RW2, R1, R2, R3, R4, R5 Presumed Ambient Noise Level Day dBA 50 and Night 40dBA and Article 6 General Noise Sec.116.01 Loud, Unnecessary and Unusual Noise.

1.2 Community Ambient Noise Protection

World Health Organization – Guidelines for Community Noise, Table 1 & Table 4.1 Guidelines Values for Community Noise in Specific Environments – Specific Environment: Inside Bedrooms 30dBA, Preschool Sleep 30dBA and School Class Rooms 35dBA.

1.3 Specific Low Frequency Noise Protection

World Health Organization – Guidelines for Community Noise, 4.2.3 Sleep Disturbance Effects states, “For noise with a large proportion of low frequency sounds a still lower guideline lower than 30dBA is recommended,” and “Since A-weighting underestimates the sound pressure level of noise with low frequency components, a better assessment of health effects would be to use C-weighting.”

1.4 American Industry Standard

The American National Standards Institute (ANSI) ANSI S12.60-2002 Acoustical Performance Criteria, Design Requirements, and Guidelines for Schools, Table 1 pg. 5 for Learning space 35dBA.

Noise Appendix N - 4

Environmental Justice Project Community Advisory Committee

1.0 Project Community Advisory Committee Purpose

TBD

2.0 PCAC Goals & Objectives

TBD

3.0 PCAC Membership

Community Advisory Committee membership shall consist of 80% local residents, 10% stakeholders and 10% representatives from local community organizations. All residents and stakeholder members must live in Wilmington, Long Beach or Carson.

4.0 PCAC Meetings

TBD

5.0 PCAC Website

TBD

6.0 Project Noise Monitoring Program

TBD

7.0 Project Traffic & Equipment Monitoring Plan

Preconstruction, Construction and Post Construction TBD

8.0 Community Noise Survey

8.1 Preconstruction Community Noise Survey

8.2 During Construction and Post Construction Community Noise Survey TBD.

9.0 Community Noise Complaint Procedure

4.1. Community Information & Complaint Hotline

4.2. Community Complaint Form

4.3. Complaint Investigation

4.4. Problem Corrective Action

4.5. Complaint Resolution

9.0 Project Noise Monitoring Status Reporting

TBD

10.0 Community Complaints Status Reporting

TBD

11.0 PCAC Termination

TBD.

Noise Appendix N - 5

Environmental Justice Community Preconstruction Noise Survey

1. The community should have a say in defining the Community Noise Standard?
Strongly Agree [] Agree [] Disagree [] Undecided []
2. The community should have a say in determining construction work days and hours?
Strongly Agree [] Agree [] Disagree [] Undecided []
3. There should be no construction work on weekends and holidays?
Strongly Agree [] Agree [] Disagree [] Undecided []
4. All construction contractors and subcontractor workers should attend a noise class?
Strongly Agree [] Agree [] Disagree [] Undecided []
5. The noise standards should provide the maximum public health & welfare protection?
Strongly Agree [] Agree [] Disagree [] Undecided []
6. Indoor school classrooms should have a stricter noise standard than day?
Strongly Agree [] Agree [] Disagree [] Undecided []
7. Preschool classrooms should have a stricter noise standard than day?
Strongly Agree [] Agree [] Disagree [] Undecided []
8. Senior housing & Hospice Facilities should have a stricter noise standard than day?
Strongly Agree [] Agree [] Disagree [] Undecided []
9. Hospitals should have a stricter noise standard than day?
Strongly Agree [] Agree [] Disagree [] Undecided []
10. Day time residential near Intermodal facilities should have a stricter noise standard?
Strongly Agree [] Agree [] Disagree [] Undecided []
11. Night time residential areas should have a stricter noise standard than day?
Strongly Agree [] Agree [] Disagree [] Undecided []
12. Sleep times should have a stricter noise standard than standard night?
Strongly Agree [] Agree [] Disagree [] Undecided []
13. A noise monitoring plan should be required as part of the project?
Strongly Agree [] Agree [] Disagree [] Undecided []
14. A Community Advisory Committee should be required as part of the project?

- | | Strongly Agree [] | Agree [] | Disagree [] | Undecided [] |
|---|--------------------|-----------|--------------|---------------|
| 15. Penalties and fines should be established for noise violations? | | | | |
| 16. There should be a public information hotline & complaint line? | | | | |
| 17. Project Noise should be mitigated to eliminate and reduce noise to less than significant? | | | | |
| 18. Port truck traffic volume near residential homes & schools should be limited to prevent increasing noise? | | | | |
| 19. Port train traffic volume near residential homes & schools should be limited to prevent increasing noise? | | | | |
| 20. Project sponsors should require and provide incentives to purchase zero emissions and near noiseless trucks? | | | | |
| 21. Project sponsors should require and provide incentives to purchase zero emissions and hear noiseless trains? | | | | |
| 22. Schools, residential homes and all sensitive receptors locations should be sound proofed to eliminate noise or reduce to less than significant? | | | | |
| 23. Environmental and public health mitigation costs should be included in project budget? | | | | |
| 24. Excessive noise disturbs my ability to sleep? | | | | |
| 25. Excessive noise disturbs my mental peacefulness? | | | | |
| 26. Excessive noise disturbs my ability to relax, watch TV and listen to music? | | | | |
| 27. Excessive noise makes me unable to concentrate and perform my daily activities? | | | | |
| 28. Train & Truck noise is a major problem in my community and has been increasing? | | | | |

AMERICAN NATIONAL STANDARD
**ACOUSTICAL PERFORMANCE CRITERIA, DESIGN
REQUIREMENTS, AND GUIDELINES FOR SCHOOLS**

Accredited Standards Committee S12, Noise

Standards Secretariat
Acoustical Society of America
35 Pinelawn Road, Suite 114E
Melville, NY 11747-3177

Noise Appendix N - 7

Environmental Justice Community Fence-Line Monitoring Program

1.0 Noise Monitoring Program

Complete detail description TBD.

2.0 Community Advisory Committee Establishment

Community Advisory Committee to be established 90 days before construction begins.

3.0 Environmental Justice Community Noise Standard

3.1 Environmental Justice Community Noise Standard

| Environment | Day 7:00am – 5:00pm | Night 5:00pm-7:00am | Night Sleep Time 9:00pm – 7:00am |
|--------------------------------|------------------------|------------------------|-------------------------------------|
| Outdoor | 50dBA | 40dBA | |
| School Indoor | 35dBA | 35dBA | |
| Preschool Sleep Time | 30dBA | | |
| Residence Indoor | 35dBA | 35dBA | |
| Residence Indoor Sleep Time | | | 30dBA |
| Residence Indoor Low Frequency | | | 25dBA |

3.2 General Ambient Noise Level

Los Angeles Noise Ordinance – Chapter XI Noise Regulation, Article 1 General Provisions Sec. 111.00 Declaration of Policy and Sec. 111.03 Minimum Ambient Noise Level Table II Zone A1, A2, RA, RE, RS, RD, RW1, RW2, R1, R2, R3, R4, R5 Presumed Ambient Noise Level Day dBA 50 and Night 40dBA and Article 6 General Noise Sec.116.01 Loud, Unnecessary and Unusual Noise.

3.3 Community Ambient Noise Protection

World Health Organization – Guidelines for Community Noise, Table 1 & Table 4.1 Guidelines Values for Community Noise in Specific Environments – Specific Environment: Inside Bedrooms 30dBA, Preschool Sleep 30dBA and School Class Rooms 35dBA.

3.4 Specific Low Frequency Noise Protection

World Health Organization – Guidelines for Community Noise, 4.2.3 Sleep Disturbance Effects states, “For noise with a large proportion of low frequency sounds a still lower guideline lower than 30dBA is recommended,” and “Since A-weighting underestimates the sound pressure level of noise with low frequency components, a better assessment of health effects would be to use C-weighting.”

3.5 American Industry Standard

The American National Standards Institute (ANSI) ANSI S12.60-2002 Acoustical Performance Criteria, Design Requirements, and Guidelines for Schools, Table 1 pg. 5 for Learning space 35dBA.

4.0 Technical Approach

Community On-Site Monitoring Technical Approach TBD.

5.0 Real Time Ambient Noise Level Monitoring

5.1 Real Time Ambient Noise Level Monitoring shall as a minimum measure Leq, L10, Ldn, Lmax, SEL and CNEL. A-Frequency Weighting and C-Frequency Weighting shall be monitored and recorded.

5.2 All measurements must be continuous and recorded.

6.0 Real Time Noise Sound Recording

6.1 Real time ambient noise shall be recorded to determine source and types of noises.

6.2 Noise sound recording will be continuous non-stop recording either analog or digital 24hrs. per day with digital preferred.

7.0 Noise Sound Level Meter

7.1 The Noise Sound Level Meter shall be a Type I to ANSI S1.4-1998 or most recent revision.

7.2 A Sound Level Meter with data-logging capability for recording a minimum of 24 hrs. continuously recording and 7 days non-stop is preferred.

7.3 A Sound Level Meter capable of recording ambient noise sound a minimum of 24 hrs. continuously and 7 days non-stop is preferred.

7.4 Sound Level Meters, Data Logging and Sound Recording Equipment and accessories must be capable of withstanding outdoor inclement weather.

8.0 Noise Monitoring Locations

Locations TBD.

9.0 Noise Monitoring

Protocol TBD

10.0 Noise Monitoring Schedule

Schedule TBD.

11.0 Frequency of Noise Monitoring

11.1 Measurements shall as a minimum be every 15 minutes for 24hrs. per day or as may be determined necessary.

12.0 Equipment Calibration

12.1 Equipment calibration shall be traceable to the National Bureau of Standards and the American National Standards Institute (ANSI) S1.4-1998 or most recent revision.

12.2 Records shall be maintained and provided upon request.

13.0 Equipment Inspection & Monitoring

On-Site Equipment Inspection & Monitoring Plan TBD.

14.0 Record Keeping Procedures

Procedures TBD.

15.0 Noise Monitoring Quality Assurance

QA Plan TBD.

16.0 Noise Monitoring Reports

Noise Monitoring Reports will be produced monthly, quarterly and annually.

17.0 Data Analysis & Review

Format TBD.

18.0 Corrective Action

CA TBD.

Noise Appendix N – 8

NOISE CONTROL ACT OF 1972

HISTORY: Public Law 92-574, Oct. 27, 1972; 86 Stat. 1234; 42 USC 4901 et seq.; Amended by PL 94-301, May 31, 1976; PL 95-609, Nov. 8, 1978; PL 100-418, Aug. 23, 1988

SEC. 1 [42 U.S.C. 4901 nt], Short Title.

This Act may be cited as the "Noise Control Act of 1972."

SEC. 2 [42 U.S.C. 4901] Findings and Policy.

(a) The Congress finds--

(1) that inadequately controlled noise presents a growing danger to the health and welfare of the Nation's population, particularly in urban areas;

(2) that the major sources of noise include transportation vehicles and equipment, machinery, appliances, and other products in commerce; and

(3) that, while primary responsibility for control of noise rests with State and local governments, Federal action is essential to deal with major noise sources in commerce control of which require national uniformity of treatment.

(b) The Congress declares that it is the policy of the United States to promote an environment for all Americans free from noise that jeopardizes their health or welfare. To that end, it is the purpose of this Act to establish a means for effective coordination of Federal research and activities in noise control, to authorize the establishment of Federal noise emission standards for products distributed in commerce, and to provide information to the public respecting the noise emission and noise reduction characteristics of such products.

SEC. 3 [42 U.S.C. 4902] Definitions.

For purposes of this Act:

(1) The term "Administrator" means the Administrator of the Environmental Protection Agency.

(2) The term "person" means an individual, corporation, partnership, or association, and (except as provided in sections 11(e) and 12(a)) includes any officer, employee, department, agency, or instrumentality of

Noise Public Health Impact Studies

Abel, K., „Noise Pollution in the Classroom.“ Family Education

Ando, Y., „Effects of daily noise on fetuses and cerebral hemisphere specialization in children.“ *Journal of Sound & Vibration*, Dec. 1988

Arnberg, P. W., O. Bennerhult, et al. (1990). "Sleep disturbances caused by vibrations from heavy road traffic." *J Acoust Soc Am* 88(3): 1486-93. Also see abstract from: Griefahn, B. and M. Spreng (2004). "Disturbed sleep patterns and limitation of noise." *Noise Health* 6(22): 27-33.

Attitudes to Noise From Aviation Sources in England, MVA Consultancy, October 2007.

Babisch, W. (2005). "Noise and health." *Environmental Health Perspectives* 113(1): A14-5.

Babisch, W., B. Beule, et al. (2005). "Traffic noise and risk of myocardial infarction." *Epidemiology* 16(1): 33-40.

Berglund, B., Lindvall, T., Schwela, D.H., Guidelines for Community Noise, world health organization April, 1999.

Booz-Allen & Hamilton Inc., FAA, Office of Environment & Energy, The effects of Airport noise on housing values: A summary report, Sep. 1994

Bronzaft, A. (2003). "United States aviation transportation policies ignore health hazards of airport-related noise." *World Transport Policy & Practice* Vol 9, Number 1

Cohen, S., Krantz, D.S., Evans, G.W., Stokols, D., "Cardiovascular and Behavioral Effects of Community Noise." *American Scientist*, Vol. 69, No. 5 Sep. 1981 pp 528-535.

Cohen, S., Evans, G.W., Krantz, D.S., Stokols, D., "Physiological, Motivational and Cognitive Effects of Aircraft Noise on Children.", *American Psychologist*, March 1980, Vol. 35, No. 3, 231-243.

De Jongh et al., 2003 R.F. De Jongh, K.C. Vissers, T.F. Meert, L.H. Booij, C.S. De Deyne and R.J. Heylen, Sustained sleep restriction reduces emotional and physical well-being. *Pain*, Volume 119, Issue 1-3, Pages 56-64.

Dugan, E., "Children suffer in classrooms with poor acoustics." *The Independent*. May 2011.

Dunne, D.W., "New Standards Should Help Children in Noisy Classrooms." *Education World* April 2000

Ehrlich, G., "New classroom acoustic standard-ANSI S12.60-2002," Wyle Laboratories, Oct. 2003

Espey, M., Lopez, H., The Impacts of Airport Noise & Proximity on Residential Property Values, Dec. 2002, *Growth and Change*, Vol. 31, issue 3, pp 408-419 2000

- Evans, G.W., Hygge, S., Bullinger, M., Chronic Noise and Psychological Stress." American Psychological Society:Vol.6, No.6 (Nov., 1995),pp333-338.
- Fath, J.M., Bloomquist, D.S., Heinen, J.M., Tarica, M., 1974. Measurements of railroad noise ± line operation, yard boundaries, and retarders. Report No. NBSIR 74±488, US Environmental Protection Agency, Office of Noise Abatement and Control, Washington, D
- Federal Highway Administration (Apr 2000). "Highway Traffic Noise in the United States."
- Forkenbrock, D.J., Comparison of external costs of rail and truck freight transportation, Public Policy Center, May 2001, Vol. 35, Issue 4,321-337.
- Franssen, E. A., C. M. van Wiechen, et al. (2004). "Aircraft noise around a large international airport and its impact on general health and medication use." Occupational Environmental Medicine 61(5): 405-13.
- Gan, W. Q., Changes in Residential Proximity to Road Traffic and the Risk of Death from Coronary Heart Disease, Epidemiology 2010; 21(5):642-649.
- Goines, L., Hagler, L., "Noise Pollution: A modern Plague." Southern Medical journal, Vol. 100, No. 3, March 2007.
- Gukelberger, D., "A new standard for Acoustics in the Classroom." Engineers Newsletter, 2003, Vol. 32, No.1.
- Haack, M., Sanchez, E., Mullington, J.M., Elevated inflammatory markers in response to prolonged sleep restriction are associated with increased pain experience in healthy volunteers. Beth Isreal Deaconess Medical Centre and Harvard Medical School, Boston. Sleep 2007;30(9):1145-52.
- Haines, M.M., Stansfeld, S.A., Job, R.F.S., Berglund, B. & Head, J. (2001a). Chronic aircraft noise exposure, stress responses mental health and cognitive performance in school children. Psychological Medicine, 31, 265-277.
- Haines, M.M., Stansfeld, S.A., Job, R.F.S, Berglund, B. & Head, J. (2001b). A follow-up study of the effects of chronic aircraft noise exposure on child stress responses and cognition. International Journal of Epidemiology, 30, 839-845.
- Haines, M.M., Brebntnall, SL, Stansfield,SA., Lineberg, EK., "Qualitative responses of children to environmental noise." Noise&Health2003;5:19-30
- Haines, M.M., Stansfeld, S.A., Brentnall, S., Head, J., Berry, B., Jiggins, M., & Hygge, S. (2001c). West London Schools Study: the effect of chronic aircraft noise exposure on child health. Psychological Medicine, 31, 1385-1396.
- Haines, M.M., Stansfield, S. A., et al. Aircraft and road traffic noise and children's cognition and health: a cross-national study. The Lancet, Vol 365, June 4th, 2005.

- Hall, F.L., Breston, B.E., Taylor, S.M., Effects of highway noise on residential property values, Transportation Research Board, 1978, Issue No. 686, 38-43.
- Hansen, C.H., The Effects of Low-Frequency Noise & Vibration on People, University of Adelaide, 2007, 416 pgs.
- Hanson, C.E., Saurenman, H.J., Towers, D.A., 1991. Rail transportation noise and vibration. In: Harris, C.M. (Ed.), Handbook of Acoustical Measurements and Noise Control. McGraw-Hill, New York, pp. 46.1±46.23
- Hygge, S., "Classroom experiments on the effects of different noise sources and sound levels on long-term recall and recognition in children." Applied Cognitive Psychology, Vol.17, Issue 8, pp 895-914 Dec. 2003
- Integrated Working Group Letter to EPA; BTH; CARB re: "... Impacts in Goods Movement Action Plan (Feb 28, 2006)
- Jakovljevic, B., Paunovic, K., Belojevic, G., Road-traffic noise and factors influencing noise annoyance in an urban population, Environment International. 2009; 35(3): 552-556
- Jarup, L., M. L. Dudley, et al. (2005). "Hypertension and Exposure to Noise near Airports (HYENA): study design and noise exposure assessment." Environmental Health Perspectives 113(11): 1473-8.
- Kawada, T. (2004). "The effect of noise on the health of children." J Nippon Medical School 71(1): 5-10.
- Krähe, D., Why can low-frequency noise be extremely unpleasant? | [Warum kann tieffrequenter Lärm außergewöhnlich unangenehm sein?], Lärmbekämpfung. 2008; 3(2): 71-78
- Landon, P., P. Breyse, et al. (2005). "Noise exposures of rail workers at a North American chemical facility." American Journal Ind Medicine 47(4): 364-9.
- Lercher, P., Evans, G.W., Meis, M., Kofler, W.W., "Ambient neighborhood noise and children's mental health," Occupational Environmental Medicine, 2002;59:380-386.
- Leventhall, G., Low frequency noise. What we know, what we do not know, and what we would like to know, Journal of Low Frequency Noise Vibration and Active Control. 2009; 28(2): 79-104
- Lundquist, P., Holmberg, K., Landstrom, U., "Annoyance and effects on work from environmental noise at school." Noise&Health, Jan.2000., BVol. 2, Issue 8, pp39-46
- Miedema, H. M. and C. G. Oudshoorn (2001). "Annoyance from Transportation Noise: Relationships with Exposure Metrics DNL and DENL and Their Confidence Intervals." Environmental Health Perspectives 109(4): 409-416.
- Miller, N. P. (2005). "Addressing the Noise from U.S. Transportation Systems, Measures and Countermeasures." TR News(240):4-16.
- Miller, T., Viner, J., Rossman S., Pindus N., Gellert W., Douglass J., Dillingham, A., Blomquist, G., 1991. The cost of highway crashes. Report No. FHWA±RD±91±055, US Department of Transportation, Federal Highway Administration, Washington, DC
- Nelson, J.P., Highway noise and property values, Journal of Transport Economics & Policy, Vol.16, No.2, May 1982, pp117-138.
- Nelson, P., Kohnert, K., Sabor, S., "Classroom Noise and Children Learning Through a Second Language." Schools, vol.36, 219-229, July 2005

- Norlander, T., Moas, L., Archer, T., "Noise and Stress in Primary and Secondary School Children: Noise Reduction and Increased Concentration Ability Through a Sort but Regular Exercise and Relaxation Program." *Web of Science* Vol. 16, Issue 1, 2005, pp91-99
- Ollerhead, J.B. et al. Report of a field study of aircraft noise and sleep disturbance. DfT for the UK Department of Safety, Environment and Engineering, CAA, December 1992.
- Pawlaczyk-Luszczynska, M., Dudarewicz, A., Szymczak, W., Sliwinska-Kowalska, M., Evaluation of annoyance from low frequency noise under laboratory conditions, *Noise and Health*. 2010; 12(48): 166-181.
- Porter, D.N., Berry, B. F., Flindell, I.H., Health Effect Based Noise Assessment Methods: A Review and Feasibility Study. National Physical Laboratory, NPL Report CMAM 16, Sept. 1998.
- Prudence, A., Allen, C., Baker, M., "Impact of Classroom Noise on Reading and Vocabulary Skills in Elementary School-Aged Children." 147th ASSA Meeting, NY, NY May, 2004.
- Remington, P. J., J. S. Knight, et al. (2005). "A hybrid active/passive exhaust noise control system for locomotives." *J Acoust Soc Am* 117(1): 68-78.
- Sanz, S.A., "Road traffic noise around schools: a risk for pupil's performance," *Intl. Archives of Occupational & Environmental Health*, Vol. 65, No. 3, 2005-2007
- Shield, B.M., Dockwell, J.E., "The effects of environment and classroom noise on the academic attainment of primary school children." *J Acoust Soc AM* 2008 Jan: 12391: 133-44.
- Shield, B.M., Dockwell, J.E., "The effects of noise on children at school: A review.", *Journal Building Acoustics*, 2003, Vol. 10(2): 97-106.
- Skarberg, A. and E. Ohrstrom (2002). "Adverse Health Effects in Relation to Urban Residential Soundscapes." *Journal of Sound and Vibration* 250(1): 151-155.
- Spreng, M. Noise induced nocturnal cortisol secretion and tolerable overhead flights. Dept. Physiology, University of Erlangen, Germany. *Noise Health* 2004; 6(22): 35-47
- Slater, B.R., "Effects of Noise on Pupil Performance." *Journal of Educational Psychology*, Vol. 59(4), Aug. 1968, 239-243.
- Sohn, E., "Background Noise Hurts Test Schools." *Discovery News* Nov. 2011.
- Standled, S.A., Berlund, B., Clark, C., Lopez-Barrio, I., Fisher, P., Ohrstrom, E., Haines, H.H., Head, J., Hygge, S., Van Kemp, I., "Aircraft and road traffic noise and children's cognition and health: a cross-national study." *The Lancet*, Vol. 365 1942-49, June 2005
- Stabsfeld, S.A., Matheson, M.P., "Noise pollution: non-auditory effects on health." *British Medical Bulletin*, 2003, Vol. 68: 243-257.
- Takahashi, Y. A study on the contribution of body vibrations to the vibratory sensation induced by high-level, complex low-frequency noise, *Noise and Health*. 2011; 13(50): 2-8

Transportation Research Board, (2005) "Noise & Vibration Committee Conference"

Terminal 5 Rebuttal by Professor Holland which included a critique by Dr. B. Berglund (see refs. 1,2 and 3 above).

Brigitta Berglund is a joint author of the WHO Community Noise Report.

Transportation Research Board, "Transportation Noise: Measures and Countermeasures" TR NEWS Number 240 (Sep-Oct 2005)

Wilson Committee on the Problem of Noise, Noise: Final Report, Cmnd 2056, London, HMSO, 1963.

Wyle Laboratories, Guide to using Supplemental Metrics, Appendix A, Effects of Noise on People-Review of Scientific Research, Policy and Guidelines., Dec. 2009.

Van Kempen, E.E.M.M., Van Kamp,L., Stellato,R.K., Lopez-Barrio,I.,Haines,M.M., Nilsson, M.E., "Childrens annoyance reaction to aircraft and road noise." Journal of the Acoustical Society of America, 2009;125(2):895-904.

Air Quality Appendices

AQ-1 Expert Witness Letter Dr. Jonathan Heller, PHD

AQ-2 Jonathan Heller CV

AQ-3 Health Impact Assessment Information

AQ-4 Medical Health Studies Index A-1 / A-10

January 27, 2012

Jesse N. Marquez
Executive Director
Coalition For A Safe Environment
1601 N. Wilmington Blvd.
Wilmington, CA 90744

Dear Mr. Marquez,

This letter describes why, in the opinion of Human Impact Partners, Environmental Impact Reports under the California Environmental Quality Act (CEQA) and Environmental Impact Statements the National Environmental Protection Act (NEPA) require a comprehensive analysis of health, how Health Impact Assessments (HIAs) can be conducted to address that requirement, and how Health Risk Assessments (HRAs) as currently conducted do not meet that requirement and are different from HIAs.

About Human Impact Partners (HIP)

Founded in June 2006, Human Impact Partners is an independent non-profit corporation (501(c)3) based in Oakland, California. HIP's mission is to increase the consideration of health and equity in decision-making. In doing so, we work to transform the policies and places people need to live healthy lives. As research indicates that approximately 55% of health status is determined by social and environmental conditions, the fundamental premise of our work is that decision-makers must understand how community-level factors, such as housing, land use, and transportation systems affect health and health disparities in order to take action to improve those conditions, and thereby improve health.

While it seems commonsense that major decisions regarding land use and transportation planning should incorporate health considerations, mechanisms for doing so often do not exist, and local and regional agencies do not have the resources or expertise to incorporate health into planning-related decisions. HIP is addressing this through its work conducting Health Impact Assessments and similar health-based analyses in collaboration with government agencies and community organizations, with a focus on communities facing health disparities. Human Impact Partners has conducted HIAs and similar analyses on the local, state and federal levels – with experience in communities across the country, from California to Maine. Our findings have been integrated into policy-making, planning and projects. To date, HIP has conducted over fifteen HIAs on land use and transportation plans and development projects.

Health Impact Assessments

Understanding and consideration of health and equity consequences of land use, transportation, goods movement, and other decisions and of potential mitigations to adverse consequences could yield policies, plans, and projects that result in better outcomes for all, but especially for vulnerable populations that currently face inequities. HIA is a public engagement and decision-support tool that can be used to assess the

health impacts of planning and policy proposals, and make recommendations to improve health outcomes associated with those proposals. In a recent book by the National Research Council, HIA is formally defined as “a systematic process that uses an array of data sources and analytic methods and considers input from stakeholders to determine the potential effects of a proposed policy, plan, program or project on the health of a population and the distribution of those effects within the population. Health impact assessment provides recommendations on monitoring and managing those effects.”¹

Environmental, social, demographic, and economic conditions drive the health and wellbeing of communities. Factors such as housing, transportation, employment and income, noise, air quality, access to goods and services, access to parks, and social networks have well-demonstrated and reproducible links to health outcomes. An HIA analyzes health from a broad perspective by evaluating how a proposed project, plan, or policy affects these factors – often collectively referred to as “determinants of health” in the public health literature – and in turn, how impacts to these factors are likely to positively or adversely influence health.

Overall, the information from an HIA, and close collaboration between public health experts, affected communities, and the decision-makers on a project, lead to practical, evidence-driven recommendations that address identified health concerns to the extent possible within the limitations of the regulatory or decision-making process. Conducting an HIA can offer many benefits:

- HIAs provide sound, objective data on health impacts. By using this information, potentially unexpected health consequences and unanticipated costs can be identified and thus avoided.
- HIA helps develop healthier communities by identifying design solutions that address the root causes of many prominent health problems like asthma, diabetes, and cardiovascular disease.
- The HIA process can be used to build consensus and buy-in by addressing the affected community’s fears about a project directly and transparently and by providing practical solutions.
- HIAs help focus community involvement on real health concerns and on feasible mitigations to those health issues.
- Health issues are typically important to community members and HIA can serve to engage community residents in decisions that impact their lives.
- HIAs give project proponents a way to recognize positive health contributions of projects on communities. It also given businesses the information they need to distinguish themselves as smart planners and build positive working relationships with the community.
- HIAs help decision-makers by ensuring that any potential concerns about a project are identified and addressed early on.

HIA may use both qualitative and quantitative data and methods to predict potential impacts. Where feasible and data allows, HIA uses quantitative modeling to increase the precision of analysis and to support significance judgments. Because of substantial data requirements, using quantitative forecasting methods exclusively may

¹ National Research Council (NRC). 2011. Improving Health in the United States: The Role of Health Impact Assessment. Available at: http://www.nap.edu/catalog.php?record_id=13229.

present a partial or biased accounting of health effects. Quantification can also be resource intensive and divert from other impact assessment activities. Qualitative analyses provide valuable data when quantitative analyses are not possible.

In 2011, the National Research Council of the National Academies of Science formed a Committee on Health Impact Assessment and released a book entitled Improving Health in the United States: The Role of Health Impact Assessment.² The book provides guidance on conducting HIAs and makes a strong case that HIAs should be integrated into the environmental review process. Additionally, The North American Health Impact Assessment Working Group released a second edition of practice standards for conducting HIAs in 2010. Those standards are attached to this letter.

The Human Impact Partners website (<http://www.humanimpact.org/>) contains information, tools, and resources regarding HIA. Other good resources include the Centers for Disease Control website (<http://www.cdc.gov/healthyplaces/hia.htm>), the Health Impact Project website (www.healthimpactproject.org), and the UCLA HIA Clearinghouse website (<http://www.ph.ucla.edu/hs/hiaclhc/>).

NEPA and CEQA require a comprehensive analysis of health impacts and HIA is a tool that can fill this requirement

As stated in “Public Health Analysis Under the National Environmental Policy Act”, a white paper by Aaron Wernham (the Director of the Health Impact Project, a collaboration of the Robert Wood Johnson Foundation and the Pew Charitable Trusts) and Dinah Bear (former General Counsel for the Council on Environmental Quality):

The inclusion of a robust, systematic approach to public health is supported by NEPA, the regulations issued by the Council on Environmental Quality (CEQ), the agency in the Executive Office of the President charged with overseeing implementation of NEPA, Executive Orders 12898 and 13045, and available guidance on NEPA and environmental justice.

Congressional Intent

In using the term “human environment,” Congress signaled that protection of human communities was a fundamental purpose of the legislation. In the debates leading to NEPA’s enactment, Senator Henry Jackson stated: “When we speak of the environment, basically, we are talking about the relationship between man and these physical and biological and social forces that impact upon him. A public policy for the environment basically is not a public policy for those things out there. It is a policy for people.”

Health in NEPA

NEPA mentions health a total of six times. Among NEPA’s fundamental purposes is: “promote efforts which will prevent or eliminate damage to the environment and biosphere and stimulate the health and welfare of man.” NEPA § 102 [42 USC § 4321]

NEPA is intended, furthermore, to: “assure for all Americans safe, healthful, productive, and aesthetically and culturally pleasing surroundings.” [42 USC § 4331]

And finally to: “attain the widest range of beneficial uses of the environment without degradation, risk to health or safety, or other undesirable and unintended consequences.” [42 USC § 4331]

Health in the CEQ Regulations

² National Research Council (NRC). 2011. Improving Health in the United States: The Role of Health Impact Assessment. Available at: http://www.nap.edu/catalog.php?record_id=13229.

Several general provisions of CEQ's NEPA regulations support the inclusion of health.

First, agencies respond to substantive public concerns in the draft EIS [40 CFR § 1503.4]. When, therefore, an agency can anticipate substantive health concerns based on scoping, it is sensible to include these issues for analysis in the DEIS.

Second, in determining whether an effect may be significant (and therefore require analysis in the EIS) one of the factors that agencies should consider is "the degree to which the effects on the human environment are likely to be highly controversial" [40 CFR § 1508.27 (b) 4]. Commonly, health often figures among the strongest concerns expressed by affected communities.

The CEQ regulations also specifically define health as one of the effects that must be considered in an EIS or an EA. In defining "effects," the regulations state that: "Effects" includes ecological, aesthetic, historic, cultural, economic, social, or health, whether direct, indirect, or cumulative." [40 C.F.R. § 1508.8] And, the regulations instruct agencies to consider "the degree to which the proposed action affects public health or safety" in determining significance. [40 C.F.R. § 1508.27]

Health in Executive Orders

Executive Order 12898 instructs agencies to: "make achieving environmental justice part of its mission by identifying and addressing, as appropriate, disproportionately high and adverse human health or environmental effects of its programs, policies, and activities on minority populations and low-income populations in the United States."

Similarly, Executive Order 13045 states that agencies must: "make it a high priority to identify and assess environmental health risks and safety risks that may disproportionately affect children; and ... shall ensure that its policies, programs, activities, and standards address disproportionate risks to children that result from environmental health risks or safety risks."

Statements relevant to NEPA-based health analysis in Federal Guidance

CEQ guidance on implementing Executive Order 12898 contains several suggestions relevant to public health analysis, including:

- Lead agencies should involve public health agencies and clinics
- Agencies should review relevant public health data (as for any other resource)
- Agencies should consider how interrelated cultural, social, occupational, historical, or economic factors may contribute to health effects of the proposed action and alternatives.

The California Environmental Quality Act contains similar requirements for conducting comprehensive health analyses. Potentially significant impacts on health trigger Environmental Impact Reports:

*A lead agency shall find that a project may have a significant effect on the environment and thereby require an EIR to be prepared for the project where there is substantial evidence, in light of the whole record, that any of the following conditions may occur ... (4) **The environmental effects of a project will cause substantial adverse effects on human beings, either directly or indirectly.** (CCR§15065(a))*

EIRs under CEQA must discuss public health impacts:

*The discussion should include relevant specifics of the area, the resources involved, physical changes, alterations to ecological systems, and changes induced in population distribution, population concentration, the human use of the land (including commercial and residential development), **health and safety problems** caused by the physical changes, and other aspects of the resource base such as water, historical resources, scenic quality, and public services. (CCR§15126.2(a))*

Several court opinions in California support the inclusion of health impacts in EIRs, including, for example, *Bakersfield Citizens for Local Control vs. City of Bakersfield* (2004) and *Californians for Alternatives to Toxics v. CDFA* (2005).

Jonathan C. Heller
304 12th Street, Suite 3B
Oakland, CA 94607
(510) 452 9442 (o)
jch@humanimpact.org

Education

University of California Berkeley, CA
1993 - 1997. Ph.D., Biophysics. Howard Hughes Fellow. Dissertation: "Solid-State Nuclear Magnetic Resonance Studies of Prion Proteins and Peptides." Advisor: Professor David Wemmer; Collaborators: Professors Alexander Pines and Stanley Prusiner. Experience in structural biology, protein chemistry, molecular biology and physical chemistry.

Harvard University Cambridge, MA
1985 - 1989. B.A., *Cum Laude*, Applied Mathematics.

Experience

Human Impact Partners Executive Director & Co-founder
May 2006 – Present. HIP, a non-profit, believes that health should be considered in all decision making. We raise awareness of and collaboratively use innovative data, processes and tools that evaluate health impacts and inequities in order to transform the policies, institutions and places people need to live healthy lives. Through training and mentorship we also build the capacity of impacted communities and their advocates, workers, public agencies, and elected officials to conduct health-based analyses and use them to take action. To pursue this mission, we are applying Health Impact Assessment as our primary approach to identifying and mitigating adverse policy and development impacts on health.

Responsibilities

- Carry out all aspects of Health Impact Assessments (HIAs) including: outreach to communities, working with residents of communities and staff of community organizations, forming stakeholder groups and collaborations, leading/facilitating HIA meetings, collaborating with and informing county health departments and elected officials, screening and scoping projects, research, reporting, evaluation;
- Conduct HIA training and mentoring;
- Strategic planning;
- Grant writing and other fundraising;
- Legislative strategy development;
- Overseeing day-to-day operations of HIP;
- Personnel management.

Accomplishments

- Built relationships and secured funding for carrying out HIAs across California, in other states, and at the federal level;
- Built HIP to a staff of 8 FTEs;
- Completed over 15 HIAs on land use, transportation and other policies;
- Improved health outcomes for several plans and projects and built awareness regarding the connections between health and policy among elected officials and the general public;
- Conducted over 20 HIA trainings and provided technical assistance to over 15 organizations, nation-wide, conducting HIAs.

Predicant Biosciences

Vice President, Information and Project Planning

Mar. 2002 – Dec. 2005. Predicant developed a novel platform to transform patient care by providing physicians a clinically reliable method of detecting, diagnosing and monitoring complex disease states through the analysis of protein patterns in blood. We developed an integrated system incorporating proprietary separation, detection and informatics technologies to provide reliable, reproducible and sensitive measurements for protein pattern discovery and clinical assay. I was the first employee at Predicant and participated in founding the company.

Responsibilities

- Provided technical leadership in informatics, pattern recognition, and bioanalytical chemistry as well as overall company leadership (business, IP, cultural, etc.);
- Project planning and management – developed strategy and timelines for research and development towards product introduction;
- Business development – in-licensing, clinical sample acquisition, collaboration with academic labs, and assessment of external technologies and opportunities for partnership;
- Intellectual property – led company's efforts in working with counsel to patent novel technologies;
- Communication and presentation – developed and delivered key presentations to Board of Directors, potential investors, potential corporate partners, and scientific community;
- Management of 11 employees.

Accomplishments

- Built company to ~50 employees (including hiring a CEO); raised ~\$37M of funding from 4 top-tier venture capital firms; established cooperative, collaborative company culture;
- Led planning and development of a novel microfluidics-mass spectrometry based diagnostics platform and data analysis methods; set key performance characteristics for components and the platform (e.g. reproducibility, sensitivity) and designed system characterization plan to demonstrate that the platform met specifications;
- Designed studies, acquired samples for and led first clinical studies that led to the discovery of protein biomarkers in prostate cancer and lung cancer;
- Developed corporate strategies (e.g. technology, business, IP, hiring, etc.) and business plan;
- Led in-licensing efforts to allow us freedom-to-operate and to build a competitive advantage;
- Represented company in Congressional hearings.

SurroMed*Oct. 2000 – Mar. 2002.*

Director, Informatics

Exelixis*Dec. 1999 – Sept. 2000.*

Research Scientist II

Dec. 1998 – Nov. 1999.

Research Scientist I

Sept. 1997 – Nov. 1998.

Associate Research Scientist II

Peace Corps, Papua New Guinea

Volunteer

1990 – 1992. Taught high school science and mathematics. Chaired science department. Supervised dormitories for 150 boarding students. Raised funds and initiated construction of school water supply. Had chloroquine-resistant malaria twice.

Awards

1993 – 1997. Howard Hughes Medical Institute Predoctoral Fellow
1993. National Science Foundation Fellowship (declined)
1987 and 1989. Harvard College Scholarship

Publications

J. Heller, R. Larsen, A.C. Kolbert, M. Ernst, M. Baldwin, S.B. Prusiner, D.E. Wemmer, A. Pines. (1996) Application of rotational resonance to inhomogenously broadened systems. *Chem. Phys. Lett.*, **251**, 223.

J. Heller, A.C. Kolbert, R. Larsen, M. Ernst, T. Bekker, M. Baldwin, S.B. Prusiner, A. Pines, D.E. Wemmer. (1996) Solid-state NMR studies of the prion protein H1 fragment. *Protein Science*, **5**, 1655.

J. Heller, D.D. Laws, M. Tomaselli, D.S. King, D.E. Wemmer, A. Pines, R.H. Havlin, E. Oldfield. (1997) Determination of dihedral angles in peptides through experimental and theoretical studies of α -carbon chemical shielding tensors. *JACS*, **119**, 7827.

J. Heller, A. Heller. (1998) On the loss of activity or gain in stability of oxidases upon their immobilization in hydrated silica: significance of the electrostatic interactions of surface arginine residues at the entrances of the reaction channels. *JACS*, **120**, 4586.

S.B. Pierce, M. Costa, R. Wisotzkey, S. Devadhar, S.A. Homburger, A.R. Buchman, K.C. Ferguson, J. Heller, D.M. Platt, A.A. Pasquinelli, L.X. Liu, S.K. Doberstein, G. Ruvkun. (2001) Regulation of DAF-2 receptor signaling by human insulin and ins-1, a member of the unusually large and diverse *C. elegans* insulin gene family. *Genes & Dev*, **15**, 672.

S.M. Norton, P. Huyn, C.A. Hastings, J.C. Heller. (2001) Data mining of spectroscopic data for biomarker discovery. *Current Opinion in Drug Discovery & Development*, **4**, 325.

N.K. Cho, L. Keyes, E. Johnson, J. Heller, L. Ryner, F. Karim, M.A. Krasnow. (2002) Developmental Control of Blood Cell Migration by the Drosophila VEGF Pathway. *Cell*, **108**, 865.

I. Guyon, H.-M. Bitter, Z. Ahmed, M. Brown, J. Heller. (2003) Multivariate Non-Linear Feature Selection with Kernel Multiplicative Updates and Gram-Schmidt Relief. *Proceeding of the BISC FLINT-CIBI 2003 Workshop*, Berkeley, CA.

A.P. Sassi, F. Andel, H.M. Bitter, M.P. Brown, R.G. Chapman, J. Espiritu, A.C. Greenquist, I. Guyon, M Horchi-Alegre, K.L. Stults, A. Wainright, J.C. Heller, J.T. Stults. (2005) An automated, sheathless capillary electrophoresis-mass spectrometry platform for the discovery of biomarkers in human serum. *Electrophoresis*, **16**, 1500.

P. de Valpine, H.M. Bitter, M.P. Brown, **J.C. Heller**. (2009) A simulation-approximation approach to sample size planning for high-dimensional classification studies. *Biostatistics*. **10**, 424.

E.C. Harris, A. Lindsey, **J.C. Heller**, K. Gilhuly, M. Williams, B. Cox, J. Rice. Humboldt County General Plan Update Health Impact Assessment: A Case Study. *Environmental Justice*, **2**, 127.

Minimum Elements and Practice Standards for Health Impact Assessment

North American HIA Practice Standards Working Group

Version 2
November 2010

Authorship and Acknowledgements

This document represents a revision of version one of Practice Standards for Health Impact Assessment (HIA) published by the North American HIA Practice Standards Working Group in April 2009. This review and revision was conducted by a working group including the following individuals: Rajiv Bhatia,¹ Jane Branscomb,² Lili Farhang,³ Murray Lee,⁴ Marla Orenstein,⁴ and Maxwell Richardson.⁵ In producing this document, the working group solicited review and comment from participants attending the second annual HIA in the Americas Workshop held in Oakland, California in March of 2010.

¹ San Francisco Department of Public Health - San Francisco, California, USA

² Georgia Health Policy Center - Atlanta, Georgia, USA

³ Human Impact Partners - Oakland, California, USA

⁴ Habitat Health Impact Consulting - Calgary, Alberta, Canada

⁵ Public Health Institute - Oakland, California, USA (affiliation for identification purposes only)

Corresponding Authors

Rajiv Bhatia, MD, MPH
Director, Occupational & Environmental Health
San Francisco Department of Public Health
Phone: 415.252.3931
Email: rajiv.bhatia@sfdph.org

Murray Lee, MD, MPH
Habitat Health Impact Consulting
Calgary, Alberta, Canada
Phone: 403.451.0097
Email: murray@habitatcorp.com

Lili Farhang, MPH
Associate Director, Human Impact Partners
Oakland, CA
Phone: 510.740.0150
Email: lili@humanimpact.org

Habitat
HEALTH IMPACT CONSULTING



Endorsements

The following HIA practitioners and organizations are committed to utilizing these working practice standards, to the greatest extent possible, in their health impact assessment practice. These organizations are listed below:

Environmental Resources Management

Georgia Health Policy Center

Habitat Health Impact Consulting Corp.

Human Impact Partners

San Francisco Department of Public Health

University of California Berkeley Health Impact Group

Suggested Citation

North American HIA Practice Standards Working Group (Bhatia R, Branscomb J, Farhang L, Lee M, Orenstein M, Richardson M). Minimum Elements and Practice Standards for Health Impact Assessment, Version 2. North American HIA Practice Standards Working Group. Oakland, CA: November 2010.

Introduction

Health Impact Assessment (HIA) is a practice to make visible the interests of public health in decision-making. The International Association of Impact Assessment defines HIA as: *a combination of procedures, methods and tools that systematically judges the potential, and sometimes unintended, effects of a policy, plan, program or project on the health of a population and the distribution of those effects within the population. HIA identifies appropriate actions to manage those effects.* With roots in the practice of Environmental Impact Assessment (EIA), HIA aims to inform the public and decision-makers when decisions about policies, plans, programs, and projects have the potential to significantly impact human health, and to advance the values of democracy, equity, sustainable development, the ethical use of evidence and a comprehensive approach to health.

While available guidance documents for HIA describe the procedural steps and products of each stage of the HIA process, there exists considerable diversity in the practice and products of HIA due to the variety of decisions assessed, diverse practice settings, and the nascent evolution of the field. This document, a collective product of a HIA practitioners' workgroup in North America, intends to translate the values underlying HIA along with key lessons from HIA practice into specific "standards for practice" for each phase of the HIA process. Participants at the first *North American Conference on Health Impact Assessment* held in Oakland, California in September 2008 identified the development of standards as a priority need for the field. Subsequent to the 2008 conference, participants collectively developed the first version of these practice standards. This document reflects the second version of those standards, and has been revised to include a set of "minimum elements" of HIA practice.

In this document, *Minimum Elements* answer the question of "what essential elements constitute an HIA"; this is distinct from *Practice Standards*, which answer the question, "how to best conduct an HIA."

Minimum Elements can serve as a basis to identify and promulgate examples of HIA within the field of practice and in broader social discourse, distinguishing HIA from other practices and methods that also aim to ensure the consideration of and action on health interests in public policy. These *Minimum Elements* apply to HIA whether conducted independently or integrated within an environmental, social or strategic impact assessment.

The *Practice Standards* are not rigid criteria for acceptability but rather guidance for effective practice. A practitioner may use the *Practice Standards* as benchmarks for their own HIA practice, to stimulate discussion about HIA content and quality, and to evaluate this emerging field.

These standards are intended support the development and institutionalization of HIA, and are aligned with the central concepts and suggested approaches described in the World Health Organization's 1999 Gothenburg Consensus Paper on HIA, a guiding document in the HIA field. The members of the North American HIA Practice Standards Working Group recognize that real-world constraints and varying levels of capacity and experience will result in appropriate and ongoing diversity of HIA practice. Every practice standard in this document may not be achieved in every example of HIA. Overall, we hope that these standards will be viewed as relevant, instructive and motivating for advancing HIA quality.

Minimum Elements of HIA

A health impact assessment (HIA) must include the following minimum elements, which together distinguish HIA from other processes. An HIA:

1. Is initiated to inform a decision-making process, and conducted in advance of a policy, plan, program, or project decision;
2. Utilizes a systematic analytic process with the following characteristics:
 - 2.1. Includes a scoping phase that comprehensively considers potential impacts on health outcomes as well as on social, environmental, and economic health determinants, and selects potentially significant issues for impact analysis;
 - 2.2. Solicits and utilizes input from stakeholders;
 - 2.3. Establishes baseline conditions for health, describing health outcomes, health determinants, affected populations, and vulnerable sub-populations;
 - 2.4. Uses the best available evidence to judge the magnitude, likelihood, distribution, and permanence of potential impacts on human health or health determinants;
 - 2.5. Rests conclusions and recommendations on a transparent and context-specific synthesis of evidence, acknowledging sources of data, methodological assumptions, strengths and limitations of evidence and uncertainties;
3. Identifies appropriate recommendations, mitigations and/or design alternatives to protect and promote health;
4. Proposes a monitoring plan for tracking the decision's implementation on health impacts/determinants of concern;
5. Includes transparent, publicly-accessible documentation of the process, methods, findings, sponsors, funding sources, participants and their respective roles.

HIA Practice Standards

Adherence to the following standards is recommended to advance effective HIA practice:

1. General standards for the HIA process

- 1.1. An HIA should include, at a minimum, the stages of **screening, scoping, assessment, recommendations, and reporting** described below.
- 1.2. **Monitoring** is an important follow-up activity in the HIA process. The HIA should include a follow-up monitoring plan to track the outcomes of a decision and its implementation.
- 1.3. **Evaluation** of the HIA process and impacts is necessary for field development and practice improvement. Each HIA process should begin with explicit, written goals that can be evaluated as to their success at the end of the process.
- 1.4. HIA should respect the needs and timing of the decision-making process it evaluates.
- 1.5. HIA requires integration of knowledge from many disciplines; the practitioner or practitioner team must take reasonable and available steps to identify, solicit and utilize the expertise, including from the community, needed to both identify and answer questions about potentially significant health impacts.
- 1.6. Meaningful and inclusive stakeholder participation (e.g., community, public agency, decision-maker) in each stage of the HIA supports HIA quality and effectiveness. Each HIA should have a specific engagement and participation approach that utilizes available participatory or deliberative methods suitable to the needs of stakeholders and context.
- 1.7. HIA is a forward looking activity intended to inform an anticipated decision; however, HIA may appropriately conduct or utilize analysis, or evaluate an existing policy, project or plan to prospectively inform a contemporary decision or discussion.
- 1.8. Where integrated impact assessment is required and conducted, and requirements for impact assessment include responsibility to analyze health impacts, HIA should be part of an integrated impact assessment process to advance efficiency, to allow for inter-disciplinary analysis and to maximize the potential for advancing health promoting mitigations or improvements.
- 1.9. HIA integrated within another impact assessment process should adhere to these practice standards to the greatest extent possible.

2. Standards for the screening stage

- 2.1. Screening should clearly identify all the decision alternatives under consideration by decision-makers at the time the HIA is considered.
- 2.2. Screening should determine whether an HIA would add value to the decision-making process. The following factors may be among those weighed in the screening process:
 - 2.2.1. The potential for the decision to result in substantial effects on public health, particularly those effects which are avoidable, involuntary, adverse, irreversible or catastrophic
 - 2.2.2. The potential for unequally distributed impacts
 - 2.2.3. Stakeholder and decision-maker concerns about a decision's health effects
 - 2.2.4. The potential for the HIA to result in timely changes to a policy plan, policy or program
 - 2.2.5. The availability of data, methods, resources and technical capacity to conduct analyses

Coalition For A Safe Environment

Public Health Impact Studies Index

(1.15.2011)

APPENDIX A:

| | |
|-------------------------|--|
| Appendix A-1: | Respiratory and Children's Health Study |
| Appendix A-2: | Traffic Proximity |
| Appendix A-3: | Particulate Matter |
| Appendix A-4: | Cardiovascular and Neurologic |
| Appendix A-5: | Reproductive and Developmental |
| Appendix A-6: | Cancer |
| Appendix A-7: | Noise |
| Appendix A-8: | Petroleum Industry |
| Appendix A-9: | Light Pollution |
| Appendix A – 10: | Mental Health |

- Note:
1. Primary Public Health Studies Research Conducted By: USC Southern California Environmental Health Sciences Center - Children's Environmental Health Center
 2. Petroleum Industry & light Pollution Public Health Studies Research Conducted By: Coalition For A Safe Environment
 3. List is periodically updated by the Coalition For A Safe Environment

Appendix A-1: Respiratory and Children's Health Study

Barck, C., J. Lundahl, et al. (2005). "Brief exposures to NO₂ augment the allergic inflammation in asthmatics." Environ Res 97(1): 58-66.

Delfino, R. J. (2002). "Epidemiologic evidence for asthma and exposure to air toxics: linkages between occupational, indoor, and community air pollution research." Environ Health Perspect 110 Suppl 4: 573-89.

Gauderman, W. J., R. McConnell, et al. (2000). "Association between air pollution and lung function growth in southern California children." Am J Respiratory Critical Care Medicine 162(4 Pt 1): 1383-90.

Gauderman, W. J., E. Avol, et al. (2004). "The effect of air pollution on lung development from 10 to 18 years of age." New England Journal Medicine 351(11): 1057-67.

Gauderman, W. J., E. Avol, et al. (2005). "Childhood asthma and exposure to traffic and nitrogen dioxide." Epidemiology 16(6): 737-43.

Gauderman, W. J. (2006). "Air Pollution and Children – An Unhealthy Mix." New England Journal Medicine 355(1): 78-79.

Gilliland, F. D., K. Berhane, et al. (2001). "The effects of ambient air pollution on school absenteeism due to respiratory illnesses." Epidemiology 12(1): 43-54.

Hall, J. V., V. Brajer, et al. (2003). "Economic valuation of ozone-related school absences in the South Coast Air Basin of California." Contemporary Economic Policy 21: 407-417.

Künzli, N., R. McConnell, et al. (2003). "Breathless in Los Angeles: the exhausting search for clean air." Am J Public Health 93(9): 1494-9.

McConnell, R., K. Berhane, et al. (2002). "Asthma in exercising children exposed to ozone: a cohort study." Lancet 359(9304): 386-91.

McConnell, R., K. Berhane, et al. (2003). "Prospective Study of Air Pollution and Bronchitic Symptoms in Children with Asthma." American Journal Respiratory Critical Care Medicine 168(7): 790-797.

McConnell, R., et al. (2006). "Traffic, Susceptibility, and Childhood Asthma." Environmental Health Perspectives 114(5): 766-772.

Pandya, R. J., G. Solomon, et al. (2002). "Diesel exhaust and asthma: hypotheses and molecular mechanisms of action." Environ Health Perspectives 110 Suppl 1: 103-12.

Peden, D. B. (2002). "Pollutants and asthma: role of air toxics." Environ Health Perspectives 110 Suppl 4: 565-8.

Pietropaoli, A. P., M. W. Frampton, et al. (2004). "Pulmonary function, diffusing capacity, and inflammation in healthy and asthmatic subjects exposed to ultrafine particles." Inhalation Toxicol 16 Suppl 1: 59-72.

University of Southern California - Health Science News. (2005). "Air Pollution Found to Pose Greater Danger to Health than Earlier Thought."

University of Southern California - Health Science News. (2005). "Researchers Link Childhood Asthma to Exposure to Traffic-related Pollution."

Appendix A-2: Traffic Proximity

Brauer, M., G. Hoek, et al. (2002). "Air pollution from traffic and the development of respiratory infections and asthmatic and allergic symptoms in children." Am J Respir Crit Care Med 166(8): 1092-8.

Brunekreef, B. and J. Sunyer (2003). "Asthma, rhinitis and air pollution: is traffic to blame?" Eur Respir J 21(6): 913-5.

Cyrus, J., J. Heinrich, et al. (2003). "Comparison between different traffic-related particle indicators: elemental carbon (EC), PM_{2.5} mass, and absorbance." J Expo Anal Environmental Epidemiology 13(2): 134-43.

Environmental Protection Agency (2004). "Study of Health Effects of Toxic Air Pollutants on Asthmatic Children in Huntington Park."

Gauderman, W.J. et al. (2007) "Effect of exposure to traffic on lung development from 10 to 18 years of age: a cohort study." Lancet 369(9561):571-7.

Gilliland, F. L., Y;Saxon,A; Diaz-Sanchez,D; (2004). "Effect of glutathione-S-transferase M1 and P1 genotypes on xenobiotic enhancement of allergic responses: randomised, placebo-controlled crossover study." Lancet 363: 119.

Green, R. S., S. Smorodinsky, et al. (2004). "Proximity of California public schools to busy roads." Environmental Health Perspectives 112(1): 61-6.

Lee, Y. L., C. K. Shaw, et al. (2003). "Climate, traffic-related air pollutants and allergic rhinitis prevalence in middle-school children in Taiwan." Eur Respir J 21(6): 964-70.

Nicolai, T., D. Carr, et al. (2003). "Urban traffic and pollutant exposure related to respiratory outcomes and atopy in a large sample of children." Eur Respir J 21(6): 956-63.

Van Vliet, P., M. Knape, et al. (1997). "Motor vehicle exhaust and chronic respiratory symptoms in children living near freeways." Environ Res 74(2): 122-32.

Zhu, Y., W. C. Hinds, et al. (2002). "Study of ultrafine particles near a major highway with heavy-duty diesel traffic." Atmospheric Environment 36: 4323-4335.

Zhu, Y., W. C. Hinds, et al. (2002)(2). "Concentration and Size Distribution of Ultrafine Particles Near a Major Highway." J Air & Waste Manage Assoc 52:1032-1042.

Appendix A-3: Particulate Matter

- Chalupa, D. C., P. E. Morrow, et al. (2004). "Ultrafine particle deposition in subjects with asthma." Environmental Health Perspectives 112(8): 879-82.
- Charron, A. and R. M. Harrison (2003). "Primary particle formation from vehicle emissions during exhaust dilution in the roadside atmosphere." Atmos Environ.
- Delfino, R. J., C. Sioutas, et al. (2005). "Potential role of ultrafine particles in associations between airborne particle mass and cardiovascular health." Environmental Health Perspectives 113(8): 934-46.
- Environmental Protection Agency (2004). "Air Quality Criteria for Particulate Matter Providing the Scientific Foundation for EPA Decision Making." Volumes 1 and 2.
- Fruin, S. A., A. M. Winera, et al. (2004). "Black carbon concentrations in California vehicles and estimation of in-vehicle diesel exhaust particulate matter exposures." Atmos Environ 38: 4123-4133.
- Garshick, E., F. Laden, et al. (2004). "Lung cancer in railroad workers exposed to diesel exhaust." Environmental Health Perspectives 112(15): 1539-43.
- Hauck, H., A. Berner, et al. (2003). "AUPHEP -Austrian Project on Health Effects of Particulates - general overview." Atmos Environ.
- Hauck, H., A. Berner, et al. (2003). "AUPHEP- Austrian Project on Health Effects of Particulates- general overview." Atmos Environ.
- Health Effects Institute (HEI) (2003). "Research on Diesel Exhaust and Other Particles."
- Lippmann, M., M. Frampton, et al. (2003). "The U.S. Environmental Protection Agency Particulate Matter Health Effects Research Centers Program: a midcourse report of status, progress, and plans." Environmental Health Perspectives 111(8): 1074-92.
- Mudway, I. S., N. Stenfors, et al. (2004). "An in vitro and in vivo investigation of the effects of diesel exhaust on human airway lining fluid antioxidants." Arch Biochem Biophys 423(1): 200-12.
- Nikasinovic, L., I. Momas, et al. (2004). "A review of experimental studies on diesel exhaust particles and nasal epithelium alterations." J Toxicol Environ Health B Crit Rev 7(2): 81-104.
- Salmon, L. G., P. R. Mayo, et al. (2004). "Determination of Elemental Carbon and Organic Carbon Concentrations During the Southern California Children's Health Study, 1999-2001."
- Saxon, A. and D. Diaz-Sanchez (2000). "Diesel exhaust as a model xenobiotic in allergic inflammation." Immunopharmacology 48(3): 325-7.
- Saxon, A. and D. Diaz-Sanchez (2005). "Air pollution and allergy: you are what you breathe."

Nat Immunology 6(3): 223-6.

Froines, J. R. (2006). "Health Effects of Airborne Particulate Matter." Presentation to the Southern California Association of Governments May 17, 2006.

Siegel, P. D., R. K. Saxena, et al. (2004). "Effect of diesel exhaust particulate (DEP) on immune responses: contributions of particulate versus organic soluble components." J Toxicol Environ Health A 67(3): 221-31.

Singh, M., H. C. Phuleria, et al. (2005). "Seasonal and spatial trends in particle number concentrations and size distributions at the children's health study sites in Southern California." J Expo Anal Environmental Epidemiology.

Sioutas, C. (2003). "Results from the Research of the Southern California Particle Center and Supersite (SCPCS)."

Sioutas, C., R. J. Delfino, et al. (2005). "Exposure assessment for atmospheric ultrafine particles (UFPs) and implications in epidemiologic research." Environmental Health Perspectives 113(8): 947-55.

Wallace, L. A., H. Mitchell, et al. (2003). "Particle concentrations in inner-city homes of children with asthma: the effect of smoking, cooking, and outdoor pollution." Environmental Health Perspectives 111(9): 1265-72.

Appendix A-4: Cardiovascular and Neurologic

- Hong, Y. C., J. T. Lee, et al. (2002). "Effects of air pollutants on acute stroke mortality." Environmental Health Perspectives 110(2): 187-91.
- Jerrett, M., R. T. Burnett, et al. (2005). "Spatial analysis of air pollution and mortality in Los Angeles." Epidemiology 16(6): 727-36.
- Johnson, R. L., Jr. (2004). "Relative effects of air pollution on lungs and heart." Circulation 109(1): 5-7.
- Krewski, D., R. Burnett, et al. (2005). "Mortality and long-term exposure to ambient air pollution: ongoing analyses based on the American Cancer Society cohort." J Toxicology Environmental Health A 68(13-14): 1093-109.
- Künzli, N., M. Jerrett, et al. (2005). "Ambient air pollution and atherosclerosis in Los Angeles." Environmental Health Perspectives 113(2): 201-6.
- Maheswaran, R. and P. Elliott (2003). "Stroke mortality associated with living near main roads in England and Wales: a geographical study." Stroke 34(12): 2776-80.
- Oberdorster, G. and M. J. Utell (2002). "Ultrafine particles in the urban air: to the respiratory tract--and beyond?" Environmental Health Perspectives 110(8): A440-1.
- Oberdorster, G., Z. Sharp, et al. (2004). "Translocation of inhaled ultrafine particles to the brain." Inhalation Toxicology 16(6-7): 437-45.
- Peters, A. and C. A. Pope (2002). "Cardiopulmonary mortality and air pollution." Lancet 360(9341): 1184-5.
- Pope, C. A., 3rd, M. J. Thun, et al. (1995). "Particulate air pollution as a predictor of mortality in a prospective study of U.S. adults." Am J Respiratory Critical Care Med 151(3 Pt 1): 669-74.
- Pope, C. A., R. T. Burnett, et al. (2004). "Cardiovascular mortality and long-term exposure to particulate air pollution: epidemiological evidence of general pathophysiological pathways of disease." Circulation 109(1): 71-7.
- Pope, C. Arden, Ezzati M, Dockey DW (2009). "Fine-Particulate Air Pollution and Life expectancy in the United States." The New England Journal of Medicine Jan 22; 360(4):376-386...
- Riediker, M., R. Williams, et al. (2003). "Exposure to particulate matter, volatile organic compounds, and other air pollutants inside patrol cars." Environmental Science Technology 37(10): 2084-93.
- Riediker, M., W. E. Cascio, et al. (2004). "Particulate matter exposure in cars is associated with cardiovascular effects in healthy young men." Am J Respiratory Critical Care Med 169(8):

934-40.

University of Rochester - Particulate Matter Center (2004). "Ultrafine Particles: Characterization, Health Effects and Pathophysiological Mechanisms."

Weinhold, B. (2004). "Environmental cardiology: getting to the heart of the matter." Environmental Health Perspectives 112(15): A880-7.

Appendix A-5: Reproductive and Developmental

California Air Resources Board (2004). "Particulate Air Pollution and Infant Mortality." Presentation May 20-21, 2004.

Salam, M. T., J. Millstein, et al. (2005). "Birth outcomes and prenatal exposure to ozone, carbon monoxide, and particulate matter: results from the Children's Health Study." Environmental Health Perspectives 113(11): 1638-44.

Sokol, R. Z., P. Kraft, et al. (2005). "Exposure To Environmental Ozone Alters Semen Quality." Environmental Health Perspectives.

Wilhelm, M. and B. Ritz (2005). "Local variations in CO and particulate air pollution and adverse birth outcomes in Los Angeles County, California, USA." Environmental Health Perspectives 113(9): 1212-21.

Appendix A-6: Cancer

Boffetta, P., M. Dosemeci, et al. (2001). "Occupational exposure to diesel engine emissions and risk of cancer in Swedish men and women." Cancer Causes Control 12(4): 365-74.

Cohen, A. J. (2003). "Air pollution and lung cancer: what more do we need to know?" Thorax 58(12): 1010-2.

Guo, J., T. Kauppinen, et al. (2004). "Risk of esophageal, ovarian, testicular, kidney and bladder cancers and leukemia among Finnish workers exposed to diesel or gasoline engine exhaust." Int J Cancer 111(2): 286-92.

Mack, T. (2006). "Cancers in the Urban Environment." Presentation to the Southern California Association of Governments, January 18, 2006. Book published by Elsevier Academic Press.

Mack, T. (2005). "Cancers in the Urban Environment." Presentation at NIEHS Town Meeting February 2005. Book published by Elsevier Academic Press.

Nafstad, P., L. L. Haheim, et al. (2003). "Lung cancer and air pollution: a 27 year follow up of 16 209 Norwegian men." Thorax 58(12): 1071-6.

Nicolich, M. J. and J. F. Gamble (2001). "Urban air pollution and lung cancer in Stockholm." Epidemiology 12(5): 590-2.

Pope, C. A., 3rd, R. T. Burnett, et al. (2002). "Lung cancer, cardiopulmonary mortality, and long-term exposure to fine particulate air pollution." Jama 287(9): 1132-41

Roosli, M., N. Kunzli, et al. (2003). "Single pollutant versus surrogate measure approaches: do single pollutant risk assessments underestimate the impact of air pollution on lung cancer risk?" J Occup Environ Med 45(7): 715-23.

South Coast Air Quality Management District (AQMD) (1999). "Multiple Air Toxics Exposure Study (MATES-II)."

South Coast Air Quality Management District (AQMD) (2008). "Multiple Air Toxics Exposure Study (MATES-III)."

Vineis, P., F. Forastiere, et al. (2004). "Outdoor air pollution and lung cancer: recent epidemiologic evidence." Int J Cancer 111(5): 647-52.

Appendix A-7: Noise

- Abel, K., „Noise Pollution in the Classroom.“ Family Education
- Ando, Y., „Effects of daily noise on fetuses and cerebral hemisphere specialization in children.“ Journal of Sound & Vibration, Dec. 1988
- Arnberg, P. W., O. Bennerhult, et al. (1990). "Sleep disturbances caused by vibrations from heavy road traffic." J Acoust Soc Am 88(3): 1486-93. Also see abstract from: Griefahn, B. and M. Spreng (2004). "Disturbed sleep patterns and limitation of noise." Noise Health 6(22): 27-33.
- Attitudes to Noise From Aviation Sources in England, MVA Consultancy, October 2007.
- Babisch, W. (2005). "Noise and health." Environmental Health Perspectives 113(1): A14-5.
- Babisch, W., B. Beule, et al. (2005). "Traffic noise and risk of myocardial infarction." Epidemiology 16(1): 33-40.
- Berglund, B., Lindvall, T., Schwela, D.H., Guidelines for Community Noise, world health organization April, 1999.
- Bronzaft, A. (2003). "United States aviation transportation policies ignore health hazards of airport-related noise." World Transport Policy & Practice Vol 9, Number 1
- Cohen, S., Krantz, D.S., Evans, G.W., Stokol, D., "Cardiovascular and Behavioral Effects of Community Noise." American Scientist, Vol. 69, No. 5 Sep. 1981 pp 528-535.
- Cohen, S., Evans, G.W., Krantz, D.S., Stokols, D., "Physiological, Motivational and Cognitive Effects of Aircraft Noise on Children.", American Psychologist, March 1980, Vol. 35, No. 3, 231-243.
- De Jongh et al., 2003 R.F. De Jongh, K.C. Vissers, T.F. Meert, L.H. Booij, C.S. De Deyne and R.J. Heylen, Sustained sleep restriction reduces emotional and physical well-being. Pain, Volume 119, Issue 1-3, Pages 56-64
- Dugan, E., "Children suffer in classrooms with poor acoustics." The Independent. May 2011.
- Dunne, D.W., "New Standards Should Help Children in Noisy Classrooms." Education World April 2000
- Ehrlich, G., "New classroom acoustic standard-ANSI S12.60-2002," Wyle Laboratories, Oct. 2003

Evans,G.W., Hygge, S., Bullinger, M., Chronic Noise and Psychological Stress." American Psychological Society:Vol.6, No.6 (Nov., 1995),pp333-338.

Federal Highway Administration (Apr 2000). "Highway Traffic Noise in the United States."

Franssen, E. A., C. M. van Wiechen, et al. (2004). "Aircraft noise around a large international airport and its impact on general health and medication use." Occupational Environmental Medicine 61(5): 405-13.

Gukelberger,D.,"A new standard for Acoustics in the Classroom." Engineers Newsletter, 2003, Vol. 32, No.1.

Haack, M., Sanchez, E., Mullington, J.M., Elevated inflammatory markers in response to prolonged sleep restriction are associated with increased pain experience in healthy volunteers. Beth Isreal Deaconess Medical Centre and Harvard Medical School, Boston. Sleep 2007;30(9):1145-52.

Haines, M.M., Stansfeld, S.A., Job, R.F.S., Berglund, B. & Head, J. (2001a). Chronic aircraft noise exposure, stress responses mental health and cognitive performance in school children. Psychological Medicine, 31, 265-277.

Haines, M.M., Stansfeld, S.A., Job, R.F.S, Berglund, B. & Head, J. (2001b). A follow-up study of the effects of chronic aircraft noise exposure on child stress responses and cognition. International Journal of Epidemiology, 30, 839-845.

Haines,M.M., Brebthall, SL, Stansfield,SA., Lineberg, EK.,"Qualitative responses of children to environmental noise."Noise&Health2003;5:19-30

Haines, M.M., Stansfeld, S.A., Brentnall, S., Head, J., Berry, B., Jiggins, M., & Hygge, S. (2001c). West London Schools Study: the effect of chronic aircraft noise exposure on child health. Psychological Medicine, 31, 1385-1396.

Haines, M.M., Stansfield, S. A., et al. Aircraft and road traffic noise and children's cognition and health: a cross-national study. The Lancet, Vol 365, June 4th, 2005.

Hygge,S., "Classroom experiments on the effects of different noise sources and sound levels on long-term recall and recognition in children." Applied Cognitive Psychology, Vol.17, Issue 8, pp 895-914 Dec. 2003

Integrated Working Group Letter to EPA; BTH; CARB re: "...Impacts in Goods Movement

Action Plan (Feb 28, 2006)

Jakovljevic, B., Paunovic, K., Belojevic, G., Road-traffic noise and factors influencing noise annoyance in an urban population, *Environment International*. 2009; 35(3): 552-556

Jarup, L., M. L. Dudley, et al. (2005). "Hypertension and Exposure to Noise near Airports (HYENA): study design and noise exposure assessment." *Environmental Health Perspectives* 113(11): 1473-8.

Kawada, T. (2004). "The effect of noise on the health of children." *J Nippon Medical School* 71(1): 5-10.

Krähe, D., Why can low-frequency noise be extremely unpleasant? | [Warum kann tieffrequenter Lärm außergewöhnlich unangenehm sein?], *Lärmbekämpfung*. 2008; 3(2): 71-78

Landon, P., P. Breyse, et al. (2005). "Noise exposures of rail workers at a North American chemical facility." *American Journal Ind Medicine* 47(4): 364-9.

Lercher, P., Evans, G.W., Meis, M., Kofler, W.W., "Ambient neighborhood noise and children's mental health," *Occupational Environmental Medicine*, 2002;59:380-386.

Leventhall, G., Low frequency noise. What we know, what we do not know, and what we would like to know, *Journal of Low Frequency Noise Vibration and Active Control*. 2009; 28(2): 79-104

Lundquist, P., Holmberg, K., Landstrom, U., "Annoyance and effects on work from environmental noise at school." *Noise&Health*, Jan.2000., BVol. 2, Issue 8, pp39-46

Miedema, H. M. and C. G. Oudshoorn (2001). "Annoyance from Transportation Noise: Relationships with Exposure Metrics DNL and DENL and Their Confidence Intervals." *Environmental Health Perspectives* 109(4): 409-416.

Miller, N. P. (2005). "Addressing the Noise from U.S. Transportation Systems, Measures and Countermeasures." *TR News*(240):4-16.

Nelson, p., Kohnert, K., Sabor, S., "Classroom Noise and Children Learning Through a Second Language." *Schools*, vol.36, 219-229, July 2005

Norlander, T., Moas, L., Archer, T., "Noise and Stress in Primary and Secondary School Children: Noise Reduction and Increased Concentration Ability Through a Sort but Regular Exercise and Relaxation Program." *Web of Science Vol. 16, Issue 1, 2005*, pp91-99

Ollerhead, J.B. et al. Report of a field study of aircraft noise and sleep disturbance. DfT for the UK Department of Safety, Environment and Engineering, CAA, December 1992.

Pawlaczyk-Luszczynska, M., Dudarewicz, A., Szymczak, W., Sliwiska-Kowalska, M., Evaluation of annoyance from low frequency noise under laboratory conditions, *Noise and Health*. 2010; 12(48): 166-181.

Porter, D.N., Berry, B. F., Flindell, I.H., Health Effect Based Noise Assessment Methods: A Review and Feasibility Study. National Physical Laboratory, NPL Report CMAM 16, Sept. 1998.

Prudence, A., Allen, C., Baker, M., "Impact of Classroom Noise on Reading and Vocabulary Skills in Elementary School-Aged Children." 147th ASSA Meeting, NY, NY May, 2004.

Remington, P. J., J. S. Knight, et al. (2005). "A hybrid active/passive exhaust noise control system for locomotives." J Acoust Soc Am 117(1): 68-78.

Sanz, S.A., "Road traffic noise around schools: a risk for pupil's performance," Intl. Archives of Occupational & Environmental Health, Vol.65, No.3, 2005-2007

Shield, BM, Dockwell, JE., "The effects of environment and classroom noise on the academic attainment of primary school children." J Acoust Soc AM 2008 Jan:12391):133-44.

Shield, BM, Dockwell, JE., "The effects of noise on children at school: A review.", Journal Building Acoustics, 2003, Vol.10(2):97-106.

Skarberg, A. and E. Ohrstrom (2002). "Adverse Health Effects in Relation to Urban Residential Soundscapes." Journal of Sound and Vibration 250(1): 151-155.

Spreng, M. Noise induced nocturnal cortisol secretion and tolerable overhead flights. Dept. Physiology, University of Erlangen, Germany. Noise Health 2004;6(22):35-47

Slater, B.R., "Effects of Noise on Pupil Performance." Journal of Educational Psychology, Vol.59(4), Aug. 1968, 239-243.

Sohn, E., "Background Noise Hurts Test Schools." DiscoveryNews Nov. 2011.

Standled, S.A., Berlund, B., Clark, C., Lopez-Barrio, I., Fisher, P., Ohrstrom, E., Haines, HH, Head, J., Hygge, S., Van Kemp, I., "Aircraft and road traffic noise and children's cognition and health: a cross-national study." The Lancet, Vol.365 1942-49, June 2005

Stabsfeld, S.A., Matheson, M.P., "Noise pollution: non-auditory effects on health." British Medical Bulletin, 2003, Vol.68: 243-257.

Takahashi, Y. A study on the contribution of body vibrations to the vibratory sensation induced by high-level, complex low-frequency noise, Noise and Health. 2011; 13(50): 2-8

Transportation Research Board, (2005) "Noise & Vibration Committee Conference"

Terminal 5 Rebuttal by Professor Holland which included a critique by Dr. B. Berglund (see refs. 1, 2 and 3 above). Brigitta Berglund is a joint author of the WHO Community Noise Report.

Transportation Research Board, "Transportation Noise: Measures and Countermeasures" TR NEWS Number 240 (Sep-Oct 2005)

Wilson Committee on the Problem of Noise, Noise: Final Report, Cmnd 2056, London, HMSO, 1963,
Van Kempen, E.E.M.M., Van Kamp, L., Stellato, R.K., Lopez-Barrio, I., Haines, M.M., Nilsson,
M.E., "Childrens annoyance reaction to aircraft and road noise." *Jornal of the Accoustical Society of
America*, 2009;125(2):895-904.

Appendix A-8: Petroleum Industry

Alexander FE, Patheal SL, Biondi A, Brandalise S, Cabrera ME, Chan LC, Chen Z, Cimino G, Cordoba JC, Gu LJ, Hussein H, Ishii E, Kamel AM, Labra S, Magalhaes IQ, Mizutani S, Petridou E, de Oliveira MP, Yuen P, Wiemels JL, Greaves MF (2001). Transplacental chemical exposure and risk of infant leukemia with MLL gene fusion. *Cancer Res* 61(6):2542-2546.

ATSDR (1997) Agency for Toxic Substances and Disease Registry. Toxicological Profile for Benzene. U.S. Department of Health and Human Services, September, 1997, Atlanta, GA.

Buckley JD, Robison LL, Swotinsky R, Garabrant DH, LeBeau M, Manchester P, Nesbit ME, Odom L, Peters JM, Woods WG, Hammond GD (1989). Occupational exposures of parents of children with acute nonlymphocytic leukemia: a report from the Children's Cancer Study Group. *Cancer Res* 49: 4030-4037.

CARB (1984). *Report to the Scientific Review Panel on Benzene*. Technical Support Document. California Air Resources Board, Stationary Source Division, Sacramento, California.

CARB (1995). *Statewide Summary of Ambient Organic Toxics*. California Air Resources Board, Technical Support Division, Sacramento, California.

CARB (1997). Data retrieved from ATEDS (Air Toxics Emission Data System). Run date: July 11, 1997. California Air Resources Board, Technical Support Division, Special Pollutants Emission Inventory Section. Sacramento, California.

CARB (1998). *Measuring concentrations of selected air pollutants inside California vehicles*. Research Division, California Air Resources Board, Sacramento, California.

CARB (2000). *California Ambient Toxics Monitoring Network, 1997-1999 summary statistics*. California Air Resources Board, Sacramento, California.

Ciranni R, Barale R, Marrazzini A, Loprieno N (1988). Benzene and the genotoxicity of its metabolites I. Transplacental activity in mouse fetuses and in their dams. *Mutat Res* 208:61-67.

Ciranni R, Barale R, Adler I-D (1991). Dose-related clastogenic effects induced by benzene in bone marrow cells and in differentiating spermatogonia of Swiss CD1 mice. *Mutagenesis* 6(5):417-422.

Colt JS, Blair A (1998). Parental occupational exposures and risks of childhood cancer. *Environmental Health Perspectives* 106(Suppl 3):909-925.

Prioritization of Toxic Air Contaminants - Children's Environmental Health Protection Act
October 2001

Corti M, Snyder CA (1996). Influences of gender, development, pregnancy and ethanol consumption on the hematotoxicity of inhaled 10 ppm benzene. *Arch Toxicology* 70(3-4):2009-2017.

Crump KS (1994). Risk of benzene-induced leukemia: a sensitivity analysis of the pliofilm cohort with additional follow-up and new exposure estimates. *J Toxicology Environ Health* 42(2):219-42.

Feingold L, Savitz DA, John EM (1992). Use of a job-exposure matrix to evaluate parental occupation and childhood cancer. *Cancer Causes Control* 3:161-169.

Feychting M, Plato N, Nise G, Ahlbom A (2001). Paternal occupational exposures and childhood cancer. *Environmental Health Perspectives* 109:193-196.

Finkelstein MM (2000). Leukemia after exposure to benzene: temporal trends and implications for standards. *Am J Ind Med* 38(1):1-7.

Frantz CE, Chen H, Eastmond DA (1996). Inhibition of human topoisomerase II in vitro by bioactive benzene metabolites. *Environmental Health Perspectives*. 104(Suppl 6):1319-1323.

Harper BL, Sadagopa Ramanujam VM, Legator MS (1989). Micronucleus formation by benzene, cyclophosphamide, benzo(a)pyrene, and benzidine in male, female, pregnant female, and fetal mice. *Teratog Carcinog Mutagen* 9:239-252.

Hayes RB, Yin SN, Dosemeci M, Li GL, Wacholder S, Travis LB, Li C-Y, Rothman N, Hoover RN, Linet MS, for the Chinese Academy of Preventive Medicine--National Cancer Institute Benzene Study Group. (1997). Benzene and the dose-related incidence of hematologic neoplasms in China. *J Natl Cancer Inst* 89(14):1065-1071.

Hommes FA, Everts RS, Havinga H (1978). The development of DT-diaphorase in rat liver and its induction by benzo(a)pyrene. *Biol Neonate*. 4(5-6):248-52.

Hutt AM, Kalf GF (1996). Inhibition of human DNA topoisomerase II by hydroquinone and pbenzoquinone, reactive metabolites of benzene. *Environmental Health Perspectives* 104(Suppl 6):1265-1269.

Prioritization of Toxic Air Contaminants - Children's Environmental Health Protection Act
October 2001

Kaatsch P, Kaletsch U, Meinert R, Miesner A, Hoisl M, Schuz J, Michaelis J (1998). German case control study on childhood leukaemia-- basic considerations, methodology, and summary of the results. *Klin Padiatr* 210:185-191.

Keller KA, Snyder CA (1986). Mice exposed *in utero* to low concentrations of benzene exhibit enduring changes in their colony forming hematopoietic cells. *Toxicology* 42:171-181.

Keller KA, Snyder CA (1988). Mice exposed *in utero* to 20 ppm benzene exhibit altered numbers of recognizable hematopoietic cells up to seven weeks after exposure. *Fundamental Appl Toxicology* 10(2):224-232.

Linnet MS, Ries LAG, Smith MA, Tarone RE, Devesa SS (1999). Cancer surveillance series: Recent trends in childhood cancer incidence and mortality in the United States. *J Natl Cancer Inst* 91:1051-1058.

Lowengart RA, Peters JM, Cicioni C, Buckley J, Bernstein L, Preston-Martin S, Rappaport E (1987). Childhood leukemia and parents' occupational and home exposures. *JNCI* 79:39-46.

Maltoni C, Conti B, Cotti G (1983). Benzene: a multipotential carcinogen. Results of long-term bioassays performed at the Bologna Institute of Oncology. *American Journal Ind Med* 4:589-630.

Maltoni C, Conti B, Cotti G, Belpoggi F (1985). Experimental studies on benzene carcinogenicity at the Bologna Institute of Oncology: current results and ongoing research. *Am J Ind Med* 7:415-446.

Maltoni C, Ciliberti A, Cotti G, Conti B, Belpoggi F (1989). Benzene, an experimental multipotential carcinogen: results of the long-term bioassays performed at the Bologna Institute of Oncology. *Environmental Health Perspectives* 82:109-124.

McKinney PA, Alexander FE, Cartwright RA, Parker L (1991). Parental occupations of children with leukaemia in West Cumbria, North Humberside, and Gateshead. *Br Med J* 302(6778):681-687.

NRC (1990). *Health effects of exposure to low levels of ionizing radiation*. BIER V, National Research Council Committee on the Biological Effects of Ionizing Radiation. National Academy Press: Washington, D.C.

Ning H, Kado NY, Kuzmicky PA, Hsieh DPH (1991). Benzene-induced micronuclei formation in mouse fetal liver blood, peripheral blood, and maternal bone marrow cells. *Environ Mol Mutagen* 18(1):1-5.

OEHHA (1997). *Hazard Identification of the Developmental and Reproductive Toxic Effects of Benzene*. Office of Environmental Health Hazard Assessment California Environmental Protection Agency, Sacramento, California. Draft, September, 1997, located at www.oehha.ca.gov/prop65/pdf/benzene.pdf.

OEHHA (1999a). *Air Toxics Hot Spots Program Risk Assessment Guidelines Part I The Determination of Acute Reference Exposure Levels for Airborne Toxicants*. Office of Environmental Health Hazard Assessment, California Environmental Protection Agency, Oakland, California, March 1999

OEHHA (2000a). *Public Health Goal for Benzene in Drinking Water*. Office of Environmental Health Hazard Assessment, California Environmental Protection Agency, Oakland, California. Draft, February 2000, located at www.oehha.ca.gov/water/phg/pdf/benene.pdf.

OEHHA (2000b). *Air Toxics "Hot Spots" Program Risk Assessment Guidelines Part III: Technical Support Document for the Determination of Noncancer Chronic Reference Exposure Levels*. Office of Environmental Health Hazard Assessment, California Environmental Protection Agency.

(OEHHA, 2001). Benzene. Toxicity Criteria Database. Office of Environmental Health Hazard Assessment, California Environmental Protection Agency, Sacramento, California, located at <http://www.oehha.ca.gov/risk/chemicalDB/index.asp>, accessed January 19, 2001.

Prioritization of Toxic Air Contaminants - Children's Environmental Health Protection Act
October 2001

Prioritization of Toxic Air Contaminants - Children's Environmental Health Protection Act
October 2001

Reis LAG, Smith MA, Gurney JG, Linet M, Tamra T, Young JL, Bunin GR (eds.) (1999). *Cancer Incidence and Survival among Children and Adolescents: United States SEER Program 1975-1995*, National Cancer Institute, NIH Publication 99-4649. Bethesda, MD.

Ross JA, Potter JD, Robison LL (1994). Infant leukemia, topoisomerase II inhibitors, and the MLL gene. *J Natl Cancer Inst* 86(22):1678-1680.

Ross JA, Potter JD, Reaman GH, Pendergrass TW, Robison LL (1996). Maternal exposure to potential inhibitors of DNA topoisomerase II and infant leukemia (United States): a report from the Children's Cancer Group. *Cancer Causes Control* 7(6):581-590.

Sammett D, Lee EW, Kocsis JJ, Snyder R (1979). Partial hepatectomy reduces both metabolism and toxicity of benzene. *J Toxicol Environ Health* 5(5):785-792.

Sandler DP, Ross JA (1997). Epidemiology of acute leukemia in children and adults. *Semin Oncol* 24(1):3-16.

Shaw G, Lavey R, Jackson R, Austin D (1984). Association of childhood leukemia with maternal age, birth order, and paternal occupation. A case-control study. *Am J Epidemiol* 119(5):788-795.

Sharma RK, Jacobson-Kram D, Lemmon M, Bakke J, Galperin I, Blazak WF (1985). Sister chromatid exchange and cell replication kinetics in fetal and maternal cells after treatment with chemical teratogens. *Mutat Res* 158:217-231.

Shu XO, Gao YT, Brinton LA, Linet MS, Tu JT, Zheng W, Fraumeni JF (1988). A population-based case-control study of childhood leukemia in Shanghai. *Cancer* 62:635-644.

Shu XO, Stewart P, Wen WQ, Han D, Potter JD, Buckley JD, Heineman E, Robison LL (1999). Parental occupational exposure to hydrocarbons and risk of acute lymphocytic leukemia in offspring. *Cancer Epidemiol Biomarkers Prev* 8:783-791.

Prioritization of Toxic Air Contaminants - Children's Environmental Health Protection Act
October 2001

Sexton, K; Adgate, JL.; Church, TR.; et al (2005). " Children's exposure to volatile organic compounds as determined by longitudinal measurements in blood. *Environmental Health Perspectives*, March 1, 2005..

Smith MT, Zhang L (1998). Biomarkers of leukemia risk: benzene as a model. *Environ Health Perspect* 106(Suppl 4):937-946.

Snyder R, Hedli CC (1996). An overview of benzene metabolism. *Environ Health Perspect* 104(Suppl6):1165-1171.

Topham JC (1980). Do induced sperm-head abnormalities in mice specifically identify mammalian mutagens rather than carcinogens? *Mutat Res* 74:379-87.

U.S. EPA (1998). *Carcinogenic effects of benzene: an update*. National Center for Environmental Assessment, Office of Research and Development, U.S. Environmental Protection Agency, Washington, D.C., EPA/600/P-97/001F.

Valentine JL, Lee SST, Seaton MJ, Asgharian B, Farris G, Corton JC (1996). Reduction of benzene metabolism and toxicity in mice that lack CYP2E1 expression. *Toxicol Appl Pharmacol* 141(1):205-213.

Wallace L (1996). Environmental exposure to benzene: an update. *Environ Health Perspect* 104(Suppl6):1129-36.

Xing SG, Shi X, Wu ZL, Chen JK, Wallace W, Whong WZ, Ong T (1992). Transplacental genotoxicity of triethylenemelamine, benzene, and vinblastine in mice. *Teratog Carcinog Mutagen* 12(5):23-30.

Appendix A-9: Light Pollution

Astronomy; Studies from Slovak Academy of Science Describe New Findings in astronomy. (2011, March). *Science Letter*, 2425. Retrieved March 24, 2011, from Research Library. (Document ID: 2274965781).

Auty, Richard M. 1997. Pollution Patterns during the Industrial Transition. *The Geographical Journal* Vol. 163, No. 2. 2 July. Pp. 206-215

Bean, Robert. "Editorial." *Lighting Research and Technology*. 40:3 (2008): 173-174.

Bertolotti L. , Salmon M. Do embedded roadway lights protect sea turtles? *Environmental Management* 2005 ; 36: 702-10.

Biersack, Aletta. "Moonlight: Negative Images of Transcendence." *Oceania* 57:3 (1983): 178.

Brandon, P.S., V. Bentivegna, and P.L. Lombardi. 1997. *Evaluation of the built environment for sustainability*. London; New York: E. & F.N. Spon.

Brons J. , Bullough J. , Rea M. Light pollution: thinking inside the box . *Lighting Journal* 2007; 72: 27-34

Brons, J., J. Bullough, and M. Rea "Outdoor site-lighting performance: A comprehensive and quantitative framework for assessing light pollution." *Lighting Research and Technology*. 40:3 (2008): 201-224.

Cartledge, Bryan. 1993. *Energy and the environment*. Oxford, New York: Oxford University Press.

Chepesiuk R. 2009. Missing the Dark: Health Effects of Light Pollution. Environmental

'Dark Skies' Ordinance Approved to Reduce Light Pollution for Residents in County Rural Areas. (2010, December 14). *Targeted News Service*, Retrieved March 24, 2011, from Research Library. (Document ID: 2212829671).

Falchi, Fabio. "Campaign of sky brightness and extinction measurements using a portable CCD camera." *Monthly Notices of the Royal Astronomical Society* 412.1 (2011): 33-48. *Academic Search Complete*. EBSCO. Web. 24 Mar. 2011

Garfinkle, Robert A. 1994. *Star-hopping: your visa to viewing the universe*. Cambridge, New York, NY.

Ghadirian, Abdu'l- Missagh A. and Heinz E. Lehmann. 1993. *Environment and psychopathology*. New York: Springer Pub Co.

Gurjar, Bhola R., Luisa T. Molina, Chandra S.P. Ojha, and Mario J. Molina. 2010. *Air pollution: health and environmental impacts*. Boca Raton, Florida. CRC Press.

Hooper, Judith. 2003. *Of moths and men: an evolutionary tale: the untold story of science and the peppered moth*. New York: Norton.

Henderson, J. "Illuminating Regulations +Architects Can Minimize Light-Pollution by Specifying Suitable Fixtures and Lamps". *Architecture- The AIA Journal*. 82:7. Pages101-105. July 1993.

Holker, F., T. Moss, and B. Griefahn. "The Dark Side of Light: A Transdisciplinary Research Agenda for Light Pollution Policy." *ECOLOGY AND SOCIETY* 15.4 (2010). Web.

Illuminating Engineering Society of North America. IESNA Publication CP-31-89. The Value of Public Lighting . New York: IESNA, 1989

Johansson, M., M. Rosen, and R. Juller. "Individual factors influencing the assessment of the outdoor lighting of an urban footpath." *Lighting Research and Technology*. 43:1 (2011): 31-43.

Longcore, Travis & Catherine Rich. 2004. Ecological Light Pollution. *Frontiers in Ecology and the Environment*, Vol. 2, No. 4. (May), pp. 1414-1418

McColgan M. *Lighting Answers: Light Pollution*. Troy: Lighting Research Center, Rensselaer Polytechnic Institute, 2003.

Miller, Mark W. "Apparent Effects of Light Pollution on Singing Behavior of American Robins." *The Condor* 108.1 (2006): 130-39. Web

Mizon, Bob. 2002. *Light pollution: responses and remedies*. London; New York: Springer.

Monks, N. "How to hunt galaxies from the suburbs." *Astronomy*. 39:2 (2011): 52-3

- Morton, J. "Brighter Isn't Better." *Buildings*. 104:12 (2010): 24
- Newbury, Harry and William De Lorne. 2009. *Industrial pollution including oil spills*. New York: Nova Science Publishers.
- New Jersey Light Pollution Study Commission's Report, Submitted April 1996 to the Governor and the Legislature.
- Nurick, Robert and Victoria Johnson. "Towards community based indicators for monitoring quality of life and the impact of industry in south Durban." *Environment and Urbanization*. 10.1: (1998-2004): 233-250.
- Pasachoff, Jay M., Rosa M. Ros, and Naomi Pasachoff. 2008. *Innovation in astronomy education*. Cambridge, New York: Cambridge University Press. (Ch.13)
- Pauley SM Lighting for the human circadian clock: recent research indicates that lighting has become a public health issue. *Medical Hypotheses* 2004; 63: 588-96.
- Pompe, Jeffery J. and James R. Rinehart. 2002. *Environmental Conflict: in search of common ground*. Albany, NY: State University of New York Press.
- Pollard, N.E. "Sky-glow conscious lighting design." *Lighting Research and Technology*. 26"3 (1994): 151-156.
- Rea, M., L. Radetsky, and J. Bullough. "Toward a model of outdoor lighting scene brightness." 43:1 (2011): 7-30.
- Reiter, Russel J., Dan Xian Tan, Thomas C. Erran, Lorena Fuentes- Broto, and Sergio D. Paredes. "Light-Mediated Perturbations of Circadian Timing and Cancer Risk: A Mechanistic Analysis." *Integrative Cancer Therapies*. 8:4 (2009): 354-360.
- Rotics, Shay, Tamar Dayan, and Noga Kronfeld-Schor. "Effect of artificial night lighting on temporally portioned spiny." *Journal of Mammalogy (Baltimore)*: 92:1 (2011): 1590-169
- Schlesinger, Michael E. 2007. *Human induced climate change: an interdisciplinary assessment*. Cambridge; New York: Cambridge University Press.
- Spivey, A. "Light at Night and Breast Cancer Risk Worldwide." *Environmental Health Perspectives*. 118:12 (2010): A525.
- Soardo, P. P. Iacomussi, G. Rossi, and L. Fellin. "Compatibility of road lighting with star visibility." *Lighting and Research and Technology*. 40:4 (2008): 307-322.
- Stevens RG, Rea MS Light in the built environment: potential role of circadian disruption in endocrine disruption and breast cancer. *Cancer Causes and Control* 2001; 12: 279-87.
- Uppgren, Arthur. *Night has a thousand eyes: a naked-eye to the sky, its science, and lore*. New York: Plenum Trade. (Ch.12)
- US Patent Issued on Jan. 25 for "Method and System for Reducing Light Pollution" (New York Inventor). (2011, January 28). *US Fed News Service, Including US State News*. Retrieved March 24, 2011, from Research Library. (Document ID: 2251159971).
- Van Der Wal, Rene, Imogen S. K. Pearce, and Rob W. Brooker. "Mosses and the Struggle for Light in a Nitrogen-Polluted World". *Oecologia*. 142:2 1 January 2005. 156-168

"Light Pollution." *Astronomy Encyclopedia*. London: Philip's, 2002. *Credo Reference*. 29 Jan. 2007. Web. 23 Mar. 2011. <http://www.credoreference.com/entry/philipsastronomy/light_pollution>.

"Light Pollution." *Academic Press Dictionary of Science and Technology*. Oxford: Elsevier Science & Technology, 1992. *Credo Reference*. 8 Jan. 2003. Web. 23 Mar. 2011. <http://www.credoreference.com/entry/apdst/light_pollution>.

"POLLUTION." *The A to Z of Corporate Social Responsibility*. Hoboken: Wiley, 2007. *Credo Reference*. 22 June 2010. Web. 23 Mar. 2011. <http://www.credoreference.com/entry/wileyazcsr/pollution>>.

<http://0proquest.umi.com.linus.lmu.edu/pqdweb?did=2262748091&Fmt=3&clientId=7693&RQT=309&VName=PQD>

Appendix A-10: Mental Health

Agin, D.P. 2010. *More than genes: what science can tell us about toxic chemicals, development, and the risk to our children*. Oxford; New York: Oxford University Press.

"Air Pollution, Health Effects of." *Encyclopedia of Energy*. Oxford: Elsevier Science & Technology, 2004. *Credo Reference*. 19 Mar. 2010. Web. 31 Mar. 2011.

Ashton, John. 1994. *The Epidemiological imagination*. Buckingham; Philadelphia: Open University Press.

Barrett, Gary W. and Rutger Rosenberg. 1981. *Stress effects on natural ecosystems*. Chichester; New York: Wwiley.

"Environmental Stress." *Encyclopedia of Applied Psychology*. Oxford: Elsevier Science & Technology, 2004. *Credo Reference*. 2 Sept. 2009. Web. 31 Mar. 2011

Evans, Gary W. "The Interaction of Stressful Life Events and Chronic Strains on Community Mental Health". *American Journal of Community Psychology*. 15:1 (1987:Feb.) p.23.

Gallagher, A.G. and K. Tierney. 1996. "The Impact of the Environment of Physical and Mental Health". *The Irish Journal of Psychology*. 17:4: 361-372.

Ghadirian, Abdu'l- Missagh A. and Heinz E. Lehmann. 1993. *Environment and psychopathology*. New York: Springer Pub Co.

"Good Mental Health." *The Hutchinson Unabridged Encyclopedia with Atlas and Weather Guide*. Abington: Helicon, 2010. *Credo Reference*. 4 Jan. 2011. Web. 31 Mar. 2011.

Greenberg, Michael R. and Dona Schneider. 1996. *Environmentally devastated neighborhoods: perceptions, policies, and realities*. New Brunswick, N.J.: Rutgers University Press.

Gurjar, Bhola R., Luisa T. Molina, and Chandra S.P. Ojha. 2010. *Air pollution: health and environmental impacts*. Boca Raton, FL: CRC Press.

Harris, Robert G. and Daniel P. Moore. 2009. *Indoor work and living environments: health, safety and performance*. New York: Nova Science Publishers

"Health Care." *World of Sociology*, Gale. Farmington: Gale, 2001. *Credo Reference*. 20 Aug. 2004. Web. 31 Mar. 2011.

"Health and Environment Blog". 2011. *CMAJ: Canadian Medical Association Journal*. 183:2.

Jacobs, Stephen V., Air Pollution and Depressive Symptomatology: Exploratory Analyses of Intervening Psychosocial Factors, *Population and Environment*, 7:4 (1984:Winter) p.260.

Miodovnik, Amir. "Environmental Neurotoxicants and Developing Brain." *Mount Sinai Journal of Medicine* 78.1 (2011): 58-77. *Academic Search Complete*. EBSCO. Web. 31 Mar. 2011.

"Radiation, Risks and Health Impacts of." *Encyclopedia of Energy*. Oxford: Elsevier Science & Technology, 2004. *Credo Reference*. 19 Mar. 2010. Web. 31 Mar. 2011.

Rotton, James, Psychological Costs of Air Pollution: Atmospheric Conditions, Seasonal Trends, and Psychiatric Emergencies, *Population and Environment*, 7:1 (1984:Spring) p.3.

"Social and environmental stressors in the home and childhood asthma". 2010. *Journal Of Epidemiology and Community Health*. 64:7: 636-642.

Stephens, Carolyn. "The urban environment, poverty and health in developing countries". *Health Policy and Planning*, 10:2 (1995:June) p.109.

"Stress and Health." *Cambridge Handbook of Psychology, Health and Medicine*. Cambridge: Cambridge UP, 2007. *Credo Reference*. 4 Dec. 2009. Web. 31 Mar. 2011.

Turner, Bryan S. 1995. *Medical power and social knowledge*. London; Thousand Oaks: Sage Publications.

1 **Coalition for a Safe Environment (CFASE)**

2 **Response to Comment CFASE-1**

3 As the Commenter mentions the SCIG project, which was recently available for public review, it is
4 uncertain whether the Commenter is making a request regarding the proposed Project and its Draft EIS/EIR
5 or just the SCIG project. The commenter is making an overall request that the Draft EIS/EIR be rescinded
6 and rewritten due to “deficiencies, errors, omissions of information, inadequate assessments, missing
7 required assessments, misrepresentative of facts, unsubstantiated information, invalidated data,
8 inappropriate assumptions, fails to eliminate where feasible all negative impacts, and fails to include all
9 reasonable and available mitigation measures, and environmental justice impacts, as detailed in subsequent
10 comments.” The comment is noted, however without clarification to which Project the commenter is
11 referring to and details regarding the suggestions that the Draft EIR/EIS is inadequate, the LAHD and
12 USACE cannot respond to this request.

13 **Response to Comment CFASE-2**

14 Comment noted. The PDF files being password protected was not intentional; however, the LAHD and
15 USACE provided the Draft EIS/EIR in a manner consistent with CEQA and NEPA, and USACE
16 regulations regarding public noticing requirements. However, for the posting of future electronic files on
17 the Port’s website, LAHD will verify that the files are not password protected.

18 **Response to Comment CFASE-3**

19 The comment asserts that the Draft EIS/EIR does not comply with CEQA because it does not disclose all
20 significant environmental impacts, does not identify all sources of related environmental impact information,
21 does not fully assess all sources of environmental impact information, does not disclose all possible ways to
22 minimize significant impacts, and dismisses or does not disclose ways to minimize significant impacts. The
23 Commenter also requests that the Draft EIS/EIR identify, disclose, and include all Port known and public
24 identified impacts, sources of impacts, source impact assessment, and available mitigation. The Commenter
25 also requests that, where no assessment exists, LAHD hire an independent third party to conduct an
26 assessment and include it in the Draft EIS/EIR. The Commenter also requests that all potential and
27 alternative mitigation that has been currently proven to be feasible and cost effective, or that will be proven
28 feasible and cost effective in the next 12-months be required and included in the Draft EIS/EIR.

29
30 The Draft EIS/EIR analysis complies with NEPA and CEQA by evaluating significant impacts and
31 disclosing the significant impacts, as well as identifying feasible alternatives and mitigation measures to
32 reduce or avoid impacts (these evaluations and discussion are contained in Chapter 3 and Chapter 4 of the
33 Draft EIS/EIR. Sources of information utilized in the impact discussion are referenced in each section of
34 the Draft EIS/EIR, and in Chapter 10 (References). The mitigation measures in the Draft EIS/EIR are all
35 currently feasible; however, the Draft EIS/EIR does not require specific measures that are not yet feasible
36 because feasibility has not yet been determined. The Draft EIS/EIR does; however, include lease measure
37 LM AQ-1, which reopens the terminal lease every 5 years to allow the incorporation of new technologies
38 that have become feasible after adoption of the Draft EIS/EIR.

39
40 In addition, the document evaluates and discloses disproportionate impacts on the minority and low income
41 community in Chapter 5, Environmental Justice, of the Draft EIS/EIR. Despite the application of all
42 feasible mitigation measures, significant unavoidable adverse Project-level and cumulative impacts would
43 remain. These impacts have been identified in the Draft EIS/EIR, and the decision-makers will consider
44 them as part of their deliberations to approve or disapprove the Project or an alternative.

1 **Response to Comment CFASE-4**

2 The Commenter asserts that that Project and alternatives are not fully consistent with the Project objectives
3 because they are not the most optimal, efficient, or cost effective, and these opinions are noted; however
4 LAHD disagrees with these opinions.

5 The Commenter asserts that the most efficient way to operate a container terminal is to have on-dock rail
6 extend to the dockside, presumably to directly transfer containers between rail and vessels, and to use zero
7 emission transport technologies for subsequent transport. Contrary to the Commenter's recommendation,
8 extending on-dock rail infrastructure to the wharf would impede transfer of containers between vessels and
9 backlands. As part of terminal operations, containers are managed in several ways, including stacking,
10 storage on chassis, transfer to on-dock rail, and transfer to near dock rail yards. Although extending rail to
11 dockside may make sense for terminals that transfer the containers primarily for rail transport, it doesn't
12 make sense to do so for the proposed Project or alternatives, as such an approach would accommodate one
13 mode while ignoring the others. Currently, zero-emission technologies are still in the evaluation phase.
14 When they are deemed to be technologically, economically, and commercially feasible, the Port intends to
15 implement zero-emission drayage options on a Port-wide basis (see the Response to Comments USEPA-17
16 and SCAQMD-8)

17 The Commenter recommends that the Draft EIS/EIR or the LAHD implement demonstration projects that
18 for more efficient container handling and transferring. The LAHD is involved in demonstrating new
19 technologies via the Technology Advancement Program (TAP), which is focused on new and emerging
20 technologies. The TAP has the objectives of streamlining the process for reaching consensus on the
21 emission reductions achieved by various technologies and facilitating development of new technologies and
22 their adoption throughout the port industry. It should be noted that the Draft EIS/EIR contains lease
23 measure LM AQ-1 that includes the incorporation of new technologies as these new technologies become
24 commercially available.

25 The Commenter also states that they previously recommended investing in more efficient terminal designs
26 such as "U" Dock where containers are loaded and unloaded from both sides of the vessel, and that such a
27 design should be considered for the proposed Project. Although such a concept could make sense for a new
28 terminal if terminal operations would be improved, it is not a viable alternative for the proposed Project and
29 the Project alternatives, which are expansions of the existing terminal configuration. Such an alternative
30 would also have the effect of reducing backlands and requiring extensive terminal and channel
31 reconfiguration to accommodate vessel maneuvering, and reduced and modified backland areas and
32 configurations. Such a terminal (and associated channel) reconfiguration would likely result in greater
33 environmental impacts than the proposed Project or Project alternatives.

34 **Response to Comment CFASE-5**

35 The Commenter reiterates their opinion that the proposed Project and alternatives are not fully consistent
36 with the proposed Project objectives because they are not the most optimal, efficient, or cost effective.
37 These opinions are noted; however LAHD disagrees with these opinions.
38

39 The Commenter states that LAHD and USACE have not conducted an assessment of optimal cargo
40 handling technologies and that there is no reason to build another outdated terminal when new state of the
41 art 21st century alternatives and zero-emission technologies have been validated or will be within the next 1-
42 3 years, The LAHD would like to note that the proposed Project, Alternatives 5 and 6 include an option for
43 an automated stacking system at on the backlands behind Berth 306, should market conditions support it
44 (see the Response to Comment USEPA-12), LAHD and USACE also evaluated a fully electrified terminal
45 and alternative transportation systems in Chapter 2 of the Draft EIS/EIR, but determined that they are not
46 feasible at this time. Although some zero-emission drayage technologies are in the demonstration phase,

1 full feasibility has not yet been determined, and it would be speculative to place a timeframe on when those
2 technologies would become technologically, economically, and commercially feasible to be implemented
3 on a port-wide basis (see the Response to Comments USEPA-13 and USEPA-17). It should be noted that
4 the Draft EIS/EIR includes lease measure LM AQ-1 that includes a lease reopener every five years to allow
5 for the incorporation of new technologies after they become commercially available (consistent with a Port-
6 wide implementation approach).

7 **Response to Comment CFASE-6**

8 The Commenter asserts that the Draft EIS/EIR fails to equally evaluate public and manufacturer
9 recommended alternatives that inadequately describes the feasibility of an Alternative Transportation
10 System Alternative, fails to disclose that there are two MagLev technologies, and fails to disclose that
11 LAHD and POLB staff have visited MagLev demonstrations. These opinions are noted; however LAHD
12 disagrees with these opinions. As discussed in the Draft EIS/EIR, an Alternative Transportation System
13 was deemed not to be a feasible Project alternative because such a system would require extensive
14 integration and capital investment on the part of rail companies; and a method for integration into the
15 existing rail system that is based on diesel locomotives would still have to be developed. Development of
16 such an alternative therefore must occur on a regional basis, would require extensive coordination by many
17 stakeholders (including railroad companies), and likely would require external funding commitments.
18 Because of this, an Alternative Transportation System does not represent an alternative that can be
19 implemented in lieu of the proposed Project or one of its feasible alternatives. Magnetic Levitation
20 technologies would be included in an Alternative Transportation System. Although LAHD staff has
21 researched MagLev technologies, such a system still would not be a feasible alternative to the proposed
22 Project or Project alternative because it would need to occur on a Port-wide basis rather than a terminal
23 specific basis, and because terminal expansion and improvements would still be required. The Commenter
24 notes that the public supports zero-emission technologies, and LAHD also supports the development of
25 such technologies, as exemplified by the zero-emission demonstration projects in the TAP. However,
26 although several zero-Emission technologies look technically promising, economic and commercial
27 feasibility would still need to be determined.

28 **Response to Comment CFASE-7**

29 The Commenter asserts that the Draft EIS/EIR fails to discuss the feasibility of an Alternative
30 Transportation System, misrepresents facts by stating that a fully electric terminal could result in only
31 marginal throughput increases; fails to identify extending on-dock rail to dockside as a more efficient way
32 of managing containers; fails to disclose that zero-emission drayage and yard tractors exist; fails to disclose
33 that AMECs is tested and feasible; and fails to disclose that a fully electric terminal is viable within 1-3
34 years. The Commenter also requests that the 50 percent of the fleet serving the APL Terminal be required
35 to use zero-emission technologies. All these assertions are noted; however LAHD disagrees with these
36 assertions. As discussed in the Response to Comment CFASE-6, implementation of an alternative
37 transportation system, such as MagLev, is not a feasible alternative or mitigation for the impacts of the
38 proposed Project. These systems generally require very large capital investments, have extensive
39 geographical coverage, and are disproportionate to the impacts of an individual project. Additionally, the
40 Project applicant has no means to implement such system-wide transportation improvements. The
41 recommendations of alternative transportation systems are better implemented on a Port-wide or regional
42 basis. The Clean Truck Program at the Port is an example of a large-scale transportation system that has
43 been implemented on a Port-wide basis. However, transportation systems for cargo movement such as
44 Maglev represent an infrastructure system over which the LAHD has no jurisdiction or ability to control.
45 The Project alternatives represent a reasonable range of alternatives, as required by CEQA that would
46 reduce or avoid the significant impacts of the proposed Project.

1 The Commenter is correct that a fully electrified terminal was not considered to be a viable alternative at
2 this time, in part, due to the berth constrained nature of the terminal. In addition, the Draft EIS/EIR
3 provides additional reasons why such a terminal was not carried forward for a co-equal evaluation.
4 Although several test projects are underway and are intended to demonstrate the feasibility and reliability of
5 the zero-emission trucks and cargo-handling equipment, full electrification of the APL Terminal is not
6 considered to be technologically feasible at this time, and therefore was not considered to be a viable or
7 feasible alternative to the proposed Project.

8 Contrary to the Commenter's opinion, extending electric on-dock rail infrastructure to the wharf would not
9 improve efficiency; on the contrary, it would impede the transfer of containers between vessels and
10 backlands. In addition, please see the Response to Comment CFASE-4.

11 Although the Commenter recommends that specific drayage truck technologies be required for the fleet the
12 serves the APL Terminal, those technologies are not yet commercially available. In addition, the fleet that
13 services the APL Terminal (and other container terminals throughout both Ports) is actually many smaller
14 fleets that are independently owned and operated by various trucking firms or individual owner-operators.
15 Because of this, the LAHD is taking a Port-wide approach to implementing zero emission trucks. Please
16 see the Response to Comments USEPA-17, SCAQMD-8, and SCAQMD-14.

17 Regarding the comment about AMECS, please see the Response to Comment CFASE-17 below.

18 **Response to Comment CFASE-8**

19 The Commenter asserts that the Draft EIS/EIR inadequately describes the feasibility of expanded rail lines;
20 fails to disclose that the Alameda Corridor is operating at less than full capacity, allegedly because both
21 Ports refuse to require its usage in lease agreements; and fails to disclose that the most efficient way to
22 manage a terminal is by extending on-dock rail lines to dockside. These assertions are noted; however,
23 LAHD disagrees with these assertions. The commenter also requests that the Draft EIS/EIR include a
24 description of current and near-term (1-3 years) technologies that optimizes cargo handling and reduce
25 emission, and require all feasible new technologies.

26
27 Regarding the comment on expanding rail lines, the Draft EIS/EIR disclosed that current and future
28 terminal operations are and would be berth-constrained, such that providing for more Port-wide rail
29 capacity would not increase projected throughput or make operations more efficient. Because the
30 recommended alternative would not meet the Project objectives, the expansion or improvements to area rail
31 lines was not considered to be a viable or feasible alternative to the proposed Project.

32
33 Regarding the comments on usage of the Alameda Corridor, the Alameda Corridor serves both Ports, and
34 utilization of that rail corridor is not a function of container terminal lease terms; rather, it is a function of
35 throughput, cargo destinations, transportation modes, and other factors. The Alameda Corridor is
36 considered adequate to support the Project's anticipated demand for container shipment by rail, and
37 establishing a lease requirement to maximize use of the Alameda Corridor would not increase the use of the
38 corridor beyond demand. The recommendation is therefore not an effective way of reducing impacts.

39
40 Regarding the comment about extending on-dock rail to the dockside, please see the Response to Comment
41 CFASE-4 above. In addition, it should be noted that only a portion any container terminal throughput is
42 transported via rail.

43
44 The Draft EIS/EIR proposes mitigation that is considered feasible and implementable. Although the
45 commenter may desire requiring new technologies that may be determined to be feasible in the next 1-3
46 years, to do so would be speculative. For a technology to be considered viable from a Port-wide

1 perspective, it must be technologically, economically, and commercially feasible, not just technologically
2 feasible.

3 **Response to Comment CFASE-9**

4 The Commenter states that the Draft EIS/EIR fails to adequately describe alternative technologies to
5 optimize cargo handling, fails to disclose the benefits of alternative transportation systems such as MagLev,
6 fails to disclose that the Alameda Corridor is used less than 35 percent of its capacity, fails to disclose that
7 the most efficient way to manage containers is to extend rail to dockside, fails to discuss more efficient
8 cargo handling technologies, fails to consider a U shaped terminal design to more efficient vessel unloading,
9 and fails to discuss new technologies that will be ready in the next 1-3 years. These assertions are noted;
10 however, LAHD disagrees with these assertions.

11
12 Please see the Response to Comments CFASE-4, CFASE-5, CFASE-6, and CFASE-8 above.

13 **Response to Comment CFASE-10**

14 The Commenter states that the Draft EIS/EIR fails to list all air pollutant (truck and train sources, including
15 emissions associated with vehicle aging), noise, traffic, and safety impact sources, that the traffic
16 projections are inaccurate and cause an understatement of other impacts, and that additional studies are
17 needed (Health Impact Assessment and Off-Port Tidelands Property Community Impact Nexus Study).
18 The commenter identifies specific impacts sources as follows:

- 19 A. Off Port Properties – Truck Transportation Corridors
- 20 B. Off Port Properties – Container Storage Yards
- 21 C. Off Port Properties – Chassis Storage Yards
- 22 D. Off Port Properties – Container Inspection Facilities
- 23 E. Off Port Properties – Fumigation Facilities
- 24 F. Off Port Properties – Truck Fuel/Gas Stations
- 25 G. Off Port Properties – Truck Maintenance Garages
- 26 H. Off Port Properties – Truck Storage Areas
- 27 I. Off Port Properties – Truck Staging Areas
- 28 J. Off Port Properties – Truck Lunch/Rest Stop Areas
- 29 K. Off Port Properties – Truck Idling Locations (i.e. bridges and intersections)
- 30 L. Off Port Properties – Truck Detour Locations
- 31 M. Off Port Properties – Truck and Reefer Container A/C HFC's due to leaking
- 32 N. Off Port Properties – Train Transportation Corridors
- 33 O. Off Port Properties – Train Idling Locations
- 34 P. Off Port Properties – Train Maintenance Yard Locations

35 The Commenter also suggests various mitigation measures and requests that all mitigation measures be
36 required in the tenant lease agreement.

37 Off-Port emission source items A-P are all existing facilities that are not components of the proposed
38 Project or Project alternatives, and therefore do not represent Project emission sources. However, to the
39 extent that Project trucks or trains would utilize the above-mentioned truck or train transportation corridors
40 within the South Coast Air Basin prior to their first point of delivery, their emissions are captured in the
41 emission calculations in the Draft EIS/EIR. The LAHD estimates emissions to the first point of delivery
42 because beyond that point, logistic variables associated with transloaded cargo shipments increase

1 dramatically, resulting in an intolerable level of speculative, as well as a lack of LAHD jurisdiction and
2 control.

3 Regarding the comment that the air analysis in the Draft EIS/EIR does not take into consideration increased
4 emissions as fleet's age, this comment is incorrect. The air quality analysis bases its emission calculations
5 on emission factors provided by the USEPA, CARB, and Starcrest. These emission factors take into
6 consideration aging of fleets, as well as other factors such as cleaner fuels, more stringent engine standards,
7 and regulatory requirements.

8 Regarding the comment that the air analysis in the Draft EIS/EIR does not take into consideration all
9 destinations, please see the Response to Comment USEPA-21. Regarding the recommendation to perform
10 a health impact assessment, please see the Response to Comment PCAC-1.

11
12 Although the Commenter believes the traffic projects are understated and impacts are underestimated, the
13 traffic projections are based on the throughput projections provided in Appendix C of the Draft EIS/EIR.
14 The throughput projections are considered conservative, and traffic projections and other impact analyses
15 based on them would also be considered conservative.

16 Regarding the recommended mitigation measures, please see the Responses to Comments CFASE-4,
17 CFASE-5, CFASE-6, CFASE-8, CFASE-17, SCAQMD-8, and SCAQMD-14. Regarding the comments on
18 feasible noise mitigation, the Draft EIS/EIR did not identify a significant operational noise impact for which
19 the recommended noise mitigation would apply. Similarly, the proposed project would not result in
20 significant air quality impacts related to CFCs or for which air purifications systems would mitigate.
21 Although the Commenter believes that the recommended mitigation measures are feasible, many are not yet
22 ready for implementation, or do not have a nexus to significant impacts identified in the Draft EIS/EIR.

23 **Response to Comment CFASE-11**

24 The Commenter repeats their statement that the Draft EIS/EIR fails to list all air pollutant (truck and train
25 sources, including emissions associated with vehicle aging), and that the traffic projections are inaccurate
26 and cause an understatement of other impacts, and that additional studies are needed (Health Impact
27 Assessment and Off-Port Tidelands Property Community Impact Study). Please see the Response to
28 Comment CFASE-10 above and Response to Comment PCAC-1.

29 **Response to Comment CFASE-12**

30 The Commenter asserts that the Draft EIS/EIR (Air Quality, Noise, and Transportation) should be revised to
31 reflect mitigation measures submitted by the Commenter and previously submitted to the LAHD.
32 Responses to specific mitigation measures and alternatives are contained or directed elsewhere in the
33 Response to Comment CFASE-10. It should be mentioned that the mitigation measures in the Draft
34 EIS/EIR are based on significant impacts identified in the analysis and will be required if either the
35 proposed Project or an alternative are approved.

36 **Response to Comment CFASE-13**

37 The Commenter asserts that the Draft EIS/EIR lease measures do not guarantee that new technologies will
38 be identified, researched, recommended, or required, and that although the Ports tenants are aware of the
39 effectiveness of zero-emission drayage technologies, no tenant has purchased a zero emission drayage truck.
40 These opinions are noted; however LAHD disagrees with these opinions. The purpose of lease measure LM
41 AQ-1 is to have a mechanism to implement new technologies after they become technologically,
42 economically, and commercially feasible, consistent with a Port-wide implementation approach. New
43 technologies are being evaluated as part of the TAP and by private companies such as Vision Motor

1 Corporation, as stated by the Commenter. Although the identified zero-emission drayage truck looks
2 promising from a technological standpoint via its demonstrations, it is unclear when demonstrated
3 technologies can become commercially viable, and when other members of the goods movement chain can
4 implement the new technologies. Because of this, the LAHD is taking a Port-wide approach to
5 implementing new technologies (see the Response to Comments USEPA-17 and SCAQMD-8).

6 **Response to Comment CFASE-14**

7 The Commenter asserts that the socioeconomic evaluation in the Draft EIS/EIR only discusses positive
8 impacts and does not include negative impacts such as health care costs, public transportation infrastructure
9 costs, costs associated with off-port accidents, costs for infrastructure repair, and costs associated with loss
10 of jobs. In addition, the Commenter states that the Port Master Plan restricts non-container uses in the Port
11 and that the LAHD is not moving forward install solar power generation capacity. These assertions are
12 noted; however LAHD disagrees with these assertions.

13
14 The socioeconomic section of the Draft EIS/EIR includes an evaluation of socioeconomic effects clearly
15 associated with the proposed Project and the Project alternatives without regards to whether the effect
16 would be considered positive or negative. The impacts listed by the Commenter are general socioeconomic
17 impacts that are affected by many factors outside of the proposed Project and alternatives. In addition, the
18 comment appears to be related to the operation and development of the two ports as a whole rather than for
19 a specific container terminal project. In addition, the Draft EIS/EIR is not required to analyze
20 socioeconomic impacts that are not related to the proposed Project or Alternatives, except to the extent that
21 those impacts may result in impacts to the environment.

22
23 Regarding the Port Master Plan (PMP) use restrictions, the PMP establishes particular uses in different
24 areas of the Port, in a similar manner as a general or community plan. There are designated areas for
25 container terminals, as well as other public uses. The Wilmington Waterfront Project and the San Pedro
26 Waterfront Project are two recent examples where non-container terminal uses were approved within the
27 Port. Regarding the comments on the Port's solar generation project, that project is not a part of the
28 proposed Project or the Project alternatives. As discussed in Chapter 1 of the Draft EIS/EIR, the Port
29 intends to construct a 10-megawatt photovoltaic solar system to offset approximately 17,000 metric tons of
30 carbon dioxide equivalent annually in accordance with the 2007 Attorney General agreement. As of August
31 2009, the Port has completed approximately 1,079 kilowatts of solar power and will continue to implement
32 solar power initiatives now and in the future. Additionally, many of the environmental programs such as
33 the Green Building Policy and the Recycling Program will serve to reduce GHG emissions.

34 **Response to Comment CFASE-15**

35 The Commenter asserts that the Draft EIS/EIR fails to list all air emission sources that feed into the health
36 risk assessment, that the traffic projections are inaccurate, and that additional studies are needed (Health
37 Impact Assessment and Off-Port Tidelands Property Community Impact Study). The facilities that the
38 Commenter provided are off-port sources that are not components of the proposed Project or Project
39 alternatives (see the Response to Comment CFASE-10); therefore, it is only appropriate to include
40 emissions associated with those facilities in the Project's HRA to the extent that those emissions are part of
41 the Project. To the extent that Project trucks and trains utilize the truck and train transportation corridor
42 within the SCAB prior to the first point of destination, their emissions are included in the Draft EIS/EIR
43 HRA. Please see the Response to Comment CFASE-10 above.

1 **Response to Comment CFASE-16**

2 The Commenter asserts that the Draft EIS/EIR fails to include a Health Impact Assessment, as requested,
3 fails to adequately evaluate health impacts, and only does a health risk assessment, which looks at deaths
4 and risk factors. In addition, the HIA methodology described by Dr. Heller may not be able to adequately
5 differentiate health effects from the proposed project versus from many of the other factors that are
6 considered in an HIA. Although Dr. Miller may have a generalized methodology for conducting HIAs, it
7 does not appear that the HIA methodology has been reviewed by or approved for use in environmental
8 documents by California Office of Environmental Health Hazards Assessment, as has the HRA
9 methodology used in the Draft EIS/EIR. Please see the Response to Comment PCAC-1.

10 **Response to Comment CFASE-17**

11 Regarding the ship emissions, the Commenter asserts that the Draft EIS/EIR understates vessel emissions
12 by only counting one-way trips rather than round trips, that it is impossible to retrofit 50 percent of the APL
13 vessel fleet with AMP by 2014, and that the Draft EIS/EIR fails to require AMECs. In the methodology
14 discussion for ship emission calculations (Section 3.2.4.1.2 of the Draft EIS/EIR), it was noted that the one-
15 way distance from the berth to the edge of SCAQMD waters was 50 miles (page 3.2-42 of the Draft
16 EIS/EIR). However, roundtrip emissions were calculated and reported in each of the operational emissions
17 tables used to determine significance.

18 The Commenter's opinions regarding AMP compliance are noted.

19 AMEC is essentially a baghouse installed over a ship's stack while it is docked. These units collect
20 pollutants, which subsequently must be disposed of in solid or liquid form. LAHD anticipates that AMECs
21 technology could eventually prove feasible and cost-effective as an alternative to AMP for some vessels
22 calling the Port, especially marine oil tankers where AMP ship-side retrofits may be technologically and
23 operationally infeasible. The system continues to be tested with generally promising preliminary results,
24 however, AMP is the preferred mitigation measure for container ships as the technology is readily available,
25 and does not collect pollutants that must be disposed of, but instead eliminates the generation of such
26 pollutants in the Port-area. LAHD and its tenants have been installing AMP (shore power that allows ships
27 to turn off main engines and auxiliary engines while docked) since 2004, and will meet CARB's
28 requirement to reduce 80 percent of these engine emissions by 2020. With mitigation, APL is expected to
29 achieve reductions of 95 percent by 2026.

30 **Response to Comment CFASE-18**

31 The Commenter asserts that the Draft EIS/EIR understates emissions by only using one-way trips instead of
32 round trips, fails to include all emission sources, that an Health Impact Assessment and Off-Port Tidelands
33 Property Community Impact Study are needed, and that fails to account for all idling sources. Regarding
34 the comment that the air analysis in the Draft EIS/EIR does not take into consideration the correct number
35 of trips or increased emissions as fleets age, this comment is incorrect. Regarding the list of emission
36 sources in this comment that the Commenter states are not included in the Draft EIS/EIR evaluation, those
37 sources are not components of the proposed Project, as detailed in the Response to Comment CFASE-10.
38 Please see the Response to Comment CFASE-10 above. As for transportation corridor and destination
39 sources, as described in Section 3.6.2.1 of the Draft EIS/EIR, the traffic setting for the proposed Project
40 includes those streets and intersections that would be used by both automobile and truck traffic to gain
41 access to and from the proposed Project site, as well as those streets that would be used by construction
42 traffic (i.e., equipment and commuting workers). Fifteen study intersections located near or on routes
43 serving the proposed Project site, were chosen for analysis. Proposed Project-related traffic on streets
44 farther away from the proposed Project site is assumed to be diminished to less than the number of trips that

1 would require analysis per the City of Los Angeles Department of Transportation (LADOT), City of Long
2 Beach, or City of Carson traffic impact guidelines. The 15 study intersections are shown on Figure 3.6-1 of
3 the Draft EIS/EIR. In addition, five Congestion Management Program (CMP) monitoring stations were
4 assessed in conformance with Los Angeles County Metropolitan Transportation Authority (LACMTA)
5 CMP guidelines all within five miles of the proposed Project site (see Figure 3.6-2 of the Draft EIS/EIR for
6 illustration of study area freeway segment locations), which is the appropriate distance of analysis for the
7 proposed Project.

8 The Commenter also states that the evaluation did not include the following truck idling circumstances:

- 9 A. When the Schuyler Heim Bridge is in the lifted position,
- 10 B. When trucks break down on the Vincent Thomas Bridge or the Gerald Desmond Bridge,
- 11 C. When there is an accident on I-110, I-701, or other connecting freeway,
- 12 D. While waiting for a container shipside,
- 13 E. While idling on the container yard,
- 14 F. While idling at fumigation facilities,
- 15 G. While idling at inspection facilities or gates,
- 16 H. While idling during lunch or breaks.

17
18 Regarding idling, the air quality analysis was conservative and assumed continuous operation of the
19 equipment engines for each working day for equipment and vehicles associated with the Project while in
20 use. Emissions during continuous vehicle operation are higher than those from idling, and thus, the
21 approach used represents a worst-case scenario. In addition, the proposed Project emphasizes the
22 importance of controlling idling emissions by including (in the mitigated analysis) all appropriate measures
23 within the power of the LAHD and that can be controlled by APL, such as mitigation measures MM AQ-3,
24 MM AQ-4, and MM AQ-5 during construction, as well as MM AQ-16 during operation.

25
26 Regarding the Health Impact Assessment and Off-Port Tidelands Property Community Impact Study,
27 please see the Response to Comment CFASE-10.

28 **Response to Comment CFASE-19**

29 The Commenter asserts that the Draft EIS/EIR should be revised because it did not include all emissions
30 sources, idling circumstances, or destinations. The Commenter also requests the preparation of a Health
31 Impact Assessment and a Public Health Survey to establish a public health baseline, establish a public
32 Health Care and Socioeconomic Mitigation Trust Fund, and to provide evidence that APL will comply with
33 a CARB schedule. Regarding the emission sources, idling, and destination comments, please see the
34 Response to Comments CFASE-10 and CFASE 18 (above). Regarding the request for a HIA and Public
35 Health Survey, please see the Response to Comment PCAC-1. Regarding the request for a Public health
36 Care and Socioeconomic Mitigation Trust Fund, mitigation has been provided to address health risk impacts
37 (see Section 3.2 of the Draft EIS/EIR). As discussed in Chapter 7 of the Draft EIS/EIR, the proposed
38 Project would not result in significant socioeconomic impacts that would warrant establishment of the
39 suggested mitigation trust fund. Regarding the request to provide proof of compliance with the CARB
40 schedule, it is unclear which schedule the Commenter is referring to.

41 **Response to Comment CFASE-20**

42 The Commenter asserts that the Draft EIS/EIR fails to do the following:

- 43 A. Conduct a noise study along freight transportation corridors,
- 44 B. Disclose that noise sensitive uses are located along freight corridors,

- 1 C. Identify Specific Off-Port Noise Sources (the list of off-port noise sources appears identical to the
2 Commenters previous list of off-port emission sources).

3 Regarding the comment on the noise study and sensitive receptors along transportation corridors, Section
4 3.11 of the Draft EIS/EIR included an evaluation of the Project's noise impacts, and included an
5 identification and evaluation of Project impacts on sensitive receptors. In addition, the noise evaluation
6 acknowledges Project operations (rail and traffic) would likely have the greatest effects on sensitive
7 receptors close to Terminal Island because they represent sensitive locations closest to the highest intensity
8 activities. At locations farther out, the Project's noise impacts would be less concentrated and
9 distinguishable from non-Project noise impacts, as rail and truck traffic become dispersed. At the sensitive
10 receptor locations closest to the rail and truck traffic, the Draft EIS/EIR discloses that there would be less
11 than significant impacts to those receptors (based on existing noise levels as determined through noise level
12 monitoring). Locations farther from the terminal have a much lower potential of being affected by Project
13 noise because trips would be dispersed.

14 Regarding the list of off-port noise sources, because those sources are not Project components, they are not
15 included in the Draft EIS/EIR noise impact evaluation. However, to the extent that Project trucks and trains
16 travel on the existing transportation systems, noise from those trucks and trains are included in the Noise
17 Section (Section 3.11) of the Draft EIS/EIR.

18 **Response to Comment CFASE-21**

19 The Commenter asserts that the Draft EIS/EIR fails to do the following:

- 20 A. State that measured sound levels do not comply with the City's Noise Ordinance or World health
21 Organization guidelines for community noise, and
- 22 B. Comply with WHO noise guidelines

23 In addition, the Commenter notes that the LAHD and BNSF failed to establish a Community Advisory
24 Committee to review noise issues and failed to conduct a CAC Environmental Justice Preconstruction
25 Noise Survey.

26 The community noise guidelines referenced by the Commenter are noise levels that are recommended for
27 communities and are usually community goals to strive for during the community planning process. The
28 LAHD, as a Lead Agency under CEQA, has discretion to select the methodology and standards of
29 significance it uses to measure impacts. The noise significance thresholds are based on the noise thresholds,
30 which were specifically developed by the City of Los Angeles (and approved by City Council) to evaluate
31 impacts under CEQA. Both the LAHD and USACE utilize the *L.A. CEQA Thresholds Guide* to evaluate
32 environmental impacts, as they were specifically developed for this purpose. In contrast, the community
33 noise guidelines referenced by the Commenter are general planning based noise guidelines or objectives to
34 be used in general and community plans, but are not specifically developed for purposes of impact
35 evaluation. The Commenter is referred to the *L.A. CEQA Thresholds Guide*.

36 Regarding the comment that the LAHD and BNSF establish a Community Advisory Committee on noise,
37 the recommendation is not a subject related to environmental review of this Project, and is not a measure
38 which would mitigate any significant noise impacts of this Project.

39 Regarding the comment that a Preconstruction Environmental Justice Noise Survey be conducted, noise
40 monitoring was performed as and the noise impacts of the proposed Project and alternatives were evaluated
41 in the Draft EIS/EIR. It is unclear why the Commenter is requesting a noise survey, but the noise level
42 monitoring performed for the Draft EIS/EIR also establishes the noise conditions prior to construction.

1 **Response to Comment CFASE-22**

2 The Commenter requests the following:

- 3 A. Include in the Draft EIS/EIR a long term noise evaluation up to 3 miles from the Project,
- 4 B. Implement an Environmental Justice fence line monitoring program overseen by the CAC,
- 5 C. Include a statement in the Draft EIS/EIR that noise levels do not comply with the Noise Ordinance
6 or World Health Organization Community Noise Guidelines,
- 7 D. Establish a Community Advisory Committee made up of Wilmington, Carson and Long Beach
8 residents to address Draft EIS/EIR deficiencies, and project issues that may arise during
9 construction,
- 10 E. Conduct Environmental Justice Preconstruction Noise Survey prior to construction,
- 11 F. Include a list of locations of off-port tidelands property truck destinations in San Pedro and
12 Wilmington,
- 13 G. Mitigate all noise impacts to a less than significant level,
- 14 H. Incorporate Environmental Justice Noise Standards into the Draft EIS/EIR to protect Wilmington,
15 Carson, and transportation corridor Environmental Justice communities.

16 Although the Commenter has requested that the Draft EIS/EIR include a long-term noise evaluation for
17 areas up to 3 miles away from the Project site, such a study is not warranted because the Draft EIS/EIR
18 disclosed that noise impacts are less than significant at sensitive receptor locations closer than 3-miles. It is
19 unclear why a 3-mile noise impact zone is being requested.

20 Although the Commenter has requested that an Environmental Justice Fence Line Monitoring Program be
21 established and monitored by a Community Advisory Committee, it is unclear what the purpose of such or
22 program would be, or why it is warranted. The Draft EIS/EIR did not identify a significant Project noise
23 impact.

24
25 Regarding the comment on WHO community noise guidelines, the need for a preconstruction noise survey,
26 and establishment of a CAC for noise issues, please see the Response to Comment CFASE-21 above.

27
28 Regarding the request for a list of truck destinations in Wilmington and San Pedro, there is no way to know
29 all of the truck destinations in advance and without individual truck destination monitoring.

30
31 The proposed Project identified a potential for construction noise impacts to receptors at Reservation Point,
32 but identified mitigation to reduce those impacts to a less than significant level.

33
34 Although the Commenter is requesting that Environmental Justice noise standards be incorporated into the
35 Draft EIS/EIR to protect receptors in Wilmington and Carson, the proposed Project would not result in
36 impacts to receptors in those communities. Regardless, mitigation has been provided to reduce construction
37 noise impacts during the noise intensive activity (pile driving), and the communities of Wilmington and
38 Carson are located too far from the Project site to be significantly affected.

1 **Response to Comment CFASE-23**

2 The Commenter asserts that the proposed Project would result in significant noise impacts during
3 construction and operation, and that adequate noise mitigation has not been provided.

4 The Commenter also states that the Draft EIS/EIR uses standards that allow high noise levels in
5 environmental justice communities, and recommends the use of specific provided noise standards.

6 The noise section of the Draft EIS/EIR evaluates noise impacts relative to the significance threshold for
7 noise provided in the *L.A. CEQA Thresholds Guide* (see the Response to Comment CFASE-21). The Draft
8 EIS/EIR identified a potential for significance noise impacts to sensitive receptors close to the Project site at
9 Reservation Point, but provided mitigation to reduce the impact to a less than significant level. Although the
10 Commenter requests that the provided noise standards be used in the noise evaluation, the Draft EIS/EIR
11 utilizes the City's CEQA thresholds because they have been developed specifically for such evaluations,
12 and because they effectively provide a method to evaluate the Projects noise impacts relative to existing
13 levels (consistent with CEQA baseline requirements). In regards to impact to environmental justice
14 populations, the Corp has adopted the City's significance thresholds, and uses them to in their NEPA
15 evaluations to identify high and adverse impacts to minority and low income populations. Because of this,
16 the significance thresholds for noise evaluations used in the Draft EIS/EIR (rather than the noise standards
17 suggested by the Commenter) are appropriate.

18 **Response to Comment CFASE-24**

19 The Commenter asserts that the following:

- 20
- 21 A. The Draft EIS/EIR fails to comply with Section 15060, 15065a, and 15126.2a of the California
 - 22 Environmental Quality Act.
 - 23 B. The Draft EIS/EIR fails to identify impacts to EJ Communities outside of the City of Los Angeles,
 - 24 C. The Port has caused disproportionate impacts to EJ communities with providing adequate mitigation,
 - 25 D. Port management is classist and racist,
 - 26 E. The Draft EIS/EIR fails to acknowledge that there is no Public Emergency Disaster Response Plan,
 - 27 F. The Port has not created an emergency fund to assist EJ Communities that could be affected by the
 - 28 Project,
 - 29 G. The Port has placed every EJ Community in extreme danger, and
 - 30 H. If there is a Port or APL emergency, that there are inadequate facilities to provide assistance.

31

32 Contrary to the comment, the Draft EIS/EIR complies with the reference CEQA sections by identifying
33 significant impacts of the proposed Project and alternative, by preparing an EIR (rather than a lower level
34 document), and by discussing anticipated environmental impacts, mitigation, and alternatives.

35

36 Chapter 5 of the Draft EIS/EIR contains an evaluation of the high and adverse impacts to minority and low
37 income populations, consistent with Executive Order 12898, *Federal Actions to Address Environmental*
38 *Justice in Minority Populations and Low-Income Populations*, which requires federal agencies to assess the
39 potential for their actions to have disproportionately high and adverse environmental and health impacts on
40 minority and/or low-income populations, and with the Council on Environmental Quality (CEQ) Guidance
41 for Environmental Justice Under NEPA (CEQ, 1997). Where the proposed Project (or alternative) has the
42 potential to result in a significant and unavoidable project-level or cumulative significant impact to a low
43 income or minority population, an environmental justice impact is identified in Chapter 5. The
44 environmental justice evaluation is also consistent with California state law regarding environmental justice.
45 The Draft EIS/EIR discusses high and adverse impacts to minority and low income population, and
46 provides mitigation, lease measures, and standard conditions of approval to reduce impacts to
47 environmental justice communities.

1
2 The Commenter believes that the LAHD is a classist and racist organization; these opinions are hereby
3 noted, but do not relate to the adequacy of the Draft EIS/EIR.
4

5 Regarding the comment that there is no Public Emergency Disaster Response Plan, Section 3.13 of the
6 Draft EIS/EIR evaluates the potential for the proposed Project and alternatives to affect the provision of law
7 enforcement and fire response in the event of an accident or emergency. The evaluation determined that
8 there is adequate response infrastructure and significant impacts to emergency services would not occur. In
9 addition, the Draft EIS/EIR evaluated the potential for the proposed Project to affect tsunami and terrorist
10 risks, and determined that significant impacts would not occur. It is unclear what impact the proposed
11 Project would result in that would require a public emergency, disaster response plan as mitigation.
12

13 Regarding the comment about an emergency fund to provide assistance to environmental justice
14 communities that could be affected by the proposed Project, the Draft EIS/EIR identifies mitigation
15 measures, lease measures, and standard conditions of approval that would reduce potential impacts to
16 environmental justice communities.
17

18 Regarding the comment that the LAHD has placed every environmental justice community in extreme
19 danger, and that if there is a Port or APL emergency, that there are inadequate facilities to provide
20 assistance, the opinions of the Commenter are noted. As discussed above, the Draft EIS/EIR evaluated the
21 proposed Project's affect on public services, including law enforcement and fire suppression services, and
22 determined that a significant impact to these services would not occur.

23 **Response to Comment CFASE-25**

24 The Commenter rejects the summary of impact determinations, the mitigation monitoring conclusions, and
25 the significant unavoidable adverse impact conclusions in the Draft EIS/EIR and they believe the
26 determinations are based on inaccuracies, and incomplete disclosure of impacts, as mentioned elsewhere in
27 the comment letter. The Commenter's rejection of the Draft EIS/EIR determinations are noted and has been
28 incorporated into the Final EIS/EIR for review and consideration by the decision-makers prior to any action
29 on the proposed Project.

30 **Response to Comment CFASE-26**

31 The Commenter requests the following:

- 32 A. The Draft EIS/EIR identify all applicable City, County, Regional, State, and Federal
33 Environmental, Environmental Justice, Public Health/Safety, and Sustainability legal requirements,
- 34 B. The Draft EIR/EIS include a matrix demonstrating compliance with the requirements,
- 35 C. The Draft EIR/EIS include non-City of Los Angeles Environmental Justice Communities,
- 36 D. The Port hire an Environmental Justice attorney and consultant to advise and supervise the port,
- 37 E. The Draft EIS/EIR include an Environmental Justice plan that includes a monitoring and
38 compliance element,
- 39 F. An Environmental Justice advisory committee be established and comprised of representatives
40 from Environmental Justice communities,
- 41 G. The Draft EIS/EIR include a Health Impact Assessment, Off-Port Tidelands Property Community
42 Impact Nexus Study, Micro Environmental Justice Climate Change Impact Assessment, Negative
43 Socioeconomic assessment, and a Public Emergency, Disaster and Response Plan.

- 1 Regarding request A and B, as discussed in the Response to Comment CFASE-24, the environmental
2 justice evaluation in Chapter 5 of the Draft EIS/EIR complies with Executive Order 12898, Federal Actions
3 To Address Environmental Justice in Minority Populations and Low-Income Populations, CEQ Guidance
4 for Environmental Justice Under NEPA (CEQ, 1997), and California state law regarding environmental
5 justice. The Commenter is referred to Section 5.3 of Chapter 5 of the Draft EIS/EIR for a discussion of the
6 applicable environmental justice regulations.
- 7 Regarding request C, the Draft EIS/EIR includes an environmental justice evaluation based on high and
8 adverse impact that could extend to Census Tract that contain minority or low income populations. As
9 stated in Chapter 5, Los Angeles County is used as the comparison population because it is considered
10 representative of the general population that could be affected by the proposed project or Alternative. The
11 Commenter is referred to Figures 5-1 and 5-2 of the Draft EIS/EIR, which shows the minority and low
12 income populations in the Project vicinity (including Census Tracts outside of the City of Los Angeles) on
13 which the environmental justice evaluation was based.
- 14 Regarding request D, the LAHD is not aware of a requirement to hire an environmental justice attorney
15 and/or consultant to oversee Port activities, and respectfully declines the request.
- 16 Regarding request E, the LAHD will be preparing a Mitigation Monitoring and Reporting Program (MMRP)
17 that tracks the implementation of all mitigation measures required in the Draft EIS/EIR, including
18 mitigation measures that would lessen impacts to minority or low income populations. The MMRP will be
19 considered by the Board of Harbor Commissioners and will be available if the Board approves the proposed
20 Project or alternative.
- 21 Regarding the request to establish an Environmental Justice Advisory Committee, LAHD is not aware of a
22 requirement to establish such a committee, and does not believe that the proposed Project warrants
23 establishment of such a committee.
- 24 Regarding the request for a Health Impact Assessment and Off-Port Tidelands Property Community Impact
25 Nexus Study, please see the Responses to Comments PCAC-1 and CFASE-10. Regarding the request to
26 prepare a Negative Socioeconomic evaluation, please see the Response to Comment CFASE-14. Regarding
27 the request to prepare a Public Emergency, Disaster and Response Plan, please see the Response to
28 Comment CFASE-24. Regarding the request to prepare a Micro Environmental Justice Climate Change
29 Impact Assessment, LAHD is not aware of a requirement to perform such an evaluation. General weather
30 patterns and localized features would be the primary determinant of localized climate conditions, and
31 neither the proposed Project nor alternatives is expected to influence localized climate conditions off-port.
- 32 The Commenter's requests are noted and have been incorporated into the Final EIS/EIR for review and
33 consideration by the decision-makers prior to any action on the proposed Project.

34 **Response to Comment CFASE-27**

- 35 The Commenter's request is noted and has been incorporated into the Final EIS/EIR for review and
36 consideration by the decision-makers prior to any action on the proposed Project.
37

38

From: RSF9873@aol.com [<mailto:RSF9873@aol.com>]
Sent: Sunday, December 18, 2011 8:08 AM
To: Ceqacomments
Subject: APL Expansion

Will the new plans for APL include automation which will take away jobs and effect local economies which is the last thing that needs to happen, or will it create more jobs and put people back to work and help our country get back to economic recovery.

RSF-1

-----Confidentiality Notice-----
This electronic message transmission contains information from the Port of Los Angeles, which may be confidential. If you are not the intended recipient, be aware that any disclosure, copying, distribution or use of the content of this information is prohibited. If you have received this communication in error, please notify us immediately by e-mail and delete the original message and any attachment without reading or saving in any manner.

1 **2.3.5 Individuals/Companies**

2 **RSF9873@aol.com (RSF)**

3 **Response to Comment RSF-1**

4 Thank you for your review and comment on the Draft EIS/EIR. As detailed throughout Chapter 2, Project
5 Description, of the Draft EIS/EIR, it is foreseeable that technology advancements could result in
6 replacement of some of the traditional backland operations at the APL Terminal through the use of an
7 automated container handling system on the 41-acre backland area adjacent to proposed Berth 306. As
8 described in Section 7.3.2.2 of the Draft EIS/EIR, if installed, automation of the 41-acre backland area is
9 expected to result in fewer jobs at the terminal when compared to a conventional terminal. However, the
10 proposed Project would continue to generate new direct long-term jobs associated with expanded operations
11 associated with the remainder of the site (i.e., the existing 291-acres). In addition, as noted throughout
12 Chapter 2 of the Draft EIS/EIR, given that future throughput under both an automated and conventional
13 backland operations on the 41-acre area would remain the same the number of secondary jobs generated by
14 the Project under either scenario would not vary substantially.

From: Arthur Crable [<mailto:dennis@crable-associates.com>]
Sent: Thursday, January 12, 2012 10:40 PM
To: Ceqacomments
Cc: dennis crable
Subject: Berths 302-306 APL Container Terminal Project

As in the SCIQ DEIR Air Quality section, the Port attempts in this DEIR isolate project impacts by subtracting baseline from project impacts, which is not possible. To isolate and assess project impacts to the environment, as required by CEQA, one must **ADD** project impacts to an existing conditions baseline, not subtract; then one applies the result to significance thresholds. Baseline is a starting point and equals zero for the purpose of quantifying project impacts; this shouldn't be so confusing for CEQA professionals. Subtracting existing conditions from project analyzes the effect of the environment on the project, not the project on the environment (as required by CEQA). This mistaken method of analyzing project impacts undermines the validity of results in other sections of the DEIR such as environmental justice.

Crable-1

Also, the federal assessment of the project never compares the project to existing conditions, as required by both CEQA and NEPA. I suggest you scrap your "baseline equals No Federal Action" tack unless you want to take out the arbitrary growth; a baseline analysis must include pre-project conditions, not future conditions the NFA or No Project Alternative analysis is used to project potential future conditions without the project.

Crable-2

In sum, please explain what rationale (or mathematical formula) leads you to believe that subtracting baseline from project equals project impacts, and what case law or statutory authority supports your use of future conditions (in this set of facts) as part of baseline for the NEPA portion of this document as noted in the Air Quality analysis section.

Crable-3

Dennis

A. Dennis Crable
Crable & Associates, Environmental Consultants
765 West Altadena Drive

Altadena, California 91001
626.676-6993

Certified SBE (MTA No. 38662), MBE, DBE, UDBE

(Specializing in CEQA/NEPA project management for over 17 years...)

1 **Arthur Crable (Crable)**

2 **Response to Comment Crable-1**

3 Thank you for your review and comment on the Draft EIS/EIR. The comment that the project's air
4 emissions should be added to the baseline then the resulting emissions compared to the significance
5 thresholds is incorrect. CEQA requires that the impacts of a project be determined relative to baseline
6 conditions (see *Communities for a Better Environment v. South Coast Air Quality Management District*
7 [2010] 48 Cal. 4th 310). Section 3.2.4.1 of the Draft EIS/EIR describes the methodology used to evaluate
8 the proposed Project's air quality impacts based on emissions that exceed the baseline conditions. As
9 described in Chapter 2, the existing APL terminal was operational during the one-year period prior to July
10 2009 (when the Notice of Preparation was issued), and the emissions associated with the existing terminal
11 operations constituted the baseline terminal emissions under CEQA. Table 2-1 in Chapter 2 summarizes
12 the existing terminal operations (one-year period prior to July 2009) that form the basis for the baseline air
13 emissions calculations. In Section 3.2, air emissions from terminal operations are calculated for the year
14 2027 (or other study year) based on total terminal throughput, which includes both the baseline throughput
15 and throughput from the expanded terminal under the proposed Project (or alternative). Since the total
16 terminal air emissions in each study year include the baseline air emissions, those emissions are subtracted
17 from the total air emissions in order to identify the air emissions associated with the Project that exceeds the
18 baseline level. The incremental levels are then compared to the significance thresholds to determine
19 significance under CEQA. Although the Commenter may not agree with this methodology, it is the proper
20 approach to evaluate the significance of air quality impacts under CEQA. If the Port were to adopt the
21 Commenter's approach and include the terminal's air emissions from the baseline year in the total air
22 emission (for each study year) then compare this to the significance thresholds, the Port would improperly
23 attribute existing baseline conditions as a Project impact, which would conflict with CEQA's requirement to
24 evaluate impacts relative to baseline conditions.

25 **Response to Comment Crable-2**

26 It is unclear what the Commenter means when he states that the federal assessment never compares the
27 project to existing conditions as required by CEQA and NEPA. CEQA is a state statute that does not
28 pertain to how a federal impact analysis is performed. It should be noted that the impact evaluation
29 performed under CEQA throughout Chapter 3 does indeed evaluate the impacts of the proposed Project and
30 alternatives relative to the existing conditions (or pre-Project conditions). Under NEPA, the federal
31 assessment of impacts of the proposed Project and alternatives are performed relative to the NEPA baseline
32 (see Section 2.6.2 of the Draft EIS/EIR). As described in Section 2.6.2, the NEPA baseline is not bound by
33 statute to a "flat" or "no-growth" scenario; rather, it includes activities that would occur absent a federal
34 action (i.e., absent a USACE permit), including increases in terminal operations and throughput over the life
35 of the existing terminal that could and would occur in the absence of a federal permit for the proposed
36 expansion. In the case of the Berths 302-306 [APL] Container Terminal project, the No Federal Action
37 alternative represents the NEPA baseline, and evaluates the impacts that would and could occur without
38 federal action/federal permit. Because NEPA requires an assessment of impacts relative to the NEPA
39 baseline, or the No Federal Action conditions, the impact analyses throughout Chapter 3 utilize this
40 methodology. Further, NEPA does not require the federal impact analysis to consider pre-Project
41 conditions, as suggested by the Commenter.

42 **Response to Comment Crable-3**

43 Please see the Response to Comments Crable -1 and Crable-2 above.
44

William B. Reynolds
1738 N. Marine Dr.
Orange, CA 92867

February 15, 2012

U.S. Army Corps of Engineers
Los Angeles District
Regulatory Division
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Suite 110
Ventura, California 93001

City of Los Angeles Harbor Department
Christopher Cannon, Director
Environmental Management Division
425 S. Palos Verdes Street
San Pedro, California 90731

Subject: APL Terminal Project / Berths 302-306 / SCH#2009071031

Dear Sirs;

I am pleased to submit the following public comments on the Draft Environmental Impact Report for Berths 302-306 APL Container Terminal Project. After review of the draft EIR for the project, I would like to voice my support for the submitted project that includes the expansion at Berth 306 and the redevelopment at Berths 302-305 of the existing APL Terminal. As presented, the environmental impacts associated with the project can be mitigated to levels that are less than significant providing for a sound environmentally conscience project.

Construction of this project will create approximately 1,169 direct jobs and 1,601 indirect jobs over the two year period. This workforce will come from our local residents that live in our local communities located in and around the Port of Los Angeles. This two year period will create almost 3,400 jobs and provide positive economic benefits to many groups and industries. Longer term, the project will provide for 2,756 permanent jobs in 2015, increasing to 3,885 permanet jobs in 2027. Most of these jobs created would be in the transportation and public utilities industrial sector of the local and regional economy. Secondary jobs totaling 2,914 in 2015 and increasing to 4,108 in 2027 will occur in many sectors of industry, but all attributable to this project.

The economic benefits of this project far exceed any of the environmental impacts that are presented in the Draft EIR. Based on the benefits of the project to the local, regional and state economies it is with great enthusiasm that I support this project and look forward to the redevelopment and expansion of Berths 302-306 of the APL Marine Terminal.

I appreciate the ability to provide you these comments and support of the subject project.

RNLDS-1

Sincerely,



Bill Reynolds

1 **William (Bill) Reynolds (Reynolds)**

2 **Response to Comment Reynolds-1**

3 Thank you for your review and comment on the Draft EIS/EIR.

4

Ty McMichael
3 Clipper Road, Apt. B
Rancho Palos Verdes, CA 90275

February 16, 2012

U.S. Army Corps of Engineers
Los Angeles District
Regulatory Division
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Suite 110
Ventura, California 93001

Via E-Mail: theresa.stevens@usace.army.mil

City of Los Angeles Harbor Department
Christopher Cannon, Director
Environmental Management Division
425 S. Palos Verdes Street
San Pedro, California 90731

Via E-Mail: ceqacomment@portla.org

Subject: APL Terminal Project / Berths 302-306 / SCH#2009071031

To whom it may concern;

I am submitting the following public comments on the Draft Environmental Impact Report for Berths 302-306 APL Container Terminal Project. After review of the draft EIR for the project, I would like to express my support for the project that includes the expansion at Berth 306 and the redevelopment at Berths 302-305 of the existing APL Terminal. As presented, the environmental impacts associated with the project can be mitigated to levels that are less than significant providing for a sound environmentally conscience project.

Construction of this project will create approximately 1,169 direct jobs and 1,601 indirect jobs over the two year period. This workforce will come from our local residents that live in our local communities located in and around the Port of Los Angeles. This two year period will create almost 3,400 jobs and provide positive economic benefits to many groups and industries. Longer term, the project will provide for 2,756 permanent jobs in 2015, increasing to 3,885 permanent jobs in 2027. Most of these jobs created would be in the transportation and public utilities industrial sector of the local and regional economy. Secondary jobs totaling 2,914 in 2015 and increasing to 4,108 in 2027 will occur in many sectors of industry, but all attributable to this project.

The economic benefits of this project far exceed any of the environmental impacts that are presented in the Draft EIR. Based on the benefits of the project to the local, regional and state economies, I enthusiastically support this project and look forward to the redevelopment and expansion of Berths 302-306 of the APL Marine Terminal.

I appreciate the ability to provide you these comments and support of the subject project.

Sincerely,



Ty McMichael

1 **Ty McMichael (TM)**

2 **Response to Comment TM-1**

3 Thank you for your review and comment on the Draft EIS/EIR.

4

February 17, 2012

Los Angeles Harbor Department
Christopher Cannon, Director Environmental Management
425 S. Palos Verdes Street
San Pedro, CA 90731

U.S. Army Corps of Engineers, Los Angeles District
Regulatory Division
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Suite 110
Ventura, CA 93001

Subject: Comments Submittal RE Berths 302-306 [APL] Container Terminal Project
Draft EIR/EIS

Summary

I appreciate that the Port plans important measures to reduce air quality impacts and I request that further actions be implemented from among current capabilities, such as more rapid phase-in of Alternative Marine Power MM AQ-9 which would result in great reduction in toxic emissions, to reduce the significant air quality impacts foreseen at start of operations. Please see detailed Comments below.

RH-1

Recognition

I appreciate and recognize the Port for the following:

- 1) Requirements applicable to Construction in MM AQ-3 that On-Road truck idling will be restricted to five minutes and in MM AQ-4 that dredging equipment be electric.
- 2) Requirement applicable to Operations in MM AQ-15 that Yard Equipment shall meet an accelerated schedule for USEPA standards compliance and a designated schedule for installation of Verified Diesel Emission Controls.
- 3) Recognition in LM AQ-1 and LM AQ-2 of the significant reduction in impacts that can result from advancing technologies.
- 4) Inclusion of the chronic non-cancer hazard index and acute non-cancer hazard index in the Health Risk Assessment.

RH-2

Recommendations

As the Proposed Project would increase criteria pollutants related to air quality and the resulting impacts are defined as significant and unavoidable in the area already considered a Federal non-attainment area for Air Quality and causing significantly increased health risks to critical sensitive receptors, the following revisions are requested to reduce impacts.

Recommendations Applicable to Construction

- 1) Revise in MM AQ-1, Harborcraft utilization of USEPA Tier 3 engines or cleaner, the exceptions #2 and #3 to clarify that such excepted equipment cannot be utilized until enhanced reduction controls (e.g., particulate trap, catalytic reduction device, etc.) are placed on the uncontrolled equipment.
- 2) Revise MM AQ-3 # 1 to require that trucks hauling any debris or fill material will be fully-covered while operating on and off Port property and # 3 b) and c) to require

RH-3

RH-4

- | | |
|--|---------------|
| that Import Haulers and Earth Movers used in construction will be required to comply with EPA 2007 or better on-road emission standards for PM10 and NOx. | RH-4 Cont. |
| 3) Require in MM AQ-4 that construction equipment incorporate latest emissions-saving technology without qualification for, "if feasible," or define feasibility exclusions and eliminate possibility for exceptions referenced on page 3.2-2 applicable to requirement for trucks' compliance with USEPA standards. | RH-5 |
| 4) Revise MM AQ-7 to require that, if a CARB-certified technology with better emission performance than MM AQ-1 through MM AQ-6 becomes available, the tenant/contractor will be required to obtain/implement the better technology within a defined schedule such as within 90 days of availability. | RH-6 |
| 5) Require that Off-Road Construction Equipment idling be restricted to maximum of five (5) minutes when not in use without qualification or exception. | RH-7 |
| 6) Implement a requirement for utilization of Best Available Control Technology (BACT) similar to CARB's regulation applicable to Mobile Cargo Handling Equipment (CHE) and that would require the contractors/lessee to accelerate equipment turnovers or install emissions reduction devices, such as Verified Diesel Emissions Controls, or to contract operators that utilize BACT applicable to all equipment requirements other than Cargo Handling Equipment. | RH-8 |
| <u>Recommendations Applicable to Operations</u> | |
| 7) Increase implementation rate for MM AQ-9 Alternative Marine Power to require 80 percent of ship calls at completion of Project in 2014 and 95 percent of total ship calls in 2017 with allowance for 92 to 93 percent verifiable compliance as may result from equipment failure. Please note the EIR reference, "... a ship hoteling with AMP reduces its criteria emissions 71 to 93 percent." | RH-9 |
| 8) Require incorporation in MM AQ-12 of all available emission reduction technology when using or retrofitting ships bound for the Port of Los Angeles rather than allowing, "the tenant to determine the feasibility of incorporation" of such technology. | RH-10 |
| 9) Implement a requirement for utilization of BACT that would require the lessee to accelerate equipment turnovers, install emissions reduction devices or to contract operators that utilize BACT applicable to all equipment requirements. | RH-11 |
| 10) Define specific requirements for implementation of new technologies referenced in LM AQ-1 rather than allowance for, "the tenant shall work with the Port to implement," and/or require implementation of newly identified emissions-reduction technology at a rate of incorporation such as 25 percent within one year of identification, 50 percent within two years, and 100% within five years. | RH-12 |
| 11) Require in LM AQ-2 the replacement of existing measure(s) with new technology proven to yield better emissions reduction performance within a defined implementation schedule without allowance for, "the technology could replace the existing measure pending approval by the Port." | RH-13 |

Thank you,



Richard Havenick
3641 South Parker Street
San Pedro CA 90731

1 **Richard Havenick (RH)**

2 **Response to Comment RH-1**

3 Thank you for your recognition of the LAHD's efforts to reduce air quality impacts. Regarding the
4 recommendation to change mitigation measure MM AQ-9, the comment is noted. The mitigation measure
5 MM AQ-9 is in compliance with CAAP measures and appropriate as written considering the worldwide
6 APL fleet and vessels anticipated under the proposed Project.

7 **Response to Comment RH-2**

8 Thank you for your comment. In addition, please refer to Response to Comment PCAC-5 for additional
9 information.

10 **Response to Comment RH-3**

11 Regarding the recommendation to change mitigation measure MM AQ-1, the comment is noted. The
12 CAAP measures are restrictions and requirements geared at requiring construction contractors working
13 within the LAHD's jurisdiction to use the cleanest feasible construction equipment. The LAHD has
14 determined that a Port-wide approach at implementing the CAAP through mitigation applied on individual
15 projects, such as mitigation measure MM AQ-1, which is the most effective and feasible way to achieve
16 Port-wide compliance.

17 **Response to Comment RH-4**

18 Regarding the recommendation to change mitigation measure MM AQ-3, the comment is noted. The
19 mitigation measure MM AQ-3 is in compliance with CAAP measures and appropriate as written for the
20 proposed Project. In addition, mitigation applied to the proposed Project, such as MM AQ-3, is consistent
21 with the LAHD's Sustainable Construction Guidelines For Reducing Air Emissions (Sustainable
22 Construction Guidelines).

23 **Response to Comment RH-5**

24 Regarding the recommendation to change mitigation measure MM AQ-4, the comment is noted. The
25 mitigation measure MM AQ-4 is in compliance with CAAP measures and appropriate as written for the
26 proposed Project. In addition, as detailed in Response to Comment USEPA-3, the Draft EIS/EIR includes
27 lease measure LM AQ-1, which requires that the terminal operator to periodically implement new emissions
28 reduction technologies as they become available/feasible. As shown in Chapter 3, modifications to the
29 Draft EIS/EIR, lease measure LM AQ-1 has also been revised to reflect a revision of the 7 year lease
30 reopener to a more stringent 5 year reopener.

31 **Response to Comment RH-6**

32 Regarding the recommendation to change mitigation measure MM AQ-7, the comment is noted. Refer to
33 Response to Comment RH-5 above regarding lease measure LM AQ-1.

34 **Response to Comment RH-7**

35 Regarding the recommendation to change off-road construction equipment idling to maximum of 5 minutes,
36 the comment is noted. Mitigation measure MM AQ-4 includes an idling restriction of a maximum of 5

1 minutes that would be applied to off-road construction equipment being used at the Project site during
2 construction. In addition, please see the Response to Comment USEPA-18.

3 **Response to Comment RH-8**

4 Comment noted. The Draft EIS/EIR analysis assumes compliance with the CAAP. In fact, proposed
5 Project-specific mitigation measures applied to reduce air emissions and public health impacts are
6 consistent with, and in some cases exceed, the emission-reduction strategies of the CAAP. The Draft
7 EIS/EIR also includes lease measures prescribed for the proposed Project or alternative that provides a
8 means for additional measures to be incorporated into the applicant's/tenant's lease should the CAAP be
9 strengthened or new technology become available in the future. In addition, implementation of the LAHD's
10 Sustainable Construction Guidelines is another way to reduce emissions from construction activity.

11 **Response to Comment RH-9**

12 Regarding the recommendation to change mitigation measure MM AQ-9, the comment is noted. The
13 mitigation measure MM AQ-9 is in compliance with CAAP measures and appropriate as written
14 considering the worldwide APL fleet and vessels anticipated under the proposed Project.

15 **Response to Comment RH-10**

16 Regarding the recommendation to change mitigation measure MM AQ-12, the comment is noted. As it
17 relates to the OGV mitigation measures associated with the proposed Project (MM AQ-11 and MM AQ-12),
18 the Draft EIS/EIR analysis assumes compliance with the CAAP. In fact, proposed Project-specific
19 mitigation measures applied to reduce air emissions and public health impacts are consistent with, and in
20 some cases exceed, the emission-reduction strategies of the CAAP. The Draft EIS/EIR also includes lease
21 measures prescribed for the proposed Project or alternative that provides a means for additional measures to
22 be incorporated into the tenant's lease should the CAAP be strengthened or new technology becomes
23 feasible in the future. In addition, please see the Response to Comment SCAQMD-13.

24 **Response to Comment RH-11**

25 Comment noted. The Draft EIS/EIR includes lease measures prescribed for the proposed Project or
26 alternative that provides a means for additional measures to be incorporated into the tenant's lease should
27 the CAAP be strengthened or new technology be feasible in the future. It should be noted that compliance
28 with the CAAP in some cases accelerates compliance with CARB regulations. In addition, as detailed in
29 Response to Comment USEPA-6, the LAHD is involved in mitigation throughout the Port and adjacent
30 communities, including the establishment of a Port Communities Mitigation Trust Fund to fund mitigation
31 and grant projects to help offset past, present, and future impacts from Port Projects on off-port areas in the
32 communities of Wilmington and San Pedro. If the proposed Project were approved, the deposit to this Fund
33 is anticipated to be over \$4.2 million and could fund projects that contribute to the furtherance or
34 development of potential projects, analysis of project results, or in furtherance of a mitigation goal or other
35 requirement.

36 **Response to Comment RH-12**

37 Regarding the recommendation to change lease measure LM AQ-1, the comment is noted. The LAHD's
38 approach to facilitate the demonstrations, development and implementation of new emission-reduction
39 technologies is to utilize a Port-wide strategy rather than on a terminal-by-terminal approach. A Port-wide
40 approach allows such technologies to be demonstrated, developed, and implemented uniformly without
41 creating competitive disadvantages between terminals and Ports, as well as in a more coordinated manner.

1 Refer to Response to Comments USEPA-3 and USEPA-17 for additional discussion to LM AQ-1 and a
2 Port-wide strategy to future technologies to reduce air emissions. Regardless, as a company APL is a leader
3 in participating in the piloting of new technologies and is a welcome partner for the LAHD in addressing
4 future technologies (refer to Response to Comment USEPA-8 for details on commitments made by APL to
5 reduce air emissions). In addition, the way that LM AQ-1 is written provides greater implementation
6 flexibility than the Commenter's suggested revisions, as timing and implementation under existing language
7 can be added once the specific technology has been identified. In addition, please see the Response to
8 Comment SCAQMD-8.

9 **Response to Comment RH-13**

10 Comment note. Please refer to Response to Comment RH-12 above.
11
12
13



February 14, 2012

U.S. Army Corps of Engineers
Los Angeles District
Regulatory Division
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Suite 110
Ventura, California 93001
Via E-Mail: theresa.stevens@usace.army.mil

City of Los Angeles Harbor Department
Christopher Cannon, Director
Environmental Management Division
425 S. Palos Verdes Street
San Pedro, California 90731
Via E-Mail: cegacomments@portla.org

Subject: Support of the APL Terminal Project - Berths 302-306

Dear Ms. Stevens and Mr. Cannon;

Please accept Marine Mechanical Inc.'s comments on the Draft Environmental Impact Report for Berths 302-306 APL Container Terminal Project. After review of the draft EIR for the project, Marine Mechanical Inc. supports the submitted project that includes the expansion at Berth 306 and the redevelopment at Berths 302-305 of the existing APL Terminal. As presented, the environmental impacts associated with the project can be mitigated to levels that are less than significant providing for a sound environmentally conscience project.

Construction of this project will create approximately 1,169 direct jobs and 1,601 indirect jobs over the two year period. This workforce will come from our local residents that live in our local communities located in and around the Port of Los Angeles. This two year period will create almost 3,400 jobs and provide positive economic benefits to many groups and industries.


Longer term, the project will provide for 2,756 permanent jobs in 2015, increasing to 3,885 permanet jobs in 2027. Most of these jobs created would be in the transportation and public utilities industrial sector of the local and regional economy. Secondary jobs totaling 2,914 in 2015 and increasing to 4,108 in 2027 will occur in many sectors of industry, but all attributable to this project.

MMI-1

The economic benefits of this project far exceed any of the less than significant environmental impacts that are presented in the Draft EIR. Based on the benefits of the project to the local, regional and state economies it is with great enthusiasm that Marine Mechanical Inc. supports this project and looks forward to the redevelopment and expansion of Berths 302-306 of the APL Marine Terminal.

We appreciate the ability to provide you these public comments and voice our support of the subject project.

Sincerely,

A handwritten signature in cursive script that reads "Diana Rodriguez".

Diana Rodriguez
Marine Mechanical Inc.

MMI-1
Cont.

1 **Marine Mechanical Inc. (MMI)**

2 **Response to Comment MMI-1**

3 Thank you for your review and comment on the Draft EIS/EIR.

4



Post Office Box 5100
San Pedro, CA 90733
Phone: (310) 549-8030
Fax: (310) 549-7365

February 14, 2012

U.S. Army Corps of Engineers
Los Angeles District
Regulatory Division
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Suite 110
Ventura, California 93001

Via E-Mail: theresa.stevens@usace.army.mil

City of Los Angeles Harbor Department
Christopher Cannon, Director
Environmental Management Division
425 S. Palos Verdes Street
San Pedro, California 90731

Via E-Mail: ceqacomment@portla.org

Subject: APL Terminal Project / Berths 302-306 / SCH#2009071031

Dear Sirs;

Maintenance Turnaround Services is pleased to submit the following public comments on the Draft Environmental Impact Report for Berths 302-306 APL Container Terminal Project. After review of the draft EIR for the project, Maintenance Turnaround Services supports the submitted project that includes the expansion at Berth 306 and the redevelopment at Berths 302-305 of the existing APL Terminal. As presented, the environmental impacts associated with the project can be mitigated to levels that are less than significant providing for a sound environmentally conscience project.

The Port of Los Angeles provides for significant and substantial contributions to the local, regional and national economy. It creates tens of billions of dollars in industry sales each year in the southern California region. These sales translate into jobs, wages, and salaries, including state and local taxes. Recent studies have determined that the Port of Los Angeles supports directly and indirectly over 1.1M full and part-time jobs throughout California and 3.3M jobs nationwide. Marine terminals, such as APL, generate a large number of these jobs, such as trucking, freight forwarders, customs house brokers, warehousing, steamship agents, chandlers, surveyors, etc.

Construction of this project will create approximately 1,169 direct jobs and 1,601 indirect jobs over the two year period. This workforce will come from our local residents that live in our local communities located in and around the Port of Los Angeles. This two year period will create almost 3,400 jobs and provide positive economic benefits to many groups and industries.

MTS-1

Longer term, the project will provide for 2,756 permanent jobs in 2015, increasing to 3,885 permanent jobs in 2027. Most of these jobs created would be in the transportation and public utilities industrial sector of the local and regional economy. Secondary jobs totaling 2,914 in 2015 and increasing to 4,108 in 2027 will occur in many sectors of industry, but all attributable to this project.

The economic benefits of this project far exceed any of the less than significant environmental impacts that are presented in the Draft EIR. Based on the benefits of the project to the local, regional and state economies it is with great pleasure that Maintenance Turnaround Services supports this project and looks forward to the redevelopment and expansion of Berths 302-306 of the APL Marine Terminal.

We appreciate the ability to provide you these public comments and voice our support of the subject project.

Sincerely,



Telvis Artis
Maintenance Turnaround Services

MTS-1
Cont.

1 **Maintenance Turnaround Services (MTS)**

2 **Response to Comment MTS-1**

3 Thank you for your review and comment on the Draft EIS/EIR.

4



February 14, 2012

U.S. Army Corps of Engineers
Los Angeles District
Regulatory Division
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Suite 110
Ventura, California 93001

Via E-Mail: theresa.stevens@usace.army.mil

City of Los Angeles Harbor Department
Christopher Cannon, Director
Environmental Management Division
425 S. Palos Verdes Street
San Pedro, California 90731

Via E-Mail: ceqacomment@portla.org

Subject: APL Terminal Project / Berths 302-306 / SCH#2009071031

Dear Sirs;

Please accept Harbor Industrial's public comments on the Draft Environmental Impact Report for Berths 302-306 APL Container Terminal Project. After review of the draft EIR for the project, Harbor Industrial supports the submitted project that includes the expansion at Berth 306 and the redevelopment at Berths 302-305 of the existing APL Terminal. As presented, the environmental impacts associated with the project can be mitigated to levels that are less than significant providing for a sound environmentally conscience project.

The Port of Los Angeles provides for significant and substantial contributions to the local, regional and national economy. It creates tens of billions of dollars in industry sales each year in the southern California region. These sales translate into jobs, wages, and salaries, including state and local taxes. Recent studies have determined that the Port of Los Angeles supports directly and indirectly over 1.1M full and part-time jobs throughout California and 3.3M jobs nationwide. Marine terminals, such as APL, generate a large number of these jobs, such as trucking, freight forwarders, customs house brokers, warehousing, steamship agents, chandlers, surveyors, etc.

Construction of this project will create approximately 1,169 direct jobs and 1,601 indirect jobs over the two year period. This workforce will come from our local residents that live in our local communities located in and around the Port of Los Angeles. This two year period will create almost 3,400 jobs and provide positive economic benefits to many groups and industries.


HI-1

Longer term, the project will provide for 2,756 permanent jobs in 2015, increasing to 3,885 permanent jobs in 2027. Most of these jobs created would be in the transportation and public utilities industrial sector of the local and regional economy. Secondary jobs totaling 2,914 in 2015 and increasing to 4,108 in 2027 will occur in many sectors of industry, but all attributable to this project.

The economic benefits of this project far exceed any of the less than significant environmental impacts that are presented in the Draft EIR. Based on the benefits of the project to the local, regional and state economies it is with great pleasure that Harbor Industrial Services Corporation supports this project and looks forward to the redevelopment and expansion of Berths 302-306 of the APL Marine Terminal.

We appreciate the ability to provide you these public comments and voice our support of the subject project.

Sincerely,

A handwritten signature in blue ink, appearing to read "W. Michael Hawke", with a long horizontal flourish extending to the right.

W. Michael Hawke
Harbor Industrial

HI-1
Cont.

1 **Harbor Industrial (HI)**

2 **Response to Comment HI-1**

3 Thank you for your review and comment on the Draft EIS/EIR.

4

From: Jesse Marquez [mailto:jnmarquez@prodigy.net]
Sent: Thursday, February 16, 2012 11:00 AM
To: Christopher Cannon; jgreenrebstock@portla.org; Stevens, Theresa SPL
Cc: John G. Miller; Janet Gunter; Kathlene Woodfield; Chuck Hart; Frank O'Brien; Jody James; Bonnie Christensen; Sofia Carrillo; Drew Wood; Ricardo Pulido; Flavio Mercado; jgaribay@ucla.edu; jnmarquez@prodigy.net; Mary Silverstein
Subject: Request to remove pass word protected APL DEIS/DEIR PDF Document ASAP

Port of Los Angeles
USACE

The Port of Los Angeles in past EIS/EIR's has never password protected documents, by doing so CFASE and member of the public are unable to copy sections, paragraphs, tables, diagrams, illustrations, information etc. and include them in our public comments. This prevents the U.S. Army Corps of Engineers, Board of Harbor Commissioners, Regulatory Agencies, Decision Makers and members of the public from being able to read public comments in a more clear context when referencing the DEIS/DEIR. The time to retype or recopy information is significant and limits CFASE and members of the public from being able to fully comment and engage in the legally protected public participation process.

CFASE Requests: The U.S. Army Corps of Engineers and the Port of Los Angeles a public agency provide all CEQA/NEPA required documents in a unlocked, unpassword protected PDF and Microsoft Word document format. There is an extra cost to CFASE and members of the public to purchase special PDF software, pay for regular future upgrades and its is more difficult to copy and paste PDF documents and information than the standard word processing Microsoft Word program. It is also a fact that the original DEIS/DEIR document is typed by the Port of Los Angeles and its consultants in Word and then converted to a PDF. We ask that you upload to the POLA website asap and to forward CFASE a digital copy asap.

Jesse N. Marquez

Executive Director

Coalition For A Safe Environment

JM-1

1 **Jesse Marquez (JM)**

2 **Response to Comment JM-1**

3 Request noted. The PDF files' being password protected was not intentional; however, the LAHD and
4 USACE provided the Draft EIS/EIR in a manner consistent with CEQA and NEPA, and USACE
5 regulations regarding public noticing requirements.
6

7

PF PROPERTIES
4400 Miraleste Drive
Rancho Palos Verdes, California 90275
(310) 831-1138
kent@pfproperties.com

February 15, 2012

U.S. Army Corps of Engineers
Los Angeles District
Regulatory Division
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Suite 110
Ventura, California 93001

Via E-Mail: theresa.stevens@usace.army.mil

City of Los Angeles Harbor Department
Christopher Cannon, Director
Environmental Management Division
425 S. Palos Verdes Street
San Pedro, California 90731

Via E-Mail: ceqacomments@portla.org

Subject: APL Terminal Project / Berths 302-306 / SCH#2009071031

Dear Ms. Stevens and Mr. Cannon;


I am pleased to submit the following public comments on the Draft Environmental Impact Report for Berths 302-306 APL Container Terminal Project. After review of the draft EIR for the project, I would like to voice my support for the submitted project that includes the expansion at Berth 306 and the redevelopment at Berths 302-305 of the existing APL Terminal. As presented, the environmental impacts associated with the project can be mitigated to levels that are less than significant providing for a sound environmentally conscience project.

Construction of this project will create approximately 1,169 direct jobs and 1,601 indirect jobs over the two year period. This workforce will come from our local residents that live in our local communities located in and around the Port of Los Angeles. This two year period will create almost 3,400 jobs and provide positive economic benefits to many groups and industries. Longer term, the project will provide for 2,756 permanent jobs in 2015, increasing to 3,885 permanet jobs in 2027. Most of these jobs created would be in the transportation and public utilities industrial sector of the local and regional economy. Secondary jobs totaling 2,914 in 2015 and increasing to 4,108 in 2027 will occur in many sectors of industry, but all attributable to this project.

The economic benefits of this project far exceed any of the environmental impacts that are presented in the Draft EIR. Based on the benefits of the project to the local, regional and state economies it is with great enthusiasm that I support this project and look forward to the redevelopment and expansion of Berths 302-306 of the APL Marine Terminal.

I appreciate the ability to provide you these comments and to express my support for the project.

Sincerely,



Kent M. Phillips
Principal

PFP-1

1 **PF Properties (PFP)**

2 **Response to Comment PFP-1**

3 Thank you for your review and comment on the Draft EIS/EIR.

4



P.O. Box 1510
San Pedro, CA 90733
Telephone: (310) 549-8030
Fax: (310) 549-7365

February 15, 2012

U.S. Army Corps of Engineers
Los Angeles District
Regulatory Division
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Suite 110
Ventura, California 93001

Via E-Mail: theresa.stevens@usace.army.mil

City of Los Angeles Harbor Department
Christopher Cannon, Director
Environmental Management Division
425 S. Palos Verdes Street
San Pedro, California 90731

Via E-Mail: ceqacomment@portla.org

Subject: APL Terminal Project / Berths 302-306 / SCH#2009071031

Dear Sirs;

Marine Technical Services is pleased to submit the following public comments on the Draft Environmental Impact Report for Berths 302-306 APL Container Terminal Project. After review of the draft EIR for the project, Marine Technical Services supports the submitted project that includes the expansion at Berth 306 and the redevelopment at Berths 302-305 of the existing APL Terminal. As presented, the environmental impacts associated with the project can be mitigated to levels that are less than significant providing for a sound environmentally conscience project.

Construction of this project will create approximately 1,169 direct jobs and 1,601 indirect jobs over the two year period. This workforce will come from our local residents that live in our local communities located in and around the Port of Los Angeles. This two year period will create almost 3,400 jobs and provide positive economic benefits to many groups and industries. Longer term, the project will provide for 2,756 permanent jobs in 2015, increasing to 3,885 permanent jobs in 2027. Most of these jobs created would be in the transportation and public utilities industrial sector of the local and regional economy. Secondary jobs totaling 2,914 in 2015 and increasing to 4,108 in 2027 will occur in many sectors of industry, but all attributable to this project.

The economic benefits of this project far exceed any of the less than significant environmental impacts that are presented in the Draft EIR. Based on the benefits of the project to the local, regional and state economies it is with great pleasure that Marine Technical Services supports this project and looks forward to the redevelopment and expansion of Berths 302-306 of the APL Marine Terminal.

We appreciate the ability to provide you these public comments and voice our support of the subject project.

Sincerely,



Frank Lopez
Vice President

MTSI-1

1 **Marine Technical Services Inc. (MTSI)**

2 **Response to Comment MTSI-1**

3 Thank you for your review and comment on the Draft EIS/EIR.

4



P.O. Box 1510
San Pedro, CA 90733
Telephone: (310) 549-8030
Fax: (310) 549-7365

February 16, 2012

U.S. Army Corps of Engineers
Los Angeles District
Regulatory Division
ATTN: Theresa Stevens, Ph.D.
2151 Alessandro Drive, Suite 110
Ventura, California 93001

Via E-Mail: theresa.stevens@usace.army.mil

City of Los Angeles Harbor Department
Christopher Cannon, Director
Environmental Management Division
425 S. Palos Verdes Street
San Pedro, California 90731

Via E-Mail: ceqacomment@portla.org

Subject: APL Terminal Project / Berths 302-306 / SCH#2009071031

Dear Sirs;

Dockside Machine & Ship Repair submits the following public comments on the Draft Environmental Impact Report for Berths 302-306 APL Container Terminal Project. After review of the draft EIR for the project, Dockside supports the submitted project that includes the expansion at Berth 306 and the redevelopment at Berths 302-305 of the existing APL Terminal. As presented, the environmental impacts associated with the project can be mitigated to levels that are less than significant providing for a sound environmentally conscience project.

The Port of Los Angeles provides for significant and substantial contributions to the local, regional and national economy. It creates tens of billions of dollars in industry sales each year in the southern California region. These sales translate into jobs, wages, and salaries, including state and local taxes.

Construction of this project will create approximately 1,169 direct jobs and 1,601 indirect jobs over the two year period. This workforce will come from our local residents that live in our local communities located in and around the Port of Los Angeles. This two year period will create almost 3,400 jobs and provide positive economic benefits to many groups and industries. Longer term, the project will provide for 2,756 permanent jobs in 2015, increasing to 3,885 permanet jobs in 2027. Most of these jobs created would be in the transportation and public utilities industrial sector of the local and regional economy. Secondary jobs totaling 2,914 in 2015 and increasing to 4,108 in 2027 will occur in many sectors of industry, but all attributable to this project.


DMSR-1

The economic benefits of this project far exceed any of the less than significant environmental impacts that are presented in the Draft EIR. Based on the benefits of the project to the local, regional and state economies it is with great pleasure that Dockside Machine & Ship Repair supports this project and looks forward to the redevelopment and expansion of Berths 302-306 of the APL Marine Terminal.

**DMSR-1
Cont.**

We appreciate the ability to provide you these public comments and voice our support of the subject project.

Sincerely,



Jim Eldridge
Vice President

1 **Dockside Machine and Ship Repair (DMSR)**

2 **Response to Comment DMSR-1**

3 Thank you for your review and comment on the Draft EIS/EIR.

4

\$Proposed La Harbor Project_JTowers_24Dec2011.txt

From: joseph towers1500@aol.com
Sent: Saturday, December 24, 2011 1:55 PM
To: Stevens, Theresa SPL
Subject: Proposed La Harbor Project

THIS IS ANOTHER OUTRAGEOUS EXAMPLE OF THE CORPS ENTERTAINING THE ACTIVITIES OF POLLUTERS WHO ARE DESTROYING THE HEALTH AND WELFARE OF RESIDENTS OF THE ADJACENT PORT AREAS. THE PORT OPERATORS HAVE LIED AND DECEIVED THE PUBLIC. THE PROMISED ELECTRIFICATIONS AND NON-POLLUTING FACILITIES HAVE NEVER BECOME A REALITY. EVERYDAY I LOOK AT THE AIR QUALITY DATA FROM THE PORT OF LONG BEACH AND SEE VIOLATION AFTER VIOLATION OF AIR QUALITY STANDARDS, BOTH FEDERAL AND STATE. WE LIVE AT ORIZABA AVENUE AND OCEAN BLVD IN A 20 STORY HI RISE WHERE WE HAVE HAD CASE AFTER CASE OF DEATHS DUE TO POLLUTED AIR IN THE FORM OF LUNG CANCERS, OTHER CANCERS AND HEART DISEASE.

YOUR ORGANIZATION, THE CORPS OF ENGINEERS, IS A QUASI CRIMINAL SETUP TO DO THE BIDDING OF THE POLLUTION INDUSTRY. YOUR NEGLIGENCE KILLED 3000 PEOPLE AS A RESULT OF KATRINA. NO CORPS OFFICIAL WAS DEMOTED OR INDICTED FOR THIS MASS MURDER. I SHOULD KNOW YOUR CRIMINAL MISDEEDS. I WAS THE DISTRICT COUNSEL FOR THE NEW ORLEANS DISTRICT FOR 35 YEARS AND WITNESSED DUMB AND STUPID CORPS MILITARY JERKS COME TO NEW ORLEANS THINKING IT WAS AN R&R ASSIGNMENT AND DRINK AND HAVE A GOOD TIME INSTEAD OF DOING THEIR JOB.

DO NOT REPEAT IN THIS COMMUNITY THE CRIMES YOUR COLONELS AND GENERALS COMMITTED IN NEW ORLEANS. TURN DOWN THIS PERMIT APPLICATION NOW!!

JT-1

1 **Joseph Towers (JT)**

2 **Response to Comment JT-1**

3 The comments do not address the adequacy of the Draft EIS/EIR analysis. The comment is noted and has
4 been incorporated into the Final EIS/EIR for review and consideration by the decision-makers prior to any
5 action on the proposed Project.
6

IN RE THE MATTER OF BERTHS 302-306)
AMERICAN PRESIDENTIAL LINES)
CONTAINER TERMINAL PROJECT;)
LOS ANGELES HARBOR DEPARTMENT;)
SAN PEDRO, CALIFORNIA.)

Transcript of Public Review Meeting
for the Proposed Berths 302-306
American Presidential Lines Container Terminal
Project Draft E.I.S./E.I.R.
Thursday January 19, 2012
San Pedro, California

SNYDER HEATHCOTE INC.

REPORTED BY Jamie L. Apodaca, CSR #10990

OUR FILE NO.

OFFICIAL COURT REPORTERS
3055 WILSHIRE BOULEVARD
SUITE 640
LOS ANGELES, CA 90010
TELEPHONE (213) 388-2151

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

IN RE THE MATTER OF BERTHS 302-306)
AMERICAN PRESIDENTIAL LINES)
CONTAINER TERMINAL PROJECT;)
LOS ANGELES HARBOR DEPARTMENT;)
SAN PEDRO, CALIFORNIA.)

Transcript of the Proposed Berths 302-306
American Presidential Lines Container Terminal
Project Draft E.I.S./E.I.R. Public Review Meeting,
Los Angeles Harbor Department, held at 6:02 P.M. on
Thursday January 19, 2012, at 425 South Palos
Verdes Street, San Pedro, California, transcribed
by Jamie L. Apodaca, CSR #10990.

1 APPEARANCES:

2 Christopher Cannon

3 Theresa Stevens -- Project Manager for the United States
4 Army Corps of Engineers

5 Lt. Col. Steven Sigloch -- Deputy District Engineer for
6 the United States Army Corps of Engineers

7 Jan Green Rebstock -- Port of Los Angeles Environmental
8 Management Division

9 Aaron Allen -- Branch Chief for the United States Army
10 Corps of Engineers

11 Christine Honeybone -- Port of Los Angeles Environmental
12 Project Manager

13

14

15

16

17

18

19

20

21

22

23

24

25

1 MR. CANNON: Okay. Good evening, everyone, and welcome
2 to Port of Los Angeles. This is our public hearing for the
3 APL Container Terminal project. It's a draft E.I.S/E.I.R.
4 public review meeting.

5 And so the purpose of public review meetings, of
6 course, is to get a chance to hear from you, and that's sort
7 of stating the obvious. But the reason I want to mention it
8 is too often you fall into a situation where, you know,
9 people expect there to be a dialogue or for us to answer
10 questions or to otherwise engage in a back-and-forth, and
11 that's not what we're here for tonight. Staff is here around
12 and if afterwards you have a question or two or need
13 clarification of something that's in the document, we're
14 certainly happy to be helpful and we want to do that. But
15 mainly tonight is your night, and so we want to hear what you
16 have to say.

17 We've got speaker cards; so if anybody wants to
18 speak, please fill out the speaker cards. I think they're
19 over here (indicating). If not, come find me, and I have a
20 few extra.

21 And so we're going to give you a chance to comment
22 on the document. Please keep your comments focused on the
23 document itself. Obviously, if you like the project and you
24 want to tell us, that's okay too. But mostly it's a chance
25 to comment on the document itself so we can make sure we did

1 a good job with it. And if there's things that we need to
2 adjust going forward for the final, we will do that.

3 I'm up here. I want to introduce the people who are
4 sitting in front of you, and I get to not be one of them; so
5 I'm actually happy about that. I can go sit down in the
6 audience.

7 But Theresa Stevens here is to my immediate left.
8 She is the project manager for the Corps of Engineers, and
9 she's probably your point of contact to the extent that you
10 need to interact with the Corps on this project.

11 Jan Green Rebstock is with the Los Angeles
12 Environmental Management Division. She's an environmental
13 specialist, and she is going to be your point of contact for
14 this project for us.

15 Lieutenant Colonel -- I have to get it right --
16 Sigloch --

17 Did I get that right, sir?

18 LT. COL. SIGLOCH: Yes.

19 MR. CANNON: Okay. He is the deputy district engineer
20 for the Corps.

21 Next to him is Aaron Allen. He's the Branch Chief
22 for the Corps.

23 And last but not least is Christine Honeybone, who
24 is going to give a presentation. She's the port engineering
25 professional, and she's going to give an overview of the

1 details of the project.

2 So these are people that you need to hear from
3 tonight, and thank you again for being here. I'll turn it
4 over to Lt. Col. Sigloch.

5 LT. COL. SIGLOCH: Okay. Thank you.

6 Good evening. I'm Lt. Colonel Steve Sigloch, the
7 Deputy Commander of the Los Angeles District for the
8 United States Army Corps of Engineers. On behalf of the
9 Corps of Engineers, I'd like to welcome you all to this
10 public meeting, which we are also conducting in Spanish as a
11 courtesy to you, the interested public.

12 In 2009 the Port of Los Angeles applied to the Corps
13 for a permit to construct wharf and terminal improvements at
14 berths 302 through 306, the APL container terminal on
15 Terminal Island. Because federal permits qualify as federal
16 actions, the Corps must also comply with the National
17 Environmental Policy Act, NEPA.

18 Due to the nature and scope of the activities in the
19 waters of the United States, the Corps has determined that
20 the proposed project could result in significant impacts and
21 therefore required an Environmental Impact Statement, or
22 E.I.S.

23 On July 9, 2009, we published a notice of intent in
24 the Federal Register to prepare an E.I.S. for the project.
25 On July 10th, 2009, the Corps and port published a Joint

1 Public Notice of this Notice of Intent and the port's Notice
2 of Preparation of an Environmental Impact Report, or E.I.R.

3 In response to public comments received at the
4 scoping meeting in 2009, the Corps and port prepared a joint
5 E.I.S./E.I.R., and on December 23rd, 2011, the Corps
6 published a notice of availability of the draft E.I.S. in the
7 Federal Register.

8 Under our Federal Permit Program, the Corps of
9 Engineers is responsible for regulating dredge and fill
10 activities in the waters of the United States, as well as any
11 activities that may affect navigation.

12 The port's proposed in-water and over-water
13 activities at berths 302 through 306 are regulated under
14 section 10 of the Rivers and Harbors Act. As proposed, these
15 activities do not include a discharge for fill material into
16 waters for the United States as regulated by section 404 of
17 the Clean Water Act. While dredged material may be disposed
18 in waters of the U.S., disposal would take place under a
19 previously issued Corps permit, permit number 2008, dash,
20 00662, dash, AOA.

21 The port is also considering transporting and
22 discharging clean, dredged material at a U.S. EPA-approved
23 ocean disposal site -- L.A., dash, 2 -- which requires
24 authorization pursuant to section 103 of the Marine
25 Protection, Research, and Sanctuaries Act, M.P.R.S.A.

1 Federal actions such as Corps permit decisions are
2 subject to compliance with a variety of federal environmental
3 laws in addition to NEPA. Consequently the Corps has a
4 responsibility to evaluate the environmental impacts that
5 would be caused by the proposed project prior to making a
6 permit decision.

7 In meeting its regulatory responsibility, the Corps
8 is neither a project proponent nor an opponent. In addition
9 to evaluating the direct, indirect, and cumulative
10 environmental impacts of the port's proposed project, the
11 Corps must determine whether the proposed project is in the
12 public interest. No permit can be granted if we find that
13 the proposal is contrary to the public interest. The
14 public-interest determination requires a careful weighing of
15 factors relevant to the particular project. The public
16 interest review requires the Corps evaluate a project's
17 benefits and balance them against a project's reasonably
18 foreseeable detriments.

19 At this public hearing, the Corps is requesting
20 input from the general public concerning the proposed project
21 and the Corps' permit action. The Corps would like to
22 emphasize that we will carefully consider all comments that
23 we receive for the proposed project, and they will be given
24 full consideration as part of our final permit decision.
25 Following tonight's meeting, all parties will be given until

1 February 17th to provide any written comments on the proposed
2 project for our permit action.

3 Staff from the Port of Los Angeles will now provide
4 you a presentation, and then we'll discuss how to take the
5 oral testimony after their presentation. Thank you.

6 MS. HONEYBONE: Thank you, Lieutenant Colonel.

7 Okay. I'm going to give an overview of the proposed
8 project, a view of description locations.

9 Here is just to give you an overview of the site.
10 The proposed project is located at Pier 300 on Terminal
11 Island, and we have another closer aerial view of the actual
12 terminal.

13 Here are the project objectives that have helped us
14 guide through the proposed project design and through the
15 document process. We want to optimize the use of the land at
16 berths 302 to 305 and accommodate for larger container ships
17 and warship calls. We would like to increase the container
18 berth size and provide sufficient backland areas, improve the
19 vacant landfill at berth 306, and increase terminal
20 efficiency.

21 Just a brief overview of the existing facilities.
22 The existing terminal is 291 acres, and our baseline for this
23 document was July, 2008 to June, 2009, in which they had 247
24 ship calls, and 1.1 TEUs. There's currently four berths of
25 1,000 feet, and they have 12 cranes and an on-dock rail

1 facility.

2 To get into the proposed project elements, I have
3 highlighted these areas in the various colored outlines. So
4 we have modifications to both their gates and the terminal
5 entrance lanes. We plan to expand the reefer unit storage
6 area; demolish and reconstruct the Roadability facilities;
7 expand the power shop facilities; various utility
8 infrastructure within the terminal; bring in four new cranes;
9 and also develop the former LAXT areas for container terminal
10 use, which is about nine acres.

11 For the proposed project at berth 306 expansion, we
12 would construct 1,250 linear feet of new wharf and bring
13 possibly up to eight new cranes with amp facilities. We'll
14 dredge 20,000 cubic yards and also develop the existing
15 landfill of 41 acres of backlands with the infrastructure
16 that would support the possible future automation with
17 equipment such as dual-hoist cranes, automated guided
18 vehicles, automated stacking cranes, and landside transfer
19 cranes.

20 This is an example of some of the common terminal
21 equipment that's at the terminal, such as the side picks and
22 top picks. The rubber-tired gantry cranes, the rail-mounted
23 gantry cranes give you an idea of what is out there.

24 And just to give a summary, the proposed project
25 would add 56 acres, which includes the landfill; so it would

1 be a total of 347 acres. The lease goes through 2027. So we
2 expect 390 ship calls and 3.2 million TEUs. There would be a
3 total of up to 24 cranes and a total of 5,250 feet of wharf.

4 I will now turn it over to Jan so she can talk
5 about the environmental process and where we're at right
6 now.

7 MS. GREEN REBSTOCK: Thank you.

8 Yes. So my name is Jan Green Rebstock. I'm with
9 the port Environmental Management Division, and I'm just
10 going to walk you through the environmental review process
11 for this project.

12 So we released the Notice to Proceed, which is the
13 formal initiation of the environmental review process, back
14 in July, 2009. We are now here at the public meeting to
15 review the results of the draft E.I.R./E.I.S. findings and
16 considerations, and then we will move forward with preparing
17 a final E.I.R./E.I.S. based on the responses we receive
18 during the comment period.

19 The draft E.I.R. was released on December 16th, and
20 there's a 60-day review period that's currently in process,
21 and as mentioned previously, it will close on February 17th.

22 Okay. So this is a summary of the findings of the
23 environmental review. After applying 33 mitigation measures,
24 standard conditions of project conditions and release
25 measures, we still have unavoidable significant impacts

1 related to air quality, greenhouse gases, and health risk and
2 also related to biological resources. The rest of the
3 resource areas, we were able to mitigate to less than
4 significant or they were already less than significant.

5 For the biological resources, the major driver there
6 was invasive species, and we did a lot of consultation with
7 APL to learn about the best practices that they have for
8 their vessel fleet. But even with experimenting with a new
9 ballast-water treatment system and how they maintain their
10 vessel hulls, we still didn't feel confident that we could
11 rule out the potential significant impact of a drain
12 introducing invasive species into the harbor with the
13 increase in ship calls over the life of the project.

14 Related to health risk, we do have a residential
15 cancer risk impact for the live-aboard population only. So
16 this doesn't apply to landside residences, but it does apply
17 to a few live-aboards within the Fish Harbor area and some of
18 the live-aboards near the Anchorage Road area.

19 I would like to mention that we did apply all of the
20 mitigation measures under the Clean Air Action Plan. If you
21 notice, the majority of the mitigation measures are related
22 to air quality, and then there's some related to biology,
23 geology, noise, and public services. So it's 33 in all.

24 The document does coequally analyze six alternatives
25 in addition to the proposed project. So there's a range of

1 alternatives that we look at, with the alternative one being
2 not moving forward with the project. There's -- the "No
3 Federal Action" alternative is what could the port do but for
4 receiving a federal permit; so that's no wharf extension, no
5 new cranes, no dredging. And then there's some various
6 reduced project alternatives as well. We also look at what
7 the project might look like with expanded on-dock rail.

8 So this is just a brief summary of some of our
9 public outreach efforts. We have a mailing list of over 200
10 interested parties that we directly mailed the document to.
11 We have a reader's guide which condenses a, you know,
12 several-thousand page document to about 30 pages, and there's
13 some extra copies in the back if you're interested. We have
14 the public meeting tonight. We're going to be receiving oral
15 comments. So if you haven't already filled out a speaker's
16 card and you're interested in participating, please do so and
17 just bring it up here to the front. And be sure to clearly
18 speak your name before you start.

19 And, you know, we'll take all of the comments that
20 we receive and then prepare a final document, and the final
21 document will reproduce all the comments verbatim and show a
22 staff response and also show how the document has changed in
23 response to any of the comments that we receive, whether it's
24 with the analysis or the project design. And we hope to
25 bring that final document to the board for consideration in

1 the spring-summer time frame.

2 So with that, we're going to move towards opening
3 the hearing for receiving public comment. I haven't received
4 any speaker cards. If there's anyone interested --

5 So I'd ask that Jay come up to the podium and state
6 his name.

7 And you'll have three minutes to speak.

8 MR. JAHANGIRA: Good evening. My name Jay Jahangira.
9 Buenas tardes. Mi nombre es Jay Jahangira.

10 First and foremost, I'd like to applaud the Port of
11 Los Angeles and the U.S. Army Corps of Engineers for engaging
12 in this development of this joint document. We believe -- on
13 behalf of WorleyParsons, the company that I work for, and a
14 resident of the Los Angeles County here that this is a
15 win-win for the community as well as the port.

16 Clearly with 39 -- 390 vessel calls and 3.2 million
17 TEU, we believe this project brings an economic prosperity to
18 the greater Los Angeles area.

19 We also want to recognize the port's efforts as well
20 as the U.S. Army Corps of Engineers' efforts in implementing
21 these 33 planned mitigation measures. We believe these are
22 -- that they demonstrate the port's stewardship, the Army
23 Corps of Engineers' stewardship, and clearly they demonstrate
24 the responsible posture of the port and the Army Corps in
25 making sure that the CEQA and the NEPA statutes are properly

1 complied with.

2 And, matter of fact, at the end of the day, folks,
3 the economic prosperity that this project brings to our
4 community -- WorleyParsons -- we are a resident of this
5 county; we are a large employer in this county, and our hope
6 is that this project is -- properly goes through the process
7 and is approved so we can also increase our employment base
8 in the county and be able to be a stakeholder to the
9 process.

10 With that, I want to appreciate your time, and I
11 want to -- definitely at the end of my discussions, I'd like
12 to stress again that this is an important project for the
13 community, it's an important project for the port, and we'd
14 like to support the project and ask for its approval. Thank
15 you.

16 MS. GREEN REBSTOCK: Thank you.

17 Do we have any other speakers?

18 Okay. Do we have any other final comments from the
19 Corps?

20 Okay. Well, with that we'll conclude this hearing.
21 Thank you.

22 (Whereupon the hearing was
23 adjourned at 6:22 P.M.)

24

25

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

STATE OF)
) SS.
CALIFORNIA)

I, Jamie L. Apodaca, Certified Shorthand Reporter
qualified in and for the State of California, do hereby
certify:

That the foregoing transcript is a true and correct
transcription of my original stenographic notes.

I further certify that I am neither attorney or
counsel for, nor related to or employed by any of the parties
to the action in which this proceeding was taken; and
furthermore, that I am not a relative or employee of any
attorney or counsel employed by the parties hereto or
financially interested in the action.

I further certify that I am not interested in the
event of the action.

IN WITNESS WHEREOF, I have hereunto set my hand this
24th day of January, 2012.



CSR No. 10990

EIS/EIR PUBLIC REVIEW MEETING
REPORTER'S TRANSCRIPT
JANUARY 19, 2012

SHEET 1 PAGE 1

1
2
3
4 IN RE THE MATTER OF BERTHS 302-306)
5 AMERICAN PRESIDENTIAL LINES)
6 CONTAINER TERMINAL PROJECT;)
7 LOS ANGELES HARBOR DEPARTMENT;)
8 SAN PEDRO, CALIFORNIA.)

9
10
11
12
13
14 Transcript of the Proposed Berths 302-306
15 American Presidential Lines Container Terminal
16 Project Draft E.I.S./E.I.R. Public Review Meeting,
17 Los Angeles Harbor Department, held at 6:02 P.M. on
18 Thursday January 19, 2012, at 425 South Palos
19 Verdes Street, San Pedro, California, transcribed
20 by Jamie L. Apodaca, CSR #10990.
21
22
23
24
25

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 3

1 MR. CANNON: Okay. Good evening, everyone, and welcome
2 to Port of Los Angeles. This is our public hearing for the
3 APL Container Terminal project. It's a draft E.I.S./E.I.R.
4 public review meeting.

5 And so the purpose of public review meetings, of
6 course, is to get a chance to hear from you, and that's sort
7 of stating the obvious. But the reason I want to mention it
8 is too often you fall into a situation where, you know,
9 people expect there to be a dialogue or for us to answer
10 questions or to otherwise engage in a back-and-forth, and
11 that's not what we're here for tonight. Staff is here around
12 and if afterwards you have a question or two or need
13 clarification of something that's in the document, we're
14 certainly happy to be helpful and we want to do that. But
15 mainly tonight is your night, and so we want to hear what you
16 have to say.

17 We've got speaker cards; so if anybody wants to
18 speak, please fill out the speaker cards. I think they're
19 over here (indicating). If not, come find me, and I have a
20 few extra.

21 And so we're going to give you a chance to comment
22 on the document. Please keep your comments focused on the
23 document itself. Obviously, if you like the project and you
24 want to tell us, that's okay too. But mostly it's a chance
25 to comment on the document itself so we can make sure we did

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 2

1 APPEARANCES:

2 Christopher Cannon

3 Theresa Stevens -- Project Manager for the United States
4 Army Corps of Engineers

5 Lt. Col. Steven Sigloch -- Deputy District Engineer for
6 the United States Army Corps of Engineers

7 Jan Green Rebstock -- Port of Los Angeles Environmental
8 Management Division

9 Aaron Allen -- Branch Chief for the United States Army
10 Corps of Engineers

11 Christine Honeybone -- Port of Los Angeles Environmental
12 Project Manager

13
14
15
16
17
18
19
20
21
22
23
24
25

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 4

1 a good job with it. And if there's things that we need to
2 adjust going forward for the final, we will do that.

3 I'm up here. I want to introduce the people who are
4 sitting in front of you, and I get to not be one of them; so
5 I'm actually happy about that. I can go sit down in the
6 audience.

7 But Theresa Stevens here is to my immediate left.
8 She is the project manager for the Corps of Engineers, and
9 she's probably your point of contact to the extent that you
10 need to interact with the Corps on this project.

11 Jan Green Rebstock is with the Los Angeles
12 Environmental Management Division. She's an environmental
13 specialist, and she is going to be your point of contact for
14 this project for us.

15 Lieutenant Colonel -- I have to get it right --
16 Sigloch --

17 Did I get that right, sir?

18 LT. COL. SIGLOCH: Yes.

19 MR. CANNON: Okay. He is the deputy district engineer
20 for the Corps.

21 Next to him is Aaron Allen. He's the Branch Chief
22 for the Corps.

23 And last but not least is Christine Honeybone, who
24 is going to give a presentation. She's the port engineering
25 professional, and she's going to give an overview of the

SNYDER HEATHCOTE, INC. (213) 388-2151

EIS/EIR PUBLIC REVIEW MEETING
REPORTER'S TRANSCRIPT
JANUARY 19, 2012

SHEET 2 PAGE 5

1 details of the project.

2 So these are people that you need to hear from
3 tonight, and thank you again for being here. I'll turn it
4 over to Lt. Col. Sigloch.

5 LT. COL. SIGLOCH: Okay. Thank you.

6 Good evening. I'm Lt. Colonel Steve Sigloch, the
7 Deputy Commander of the Los Angeles District for the
8 United States Army Corps of Engineers. On behalf of the
9 Corps of Engineers, I'd like to welcome you all to this
10 public meeting, which we are also conducting in Spanish as a
11 courtesy to you, the interested public.

12 In 2009 the Port of Los Angeles applied to the Corps
13 for a permit to construct wharf and terminal improvements at
14 berths 302 through 306, the APL container terminal on
15 Terminal Island. Because federal permits qualify as federal
16 actions, the Corps must also comply with the National
17 Environmental Policy Act, NEPA.

18 Due to the nature and scope of the activities in the
19 waters of the United States, the Corps has determined that
20 the proposed project could result in significant impacts and
21 therefore required an Environmental Impact Statement, or
22 E.I.S.

23 On July 9, 2009, we published a notice of intent in
24 the Federal Register to prepare an E.I.S. for the project.
25 On July 10th, 2009, the Corps and port published a Joint

5

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 7

1 Federal actions such as Corps permit decisions are
2 subject to compliance with a variety of federal environmental
3 laws in addition to NEPA. Consequently the Corps has a
4 responsibility to evaluate the environmental impacts that
5 would be caused by the proposed project prior to making a
6 permit decision.

7 In meeting its regulatory responsibility, the Corps
8 is neither a project proponent nor an opponent. In addition
9 to evaluating the direct, indirect, and cumulative
10 environmental impacts of the port's proposed project, the
11 Corps must determine whether the proposed project is in the
12 public interest. No permit can be granted if we find that
13 the proposal is contrary to the public interest. The
14 public-interest determination requires a careful weighing of
15 factors relevant to the particular project. The public
16 interest review requires the Corps evaluate a project's
17 benefits and balance them against a project's reasonably
18 foreseeable detriments.

19 At this public hearing, the Corps is requesting
20 input from the general public concerning the proposed project
21 and the Corps' permit action. The Corps would like to
22 emphasize that we will carefully consider all comments that
23 we receive for the proposed project, and they will be given
24 full consideration as part of our final permit decision.
25 Following tonight's meeting, all parties will be given until

7

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 6

1 Public Notice of this Notice of Intent and the port's Notice
2 of Preparation of an Environmental Impact Report, or E.I.R.

3 In response to public comments received at the
4 scoping meeting in 2009, the Corps and port prepared a joint
5 E.I.S./E.I.R., and on December 23rd, 2011, the Corps
6 published a notice of availability of the draft E.I.S. in the
7 Federal Register.

8 Under our Federal Permit Program, the Corps of
9 Engineers is responsible for regulating dredge and fill
10 activities in the waters of the United States, as well as any
11 activities that may affect navigation.

12 The port's proposed in-water and over-water
13 activities at berths 302 through 306 are regulated under
14 section 10 of the Rivers and Harbors Act. As proposed, these
15 activities do not include a discharge for fill material into
16 waters for the United States as regulated by section 404 of
17 the Clean Water Act. While dredged material may be disposed
18 in waters of the U.S., disposal would take place under a
19 previously issued Corps permit, permit number 2008, dash,
20 00662, dash, AOA.

21 The port is also considering transporting and
22 discharging clean, dredged material at a U.S. EPA-approved
23 ocean disposal site -- L.A., dash, 2 -- which requires
24 authorization pursuant to section 103 of the Marine
25 Protection, Research, and Sanctuaries Act, M.P.R.S.A.

6

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 8

1 February 17th to provide any written comments on the proposed
2 project for our permit action.

3 Staff from the Port of Los Angeles will now provide
4 you a presentation, and then we'll discuss how to take the
5 oral testimony after their presentation. Thank you.

6 MS. HONEYBONE: Thank you, Lieutenant Colonel.

7 Okay. I'm going to give an overview of the proposed
8 project, a view of description locations.

9 Here is just to give you an overview of the site.
10 The proposed project is located at Pier 300 on Terminal
11 Island, and we have another closer aerial view of the actual
12 terminal.

13 Here are the project objectives that have helped us
14 guide through the proposed project design and through the
15 document process. We want to optimize the use of the land at
16 berths 302 to 305 and accommodate for larger container ships
17 and warship calls. We would like to increase the container
18 berth size and provide sufficient backland areas, improve the
19 vacant landfill at berth 306, and increase terminal
20 efficiency.

21 Just a brief overview of the existing facilities.
22 The existing terminal is 291 acres, and our baseline for this
23 document was July, 2008 to June, 2009, in which they had 247
24 ship calls, and 1.1 TEUs. There's currently four berths of
25 1,000 feet, and they have 12 cranes and an on-dock rail

8

SNYDER HEATHCOTE, INC. (213) 388-2151

**EIS/EIR PUBLIC REVIEW MEETING
REPORTER'S TRANSCRIPT
JANUARY 19, 2012**

SHEET 3 PAGE 9

1 facility.
2 To get into the proposed project elements, I have
3 highlighted these areas in the various colored outlines. So
4 we have modifications to both their gates and the terminal
5 entrance lanes. We plan to expand the reefer unit storage
6 area; demolish and reconstruct the Roadability facilities;
7 expand the power shop facilities; various utility
8 infrastructure within the terminal; bring in four new cranes;
9 and also develop the former LAXT areas for container terminal
10 use, which is about nine acres.

11 For the proposed project at berth 306 expansion, we
12 would construct 1,250 linear feet of new wharf and bring
13 possibly up to eight new cranes with amp facilities. We'll
14 dredge 20,000 cubic yards and also develop the existing
15 landfill of 41 acres of backlands with the infrastructure
16 that would support the possible future automation with
17 equipment such as dual-hoist cranes, automated guided
18 vehicles, automated stacking cranes, and landside transfer
19 cranes.

20 This is an example of some of the common terminal
21 equipment that's at the terminal, such as the side picks and
22 top picks. The rubber-tired gantry cranes, the rail-mounted
23 gantry cranes give you an idea of what is out there.

24 And just to give a summary, the proposed project
25 would add 56 acres, which includes the landfill; so it would

9

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 11

1 related to air quality, greenhouse gases, and health risk and
2 also related to biological resources. The rest of the
3 resource areas, we were able to mitigate to less than
4 significant or they were already less than significant.

5 For the biological resources, the major driver there
6 was invasive species, and we did a lot of consultation with
7 APL to learn about the best practices that they have for
8 their vessel fleet. But even with experimenting with a new
9 ballast-water treatment system and how they maintain their
10 vessel hulls, we still didn't feel confident that we could
11 rule out the potential significant impact of a drain
12 introducing invasive species into the harbor with the
13 increase in ship calls over the life of the project.

14 Related to health risk, we do have a residential
15 cancer risk impact for the live-aboard population only. So
16 this doesn't apply to landside residences, but it does apply
17 to a few live-aboards within the Fish Harbor area and some of
18 the live-aboards near the Anchorage Road area.

19 I would like to mention that we did apply all of the
20 mitigation measures under the Clean Air Action Plan. If you
21 notice, the majority of the mitigation measures are related
22 to air quality, and then there's some related to biology,
23 geology, noise, and public services. So it's 33 in all.

24 The document does coequally analyze six alternatives
25 in addition to the proposed project. So there's a range of

11

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 10

1 be a total of 347 acres. The lease goes through 2027. So we
2 expect 390 ship calls and 3.2 million TEUs. There would be a
3 total of up to 24 cranes and a total of 5,250 feet of wharf.

4 I will now turn it over to Jan so she can talk
5 about the environmental process and where we're at right
6 now.

7 MS. GREEN REBSTOCK: Thank you.

8 Yes. So my name is Jan Green Rebstock. I'm with
9 the port Environmental Management Division, and I'm just
10 going to walk you through the environmental review process
11 for this project.

12 So we released the Notice to Proceed, which is the
13 formal initiation of the environmental review process, back
14 in July, 2009. We are now here at the public meeting to
15 review the results of the draft E.I.R./E.I.S. findings and
16 considerations, and then we will move forward with preparing
17 a final E.I.R./E.I.S. based on the responses we receive
18 during the comment period.

19 The draft E.I.R. was released on December 16th, and
20 there's a 60-day review period that's currently in process,
21 and as mentioned previously, it will close on February 17th.

22 Okay. So this is a summary of the findings of the
23 environmental review. After applying 33 mitigation measures,
24 standard conditions of project conditions and release
25 measures, we still have unavoidable significant impacts

10

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 12

1 alternatives that we look at, with the alternative one being
2 not moving forward with the project. There's -- the "No
3 Federal Action" alternative is what could the port do but for
4 receiving a federal permit; so that's no wharf extension, no
5 new cranes, no dredging. And then there's some various
6 reduced project alternatives as well. We also look at what
7 the project might look like with expanded on-dock rail.

8 So this is just a brief summary of some of our
9 public outreach efforts. We have a mailing list of over 200
10 interested parties that we directly mailed the document to.
11 We have a reader's guide which condenses a, you know,
12 several-thousand page document to about 30 pages, and there's
13 some extra copies in the back if you're interested. We have
14 the public meeting tonight. We're going to be receiving oral
15 comments. So if you haven't already filled out a speaker's
16 card and you're interested in participating, please do so and
17 just bring it up here to the front. And be sure to clearly
18 speak your name before you start.

19 And, you know, we'll take all of the comments that
20 we receive and then prepare a final document, and the final
21 document will reproduce all the comments verbatim and show a
22 staff response and also show how the document has changed in
23 response to any of the comments that we receive, whether it's
24 with the analysis or the project design. And we hope to
25 bring that final document to the board for consideration in

12

SNYDER HEATHCOTE, INC. (213) 388-2151

EIS/EIR PUBLIC REVIEW MEETING
REPORTER'S TRANSCRIPT
JANUARY 19, 2012

SHEET 4 PAGE 13

1 the spring-summer time frame.

2 So with that, we're going to move towards opening
3 the hearing for receiving public comment. I haven't received
4 any speaker cards. If there's anyone interested --

5 So I'd ask that Jay come up to the podium and state
6 his name.

7 And you'll have three minutes to speak.

8 MR. JAHANGIRA: Good evening. My name Jay Jahangira.
9 Buenas tardes. Mi nombre es Jay Jahangira.

10 First and foremost, I'd like to applaud the Port of
11 Los Angeles and the U.S. Army Corps of Engineers for engaging
12 in this development of this joint document. We believe -- on
13 behalf of WorleyParsons, the company that I work for, and a
14 resident of the Los Angeles County here that this is a
15 win-win for the community as well as the port.

16 Clearly with 39 -- 390 vessel calls and 3.2 million
17 TEU, we believe this project brings an economic prosperity to
18 the greater Los Angeles area.

19 We also want to recognize the port's efforts as well
20 as the U.S. Army Corps of Engineers' efforts in implementing
21 these 33 planned mitigation measures. We believe these are
22 -- that they demonstrate the port's stewardship, the Army
23 Corps of Engineers' stewardship, and clearly they demonstrate
24 the responsible posture of the port and the Army Corps in
25 making sure that the CEQA and the NEPA statutes are properly

13

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 15

1 STATE OF)
2 CALIFORNIA) SS.

3
4 I, Jamie L. Apodaca, Certified Shorthand Reporter
5 qualified in and for the State of California, do hereby
6 certify:

7 That the foregoing transcript is a true and correct
8 transcription of my original stenographic notes.

9 I further certify that I am neither attorney or
10 counsel for, nor related to or employed by any of the parties
11 to the action in which this proceeding was taken; and
12 furthermore, that I am not a relative or employee of any
13 attorney or counsel employed by the parties hereto or
14 financially interested in the action.

15 I further certify that I am not interested in the
16 event of the action.

17 IN WITNESS WHEREOF, I have hereunto set my hand this
18 24th day of January, 2012.

19

20

CSR No. 10990

21

22

23

24

25

15

SNYDER HEATHCOTE, INC. (213) 388-2151

PAGE 14

1 complied with.

2 And, matter of fact, at the end of the day, folks,
3 the economic prosperity that this project brings to our
4 community -- WorleyParsons -- we are a resident of this
5 county; we are a large employer in this county, and our hope
6 is that this project is -- properly goes through the process
7 and is approved so we can also increase our employment base
8 in the county and be able to be a stakeholder to the
9 process.

10 With that, I want to appreciate your time, and I
11 want to -- definitely at the end of my discussions, I'd like
12 to stress again that this is an important project for the
13 community, it's an important project for the port, and we'd
14 like to support the project and ask for its approval. Thank
15 you.

16 MS. GREEN REBSTOCK: Thank you.

17 Do we have any other speakers?

18 Okay. Do we have any other final comments from the
19 Corps?

20 Okay. Well, with that we'll conclude this hearing.
21 Thank you.

22 (Whereupon the hearing was
23 adjourned at 6:22 P.M.)

24

25

14

SNYDER HEATHCOTE, INC. (213) 388-2151

| |
|------------------------------------|
| # |
| #10990 [1] 1:17 |
| 0 |
| 00662 [1] 6:20 |
| 1 |
| 1,000 [1] 8:25 |
| 1,250 [1] 9:12 |
| 1.1 [1] 8:24 |
| 10 [1] 6:14 |
| 103 [1] 6:24 |
| 10th [1] 5:25 |
| 12 [1] 8:25 |
| 16th [1] 10:19 |
| 17th [2] 8:1 10:21 |
| 19 [1] 1:16 |
| 2 |
| 2 [1] 6:23 |
| 20,000 [1] 9:14 |
| 200 [1] 12:9 |
| 2008 [2] 6:19 8:23 |
| 2009 [6] 5:12,23,25 6:4 8:23 10:14 |
| 2011 [1] 6:5 |
| 2012 [2] 1:16 15:18 |
| 2027 [1] 10:1 |
| 23rd [1] 6:5 |
| 24 [1] 10:3 |
| 247 [1] 8:23 |
| 24th [1] 15:18 |
| 291 [1] 8:22 |
| 3 |
| 3.2 [2] 10:2 13:16 |
| 30 [1] 12:12 |
| 300 [1] 8:10 |
| 302 [3] 5:14 6:13 8:16 |
| 302-306 [2] 1:4,14 |
| 305 [1] 8:16 |
| 306 [4] 5:14 6:13 8:19 9:11 |
| 33 [3] 10:23 11:23 13:21 |
| 347 [1] 10:1 |
| 39 [1] 13:16 |
| 390 [2] 10:2 13:16 |
| 4 |
| 404 [1] 6:16 |
| 41 [1] 9:15 |
| 425 [1] 1:16 |
| 5 |
| 5,250 [1] 10:3 |
| 56 [1] 9:25 |
| 6 |
| 6:22 [1] 14:23 |
| 60-day [1] 10:20 |
| 9 |
| 9 [1] 5:23 |
| A |
| aaron [1] 4:21 |
| able [2] 11:3 14:8 |
| accommodate [1] 8:16 |
| acres [5] 8:22 9:10,15,25 10:1 |
| act [4] 5:17 6:14,17,25 |

| |
|--|
| action [7] 7:21 8:2 11:20 12:3 15:11,14,16 |
| actions [2] 5:16 7:1 |
| activities [5] 5:18 6:10,11,13,15 |
| actual [1] 8:11 |
| actually [1] 4:5 |
| add [1] 9:25 |
| addition [3] 7:3,8 11:25 |
| adjourned [1] 14:23 |
| adjust [1] 4:2 |
| aerial [1] 8:11 |
| affect [1] 6:11 |
| afterwards [1] 3:12 |
| air [3] 11:1,20,22 |
| allen [1] 4:21 |
| already [2] 11:4 12:15 |
| alternative [2] 12:1,3 |
| alternatives [3] 11:24 12:1,6 |
| amp [1] 9:13 |
| analysis [1] 12:24 |
| analyze [1] 11:24 |
| anchorage [1] 11:18 |
| angeles [10] 2:6,9 3:2 4:11 5:7,12 8:3 13:11,14,18 |
| another [1] 8:11 |
| answer [1] 3:9 |
| anybody [1] 3:17 |
| aoa [1] 6:20 |
| apl [3] 3:3 5:14 11:7 |
| apodaca [2] 1:17 15:4 |
| appearances [1] 2:1 |
| applaud [1] 13:10 |
| applied [1] 5:12 |
| apply [3] 11:16,16,19 |
| applying [1] 10:23 |
| appreciate [1] 14:10 |
| approval [1] 14:14 |
| approved [1] 14:7 |
| area [4] 9:6 11:17,18 13:18 |
| areas [4] 8:18 9:3,9 11:3 |
| army [6] 2:5 5:8 13:11,20,22,24 |
| around [1] 3:11 |
| attorney [2] 15:9,13 |
| audience [1] 4:6 |
| authorization [1] 6:24 |
| automated [2] 9:17,18 |
| automation [1] 9:16 |
| availability [1] 6:6 |
| B |
| back [2] 10:13 12:13 |
| back-and-forth [1] 3:10 |
| backland [1] 8:18 |
| backlands [1] 9:15 |
| balance [1] 7:17 |
| ballast-water [1] 11:9 |
| base [1] 14:7 |
| based [1] 10:17 |
| baseline [1] 8:22 |
| behalf [2] 5:8 13:13 |
| believe [3] 13:12,17,21 |
| benefits [1] 7:17 |
| berth [3] 8:18,19 9:11 |
| berths [6] 1:4,14 5:14 6:13 8:16,24 |
| best [1] 11:7 |
| biological [2] 11:2,5 |

| |
|---|
| biology [1] 11:22 |
| board [1] 12:25 |
| both [1] 9:4 |
| branch [1] 4:21 |
| brief [2] 8:21 12:8 |
| bring [4] 9:8,12 12:17,25 |
| brings [2] 13:17 14:3 |
| buenas [1] 13:9 |
| C |
| california [3] 1:6 15:2,5 |
| calls [5] 8:17,24 10:2 11:13 13:16 |
| cancer [1] 11:15 |
| cannon [3] 2:2 3:1 4:19 |
| card [1] 12:16 |
| cards [3] 3:17,18 13:4 |
| careful [1] 7:14 |
| carefully [1] 7:22 |
| caused [1] 7:5 |
| ceqa [1] 13:25 |
| certainly [1] 3:14 |
| certified [1] 15:4 |
| certify [3] 15:6,9,15 |
| chance [3] 3:6,21,24 |
| changed [1] 12:22 |
| chief [1] 4:21 |
| christine [2] 2:9 4:23 |
| christopher [1] 2:2 |
| clarification [1] 3:13 |
| clean [3] 6:17,22 11:20 |
| clearly [3] 12:17 13:16,23 |
| close [1] 10:21 |
| closer [1] 8:11 |
| coequally [1] 11:24 |
| col [3] 4:18 5:4,5 |
| colonel [3] 4:15 5:6 8:6 |
| colored [1] 9:3 |
| come [2] 3:19 13:5 |
| commander [1] 5:7 |
| comment [4] 3:21,25 10:18 13:3 |
| comments [9] 3:22 6:3 7:22 8:1 12:15,19,21,23 14:18 |
| common [1] 9:20 |
| community [3] 13:15 14:4,13 |
| company [1] 13:13 |
| compliance [1] 7:2 |
| complied [1] 14:1 |
| comply [1] 5:16 |
| concerning [1] 7:20 |
| conclude [1] 14:20 |
| condenses [1] 12:11 |
| conditions [2] 10:24,24 |
| conducting [1] 5:10 |
| confident [1] 11:10 |
| consequently [1] 7:3 |
| consider [1] 7:22 |
| consideration [2] 7:24 12:25 |
| considerations [1] 10:16 |
| considering [1] 6:21 |
| construct [2] 5:13 9:12 |
| consultation [1] 11:6 |
| contact [2] 4:9,13 |
| container [6] 1:5 3:3 5:14 8:16,17 9:9 |
| contrary [1] 7:13 |
| copies [1] 12:13 |
| corps [28] 2:5,8 4:8,10,20,22 5:8,9, |

| |
|--|
| 12,16,19,25 6:4,5,8,19 7:1,3,7,11,16,19,21 13:11,20,23,24 14:19 |
| corps' [1] 7:21 |
| correct [1] 15:7 |
| counsel [2] 15:10,13 |
| county [4] 13:14 14:5,5,8 |
| course [1] 3:6 |
| courtesy [1] 5:11 |
| cranes [10] 8:25 9:8,13,17,18,19,22,23 10:3 12:5 |
| csr [1] 1:17 |
| cubic [1] 9:14 |
| cumulative [1] 7:9 |
| currently [2] 8:24 10:20 |
| D |
| dash [3] 6:19,20,23 |
| day [2] 14:2 15:18 |
| december [2] 6:5 10:19 |
| decision [2] 7:6,24 |
| decisions [1] 7:1 |
| definitely [1] 14:11 |
| demolish [1] 9:6 |
| demonstrate [2] 13:22,23 |
| deputy [2] 4:19 5:7 |
| description [1] 8:8 |
| design [2] 8:14 12:24 |
| details [1] 5:1 |
| determination [1] 7:14 |
| determine [1] 7:11 |
| determined [1] 5:19 |
| detriments [1] 7:18 |
| develop [2] 9:9,14 |
| development [1] 13:12 |
| dialogue [1] 3:9 |
| direct [1] 7:9 |
| directly [1] 12:10 |
| discharge [1] 6:15 |
| discharging [1] 6:22 |
| discuss [1] 8:4 |
| discussions [1] 14:11 |
| disposal [2] 6:18,23 |
| disposed [1] 6:17 |
| district [2] 4:19 5:7 |
| division [2] 4:12 10:9 |
| document [14] 3:13,22,23,25 8:15,23 11:24 12:10,12,20,21,22,25 13:12 |
| down [1] 4:5 |
| draft [5] 1:15 3:3 6:6 10:15,19 |
| drain [1] 11:11 |
| dredge [2] 6:9 9:14 |
| dredged [2] 6:17,22 |
| dredging [1] 12:5 |
| driver [1] 11:5 |
| dual-hoist [1] 9:17 |
| due [1] 5:18 |
| during [1] 10:18 |
| E |
| e.i.r [2] 6:2 10:19 |
| e.i.r./e.i.s [2] 10:15,17 |
| e.i.s [3] 5:22,24 6:6 |
| e.i.s./e.i.r [2] 1:15 6:5 |
| e.i.s/e.i.r [1] 3:3 |
| economic [2] 13:17 14:3 |
| efficiency [1] 8:20 |

efforts [3] 12:9 13:19,20
eight [1] 9:13
elements [1] 9:2
emphasize [1] 7:22
employed [2] 15:10,13
employee [1] 15:12
employer [1] 14:5
employment [1] 14:7
end [2] 14:2,11
engage [1] 3:10
engaging [1] 13:11
engineer [1] 4:19
engineering [1] 4:24
engineers [7] 2:5,8 4:8 5:8,9 6:9 13:11
engineers' [2] 13:20,23
entrance [1] 9:5
environmental [15] 2:6,9 4:12,12 5:17,21 6:2 7:2,4,10 10:5,9,10,13, 23
epa-approved [1] 6:22
equipment [2] 9:17,21
es [1] 13:9
evaluate [2] 7:4,16
evaluating [1] 7:9
even [1] 11:8
evening [3] 3:1 5:6 13:8
event [1] 15:16
everyone [1] 3:1
example [1] 9:20
existing [3] 8:21,22 9:14
expand [2] 9:5,7
expanded [1] 12:7
expansion [1] 9:11
expect [2] 3:9 10:2
experimenting [1] 11:8
extension [1] 12:4
extent [1] 4:9
extra [2] 3:20 12:13

F

facilities [4] 8:21 9:6,7,13
facility [1] 9:1
fact [1] 14:2
factors [1] 7:15
fall [1] 3:8
february [2] 8:1 10:21
federal [9] 5:15,15,24 6:7,8 7:1,2 12:3,4
feel [1] 11:10
feet [3] 8:25 9:12 10:3
few [2] 3:20 11:17
fill [3] 3:18 6:9,15
filled [1] 12:15
final [7] 4:2 7:24 10:17 12:20,20, 25 14:18
financially [1] 15:14
find [2] 3:19 7:12
findings [2] 10:15,22
first [1] 13:10
fish [1] 11:17
fleet [1] 11:8
focused [1] 3:22
folks [1] 14:2
following [1] 7:25
foregoing [1] 15:7
foremost [1] 13:10

foreseeable [1] 7:18
formal [1] 10:13
former [1] 9:9
forward [3] 4:2 10:16 12:2
four [2] 8:24 9:8
frame [1] 13:1
front [2] 4:4 12:17
full [1] 7:24
further [2] 15:9,15
furthermore [1] 15:12
future [1] 9:16

G

gantry [2] 9:22,23
gases [1] 11:1
gates [1] 9:4
general [1] 7:20
geology [1] 11:23
give [7] 3:21 4:24,25 8:7,9 9:23,24
given [2] 7:23,25
got [1] 3:17
granted [1] 7:12
greater [1] 13:18
green [5] 2:6 4:11 10:7,8 14:16
greenhouse [1] 11:1
guide [2] 8:14 12:11
guided [1] 9:17

H

hand [1] 15:17
happy [2] 3:14 4:5
harbor [2] 11:12,17
harbors [1] 6:14
health [2] 11:1,14
hear [3] 3:6,15 5:2
hearing [5] 3:2 7:19 13:3 14:20,22
helped [1] 8:13
helpful [1] 3:14
hereby [1] 15:5
hereto [1] 15:13
hereunto [1] 15:17
highlighted [1] 9:3
honeybone [3] 2:9 4:23 8:6
hope [2] 12:24 14:5
hulls [1] 11:10

I

idea [1] 9:23
immediate [1] 4:7
impact [4] 5:21 6:2 11:11,15
impacts [4] 5:20 7:4,10 10:25
implementing [1] 13:20
important [2] 14:12,13
improve [1] 8:18
improvements [1] 5:13
in-water [1] 6:12
include [1] 6:15
includes [1] 9:25
increase [4] 8:17,19 11:13 14:7
indicating [1] 3:19
indirect [1] 7:9
infrastructure [2] 9:8,15
initiation [1] 10:13
input [1] 7:20
intent [2] 5:23 6:1
interact [1] 4:10
interest [3] 7:12,13,16

interested [7] 5:11 12:10,13,16 13:4 15:14,15
introduce [1] 4:3
introducing [1] 11:12
invasive [2] 11:6,12
island [2] 5:15 8:11
issued [1] 6:19
itself [2] 3:23,25

J

jahangira [3] 13:8,8,9
jamie [2] 1:17 15:4
jan [4] 2:6 4:11 10:4,8
january [2] 1:16 15:18
jay [3] 13:5,8,9
job [1] 4:1
joint [3] 5:25 6:4 13:12
july [4] 5:23,25 8:23 10:14
june [1] 8:23

K

keep [1] 3:22

L

l.a [1] 6:23
land [1] 8:15
landfill [3] 8:19 9:15,25
landside [2] 9:18 11:16
lanes [1] 9:5
large [1] 14:5
larger [1] 8:16
last [1] 4:23
laws [1] 7:3
laxt [1] 9:9
learn [1] 11:7
lease [1] 10:1
least [1] 4:23
left [1] 4:7
less [2] 11:3,4
lieutenant [2] 4:15 8:6
life [1] 11:13
linear [1] 9:12
list [1] 12:9
live-aboard [1] 11:15
live-aboards [2] 11:17,18
located [1] 8:10
locations [1] 8:8
look [3] 12:1,6,7
los [10] 2:6,9 3:2 4:11 5:7,12 8:3 13:11,14,18
lot [1] 11:6
lt [4] 4:18 5:4,5,6

M

m.p.r.s.a [1] 6:25
mailed [1] 12:10
mailing [1] 12:9
mainly [1] 3:15
maintain [1] 11:9
major [1] 11:5
majority [1] 11:21
management [2] 4:12 10:9
manager [2] 2:3 4:8
marine [1] 6:24
material [3] 6:15,17,22
matter [2] 1:4 14:2
measures [5] 10:23,25 11:20,21 13:21

meeting [8] 1:15 3:4 5:10 6:4 7:7, 25 10:14 12:14
meetings [1] 3:5
mention [2] 3:7 11:19
mentioned [1] 10:21
mi [1] 13:9
might [1] 12:7
million [2] 10:2 13:16
minutes [1] 13:7
mitigate [1] 11:3
mitigation [4] 10:23 11:20,21 13:21
modifications [1] 9:4
mostly [1] 3:24
move [2] 10:16 13:2
moving [1] 12:2
ms [3] 8:6 10:7 14:16
must [2] 5:16 7:11

N

name [4] 10:8 12:18 13:6,8
national [1] 5:16
nature [1] 5:18
navigation [1] 6:11
near [1] 11:18
need [4] 3:12 4:1,10 5:2
neither [2] 7:8 15:9
nepa [3] 5:17 7:3 13:25
new [5] 9:8,12,13 11:8 12:5
next [1] 4:21
night [1] 3:15
nine [1] 9:10
noise [1] 11:23
nombre [1] 13:9
nor [2] 7:8 15:10
notes [1] 15:8
notice [7] 5:23 6:1,1,1,6 10:12 11:21
number [1] 6:19

O

objectives [1] 8:13
obvious [1] 3:7
obviously [1] 3:23
ocean [1] 6:23
often [1] 3:8
okay [8] 3:1,24 4:19 5:5 8:7 10:22 14:18,20
on-dock [2] 8:25 12:7
one [2] 4:4 12:1
only [1] 11:15
opening [1] 13:2
opponent [1] 7:8
optimize [1] 8:15
oral [2] 8:5 12:14
original [1] 15:8
other [2] 14:17,18
otherwise [1] 3:10
out [4] 3:18 9:23 11:11 12:15
outlines [1] 9:3
outreach [1] 12:9
over [3] 3:19 5:4 10:4 11:13 12:9
over-water [1] 6:12
overview [4] 4:25 8:7,9,21

P

p.m [1] 14:23

page ^[1] 12:12
pages ^[1] 12:12
palos ^[1] 1:16
part ^[1] 7:24
participating ^[1] 12:16
particular ^[1] 7:15
parties ^[4] 7:25 12:10 15:10,13
pedro ^[1] 1:6
people ^[3] 3:9 4:3 5:2
permit ^[2] 10:18,20
permit ^[1] 5:13 6:8,19,19 7:1,6,12,
21,24 8:2 12:4
permits ^[1] 5:15
picks ^[2] 9:21,22
pier ^[1] 8:10
place ^[1] 6:18
plan ^[2] 9:5 11:20
planned ^[1] 13:21
please ^[3] 3:18,22 12:16
podium ^[1] 13:5
point ^[2] 4:9,13
policy ^[1] 5:17
population ^[1] 11:15
port ^[5] 2:6,9 3:2 4:24 5:12,25 6:4,
21 8:3 10:9 12:3 13:10,15,24 14:
13
port's ^[5] 6:1,12 7:10 13:19,22
possible ^[1] 9:16
possibly ^[1] 9:13
posture ^[1] 13:24
potential ^[1] 11:11
power ^[1] 9:7
practices ^[1] 11:7
preparation ^[1] 6:2
prepare ^[2] 5:24 12:20
prepared ^[1] 6:4
preparing ^[1] 10:16
presentation ^[3] 4:24 8:4,5
previously ^[2] 6:19 10:21
prior ^[1] 7:5
probably ^[1] 14:9
proceed ^[1] 10:12
proceeding ^[1] 15:11
process ^[7] 8:15 10:5,10,13,20 14:
6,9
professional ^[1] 4:25
program ^[1] 6:8
project ^[40] 1:5,15 2:3 3:3,23 4:8,
10,14 5:1,20,24 7:5,8,10,11,15,20,
23 8:2,8,10,13,14 9:2,11,24 10:11,
24 11:13,25 12:2,6,7,24 13:17 14:
3,6,12,13,14
project's ^[2] 7:16,17
properly ^[2] 13:25 14:6
proponent ^[1] 7:8
proposal ^[1] 7:13
proposed ^[17] 1:14 5:20 6:12,14 7:
5,10,11,20,23 8:1,7,10,14 9:2,11,
24 11:25
prosperity ^[2] 13:17 14:3
protection ^[1] 6:25
provide ^[3] 8:1,3,18
public ^[18] 1:15 3:2,4,5 5:10,11 6:
1,3 7:12,13,15,19,20 10:14 11:23
12:9,14 13:3
public-interest ^[1] 7:14

published ^[3] 5:23,25 6:6
purpose ^[1] 3:5
pursuant ^[1] 6:24

Q

qualified ^[1] 15:5
qualify ^[1] 5:15
quality ^[2] 11:1,22
question ^[1] 3:12
questions ^[1] 3:10

R

rail ^[2] 8:25 12:7
rail-mounted ^[1] 9:22
range ^[1] 11:25
re ^[1] 1:4
reader's ^[1] 12:11
reason ^[1] 3:7
reasonably ^[1] 7:17
rebreastock ^[5] 2:6 4:11 10:7,8 14:16
receive ^[4] 7:23 10:17 12:20,23
received ^[2] 6:3 13:3
receiving ^[3] 12:4,14 13:3
recognize ^[1] 13:19
reconstruct ^[1] 9:6
reduced ^[1] 12:6
reefer ^[1] 9:5
register ^[2] 5:24 6:7
regulated ^[2] 6:13,16
regulating ^[1] 6:9
regulatory ^[1] 7:7
related ^[6] 11:1,2,14,21,22 15:10
relative ^[1] 15:12
release ^[1] 10:24
released ^[2] 10:12,19
relevant ^[1] 7:15
report ^[1] 6:2
reporter ^[1] 15:4
reproduce ^[1] 12:21
requesting ^[1] 7:19
required ^[1] 5:21
requires ^[3] 6:23 7:14,16
research ^[1] 6:25
residences ^[1] 11:16
resident ^[2] 13:14 14:4
residential ^[1] 11:14
resource ^[1] 11:3
resources ^[2] 11:2,5
response ^[3] 6:3 12:22,23
responses ^[1] 10:17
responsibility ^[2] 7:4,7
responsible ^[2] 6:9 13:24
rest ^[1] 11:2
result ^[1] 5:20
results ^[1] 10:15
review ^[9] 1:15 3:4,5 7:16 10:10,
13,15,20,23
risk ^[3] 11:1,14,15
rivers ^[1] 6:14
road ^[1] 11:18
roadability ^[1] 9:6
rubber-tired ^[1] 9:22
rule ^[1] 11:11

S

san ^[1] 1:6
sanctuaries ^[1] 6:25

scope ^[1] 5:18
scoping ^[1] 6:4
section ^[3] 6:14,16,24
services ^[1] 11:23
set ^[1] 15:17
several-thousand ^[1] 12:12
she's ^[4] 4:9,12,24,25
ship ^[3] 8:24 10:2 11:13
ships ^[1] 8:16
shop ^[1] 9:7
shorthand ^[1] 15:4
show ^[2] 12:21,22
side ^[1] 9:21
sigloch ^[5] 4:16,18 5:4,5,6
significant ^[5] 5:20 10:25 11:4,4,
11
sir ^[1] 4:17
sit ^[1] 4:5
site ^[2] 6:23 8:9
sitting ^[1] 4:4
situation ^[1] 3:8
six ^[1] 11:24
size ^[1] 8:18
sort ^[1] 3:6
south ^[1] 1:16
spanish ^[1] 5:10
speaker ^[3] 3:17,18 13:4
speaker's ^[1] 12:15
speakers ^[1] 14:17
specialist ^[1] 4:13
species ^[2] 11:6,12
spring-summer ^[1] 13:1
stacking ^[1] 9:18
staff ^[3] 3:11 8:3 12:22
stakeholder ^[1] 14:8
standard ^[1] 10:24
start ^[1] 12:18
state ^[3] 13:5 15:1,5
statement ^[1] 5:21
states ^[6] 2:3,5 5:8,19 6:10,16
stating ^[1] 3:7
statutes ^[1] 13:25
statenographic ^[1] 15:8
steve ^[1] 5:6
stevens ^[2] 2:3 4:7
stewardship ^[2] 13:22,23
still ^[2] 10:25 11:10
storage ^[1] 9:5
stress ^[1] 14:12
subject ^[1] 7:2
sufficient ^[1] 8:18
summary ^[3] 9:24 10:22 12:8
support ^[2] 9:16 14:14
system ^[1] 11:9

T

tardes ^[1] 13:9
terminal ^[14] 1:5 3:3 5:13,14,15 8:
10,12,19,22 9:4,8,9,20,21
testimony ^[1] 8:5
teu ^[1] 13:17
teus ^[2] 8:24 10:2
there's ^[9] 4:1 8:24 10:20 11:22,25
12:2,5,12 13:4
therefore ^[1] 5:21
theresa ^[2] 2:3 4:7
three ^[1] 13:7

thursday ^[1] 1:16
tonight ^[4] 3:11,15 5:3 12:14
tonight's ^[1] 7:25
top ^[1] 9:22
total ^[3] 10:1,3,3
towards ^[1] 13:2
transcript ^[2] 1:14 15:7
transcription ^[1] 15:8
transfer ^[1] 9:18
transporting ^[1] 6:21
treatment ^[1] 11:9
true ^[1] 15:7
turn ^[2] 5:3 10:4
two ^[1] 3:12

U

u.s ^[4] 6:18,22 13:11,20
unavoidable ^[1] 10:25
under ^[4] 6:8,13,18 11:20
unit ^[1] 9:5
united ^[6] 2:3,5 5:8,19 6:10,16
until ^[1] 7:25
up ^[5] 4:3 9:13 10:3 12:17 13:5
utility ^[1] 9:7

V

vacant ^[1] 8:19
variety ^[1] 7:2
various ^[3] 9:3,7 12:5
vehicles ^[1] 9:18
verbatim ^[1] 12:21
vessel ^[3] 11:8,10 13:16
view ^[2] 8:8,11

W

walk ^[1] 10:10
wants ^[1] 3:17
warship ^[1] 8:17
water ^[1] 6:17
waters ^[4] 5:19 6:10,16,18
weighing ^[1] 7:14
welcome ^[2] 3:1 5:9
wharf ^[4] 5:13 9:12 10:3 12:4
whereof ^[1] 15:17
whereupon ^[1] 14:22
whether ^[2] 7:11 12:23
will ^[9] 4:2 7:22,23,25 8:3 10:4,16,
21 12:21
win-win ^[1] 13:15
within ^[2] 9:8 11:17
witness ^[1] 15:17
work ^[1] 13:13
worleyparsons ^[2] 13:13 14:4
written ^[1] 8:1

Y

yards ^[1] 9:14

- 1 **2.3.6 Draft EIS/EIR Public Hearing**
- 2 **APL Public Hearing Transcript (APLPH)**
- 3 **Response to Comment APLPH-1**
- 4 Thank you for your comment on the proposed Project and Draft EIS/EIR.
- 5

1 **2.4 References**

2 Following are additional materials referenced in the Section 2.3, Response to Comments,
3 above:

- 4 ▪ Estimated Tugboat Transit Emissions from Seattle, Washington to the Port of Los
5 Angeles, California
- 6 ▪ Letter from the Office of Historic Preservation to the USACE – Section 106
7 determination (May 2, 2012)

8

Harbor Craft Construction Emissions

Tugboat Transit Emissions: Seattle, WA to Port of Los Angeles, CA

Distance: 1200 nautical miles (one way)
 Estimated Speed: 13 knots
 Travel time: 92.31 hours
 Estimated Engine Size: 1810 HP = 1350 kW
 Estimated Load Factor for Transit: 0.85

| | NOx | HC | PM |
|----------------------------------|-----|------|------|
| Tier 4 Emission Standards, g/kWh | 1.8 | 0.19 | 0.04 |

| | | | |
|--|---------------|--------------|--------------|
| Round trip Transit Emissions, lbs per tug | 840.68 | 88.74 | 18.68 |
|--|---------------|--------------|--------------|

Reference

See "Distance" tab in this spreadsheet.
 See "Speed" tab in this spreadsheet.
 Calculated.
 Draft EIS/EIR, Appendix E1, Table 1.2-1 General Conformity Applicability Analysis
 Estimated by CDM Smith.

See "Tier4Standards" tab in this spreadsheet.


Calculated.

APL Construction Barge Tug Emissions (Transporting dredged material)

| | VOC | CO | NOx | SOx | PM10 | PM2.5 |
|--|---------------|-----------------|-----------------|-------------|--------------|--------------|
| APL Barge Tug Emissions | | | | | | |
| Tier 3 Emission Factor, g/kWh | 0.58 | 5.00 | 5.22 | 0.01 | 0.11 | 0.10 |
| Construction Emissions, lbs | 32.18 | 277.41 | 289.62 | 0.41 | 6.10 | 5.61 |
| Tier 4 Emissions | | | | | | |
| Construction Emissions, lbs | 10.54 | 277.41 | 99.87 | 0.41 | 2.22 | 2.04 |
| Transit Emissions (2 tugs), lbs | 177.48 | 4,670.43 | 1,681.36 | 6.91 | 37.36 | 34.37 |
| Total Emissions, lbs | 188.02 | 4,947.84 | 1,781.22 | 7.33 | 39.58 | 36.42 |
| Net Increase due to transporting Tier 4 compliant tug to POLA from Seattle, lbs | | | | | | |
| | 155.84 | 4,670.43 | 1,491.61 | 6.91 | 33.48 | 30.80 |

| HP Rating | Load Factor | # Active | Equip-Hrs Day | Daily hp-hr | Total Work Days |
|-----------|-------------|----------|---------------|-------------|-----------------|
| 1350 | 0.31 | 2 | 6.72 | 5625 | 6 |

Source:
 Draft EIS/EIR, Appendix E1, Table 1.2-1 General Conformity Applicability Analysis



December 15, 2005 Prince William Sound Tug Fleet Workshop Summary

Report to:
Prince William Sound Regional Citizens' Advisory Council

PWSRCAC Contract No: 801.06.01

Prepared by:



**HARVEY
CONSULTING**

Oil & Gas, Environmental, Regulatory Compliance, and Training

February 23, 2006

Email: sharvcy@harveyninc.net

Phone: (907) 694-7994
Fax: (907) 694-7995

PO Box 771026
Eagle River, Alaska 99577

Standard (RPS) as described in Scenario 809 of the PWS Tanker Oil Spill Discharge Prevention and Contingency Plans (PWS Tanker C-plans).

The workshop *is not* a request for agency approval to change the escort system at this time; this will be associated with a "long trek, including a risk assessment and disabled tanker towing study."

Workshop Assumptions:

Workshop participants were asked to apply four major assumptions throughout the workshop:

1. All of the tugs in PWS are available to respond to the Scenario 809 tanker oil spill;
2. The Tanker of Opportunity (TOO) at hour 24 of the oil spill response does not require additional tugs to approach and lighten the stricken tanker;
3. The peak tug requirements for a Scenario 809 tanker oil spill occur within the first 12 hours of the oil spill response; and
4. The need to resume oil transportation simultaneous to oil spill response is ignored.

Workshop "Compliance Test" Rules:

According to the PWS Tanker Owners interpretation of the 1995 PWS Tanker C-Plan Settlement, and currently approved plan, the following "compliance test" rules were applied throughout the workshop to determine whether or not the proposed tug configurations met state and federal compliance tests. These "compliance test" rules were not validated by the agencies, nor agreed to by PWSRCAC.

1. TransRee barges must be on-scene by hour 7.7;
2. Lightering Barge must be on-scene by hour 9; and
3. Nearshore Barge must be on-scene by hour 24.

ADEC pointed out the VMT C-plan requirement to have two tugs within two hours of Valdez, was an important compliance test which was being ignored, when tanker oil spill response operations are conducted parallel to ongoing VMT operations.

Workshop Logistics Rules:

The PWS Tanker Owners used the following logistics rules to compute the tug and barge deployment and transit times:

1. Tug boat speed without a barge in tow = 13 knots (kts);
2. Tug boat speed with a barge in tow = 10 kts;
3. One-hour setup time for manned barges, and 1.5 hours for unmanned barges; and
4. One-hour barge deployment time.

PWSRCAC questioned the use of the same tug speed assumptions in all seasons and all weather conditions.

Agency & PWSRCAC Concerns About Assumptions and Rules

Both ADEC and PWSRCAC participants repeatedly expressed concern about the proposed workshop assumptions and rules. PWSRCAC also requested an opportunity to verify the 1995 settlement terms and conditions to verify the "compliance test" assumptions. Both PWSRCAC and the agencies were

| | | | |
|-------------|------|-------------------|------|
| 15 ≤ D < 20 | 7.0 | 0.27 ^a | 2014 |
| 20 ≤ D < 25 | 9.8 | 0.27 | 2014 |
| 25 ≤ D < 30 | 11.0 | 0.27 | 2014 |

‡ Option: Tier 3 PM/NOx+HC at 0.14/7.8 g/kWh in 2012, and Tier 4 in 2015.
† Tier 3 NOx+HC standards do not apply to 2000-3700 kW engines.
a - 0.34 g/kWh for engines below 3300 kW.

In addition to the above NOx+HC and PM standards, the following CO emission standards apply for all Category 1/2 engines starting with the applicable Tier 3 model year:

- i. 8.0 g/kWh for engines < 8 kW,
- ii. 6.6 g/kWh for engines ≥ 8 kW and < 19 kW,
- iii. 5.5 g/kWh for engines ≥ 19 kW and < 37 kW,
- iv. 5.0 g/kWh for engines ≥ 37 kW.

Table 8. Tier 4 Standards for Marine Diesel Category 1/2 Engines

| Power (P) | NOx | HC | PM | Date |
|-----------------|--------------|--------------|-------------------|---------------------|
| <i>kW</i> | <i>g/kWh</i> | <i>g/kWh</i> | <i>g/kWh</i> | |
| P ≥ 3700 | 1.8 | 0.19 | 0.12 ^a | 2014 ^c |
| | 1.8 | 0.19 | 0.06 | 2016 ^{b,c} |
| 2000 ≤ P < 3700 | 1.8 | 0.19 | 0.04 | 2014 ^{c,d} |
| 1400 ≤ P < 2000 | 1.8 | 0.19 | 0.04 | 2016 ^c |
| 600 ≤ P < 1400 | 1.8 | 0.19 | 0.04 | 2017 ^d |

a - 0.25 g/kWh for engines with 15-30 dm³/cylinder displacement.
b - Optional compliance start dates can be used within these model years.
c - Option for Cal 2: Tier 3 PM/NOx+HC at 0.14/7.8 g/kWh in 2012, and Tier 4 in 2015
d - The Tier 3 PM standards continue to apply for these engines in model years 2014 and 2015 only.

**OFFICE OF HISTORIC PRESERVATION
DEPARTMENT OF PARKS AND RECREATION**

P.O. BOX 942896
SACRAMENTO, CA 94296-0001
(916) 653-6624 Fax: (916) 653-9824
calshpo@ohp.parks.ca.gov
www.ohp.parks.ca.gov



May 02, 2012

In Reply Refer To: COE120224A

Aaron O. Allen
Chief, North Coast Branch
Department of the Army
Los Angeles District, Corps of Engineers
Ventura Field Office
2151 Alessandro Drive, Suite 110
Ventura, CA 93001

RECEIVED
MAY - 3 2012
Regulatory Branch

Re: Berths 302-306 Container Terminal Project, Port of Los Angeles

Dear Mr. Allen:

Pursuant to 36 CFR Part 800 (as amended 8-05-04) regulations implementing Section 106 of the National Historic Preservation Act, the Army Corps of Engineers (COE), is seeking my comments on its determination of the Area of Potential Effects (APE), historic property identification efforts, determination of National Register of Historic Places (NRHP), and finding of effects that the proposed undertaking will have on historic properties.

The proposed project will consist of construction of a 1,250-foot-long wharf extension to pier 300 (which is built on redeposited dredged sediment) and the installation of 12 new cranes. You have conducted Native American consultation, a records search, and have submitted the following document as evidence of your efforts to identify historic properties in the project Area of Potential Effects (APE):

- *Application for Permit, Notice of Availability for a draft Environmental Impact Statement (EIS) & Public Hearing*

No historic properties within the APE were identified in the records search. Native American consultation determined no sacred lands and no concerns with the project. After reviewing your letter and supporting documentation, pursuant to 36 CFR 800.4(d), I concur that there will be no historic properties affected by this undertaking.

Be advised that under certain circumstances, such as unanticipated discovery or a change in project description, the COE may have additional future responsibilities for this undertaking under 36 CFR Part 800. Thank you for seeking my comments and for considering historic properties in planning your project. If you require further information, please contact Brendon Greenaway of my staff at phone 916-445-7036 or email bgreenaway@parks.ca.gov.

Sincerely,

Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

1 *This page left intentionally blank*

Modifications to the Draft EIS/EIR

Introduction

This chapter of the document addresses modifications to the Draft EIS/EIR for the Berths 302-206 [APL] Container Terminal Project (proposed Project) at the Port of Los Angeles (Port). It presents all revisions related to public comments, as determined necessary by the lead agencies, for the following areas of the document:

- Global Revision;
- Executive Summary;
- Chapter 1, Introduction
- Chapter 2, Project Description
- Section 3.2, Air Quality, Meteorology and Greenhouse Gases;
- Section 3.3, Biological Resources
- Chapter 11, List of Preparers and Contributors;
- Appendix E1, Construction Emissions;
- Appendix F3; Essential Fish Habitat Analysis

Any revisions to supporting documentation are also presented. The numbering format from the Draft EIS/EIR is maintained in the sections presented here. Only sections that have revisions based on public comment are included, and sections that have no revisions are not included. Readers are referred to the Draft EIS/EIR to view complete sections.

It should be noted that most of the changes were editorial in nature. Some mitigation measures were strengthened and a new standard condition related to biological resources (SC BIO-2) was added to include NMFS notification. None of the edits result in changes to significance findings.

As provided in Section 15088(c) of the State CEQA Guidelines, responses to comments may take the form of a revision to a Draft EIR or may be separate section in the Final EIR. As provided in 40 CFR 1503.4(c), to comply with NEPA, responses to comments may take the form of revisions to a Draft EIS, or if changes to the EIS in responses to comments are minor, then changes may be provided on errata sheets attached to the Draft EIS. This chapter complies with the latter of these two guidelines and provides changes to the Draft EIS/EIR in revision-mode text (i.e., deletions are shown with ~~striketrough~~ and additions are shown with underline). These notations are meant to provide

1 clarification, corrections, or minor revisions as needed as a result of public comments or
2 because of changes in the proposed Project since the release of the Draft EIS/EIR.

3 **Changes to the Draft EIS/EIR**

4 The following changes to the text as presented below are incorporated into the Final
5 EIS/EIR:

6 **Global Revision**

7 The cover and throughout the entire Draft EIS/EIR (i.e., within the footer), the State
8 Clearinghouse Number (SCH#) was incorrectly shown as SCH# 2009071021. On
9 January 11, 2012, a letter was sent to all regulatory and trustee agencies notifying them
10 that the Draft EIS/EIR notice and document was circulated for public review with an
11 incorrect SCH# and that the correct number is as follows:

12 SCH# 2009071031

13 **Changes Made to the Executive Summary**

14 **Section ES.3.1, Page ES-8, Table ES-1**

15 The row labeled “% TEUs by Near Dock Rail” is revised to clarify that the % TEUs in
16 that row represents trips to and from both near-dock and off-dock railyards.

1

Table ES-1: Existing and Projected Berths 302-306 [APL] Container Terminal Throughput

| | CEQA Baseline (July 2008- June 2009) | NEPA Baseline (2027) | Proposed Project (at capacity) | | | | | No Project (at capacity) 2027 |
|--|--|-------------------------|-----------------------------------|-----------|-----------|-----------|-----------|----------------------------------|
| | | | 2012 | 2015 | 2020 | 2025 | 2027 | |
| Annual TEUs ^{a,b} | 1,128,080 | 2,153,000 | 1,906,000 | 2,702,000 | 2,912,000 | 3,122,000 | 3,206,000 | 2,153,000 |
| Annual Ship Calls | 247 | 286 | 234 | 286 | 338 | 364 | 390 | 286 |
| Annual Truck Trips (Total) | 998,728 | 1,922,497 | 1,701,940 | 2,412,720 | 2,600,240 | 2,879,170 | 3,003,160 | 1,922,500 |
| Annual Rail Trips (Total) | 1,676 | 2,336 | 2,197 | 2,627 | 2,831 | 2,876 | 2,953 | 2,336 |
| % Truck/Rail Splits | 46/54 | 45/55 | 45/55 | 45/55 | 45/55 | 45/55 | 45/55 | 45/55 |
| <i>% TEUs by On-dock Rail</i> | 35% | 35% | 35% | 35% | 35% | 33% | 32% | 35% |
| <i>% TEUs by Near Dock/Off-Dock Rail</i> | 11% | 10% | 10% | 10% | 10% | 12% | 13% | 10% |
| <i>% TEUs by Truck</i> | 54% | 55% | 55% | 55% | 55% | 55% | 55% | 55% |
| Terminal Acreage | 291 | 291 | 291 | 347 | 347 | 347 | 347 | 291 |
| Number of A-frame Gantry Cranes | 12 | 12 | 16 | 18 | 24 | 24 | 24 | 12 |
| Number of Berths ^c | 4 | 3.5 | 3.5 | 4.5 | 4 | 4 | 4 | 3.5 |

a. Baseline throughput numbers were generated by LAHD Wharfingers Office

b. NEPA Baseline, Proposed Project and No Project throughput numbers represent terminal capacity throughput levels

c. Useable berth space refers to the amount of space available to berth vessels and is dependent on vessel sizes. As ships get bigger, a fixed wharf length will have less berth space

Section ES.5.2, Table ES-3, Pages ES-49, ES-54, and ES-56

In Table ES-3, under Proposed Project (page ES-49), Alternative 5 (page ES-54), and Alternative 6 (page ES-56), standard condition of approval SC BIO-2 has been added under Impact BIO-4a.

| | | | |
|---|-----------------------------|--|-----------------------------|
| BIO-4a: Construction activities would not substantially disrupt local biological communities. | CEQA: Less than significant | Mitigation not required; however, MM BIO-1 and SC BIO-1 and SC BIO-2 would further reduce any potential for impact | CEQA: Less than significant |
| | NEPA: Less than significant | | NEPA: Less than significant |

Section ES.5.2.4, Page ES-98

Add SC BIO-2 under “Biology”, second column, as follows:

Biology

- MM BIO-1: Conduct nesting bird surveys.
- SC BIO-1: Avoid marine mammals
- SC BIO-2: NMFS Notification

Section ES.5.2.4.1, Page ES-100

Revise mitigation measures MM AQ-3 and MM AQ-4, as follows:

MM AQ-3: Fleet Modernization for On-Road Trucks Used During Construction

1. Trucks hauling material such as debris or any fill material will be fully covered while operating off Port property.
2. Idling will be restricted to a maximum of 5 minutes when not in use.
3. USEPA Standards:
 - a. For On-road trucks with a gross vehicle weight rating (GVWR) of at least 19,500 pounds (~~except for Import Haulers and Earth Movers~~): Comply with USEPA 2007 on-road emission standards for PM₁₀ and NO_x (0.01 grams per brake horsepower-hour (g/bhp-hr) and 1.2 g/bhp-hr or better, respectively).
 - b. ~~For Import Haulers with a GVWR of at least 19,500 pounds used to move dirt and debris to and from the construction site via public roadways: Comply with USEPA 2004 on road emission standards for PM₁₀ and NO_x (0.10 g/bhp-hr and 2.0 g/bhp-hr, respectively).~~
 - ~~For Earth Movers with a GVWR of at least 19,500 pounds used to move dirt and debris within the construction site: Comply with USEPA 2004 on road emission standards for PM₁₀ and NO_x (0.10 g/bhp-hr and 2.0 g/bhp-hr, respectively).~~

MM AQ-4: Fleet Modernization for Construction Equipment (except Vessels, Harbor Craft and On-Road Trucks)

1. Construction equipment will incorporate, where feasible, emissions-savings technology such as hybrid drives and specific fuel economy standards.
2. Idling will be restricted to a maximum of 5 minutes when not in use.

1 3. Equipment Engine Specifications:

- 2 a. Tier 4 equipment shall be considered based on availability at the time the
3 construction bid is issued.
- 4 b. At a minimum, ~~P~~prior to January 1, 2015, ~~A~~all off-road diesel-powered
5 construction equipment greater than 50 hp will meet Tier 3 off-road emission
6 standards at a minimum. In addition, this equipment will be retrofitted with a
7 CARB-verified Level 3 DECS.
- 8 c. From January 1, 2015 on: All off-road diesel-powered construction
9 equipment greater than 50 hp will meet Tier 4 off-road emission standards at
10 a minimum.

11 **Section ES.5.2.4.2, Page ES-106**

12 Add SC BIO-2 after SC BIO-1, as follows:

13 **SC BIO-2: NMFS Notification**

14 The Los Angeles Harbor Department (LAHD) will notify the National Marine Fisheries
15 Service (NMFS) no less than 14 calendar days prior to commencing construction,
16 dredging, and disposal operations associated with the proposed Project. LAHD will also
17 notify NMFS no less than five calendar days prior to completion of construction,
18 dredging, and disposal operations.

19 **Section ES.5.2.4.3, Pages ES-107 to ES-108**

20 Revise lease measure LM AQ-1, as follows:

21 **LM AQ-1: Periodic Review of New Technology and Regulations.**

22

23 The Port shall require the Berths 302-306 tenant to review, in terms of feasibility and
24 benefits, any Port-identified or other new emissions-reduction technology, and report to
25 the Port. Such technology feasibility reviews shall take place at the time of the Port's
26 consideration of any lease amendment or facility modification for the proposed Project
27 site. If the technology is determined by the Port to be feasible in terms of cost, technical
28 and operational feasibility, the tenant shall work with the Port to implement such
29 technology.

30 Potential technologies that may further reduce emission and/or result in cost-savings
31 benefits for the tenant may be identified through future work on the CAAP, Technology
32 Advancement Program, Zero Emissions Technology Program, and terminal automation.
33 Over the course of the lease, the tenant and the Port shall work together to identify
34 potential new technologies. Such technology shall be studied for feasibility, in terms of
35 cost, technical and operational feasibility, and emissions reduction benefits.

36 As partial consideration for the Port agreement to issue the permit to the tenant, the tenant
37 shall implement not less frequently than once every ~~7~~5 years following the effective date
38 of the permit, new air quality technological advancements, subject to mutual agreement
39 on operational feasibility and cost sharing, which shall not be unreasonably withheld.

40 The effectiveness of this measure depends on the advancement of new technologies and
41 the outcome of future feasibility or pilot studies. As discussed in the Draft EIS/EIR

1 under Section 3.2.4.1 of Section 3.2, Air Quality, Meteorology, and Greenhouse Gases, if
2 the tenant requests future Project changes that would require environmental clearance and
3 a lease amendment, future CAAP mitigation measures would be incorporated into the
4 new lease at that time.

5 **Changes Made to Chapter 1, Introduction**

6 **Section 1.8, Page 1-58**

7 Los Angeles Public Library
8 San Pedro Branch
9 ~~924~~931 South Gaffey Street
10 San Pedro, California 90731

11 **Changes Made to Chapter 2, Project** 12 **Description**

13 **Chapter Summary, Pages 2-2, Table 2-1**

14 The row labeled “% TEUs by Near Dock Rail” is revised to clarify that the % TEUs in
15 that row represents trips to and from both near-dock and off-dock railyards.

Table 2-1: Existing and Projected Berths 302-306 Container Terminal Throughput

| | CEQA Baseline (July 2008- June 2009) | NEPA Baseline (2027) | Proposed Project (at capacity) | | | | | No Project (at capacity) 2027 |
|--|---|----------------------------|-----------------------------------|-----------|-----------|-----------|-----------|-------------------------------------|
| | | | 2012 | 2015 | 2020 | 2025 | 2027 | |
| Annual TEUs^{a,b} | 1,128,080 | 2,153,000 | 1,906,000 | 2,702,000 | 2,912,000 | 3,122,000 | 3,206,000 | 2,153,000 |
| Annual Ship Calls | 247 | 286 | 234 | 286 | 338 | 364 | 390 | 286 |
| Annual Truck Trips (Total) | 998,728 | 1,922,497 | 1,701,940 | 2,412,720 | 2,600,240 | 2,879,170 | 3,003,160 | 1,922,500 |
| Annual Rail Trips (Total) | 1,676 | 2,336 | 2,197 | 2,627 | 2,831 | 2,876 | 2,953 | 2,336 |
| % Truck/Rail Splits | 46/54 | 45/55 | 45/55 | 45/55 | 45/55 | 45/55 | 45/55 | 45/55 |
| <i>% TEUs by On-dock Rail</i> | 35% | 35% | 35% | 35% | 35% | 33% | 32% | 35% |
| <i>% TEUs by Near Dock/Off-Dock Rail</i> | 11% | 10% | 10% | 10% | 10% | 12% | 13% | 10% |
| <i>% TEUs by Truck</i> | 54% | 55% | 55% | 55% | 55% | 55% | 55% | 55% |
| Terminal Acreage | 291 | 291 | 291 | 347 | 347 | 347 | 347 | 291 |
| Number of A-Frame Gantry Cranes | 12 | 12 | 16 | 18 | 24 | 24 | 24 | 12 |
| Number of Berths^c | 4 | 3.5 | 3.5 | 4.5 | 4 | 4 | 4 | 3.5 |

a Baseline throughput numbers were generated by LAHD Wharfingers Office

b NEPA Baseline, Proposed Project and No Project throughput numbers represent terminal capacity throughput levels

c Useable berth space refers to the amount of space available to berth vessels and is dependent on vessel sizes. As ships get bigger, a fixed wharf length will have less berth space.

1
2
3
4

Changes Made to Section 3.2, Air Quality, Meteorology, and Greenhouse Gases

Section 3.2.4.1.1, Pages 3.2-37, Table 3.2-7a

Table 3.2-7a: Regulations and Agreements Assumed in the Unmitigated Construction Emissions

| Off-Road Construction Equipment | On-Road Trucks | Tugboats | General Cargo Ships | Fugitive Dust |
|--|---|---|--|--|
| <p>Emission Standards for Non-road Diesel Engines – Tier 1, 2, 3, and 4 standards gradually phased in over all years due to normal construction equipment fleet turnover.</p> <p>California Diesel Fuel Regulations – 15-ppm sulfur.</p> <p>CARB Portable Diesel-Fueled Engines Air Toxic Control Measure (ATCM) – Effective September 12, 2007, all portable engines having a maximum rated horsepower of 50 bhp and greater and fueled with diesel shall meet weighted fleet average PM emission standards.</p> | <p>Emission Standards for On-road Trucks – Tiered standards gradually phased in over all years due to normal truck fleet turnover.</p> <p>California Diesel Fuel Regulations – 15-ppm sulfur.</p> <p>Airborne Toxic Control Measure to Limit Diesel-Fueled Commercial Motor Vehicle Idling – Diesel trucks are subject to idling limits, when not being used to power concrete mixing, water pumps, etc.</p> | <p>California Diesel Fuel Regulations – 15-ppm sulfur.</p> <p>From January 1, 2011 on: All harbor craft with C1 or C2 marine engines must utilize a USEPA Tier-3 engine, or cleaner.</p> | <p>IMO Marpol VI - 0.1 1.0 percent sulfur fuel</p> <p>VSRP – comply with the expanded Vessel Speed Reduction Program (VSRP) of 12 knots between 40 nautical miles (nm) from Point Fermin and the Precautionary Area.</p> <p>These ships must also use low-sulfur fuel (maximum sulfur content of 0.2 percent) in auxiliary engines, main engines, and boilers within 40 nm of Point Fermin.</p> | <p>SCAQMD Rule 403 Compliance – 60 percent reduction in fugitive dust due to watering three times per day.</p> <p>SCAQMD Rule 1403 Compliance – Work practices will limit asbestos emissions from demolition or renovations.</p> |

Note: This table is not a comprehensive list of all applicable regulations; rather, the table lists key regulations and agreements that substantially affect the emission calculations for the proposed Project. A description of each regulation or agreement is provided in Section 3.2.3.

Section 3.2.4.1.1, Page 3.2-39

Revise third paragraph, as follows:

~~Within 40 nm of Point Fermin, the maximum sulfur content of fuel burned in propulsion and auxiliary engines and boilers was conservatively assumed to be 0.2 percent. Within 24 nautical miles of the California baseline, the maximum sulfur content was assumed to be 0.1 1.0 percent (13 CCR, Section 2299.2). Within 40 nm of Point Fermin, the maximum sulfur content of fuel burned in propulsion and auxiliary engines and boilers was conservatively assumed to be 0.2 percent for the mitigated conditions.~~

Within 40 nm of Point Fermin, the maximum sulfur content of fuel burned in propulsion and auxiliary engines and boilers was conservatively assumed to be 0.2 percent for the mitigated conditions.

Section 3.2.4.3.1, Pages 3.2-75 to 3.2-76, Revise Tables 3.2-20a and 3.2-20b

Table 3.2-20a: Peak Daily Emissions Associated with Proposed Project Construction Activities – Proposed Project Without Mitigation

| Emission Source | Peak Daily Emissions (lb/day) ^d | | | | | |
|--|--|--------------------------|------------------------------|-------------------------|-------------------------------|--------------------------------|
| | VOC | CO | NO _x | SO _x | PM ₁₀ ^a | PM _{2.5} ^a |
| Project Year 2012 | | | | | | |
| Phase 1a - Wharf Construction | 73 | 268 | 692 | 1 | 113 | 45 |
| Phase 1b - Backland Construction | 37 | 153 | 331 | 0 | 53 | 22 |
| Phase 1h - Crane Installation ^b | 101 69 | 95 100 | 794 643 | 37 130 | 97 83 | 90 76 |
| Phase 1e - Building Construction | 13 | 54 | 127 | 0 | 23 | 9 |
| Phase 1f - Reefer Area Expansion | 13 | 52 | 119 | 0 | 11 | 6 |
| Phase 1g - Utility Infrastructure | 5 | 18 | 49 | 0 | 2 | 2 |
| All Phases - Worker Commute | 1 | 11 | 1 | 0 | 16 | 4 |
| Peak Daily 2012 – CEQA Impact^c | 243 211 | 651 656 | 2,113 1,962 | 38 131 | 313 299 | 176 162 |
| Peak Daily 2012 – NEPA Impact^{c,e} | 224 192 | 571 576 | 1,944 1,793 | 38 131 | 300 286 | 169 155 |
| Thresholds | 75 | 550 | 100 | 150 | 150 | 55 |
| CEQA Significant? | Yes | Yes | Yes | No | Yes | Yes |
| NEPA Significant? | Yes | Yes | Yes | No | Yes | Yes |
| Project Year 2013 | | | | | | |
| Phase 1a - Wharf Construction | 73 | 268 | 692 | 1 | 112 | 45 |
| Phase 1b - Backland Construction | 37 | 153 | 331 | 0 | 53 | 22 |
| Phase 1c - AMP Installation (Berth 306) | 5 | 20 | 46 | 0 | 7 | 3 |
| Phase 1e - Building Construction | 13 | 54 | 127 | 0 | 22 | 9 |
| Phase 2 - Grading, Paving, Striping | 12 | 47 | 116 | 0 | 13 | 6 |
| All Phases - Worker Commute | 1 | 11 | 1 | 0 | 16 | 4 |
| Peak Daily 2013 – CEQA Impact^c | 141 | 553 | 1,313 | 2 | 223 | 88 |
| Peak Daily 2013 – NEPA Impact^{c,e} | 79 | 289 | 738 | 1 | 119 | 48 |
| Thresholds | 75 | 550 | 100 | 150 | 150 | 55 |
| CEQA Significant? | Yes | Yes | Yes | No | Yes | Yes |
| NEPA Significant? | Yes | No | Yes | No | No | No |

Notes:

- Emissions of PM₁₀ and PM_{2.5} assume that fugitive dust is controlled in accordance with SCAQMD Rule 403 by watering disturbed areas 3 times per day.
- One general cargo ship delivers four shoreside cranes in Phase I
- Emissions might not add precisely due to rounding. For more explanation, refer to the discussion in Section 3.2.4.1.
- The emission estimates presented in this table were calculated using the latest available data, assumptions, and emission factors at the time this document was prepared. Construction is assumed to occur during most of Year 2012. This is assumed as it is conservative (i.e. worst-case). Future studies might use updated data, assumptions, and emission factors that are not currently available.
- The CEQA Impact equals total Project construction emissions minus CEQA baseline construction emissions (which are zero). The NEPA impact equals total Project construction emissions minus NEPA baseline construction emissions as reported in Table 3.2-11.

Table 3.2-20b: Peak Daily^a Combined Construction and Operational Emissions Without Mitigation—Proposed Project

| Emission Source | Peak Daily Emissions (lb/day) ^d | | | | | |
|--|--|--|--|--------------------------------------|--------------------------------------|--------------------------------------|
| | VOC | CO | NO _x | SO _x | PM ₁₀ | PM _{2.5} |
| Project Year 2012 | | | | | | |
| <i>Operational Emission Sources</i> | | | | | | |
| Ships – Transit ^b and Anchoring | 205 | 381 | 3,278 | 84 | 60 | 48 |
| Ships – Hoteling | 87 | 223 | 2,461 | 140 | 58 | 46 |
| Tugboats | 5 | 23 | 89 | 0 | 4 | 3 |
| Trucks ^b | 161 | 494 | 1,844 | 4 | 102 | 30 |
| Trains ^b | 86 | 319 | 1,703 | 1 | 48 | 44 |
| Terminal Equipment | 47 | 280 | 1,115 | 1 | 36 | 33 |
| Worker Trips | 29 | 296 | 24 | 0 | 47 | 10 |
| <i>Construction Emission Sources</i> | | | | | | |
| Wharf Construction | 73 | 268 | 692 | 1 | 113 | 45 |
| Backland Construction | 37 | 153 | 331 | 0 | 53 | 22 |
| Crane Installation ^b | 101 <u>69</u> | 95 <u>100</u> | 794 <u>643</u> | 37 <u>130</u> | 97 <u>83</u> | 90 <u>76</u> |
| Building Construction | 13 | 54 | 127 | 0 | 23 | 9 |
| Reefer Area Expansion | 13 | 52 | 119 | 0 | 11 | 6 |
| Utility Infrastructure | 5 | 18 | 49 | 0 | 2 | 2 |
| Worker Commute | 1 | 11 | 1 | 0 | 16 | 4 |
| Total – Project Year 2012^c | 863 <u>831</u> | 2,667 <u>2,672</u> | 12,627 <u>12,476</u> | 268 <u>361</u> | 670 <u>656</u> | 392 <u>378</u> |
| CEQA Impacts | | | | | | |
| CEQA Baseline Emissions | 924 | 3,539 | 13,126 | 5,394 | 1,115 | 863 |
| Project minus CEQA Baseline | (61) <u>(93)</u> | (872) <u>(867)</u> | (499) <u>(650)</u> | (5,126) <u>(5,033)</u> | (445) <u>(459)</u> | (471) <u>(485)</u> |
| Thresholds | 75 | 550 | 100 | 150 | 150 | 55 |
| Significant? | No | No | No | No | No | No |
| NEPA Impacts | | | | | | |
| NEPA Baseline Emissions | 620 | 2,016 | 10,515 | 231 | 354 | 214 |
| Project minus NEPA Baseline ^f | 224 <u>192</u> | 571 <u>576</u> | 1,944 <u>1,793</u> | 38 <u>131</u> | 300 <u>286</u> | 169 <u>155</u> |
| Thresholds | 75 | 550 | 100 | 150 | 150 | 55 |
| Significant? | Yes | Yes | Yes | No | Yes | Yes |

Notes:

- Emissions assume the simultaneous occurrence of maximum theoretical daily equipment activity levels. Such levels would rarely occur during day-to-day terminal operations.
- Truck, train, ship, and worker commute emissions include transport within the South Coast Air Basin.
- Hoteling emissions include regional power plant emissions from AMP electricity generation.
- Emissions might not precisely add due to rounding. For further explanation, refer to the discussion in Section 3.2.4.1.
- The emission estimates presented in this table were calculated using the latest available data, assumptions, and emission factors at the time this document was prepared. Construction is assumed to occur during most of Year 2012. This is assumed as it is conservative (i.e. worst-case). Future studies might use updated data, assumptions, and emission factors that are not currently available.
- Emissions represent proposed Project construction emissions minus NEPA baseline construction emissions as shown in Table 3.2-11.

Section 3.2.4.3.1, Pages 3.2-78 to 3.2-79

Revise mitigation measure MM AQ-3, as follows:

MM AQ-3: Fleet Modernization for On-Road Trucks Used During Construction

4. Trucks hauling material such as debris or any fill material will be fully covered while operating off Port property.

5. Idling will be restricted to a maximum of 5 minutes when not in use.

6. USEPA Standards:

e. For On-road trucks with a gross vehicle weight rating (GVWR) of at least 19,500 pounds (except for Import Haulers and Earth Movers): Comply with USEPA 2007 on-road emission standards for PM₁₀ and NO_x (0.01 grams per brake horsepower-hour (g/bhp-hr) and 1.2 g/bhp-hr or better, respectively).

d. For Import Haulers with a GVWR of at least 19,500 pounds used to move dirt and debris to and from the construction site via public roadways: Comply with USEPA 2004 on road emission standards for PM₁₀ and NO_x (0.10 g/bhp-hr and 2.0 g/bhp-hr, respectively).

For Earth Movers with a GVWR of at least 19,500 pounds used to move dirt and debris within the construction site: Comply with USEPA 2004 on road emission standards for PM₁₀ and NO_x (0.10 g/bhp-hr and 2.0 g/bhp-hr, respectively).

Section 3.2.4.3.1, Page 3.2-79

Revise mitigation measure MM AQ-4, as follows:

MM AQ-4: Fleet Modernization for Construction Equipment (except Vessels, Harbor Craft and On-Road Trucks)

1. Construction equipment will incorporate, where feasible, emissions-savings technology such as hybrid drives and specific fuel economy standards.

2. Idling will be restricted to a maximum of 5 minutes when not in use.

3. Equipment Engine Specifications:

a. Tier 4 equipment shall be considered based on availability at the time the construction bid is issued.

b. At a minimum, Pprior to January 1, 2015; All off-road diesel-powered construction equipment greater than 50 hp will meet Tier 3 off-road emission standards at a minimum. In addition, this equipment will be retrofitted with a CARB-verified Level 3 DECS.

c. From January 1, 2015 on: All off-road diesel-powered construction equipment greater than 50 hp will meet Tier 4 off-road emission standards at a minimum.

Section 3.2.4.3.1, Pages 3.2-81 to 3.2-82, Tables 3.2-22a and 3.2-22b

Revise Tables 3.2-22a and 3.2-22b, as follows:

Table 3.2-22a: Peak Daily Emissions Associated with Proposed Project Construction Activities – Proposed Project With Mitigation

| Emission Source | Daily Emissions (lb/day) ^d | | | | | |
|--|--|--|--|--------------------------------------|--|--|
| | VOC | CO | NO _x | SO _x | PM ₁₀ ^a | PM _{2.5} ^a |
| Project Year 2012 | | | | | | |
| Wharf Construction | 69 | 260 | 334 | 1 | 87 | 21 |
| Backland Construction | 37 | 152 | 218 | 0 | 40 | 9 |
| Crane Installation ^b | 72 64 | 95 100 | 598 522 | 18 26 | 78 77 | 72 71 |
| Building Construction | 13 | 54 | 109 | 0 | 19 | 5 |
| Reefer Area Expansion | 13 | 52 | 90 | 0 | 7 | 2 |
| Utility Infrastructure | 5 | 18 | 41 | 0 | 0 | 0 |
| Worker Commute | 1 | 11 | 1 | 0 | 16 | 4 |
| Peak Daily 2012 – CEQA Impact^{c,e} | <u>211</u> <u>203</u> | <u>641</u> <u>646</u> | <u>1,392</u> <u>1,316</u> | <u>20</u> <u>28</u> | <u>246</u> <u>245</u> | <u>114</u> <u>113</u> |
| Peak Daily 2012 – NEPA Impact^e | <u>192</u> <u>184</u> | <u>561</u> <u>565</u> | <u>1,223</u> <u>1,147</u> | <u>20</u> <u>28</u> | <u>232</u> <u>231</u> | <u>106</u> <u>105</u> |
| Thresholds | 75 | 550 | 100 | 150 | 150 | 55 |
| CEQA Significant? | Yes | Yes | Yes | No | Yes | Yes |
| NEPA Significant? | Yes | Yes | Yes | No | Yes | Yes |
| Project Year 2013 | | | | | | |
| Wharf Construction | 69 | 260 | 334 | 1 | 87 | 21 |
| Backland Construction | 37 | 152 | 218 | 0 | 40 | 9 |
| AMP Installation (Berth 306) | 5 | 20 | 42 | 0 | 5 | 1 |
| Building Construction | 13 | 54 | 109 | 0 | 19 | 5 |
| Grading, Paving, Striping | 12 | 47 | 89 | 0 | 10 | 3 |
| Worker Commute | 1 | 11 | 1 | 0 | 16 | 4 |
| Peak Daily 2013 – CEQA Impact^{c,e} | 137 | 543 | 794 | 2 | 175 | 44 |
| Peak Daily 2013 – NEPA Impact^e | 75 | 279 | 219 | 1 | 70 | 3 |
| Thresholds | 75 | 550 | 100 | 150 | 150 | 55 |
| CEQA Significant? | Yes | No | Yes | No | Yes | No |
| NEPA Significant? | Yes | No | Yes | No | No | No |

Notes:

- Emissions of PM₁₀ and PM_{2.5} assume that fugitive dust is controlled in accordance with SCAQMD Rule 403 to achieve a 60 percent reduction relative to uncontrolled levels..
- One general cargo ship delivers four shoreside cranes in Phase I
- Emissions might not add precisely due to rounding. For more explanation, refer to the discussion in Section 3.2.4.1.
- The emission estimates presented in this table were calculated using the latest available data, assumptions, and emission factors at the time this document was prepared. Construction is assumed to occur during most of Year 2012. This is assumed as it is conservative (i.e. worst-case). Future studies might use updated data, assumptions, and emission factors that are not currently available.
- The CEQA Impact equals total Project construction emissions minus CEQA baseline construction emissions (which are zero). The NEPA impact equals total Project construction emissions minus NEPA baseline construction emissions as reported in Table 3.2-11.

Table 3.2-22b: Peak Daily^a Combined Construction and Operational Emissions With Mitigation – Proposed Project

| Emission Source | Peak Daily Emissions (lb/day) ^d | | | | | |
|--|--|--------------|-----------------|-------------------------------|------------------|-------------------|
| | VOC | CO | NO _x | SO _x | PM ₁₀ | PM _{2.5} |
| Project Year 2012 | | | | | | |
| <i>Operational Emission Sources</i> | | | | | | |
| Ships – Transit ^b and Anchoring | 205 | 381 | 3,278 | 84 | 60 | 48 |
| Ships – Hoteling | 87 | 223 | 2,461 | 140 | 58 | 46 |
| Tugboats | 5 | 23 | 89 | 0 | 4 | 3 |
| Trucks ^b | 161 | 494 | 1,844 | 4 | 102 | 30 |
| Trains ^b | 86 | 319 | 1,703 | 1 | 48 | 44 |
| Terminal Equipment | 47 | 280 | 1,115 | 1 | 36 | 33 |
| Worker Trips | 29 | 296 | 24 | 0 | 47 | 10 |
| <i>Construction Emission Sources</i> | | | | | | |
| Wharf Construction | 69 | 260 | 334 | 1 | 86 | 21 |
| Backland Construction | 37 | 152 | 218 | 0 | 39 | 9 |
| Crane Installation ^b | 72 | 95 | 598 | 26 18 | 78 | 72 |
| Building Construction | 13 | 54 | 109 | 0 | 18 | 5 |
| Reefer Area Expansion | 13 | 52 | 90 | 0 | 7 | 2 |
| Utility Infrastructure | 5 | 18 | 41 | 0 | 0 | 0 |
| Worker Commute | 1 | 11 | 1 | 0 | 16 | 4 |
| Total – Project Year 2012^c | 831 | 2,657 | 11,907 | 257 251 | 599 | 328 |
| CEQA Impacts | | | | | | |
| CEQA Baseline Emissions | 924 | 3,539 | 13,126 | 5,394 | 1,115 | 863 |
| Project minus CEQA Baseline | (94) | (882) | (1,219) | (5,137) (5,143) | (516) | (534) |
| Thresholds | 75 | 550 | 100 | 150 | 150 | 55 |
| Significant? | No | No | No | No | No | No |
| NEPA Impacts | | | | | | |
| NEPA Baseline Emissions | 620 | 2,016 | 10,515 | 231 | 354 | 214 |
| Project minus NEPA Baseline ^f | 192 | 561 | 1,223 | 20 | 232 | 106 |
| Thresholds | 75 | 550 | 100 | 150 | 150 | 55 |
| Significant? | Yes | Yes | Yes | No | Yes | Yes |

Notes:

- Emissions assume the simultaneous occurrence of maximum theoretical daily equipment activity levels. Such levels would rarely occur during day-to-day terminal operations.
- Truck, train, ship, and worker commute emissions include transport within the South Coast Air Basin.
- Hoteling emissions include regional power plant emissions from AMP electricity generation.
- Emissions might not precisely add due to rounding. For further explanation, refer to the discussion in Section 3.2.4.1.
- The emission estimates presented in this table were calculated using the latest available data, assumptions, and emission factors at the time this document was prepared. Construction is assumed to occur during most of Year 2012. This is assumed as it is conservative (i.e. worst-case). Future studies might use updated data, assumptions, and emission factors that are not currently available.
- Emissions represent proposed Project construction emissions minus NEPA baseline construction emissions as shown in Table 3.2-11.

Section 3.2.4.3.1, Pages 3.2-111 to 3.2-112

Revise lease measure LM AQ-1, as follows:

LM AQ-1: Periodic Review of New Technology and Regulations. The Port shall require the Berths 302-306 tenant to review, in terms of feasibility and benefits, any Port-identified or other new emissions-reduction technology, and report to the Port. Such technology feasibility reviews shall take place at the time of the Port's consideration of any lease amendment or facility modification for the proposed Project site. If the technology is determined by the Port to be feasible in terms of cost, technical and operational feasibility, the tenant shall work with the Port to implement such technology.

Potential technologies that may further reduce emission and/or result in cost-savings benefits for the tenant may be identified through future work on the CAAP, Technology Advancement Program, Zero Emissions Technology Program, and terminal automation. Over the course of the lease, the tenant and the Port shall work together to identify potential new technologies. Such technology shall be studied for feasibility, in terms of cost, technical and operational feasibility, and emissions reduction benefits.

As partial consideration for the Port agreement to issue the permit to the tenant, the tenant shall implement not less frequently than once every ~~7~~⁵ years following the effective date of the permit, new air quality technological advancements, subject to mutual agreement on operational feasibility and cost sharing, which shall not be unreasonably withheld.

The effectiveness of this measure depends on the advancement of new technologies and the outcome of future feasibility or pilot studies. As discussed in Section 3.2.4.1, if the tenant requests future Project changes that would require environmental clearance and a lease amendment, future CAAP mitigation measures would be incorporated into the new lease at that time.

Section 3.2.4.6, Pages 3.2-338 to 3.2-339

Under Impact AQ-1, revise mitigation measures MM AQ-3 and MM AQ-4, as follows:

| | |
|--------------------|--|
| Mitigation Measure | <p>MM AQ-3. Fleet Modernization for On-Road Trucks</p> <ol style="list-style-type: none"> 1. Trucks hauling material such as debris or any fill material will be fully covered while operating off Port property. 2. Idling will be restricted to a maximum of 5 minutes when not in use. 3. EPA Standards: <ol style="list-style-type: none"> a. For On-road trucks except for Import Haulers and Earth Movers: Comply with 2004 or 2007 on-road emission standards for PM₁₀ and NO_x b. For Import Haulers: Comply with 1998 or 2004 on road emission standards for PM₁₀ and NO_x c. For Earth Movers: Comply with 1998 or 2004 on road emission standards for PM₁₀ and NO_x |
| Timing | During specified construction phases. |
| Methodology | LAHD will include MM AQ-3 in the contract specifications for construction. LAHD will monitor implementation of mitigation measures during construction. |

| | |
|---------------------|--|
| Responsible Parties | LAHD |
| Mitigation Measure | <p>MM AQ-4. Fleet Modernization for Construction Equipment</p> <ol style="list-style-type: none"> 1. All dredging equipment shall be electric. 2. Construction equipment will incorporate, where feasible, emissions-savings technology such as hybrid drives and specific fuel economy standards. 3. Idling will be restricted to a maximum of 5 minutes when not in use. 4. Equipment Engine Specifications: <ol style="list-style-type: none"> a. <u>Tier 4 equipment shall be considered based on availability at the time the construction bid is issued. Meet Tier 2, 3, or 4 standards depending on timing.</u> b. Two categories of <u>standards exceptions</u> exist based on <u>timing</u> |
| Timing | During specified construction phases. |
| Methodology | LAHD will include MM AQ-4 in the contract specifications for construction. LAHD will monitor implementation of mitigation measures during construction. |
| Responsible Parties | LAHD |

1
2
3
4

Section 3.2.4.6, Page 3.2-344

Revise lease measure LM AQ-1, as follows:

| | |
|---|---|
| AQ-3: The proposed Project would result in operational emissions that exceed 10 tons per year of VOCs or a SCAQMD threshold of significance in Table 3.2-18. | |
| <i>(Also applies to Impact AQ-3 for Alternatives 3-6)</i> | |
| Lease Measure | <p>LM AQ-1. Periodic Review of New Technology and Regulations. The Port shall require the Berths 302-306 tenant to review, in terms of feasibility and benefits, any Port-identified or other new emissions-reduction technology, and report to the Port. Such technology feasibility reviews shall take place at the time of the Port's consideration of any lease amendment or facility modification for the proposed Project site. If the technology is determined by the Port to be feasible in terms of cost, technical and operational feasibility, the tenant shall work with the Port to implement such technology.</p> <p>Potential technologies that may further reduce emission and/or result in cost-savings benefits for the tenant may be identified through future work on the CAAP, Technology Advancement Program, Zero Emissions Technology Program, and terminal automation. Over the course of the lease, the tenant and the Port shall work together to identify potential new technologies. Such technology shall be studied for feasibility, in terms of cost, technical and operational feasibility, and emissions reduction benefits.</p> <p>As partial consideration for the Port agreement to issue the permit to the tenant, the tenant shall implement not less frequently than once every <u>75</u> years following the effective date of the permit, new air quality technological advancements, subject to mutual agreement on operational feasibility and cost sharing, which shall not be unreasonably withheld.</p> <p>The effectiveness of this measure depends on the advancement of new technologies and the outcome of future feasibility or pilot studies. As discussed in Section 3.2.4.1, if the tenant requests future Project changes that would require environmental clearance and a lease amendment, future CAAP mitigation measures would be incorporated into the new lease at that time.</p> |
| Timing | During operation |
| Methodology | LAHD will include this mitigation measure in lease agreements with tenants. |
| Responsible Parties | APL, LAHD. |

1

2

3

Changes Made to Section 3.3, Biological Resources

4

Section Summary, Key Points of Section 3.3, Page 3.3-2

5

Add SC BIO-2 after SC BIO-1, as follows:

6

7

8

9

10

SC BIO-2. NMFS Notification. The Los Angeles Harbor Department (LAHD) will notify the National Marine Fisheries Service (NMFS) no less than 14 calendar days prior to commencing construction, dredging, and disposal operations associated with the proposed Project. LAHD will also notify NMFS no less than five calendar days prior to completion of construction, dredging, and disposal operations.

Section 3.3.2.9, Pages 3.3-23 to 3.3-25

Essential Fish Habitat (EFH)

In accordance with the 1996 amendments to the Magnuson-Stevens Fishery Management and Conservation Act, an assessment of EFH was prepared for the proposed Project and alternatives, which includes impacts of dredging and wharf construction along Berths 302-305 and the 41-acre fill site (Appendix F3). The proposed Project/alternative area is located in an area designated as EFH for two Fishery Management Plans (FMPs): the Coastal Pelagics and Pacific Groundfish Management Plans. Of the 95 species federally managed under these plans, 2419 adult species are known to occur in the Port Complex and could potentially be affected by the proposed Project or alternatives (Appendix F3). However, most of these 2419 species have been collected only sporadically and in very low numbers, and habitat near the proposed Project site is not suitable for these species. The species with the highest potential to be affected by the proposed Project/alternatives are identified in Table 3.3-5.

Two coastal pelagic - northern anchovy and Pacific sardine - are likely to occur in the vicinity of the proposed Project. As summarized in Appendix F3, northern anchovy is among the most common and abundant fish species in the Port Complex. In 2006, larvae were present in the Port Complex during two seasonal periods: a greater peak in March-July and a lesser peak in October-December (MBC et al., 2007). Juvenile and adult anchovies have consistently been collected during fish sampling near the proposed Project site (MEC and Associates, 2002; SAIC, 2010). Northern anchovy are found from the surface to depths of 1,017 ft, though juveniles are generally more common inshore and in estuaries (Davies and Bradley, 1972).

Pacific sardine were not abundant during 2006 ichthyoplankton sampling throughout the Port Complex; two sardine larvae were collected in the Outer Harbor in April 2006 (MBC et al., 2007). This species is also less common than northern anchovy near the proposed Project site (MEC and Associates, 2002; SAIC, 2010). Pacific sardine is epipelagic, occurring in loosely aggregated schools (Wolf et al., 2001).

Jack mackerel (*Trachurus symmetricus*) and Pacific mackerel (*Scomber japonicus*) have been collected in Harbor, but in much lower frequency and numbers than northern anchovy and Pacific sardine. ~~While no mature market squid (*Doryteuthis opalescens*) have been reported in recent surveys, market squid paralarvae were collected in Inner and Outer Harbor areas in 2006 (MBC et al., 2007). All coastal pelagics are associated with the water column (as opposed to the seafloor like many of the groundfish); however, female squid also lay egg masses on sandy bottoms during spawning (at depths of about 16-180 ft, with most occurring between 66-115 ft) (PFMC, 1998).~~

None of the species covered under the Pacific Groundfish FMP are considered abundant in the area of the proposed Project. However, many are associated with hard substrate, kelp, and/or eelgrass (*Zostera marina*), which are less frequently sampled habitats than soft bottoms. Pacific sanddab (*Citharichthys sordidus*) is considered common in the vicinity of the proposed Project because it was collected by trawl in all three of the Harbor-wide biological studies, though not in great numbers (MEC 1988; MEC and Associates, 2002; SAIC, 2010). One individual was collected in 1986, 51 were collected in 2000, and 171 were collected in 2008. English sole (*Parophrys vetulus*) has also been collected during all three trawl studies, but in relatively low numbers: one individual in

1 1986, three individuals in 2002, and 24 individuals in 2008. Larvae of English sole were
 2 also collected in 2008. English sole prefer soft bottoms from 60 to 1,000 ft, while Pacific
 3 sanddab are found between 30 and 1,800 ft (Miller and Lea, 1972).

4 California skate (*Raja inornata*) and big skate (*R. binoculata*) were collected by trawl
 5 during the biological surveys of the Harbor, although only 23 California skate were
 6 collected in 2008, and no big skate were collected. Like English sole, California skate
 7 has been collected in all three Harbor-wide biological surveys, whereas big skate was
 8 only collected in 2002. Both species prefer soft-bottom habitat, although California skate
 9 occurs in much deeper waters (60 to 2,200 ft) than big skate (10 to 360 ft) (Miller and
 10 Lea, 1972). California scorpionfish (*Scorpaena guttata*) is another species collected in
 11 all three Harbor-wide surveys, with 11 individuals in 2008. Vermilion rockfish (*Sebastes*
 12 *miniatus*) was only collected in 2002 (four individuals) and 2008 (20 individuals).
 13 Vermilion rockfish occur between 20 and 1,440 ft, but are most common between 165
 14 and 495 ft. Juveniles are common in shallower water (20 to 120 ft), where they hover
 15 over sand patches near algae or structures, including pier pilings (Love et al., 2002). The
 16 remaining species in the table have only been collected sporadically and in low numbers.

Table 3.3-5: Managed Adult Fish/invertebrate Species Most Likely to Occur off Pier 300 Found in Los Angeles Harbor Based on Past Occurrences

| Common Name | Potential Habitat Use | Larval Occurrence ^{1,2,4} | Juv./Adult Occurrence ^{2,3,4,5} |
|---------------------------|---|------------------------------------|--|
| Coastal Pelagics | | | |
| northern anchovy | Open water. | Abundant | Abundant |
| Pacific sardine | Open water. | Uncommon | Common |
| Pacific (chub) mackerel | Open water, juveniles off sandy beaches and around kelp beds. | - | Uncommon |
| jack mackerel | Open water, young fish over shallow banks and juveniles around kelp beds. | Rare | Uncommon |
| market squid | Open water. Rare near bays, estuaries, and river mouths. | Rare | - |
| Pacific Groundfish | | | |
| English sole | Soft bottom habitats. | Rare | Uncommon |
| Pacific sanddab | Soft bottom habitats. | Rare | Common |
| butter sole | Soft bottom habitats. | Rare | - |
| black rockfish | Along breakwater, near deep piers and pilings. Associated with kelp, eelgrass, high relief reefs. | - | Rare |
| Bocaccio | Multiple habitat associations, including soft and hard bottom, kelp, eelgrass, etc. | - | Rare |
| brown rockfish | Multiple habitat associations but prefer hard substrata and rocky interfaces. | - | Rare |
| calico rockfish | Multiple habitat associations but prefer hard substrata and rocky interfaces. | - | Rare |
| California scorpionfish | Benthic, on soft and hard bottoms, as well as around structures. | - | Uncommon |
| grass rockfish | Common on hard substrate, kelp, and eelgrass habitats. | - | Rare |
| kelp rockfish | Common on hard substrate, kelp; reported along breakwater. | - | Rare |

| | | | |
|---------------------|--|------|----------|
| olive rockfish | Common around hard substrate, kelp; reported along breakwater. | - | Rare |
| vermillion rockfish | Juveniles over soft-bottom and kelp, adults associated with hard substrate. | - | Uncommon |
| Lingcod | Multiple habitat associations but prefer hard substrata and rocky interfaces. | - | Rare |
| Cabezon | Multiple habitat associations but prefer hard substrata and rocky interfaces. | Rare | Rare |
| Pacific hake | Common offshore, juveniles in open water. | Rare | - |
| leopard shark | Multiple habitat associations, including soft bottoms, and near structure, kelp, and eelgrass. | N/A | Rare |
| spiny dogfish | Pelagic and on muddy bottoms. | N/A | Rare |
| big skate | Soft bottom habitat. | N/A | Rare |
| California skate | Soft bottom habitat. | N/A | Uncommon |

Sources: 1 – MBC et al. (2007), 2 – MEC and Associates (2002), 3 – MBC (2009a,b), 4 – SAIC (2010), 5 – MEC (1999). N/A = Not applicable, internal fertilization. Abundant>Common>Uncommon>Rare.
 Note - Most rockfish larvae not identifiable to species.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27

Section 3.3.3, add Subsection 3.3.3.11, Pages 3.3-31

3.3.3.11 Vessel General Permit

The USEPA Vessel General Permit (VGP) was released on December 19, 2008, and applies to all non-military and non-recreational vessels of 79 feet or greater in length. Requirements for the VGP include:

- Submission of a Notice of Intent for vessels over 300 gross tons (or vessels with a capacity to hold or discharge 2,113 gallons [8 cubic meters] or more of ballast water;
- Corrective actions for violations of VGP limits;
- Requirements for visual and annual inspections; and
- Reporting requirements, which vary by vessel class.

In addition to general VGP regulations, states with authority to implement the CWA may add specific provisions, including performance standards, for vessel discharges in state waters through the Section 401 Water Quality Certification process. The state of California has issued additional conditions for vessels while in state waters. The VGP expires in December 2013, and the USEPA recently solicited public comment on a new draft VGP that would take effect upon expiration of the original VGP. The proposed VGP includes numeric criteria for discharged ballast water, and would impose several ballast water management (BWM) best management practices (BMPs) substantially similar to those in the 2008 VGP.

Section 3.3.4.3.1.1 (Proposed Project), Pages 3.3-49 to 3.3-50

CEQA Impact Determination

As described above, construction activities in the proposed Project site, particularly pile-driving, could cause short-term impacts on individuals (e.g. marine mammals and fishes,

1 including those with designated EFH) in the immediate vicinity of pile-driving.
2 However, no substantial disruption of biological communities would result from
3 proposed Project construction, and impacts are considered insignificant. In addition, with
4 implementation of standard condition of approval **SC BIO-1**, the pile-driving would
5 initiate with a soft start, which would minimize impacts to fish and marine mammals near
6 construction activities, as they would leave the area. Furthermore, night construction, if
7 required, would not result in significant impacts to biological resources.

8 Potential biological impacts from disposal of dredged sediments would depend on the
9 disposal method. Impacts from disposal at the LA-2 (as well as the LA-3) disposal site
10 was evaluated during the site designation process (USEPA and USACE, 2005).
11 Biological impacts due to construction and fill of the CDF, as well as expansion and fill
12 of the Cabrillo shallow water habitat, were evaluated in the *Final Supplemental*
13 *Environmental Impact Statement / Final Supplemental Environmental Impact Report*
14 *(EIS/EIR) for the Port of Los Angeles Channel Deepening Project* (USACE and LAHD,
15 2009). Any temporary water quality impacts would be minimized as discussed by pre-
16 dredge screening, water quality monitoring, and adaptive management and use of BMPs.

17 Construction activities that have the potential to introduce or redistribute invasive species
18 would be less than significant. All construction impacts that could substantially disrupt
19 local biological communities resulting from the proposed Project would be less than
20 significant under CEQA.

21 *Mitigation Measures*

22 No mitigation is required. Implementation of mitigation measure **MM BIO-1** and
23 standard conditions of approval **SC BIO-1** and **SC BIO-2** would further reduce
24 impacts.

25 **SC BIO-2. NMFS Notification.** The Los Angeles Harbor Department (LAHD) will
26 notify the National Marine Fisheries Service (NMFS) no less than 14
27 calendar days prior to commencing construction, dredging, and disposal
28 operations associated with the proposed Project. LAHD will also notify
29 NMFS no less than five calendar days prior to completion of
30 construction, dredging, and disposal operations.

31 *Residual Impacts*

32 Impacts would be less than significant.

33 **NEPA Impact Determination**

34 Construction of the proposed Project would result in limited upland construction,
35 in-water, and over-water construction activities not included in the NEPA baseline.
36 As described above, construction activities at the proposed Project site, particularly
37 pile-driving, could cause short-term impacts on individuals (e.g. marine mammals and
38 fishes, including those with designated EFH) in the immediate vicinity of pile-driving.
39 However, no substantial disruption of biological communities would result from
40 proposed Project construction, and impacts are considered insignificant. In addition, with
41 implementation of standard condition of approval **SC BIO-1**, the pile-driving would
42 initiate with a soft start, which would minimize impacts to fish and marine mammals near
43 construction activities, as they would leave the area. Furthermore, night construction, if
44 required, would not result in significant impacts to biological resources.

1 Potential biological impacts from disposal of dredged sediments would depend on the
 2 disposal method. Impacts from disposal at the LA-2 (as well as the LA-3) disposal site
 3 was evaluated during the site designation process (USEPA and USACE, 2005).
 4 Biological impacts due to construction and fill of the CDF, as well as expansion and fill
 5 of the Cabrillo shallow water habitat, were evaluated in the *Final Supplemental*
 6 *Environmental Impact Statement / Final Supplemental Environmental Impact Report*
 7 *(EIS/EIR) for the Port of Los Angeles Channel Deepening Project* (USACE and LAHD,
 8 2009). Any temporary water quality impacts would be minimized as discussed by pre-
 9 dredge screening, water quality monitoring, and adaptive management and use of BMPs.

10 Construction activities that have the potential to introduce or redistribute invasive species
 11 would be less than significant. All construction impacts that could substantially disrupt
 12 local biological communities resulting from the proposed Project would be less than
 13 significant under NEPA.

14 *Mitigation Measures*

15 No mitigation is required. Implementation of mitigation measure **MM BIO-1** and
 16 standard conditions of approval **SC BIO-1** and **SC BIO-2** would further reduce
 17 impacts.

18 *Residual Impacts*

19 Impacts would be less than significant.

20 **Section 3.3.4.3.2.5 (Alternative 5), Pages 3.3-96 to 3.3-97**

21 **Impact BIO-4a: Construction activities would not substantially** 22 **disrupt local biological communities.**

23 **CEQA Impact Determination**

24 Because the terrestrial portions of the Project site are largely developed, impacts on
 25 terrestrial biological communities would be limited. Plant communities on the backlands
 26 site are mostly introduced, weedy species, with Russian thistle (tumbleweed) the most
 27 abundant species. In addition, noise from night construction is not expected to result in
 28 significant impacts to biological resources because few birds/wildlife are scarce in upland
 29 areas and upland construction would not affect underwater noise levels

30 Construction impacts for Alternative 5 would be essentially the same as those described
 31 for the proposed Project (Impact BIO-4a). Construction activities at the proposed Project
 32 site, particularly pile-driving, could cause short-term impacts on individuals (e.g. marine
 33 mammals and fishes, including those with designated EFH) in the immediate vicinity of
 34 pile-driving. However, no substantial disruption of biological communities would result
 35 from Alternative 5 construction, and impacts are considered insignificant under CEQA.

36 Potential biological impacts from disposal of dredged sediments would depend on the
 37 disposal method. However, for all in-water disposal options (such as confined aquatic
 38 disposal or at the LA-2 ~~ODMDS~~), potential impacts include: water quality impacts from
 39 turbidity or contaminants and smothering of resident fishes and invertebrates. Impacts
 40 from disposal at the LA-2 (as well as the LA-3) disposal site was evaluated during the
 41 site designation process (USEPA and USACE, 2005). Biological impacts due to
 42 construction and fill of the CDF, as well as expansion and fill of the Cabrillo sShallow

1 ~~w~~Water ~~h~~Habitat Area, were evaluated in the *Final Supplemental Environmental Impact*
2 *Statement / Final Supplemental Environmental Impact Report (EIS/EIR) for the Port of*
3 *Los Angeles Channel Deepening Project* (USACE and LAHD, 2009). Any temporary
4 water quality impacts would be minimized as discussed by pre-dredge screening, water
5 quality monitoring, and adaptive management and use of BMPs.

6 Construction activities that have the potential to introduce or redistribute invasive species
7 would be less than significant. All construction impacts that could substantially disrupt
8 local biological communities resulting from Alternative 5 would be less than significant
9 under CEQA.

10 *Mitigation Measures*

11 No mitigation is required. As described under the proposed Project, the potential for
12 impacts could be further reduced with implementation of mitigation measure
13 **MM BIO-1** and standard conditions of approval **SC BIO-1** and **SC BIO-2**.

14 *Residual Impacts*

15 Impacts would be less than significant.

16 **NEPA Impact Determination**

17 Alternative 5 would include upland, over-water, and in-water development not included
18 in the NEPA baseline. However, because the terrestrial portions of the Project site are
19 largely developed, impacts on terrestrial biological communities would be limited. Plant
20 communities on the backlands site are mostly introduced, weedy species, with Russian
21 thistle (tumbleweed) the most abundant species. In addition, noise from night
22 construction is not expected to result in significant impacts to biological resources
23 because few birds/wildlife are scarce in upland areas and upland construction would not
24 affect underwater noise levels.

25 Construction activities at the terminal site, particularly pile-driving, could cause short-
26 term impacts on individuals (e.g. marine mammals and fishes, including those with
27 designated EFH) in the immediate vicinity of pile-driving. However, no substantial
28 disruption of biological communities would result from Alternative 5 construction, and
29 impacts are considered insignificant under NEPA.

30 Potential biological impacts from disposal of dredged sediments would depend on the
31 disposal method. However, for all in-water disposal options (such as confined aquatic
32 disposal or at the LA-2 ~~ODMDS~~), potential impacts include: water quality impacts from
33 turbidity or contaminants and smothering of resident fishes and invertebrates. Impacts
34 from disposal at the LA-2 (as well as the LA-3) disposal site was evaluated during the
35 site designation process (USEPA and USACE, 2005). Biological impacts due to
36 construction and fill of the CDF, as well as expansion and fill of the Cabrillo ~~s~~Shallow
37 ~~w~~Water ~~h~~Habitat Area, were evaluated in the *Final Supplemental Environmental Impact*
38 *Statement / Final Supplemental Environmental Impact Report (EIS/EIR) for the Port of*
39 *Los Angeles Channel Deepening Project* (USACE and LAHD, 2009). Any temporary
40 water quality impacts would be minimized as discussed by pre-dredge screening, water
41 quality monitoring, and adaptive management and use of BMPs.

42 Construction activities that have the potential to introduce or redistribute invasive species
43 would be less than significant. All construction impacts that could substantially disrupt

1 local biological communities resulting Alternative 5 would be less than significant under
2 NEPA.

3 *Mitigation Measures*

4 No mitigation is required. As described under the proposed Project, the potential for
5 impacts could be further reduced with implementation of mitigation measure
6 **MM BIO-1** and standard conditions of approval **SC BIO-1** and **SC BIO-2**.

7 **Section 3.3.4.3.2.6 (Alternative 6), Pages 3.3-111 to 3.3-112**

8 **Impact BIO-4a: Construction activities would not substantially** 9 **disrupt local biological communities.**

10 **CEQA Impact Determination**

11 Because the terrestrial portions of the proposed Project site are largely developed,
12 impacts on terrestrial biological communities resulting from Alternative 6 would be
13 limited. Plant communities on the backlands site are mostly introduced, weedy species,
14 with Russian thistle (tumbleweed) the most abundant species. In addition, noise from
15 night construction is not expected to result in significant impacts to biological resources
16 because few birds/wildlife are scarce in upland areas and upland construction would not
17 affect underwater noise levels. Construction impacts for Alternative 6 would be
18 essentially the same as those described for the proposed Project (Impact BIO-4a).
19 Construction activities at the proposed Project site, particularly pile-driving, could cause
20 short-term impacts on individuals (e.g. marine mammals and fishes, including those with
21 designated EFH) in the immediate vicinity of pile-driving. However, no substantial
22 disruption of biological communities would result from Alternative 6 construction, and
23 impacts are considered insignificant. In addition, with implementation of standard
24 condition of approval **SC BIO-1**, the pile-driving would initiate with a soft start, which
25 would minimize impacts to fish and marine mammals near construction activities, as they
26 would leave the area.

27 Potential biological impacts from disposal of dredged sediments would depend on the
28 disposal method. However, for all in-water disposal options (such as confined aquatic
29 disposal or at the LA-2-ODMDS), potential impacts include: water quality impacts from
30 turbidity or contaminants and smothering of resident fishes and invertebrates. Impacts
31 from disposal at the LA-2 (as well as the LA-3) disposal site was evaluated during the
32 site designation process (USEPA and USACE, 2005). Biological impacts due to
33 construction and fill of the CDF, as well as expansion and fill of the Cabrillo ~~s~~Shallow
34 ~~w~~Water ~~h~~Habitat Area, were evaluated in the *Final Supplemental Environmental Impact*
35 *Statement / Final Supplemental Environmental Impact Report (EIS/EIR) for the Port of*
36 *Los Angeles Channel Deepening Project* (USACE and LAHD, 2009). Any temporary
37 water quality impacts would be minimized as discussed by pre-dredge screening, water
38 quality monitoring, and adaptive management and use of BMPs.

39 Construction activities that have the potential to introduce or redistribute invasive species
40 would be less than significant. All construction impacts that could substantially disrupt
41 local biological communities resulting from Alternative 6 would be less than significant
42 under CEQA.

1 *Mitigation Measures*

2 No mitigation is required. As described under the proposed Project, the potential for
3 impacts could be further reduced with implementation of mitigation measure
4 **MM BIO-1** and standard conditions of approval **SC BIO-1** and **SC BIO-2**.

5 *Residual Impacts*

6 Impacts would be less than significant.

7 **NEPA Impact Determination**

8 Alternative 6 would include upland, overwater, and in-water development not included in
9 the NEPA baseline. Construction impacts for Alternative 6 would be essentially the same
10 as those described for the proposed Project (Impact BIO-4a). Because the terrestrial
11 portions of the Project site are largely developed, impacts on terrestrial biological
12 communities resulting from Alternative 6 would be limited. Plant communities on the
13 backlands site are mostly introduced, weedy species, with Russian thistle (tumbleweed)
14 the most abundant species. In addition, noise from night construction is not expected to
15 result in significant impacts to biological resources because few birds/wildlife are scarce
16 in upland areas and upland construction would not affect underwater noise levels.

17 Construction activities at the proposed Project site, particularly pile-driving, could cause
18 short-term impacts on individuals (e.g. marine mammals and fishes, including those with
19 designated EFH) in the immediate vicinity of pile-driving. However, no substantial
20 disruption of biological communities would result from Alternative 6 construction, and
21 impacts are considered insignificant. In addition, with implementation of standard
22 condition of approval **SC BIO-1**, the pile-driving would initiate with a soft start, which
23 would minimize impacts to fish and marine mammals near construction activities, as they
24 would leave the area.

25 Potential biological impacts from disposal of dredged sediments would depend on the
26 disposal method. However, for all in-water disposal options (such as confined aquatic
27 disposal or at the LA-2-~~ODMDS~~), potential impacts include: water quality impacts from
28 turbidity or contaminants and smothering of resident fishes and invertebrates. Impacts
29 from disposal at the LA-2 (as well as the LA-3) disposal site was evaluated during the
30 site designation process (USEPA and USACE, 2005). Biological impacts due to
31 construction and fill of the CDF, as well as expansion and fill of the Cabrillo ~~s~~Shallow
32 ~~w~~Water ~~h~~Habitat Area, were evaluated in the *Final Supplemental Environmental Impact*
33 *Statement / Final Supplemental Environmental Impact Report (EIS/EIR) for the Port of*
34 *Los Angeles Channel Deepening Project* (USACE and LAHD, 2009). Construction
35 activities that have the potential to introduce or redistribute invasive species would be
36 less than significant. All construction impacts that could substantially disrupt local
37 biological communities resulting from Alternative 6 would be less than significant under
38 NEPA.

39 *Mitigation Measures*

40 No mitigation is required. However, as with the proposed Project, the potential for
41 impacts under Alternative 6 could be further reduced with implementation of
42 mitigation measure **MM BIO-1** and standard conditions of approval **SC BIO-1** and
43 **SC BIO-2**.

1 *Residual Impacts*
 2 Impacts would be less than significant.

3 **Section 3.3.4.4, Table 3.3-6, Pages 3.3-120, 3.3-127, and 3.3-**
 4 **129**

5 In Table 3.3-6, under Proposed Project (page 3.3-120), Alternative 5 (page 3.3-127), and
 6 Alternative 6 (page 3.3-129), standard condition of approval SC BIO-2 has been added
 7 under Impact BIO-4a.

| | | | |
|---|-----------------------------|--|-----------------------------|
| BIO-4a: Construction activities would not substantially disrupt local biological communities. | CEQA: Less than significant | Mitigation not required; however, MM BIO-1 and SC BIO-1 and SC BIO-2 would further reduce any potential for impact | CEQA: Less than significant |
| | NEPA: Less than significant | | NEPA: Less than significant |

8
 9 **Section 3.3.4.5, Page 3.3-131**

10 Add SC BIO-2 after SC BIO-1, as follows:

11 **SC BIO-2. NMFS Notification.** The Los Angeles Harbor Department (LAHD) will
 12 notify the National Marine Fisheries Service (NMFS) no less than 14 calendar days prior
 13 to commencing construction, dredging, and disposal operations associated with the
 14 proposed Project. LAHD will also notify NMFS no less than five calendar days prior to
 15 completion of construction, dredging, and disposal operations.

16
 17 **Changes Made to Chapter 11, List of**
 18 **Preparers and Contributors**

19 **Section 11.3, Pages 11-2 to 11-3**

20 **CDM Smith**

21 **Project Management Team**

22 Principal-in-Charge David Jensen, P.E.

23 Project Manager and Technical Reviewer Dorothy Meyer

24 **Technical Team**

25 Aesthetics and Visual Resources Katie Owston

26 Juan Ramirez

27 Davey Dobbs

28 Air Quality, Meteorology, Greenhouse Gases,
 29 and Health Risk Analysis (HRA) John Pehrson

30 Katie Travis

| | | |
|----|---|---------------------|
| 1 | | Gwen Pelletier |
| 2 | | Wei Guo |
| 3 | Cultural Resources | Katie Owston |
| 4 | | Phil Kennedy |
| 5 | | <u>Davey Dobbs</u> |
| 6 | Environmental Justice | Katie Owston |
| 7 | | Gwen Pelletier |
| 8 | Geology | Juan Ramirez |
| 9 | | Katie Owston |
| 10 | | <u>Davey Dobbs</u> |
| 11 | Groundwater and Soils | Katie Owston |
| 12 | | Sibel Tekce |
| 13 | | <u>Davey Dobbs</u> |
| 14 | Hazards and Hazardous Materials | Hari Gupta |
| 15 | | Juan Ramirez |
| 16 | | <u>Davey Dobbs</u> |
| 17 | Land Use | Katie Owston |
| 18 | Marine Transportation | Katie Owston |
| 19 | | <u>Davey Dobbs</u> |
| 20 | Noise | Juan Ramirez |
| 21 | Recreation | Juan Ramirez |
| 22 | | <u>Davey Dobbs</u> |
| 23 | Public Services and Utilities | Juan Ramirez |
| 24 | | Katie Owston |
| 25 | | <u>Davey Dobbs</u> |
| 26 | Socioeconomics | Katie Owston |
| 27 | Water Quality, Sediments and Oceanography | Don Schroeder, P.E. |
| 28 | <u>Miscellaneous Chapters and Support</u> | <u>Drew Poulter</u> |
| 29 | | |

Changes Made to Appendix E.1, Construction Emissions

Appendix E1 is a compilation of construction emission worksheets that are generated from air quality modeling efforts. Due to the nature of the model and output tables, the revisions cannot be shown in the typical revision-mode text (i.e., deletions are shown with ~~strikethrough~~ and additions are shown with underline). The corrections provided in the attached construction emission tables are shown in **bold/underline**. Please refer to Appendix E1 of the Draft EIS/EIR for original information.

The following tables have been included in their entirety; however, on the noted pages have been revised:

- **Table 1.1-4, Pages 17 and 18 of 61**
- **Table 1.1-5, Page 25 of 61**
- **Table 1.1-11, Page 37 of 61**
- **Table 1.1-17, Page 43 of 61**
- **Table 1.1-22, Page 48 of 61**
- **Table 1.1-24, Page 50 of 61**
- **Table 1.1-26, Page 52 of 61**
- **Table 1.1-28, Page 54 of 61**

1
2
3

INSERT PDF's OF REVISED TABLES (23 pages) ... I'll add slip pages when we final

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

In addition, to clarify, in Table 1.7.3 of Appendix E1, the term “Near Dock” should be considered “Near Dock/Off-Dock” as the trips represented consider the ICTF railyard located approximately 5 miles from the Project site, as well as the BNSF railyard in Los Angeles located approximately 18 miles from the Project site.

Changes Made to Appendix F3, Essential Fish Habitat Assessment, APL Terminal Project, EFH Analysis

Section 5.2.1, Pages 15 to 17

Coastal Pelagics

Two coastal pelagics—northern anchovy and Pacific sardine—are likely to occur in the vicinity of the proposed Project. As summarized in Section 4, northern anchovy is among the most common and abundant fish species in the Port Complex. In 2006, larvae were present in the Port Complex during two seasonal periods, a greater peak in March-July and a lesser peak in October-December (MBC et al., 2007). Juvenile and adult anchovies have consistently been collected during fish sampling near the proposed project site (MEC and Associates, 2002; SAIC, 2010). Northern anchovy are found from the surface to depths of 1,017 ft (310 m), though juveniles are generally more common inshore and in estuaries (Davies and Bradley, 1972).

Table 1. Managed adult fish/invertebrate species ~~potentially occurring~~found in Los Angeles Harbor based on past occurrences.

| Common Name | Potential Habitat Use | Larval Occurrence ^{1,2,4} | |
|---|---|------------------------------------|--|
| | | Larval Occurrence ^{1,2,4} | Juv./Adult Occurrence ^{2,3,4,5} |
| Coastal Pelagics | | | |
| northern anchovy (<i>Engraulis mordax</i>) | Open water. | Abundant | Abundant |
| Pacific sardine (<i>Sardinops sagax</i>) | Open water. | Uncommon | Common |
| Pacific (chub) mackerel (<i>Scomber japonicus</i>) | Open water, juveniles off sandy beaches and around kelp beds. | - | Uncommon |
| jack mackerel (<i>Trachurus symmetricus</i>) | Open water, young fish over shallow banks and juveniles around kelp beds. | Rare | Uncommon |
| market squid (<i>Doryteuthis opalescens</i>) | Open water. Rare near bays, estuaries, and river mouths. | Rare | - |
| Pacific Groundfish | | | |
| English sole (<i>Parophrys vetulus</i>) | Soft bottom habitats. | Rare | Uncommon |
| Pacific sanddab (<i>Citharichthys sordidus</i>) | Soft bottom habitats. | Rare | Common |
| butter sole (<i>Isopsetta isolepis</i>) | Soft bottom habitats. | Rare | - |

| | | | |
|---|---|----------------|-----------------|
| black rockfish (<i>Sebastes melanops</i>) | Along breakwater, near deep piers and pilings. Associated with kelp, eelgrass, high relief reefs. | - | Rare |
| bocaccio (<i>Sebastes paucispinis</i>) | Multiple habitat associations, including soft and hard bottom, kelp, eelgrass, etc. | - | Rare |
| brown rockfish (<i>Sebastes auriculatus</i>) | Multiple habitat associations but prefer hard substrata and rocky interfaces. | - | Rare |
| calico rockfish (<i>Sebastes dallii</i>) | Multiple habitat associations but prefer hard substrata and rocky interfaces. | - | Rare |
| California scorpionfish (<i>Scorpaena guttata</i>) | Benthic, on soft and hard bottoms, as well as around structures. | - | Uncommon |
| grass rockfish (<i>Sebastes rastrelliger</i>) | Common on hard substrate, kelp, and eelgrass habitats. | - | Rare |
| kelp rockfish (<i>Sebastes atrovirens</i>) | Common on hard substrate, kelp; reported along breakwater. | - | Rare |
| olive rockfish (<i>Sebastes serranoides</i>) | Common around hard substrate, kelp; reported along breakwater. | - | Rare |
| vermillion rockfish (<i>Sebastes miniatus</i>) | Juveniles over soft-bottom and kelp, adults associated with hard substrate. | - | Uncommon |
| lingcod (<i>Ophiodon elongatus</i>) | Multiple habitat associations but prefer hard substrata and rocky interfaces. | - | Rare |
| cabezon (<i>Scorpaenichthys marmoratus</i>) | Multiple habitat associations but prefer hard substrata and rocky interfaces. | Rare | Rare |
| Pacific hake (<i>Merluccius productus</i>) | Common offshore, juveniles in open water. | Rare | - |
| leopard shark (<i>Triakis semifasciata</i>) | Multiple habitat associations, including soft bottoms, and near structure, kelp, and eelgrass. | N/A | Rare |
| spiny dogfish (<i>Squalus acanthias</i>) | Pelagic and on muddy bottoms. | N/A | Rare |
| big skate (<i>Raja binoculata</i>) | Soft bottom habitat. | N/A | Rare |
| California skate (<i>Raja inornata</i>) | Soft bottom habitat. | N/A | Uncommon |
| Sources: 1 – MBC et al. (2007), 2 – MEC and Associates (2002), 3 – MBC (2009a,b), 4 – SAIC (2010), 5 – MEC (1999). N/A = Not applicable, internal fertilization. Abundant>Common>Uncommon>Rare. Note - Most rockfish larvae not identifiable to species. | | | |

1
2 Pacific sardine were not abundant during 2006 ichthyoplankton sampling throughout the
3 Port Complex; two sardine larvae were collected in the Outer Harbor in April 2006
4 (MBC et al., 2007). This species is also found less frequently than northern anchovy near
5 the project site (MEC and Associates, 2002; SAIC, 2010). Pacific sardine is epipelagic,
6 occurring in loosely aggregated schools (Wolf et al., 2001). Jack mackerel and Pacific
7 mackerel have been collected in Los Angeles Harbor, but in much lower frequency and
8 numbers than northern anchovy and Pacific sardine. ~~While no mature market squid have~~
9 ~~been reported in recent surveys, market squid paralarvae were collected in Inner and~~
10 ~~Outer Harbor areas in 2006 (MBC et al., 2007). All coastal pelagics are associated with~~
11 ~~the water column (as opposed to the seafloor like many of the groundfish); however,~~
12 ~~female squid also lay egg masses on sandy bottoms during spawning (at depths of about~~
13 ~~16-180 ft [5-55 m], with most occurring between 66-115 ft [20-35 m]) (PFMC, 2008a).~~

1 *This page left intentionally blank*

CONTENTS

| | | |
|------------------|--|------------|
| Chapter 1 | Introduction..... | 1-1 |
| 1.1 | Final EIS/EIR Organization | 1-1 |
| 1.2 | Project Background..... | 1-1 |
| 1.3 | Existing Conditions | 1-4 |
| 1.3.1 | Regional Context..... | 1-4 |
| 1.3.2 | Project Setting | 1-4 |
| 1.3.3 | Project Site and Surrounding Uses | 1-4 |
| 1.3.4 | Historic Use of the Project Site | 1-6 |
| 1.4 | Project Purpose | 1-8 |
| 1.4.1 | CEQA Objectives | 1-9 |
| 1.4.2 | NEPA purpose and Need..... | 1-10 |
| 1.4.3 | Federal Scope of Analysis | 1-10 |
| 1.5 | Proposed Project | 1-12 |
| 1.5.1 | Project Elements..... | 1-15 |
| 1.5.2 | Project Construction..... | 1-26 |
| 1.6 | Port of Los Angeles Environmental Initiatives..... | 1-39 |
| 1.6.1 | Port Environmental Policy | 1-40 |
| 1.6.2 | Environmental Plans and Programs..... | 1-40 |
| 1.6.3 | Port of Los Angeles Leasing Policy..... | 1-46 |
| 1.6.4 | Port Community Advisory Committee | 1-46 |
| 1.7 | Changes to the Draft EIS/EIR | 1-47 |
| 1.8 | References | 1-47 |
| 1.8-1 | Printed References | 1-47 |
| Chapter 2 | Response to Comments | 2-1 |
| 2.1 | Distribution of the Draft EIS/EIR | 2-1 |
| 2.2 | Comments on the Draft EIS/EIR | 2-2 |
| 2.3 | Responses to Comments | 2-3 |
| 2.3.1 | Federal Government | 2-17 |
| 2.3.2 | State Government | 2-57 |
| 2.3.3 | Local Government..... | 2-111 |
| 2.3.4 | Organizations..... | 2-124 |
| 2.3.5 | Individuals/Companies..... | 2-216 |
| 2.3.6 | Draft EIS/EIR Public Hearing | 2-271 |
| 2.4 | References | 2-272 |

Chapter 3 Modifications to the Draft EIS/EIR..... 3-1
Introduction 3-1
Changes to the Draft EIS/EIR..... 3-2
 Changes Made to Executive Summary..... 3-2
 Changes Made to Chapter 1, Introduction 3-6
 Changes Made to Chapter 2, Project Description..... 3-6
 Changes Made to Section 3.2, Air Quality, Meteorology and
 Greenhouse Gases..... 3-8
 Changes Made to Section 3.3, Biological Resources 3-16
 Changes Made to Chapter 11, List of Preparers and
 Contributors 3-25
 Changes Made to Appendix E.1, Construction Emissions..... 3-27
 Changes Made to Appendix F3, Essential Fish Habitat
 Assessment, APL Terminal Project, EFH Analysis..... 3-50

TABLES

Table 1-1: Berths 302-306 [APL] Container Terminal Construction Phasing..... 1-26
Table 1-2: Project Throughput Comparison..... 1-32

FIGURES

Figure 1-1: Project Site and Vicinity 1-3
Figure 1-2: Regional Location Map 1-5
Figure 1-3: Project Site-Existing Conditions Buildings 1-7
Figure 1-4: USACE Scope of Federal Review 1-13
Figure 1-5: Proposed Project 1-14
Figure 1-6: Proposed Layout-Sections..... 1-24
Figure 1-7: Landside Transfer Area 1-25

This page left intentionally blank