

DISTRIBUTION LIST

Jon Petke
The Planning Associates
3151 Airway Avenue, Suite R-1
Costa Mesa, CA 92626

Oscar Balaguer
State Water Resources Control Board
Division of Water Quality
P.O. Box 944213
Sacramento, CA 94244-2130

Betty Courtney
California Department of Fish and Game
Streambed Alteration Team
4949 View Ridge Avenue
San Diego, CA 92123

Kenneth Wong
U.S. Army Corps of Engineers
Regulatory Branch, Los Angeles District
P.O. Box 532711
Los Angeles, CA 90053-2325

Eric Raffini
U.S. Environmental Protection Agency
600 Wilshire Boulevard, Suite 1460
Los Angeles, CA 90017

Tim Vendlinski
Supervisor, Wetlands Regulatory Office (WTR-8)
US EPA, Region 9
75 Hawthorne
San Francisco, CA 94105

Ken Berg
U.S. Fish and Wildlife Service
6010 Hidden Valley Road
Carlsbad, CA 92009

ATTACHMENT A

Project Information File No. 05-176

1. Applicant: Mr. Bob Yurosek
Toll Brothers Incorporation
725 Town and Country Road
Orange, CA 92868

Phone: (805) 532-2891 Fax: (805) 532-1459

2. Applicant's Agent: Jon Petke
The Planning Associates
3151 Airway Avenue. Suite R-1
Costa Mesa, CA 92626

Phone: (714) 556-5200 Fax: (714) 556-3905

3. Project Name: Tapia Ranch North Tributary Access Road

4. Project Location: Castaic, Los Angeles County
Longitude: 118° 35' 58"; Latitude: 34° 28' 55"

5. Type of Project: Repair Access Road

6. Project Purpose: The proposed project (Project) will repair Tapia Ranch North Tributary Access Road (Road) damaged by the winter 2005 storms, and return the Road to conditions existing prior to the storms.

7. Project Description: The roads in Tapia Ranch are used by both the private and public sectors. Livestock management, oil extraction facilities, upstream property owners, the Los Angeles County Fire and Sheriff Departments depend on the dirt roads.

The impact of the minor repair work proposed to the Road that roughly parallels Tapia Canyon Road, running roughly northeast alongside an unnamed tributary to Tapia Creek and providing the primary access to the northwest area of the property is as follows:

A jurisdictional delineation of Tapia Ranch identified the width of

ATTACHMENT A

Project Information File No. 05-176

the stream for Army Corps of Engineering purposes as being between 2 and 34 feet. The Project will be designed to avoid the primary jurisdictional flow line and to limit the number of crossings of this stream to the two crossings made by the previous road. A typical width for the dirt roads on the property is 12 to 16 feet. This will be narrowed to 12 feet at the stream crossings to minimize any impact on the waters of the United States. At a maximum, the Project will affect 0.019 acres (816 square feet; two crossings, 34 feet by 12 feet). The same best management practices used by the Los Angeles County Fire Department in the repair of work of Tapia Creek Road will be incorporated for the Tapia Ranch North Tributary Road remediation work.

- | | |
|--|--|
| 8. Federal Agency/Permit: | U.S. Army Corps of Engineers
NWP No. 3 (Permit No. 2005-01744-KW) |
| 9. Other Required Regulatory Approvals: | California Department of Fish and Game
Streambed Alteration Agreement |
| 10. California Environmental Quality Act Compliance: | The proposed project is Categorical Exempt from CEQA pursuant to the CEQA Guidelines, Section 15304 (Minor Alterations to Land). |
| 11. Receiving Water: | Castaic Creek (Hydrologic Unit No. 403.51) |
| 12. Designated Beneficial Uses: | MUN, IND, PROC, AGR, GWR, FRSH, REC-1, REC-2, WARM, WILD, RARE |
| 13. Impacted Waters of the United States: | Non-wetland waters (streambed): 0.019 temporary acres (68 temporary linear feet) |
| 14. Dredge Volume: | None |

ATTACHMENT A

Project Information File No. 05-176

15. Related Projects Implemented/to be Implemented by the Applicant: The Applicant has not identified any related projects carried out in the last 5 years or planned for implementation in the next 5 years.
16. Avoidance/Minimization Activities: The Applicant has proposed to implement several Best Management Practices, including, but not limited to, the following:
- Use native soil dip crossings wherever practical, and only restore corrugated pipe crossings where feasible.
 - Relocate native soil, rocks, and boulders in remediating and protecting road from the restored ephemeral stream.
 - Use contour and sheet flow grading techniques to minimize concentration of natural runoff patterns and optimize natural drainage patterns in the ravines and native washes; and
 - Use native seed mix hand broadcast at appropriate times during rainy season and/ or natural recruitment of native landscape species in the reconstructed flowline.
17. Proposed Compensatory Mitigation: The Applicant has proposed to enhance 0.71 acres of streambed (3.74:1 ratio) onsite.
18. Required Compensatory Mitigation: The Applicant shall provide compensatory mitigation to offset the proposed temporal loss of 0.019 acres waters of the United States by enhancing riparian habitat at a minimum 37.4:1 area replacement ratio (0.71 acres). See Items 22 through 24 of Attachment B for the description of mitigation requirements.
- See Attachment B Conditions of Certifications, Additional Conditions for modifications and additions to the above proposed compensatory mitigation.*

ATTACHMENT B

Conditions of Certification File No. 05-176

STANDARD CONDITIONS

Pursuant to §3860 of Title 23 of the California Code of Regulations (23 CCR), the following three standard conditions shall apply to this project:

1. This Certification action is subject to modification or revocation upon administrative or judicial review, including review and amendment pursuant to §13330 of the California Water Code and Article 6 (commencing with 23 CCR §3867).
2. This Certification action is not intended and shall not be construed to apply to any activity involving a hydroelectric facility and requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent Certification application was filed pursuant to 23 CCR Subsection 3855(b) and the application specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.
3. Certification is conditioned upon total payment of any fee required pursuant to 23 CCR Chapter 28 and owed by the Applicant.

ADDITIONAL CONDITIONS

Pursuant to 23 CCR §3859(a), the Applicant shall comply with the following additional conditions:

1. The Applicant shall submit to this Regional Board copies of any other final permits and agreements required for this project, including, but not limited to, the U.S. Army Corps of Engineers' (ACOE) Section 404 Permit and the California Department of Fish and Game's (CDFG) Streambed Alteration Agreement. **These documents shall be submitted prior to any discharge to waters of the State.**
2. The Applicant shall adhere to the most stringent conditions indicated with either this certification, the CDFG's Streambed Alteration Agreement, or the ACOE Section 404 Permit.
3. The Applicant shall comply with all water quality objectives, prohibitions, and policies set forth in the *Water Quality Control Plan, Los Angeles Region (1994)*.
4. The Avoidance/Minimization activities proposed by the Applicant as described in Attachment A, No. 15, are incorporated as additional conditions herein.
5. The Applicant and all contractors employed by the Applicant shall have copies of this Certification, the approved maintenance plan, and all other regulatory approvals for this

ATTACHMENT B

Conditions of Certification File No. 05-176

project on site at all times so that all project personnel are familiar with all applicable conditions set forth.

6. Fueling, lubrication, maintenance, operation, and storage of vehicles and equipment shall not result in a discharge or a threatened discharge to waters of the State. At no time shall the Applicant use any vehicle or equipment which leaks any substance that may impact water quality. Staging and storage areas for vehicles and equipment shall be located outside of waters of the State.
7. All excavation, construction, or maintenance activities shall follow best management practices to minimize impacts to water quality and beneficial uses. Dust control activities shall be conducted in such a manner that will not produce downstream runoff.
8. No construction material, spoils, debris, or any other substances associated with this project that may adversely impact water quality standards, shall be located in a manner which may result in a discharge or a threatened discharge to waters of the State. Designated spoil and waste areas shall be visually marked prior to any excavation and/or construction activity, and storage of the materials shall be confined to these areas.
9. All waste and/or dredged material removed shall be relocated to a legal point of disposal if applicable. A legal point of disposal is defined as one for which Waste Discharge Requirements have been established by a California Regional Water Quality Control Board, and is in full compliance therewith. Please contact Rodney Nelson, Land Disposal Unit, at (213) 620-6119 for further information.
10. The Applicant shall implement all necessary control measures to prevent the degradation of water quality from the proposed project in order to maintain compliance with the Basin Plan. The discharge shall meet all effluent limitations and toxic and effluent standards established to comply with the applicable water quality standards and other appropriate requirements, including the provisions of Sections 301, 302, 303, 306, and 307 of the Clean Water Act. This Certification does not authorize the discharge by the applicant for any other activity than specifically described in the 404 Permit.
11. The discharge shall not: a) degrade surface water communities and populations including vertebrate, invertebrate, and plant species; b) promote the breeding of mosquitoes, gnats, black flies, midges, or other pests; c) alter the color, create visual contrast with the natural appearance, nor cause aesthetically undesirable discoloration of the receiving waters; d) cause formation of sludge deposits; or e) adversely affect any designated beneficial uses.
12. The Applicant shall allow the Regional Board and its authorized representative entry to the premises, including all mitigation sites, to inspect and undertake any activity to determine compliance with this Certification, or as otherwise authorized by the California Water Code.

ATTACHMENT B

Conditions of Certification File No. 05-176

13. Application of pesticides must be supervised by a certified applicator and be in conformance with manufacturer's specifications for use. Compounds used must be appropriate to the target species and habitat. All pesticides directed toward aquatic species must be approved by the Regional Board. Pesticide utilization shall be in accordance with State Water Resources Control Board Water Quality Order Nos. 2004-0008-DWQ and 2004-0009-DWQ.
14. The Applicant shall not conduct any construction activities within waters of the State during a rainfall event. The Applicant shall maintain a **five-day (5-day) clear weather forecast** before conducting any operations within waters of the State.
15. The Applicant shall not conduct any maintenance activities within waters of the State during a rainfall event, or at any period when site conditions would lead to excessive erosion. If any maintenance activities are to be held within five (5) days of a predicted rainfall event, the Applicant shall stage materials necessary to prevent water degradation on site, and shall ensure that all stabilization procedures are completed prior to the rainfall event.
16. If rain is predicted after operations have begun, grading activities must cease immediately and the site must be stabilized to prevent impacts to water quality, and minimize erosion and runoff from the site.
17. Sediment removal at each phase shall not go beyond the extent as defined in the application packet.
18. The grading, stabilization and re-vegetation will be phased to limit the exposed or working face such that the graded area can be stabilized within 24 hours after the first prediction of rain during the 5-day forecast or within 24 hours after final grading of the phased area.
19. No activities shall involve wet excavations (i.e., no excavations shall occur below the seasonal high water table). A minimum **5-foot** buffer zone shall be maintained above the existing groundwater level. If construction or groundwater dewatering is proposed or anticipated, the Applicant shall file a **Report of Waste Discharge** to this Regional Board and obtain any necessary NPDES permits/Waste Discharge Requirements prior to discharging waste. Sufficient time should be allowed to obtain any such permits (generally 180 days). If groundwater is encountered without the benefit of appropriate permits, the Applicant shall cease all activities in the areas where groundwater is present, file a Report of Waste Discharge to this Regional Board, and obtain any necessary permits prior to discharging waste.
20. All project, construction, or maintenance activities not included in this Certification, and which may require a permit, must be reported to the Regional Board for appropriate

ATTACHMENT B

Conditions of Certification File No. 05-176

permitting. Bank stabilization and grading, as well as any other ground disturbances, are subject to restoration and revegetation requirements, and may require additional Certification action.

21. All surface waters, including ponded waters, shall be diverted away from areas undergoing grading, construction, excavation, vegetation removal, and/or any other activity which may result in a discharge to the receiving water. If surface water diversions are anticipated, the Applicant shall develop and submit a **Surface Water Diversion Plan** (plan) to this Regional Board. The plan shall include the proposed method and duration of diversion activities, structure configuration, construction materials, equipment, erosion and sediment controls, and a map or drawing indicating the locations of diversion and discharge points. Contingency measures shall be a part of this plan to address various flow discharge rates. The plan shall be submitted prior to any surface water diversions. If surface flows are present, then upstream and downstream monitoring for the following shall be implemented:
 - pH
 - temperature
 - dissolved oxygen
 - turbidity
 - total suspended solids(TSS)
 - Downstream TSS shall be maintained at ambient levels
 - Where natural turbidity is between 0 and 50 Nephelometric Turbidity Units (NTU), increases shall not exceed 20%. Where natural turbidity is greater than 50 NTU, increases shall not exceed 10%.

Analyses must be performed using approved US Environmental Protection Agency methods, where applicable. These constituents shall be monitored for on a daily basis during the first week of diversion and/or dewatering activities, and then on a weekly basis, thereafter, until the in-stream work is complete.

Results of the analyses shall be submitted to this Regional Board by the 15th day of each subsequent sampling month. A map or drawing indicating the locations of sampling points shall be included with each submittal. Diversion activities shall not result in the degradation of beneficial uses or exceedance of water quality objectives of the receiving waters. Any such violations may result in corrective and/or enforcement actions, including increased monitoring and sample collection.

22. The Applicant shall restore the proposed **0.019 acres** of TEMPORARY IMPACTS to waters of the United States and all other areas of temporary disturbance which could result in a discharge or a threatened discharge to waters of the State. Restoration shall include grading of disturbed areas to pre-project contours and revegetation with native species. The Applicant shall implement all necessary Best Management Practices to control erosion and runoff from areas associated with this project.

ATTACHMENT B

Conditions of Certification File No. 05-176

23. The Applicant shall provide COMPENSATORY MITIGATION to offset the proposed temporal loss of **0. 019 acres** waters of the United States by enhancing riparian habitat at a minimum **37.4:1** area replacement ratio (**0.71** acres) as described in 2.c) of the revised 401 Application submitted to this Regional Board April 28, 2006.
24. The Applicant shall submit to this Regional Board **Annual Mitigation Monitoring Reports** by **January 1st** of each year for a minimum period of **five (5) years** after planting or until mitigation success has been achieved. The report shall describe in detail all of the project/construction activities performed during the previous year and all restoration and mitigation efforts; including percent survival by plant species and percent cover. This report shall include as a minimum, the following documentation:
 - (a) Color photo documentation of the pre- and post-project and mitigation site conditions;
 - (b) Geographical Positioning System (GPS) coordinates in decimal-degrees format outlining the boundary of the project and mitigation areas;
 - (c) The overall status of project including a detailed schedule of work;
 - (d) Copies of all permits revised as required in Additional Condition 1;
 - (e) Water quality monitoring results for each reach (as required) compiled in an easy to interpret format;
 - (f) A certified Statement of “no net loss” of wetlands associated with this project;
 - (g) Discussion of any monitoring activities and exotic plant control efforts; and
 - (h) A certified Statement from the permittee or his/her representative that all conditions of this Certification have been met.
25. Prior to any subsequent maintenance activities within the subject drainages, including clearing, maintenance by-hand, and/or the application of pesticides, the Applicant shall submit to this Regional Board a NOTIFICATION of any such activity. Notification shall include: (a) the proposed schedule; (b) a description of the drainage’s existing condition and/or capacity; (c) the area of proposed temporary impact within waters of the State; (c) a description of any existing aquatic resources (e.g., wetland/riparian vegetation); and (d) any proposed compensatory mitigation. Notifications must be submitted a minimum of **three (3) weeks** prior to commencing work activities.
26. All applications, reports, or information submitted to the Regional Board shall be signed:

ATTACHMENT B

**Conditions of Certification
File No. 05-176**

- (a) For corporations, by a principal executive officer at least of the level of vice president or his duly authorized representative, if such representative is responsible for the overall operation of the facility from which discharge originates.
 - (b) For a partnership, by a general partner.
 - (c) For a sole proprietorship, by the proprietor.
 - (d) For a municipal, State, or other public facility, by either a principal executive officer, ranking elected official, or other duly authorized employee.
27. Each and any report submitted in accordance with this Certification shall contain the following completed declaration:

“I declare under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who managed the system or those directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Executed on the _____ day of _____ at _____.

_____ (Signature)
_____ (Title)”

- 28. All communications regarding this project and submitted to this Regional Board shall identify the Project File Number **05-176**. Submittals shall be sent to the attention of the Nonpoint Source Unit.
- 29. Any modifications of the proposed project may require submittal of a new Clean Water Act Section 401 Water Quality Certification application and appropriate filing fee.
- 30. The project shall comply with the local regulations associated with the Regional Board’s **Municipal Stormwater Permit** issued to Los Angeles County and co-permittees under NPDES No. CAS004001 and Waste Discharge Requirements Order No. 01-182. This includes the Standard Urban Storm Water Mitigation Plan (SUSMP) and all related implementing local ordinances and regulations for the control of stormwater pollution from new development and redevelopment. The project shall also comply with all requirements of the National Pollutant Discharge Elimination System (NPDES) **General Permit** for

ATTACHMENT B

Conditions of Certification File No. 05-176

Storm Water Discharges Associated with Construction Activity, Order No. 99-08-DWQ. All stormwater treatment systems shall be located outside of any water of the State and shall not be used as a wetland or riparian mitigation credit.

31. Coverage under this Certification may be transferred to the extent the underlying federal permit may legally be transferred and further provided that the Applicant notifies the Executive Officer at least 30 days before the proposed transfer date, and the notice includes a written agreement between the existing and new Applicants containing a specific date of coverage, responsibility for compliance with this Certification, and liability between them.
32. The Applicant or their agents shall report any noncompliance. Any such information shall be provided verbally to the Executive Officer within 24 hours from the time the Applicant becomes aware of the circumstances. A written submission shall also be provided within five days of the time the Applicant becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected; the anticipated time it is expected to continue and steps taken or planned to reduce, eliminate and prevent recurrence of the noncompliance. The Executive Officer, or an authorized representative, may waive the written report on a case-by-case basis if the oral report has been received within 24 hours.
33. *Enforcement:*
 - (a) In the event of any violation or threatened violation of the conditions of this Certification, the violation or threatened violation shall be subject to any remedies, penalties, process or sanctions as provided for under State law. For purposes of section 401(d) of the Clean Water Act, the applicability of any State law authorizing remedies, penalties, process or sanctions for the violation or threatened violation constitutes a limitation necessary to assure compliance with the water quality standards and other pertinent requirements incorporated into this Certification.
 - (b) In response to a suspected violation of any condition of this Certification, the State Water Resources Control Board (SWRCB) or Regional Water Quality Control Board (RWQCB) may require the holder of any permit or license subject to this Certification to furnish, under penalty of perjury, any technical or monitoring reports the SWRCB deems appropriate, provided that the burden, including costs, of the reports shall be a reasonable relationship to the need for the reports and the benefits to be obtained from the reports.
 - (c) In response to any violation of the conditions of this Certification, the SWRCB or RWQCB may add to or modify the conditions of this Certification as appropriate to ensure compliance.

ATTACHMENT B

Conditions of Certification

File No. 05-176

34. This Certification shall expire **five (5) years** from date of this Certification. The Applicant shall submit a complete application prior to termination of this Certification if renewal is requested.