



Linda S. Adams
Secretary for
Environmental Protection

**California Regional Water Quality Control Board
North Coast Region
Geoffrey M. Hales, Chairman**

www.waterboards.ca.gov/northcoast
5550 Skylane Boulevard, Suite A, Santa Rosa, California 95403
Phone: (877) 721-9203 (toll free) • Office: (707) 576-2220 • FAX: (707) 523-0135



Arnold
Schwarzenegger
Governor

March 15, 2010

In the Matter of
Water Quality Certification
For the
City of Healdsburg West Grant Street Sidewalk
And Bridge Improvements Project

APPLICANT: Mr. Scott Rodolph, City of Healdsburg
RECEIVING WATER: Foss Creek
HYDROLOGIC UNIT: Warm Springs Hydrologic Sub Area No. 114.24, Russian
River Hydrologic Unit No. 114.00
COUNTY: Sonoma
FILE NAME: Healdsburg West Grant Street Sidewalk & Bridge
Improvements
WDID No. 1B09066WNSO

BY THE EXECUTIVE OFFICER:

1. On May 26, 2009, the North Coast Regional Water Quality Control Board (Regional Water Board) received an application from Ms. Lucy Macmillan, on behalf of Mr. Scott Rodolph of the City of Healdsburg (Applicant), for water quality certification (certification) under section 401 of the Clean Water Act (33 U.S.C. § 1341) with the California Regional Water Quality Control Board, North Coast Region (Regional Water Board) for activities related to the West Grant Street Sidewalk and Bridge Improvements Project (Project), located in Sonoma County. The Project will cause permanent impacts to approximately 0.026 acres of waters of the State associated with banks and bed of Foss Creek in the Warm Springs Hydrologic Sub Area No. 114.24, Russian River Hydrologic Unit No. 114.00. Total fees in the amount of \$723 have been received. The Regional Water Board provided public notice of the application pursuant to title 23, California Code of Regulations, section 3858 on October 15, 2009, and posted information describing the Project on the Regional Water Board's website. One public comment was received, which was considered and addressed with an improvement to the compensatory mitigation for the Project.
2. The Project is located at the bridge of West Grant Street over Foss Creek , Healdsburg, CA, latitude 38.615803° N and longitude 122.873363° W.

California Environmental Protection Agency

Recycled Paper

3. The purpose of the project is to accommodate safe pedestrian access over Foss Creek by widening West Grant Street for a length of approximately 40 feet at the culvert crossing as part of the Safe Routes to School program.
4. The Applicant will temporarily divert the flow of Foss Creek by use of a pump and cofferdam, in order to dewater the work area during construction. The cofferdam will be installed at the northern limit of the work area and water will be released or pumped downstream at an appropriate rate to maintain downstream flows during construction. The section of the road to be widened would include curb, gutter and sidewalk along both sides of the street, pedestrian safety railings at the back of the sidewalks, a new 12-inch water main connection hung from the top section of the new section of box culvert on the south side, and a new street width of 40 feet. The newly widened roadway would match existing sections of West Grant Street to the east and west. The Applicant will extend the culvert approximately 10 feet to the north and 20 feet to the south, adjoining the existing structure. Reinforced concrete box extensions and bridge deck will be constructed, adjoining and matching the dimensions of the existing structure. New wing walls on continuous spread footings will connect from the extension walls into the existing creek bank. Additionally, several large chunks of concrete and old pipes will be removed from the base of the creek banks which will allow vegetation to reestablish along the base of the creek banks.
5. Compensatory mitigation will consist of planting of native vegetation along both sides of an approximately 700 foot long drainage channel that parallels Foss Creek, south of the bridge construction at West Grant Street, as detailed in the "Mitigation Planting Plan, West Grant Street Safe Routes to School Sidewalk & Bridge Widening Project, City of Healdsburg", prepared by Circuit Rider Productions, Inc., dated July 22, 2009. The channel drains to Norton Slough and then to Foss Creek. Native shrubs, (78) Coyote Bush (*Baccharis pilularis cons.*) and (17) Blue Elderberry (*Sambucus mexicana*), as well as (15) Red Willow trees (*Salix leevigata*) will be planted within this area. Irrigation will be provided as necessary. The mitigation area will be monitored and maintained for five years. Annual reports will be submitted to the Regional Water Board by December 31 after the first year of planting and shall continue for five years or longer, until survival of planted vegetation is at least 85%. Annual monitoring reports shall include photos of the revegetated areas, and include survival rates and a narrative summary of the status of the revegetation/mitigation effort. Continued maintenance of these facilities shall be the responsibility of the Applicant.
6. Non-compensatory mitigation measures include the use of Best Management Practices (BMPs) to be employed during construction to minimize sediment production and prevent the movement of loose soil off-site. Ground disturbance will be limited to the minimum necessary and all disturbed ground will be treated with native grass seed, or native grass plugs, or other erosion control measures. Hydro-mulching shall not be used within the creek top-of-bank, or in areas where it

may wash into the creek. Silt fences, silt curtains and straw bales will be used to avoid delivery of sediment into sensitive areas during construction. All erosion control measures will be installed and in place by October 15 and maintained thereafter by the contractor/Applicant. Additionally, all required BMPs shall be on-site and ready for timely deployment before the start of construction activities.

7. The City of Healdsburg Community Development Center, as lead California Environmental Quality Act (CEQA) agency, submitted a Mitigated Negative Declaration to the State Clearinghouse (SCH No. 2003052025) on June 16, 2003, pursuant to CEQA guidelines.
8. This discharge is also regulated under State Water Resources Control Board Order No. 2003-0017-DWQ, "General Waste Discharge Requirements for Dredge and Fill Discharges That Have Received State Water Quality Certification," which requires compliance with all conditions of this water quality certification.

Receiving Water: Lake Sonoma in the Warm Springs Hydrologic Sub Area
No. 114.24, Russian River Hydrologic Unit No. 114.00

Filled or Excavated Area: Area permanently impacted: 0.026 acres of Creek bed and
bank

Latitude/Longitude: 38.615803° N / 122.873363° W

Expiration: March 4, 2015

Accordingly, based on its independent review of the record, the Regional Water Board certifies that the City of Healdsburg West Grant Street Sidewalk and Bridge Improvements Project, (WDID No. 1B09066WNSO), as described in the application, will comply with sections 301, 302, 303, 306 and 307 of the Clean Water Act, and with applicable provisions of state law, provided that the Applicant complies with the following terms and conditions:

1. This certification action is subject to modification or revocation upon administrative or judicial review; including review and amendment pursuant to Water Code section 13330 and title 23, California Code of Regulations, section 3867.
2. This certification action is not intended and shall not be construed to apply to any discharge from any activity involving a hydroelectric facility requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent certification application was filed pursuant to title 23, California Code of Regulations, section 3855, subdivision (b) and the application specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.

3. This certification is conditioned upon total payment of any fee required under title 23, California Code of Regulations, section 2200, and owed by the Applicant.
4. This discharge is also regulated under State Water Resources Control Board Order No. 2003-0017-DWQ, "General Waste Discharge Requirements for Dredge and Fill Discharges That Have Received State Water Quality Certification" which requires compliance with all conditions of this Order (Enclosed).
5. The Russian River is identified as impaired on the Clean Water Act Section 303(d) list. The Russian River is listed as impaired for sediment and temperature. At present, total maximum daily loads (TMDLs) have not been established for this water body. If TMDLs are established and implementation plans are adopted for this watershed prior to the expiration date of this Order, the Regional Water Board may revise the provisions of this Order to address actions identified in such action plans.
6. The Applicant shall not discharge any water from the water main (or from any other utility pipe) involved in this project, to Foss Creek, or to other waters of the State.
7. If dewatering in the construction area is necessary, water shall not be discharged back to the creek. Dewatering water shall be pumped to a storage tank, or other conveyance, and be disposed of properly. Dewatering water shall not be discharged to waters of the State.
8. Poured concrete shall be isolated from the wetted channel for at least 30 days after it is poured. Sealants may be used and water shall be excluded until sealants are dry and until no detrimental impacts to water quality shall occur to the creek due to water contact with sealed surfaces. Water contacting the concrete within the 30 day period after the concrete after it is poured shall not be discharged back to the creek and must be pumped to a storage tank or other conveyance and disposed of properly.
9. Work within the creek corridor will be confined to between June 15th and October 15th. Vegetation may be planted at any time.
10. Applicant shall prioritize use of wildlife-friendly 100% biodegradable erosion control products/BMPs wherever feasible. For purposes of this Order, photodegradable synthetic products are not considered biodegradable. Applicant shall not use or allow the use of erosion control products, that contain synthetic (e.g., plastic or nylon) netting or materials for permanent erosion control (i.e., erosion control materials to be left in place for two years or after the completion date of the project). If the Applicant finds that erosion control netting or products have entrapped or harmed wildlife, the Applicant shall remove the netting or product and replace it with wildlife-friendly biodegradable products. The Applicant shall not use or allow the use of soil stabilization products that contain synthetic materials within waters of the United States or waters of the State at any time. Applicant shall

- remove any remaining synthetic netting or materials remaining at the end of two years, or sooner.
11. The Regional Water Board shall be notified prior to the commencement of ground disturbing activities, with details regarding the construction schedule, in order to allow staff to be present onsite during construction, and to answer any public inquiries that may arise regarding the project.
 12. No debris, soil, silt, sand, bark, slash, sawdust, rubbish, cement or concrete washings, oil or petroleum products, or other organic or earthen material from any construction or associated activity of whatever nature, other than that authorized by this Order, shall be allowed to enter into or be placed where it may be washed by rainfall into waters of the State. When operations are completed, any excess material or debris shall be removed from the work area. No rubbish shall be deposited within 150 feet of the high water mark of any stream.
 13. BMPs for erosion, sediment and turbidity control shall be implemented and in place at commencement of, during and after any ground- clearing activities or any other project activities that could result in erosion or sediment discharges to surface water.
 14. All activities and BMPs shall be implemented according to the submitted application and the conditions in this certification.
 15. A copy of this Order and the application documents submitted by the Applicant for this certification shall be provided to all contractors and subcontractors conducting the work, and shall be in their possession at the work site.
 16. If, at any time, an unauthorized discharge to surface water (including wetlands, rivers or streams) occurs, or any water quality problem arises, the associated project activities shall cease immediately until adequate BMPs are implemented. The Regional Water Board shall be notified promptly and in no case more than 24 hours after the unauthorized discharge or water quality problem arises.
 17. Disturbance or removal of vegetation shall not exceed the minimum necessary to complete the project.
 18. Prior to implementing any change to the project that may have a significant or material effect on the findings, conclusions, or conditions of this Order, the Applicant shall obtain the written approval of the Regional Water Board Executive Officer.
 19. All project work shall be conducted as described in this Order and in the application submitted by the Applicant. If the Regional Water Board is not notified of a significant alteration to the project, it will be considered a violation of this

Order, and the Applicant may be subject to Regional Water Board enforcement actions.

20. The Regional Water Board may add to or modify the conditions of this Order, as appropriate, to implement any new or revised water quality standards and implementation plans adopted and approved pursuant to the Porter-Cologne Water Quality Control Act or Section 303 of the Clean Water Act.
21. The Applicant shall provide Regional Water Board staff access to the project site to document compliance with this certification.
22. In the event of any violation or threatened violation of the conditions of this certification, the violation or threatened violation shall be subject to any remedies, penalties, process or sanctions as provided for under applicable State or federal law. For the purposes of section 401(d) of the Clean Water Act, the applicability of any State law authorizing remedies, penalties, process or sanctions constitutes a limitation necessary to assure compliance with the water quality standards and other pertinent requirements incorporated into this certification. In response to a suspected violation of any condition of this certification, the Regional Water Board may require the holder of any federal permit or license subject to this certification to furnish, under penalty of perjury, any technical or monitoring reports the Regional Water Board deems appropriate, provided that the burden, including costs, of the reports shall bear a reasonable relationship to the need for the reports and the benefits to be obtained from the reports. In response to any violation of the conditions of this certification, the Regional Water Board may add to or modify the conditions of this certification as appropriate to ensure compliance.
23. In the event of any change in control of ownership of land presently owned or controlled by the Applicant, the Applicant shall notify the successor-in-interest of the existence of this Order by letter and shall forward a copy of the letter to the Regional Water Board at the above address.

To discharge dredged or fill material under this Order, the successor-in-interest must send to the Regional Water Board Executive Officer a written request for transfer of the Order. The request must contain the requesting entity's full legal name, the state of incorporation if a corporation, and the address and telephone number of the person(s) responsible for contact with the Regional Water Board. The request must also describe any changes to the project proposed by the successor-in-interest or confirm that the successor-in-interest intends to implement the project as described in this Order.

Except as may be modified by any preceding conditions, all certification actions are contingent on: a) the discharge being limited to and all proposed mitigation being completed in strict compliance with the Applicant's project description, and; b) compliance with all applicable requirements of the Water Quality Control Plan for the North Coast Region (Basin Plan).

24. The authorization of this certification for any dredge and fill activities expires on March 15, 2015. Conditions and monitoring requirements outlined in this certification are not subject to the expiration date outlined above, and remain in full effect and are enforceable.

If you have any questions or comments, please call Stephen Bargsten of our office at (707) 576-2653.

Sincerely,

Catherine Kuhlman
Executive Officer

100314_SKB_Healdsburg_West_Grant_Street_Bridge_Improvements_401.doc

Web link: State Water Resources Control Board Order No. 2003-0017 -DWQ, General Waste Discharge Requirements for Dredge and Fill Discharges That Have Received State Water Quality Certification may be found at:
http://www.waterboards.ca.gov/board_decisions/adopted_orders/water_quality/2003/wqo/wqo2003-0017.pdf

Original to: Mr. Scott Rodolph, City of Healdsburg, 401 Grove St,
Healdsburg, CA 95448

Copies to: Mr. Bill Orme, SWRCB, 401 Program Manager, SWRCB
Ms. Kim Niemeyer, SWRCB, Office of the Chief Counsel
Ms. Laurie Monarres, U.S. ACOE, Regulatory Functions, 1455 Market
Street, San Francisco, CA 94103-1398
Mr. Richard Fitzgerald, California Department of Fish and Game,
P.O. Box 47, Yountville, CA 94558
Ms. Lucy Macmillan, Environmental Scientist, 108 Rising Road,
Mill Valley, CA 94941