
North Coast Regional Water Quality Control Board

September 9, 2015

**In the Matter of
Water Quality Certification**

for the

**Noyo Harbor Mooring Basin Maintenance Dredging Project
WDID No. 1B15106WNME**

APPLICANT: Noyo Harbor District
RECEIVING WATER: Noyo River
HYDROLOGIC UNIT: Mendocino Coast Hydrologic Unit, Noyo River Hydrologic Area
113.20
COUNTY: Mendocino
FILE: Noyo Harbor Mooring Basin Maintenance Dredging Project,
ECM PIN CW-817262

BY THE EXECUTIVE OFFICER:

1. On June 30, 2015, the Noyo Harbor District (Applicant) filed an application for water quality certification (certification) under section 401 of the Clean Water Act (33 U.S.C. § 1341) with the California Regional Water Quality Control Board, North Coast Region (Regional Water Board) for activities associated with maintenance dredging of the Noyo Harbor Mooring Basin Project (Project). Information describing the Project was noticed for public comment on the Regional Water Board's website on August 5, 2015. We received no comments. The proposed Project will cause disturbances to waters of the United States associated with the Noyo River within the Mendocino Coast Hydrologic Unit No. 113.20. The Project is located at the Mooring Basin in Noyo Harbor near the mouth of the Noyo River, Mendocino County, at latitude 39.424074°N, and longitude 123.801380°W. Temporary impacts to waters of the U.S. include approximately 8 acres of river channel dredging and removal of approximately 35,000 cubic yards of sediment.

2. The primary purpose of the Project is to conduct maintenance dredging of the mooring basin to design depth to provide navigational access. The proposed Project would include using a suction dredge with barge to remove approximately 35,000 cubic yards of sediment. Sediment is proposed to be placed at the 3-acre approved Noyo upland storage site for dewatering and then moved to an approved beneficial reuse or disposal site.

Maintenance dredging is planned for the entire mooring basin to return the area to permitted maintenance depths. Maintenance dredging is planned for depths of -12 feet mean lower low water (MLLW) plus 1 foot of overdepth dredging in the access channel and deep vessel mooring basin west of third dock. The remaining areas of the boat basin will have maintenance dredging occur to a depth range of -6 to -10 feet MLLW plus 1 foot of overdepth dredging.

3. The Project is planned to take place during the fall of 2015 or 2016 depending on funding and permitting. Dredging is expected to take 5 weeks to complete.
4. Eelgrass surveys were conducted 60 days prior to dredging to identify possible areas of impact that would necessitate mitigation. Eelgrass surveys were conducted in accordance with the *California Eelgrass Mitigation Policy and Implementation Guidelines* (NOAA 2014). Surveys demonstrated that no Eelgrass is present in the proposed dredge area. Additionally, the Applicant conducted appropriate sediment sampling and analysis for agency review and approval prior to commencing maintenance dredging. The Project proposes to employ best management practices (BMPs) to prevent or reduce any discharges during and after dredging at the dredge and dewatering sites.
5. The Applicant has applied for authorization from the United States Army Corps of Engineers for a Clean Water Act, section 404 Permit (Nationwide Permit No. 35, Maintenance Dredging of Existing Basins). The Applicant has applied to the California Department of Fish and Wildlife to obtain a Streambed Alteration Agreement.
6. The North Coast Regional Water Quality Control Board, as lead California Environmental Quality Act (CEQA) agency, has determined that the project qualifies for a Categorical Exemption, 15304 (g) Minor Alterations to Land, and will file a Notice of Exemption with the State Clearinghouse concurrent with issuance of the 401 Water Quality Certification, pursuant to CEQA guidelines.
7. The Noyo River is identified as impaired for sediment and temperature under Clean Water Act Section 303(d). Bank erosion is identified as a source contributing to the sediment impairment. Removal of dredged material with a suction dredge may only temporarily increase suspended sediment at the dredge site. Dredged material at the approved upland storage site shall not cause turbidity levels to exceed limits

allowable by Regional Water Board Order No. 86-51 Waste Discharge Requirements for US Army Corps of Engineers and the Noyo Harbor District Maintenance Dredging, Noyo Harbor. Accordingly, this Order is consistent with, and implements, BMPs that would attenuate sediment and temperature adverse impacts.

8. Pursuant to Regional Water Board Resolution R1-2004-0087, Total Maximum Daily Load Implementation Policy Statement for Sediment-Impaired Receiving Waters within the North Coast Region (Sediment TMDL Implementation Policy), the Executive Officer is directed to "rely on the use of all available authorities, including existing regulatory standards, and permitting and enforcement tools to more effectively and efficaciously pursue compliance with sediment-related standards by all dischargers of sediment waste."
9. The federal antidegradation policy requires that state water quality standards include an antidegradation policy consistent with the federal policy. The State Water Board established California's antidegradation policy in State Water Board Resolution No. 68-16. Resolution No. 68-16 incorporates the federal antidegradation policy where the federal policy applies under federal law. Resolution No. 68-16 requires that existing quality of waters be maintained unless degradation is justified based on specific findings. The Regional Water Board's Basin Plan implements, and incorporates by reference, both the State and federal antidegradation policies. This Order is consistent with applicable federal and State antidegradation policies, as it does not authorize the discharge of increased concentrations of pollutants or increased volumes of treated wastewater.
10. This discharge is also regulated under State Water Resources Control Board Order No. 2003-0017-DWQ, "General Waste Discharge Requirements for Dredge and Fill Discharges That Have Received State Water Quality Certification," which requires compliance with all conditions of this water quality certification. (Weblink attached below).

Receiving Water: Noyo River,
Noyo River Hydrologic Unit, 113.20

In channel: Temporary impact to waters of the US:
8 acres Noyo River bed

Dredge Volume: 35,000 cubic yards

Latitude/Longitude: 39.424074°N / 123.801380°W

Expiration: September 9, 2020

Accordingly, based on its independent review of the record, the Regional Water Board certifies that the Noyo Harbor Mooring Basin Maintenance Dredging Project (WDID No. 1B15106WNME), as described in the application, will comply with sections 301, 302, 303, 306 and 307 of the Clean Water Act, and with applicable provisions of state law, provided that the Applicant complies with the following terms and conditions:

All conditions of this order apply to the Applicant (and all their employees) and all contractors (and their employees), sub-contractors (and their employees), and any other entity or agency that performs activities or work on the project as related to this Water Quality Certification.

1. This certification action is subject to modification or revocation upon administrative or judicial review, including review and amendment pursuant to Water Code section 13330 and title 23, California Code of Regulations, section 3867.
2. This certification action is not intended and shall not be construed to apply to any discharge from any activity involving a hydroelectric facility requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent certification application was filed pursuant to title 23, California Code of Regulations, section 3855, subdivision (b) and the application specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.
3. The validity of this certification is conditioned upon total payment of any fee required under title 23, California Code of Regulations, section 3833, and owed by the Applicant.
4. A fee of \$600 was received for this project on August 10, 2015. This certification will be subject to annual billing during the dredging phase ("Annual Active Discharge Fee") and during the monitoring phase of the project ("Annual Post Discharge Monitoring Fee"), per the current fee schedule, which can be found on our website: http://www.swrcb.ca.gov/northcoast/water_issues/programs/water_quality_certification.shtml These fees will be automatically invoiced to the Applicant. Based on the current fee calculator and proposed activities of dredging approximately 35,000 cubic yards of sediment, the applicant will be billed the "Annual Active Discharge Fee" of \$7,350.

The Applicant must notify the Regional Water Board of the end of the dredging phase of the Project in order to request the Regional Water Board to terminate annual construction period billing and to receive a "Notice of Completion of Discharges Letter". If the Project is subject to annual monitoring fees, the Applicant must also notify the Regional Water Board at the end of the monitoring period in order to request to terminate annual monitoring period billing and receive a "Notice of Project Complete Letter". Completion reports may be necessary to be submitted by the

Applicant at the end of each of these phases. Regional Water Board staff may request site visits at the end of each phase of the project to confirm status of Project and compliance with this Order.

5. The proposed Project will have only temporary impacts to waters of the U.S. Eelgrass surveys conducted in accordance with the *California Eelgrass Mitigation Policy and Implementation Guidelines* (NOAA 2014) demonstrated that no Eelgrass will be disturbed during dredging activities, and therefore, compensatory mitigation is not necessary.
6. The Applicant shall submit a dredged material beneficial reuse or disposal plan for review and approval to Regional Water Board Staff, prior to permanently relocating the dewatered dredged material. The Applicant shall comply with Regional Water Board Order No. 86-51 Waste Discharge Requirements for US Army Corps of Engineers and the Noyo Harbor District Maintenance Dredging, Noyo Harbor, including associated monitoring and reporting.
7. Only wildlife-friendly, 100 percent biodegradable erosion and sediment control products that will not entrap or harm wildlife shall be used. Erosion and sediment control products shall not contain synthetic (e.g., plastic or nylon) netting. Photodegradable synthetic products are not considered biodegradable. The Applicant shall request approval from the Regional Water Board if an exception from this requirement is needed for a specific location.
8. BMPs shall be implemented as proposed in the application materials. BMPs for erosion, sediment and turbidity control shall be implemented and in place at commencement of, during and after any ground clearing activities or any other Project activities that could result in erosion or sediment discharges to surface water. Severe and unseasonal rain events are becoming more frequent due to the effects of climate change. Therefore, BMPs shall be immediately available for deployment at all times to prevent discharges to waters of the state.
9. No debris, soil, silt, sand, bark, slash, sawdust, rubbish, cement or concrete washings, oil or petroleum products, or other organic or earthen material from any construction or associated activity of whatever nature, other than that authorized by this Order, shall be allowed to enter into or be placed where it may be washed by rainfall into waters of the State. When operations are completed, any excess material or debris shall be removed from the work area.
10. The Applicant shall provide Regional Water Board staff access to the Project site to document compliance with this certification.
11. If, at any time, an unauthorized discharge to surface water (including wetlands, lakes, rivers or streams) occurs, or any water quality problem arises, the associated Project

activities shall cease immediately until adequate BMPs are implemented including stopping work. The Regional Water Board shall be notified promptly and in no case more than 24 hours after the unauthorized discharge or water quality problem arises.

12. Prior to implementing any change to the Project that may have a significant or material effect on the findings, conclusions, or conditions of this Order, the Applicant shall obtain the written approval of the Regional Water Board Executive Officer. If the Regional Water Board is not notified of a significant alteration to the Project, it will be considered a violation of this Order, and the Applicant may be subject to Regional Water Board enforcement action(s).
13. All Project work shall be conducted as described in this Order and in the application submitted by the Applicant, and shall comply with all applicable water quality standards as detailed in the Basin Plan. If the Regional Water Board is not notified of a significant alteration to the Project, it will be considered a violation of this Order, and the Applicant may be subject to Regional Water Board enforcement actions.
14. The Applicant shall provide a copy of this Order and State Water Resources Control Board (SWRCB) Order No. 2003-0017-DWQ to any contractor(s), subcontractor(s), and utility company(ies) conducting work on the Project, and shall require that copies remain in their possession at the work site. The Applicant shall be responsible for ensuring that all work conducted by its contractor(s), subcontractor(s), and utility companies is performed in accordance with the information provided by the Applicant to the Regional Water Board.
15. Disturbance or removal of existing vegetation shall not exceed the minimum necessary to complete the Project.
16. Fueling, lubrication, maintenance, storage, and staging of vehicles and equipment shall not result in a discharge or threatened discharge to any waters of the State including dry portions of the shoreline. At no time shall the Applicant or its contractors allow use of any vehicle or equipment, which leaks any substance that may impact water quality.
17. The Regional Water Board may add to or modify the conditions of this Order, as appropriate, to implement any new or revised water quality standards and implementation plans adopted and approved pursuant to the Porter-Cologne Water Quality Control Act or section 303 of the Clean Water Act.
18. In the event of any violation or threatened violation of the conditions of this Order, the violation or threatened violation shall be subject to any remedies, penalties, process or sanctions as provided for under applicable state or federal law. For the purposes of section 401(d) of the Clean Water Act, the applicability of any state law authorizing remedies, penalties, process or sanctions for the violation or threatened

violation constitutes a limitation necessary to assure compliance with the water quality standards and other pertinent requirements incorporated into this Order. In response to a suspected violation of any condition of this certification, the State Water Board may require the holder of any federal permit or license subject to this Order to furnish, under penalty of perjury, any technical or monitoring reports the State Water Board deems appropriate, provided that the burden, including costs, of the reports shall bear a reasonable relationship to the need for the reports and the benefits to be obtained from the reports. In response to any violation of the conditions of this Order, the Regional Water Board may add to or modify the conditions of this Order as appropriate to ensure compliance.

19. In the event of any change in control of ownership of land presently owned or controlled by the Applicant, the Applicant shall notify the successor-in-interest of the existence of this Order by letter and shall email a copy of the letter to the following email address: NorthCoast@waterboards.ca.gov

To discharge dredged or fill material under this Order, the successor-in-interest must email the Regional Water Board Executive Officer at: NorthCoast@waterboards.ca.gov a written request for transfer of the Order. The request must contain the requesting entity's full legal name, the state of incorporation if a corporation, and the address and telephone number of the person(s) responsible for contact with the Regional Water Board.

The request must also describe any changes to the Project proposed by the successor-in-interest or confirm that the successor-in-interest intends to implement the Project as described in this Order. Except as may be modified by any preceding conditions, all certification actions are contingent on: a) the discharge being limited to and all proposed mitigation being completed in strict compliance with the Applicant's Project description, and b) compliance with all applicable requirements of the Water Quality Control Plan for the North Coast Region (Basin Plan).

20. The authorization of this certification for any dredge and fill activities expires on September 9, 2020. Conditions and monitoring requirements outlined in this Order are not subject to the expiration date outlined above, and remain in full effect and are enforceable.

If you have any questions or comments, please call Gil Falcone at (707) 576-2830 or Stephen Bargsten at (707) 576-2653.

Executive Officer

150909_GBF_dp_NoyoMooringBasinDredge_401

Weblink: State Water Resources Control Board Order No. 2003-0017 -DWQ, General Waste Discharge Requirements for Dredge and Fill Discharges That Have Received State Water Quality Certification can be found at:
http://www.waterboards.ca.gov/board_decisions/adopted_orders/water_quality/2003/wqo/wqo2003-0017.pdf

Original to: Mr. Jere Kleinbach, Noyo Harbor District, 19101 South Harbor Drive, Fort Bragg, CA 95437

Copy to: Holly Costa, US Army Corps of Engineers holly.n.costa@usace.army.mil

Mark D'Avignon, US Army Corps of Engineers
Mark.R.D'Avignon@usace.army.mil

Erik Nielsen, SHN Engineers enielsen@shn-engr.com

Rebecca Garwood, CA Fish and Wildlife Rebecca.Garwood@wildlife.ca.gov