
Staff Report for the Action Plan for the Scott River Watershed Sediment and Temperature Total Maximum Daily Loads



December 7, 2005



State of California
North Coast Regional Water Quality Control Board
5550 Skylane Boulevard, Suite A
Santa Rosa, California 95403
707-576-2220
www.waterboards.ca.gov/northcoast



TMDL Development Team

Donald A. Coates
Elmer Dudik
Richard Fadness
Rebecca Fitzgerald
Ranjit Gill
Bruce Gwynne
David Leland
Bryan McFadin
Carey Wilder
Ben Zabinsky

Acknowledgments

The TMDL Development Team of the North Coast Regional Water Quality Control Board was responsible for data collection, data interpretation, modeling, and preparation of the report. This effort would not have been possible without the efforts and contributions of many people and organizations, including:

- The University of California Information Center for the Environment, who prepared shade modeling analyses and provided technical support.
- Resource Management Inc., who provided road inventory summaries.
- Fruit Growers Supply Company and Timber Products Corporation, who allowed access to certain lands.
- VESTRA Resources, who performed the aerial photo landslide inventory.
- The California Department of Forestry and Fire Protection and the U.S. Forest Service, who provided stream and road survey data and information on landslides.

Our thanks and appreciation to you all.

TABLE OF CONTENTS

	Page
TITLE PAGE	i
ACKNOWLEDGEMENTS	iii
TABLE OF CONTENTS	v
LIST OF FIGURES	xii
LIST OF TABLES	xiv
EXECUTIVE SUMMARY	xvii
CHAPTER 1: INTRODUCTION.....	1-1
 1.1 Document Structure & Contents.....	1-1
1.1.1 Scott River TMDL Action Plan.....	1-1
1.1.2 TMDL Introductory Language	1-2
 1.2 Rationale	1-3
 1.3 Purpose and Goals	1-3
 1.4 Watershed Restoration and Enhancement Efforts.....	1-4
1.4.1 Siskiyou Resource Conservation District.....	1-4
1.4.2 Scott River Watershed Council	1-4
1.4.3 Joint Projects of the Siskiyou RCD and the SRWC.....	1-5
1.4.4 French Creek Watershed Advisory Group	1-7
1.4.5 Industrial Timber Companies	1-8
1.4.6 Siskiyou County & Five Counties Salmonid Conservation Program	1-8
1.4.7 CDFG's Coho Recovery Process and Incidental Take Permits	1-8
1.4.8 Department of Water Resources.....	1-9
1.4.9 United States Forest Service.....	1-9
1.4.10 Klamath River Basin Fisheries Task Force	1-10
 1.5 Scott River Watershed Characteristics.....	1-10
1.5.1 Area and Location	1-10
1.5.2 Population.....	1-10
1.5.3 Climate and Hydrology	1-11
1.5.4 Topography	1-14
1.5.5 Vegetation	1-15
1.5.6 Geology	1-15
1.5.7 History and Land Use.....	1-16
1.5.8 Ownership	1-17
 1.6 Endangered Species Act Consultation	1-17
CHAPTER 2: PROBLEM STATEMENT	2-1
 2.1 Introduction.....	2-2
 2.2 Water Quality Standards	2-3
2.2.1 Beneficial Uses.....	2-3
2.2.2 Water Quality Objectives	2-4

2.3 Salmonid Populations and Periodicity	2-4
2.3.1 Salmonid Populations.....	2-4
2.3.2 Salmonid Habitat	2-6
2.3.3 Salmonid Periodicity	2-8
2.4 Sediment Problem Statement.....	2-9
2.4.1 Sediment Desired Conditions	2-9
2.4.1.1 Instream Desired Conditions for Sediment	2-10
2.4.1.2 Watershed Desired Conditions for Sediment	2-10
2.4.2 Instream Sediment Conditions in the Scott River Watershed	2-16
2.4.2.1 Benthic Macroinvertebrate Assemblages.....	2-17
2.4.2.2 Embeddedness Conditions	2-19
2.4.2.3 Large Woody Debris Conditions.....	2-19
2.4.2.4 Pool Distribution and Depth Conditions	2-20
2.4.2.5 Percent Fines Conditions.....	2-22
2.4.2.6 Thalweg Profile Conditions.....	2-23
2.4.2.7 V* Conditions.....	2-24
2.4.3 Watershed Sediment Conditions in the Scott River Watershed	2-25
2.4.3.1 Stream Crossings with Diversion or Significant Failure Potential.....	2-25
2.4.3.2 Hydrologic Connectivity	2-26
2.4.3.3 Annual Road Inspection and Correction	2-26
2.4.3.4 Road Location, Surfacing, & Sidecast	2-26
2.4.3.6 Disturbed Areas	2-27
2.5 Temperature Problem Statement.....	2-27
2.5.1 Salmonid Temperature Requirements	2-27
2.5.1.1 Temperature Metrics	2-28
2.5.2 Temperature Desired Conditions.....	2-29
2.5.2.1 Effective Shade.....	2-29
2.5.2.2 Thermal Refugia.....	2-30
2.5.3 Temperature Conditions in the Scott River Watershed.....	2-33
2.5.3.1 Summary of Temperature Conditions	2-33
2.5.3.2 Scott River Mainstem.....	2-33
2.5.3.3 West Headwaters / South Fork Scott River	2-34
2.5.3.4 East Headwaters	2-34
2.5.3.5 Westside Tributaries.....	2-34
2.5.3.6 Eastside Tributaries	2-34
2.5.3.7 Canyon Tributaries	2-34
CHAPTER 3: SEDIMENT	3-1
3.1 Study Methods.....	3-2
3.1.1 Sampling Approach and Rationale	3-2
3.1.2 Subwatersheds Used in Compilation	3-2
3.1.3 Combined Geologic Units.....	3-3
3.1.4 Description of Geologic Units	3-3
3.1.4.1 Quaternary Deposits	3-3
3.1.4.2 Granitic Bedrock	3-4
3.1.4.3 Mafic and Ultramafic Bedrock.....	3-4

3.1.4.4	Sedimentary and Metamorphic Bedrock	3-4
3.1.4.5	Extent of Geologic Units	3-4
3.1.5	The Role of DG Soils.....	3-5
3.1.6	Effects of Multiple Interacting Human Activities	3-6
3.1.7	Sources of Information	3-7
3.1.8	South Fork Pilot Study.....	3-8
3.2	Road Related Sediment Delivery	3-8
3.2.1	Two Estimates Made.....	3-8
3.2.2	Discrete Sediment Sources (Road Inventory and Field-Check)	3-10
3.2.3	Granitic Substrate and Road-Associated Sediment – The DG Factor	3-11
3.2.4	Estimates of Road-Related Sediment Contribution	3-13
3.3	Aerial Photo Landslide Survey	3-15
3.3.1	Methods.....	3-15
3.3.2	VESTRA Aerial Photo Interpretation.....	3-15
3.3.3	Estimation of Sediment Delivery Rates.....	3-16
3.3.4	Volume Estimate of Slide Features	3-16
3.3.4.1	Polygon features	3-16
3.3.4.2	Line features	3-17
3.3.4.3	Point features	3-17
3.3.5	Initial Estimate of Connectivity and Age.....	3-17
3.3.5.1	Connectivity	3-17
3.3.5.2	Age.....	3-17
3.3.6	US Forest Service Landslide Inventory	3-17
3.3.6.1	1992 Photo Inventory	3-18
3.3.6.2	1997 Photo Inventory	3-18
3.3.6.3	Discussion of USFS Landslide Inventory	3-18
3.3.7	Estimate of Sediment Delivery Rate.....	3-19
3.3.8	Summary of VESTRA Landslide Inventory	3-20
3.3.8.1	West Canyon Subwatershed	3-20
3.3.8.2	East Canyon Subwatershed	3-20
3.3.8.3	Eastside Subwatershed	3-20
3.3.8.4	East Headwater Subwatershed	3-21
3.3.8.5	West Headwater Subwatershed	3-21
3.3.8.6	Westside Subwatershed	3-21
3.3.8.7	Scott Valley-Eastern Valley Side Subwatershed.....	3-21
3.4	Streamside Sediment Delivery	3-22
3.4.1	Soil Creep Contribution	3-22
3.4.2	Streamside Mass Wasting & Erosion Features - Stratified Random Sampling...	3-24
3.4.3	Effects of Multiple Interacting Human Activities	3-25
3.4.4	Estimation of Sediment Delivery from Small and Large Features	3-28
3.4.5	Streamside Large Discrete Features.....	3-29
3.4.5.1	Feature 92 – A Special Case.....	3-29
3.4.5.2	East Boulder Creek – A Special Case	3-30
3.4.6	Streamside Small Discrete Features.....	3-31
3.4.7	Callahan Area Dredger Tailings	3-31
3.5	Sediment Analysis Summary, TMDL, Allocations, & Margin of Safety	3-32

3.5.1	Sediment Source Analysis Results.....	3-32
3.5.2	Sediment TMDL.....	3-32
3.5.3	Load Allocations.....	3-33
3.5.4	Margin of Safety	3-34
3.5.5	Seasonal Variation and Critical Conditions.....	3-35
CHAPTER 4: TEMPERATURE.....		4-1
4.1	Introduction.....	4-3
4.1.1	Temperature Sources: Stream Heating Processes.....	4-3
4.1.2	Stream Heating Processes Affected by Human Activities.....	4-5
4.1.2.1	Stream Shade.....	4-6
4.1.2.2	Groundwater.....	4-6
4.1.2.3	Surface Water.....	4-8
4.1.2.4	Channel Geometry.....	4-9
4.1.2.5	Microclimate	4-9
4.2	Methods.....	4-10
4.2.1	Sources of Information	4-10
4.2.2	Approach and Model Selection.....	4-11
4.2.3	Collection and Use of Stream Temperature and Meteorology Data.....	4-12
4.2.4	Collection and Use of Infrared Imagery	4-12
4.2.5	Rectification and Use of Color Imagery	4-13
4.2.6	Mapping and Classification of Land Cover	4-14
4.2.7	Collection and Use of Flow Data.....	4-14
4.2.8	Estimation of Stream Diversions	4-14
4.2.9	Measurement and Estimation of Channel Geometry and Morphology	4-14
4.2.10	Development of Potential Condition Scenarios.....	4-15
4.2.10.1	Shade	4-15
4.2.10.2	Flow.....	4-16
4.2.10.3	Width	4-16
4.2.10.4	Sinuosity	4-16
4.2.10.5	Combined Factors.....	4-17
4.3	Model Applications	4-17
4.3.1	Scott River Mainstem	4-17
4.3.1.1	Boundary Conditions.....	4-18
4.3.1.2	Channel Geometry and Substrate Representation	4-18
4.3.1.3	Flow Simulation	4-19
4.3.1.4	Shade Simulation.....	4-20
4.3.1.5	Meteorological Data	4-21
4.3.1.6	Model Calibration and Validation	4-21
4.3.1.7	Results and Discussion.....	4-23
4.3.2	South Fork Scott River.....	4-27
4.3.2.1	Boundary Conditions.....	4-28
4.3.2.2	Channel Geometry and Substrate Representation	4-28
4.3.2.3	Flow Simulation	4-29
4.3.2.4	Shade Simulation.....	4-29
4.3.2.5	Meteorological Data	4-30

4.3.2.6	Model Calibration and Validation	4-30
4.3.2.7	Results and Discussion	4-30
4.3.3	East Fork Scott River	4-31
4.3.3.1	Boundary Conditions.....	4-31
4.3.3.2	Channel Geometry and Substrate Representation	4-32
4.3.3.3	Flow Simulation	4-32
4.3.3.4	Shade Simulation.....	4-33
4.3.3.5	Meteorological Data	4-34
4.3.3.6	Model Calibration and Validation	4-34
4.3.3.7	Results and Discussion.....	4-34
4.3.4	Houston/Cabin Meadows Creeks.....	4-36
4.3.4.1	Boundary Conditions.....	4-36
4.3.4.2	Channel Geometry and Substrate Representation	4-36
4.3.4.3	Flow Simulation	4-37
4.3.4.4	Shade Simulation.....	4-37
4.3.4.5	Meteorological Data	4-38
4.3.4.6	Model Calibration and Validation	4-38
4.3.4.7	Results and Discussion.....	4-38
4.3.5	Conclusions of Model Applications.....	4-41
4.4	Temperature TMDL and Allocations	4-42
4.4.1	Development of Pollutant Load Capacity and Surrogate Measures	4-42
4.4.2	Load Allocations.....	4-44
4.5	Synthesis.....	4-45
4.5.1	Mainstem Scott River	4-45
4.5.2	Scott River Tributaries.....	4-46
4.6	Recommendations for Additional Study and Future Action	4-47
4.7	Margin of Safety & Seasonal Variation	4-48

CHAPTER 5: IMPLEMENTATION	5-1	
5.1. Implementation Actions	5-2	
5.1.1	Introduction to Implementation Actions	5-2
5.1.1.1	Prioritization of Implementation Actions	5-4
5.1.2	Road and Sediment Discharge Implementation Actions for Individuals.....	5-4
5.1.2.1	Encouragement of Road-Related Sediment Control Actions.....	5-4
5.1.2.2	Erosion Control Plans & Monitoring	5-5
5.1.3	Road Implementation Actions for Caltrans	5-7
5.1.4	Road Implementation Actions for the County of Siskiyou.....	5-8
5.1.5	Ground Disturbance Implementation Actions for the County of Siskiyou.....	5-9
5.1.6	Dredge Mining Implementation Actions	5-10
5.1.7	Implementation Actions to Address Water Temperature and Vegetation	5-13
5.1.8	Water Use Implementation Actions.....	5-16
5.1.8.1	Water Conservation Implementation Actions	5-16
5.1.8.2	Water Use Implementation Actions	5-17
5.1.9	Flood Control and Bank Stabilization Implementation Actions	5-18
5.1.10	Timber Harvest Implementation Actions.....	5-20
5.1.10.1	Timber Harvest Project Approval Process	5-20

5.1.10.2	Timber Harvest General WDRs & Waivers.....	5-21
5.1.10.3	Habitat Conservation Plans	5-22
5.1.11	Implementation Actions for the U.S. Forest Service	5-23
5.1.11.1	Sediment-Related Efforts	5-23
5.1.11.2	Temperature-Related Efforts	5-24
5.1.11.3	Grazing-Related Efforts	5-25
5.1.11.4	Implementation Actions	5-26
5.1.12	Implementation Actions for the U.S. Bureau of Land Management	5-27
5.1.13	Grazing Implementation Actions.....	5-29
5.1.13.1	Encouragement of Grazing-Related Sediment and Temperature Control Actions	5-29
5.1.13.2	Grazing & Riparian Management Plans.....	5-29
5.1.14	Implementation Actions for the Scott River Watershed Council and the Siskiyou Resource Conservation District	5-32
5.1.14.1	Strategic Action Plan.....	5-33
5.1.14.2	Grazing Management Practices.....	5-34
5.1.14.3	Historic Mining Issues.....	5-34
5.1.14.4	Implementation Actions	5-35
5.1.15	Implementation Actions for the Natural Resources Conservation Service and University of California Cooperative Extension.....	5-35
5.1.16	Implementation Actions for the California Department of Fish and Game.....	5-36
5.1.16.1	1600 Permits.....	5-36
5.1.16.2	Outreach Efforts	5-37
5.1.16.3	Coho Recovery Strategy.....	5-37
5.1.16.4	Incidental Take Permits	5-39
5.1.16.5	Implementation Actions	5-39
5.2	Permitting and Enforcement Actions.....	5-43
5.2.1	Permitting.....	5-43
5.2.2	Enforcement.....	5-43
5.3	Compliance with the Non-Point Source Policy	5-44
5.3.1	Non-Point Source Pollution Control Programs and the Five Key Elements	5-44
CHAPTER 6: MONITORING		6-1
6.1	Types of Monitoring	6-1
6.1.1	Implementation Monitoring	6-1
6.1.2	Upslope Effectiveness Monitoring	6-1
6.1.3	Instream Effectiveness Monitoring.....	6-2
6.1.4	Compliance & Trend Monitoring	6-2
6.2	Monitoring Requirements	6-3
6.2.1	General Monitoring Requirements	6-3
6.2.2	Compliance and Trend Monitoring Requirements	6-4
6.2.3	Monitoring Requirements Specific to the County, USFS, and BLM	6-5
6.2.4	Monitoring Requirements Specific to Erosion Control Plans and Grazing and Riparian Management Plans.....	6-5

CHAPTER 7: REASSESSMENT.....7-1

CHAPTER 8: ANTIDEGRADATION8-1

8.1 State and Federal Antidegradation Policies	8-1
8.2 Applicability to the Scott River TMDL Action Plan	8-2

CHAPTER 9: ENVIRONMENTAL ANALYSIS9-1

9.1 Environmental Analysis Requirements	9-2
9.2 Scoping Meeting	9-3
9.3 Functionally Equivalent Substitute Document	9-3
9.4 Alternatives & Staff Recommendation	9-3
9.4.1 Alternative 1: No Action.....	9-5
9.4.2 Alternative 2: Scott River TMDL Action Plan.....	9-6
9.4.3 Alternative 3: WDR-based Implementation Actions.....	9-7
9.4.4 Staff Recommendation.....	9-7
9.5 CEQA Checklist	9-7
9.6 Analysis of Environmental Impacts	9-8
9.7 Mitigation Measures	9-8

CHAPTER 10: ECONOMIC ANALYSIS.....10-1

10.1 Legal Framework.....	10-2
10.2 Scope of the Economic Analysis.....	10-3
10.2.1 Existing Requirements	10-3
10.2.2 Geographic Scope	10-3
10.3 Benefits.....	10-4
10.3.1 Fishing – Commercial, Subsistence, & Cultural.....	10-4
10.3.2 Flooding	10-5
10.3.3 Properly Functioning Ecosystems.....	10-6
10.3.4 Recreation	10-6
10.3.5 Remediation – Habitat Restoration and Road Maintenance	10-7
10.3.6 Residential Land Prices.....	10-9
10.3.7 Water Conveyance and Storage Facilities	10-9
10.4 Costs	10-10
10.4.1 Methodology	10-10
10.4.2 Estimated Costs for the Scott River TMDL Action Plan.....	10-11
10.5 Sources of Funding	10-13

CHAPTER 11: PUBLIC PARTICIPATION11-1

11.1 Scott River TMDL Technical Advisory Group.....	11-1
11.2 Scoping Meeting	11-3
11.3 Presentations to the Regional Water Board	11-3
11.4 Other Activities	11-3
11.5 Public Draft	11-4
11.6 Future Public Participation Opportunities	11-4

REFERENCES..... R-1

GLOSSARY..... G-1

APPENDICES

- | | |
|--|-----|
| A. Current and Potential Riparian Forest Condition along Scott River Tributaries | A-1 |
| B. Aerial Surveys Using Thermal Infrared & Color Videography..... | B-1 |
| C. Calibration & Validation Results, Scott River Temperature TMDL Analyses | C-1 |
| D. Erosion Control Plan Guidance | D-1 |
| E. CEQA Checklist..... | E-1 |
| F. Peer Review Comments and Responses | F-1 |
| G. Public Comments and Response..... | G-1 |

LIST OF FIGURES

	Page
Figure 1.1 Index map.....	Back
Figure 1.2 Interaction of ground water and surface water	1-11
Figure 1.3 Annual precipitation measured at Fort Jones.....	1-13
Figure 1.4 Peak flows by water year, Scott River near Fort Jones 1942-2004	1-13
Figure 1.5 Minimum flows by water year, Scott River near Fort Jones 1942-2004	1-14
Figure 1.6 Distribution of ownership in the Scott River watershed.....	Back
 Figure 2.1 Scott River fall chinook spawner escapement	2-7
Figure 2.2 Scott Juvenile coho estimates from electroshocking surveys on five reaches of French Creek from 1992-2004	2-8
Figure 2.3 Salmonid periodicity in the Scott River watershed.....	2-9
Figure 2.4 French Creek monitoring results – fine sediment in pools (V*).....	2-24
Figure 2.5 Effective shade vs. channel width, Douglas Fir forest	2-31
Figure 2.6 Effective shade vs. channel width, Klamath Mixed Conifer forest	2-32
Figure 2.7 Effective shade vs. channel width, oak woodland	2-32
 Figure 3.1 Subwatersheds in the Scott River watershed	Back
Figure 3.2 Geologic map of the Scott River watershed	Back
Figure 3.3 Map of aerial photo coverage	Back
Figure 3.4 Locations of landslides in photo-analysis by Vestra Resources	Back
Figure 3.5 Locations of randomly stratified streamside sampling sites	Back
Figure 3.6 Index map showing locations of areas detailed in Figures 3.7 – 3.14	Back
Figure 3.7 Orthophoto showing 0% disturbance history, Jackson Creek	Back
Figure 3.8 GIS showing 0% disturbance history, Jackson Creek	Back
Figure 3.9 Orthophoto showing 25% disturbance history, unnamed tributary	Back
Figure 3.10 GIS showing 25% disturbance history, unnamed tributary	Back
Figure 3.11 Orthophoto showing 50% disturbance history, NF French Creek	Back
Figure 3.12 GIS showing 50% disturbance history, NF French Creek	Back
Figure 3.13 Orthophoto showing 75% disturbance history, NF Kelsey Creek	Back
Figure 3.14 GIS showing 75% disturbance history, NF Kelsey Creek	Back
 Figure 4.1A Daily heat flux, Scott River at Island Road	Back
Figure 4.1B Daily heat flux, Scott River at Jones Beach.....	Back
Figure 4.1C Daily heat flux, South Fork Scott River downstream of Blue Jay Creek	Back
Figure 4.1D Daily heat flux, South Fork Scott River upstream of Highway 3.....	Back
Figure 4.2 Water table measurements, Scott Valley	Back
Figure 4.3A Scott River and River Mile 3.1 to 3.9	Back
Figure 4.3B South Fork Scott River at River Mile 4.7 to 5.3	Back
Figure 4.3C Scott River at River Mile 39.6 to 40.6	Back
Figure 4.3D East Fork Scott River at River Mile 3.1 to 3.9.....	Back
Figure 4.4 Scott River bankfull area-to-drainage area relationship	Back
Figure 4.5 Scott River bankfull width-to-drainage area relationship.....	Back

Figure 4.6	Scott River watershed data collection sites and modeled segments	Back
Figure 4.7	Particle size and embeddedness, Scott River mainstem	Back
Figure 4.8	Stream gradient, Scott River mainstem	Back
Figure 4.9	Manning's n values, Scott River mainstem	Back
Figure 4.10	Modeled stream flows, Scott River mainstem	Back
Figure 4.11	Estimated groundwater accretion flows, Scott River mainstem	Back
Figure 4.12	Current and potential effective shade, Scott River mainstem, July 30, 2003 ...	Back
Figure 4.13	Longitudinal profiles of temperature modeling results quantifying effects of groundwater accretion, Scott River mainstem; 3:00 PM, July 30, 2003.....	Back
Figure 4.14A	Modeled average land cover heights, left bank, Scott River mainstem.....	Back
Figure 4.14b	Modeled average land cover heights, right bank, Scott River mainstem.....	Back
Figure 4.15	Longitudinal profiles of temperature modeling results quantifying effects of riparian vegetation in the Scott River mainstem; 3:00 PM, July 30, 2003	Back
Figure 4.16	Stream temperature differences resulting from current and potential vegetation; Scott River Mainstem; July 31, 2003, 3:00 PM.....	Back
Figure 4.17	Longitudinal profiles of temperature modeling results quantifying effects of changes in surface water diversions in the Scott River Mainstem; 3:00 PM, July 30, 2003	Back
Figure 4.18	Longitudinal profile of temperature modeling results quantifying effects of changes in stream geometry in the Scott River mainstem; 3:00 PM, July 30, 2003	Back
Figure 4.19	Longitudinal profiles of temperature modeling results quantifying effects of combined scenarios, July 30, 2003, Scott River mainstem.....	Back
Figure 4.20	Relationship of flow at South Fork Scott River gage to measured flows at the upper model boundary	Back
Figure 4.21	Stream gradients, South Fork Scott River	Back
Figure 4.22	Current and potential effective stream shade, South Fork Scott River, July 26, 2003	Back
Figure 4.23	Longitudinal profiles of temperature modeling results quantifying effects of vegetation and surface diversions, South Fork Scott River; 3:00 PM, July 26, 2003.	Back
Figure 4.24	Relationship of flows at East Fork Scott River gage to measured flows at the upper model boundary	Back
Figure 4.25	Stream gradients, East Fork Scott River	Back
Figure 4.26	Modeled Stream Flows, East Fork Scott River, July 25, 2003	Back
Figure 4.27	Modeled groundwater accretion, East Fork Scott River	Back
Figure 4.28	Current and potential effective stream shade, East Fork Scott River, July 25, 2003	Back
Figure 4.29	Longitudinal profiles of temperature modeling results quantifying effects of vegetation and surface diversions, East Fork Scott River; 3:00 PM, July 25, 2003	Back
Figure 4.30	Stream gradients, Houston and Cabin Meadows Creeks	Back
Figure 4.31	Longitudinal profiles of temperature modeling results quantifying effects of changes in surface water flow in Houston and Cabin Meadows Creek; 3:00 PM, August 2, 2004 ..	Back

- Figure 4.32: Diurnal temperature modeling results quantifying effects of CA Forest Practice Rules' threatened and impaired riparian buffer requirements and potential microclimate effects 3:00 PM, August 2, 2004 Back
- Figure 4.33: Diurnal temperature modeling results quantifying effects of CA Forest Practice Rules' standard riparian buffer requirements and potential microclimate effects; 3:00 PM, August 2, 2004. Back
- Figure 4.34: Current and desired effective shade exceedence curves, Scott River watershed. Back
- Figure 4.35: Distribution of current and desired effective Shade, Scott River Watershed..... Back
- Figure 4.36: Desired effective shade, Scott River watershed Back

LIST OF TABLES

	Page	
Table 1.1	Relative extent of vegetation types in Scott River watershed.....	1-15
Table 2.1	Water quality objectives applicable to the Scott River TMDL.....	2-4
Table 2.2	Instream Desired Conditions for sediment	2-11
Table 2.3	Russian River Index of Biological Integrity	2-13
Table 2.4	Watershed Desired Conditions for sediment	2-13
Table 2.5	Instream sediment conditions in the Scott River watershed	2-17
Table 2.6	Embeddedness of gravels in the Scott River and four tributaries	2-19
Table 2.7	LWD Key Piece Volume Criteria	2-21
Table 2.8	Recommended Criteria for summer maximum water temperatures	2-28
Table 2.9	Stream MWATs, Scott River mainstem, 1995-2004	2-35
Table 2.10	Stream MWATs, South Fork Scott River, 1996-2004.....	2-35
Table 2.11	Stream MWATs, East Fork Scott River, 1998-2004	2-35
Table 2.12	Stream MWATs, westside tributaries of Scott River, 1996-2004	2-36
Table 2.13	Stream MWATs, eastside tributaries of Scott River, 1997-2001	2-36
Table 2.14	Stream MWATs, tributaries of canyon section of the Scott River, '96-'03	2-37
Table 3.1	Areas and stream miles in geologic units in the Scott River watershed	Back
Table 3.2	Areas and stream miles in geologic units in the subwatersheds	Back
Table 3.3	Mileage of roads and distances from streams, Scott River watershed.....	Back
Table 3.4	Mileage of roads and distances from streams, Subwatershed.....	Back
Table 3.5	Road-related sediment contribution, South Fork Scott River	Back
Table 3.6	Road-related sediment contribution, Scott River watershed.....	Back
Table 3.7	Road-related sediment contribution, Scott River watershed.....	Back
Table 3.8	Road-related granitic sediment delivery, Scott River watershed.....	Back
Table 3.9	Summary of number of features photointerpreted as possible landslides.....	Back
Table 3.10	Summary of the sediment delivery from photointerpreted features	Back
Table 3.11	Tons/year of landslide sediment, human-activity related.	Back
Table 3.12	Comparison of soil creep contribution estimates	Back
Table 3.13	Soil creep estimates in seven subwatersheds, including granite.....	Back
Table 3.14	Soil creep estimates in seven subwatersheds, excluding granite	Back
Table 3.15	Large and small discrete features sediment contributions	Back
Table 3.16	Large discrete features sediment contributions, Scott River watershed	Back
Table 3.17	Large discrete features sediment contributions, Subwatersheds.....	Back
Table 3.18	Small discrete features sediment contributions, using data from stream surveys in all geologic units.....	Back
Table 3.19	Small discrete features sediment contributions, using data from Quaternary, Mafic, and Sedimentary/Metamorphic geologic units.....	Back
Table 3.20	Small discrete features sediment contributions, no direct human activity associations	Back
Table 3.21	Small discrete features sediment contributions, documented associated with human activity.....	Back

Table 3.22	Scott River Watershed Sediment Source Summary.....	Back
Table 3.23	Load Allocations for Sediment.....	Back
Table 4.1	Data required for operation of the Heat Source model	Back
Table 4.2	Data used in the development of stream temperature model applications.....	Back
Table 4.3	Measured and estimated flows.....	Back
Table 4.4	Modeled and measure effective shade, mainstem Scott River	Back
Table 4.5	Distribution of data used to define meteorological conditions	Back
Table 4.6A	Model calibration results, August 27 to September 10, 2003	Back
Table 4.6B	Model validation results, July 28 to August 1, 2003	Back
Table 4.7	South Fork Scott River model calibration and validation results	Back
Table 4.8	East Fork Scott River model calibration results	Back
Table 4.9	Performance of Houston / Cabin Meadows Creek temperature model.	Back
Table 4.10	Constants used to develop microclimate depictions.	Back
Table 4.11	Summary of stream lengths in shade classes.	Back
Table 5.1	Water right adjudications	5-16
Table 5.2	Waiver Categories.....	5-21
Table 5.3	Riparian Reserve Buffer Widths for the Lower Scott River.....	5-24
Table 5.4	Riparian Reserve Buffer Widths for the Callahan Management Area	5-25
Table 5.5	Recommended Grazing Management Practices	5-30
Table 5.6	Strategic Actions from the Strategic Action Plan	5-33
Table 5.7	Tasks and Actions from the Coho Recovery Strategy	5-38
Table 5.8	Incidental Take Permit Application's measures	5-40
Table 5.9	Summary comparison of the ITP and the Scott River TMDL Action Plan.....	5-42
Table 5.10	Comparison of Coho Recovery Strategy, ITP, SAP, & TMDL Action Plan....	Back
Table 5.11	Summary of the NPS Policy's Five Key Elements.....	5-45
Table 7.1	Reassessment considerations	7-2
Table 9.1	Comments & responses from the CEQA Scoping Meeting.....	9-4
Table 10.1	Costs of typical habitat restoration activities	10-9
Table 10.2	NRCS Program Costs Management Measures	10-11
Table 10.3	Estimated costs for the Scott River TMDL Action Plan.....	10-12