

Watershed Management Program Appendix 1

# A-1-1 Definitions, Acronyms and Abbreviations

DRAFT

# DEFINITIONS, ACRONYMS AND ABBREVIATIONS

The following are definitions for terms in this Watershed Management Program:

**Bacteria Total Maximum Daily Load (TMDL) Dry Weather:** Defined in the Bacteria TMDLs as those days with less than 0.1 inch of rainfall and those days occurring more than 3 days after a rain.

**Bacteria Total Maximum Daily Load (TMDL) Wet Weather:** Defined in the Bacteria TMDLs as a day with 0.1 inch or more of rain and 3 days following the rain event.

**Baseline Waste Load Allocation:** The Waste Load Allocation assigned before reductions are required. The progressive reductions in the Waste Load Allocations are based on a percentage of the Baseline Waste Load Allocation. The Baseline Waste Load Allocation for each jurisdiction was calculated based on the annual average amount of trash discharged to the storm drain system from a representative sampling of land use areas, as determined during the Baseline Monitoring Program.

**Basin Plan:** The Water Quality Control Plan, Los Angeles Region, Basin Plan for the Coastal Watersheds of Los Angeles and Ventura Counties, adopted by the Regional Water Board on June 13, 1994 and subsequent amendments.

**Beneficial Uses:** The existing or potential uses of receiving waters as designated by the Regional Board in the Basin Plan.

**Best Management Practices (BMPs):** BMPs are practices or physical devices or systems designed to prevent or reduce pollutant loading from and or volume of stormwater or nonstormwater discharges to receiving waters.

**Commercial Development:** Any development on private land that is not heavy industrial or residential. The category includes, but is not limited to: hospitals, laboratories and other medical facilities, educational institutions, recreational facilities, plant nurseries, car wash facilities; mini-malls and other business complexes, shopping malls, hotels, office buildings, public warehouses and other light industrial complexes.

**Commercial Malls:** Any development on private land comprised of one or more buildings forming a complex of stores which sells various merchandise, with interconnecting walkways enabling visitors to easily walk from store to store, along with parking area(s). A commercial mall includes, but is not limited to: mini-malls, strip malls, other retail complexes, and enclosed shopping malls or shopping centers.

**Daily Generation Rate (DGR):** The estimated amount of trash deposited within a representative drainage area during a 24-hour period, derived from the amount of trash collected from streets and catch basins in the area over a 30-day period.

**Disturbed Area:** An area that is altered as a result of clearing, grading, and/or excavation.

**Effluent Limitation:** Any restriction imposed on quantities, discharge rates, and concentrations of pollutants, which are discharged from point sources to waters of the U.S.

**Environmentally Sensitive Areas (ESAs):** An area in which plant or animal life or their habitats are either rare or especially valuable because of their special nature or role in an ecosystem and which would be easily disturbed or degraded by human activities and developments (California Public Resources Code § 30107.5). Areas subject to stormwater mitigation requirements are: areas designated as Significant Ecological Areas by the County of Los Angeles (Los Angeles County Significant Areas

Study, Los Angeles County Department of Regional Planning (1976) and amendments); an area designated as a Significant Natural Area by the California Department of Fish and Game's Significant Natural Areas Program, provided that area has been field verified by the Department of Fish and Game; an area listed in the Basin Plan as supporting the "Rare, Threatened, or Endangered Species (RARE)" beneficial use; and an area identified by a Permittee as environmentally sensitive.

**Estuaries:** Estuaries means waters, including coastal lagoons, located at the mouths of streams that serve as areas of mixing for fresh and ocean waters. Coastal lagoons and mouths of streams that are temporarily separated from the ocean by sandbars shall be considered estuaries. Estuarine waters shall be considered to extend from a bay or the open ocean to a point upstream where there is no significant mixing of fresh water and seawater.

**Hillside:** Property located in an area with known erosive soil conditions, where the development contemplates grading on any natural slope that is 25% or greater and where grading contemplates cut or fill slopes.

**Hydrologic Unit Code (HUC):** A standardized watershed classification system in which each hydrologic unit is identified by a unique hydrologic unit code (HUC).

**Illicit Connection:** Any man-made conveyance that is connected to the storm drain system without a permit, excluding roof drains and other similar type connections. Examples include channels, pipelines, conduits, inlets, or outlets that are connected directly to the storm drain system.

**Illicit Discharge:** Any discharge into the MS4 or from the MS4 into a receiving water that is prohibited under local, state, or federal statutes, ordinances, codes, or regulations.

**Industrial/Commercial Facility:** Any facility involved and/or used in the production, manufacture, storage, transportation, distribution, exchange or sale of goods and/or commodities, and any facility involved and/or used in providing professional and non-professional services. This category of facilities includes, but is not limited to, any facility defined by either the Standard Industrial Classifications (SIC) or the North American Industry Classification System (NAICS). Facility ownership (federal, state, municipal, private) and profit motive of the facility are not factors in this definition.

**Industrial Park:** A land development that is set aside for industrial development. Industrial parks are usually located close to transport facilities, especially where more than one transport modalities coincide: highways, railroads, airports, and navigable rivers. It includes office parks, which have offices and light industry.

**Institutional Controls:** Programmatic control measures that do not require construction or structural modifications to the MS4. Examples include street sweeping, public education, and clean out of catch basins that discharge to storm drains.

**Integrated Pest Management (IPM):** An ecosystem-based strategy that focuses on long-term prevention of pests or their damage through a combination of techniques such as biological control, habitat manipulation, modification of cultural practices, and use of resistant varieties.

**Low Impact Development (LID):** LID consists of building and landscape features designed to retain or filter stormwater runoff.

**Low Impact Development (LID) Plan:** See "SUSMP" definition.

**Maximum Extent Practicable (MEP):** The process in choosing effective BMPs and rejecting applicable BMPs only where other effective BMPs will serve the same purpose, the BMPs would not be technically feasible, or the cost would be prohibitive.

**National Pollutant Discharge Elimination System (NPDES):** The national program for issuing, modifying, revoking and reissuing, terminating, monitoring and enforcing permits, and imposing and enforcing pretreatment requirements, under CWA §307, 402, 318, and 405.

**Natural Drainage System:** A natural drainage system is a drainage system that has not been improved (e.g., channelized or armored). The clearing or dredging of a natural drainage system does not cause the system to be classified as an improved drainage system.

**New Development:** Land disturbing activities; structural development, including construction or installation of a building or structure, creation of impervious surfaces; and land subdivision.

**Nonstormwater Discharge:** Any discharge into the MS4 or from the MS4 into a receiving water that is not composed entirely of stormwater.

**Not Detected (ND):** Sample results which are less than the laboratory's minimum detection level.

**Nuisance:** Anything that meets all of the following requirements: (1) is injurious to health, or is indecent or offensive to the senses, or an obstruction to the free use of property, so as to interfere with the comfortable enjoyment of life or property; (2) affects at the same time an entire community or neighborhood, or any considerable number of persons, although the extent of the annoyance or damage inflicted upon individuals may be unequal.; (3) occurs during, or as a result of, the treatment or disposal of wastes.

**Receiving Water:** A "water of the United States" into which stormwater runoff is or may be discharged.

**Receiving Water Limitation:** Any applicable numeric or narrative water quality objective or criterion, or limitation to implement the applicable water quality objective or criterion.

**Redevelopment:** Land-disturbing activity that results in the creation, addition, or replacement of impervious surface area on an already developed site. Redevelopment includes, but is not limited to: the expansion of a building footprint; addition or replacement of a structure; replacement of impervious surface area that is not part of a routine maintenance activity; and land disturbing activities related to structural or impervious surfaces. It does not include routine maintenance to maintain original line and grade, hydraulic capacity, or original purpose of facility, nor does it include emergency construction activities required to immediately protect public health and safety.

**Significant Ecological Areas (SEAs):** An area that is determined to possess an example of biotic resources that cumulatively represent biological diversity, for the purposes of protecting biotic diversity, as part of the Los Angeles County General Plan.

**Source Control BMP:** Any schedules of activities, prohibitions of practices, maintenance procedures, managerial practices or operational practices that aim to prevent stormwater pollution by reducing the potential for contamination at the source of pollution.

**SUSMP:** The Los Angeles Countywide Standard Urban Stormwater Mitigation Plan. The SUSMP shall address the Planning and Land Development conditions and requirements of the MS4 Permit.

**Wet Season:** The calendar period beginning October 1 through April 15.

<b>Acronym/Abbreviation</b>	<b>Full Phrase/Definition</b>
µg/L	micrograms per Liter
303(d) List	California's Clean Water Act Section 303(d) List
ASBS	Areas of Special Biological Significance
Basin Plan	Water Quality Control Plan for the Coastal Watersheds of Los Angeles and Ventura Counties
BMP	Best Management Practices
Caltrans Permit	The State Board's Caltrans NPDES Permit, Order No. 2012-0011-DWQ
CASQA	California Stormwater Quality Association
CEQA	California Environmental Quality Act
CFR	Code of Federal Regulations
CGP	The State Board's Construction General Permit Order No. 2009-0009-DWQ, or as amended.
CIMP	The Lower San Gabriel River Watershed Group Coordinated Integrated Monitoring Program.
Cities	The Lower San Gabriel River Watershed Group participating cities, only.
County	The LACFCD and the LA County DPW
CTR	California Toxics Rule
CWA	Clean Water Act
CWC	California Water Code
DC	Development Construction Program
ELRS	Equivalent Load Reduction Strategy
EPA	United States Environmental Protection Agency
GIS	Geographical Information System
gpd	gallons per day
GWMA	Gateway Water Management Authority
HUC	Hydrologic Unit Code
ICF	Industrial/Commercial Facilities Program
ICID	Illicit Connection and Illicit Discharge Elimination Program
IGP	The State Board's Industrial Storm Water General Permit Order No. 2014-0057-DWQ, or as amended.
INI	Initiatives (as defined in the WMP)
IPM	Integrated Pest Management
JSWMP	Jurisdictional Stormwater Management Program
LA	Load Allocations
LA County DPW	Los Angeles County Department of Public Works
LA MS4 Permit	The Los Angeles Regional Water Quality Control Board Order No. R4-2012-0175, only (excluding LB MS4 and Caltrans Permits).
LACFCD	Los Angeles County Flood Control District
LB MS4 Permit	The Los Angeles Regional Water Quality Control Board Order No. R4-2014-0024, only (excluding LA MS4 and Caltrans Permits).
LID	Low Impact Development
LID Plan	Low Impact Development Plan

<b>Acronym/Abbreviation</b>	<b>Full Phrase/Definition</b>
Lower SGR Watershed	Lower San Gabriel River Watershed
MCM	Minimum Control Measure
MEP	Maximum Extent Practicable
mg/L	milligrams per Liter
MGD	Million Gallons Per Day
MRP	Monitoring and Reporting Program
MS4	Municipal Separate Storm Sewer System
MS4 Permit	The Los Angeles Regional Water Quality Control Board Order No. R4-2012-0175 and Order No. R4-2014-0024.
NAICS	North American Industry Classification System
NPDES	National Pollutant Discharge Elimination System
NSWD	Nonstormwater Discharge
Ocean Plan	Water Quality Control Plan for Ocean Waters of California
PAA	Public Agency Activities Program
Participating Agencies	The Lower San Gabriel River Watershed Group participating agencies, excluding Caltrans.
PEP	Progressive Enforcement Policy
Permittees	The County of Los Angeles and 85 cities within the coastal watersheds of Los Angeles County
PIP	Public Information and Participation Program
PLD	Planning and Land Development Program
PMP	Pollutant Minimization Plan
POTW	Publicly Owned Treatment Works
QA	Quality Assurance
QA/QC	Quality Assurance/Quality Control
QSD	Qualified SWPPP Developer
QSP	Qualified SWPPP Practitioner
RAA	Reasonable Assurance Analysis
RAP	Reasonable Assurance Program
REAP	Rain Event Action Plan
Regional Board	California Regional Water Quality Control Board, Los Angeles Region
RP	Responsible Party
SEA	Significant Ecological Area
SIC	Standard Industrial Classification
SMARTS	State Water Resources Control Board's Storm Water Multiple Application and Report Tracking System
SQMP	Stormwater Quality Management Programs
SSO	Sewer Leaks, sanitary sewer overflow
State Board	California State Water Resources Control Board
State Listing Policy	State Board's Water Quality Control Policy for Developing California's Clean Water Act Section 303(d) List

<b>Acronym/Abbreviation</b>	<b>Full Phrase/Definition</b>
SUSMP	Standard Urban Stormwater Mitigation Plan
SWPPP	Stormwater Pollution Prevention Plan
SWQDv	Stormwater Quality Design Volume
TAC	Technical Advisory Committee
TCM	Targeted Control Measure
TMDL	Total Maximum Daily Load
TRA	Training
TSS	Total Suspended Solids
WAG	Watershed Authority Group
WDID	Waste Discharge Identification
WLA	Waste Load Allocations
WMP	The Lower San Gabriel River Watershed Group Watershed Management Program
WQBEL	Water Quality Based Effluent Limitations
WQO	Water Quality Objective
WQP	Water Quality Priority
WRP	Water Reclamation Plant

Watershed Management Program Appendix 2

# A-2-1 2010 303(d) List

DRAFT

Lower San Gabriel River Watershed 303(d) Listed Segments

REGION/REGION NAME	WATER BODY NAME	POLLUTANT	POLLUTANT CATEGORY	POTENTIAL SOURCES	SOURCE CATEGORY
Regional Board 4 - Los Angeles Region	Coyote Creek	Ammonia	Nutrients	Point Source	Unspecified Point Source
Regional Board 4 - Los Angeles Region	Coyote Creek	Copper, Dissolved	Metals/Metalloids	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	Coyote Creek	Diazinon	Pesticides	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	Coyote Creek	Indicator Bacteria	Pathogens	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	Coyote Creek	Lead	Metals/Metalloids	Major Municipal Point Source-wet weather discharge	Municipal Wastewater
Regional Board 4 - Los Angeles Region	Coyote Creek	Toxicity	Toxicity	Point Source	Unspecified Point Source
Regional Board 4 - Los Angeles Region	Coyote Creek	pH	Miscellaneous	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	Coyote Creek, North Fork	Indicator Bacteria	Pathogens	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	Coyote Creek, North Fork	Selenium	Metals/Metalloids	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Gabriel River Reach 1 (Estuary to Firestone)	Coliform Bacteria	Pathogens	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Gabriel River Reach 1 (Estuary to Firestone)	pH	Miscellaneous	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Gabriel River Reach 2 (Firestone to Whittier Narrows Dam)	Coliform Bacteria	Pathogens	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Gabriel River Reach 2 (Firestone to Whittier Narrows Dam)	Cyanide	Other Inorganics	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Gabriel River Reach 2 (Firestone to Whittier Narrows Dam)	Lead	Metals/Metalloids	Nonpoint Source	Unspecified Nonpoint Source
Regional Board 4 - Los Angeles Region	San Gabriel River Reach 2 (Firestone to Whittier Narrows Dam)	Lead	Metals/Metalloids	Point Source	Unspecified Point Source
Regional Board 4 - Los Angeles Region	San Gabriel River Reach 3 (Whittier Narrows to Ramona)	Indicator Bacteria	Pathogens	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Jose Creek Reach 1 (SG Confluence to Temple St.)	Ammonia	Nutrients	Nonpoint Source	Unspecified Nonpoint Source
Regional Board 4 - Los Angeles Region	San Jose Creek Reach 1 (SG Confluence to Temple St.)	Ammonia	Nutrients	Point Source	Unspecified Point Source
Regional Board 4 - Los Angeles Region	San Jose Creek Reach 1 (SG Confluence to Temple St.)	Coliform Bacteria	Pathogens	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Jose Creek Reach 1 (SG Confluence to Temple St.)	Total Dissolved Solids	Salinity	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Jose Creek Reach 1 (SG Confluence to Temple St.)	Toxicity	Toxicity	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Jose Creek Reach 1 (SG Confluence to Temple St.)	pH	Miscellaneous	Source Unknown	Source Unknown
Regional Board 4 - Los Angeles Region	San Jose Creek Reach 2 (Temple to I-10 at White Ave.)	Coliform Bacteria	Pathogens	Point Source	Unspecified Point Source
Regional Board 4 - Los Angeles Region	San Jose Creek Reach 2 (Temple to I-10 at White Ave.)	Coliform Bacteria	Pathogens	Nonpoint Source	Unspecified Nonpoint Source

Watershed Management Program Appendix 2

# A-2-2 Mass Emission Station Monitoring Results

DRAFT

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE					Wet				Dry	
					S13 Coyote Creek 0203-01 11/08/2002	S13 Coyote Creek 0203-02 12/16/2002	S13 Coyote Creek 0203-03 02/11/2003	S13 Coyote Creek 0203-05 03/15/2003	S13 Coyote Creek 0203-01 10/10/2002	S13 Coyote Creek 0203-02 04/30/2003
Sample Type	EPA Method	PQL	Units							
<b>Conventional</b>										
Oil and Grease	Grab	EPA413.1	1	mg/L	2.6	0	1	0	0	0
Total Phenols	Grab	EPA420.1	0.1	mg/L	0	0	0	0	0	0
Cyanide	Grab	EPA335.2	0.01	mg/L	0.126	0	0.018	0	0	0.019
pH	Comp	SM4500H B	0-14		7.82	7.06	8.03	7.02	8.75	8.65
Dissolved Oxygen	Grab	SM4500 G	1	mg/L	5.5	8.2	8.58	9.38	9.18	9.61
<b>Indicator Bacteria</b>										
Total Coliform	Grab	SM9230B	20	MPN/100ml	300000	500000	800000	500000	8000	3500
Fecal Coliform	Grab	SM9230B	20	MPN/100ml	300000	300000	9000	300000	1700	70
Ratio Fecal Coliform/Total Coliform					1.0	0.6	0.011	0.6	0.21	0.02
Fecal Streptococcus	Grab	SM9230B	20	MPN/100ml	800000	110000	170000	130000	800	800
Fecal Enterococcus	Grab	SM9230B		MPN/100ml	800000	50000	170000	130000	800	800
<b>General</b>										
Chloride	Comp	EPA300.0	2	mg/L	29.5	9.13	78	14.8	88	87
Fluoride	Comp	EPA300.0	0.1	mg/L	0.36	0.14	0.54	0.1	0.46	1
Nitrate	Comp	EPA300.0	0.1	mg/L	7.32	1.61	8.31	2.89	2.28	8.9
Sulfate	Comp	EPA300.0	0.1	mg/L	44.5	10.4	114	22.1	125	129
Alkalinity	Comp	EPA310.1	4	mg/L	69	43	137.5	27.5	155	220
Hardness	Comp	EPA130.2	2	mg/L	130	60	180	45.6	195	340
COD	9i	EPA410.4	10	mg/L	96.1	24.4	148	24	28	87.6
TPH	Grab	EPA418.1	1	mg/L	1.4	1	2.8	0	0	0
Specific Conductance	Comp	EPA120.1	1	umhos/cm	522	160.8	792	171.1	831	2020
Total Dissolved Solids	Comp	EPA160.1	2	mg/L	370	114	522	112	518	1250
Turbidity	Comp	EPA180.1	0.1	NTU	48	54.5	45.1	67.4	0.73	1.98
Total Suspended Solids	Comp	EPA160.2	2	mg/L	648	351	204	181	63	12
Volatile Suspended Solids	Comp	EPA160.4	1	mg/L	123	68	14.8	2.4	15	9
MBAS	Comp	EPA425.1	0.05	mg/L	0.27	0.053	0.151	0	0	0.062
Total Organic Carbon	Comp	EPA415.1	1	mg/L	29.3	7.81	17.9	4.27	5.35	10.1
BOD	Comp	SM5210B	2	mg/L	52.1	9.4	12.1	6.03	6.62	42.4
<b>Nutrients</b>										
Dissolved Phosphorus	Comp	EPA365.3	0.05	mg/L	0.442	0.096	0.441	0.242	0	0
Total Phosphorus	Comp	EPA365.3	0.05	mg/L	0.46	0.155	0.524	0.259	0	0
NH3-N	Comp	EPA350.3	0.1	mg/L	2.51	0.158	2.11	0	0	0.298
Nitrate-N	Comp	SM4110B	0.5	mg/L	1.65	0.364	1.87	0.6525	0.515	2.01
Nitrite-N	Comp	SM4110B	0.03	mg/L	1.01	0.198	1.42	0	0	0.365
Kjeldahl-N	Comp	EPA351.4	0.1	mg/L	3.36	0.558	6.84	1.16	0.82	1.87
<b>Metals</b>										
Dissolved Aluminum	Comp	EPA200.8	100	ug/l	0	0	0	0	0	0
Total Aluminum	Comp	EPA200.8	100	ug/l	1118	0	0	134	0	0
Dissolved Antimony	Comp	EPA200.8	5	ug/l	2.99	0.83	1.22	0	0.64	0.68
Total Antimony	Comp	EPA200.8	5	ug/l	3.56	0.87	1.27	0	0.64	0.7
Dissolved Arsenic	Comp	EPA200.8	5	ug/l	2.48	0	2.28	0	6.19	2.27
Total Arsenic	Comp	EPA200.8	5	ug/l	3.01	1.42	2.43	1.19	6.19	3.46
Dissolved Beryllium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0
Total Beryllium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0
Dissolved Cadmium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0
Total Cadmium	Comp	EPA200.8	1	ug/l	0.97	0	0	0	0	0
Dissolved Chromium	Comp	EPA200.8	5	ug/l	3.15	1.16	4.11	3.37	2.06	1.02
Total Chromium	Comp	EPA200.8	5	ug/l	8.49	11.7	4.55	9.25	12.5	2.6
Dissolved Chromium +6	Comp	EPA200.8	10	ug/l	0	0	0	0	0	0
Total Chromium +6	Comp	EPA200.8	10	ug/l	0	0	0	0	0	0
Dissolved Copper	Comp	EPA200.8	5	ug/l	11.7	4.21	4.83	4.76	3.98	6.9
Total Copper	Comp	EPA200.8	5	ug/l	45.9	9.91	17.9	12.1	9.94	10.1

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE					Wet				Dry	
					S13 Coyote Creek 0203-01 11/08/2002	S13 Coyote Creek 0203-02 12/16/2002	S13 Coyote Creek 0203-03 02/11/2003	S13 Coyote Creek 0203-05 03/15/2003	S13 Coyote Creek 0203-01 10/10/2002	S13 Coyote Creek 0203-02 04/30/2003
	Sample Type	EPA Method	PQL	Units						
Dissolved Iron	Comp	EPA200.8	100	ug/l	0	109	163	213	0	0
Total Iron	Comp	EPA200.8	100	ug/l	1420	225	209	581	203	145
Dissolved Lead	Comp	EPA200.8	5	ug/l	0	0.62	0.58	0	0	0
Total Lead	Comp	EPA200.8	5	ug/l	20.9	1.44	1.27	2.05	1.25	0.54
Dissolved Mercury	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0
Total Mercury	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0
Dissolved Nickel	Comp	EPA200.8	5	ug/l	14.2	2.25	7.65	2.68	2.29	3.37
Total Nickel	Comp	EPA200.8	5	ug/l	17	15.5	9.57	6.01	18.9	4.3
Dissolved Selenium	Comp	EPA200.8	5	ug/l	2.37	0	0	0	1.92	0
Total Selenium	Comp	EPA200.8	5	ug/l	2.37	0	0	0	1.92	0
Dissolved Silver	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0
Total Silver	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0
Dissolved Thallium	Comp	EPA200.8	5	ug/l	0	0	0	0	0	0
Total Thallium	Comp	EPA200.8	5	ug/l	0	0	0	0	0	0
Dissolved Zinc	Comp	EPA200.8	50	ug/l	84.5	32	52	6	9.32	53
Total Zinc	Comp	EPA200.8	50	ug/l	219	52	61	41	11.6	84
Semi-Volatiles Organics (EPA 625)										
2- Chlorophenol	Comp	EPA625	2	ug/l	0	0	0	0	0	0
2,4-dichloropheno	Comp	EPA625	2	ug/l	0	0	0	0	0	0
2,4-dimethylpheno	Comp	EPA625	2	ug/l	0	0	0	0	0	0
2,4-dinitropheno	Comp	EPA625	3	ug/l	0	0	0	0	0	0
2-nitrophenol	Comp	EPA625	3	ug/l	0	0	0	0	0	0
4-nitrophenol	Comp	EPA625	3	ug/l	0	0	0	0	0	0
4-chloro_3_methylpheno	Comp	EPA625	3	ug/l	0	0	0	0	0	0
Pentachloropheno	Comp	EPA625	2	ug/l	0	0	0	0	0	0
Phenol	Comp	EPA625	1	ug/l	0	0	0	0	0	0
2,4,6-trichlorophenol	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Base/Neutral										
Acenaphthene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Acenaphthylene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Anthracene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Benzidine	Comp	EPA625	3	ug/l	0	0	0	0	0	0
1,2 Benzantracene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Benzo(a)pyrene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Benzo(k)flouranthene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Bis(2-Chloroethoxy) methane	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Bis(2-Chloroisopropyl) ether	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Bis(2-Chloroethyl) ether	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Bis(2-Ethylhexl) phthalate	Comp	EPA625	1	ug/l	0	0	0	0	0	0
4-Bromophenyl phenyl ether	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Butyl benzyl phthalate	Comp	EPA625	0.3	ug/l	0	0	0	0	0	0
2-Chloronaphthalene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
4-Chlorophenyl phenyl ether	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Chrysene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Dibenzo(a,h)anthracene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
1,3-Dichlorobenzene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
1,4-Dichlorobenzene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
1,2-Dichlorobenzene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
3,3-Dichlorobenzidine	Comp	EPA625	3	ug/l	0	0	0	0	0	0
Diethyl phthalate	Comp	EPA625	0.5	ug/l	0	0	0	0	0	0
Dimethyl phthalate	Comp	EPA625	0.5	ug/l	0	0	0	0	0	0
di-n-Butyl phthalate	Comp	EPA625	1	ug/l	0	0	0	0	0	0

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE					Wet				Dry	
					S13 Coyote Creek 0203-01 11/08/2002	S13 Coyote Creek 0203-02 12/16/2002	S13 Coyote Creek 0203-03 02/11/2003	S13 Coyote Creek 0203-05 03/15/2003	S13 Coyote Creek 0203-01 10/10/2002	S13 Coyote Creek 0203-02 04/30/2003
Sample Type	EPA Method	PQL	Units							
2,4-Dinitrotoluene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
2,6-Dinitrotoluene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
4,6 Dinitro-2-methylphenol	Comp	EPA625	3	ug/l	0	0	0	0	0	0
1,2-Diphenylhydrazine	Comp	EPA625	3	ug/l	0	0	0	0	0	0
di-n-Octyl phthalate	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Fluoranthene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Fluorene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Hexachlorobenzene	Comp	EPA625	0.5	ug/l	0	0	0	0	0	0
Hexachlorobutadiene	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Hexachloro-cyclopentadiene	Comp	EPA625	3	ug/l	0	0	0	0	0	0
Hexachloroethane	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Indeno(1,2,3-cd)pyrene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Isophorone	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Naphthalene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Nitrobenzene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
N-Nitroso-dimethyl amine	Comp	EPA625	0.3	ug/l	0	0	0	0	0	0
N-Nitroso-diphenyl amine	Comp	EPA625	0.3	ug/l	0	0	0	0	0	0
N-Nitroso-di-n-propyl amine	Comp	EPA625	0.3	ug/l	0	0	0	0	0	0
Phenanthrene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Pyrene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
1,2,4-Trichlorobenzene	Comp	EPA625	0.5	ug/l	0	0	0	0	0	0
Chlorinated Pesticides										
Aldrin	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
alpha-BHC	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
beta-BHC	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
delta-BHC	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
gamma-BHC (lindane)	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
alpha-chlordane	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
gamma-chlordane	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
4,4'-DDD	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
4,4'-DDE	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
4,4'-DDT	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Dieldrin	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
alpha-Endosulfan	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
beta-Endosulfan	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Endosulfan sulfate	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Endrin	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Endrin aldehyde	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Heptachlor	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Heptachlor Epoxide	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Toxaphene	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Polychlorinated Biphenyls										
Aroclor-1016	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1221	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1232	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1242	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1248	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1254	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1260	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Organophosphate Pesticides										
Chlorpyrifos	Comp	EPA507	0.05	ug/l	0	0	0	0	0	0
Diazinon	Comp	EPA507	0.01	ug/l	0.31	0	0.085	0.07	0	0.038

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE					Wet				Dry	
					S13 Coyote Creek 0203-01 11/08/2002	S13 Coyote Creek 0203-02 12/16/2002	S13 Coyote Creek 0203-03 02/11/2003	S13 Coyote Creek 0203-05 03/15/2003	S13 Coyote Creek 0203-01 10/10/2002	S13 Coyote Creek 0203-02 04/30/2003
	Sample Type	EPA Method	PQL	Units						
Prometryn	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Atrazine	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Simazine	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Cyanazine	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Malathion	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Herbicides										
Glyphosate	Comp	EPA547	25	ug/l	0	0	0	0	0	0
2,4-D	Comp	EPA515.3	10	ug/l	0	0	0	0	0	0
2,4,5-TP-SILVEX	Comp	EPA515.3	1	ug/l	0	0	0	0	0	0

## Note:

- 1) blank cell indicates sample was not analyzed
- 2) 0 indicates concentration below minimum detection level
- 3) PQL = minimum level
- 4) Highlighted cells show exceedances

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE					Wet				Dry	
					S14 San Gabriel River 0203-01 11/08/2002	S14 San Gabriel River 0203-02 12/16/2002	S14 San Gabriel River 0203-03 02/11/2003	S14 San Gabriel River 0203-05 03/15/2003	S14 San Gabriel River 0203-01 10/10/2002	S14 San Gabriel River 0203-02 04/30/2003
	Sample Type	EPA Method	PQL	Units						
Conventional										
Oil and Grease	Grab	EPA413.1	1	mg/L	0	12.9	0	0	0	0
Total Phenols	Grab	EPA420.1	0.1	mg/L	0	0	0	0	0	0
Cyanide	Grab	EPA335.2	0.01	mg/L	0.029	0.005	0.047	0	0	0.019
pH	Comp	SM4500H B	0-14		8.26	7.24	7.79	7.4	8.32	7.4
Dissolved Oxygen	Grab	SM4500O G	1	mg/L	7.1	8.4	9.39	8.26	8	8.9
Indicator Bacteria										
Total Coliform	Grab	SM9230B	20	MPN/100ml	300000	300000	240000	500000	17000	50000
Fecal Coliform	Grab	SM9230B	20	MPN/100ml	50000	300000	17000	220000	500	50000
Ratio Fecal Coliform/Total Coliform					0.17	1.0	0.071	0.44	0.029	1.0
Fecal Streptococcus	Grab	SM9230B	20	MPN/100ml	24000	300000	130000	500000	230	1700
Fecal Enterococcus	Grab	SM9230B		MPN/100ml	3000	300000	130000	500000	80	1300
General										
Chloride	Comp	EPA300.0	2	mg/L	74	25.4	20.6	23.2	167	93.2
Fluoride	Comp	EPA300.0	0.1	mg/L	0.35	0.19	0.13	0.19	0.23	0.21
Nitrate	Comp	EPA300.0	0.1	mg/L	2.5	6.63	3.87	3.88	34.9	30.9
Sulfate	Comp	EPA300.0	0.1	mg/L	102	38.3	21.9	36.1	150	117
Alkalinity	Comp	EPA310.1	4	mg/L	69	64	55	60.5	107	
Hardness	Comp	EPA130.2	2	mg/L	210	108	80	103	270	250
COD	9i	EPA410.4	10	mg/L	83.7	41.4	121	36	37.5	66.6
TPH	Grab	EPA418.1	1	mg/L	0	1	1.1	1	0	0
Specific Conductance	Comp	EPA120.1	1	umhos/cm	732	313	229	281	1215	1012
Total Dissolved Solids	Comp	EPA160.1	2	mg/L	464	206	152	190	806	636
Turbidity	Comp	EPA180.1	0.1	NTU	143	963	46	457.5	0.13	9.8
Total Suspended Solids	Comp	EPA160.2	2	mg/L	630	1258	543	794	5	28
Volatile Suspended Solids	Comp	EPA160.4	1	mg/L	437	63	48.1	7	3	8
MBAS	Comp	EPA425.1	0.05	mg/L	0.209	0	0	0	0.085	0.088
Total Organic Carbon	Comp	EPA415.1	1	mg/L	10.2	6.44	6.75	6.77	7.77	7.95
BOD	Comp	SM5210B	2	mg/L	21.46	21.3	11.9	6.46	69.9	50.6
Nutrients										
Dissolved Phosphorus	Comp	EPA365.3	0.05	mg/L	0.343	0.195	0.218	0.347	0.362	
Total Phosphorus	Comp	EPA365.3	0.05	mg/L	0.356	0.713	0.236	0.349	0.411	
NH3-N	Comp	EPA350.3	0.1	mg/L	0.466	0	0	0	0.314	
Nitrate-N	Comp	SM4110B	0.5	mg/L	0.565	1.5	0.87	0.876	7.88	9.4
Nitrite-N	Comp	SM4110B	0.03	mg/L	0	0	0	0	5.81	0
Kjeldahl-N	Comp	EPA351.4	0.1	mg/L	3.58	0.372	2.44	7.64	0.314	
Metals										
Dissolved Aluminum	Comp	EPA200.8	100	ug/l	0	0	0	0	0	
Total Aluminum	Comp	EPA200.8	100	ug/l	2780	158	100	122	0	
Dissolved Antimony	Comp	EPA200.8	5	ug/l	1.68	0.98	0.78	0.51	0.55	
Total Antimony	Comp	EPA200.8	5	ug/l	3.87	1.02	0.81	0.58	0.58	
Dissolved Arsenic	Comp	EPA200.8	5	ug/l	0	3.15	1.3	1.94	1.05	
Total Arsenic	Comp	EPA200.8	5	ug/l	4.49	6.1	1.39	2.18	1.05	
Dissolved Beryllium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	
Total Beryllium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	
Dissolved Cadmium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	
Total Cadmium	Comp	EPA200.8	1	ug/l	2.15	0	0	0	0	
Dissolved Chromium	Comp	EPA200.8	5	ug/l	0	0.97	1.88	6.18	3.54	
Total Chromium	Comp	EPA200.8	5	ug/l	17.5	12.5	4.36	10.1	12.3	
Dissolved Chromium +6	Comp	EPA200.8	10	ug/l	0	0	0	0	0	0
Total Chromium +6	Comp	EPA200.8	10	ug/l	0	0	0	0	0	0
Dissolved Copper	Comp	EPA200.8	5	ug/l	8.98	4.23	6.01	5.82	4.39	
Total Copper	Comp	EPA200.8	5	ug/l	81.4	10.5	11.9	13.1	18.1	

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE					Wet				Dry	
					S14 San Gabriel River 0203-01 11/08/2002	S14 San Gabriel River 0203-02 12/16/2002	S14 San Gabriel River 0203-03 02/11/2003	S14 San Gabriel River 0203-05 03/15/2003	S14 San Gabriel River 0203-01 10/10/2002	S14 San Gabriel River 0203-02 04/30/2003
	Sample Type	EPA Method	PQL	Units						
Dissolved Iron	Comp	EPA200.8	100	ug/l	221	220	311	953	0	
Total Iron	Comp	EPA200.8	100	ug/l	3680	540	431	1730	207	
Dissolved Lead	Comp	EPA200.8	5	ug/l	0.67	1.21	1.55	0	0	
Total Lead	Comp	EPA200.8	5	ug/l	56	2.52	2.16	5.39	1.38	
Dissolved Mercury	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0
Total Mercury	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0
Dissolved Nickel	Comp	EPA200.8	5	ug/l	9.92	2.9	3.22	4.29	7.46	
Total Nickel	Comp	EPA200.8	5	ug/l	21.1	15.9	5.76	8.22	23.5	
Dissolved Selenium	Comp	EPA200.8	5	ug/l	2.61	0	0	0	1.95	
Total Selenium	Comp	EPA200.8	5	ug/l	3.86	0	0	0	1.95	
Dissolved Silver	Comp	EPA200.8	1	ug/l	0	0	0	0	0	
Total Silver	Comp	EPA200.8	1	ug/l	0.43	0	0	0	0	
Dissolved Thallium	Comp	EPA200.8	5	ug/l	0	0	0	0	0	
Total Thallium	Comp	EPA200.8	5	ug/l	0	0	0	0	0	
Dissolved Zinc	Comp	EPA200.8	50	ug/l	23.8	26	22	4	36.4	
Total Zinc	Comp	EPA200.8	50	ug/l	440	74	41	48	36.4	
Semi-Volatiles Organics (EPA 625)										
2- Chlorophenol	Comp	EPA625	2	ug/l	0	0	0	0	0	0
2,4-dichloropheno	Comp	EPA625	2	ug/l	0	0	0	0	0	0
2,4-dimethylpheno	Comp	EPA625	2	ug/l	0	0	0	0	0	0
2,4-dinitropheno	Comp	EPA625	3	ug/l	0	0	0	0	0	0
2-nitrophenol	Comp	EPA625	3	ug/l	0	0	0	0	0	0
4-nitrophenol	Comp	EPA625	3	ug/l	0	0	0	0	0	0
4-chloro_3_methylpheno	Comp	EPA625	3	ug/l	0	0	0	0	0	0
Pentachloropheno	Comp	EPA625	2	ug/l	0	0	0	0	0	0
Phenol	Comp	EPA625	1	ug/l	0	0	0	0	0	0
2,4,6-trichlorophenol	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Base/Neutral										
Acenaphthene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Acenaphthylene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Anthracene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Benzidine	Comp	EPA625	3	ug/l	0	0	0	0	0	0
1,2 Benzantracene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Benzo(a)pyrene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Benzo(k)flouranthene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Bis(2-Chloroethoxy) methane	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Bis(2-Chloroisopropyl) ether	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Bis(2-Chloroethyl) ether	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Bis(2-Ethylhexl) phtalate	Comp	EPA625	1	ug/l	0	0	0	0	0	0
4-Bromophenyl phenyl ether	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Butyl benzyl phtalate	Comp	EPA625	0.3	ug/l	0	0	0	0	0	0
2-Chloronaphthalene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
4-Chlorophenyl phenyl ether	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Chrysene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Dibenzo(a,h)anthracene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
1,3-Dichlorobenzene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
1,4-Dichlorobenzene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
1,2-Dichlorobenzene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
3,3-Dichlorobenzidine	Comp	EPA625	3	ug/l	0	0	0	0	0	0
Diethyl phtalate	Comp	EPA625	0.5	ug/l	0	0	0	0	0	0
Dimethyl phtalate	Comp	EPA625	0.5	ug/l	0	0	0	0	0	0
di-n-Butyl phtalate	Comp	EPA625	1	ug/l	0	0	0	0	0	0

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE					Wet				Dry	
					S14 San Gabriel River 0203-01 11/08/2002	S14 San Gabriel River 0203-02 12/16/2002	S14 San Gabriel River 0203-03 02/11/2003	S14 San Gabriel River 0203-05 03/15/2003	S14 San Gabriel River 0203-01 10/10/2002	S14 San Gabriel River 0203-02 04/30/2003
Sample Type	EPA Method	PQL	Units							
2,4-Dinitrotoluene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
2,6-Dinitrotoluene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
4,6 Dinitro-2-methylphenol	Comp	EPA625	3	ug/l	0	0	0	0	0	0
1,2-Diphenylhydrazine	Comp	EPA625	3	ug/l	0	0	0	0	0	0
di-n-Octyl phthalate	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Fluoranthene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Fluorene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Hexachlorobenzene	Comp	EPA625	0.5	ug/l	0	0	0	0	0	0
Hexachlorobutadiene	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Hexachloro-cyclopentadiene	Comp	EPA625	3	ug/l	0	0	0	0	0	0
Hexachloroethane	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Indeno(1,2,3-cd)pyrene	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Isophorone	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Naphthalene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Nitrobenzene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
N-Nitroso-dimethyl amine	Comp	EPA625	0.3	ug/l	0	0	0	0	0	0
N-Nitroso-diphenyl amine	Comp	EPA625	0.3	ug/l	0	0	0	0	0	0
N-Nitroso-di-n-propyl amine	Comp	EPA625	0.3	ug/l	0	0	0	0	0	0
Phenanthrene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Pyrene	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
1,2,4-Trichlorobenzene	Comp	EPA625	0.5	ug/l	0	0	0	0	0	0
Chlorinated Pesticides										
Aldrin	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
alpha-BHC	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
beta-BHC	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
delta-BHC	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
gamma-BHC (lindane)	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
alpha-chlordane	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
gamma-chlordane	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
4,4'-DDD	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
4,4'-DDE	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
4,4'-DDT	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Dieldrin	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
alpha-Endosulfan	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
beta-Endosulfan	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Endosulfan sulfate	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Endrin	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Endrin aldehyde	Comp	EPA625	0.1	ug/l	0	0	0	0	0	0
Heptachlor	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Heptachlor Epoxide	Comp	EPA625	0.05	ug/l	0	0	0	0	0	0
Toxaphene	Comp	EPA625	1	ug/l	0	0	0	0	0	0
Polychlorinated Biphenyls										
Aroclor-1016	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1221	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1232	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1242	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1248	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1254	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Aroclor-1260	Comp	EPA608	0.5	ug/l	0	0	0	0	0	0
Organophosphate Pesticides										
Chlorpyrifos	Comp	EPA507	0.05	ug/l	0	0	0	0	0	0
Diazinon	Comp	EPA507	0.01	ug/l	0.34	0	0.41	0.035	0	0.047

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE					Wet				Dry	
					S14 San Gabriel River 0203-01 11/08/2002	S14 San Gabriel River 0203-02 12/16/2002	S14 San Gabriel River 0203-03 02/11/2003	S14 San Gabriel River 0203-05 03/15/2003	S14 San Gabriel River 0203-01 10/10/2002	S14 San Gabriel River 0203-02 04/30/2003
	Sample Type	EPA Method	PQL	Units						
Prometryn	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Atrazine	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Simazine	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Cyanazine	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Malathion	Comp	EPA507	2	ug/l	0	0	0	0	0	0
Herbicides										
Glyphosate	Comp	EPA547	25	ug/l	0	0	0	0	0	0
2,4-D	Comp	EPA515.3	10	ug/l	0	0	0	0	0	0
2,4,5-TP-SILVEX	Comp	EPA515.3	1	ug/l	0	0	0	0	0	0

Note:

- 1) blank cell indicates sample was not analyzed
- 2) 0 indicates concentration below minimum detection level
- 3) PQL = minimum level
- 4) Highlighted cells show exceedances

Appendix B. 2003-2004 Sampling Results for Coyote Creek

Mass Emission Monitoring

WEATHER CONDITION				Wet				Dry			
STATION NO.				Coyote Creek				Coyote Creek			
STATION NAME				0304-02				0304-01			
EVENT NO.				12/25/2003				10/28/2003			
DATE				1/1/2004				1/13/2004			
	Sample Type	EPA Method	PQL	Units	S13 Coyote Creek 0304-01 10/31/2003	S13 Coyote Creek 0304-02 12/25/2003	S13 Coyote Creek 0304-03 1/1/2004	S13 Coyote Creek 0304-01 10/28/2003	S13 Coyote Creek 0304-02 1/13/2004		
Conventional	Grab	EPA413.1	1	mg/L	0	0	0	0	0		
Oil and Grease	Grab	EPA420.1	0.1	mg/L	0	0	0	0	0		
Total Phenols	Grab	EPA335.2	0.01	mg/L	0.02	0	0.017	0.007	0.01		
Cyanide	Comp	SMA500H B	0-14	mg/L	7.5	6.89	6.89	7.39	8.16		
pH	Grab	SMA5000 G	1	mg/L	3.02	8.12	11.28	6.6	17.1		
Dissolved Oxygen											
Indicator Bacteria											
Total Coliform	Grab	SM9230B	20	MPN/100ml	50000	170000	24000	80000	2400		
Fecal Coliform	Grab	SM9230B	20	MPN/100ml	3000	110000	3000	1700	2400		
Ratio Fecal Coliform/Total Coliform					0.06	0.65	0.13	0.02	1.00		
Fecal Streptococcus	Grab	SM9230B	20	MPN/100ml	24000	110000	17000	1100	900		
Fecal Enterococcus	Grab	SM9230B	20	MPN/100ml	24000	80000	13000	1100	260		
General											
Chloride	Comp	EPA300.0	2	mg/L	64.3	15.1	32.4	219	103		
Fluoride	Comp	EPA300.0	0.1	mg/L	0.29	0.16	0.15	0.63	0.54		
Nitrate	Comp	EPA300.0	0.1	mg/L	0	6.63	12.3	0.96	17.5		
Sulfate	Comp	EPA300.0	0.1	mg/L	78.8	24	53	317	158		
Alkalinity	Comp	EPA310.1	4	mg/L	157.3	77	78	217	237		
Hardness	Comp	EPA130.2	2	mg/L	225	92.8	112	325	395		
COD	9l	EPA410.4	10	mg/L	279.1	30	38.6	70.8	125		
TPH	Grab	EPA418.1	1	mg/L	0	0	0	0	0		
Specific Conductance	Comp	EPA120.1	1	umhos/cm	649	277	374	1735	1767		
Total Dissolved Solids	Comp	EPA160.1	2	mg/L	408	192	250	1000	1100		
Turbidity	Comp	EPA180.1	0.1	NTU	16.3	60	1.02	1.15	0.7		
Total Suspended Solids	Comp	EPA160.2	2	mg/L	2061	336	102	445	9		
Volatile Suspended Solids	Comp	EPA160.4	1	mg/L	394	88	25	77	7		
MBAS	Comp	EPA425.1	0.05	mg/L	0.466	0.113	0.181	0.058	0		
Total Organic Carbon	Comp	EPA415.1	1	mg/L	69.5	10	10.1	10.9	6.63		
BOD	Comp	SM5210B	2	mg/L	119	20.3	17.3	4.31	14.4		
Nutrients											
Dissolved Phosphorus	Comp	EPA365.3	0.05	mg/L	0.763	0.32	0.26	0.10	0.00		
Total Phosphorus	Comp	EPA365.3	0.05	mg/L	0.844	0.36	0.30	0.13	0.00		
NH3-N	Comp	EPA350.3	0.1	mg/L	4.64	0.00	0.00	0.14	0.19		
Nitrate-N	Comp	SM4110B	0.5	mg/L	0	1.50	2.78	0.22	3.95		
Nitrite-N	Comp	SM4110B	0.03	mg/L	0.18	0.07	0.13	0.69	1.11		
Kjeldahl-N	Comp	EPA351.4	0.1	mg/L	7	1.73	2.28	2.34	1.16		
Metals											
Dissolved Aluminum	Comp	EPA200.8	100	ug/l	0	0	0	0	0		
Total Aluminum	Comp	EPA200.8	100	ug/l	5856	112	130	0	0		
Dissolved Antimony	Comp	EPA200.8	5	ug/l	2.63	1.58	1.88	1.39	0.65		
Total Antimony	Comp	EPA200.8	5	ug/l	4.75	1.63	2.02	1.39	0.65		
Dissolved Arsenic	Comp	EPA200.8	5	ug/l	3.44	1.91	1.78	3.94	2.85		
Total Arsenic	Comp	EPA200.8	5	ug/l	7.17	1.96	1.78	3.94	3.71		
Dissolved Beryllium	Comp	EPA200.8	1	ug/l	0	0	0	0	0		
Total Beryllium	Comp	EPA200.8	1	ug/l	0	0	0	0	0		
Dissolved Cadmium	Comp	EPA200.8	1	ug/l	0	0	0	0	0		
Total Cadmium	Comp	EPA200.8	1	ug/l	2.46	0	0	0	0		
Dissolved Chromium	Comp	EPA200.8	5	ug/l	5.96	1.52	3.1	7.7	4.78		
Total Chromium	Comp	EPA200.8	5	ug/l	19	5.78	6.26	19.2	6.66		
Dissolved Chromium +6	Comp	EPA200.8	10	ug/l	0	0	0	0	0		
Total Chromium +6	Comp	EPA200.8	10	ug/l	5.56	7.4	11	8.56	6.35		
Dissolved Copper	Comp	EPA200.8	5	ug/l	97.5	21.6	17.6	16.6	8.58		
Total Copper	Comp	EPA200.8	5	ug/l	316	0	0	0	0		
Dissolved Iron	Comp	EPA200.8	100	ug/l	20100	294	318	157	0		
Total Iron	Comp	EPA200.8	100	ug/l	0	0.96	1.5	0	0		
Dissolved Lead	Comp	EPA200.8	5	ug/l	73.1	1.85	2.25	0.81	0.82		
Total Lead	Comp	EPA200.8	5	ug/l	0	0	0	0	0		
Dissolved Mercury	Comp	EPA200.8	1	ug/l	0.236	0	0	0	0		
Total Mercury	Comp	EPA200.8	5	ug/l	15.1	3.94	4.53	6.62	5.3		
Dissolved Nickel	Comp	EPA200.8	5	ug/l	38	6.12	6.47	6.62	7.26		
Total Nickel	Comp	EPA200.8	5	ug/l	2.36	0	0	4.6	4.55		
Dissolved Selenium	Comp	EPA200.8	5	ug/l	2.85	0	0	4.6	5.64		
Total Selenium	Comp	EPA200.8	1	ug/l	0	0	0	0	0		
Dissolved Silver	Comp	EPA200.8	1	ug/l	1.2	0	0	0	0		
Total Silver	Comp	EPA200.8	5	ug/l	0	0	0	0	0		
Dissolved Thallium	Comp	EPA200.8	5	ug/l	0	0	0	0	0		
Total Thallium	Comp	EPA200.8	5	ug/l	0	0	0	0	0		

## Appendix B. 2003-2004 Sampling Results for Coyote Creek

## Mass Emission Monitoring

WEATHER CONDITION		Station				Wet		Dry		
STATION NO.	STATION NAME	Sample Type	EPA Method	PQL	Units	S13 Coyote Creek 0304-01 10/31/2003	S13 Coyote Creek 0304-02 12/25/2003	S13 Coyote Creek 0304-03 1/1/2004	S13 Coyote Creek 0304-01 10/28/2003	S13 Coyote Creek 0304-02 1/13/2004
		Disolved Zinc	EPA200.8	50	ug/l	6.9	40	65	17.1	13
		Total Zinc	EPA200.8	50	ug/l	530	52	90	17.1	50
Semi-Volatiles Organics (EPA 625)										
		2-Chlorophenol	EPA625	2	ug/l	0	0	0	0	0
		2,4-dichlorophenol	EPA625	2	ug/l	0	0	0	0	0
		2,4-dimethylphenol	EPA625	2	ug/l	0	0	0	0	0
		2,4-dinitrophenol	EPA625	3	ug/l	0	0	0	0	0
		2-nitrophenol	EPA625	3	ug/l	0	0	0	0	0
		4-nitrophenol	EPA625	3	ug/l	0	0	0	0	0
		4-chloro_3_methylphenol	EPA625	3	ug/l	0	0	0	0	0
		Pentachlorophenol	EPA625	2	ug/l	0	0	0	0	0
		Phenol	EPA625	1	ug/l	0	0	0	0	0
		2,4,6-trichlorophenol	EPA625	1	ug/l	0	0	0	0	0
Base/Neutral										
		Acenaphthene	EPA625	0.05	ug/l	0	0	0	0	0
		Acenaphthylene	EPA625	0.05	ug/l	0	0	0	0	0
		Anthracene	EPA625	0.05	ug/l	0	0	0	0	0
		Benztidine	EPA625	3	ug/l	0	0	0	0	0
		1,2-Benzanthracene	EPA625	0.1	ug/l	0	0	0	0	0
		Benzoflouranthene	EPA625	0.1	ug/l	0	0	0	0	0
		Bis(2-Chloroethoxy) methane	EPA625	0.1	ug/l	0	0	0	0	0
		Bis(2-Chloroisopropyl) ether	EPA625	1	ug/l	0	0	0	0	0
		Bis(2-Chloroethyl) ether	EPA625	0.1	ug/l	0	0	0	0	0
		Bis(2-Ethylhexyl) phthalate	EPA625	1	ug/l	48.4	0	40.7	31.5	0
		4-Bromophenyl phenyl ether	EPA625	1	ug/l	0	0	0	0	0
		Bulyl benzyl phthalate	EPA625	0.3	ug/l	0	0	0	0	0
		2-Chloronaphthalene	EPA625	0.1	ug/l	0	0	0	0	0
		4-Chlorophenyl phenyl ether	EPA625	0.1	ug/l	0	0	0	0	0
		Chrysene	EPA625	0.1	ug/l	0	0	0	0	0
		Dibenzo(a,h)anthracene	EPA625	0.1	ug/l	0	0	0	0	0
		1,3-Dichlorobenzene	EPA625	0.05	ug/l	0	0	0	0	0
		1,4-Dichlorobenzene	EPA625	0.05	ug/l	0	0	0	0	0
		1,2-Dichlorobenzene	EPA625	0.05	ug/l	0	0	0	0	0
		3,3-Dichlorobenzidine	EPA625	3	ug/l	0	0	0	0	0
		Diethyl phthalate	EPA625	0.5	ug/l	0	0	0.7	0	0
		Dimethyl phthalate	EPA625	0.5	ug/l	0	0	0	0	0
		di-n-Bulyl phthalate	EPA625	1	ug/l	0	0	0	6.4	0
		2,4-Dinitrotoluene	EPA625	0.05	ug/l	0	0	0	0	0
		2,6-Dinitrotoluene	EPA625	0.05	ug/l	0	0	0	0	0
		4,6 Dinitro-2-methylphenol	EPA625	3	ug/l	0	0	6.6	0	0
		1,2-Diphenylhydrazine	EPA625	3	ug/l	0	0	0	0	0
		di-n-Octyl phthalate	EPA625	1	ug/l	0	0	0	0	0
		Fluoranthene	EPA625	0.1	ug/l	0	0	0	0	0
		Fluorene	EPA625	0.1	ug/l	0	0	0	0	0
		Hexachlorobenzene	EPA625	0.5	ug/l	0	0	0	0	0
		Hexachlorobutadiene	EPA625	1	ug/l	0	0	0	0	0
		Hexachlorocyclopentadiene	EPA625	3	ug/l	0	0	0	0	0
		Hexachloroethane	EPA625	1	ug/l	0	0	0	0	0
		Indeno(1,2,3-cd)pyrene	EPA625	0.1	ug/l	0	0	0	0	0
		Isochlorone	EPA625	0.05	ug/l	0	0	0	0	0
		Naphthalene	EPA625	0.05	ug/l	0	0	0	0	0
		Nitrobenzene	EPA625	0.05	ug/l	0	0	0	0	0
		N-Nitroso-dimethyl amine	EPA625	0.3	ug/l	0	0	0	0	0
		N-Nitroso-diphenyl amine	EPA625	0.3	ug/l	0	0	0	0	0
		N-Nitroso-di-n-propyl amine	EPA625	0.3	ug/l	0	0	0	0	0
		Phenanthrene	EPA625	0.05	ug/l	0	0	0	0	0
		Pyrene	EPA625	0.05	ug/l	0	0	0	0	0
Chlorinated Pesticides										
		1,2,4-Trichlorobenzene	EPA625	0.5	ug/l	0	0	0	0	0
		Aldrin	EPA625	0.05	ug/l	0	0	0	0	0
		alpha-BHC	EPA625	0.05	ug/l	0	0	0	0	0
		beta-BHC	EPA625	0.05	ug/l	0	0	0	0	0
		delta-BHC	EPA625	0.05	ug/l	0	0	0	0	0
		gamma-BHC (lindane)	EPA625	0.05	ug/l	0	0	0	0	0
		alpha-chlordane	EPA625	0.05	ug/l	0	0	0	0	0
		gamma-chlordane	EPA625	0.05	ug/l	0	0	0	0	0

## Appendix B. 2003-2004 Sampling Results for Coyote Creek

## Mass Emission Monitoring

WEATHER CONDITION		Wet			Dry	
STATION NO.	STATION NAME	S13 Coyote Creek 0304-01 10/31/2003	S13 Coyote Creek 0304-02 12/25/2003	S13 Coyote Creek 0304-03 1/1/2004	S13 Coyote Creek 0304-01 10/28/2003	S13 Coyote Creek 0304-02 1/13/2004
EVENT NO.	DATE					
Sample Type	EPA Method	PQL	Units			
4,4'-DDD	Comp EPA625	0.1	ug/l	0	0	0
4,4'-DDE	Comp EPA625	0.1	ug/l	0	0	0
4,4'-DDT	Comp EPA625	0.1	ug/l	0	0	0
Dieldrin	Comp EPA625	0.1	ug/l	0	0	0
alpha-Endosulfan	Comp EPA625	0.1	ug/l	0	0	0
beta-Endosulfan	Comp EPA625	0.1	ug/l	0	0	0
Endosulfan sulfate	Comp EPA625	0.1	ug/l	0	0	0
Endrin	Comp EPA625	0.1	ug/l	0	0	0
Endrin aldehyde	Comp EPA625	0.1	ug/l	0	0	0
Heptachlor	Comp EPA625	0.05	ug/l	0	0	0
Heptachlor Epoxide	Comp EPA625	0.05	ug/l	0	0	0
Toxaphene	Comp EPA625	1	ug/l	0	0	0
Polychlorinated Biphenyls						
Aroclor-1016	Comp EPA608	0.5	ug/l	0	0	0
Aroclor-1221	Comp EPA608	0.5	ug/l	0	0	0
Aroclor-1232	Comp EPA608	0.5	ug/l	0	0	0
Aroclor-1242	Comp EPA608	0.5	ug/l	0	0	0
Aroclor-1248	Comp EPA608	0.5	ug/l	0	0	0
Aroclor-1254	Comp EPA608	0.5	ug/l	0	0	0
Aroclor-1260	Comp EPA608	0.5	ug/l	0	0	0
Organophosphate Pesticides						
Chlorpyrifos	Comp EPA507	0.05	ug/l	0	0	0
Diazinon	Comp EPA507	0.01	ug/l	0	0.104	0.181
Promethyn	Comp EPA507	2	ug/l	0	0	0
Atrazine	Comp EPA507	2	ug/l	0	0	0
Simazine	Comp EPA507	2	ug/l	0	0	0
Cyanazine	Comp EPA507	2	ug/l	0	0	0
Malathion	Comp EPA507	2	ug/l	0	0	0
Herbicides						
Glyphosate	Comp EPA547	25	ug/l	0	0	0
2,4-D	Comp EPA515.3	10	ug/l	0	0	0
2,4,5-TP-SILVEX	Comp EPA515.3	1	ug/l	0	0	0

## Note:

- 1) blank cell indicates sample was not analyzed
- 2) 0 indicates concentration below minimum detection level
- 3) PQL = minimum level
- 4) Highlighted cells show exceedances

Appendix B - 2003-2004 Sampling Results for San Gabriel River

Mass Emission Monitoring

WEATHER CONDITION				Wet				Dry			
STATION NO.				S14		S14		S14		S14	
STATION NAME				San Gabriel River		San Gabriel River		San Gabriel River		San Gabriel River	
EVENT NO.				0304-01		0304-02		0304-03		0304-01	
DATE				10/31/2003		12/25/2003		1/1/2004		10/28/2003	
Conventional	Sample Type	EPA Method	POL	Units							
Oil and Grease	Grab	EPA413.1	1	mg/L	0	0	0	0	0	0	3.3
Total Phenols	Grab	EPA420.1	0.1	mg/L	0	0	0	0	0	0	0
Cyanide	Grab	EPA35.2	0.01	mg/L	0.012	0.022	0.015	0.023	0.023	0.023	0
pH	Comp	SM4500 B	0-14		8.17	7.68	7.64	7.49	7.92	7.92	7.92
Dissolved Oxygen	Grab	SM4500 G	1	mg/L	9.56	9.02	10.68	8.52	10.38	10.38	10.38
Indicator Bacteria											
Total Coliform	Grab	SM9230B	20	MPN/100ml	30000	170000	3000	30000	13000	13000	13000
Fecal Coliform	Grab	SM9230B	20	MPN/100ml	500	130000.00	270	110.00	500.00	500.00	500.00
Ratio Fecal Coliform/Total Coliform	Grab	SM9230B	20	MPN/100ml	0.02	0.76	0.09	0.00	0.04	0.04	0.04
Fecal Streptococcus	Grab	SM9230B	20	MPN/100ml	1300	22000	1300	700	700	300	300
Fecal Enterococcus	Grab	SM9230B	20	MPN/100ml	1300	17000	800	700	700	170	170
General											
Chloride	Comp	EPA300.0	2	mg/L	153	123	132	147	111	111	111
Fluoride	Comp	EPA300.0	0.1	mg/L	0.32	0.17	0.17	0.23	0.11	0.11	0.11
Nitrate	Comp	EPA300.0	0.1	mg/L	24.6	32.4	36.3	31.5	10.3	10.3	10.3
Sulfate	Comp	EPA300.0	0.1	mg/L	191	186	174	132	121	121	121
Alkalinity	Comp	EPA310.1	4	mg/L	140.8	169	152	112	107	107	107
Hardness	Comp	EPA130.2	2	mg/L	260	320	305	210	195	195	195
COD	9l	EPA410.4	10	mg/L	103.5	45.3	44.5	40.7	31.7	31.7	31.7
TPH	Grab	EPA418.1	1	mg/L	0	0	0	0	0	0	0
Specific Conductance	Comp	EPA120.1	1	umhos/cm	1116	1167	1107	1008	733	733	733
Total Dissolved Solids	Comp	EPA160.1	2	mg/L	706	716	682	594	450	450	450
Turbidity	Comp	EPA180.1	0.1	NTU	0.35	30	1.16	0.5	0.2	0.2	0.2
Total Suspended Solids	Comp	EPA160.2	2	mg/L	10	29	80	6	23	23	23
Volatile Suspended Solids	Comp	EPA160.4	1	mg/L	4	10	14	2	11	11	11
MBAS	Comp	EPA425.1	0.05	mg/L	0.061	0.052	0.07	0.054	0.05	0.05	0.05
Total Organic Carbon	Comp	EPA415.1	1	mg/L	8.69	5.49	5.81	6.75	5.42	5.42	5.42
BOD	Comp	SM6210B	2	mg/L	16.7	5.87	14.8	3.4	3.93	3.93	3.93
Nutrients											
Dissolved Phosphorus	Comp	EPA365.3	0.05	mg/L	0.09	0.54	0.35	0.13	0.09	0.09	0.09
Total Phosphorus	Comp	EPA365.3	0.05	mg/L	0.11	0.65	0.38	0.14	0.11	0.11	0.11
NH3-N	Comp	EPA350.3	0.1	mg/L	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Nitrate-N	Comp	SM4110B	0.5	mg/L	5.55	7.32	8.20	7.11	2.33	2.33	2.33
Nitrite-N	Comp	SM4110B	0.03	mg/L	0.76	0.48	0.44	1.93	0.37	0.37	0.37
Kjeldahl-N	Comp	EPA351.4	0.1	mg/L	0.95	1.71	0.77	0.64	0.17	0.17	0.17
Metals											
Dissolved Aluminum	Comp	EPA200.8	100	ug/l	0	0	0	0	0	0	0
Total Aluminum	Comp	EPA200.8	100	ug/l	198	258	178	0	0	0	0
Dissolved Antimony	Comp	EPA200.8	5	ug/l	0.529	0	0.6	0	0	0	0
Total Antimony	Comp	EPA200.8	5	ug/l	0.529	0	0.74	0	0.88	0.88	0.88
Dissolved Arsenic	Comp	EPA200.8	5	ug/l	0	1.52	1.44	1.01	1.67	1.67	1.67
Total Arsenic	Comp	EPA200.8	5	ug/l	1.05	1.58	1.55	1.01	1.88	1.88	1.88
Dissolved Beryllium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0	0
Total Beryllium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0	0
Dissolved Cadmium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0	0
Total Cadmium	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0	0
Dissolved Chromium	Comp	EPA200.8	5	ug/l	0.807	1.19	3.81	5.93	0	0	0
Total Chromium	Comp	EPA200.8	5	ug/l	0.807	4.76	4.74	14.6	0.86	0.86	0.86
Dissolved Chromium +6	Comp	EPA200.8	10	ug/l	0	0	0	0	0	0	0
Total Chromium +6	Comp	EPA200.8	10	ug/l	0	0	0	0	0	0	0
Dissolved Copper	Comp	EPA200.8	5	ug/l	2.21	4.3	5.95	4.96	4.86	4.86	4.86
Total Copper	Comp	EPA200.8	5	ug/l	12.5	16	10.5	13.9	10.7	10.7	10.7
Dissolved Iron	Comp	EPA200.8	100	ug/l	0	115	102	0	0	0	0
Total Iron	Comp	EPA200.8	100	ug/l	160	423	320	150	0	0	0
Dissolved Lead	Comp	EPA200.8	5	ug/l	0	0.92	1.46	0	0	0	0
Total Lead	Comp	EPA200.8	5	ug/l	3.34	1.72	2.14	1.04	0.72	0.72	0.72
Dissolved Mercury	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0	0
Total Mercury	Comp	EPA200.8	1	ug/l	0	0	0.234	0	0	0	0
Dissolved Nickel	Comp	EPA200.8	5	ug/l	3.7	4.97	5.62	4.61	3.47	3.47	3.47
Total Nickel	Comp	EPA200.8	5	ug/l	7.32	6.36	6.66	5.37	3.62	3.62	3.62
Dissolved Selenium	Comp	EPA200.8	5	ug/l	2.52	2.3	1.55	1.55	1.54	1.54	1.54
Total Selenium	Comp	EPA200.8	5	ug/l	2.69	2.39	2.58	1.55	1.65	1.65	1.65
Dissolved Silver	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0	0
Total Silver	Comp	EPA200.8	1	ug/l	0	0	0	0	0	0	0
Dissolved Thallium	Comp	EPA200.8	5	ug/l	0	0	0	0	0	0	0
Total Thallium	Comp	EPA200.8	5	ug/l	0	0	0	0	0	0	0
Dissolved Zinc	Comp	EPA200.8	50	ug/l	26.9	46	42	36.8	13	13	13
Total Zinc	Comp	EPA200.8	50	ug/l	64.5	61	67	36.8	33	33	33

## Appendix B. 2003-2004 Sampling Results for San Gabriel River

## Mass Emission Monitoring

WEATHER CONDITION STATION NAME EVENT NO. DATE	Wet			Dry	
	S14 San Gabriel River 0304-01 10/31/2003	S14 San Gabriel River 0304-02 12/25/2003	S14 San Gabriel River 0304-03 1/1/2004	S14 San Gabriel River 0304-01 10/28/2003	S14 San Gabriel River 0304-02 3/7999
Sample Type	EPA Method	PQL	Units		
<b>Semi-Volatiles Organics (EPA 625)</b>					
2-Chlorophenol	Comp EPA625	2	ug/l	0	0
2,4-dichlorophenol	Comp EPA625	2	ug/l	0	0
2,4-dimethylphenol	Comp EPA625	2	ug/l	0	0
2,4-dinitrophenol	Comp EPA625	3	ug/l	0	0
2-nitrophenol	Comp EPA625	3	ug/l	0	0
4-nitrophenol	Comp EPA625	3	ug/l	0	0
4-chloro_3_methylphenol	Comp EPA625	3	ug/l	0	0
Pentachlorophenol	Comp EPA625	2	ug/l	0	0
Phenol	Comp EPA625	1	ug/l	0	0
2,4,6-trichlorophenol	Comp EPA625	1	ug/l	0	2.1
<b>Base/Neutral</b>					
Acenaphthene	Comp EPA625	0.05	ug/l	0	0
Acenaphthylene	Comp EPA625	0.05	ug/l	0	0
Anthracene	Comp EPA625	0.05	ug/l	0	0
Benzidine	Comp EPA625	3	ug/l	0	0
1,2-Benzanthracene	Comp EPA625	0.1	ug/l	0	0
Benz(a)pyrene	Comp EPA625	0.1	ug/l	0	0
Benzo(k)fluoranthene	Comp EPA625	0.1	ug/l	0	0
Bis(2-Chloroethoxy) methane	Comp EPA625	0.1	ug/l	0	0
Bis(2-Chloroisopropyl) ether	Comp EPA625	1	ug/l	0	0
Bis(2-Chloroethyl) ether	Comp EPA625	0.1	ug/l	0	0
Bis(2-Ethylhexyl) phthalate	Comp EPA625	1	ug/l	42.4	19.8
4-Biomophenyl phenyl ether	Comp EPA625	1	ug/l	43.4	18.7
Buyl benzyl phthalate	Comp EPA625	0.3	ug/l	0	0
2-Chloronaphthalene	Comp EPA625	0.1	ug/l	0	0
4-Chlorophenyl phenyl ether	Comp EPA625	0.1	ug/l	0	0
Chrysene	Comp EPA625	0.1	ug/l	0	0
Dibenz(a,h)anthracene	Comp EPA625	0.1	ug/l	0	0
1,3-Dichlorobenzene	Comp EPA625	0.05	ug/l	0	0
1,4-Dichlorobenzene	Comp EPA625	0.05	ug/l	0	0
1,2-Dichlorobenzene	Comp EPA625	0.05	ug/l	0	0
3,3-Dichlorobenzidine	Comp EPA625	0.05	ug/l	0	0
Diethyl phthalate	Comp EPA625	3	ug/l	0	0
Dimethyl phthalate	Comp EPA625	0.5	ug/l	9.5	0
di-n-Buyl phthalate	Comp EPA625	1	ug/l	1	3.1
2,4-Dinitrotoluene	Comp EPA625	0.05	ug/l	0	7.2
2,6-Dinitrotoluene	Comp EPA625	0.05	ug/l	0	0
4,6 Dinitro-2-methylphenol	Comp EPA625	3	ug/l	0	0
1,2-Diphenylhydrazine	Comp EPA625	3	ug/l	0	0
di-n-Octyl phthalate	Comp EPA625	1	ug/l	0	0
Fluoranthene	Comp EPA625	0.1	ug/l	0	0
Fluorene	Comp EPA625	0.1	ug/l	0	0
Hexachlorobenzene	Comp EPA625	0.5	ug/l	0	0
Hexachlorobutadiene	Comp EPA625	1	ug/l	0	0
Hexachloro-cyclopentadiene	Comp EPA625	3	ug/l	0	0
Hexachloroethane	Comp EPA625	1	ug/l	0	0
Indenol (1,2,3-cd)pyrene	Comp EPA625	1	ug/l	0	0
Isophorone	Comp EPA625	0.1	ug/l	0	0
Naphthalene	Comp EPA625	0.05	ug/l	0	0
Nitrobenzene	Comp EPA625	0.05	ug/l	0	0
N-Nitroso-dimethyl amine	Comp EPA625	0.3	ug/l	0	0
N-Nitroso-diphenyl amine	Comp EPA625	0.3	ug/l	0	0
N-Nitroso-di-n-propyl amine	Comp EPA625	0.3	ug/l	0	0
Phenanthrene	Comp EPA625	0.05	ug/l	0	0
Pyrene	Comp EPA625	0.05	ug/l	0	0
1,2,4-Trichlorobenzene	Comp EPA625	0.5	ug/l	0	0
<b>Chlorinated Pesticides</b>					
Aldrin	Comp EPA625	0.05	ug/l	0	0
alpha-BHC	Comp EPA625	0.05	ug/l	0	0
beta-BHC	Comp EPA625	0.05	ug/l	0	0
delta-BHC	Comp EPA625	0.05	ug/l	0	0
gamma-BHC (lindane)	Comp EPA625	0.05	ug/l	0	0
alpha-chlordane	Comp EPA625	0.05	ug/l	0	0
gamma-chlordane	Comp EPA625	0.05	ug/l	0	0
4,4'-DDD	Comp EPA625	0.1	ug/l	0	0
4,4'-DDE	Comp EPA625	0.1	ug/l	0	0
4,4'-DDT	Comp EPA625	0.1	ug/l	0	0
Dieldrin	Comp EPA625	0.1	ug/l	0	0

## Appendix B. 2003-2004 Sampling Results for San Gabriel River

## Mass Emission Monitoring

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE	Wet			Dry	
	S14 San Gabriel River 0304-01 10/31/2003	S14 San Gabriel River 0304-02 12/25/2003	S14 San Gabriel River 0304-03 1/11/2004	S14 San Gabriel River 0304-01 10/28/2003	S14 San Gabriel River 0304-02 3/7999
Sample Type	EPA Method	PQL	Units		
alpha-Endosulfan	Comp EPA625	0.1	ug/l	0	0
beta-Endosulfan	Comp EPA625	0.1	ug/l	0	0
Endosulfan sulfate	Comp EPA625	0.1	ug/l	0	0
Endrin	Comp EPA625	0.1	ug/l	0	0
Endrin aldehyde	Comp EPA625	0.1	ug/l	0	0
Heptachlor	Comp EPA625	0.05	ug/l	0	0
Heptachlor Epoxide	Comp EPA625	0.05	ug/l	0	0
Toxaphene	Comp EPA625	1	ug/l	0	0
Polychlorinated Biphenyls					
Aroclor-1016	Comp EPA608	0.5	ug/l	0	0
Aroclor-1221	Comp EPA608	0.5	ug/l	0	0
Aroclor-1232	Comp EPA608	0.5	ug/l	0	0
Aroclor-1242	Comp EPA608	0.5	ug/l	0	0
Aroclor-1248	Comp EPA608	0.5	ug/l	0	0
Aroclor-1254	Comp EPA608	0.5	ug/l	0	0
Aroclor-1260	Comp EPA608	0.5	ug/l	0	0
Organophosphate Pesticides					
Chlorpyrifos	Comp EPA507	0.05	ug/l	0	0
Diazinon	Comp EPA507	0.01	ug/l	0	0
Promethyn	Comp EPA507	2	ug/l	0	0
Atrazine	Comp EPA507	2	ug/l	0	0
Simazine	Comp EPA507	2	ug/l	0	0
Cyanazine	Comp EPA507	2	ug/l	0	0
Malathion	Comp EPA507	2	ug/l	0	0
Herbicides					
Glyphosate	Comp EPA547	25	ug/l	0	0
2,4-D	Comp EPA515.3	10	ug/l	0	0
2,4,5-TP-SILVEX	Comp EPA515.3	1	ug/l	0	0

- Note:  
 1) blank cell indicates sample was not analyzed  
 2) 0 indicates concentration below minimum detection level  
 3) PQL = minimum level  
 4) Highlighted cells show exceedances

**Table C-1. Water Quality Results for Constituents Measured at the San Gabriel River Mass Emission Site for the 2004-2005 Monitoring Season.**

CONSTITUENT	PQL	UNITS	Water Quality Objectives				Wet Weather Monitoring <sup>2</sup>				Dry Weather Monitoring <sup>2</sup>	
			Ocean Plan	Basin Plan	Freshwater CTR (CCC) <sup>1</sup>	Freshwater CTR (CMC) <sup>1</sup>	10/17/2004	10/26/2004	12/5/2004	1/7/2005	3/17/2005	6/21/2005
General Chemistry												
Cyanide	0.01	mg/L	0.004				0.010	0.000	0.000	0.000	0.008	0.013
pH		mg/L		6.5<pH<8.5			7.04	7.42	7.29	7.52	8.18	8.04
TPH	1						0.00	0.00	0.00	0.00	0.00	0.00
Oil and Grease	1	mg/L	75				0.00	0.00	0.00	0.00	0.00	0.00
Total Phenols	0.1	mg/L					0.00	9.10	0.00	0.00	0.00	0.00
Dissolved Oxygen	1	mg/L		<5			8.40		8.91	10.40	11.72	7.30
Calcium	1	mg/L					56.90	35.30	29.70	32.10	80.00	84.20
Magnesium	1	mg/L					16.00	10.20	13.60	10.70	34.00	29.20
Potassium	1	mg/L					9.95	5.10	4.47	3.75	12.50	11.70
Sodium	1	mg/L					34.40	25.70	42.30	23.00	118.00	110.00
Bicarbonate	2	mg/L					168.00	87.20	89.90		0.00	
Carbonate	2	mg/L					0.00	0.00	0.00	0.00	0.00	0.00
Chloride	2	mg/L		150			52.50	33.90	59.20	25.10	134.0	220.0
Fluoride	0.1	mg/L		2.2			0.36	0.18	0.13	0.18	0.40	0.26
Sulfate	0.1	mg/L		350			95.50	58.70	66.30	37.90	196.00	198.00
Alkalinity	0.1	mg/L					138.00	71.50	73.70	77.00	178.00	165.00
Hardness	2	mg/L					208	130	130	124	340	330
COD	10	mg/L					102.70	14.90	45.90	45.16	85.70	57.40
Specific Conductance	1	umhos/cm					598	391	451	337	1107	1072
Total Dissolved Solids	2	mg/L		1500			352	214	254	200	748	738
Turbidity	0.1	NTU	225				87.60	20.70	0.53	107.00	4.23	3.41
Total Suspended Solids	2	mg/L					723	48	18	1246	34	47
Volatile Suspended Solids	1	mg/L					140	11	6	69	15	10
MBAS	0.05	mg/L					0.31	0.07	0.00	0.00	0.06	0.06
Total Organic Carbon	1	mg/L					41.79	8.18	4.80	8.28	5.16	5.59
BOD	2	mg/L					59.70	6.79	4.58	3.30	21.00	30.60
Nutrients												
Dissolved Phosphorus	0.05	mg/L					0.27	0.19	0.10	0.10	0.00	0.00
Total Phosphorus	0.05	mg/L					0.62	0.30	0.15	0.77	0.11	0.12
Ammonia	0.1	mg/L					4.99	0.00	0.15	0.00	0.25	0.62
NH3-N	0.1	mg/L					4.12	0.00	0.12	0.00	0.21	0.51
Nitrate	0.1	mg/L					5.39	9.10	6.89	5.30	16.50	12.4
Nitrate-N	0.5	mg/L		10			1.22	2.05	1.56	1.20	3.73	2.80
Nitrite-N	0.03	mg/L		1			1.04	0.00	0.04	0.00	0.18	0.34
Kjeldahl-N	0.1	mg/L					15.30	1.49	0.89	1.87	1.37	0.64
Indicator Bacteria												
Total Coliform	20	MPN/100ml		10,000			1,400,000	240,000	240,000	17,000	17,000	9000
Fecal Coliform	20	MPN/100ml		400			140,000	17,000	90,000	2,800	170	40
Fecal Streptococcus	20	MPN/100ml					300,000	90,000	35,000	2,800	40	20
Enterococcus	20	MPN/100ml		104			300,000	90,000	35,000	1,700	40	20
Metals												
Dissolved Aluminum	100	ug/l					0.00	0.00	0.00	1215.00	0.00	0.00
Total Aluminum	100	ug/l		1000			260	776	1,240	16,100	175	0
Dissolved Antimony	5	ug/l					2.17	0.64	0.58	0.68	0.00	0.50
Total Antimony	5	ug/l		6			2.26	0.83	0.60	1.12	0.00	0.51
Dissolved Arsenic	5	ug/l					2.20	1.50	2.10	2.91	1.35	2.00
Total Arsenic	5	ug/l	32	50			2.34	1.73	2.54	6.74	1.75	2.27
Dissolved Barium	10	ug/l					36.70	29.10	32.70	95.50	51.40	50.30
Total Barium	10	ug/l					49.70	32.10	63.10	257.00	51.60	51.00
Dissolved Beryllium	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Beryllium	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dissolved Boron	100	ug/l					530	150	108	137	348	351
Total Boron	100	ug/l					710	940	126	152	674	378
Dissolved Cadmium	1	ug/l			2.7-4.0	5.4-9.4	0.00	0.00	0.00	0.33	0.00	0.00
Total Cadmium	1	ug/l			2.9-4.4	5.8-10.3	0.00	0.00	0.00	0.82	0.00	0.00
Dissolved Chromium	5	ug/l			78.0-9119.2	680.3-999.7	1.26	1.08	1.74	0.70	0.56	12.60
Total Chromium	5	ug/l		50	246.9-377.1	2071.1-3163.5	1.87	2.68	4.91	19.20	1.42	18.80

**Table C-1. Water Quality Results for Constituents Measured at the San Gabriel River Mass Emission Site for the 2004-2005 Monitoring Season.**

CONSTITUENT	PQL	UNITS	Water Quality Objectives				Wet Weather Monitoring <sup>2</sup>				Dry Weather Monitoring <sup>2</sup>	
			Ocean Plan	Basin Plan	Freshwater CTR (CCC) <sup>1</sup>	Freshwater CTR (CMC) <sup>1</sup>	10/17/2004	10/26/2004	12/5/2004	1/7/2005	3/17/2005	6/21/2005
Dissolved Chromium +6	10	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Chromium +6	10	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dissolved Copper	5	ug/l			10.8-16.8	16.4-26.8	6.16	5.36	3.57	10.20	4.59	3.59
Total Copper	5	ug/l	12		11.2-17.4	17.1-27.9	22.50	12.70	32.20	37.90	9.05	11.00
Dissolved Iron	100	ug/l					203	0	0	849	0	0
Total Iron	100	ug/l					896	1,340	1,950	15,050	104	119
Dissolved Lead	5	ug/l			3.2-5.5	81.6-141.9	0.00	0.00	0.00	11.40	0.00	0.00
Total Lead	5	ug/l	8		4.2-8.1	107.4-207.4	3.78	4.42	9.05	37.50	1.17	1.07
Dissolved Manganese	30	ug/l					0.00	0.00	0.00	79.40	0.00	0.00
Total Manganese	30	ug/l					165.00	32.40	48.30	648.00	0.00	52.10
Dissolved Mercury	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Mercury	1	ug/l	0.16	2			0.25	0.00	0.00	0.00	0.00	0.00
Dissolved Nickel	5	ug/l			65.0-96.7	561.7-870.1	9.43	3.50	2.18	2.71	5.32	5.13
Total Nickel	5	ug/l	20	100	65.1-96.9	562.8-871.8	11.30	4.99	6.66	18.30	5.36	5.82
Dissolved Selenium	5	ug/l					1.79	0.00	1.03	0.00	2.56	3.58
Total Selenium	5	ug/l	60	50			2.02	0.00	1.06	0.00	3.58	3.71
Dissolved Silver	1	ug/l				5.0-12.2	0.00	0.00	0.00	0.00	0.00	0.00
Total Silver	1	ug/l	80			5.9-14.3	0.00	0.00	0.00	0.00	0.00	0.00
Dissolved Thallium	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Thallium	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dissolved Zinc	50	ug/l			140.6-218.0	140.6-218.0	32.20	10.30	15.90	17.70	22.80	9.49
Total Zinc	50	ug/l			143.8-222.9	143.8-222.9	49.60	24.60	69.30	90.70	33.40	21.80
Semi-Volatiles												
Acenaphthylene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Acetophenone	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Anthracene	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Antracene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Aminobiphenyl	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzidine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzo(a)anthracene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzo(b)fluoranthene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzo(k)fluoranthene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzo(a)pyrene	0.1	ug/l		0.2			0.00	0.00	0.00	0.00	0.00	0.00
Butyl benzyl phthalate	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Bis(2-chloroethyl)ether	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Bis(2-Chloroethoxy) methane	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Bis(2-Ethylhexyl) phthalate	1	ug/l					0.00	0.00	0.00	0.00	26.70	0.00
Bis(2-chlorisopropyl) ether	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-Bromophenyl phenyl ether	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Chloroaniline	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1-Chloronaphthalene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Chloronaphthalene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-Chlorophenyl phenyl ether	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Chrysene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dimethyl phthalate	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
7,12-Dimethyl-benz(a)-anthracene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
alpha,alpha-Dimethylphenethylamine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dibenz(a,j)acridine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dibenzo(a,h)anthracene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,3-Dichlorobenzene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,2-Dichlorobenzene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,4-Dichlorobenzene	0.05	ug/l		5			0.00	0.00	0.00	0.00	0.00	0.00
3,3-Dichlorobenzidine	0.05	ug/l		600			0.00	0.00	0.00	0.00	0.00	0.00
Diethyl phthalate	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dimethyl phthalate	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
di-n-Butyl phthalate	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4-Dinitrotoluene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,6-Dinitrotoluene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Diphenylamine	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,2-Diphenylhydrazine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00

**Table C-1. Water Quality Results for Constituents Measured at the San Gabriel River Mass Emission Site for the 2004-2005 Monitoring Season.**

CONSTITUENT	PQL	UNITS	Water Quality Objectives				Wet Weather Monitoring <sup>2</sup>				Dry Weather Monitoring <sup>2</sup>	
			Ocean Plan	Basin Plan	Freshwater CTR (CCC) <sup>1</sup>	Freshwater CTR (CMC) <sup>1</sup>	10/17/2004	10/26/2004	12/5/2004	1/7/2005	3/17/2005	6/21/2005
di-n-Octyl phthalate	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Ethyl methanesulfonate	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Endrin ketone	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Fluoranthene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Fluorene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Hexachlorobenzene	0.5	ug/l		1			0.00	0.00	0.00	0.00	0.00	0.00
Hexachlorobutadiene	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Hexachloro-cyclopentadiene	3	ug/l		50			0.00	0.00	0.00	0.00	0.00	0.00
Hexachloroethane	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Indeno(1,2,3-cd)pyrene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Isophorone	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Methylcholanthrene	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Methylmethanesulfonate	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Naphthalene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1-Naphthylamine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Naphthylamine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Nitroaniline	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
3-Nitroaniline	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-Nitroaniline	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Nitrobenzene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitroso-butyl amine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitroso-dimethyl amine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitroso-diphenyl amine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitroso-di-n-propyl amine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitrosopiperidine	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Pentachlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Phenacetin	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Phenanthrene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Picoline	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Pronamide	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Pyrene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,2,4,5-Tetra-chlorobenzene	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,2,4-Trichlorobenzene	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzoic acid	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-chloro-3-methylphenol	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-chloro-3-methylphenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Chlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4-dichlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,6-Dichlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4-dimethylphenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4-dinitrophenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4,6 Dinitro-2-methylphenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Methylphenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-Methylphenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-nitrophenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-nitrophenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Pentachlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Phenol	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,3,4,6-Tetrachlorophenol	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4,5-Trichlorophenol	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4,6-trichlorophenol	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
PCBs												
Aroclor-1016	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1221	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1232	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1242	0.5	ug/l		0.03		0.014	0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1248	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1254	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1260	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00

**Table C-1. Water Quality Results for Constituents Measured at the San Gabriel River Mass Emission Site for the 2004-2005 Monitoring Season.**

CONSTITUENT	PQL	UNITS	Water Quality Objectives				Wet Weather Monitoring <sup>2</sup>				Dry Weather Monitoring <sup>2</sup>	
			Ocean Plan	Basin Plan	Freshwater CTR (CCC) <sup>1</sup>	Freshwater CTR (CMC) <sup>1</sup>	10/17/2004	10/26/2004	12/5/2004	1/7/2005	3/17/2005	6/21/2005
Pesticides												
Aldrin	0.05	ug/l				3	0.00	0.00	0.00	0.00	0.00	0.00
alpha-BHC	0.05	ug/l	0.008				0.00	0.00	0.00	0.00	0.00	0.00
beta-BHC	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
delta-BHC	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
gamma-BHC (lindane)	0.05	ug/l		0.2		0.95	0.00	0.00	0.00	0.00	0.00	0.00
Chlordane	0.05	ug/l			0.0043	2.4	0.00	0.00	0.00	0.00	0.00	0.00
4,4'-DDD	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4,4'-DDE	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4,4'-DDT	0.1	ug/l			0.001	1.1	0.00	0.00	0.00	0.00	0.00	0.00
Dieldrin	0.1	ug/l			0.056	0.24	0.00	0.00	0.00	0.00	0.00	0.00
Endosulfan 1	0.1	ug/l	0.018		0.056	0.22	0.00	0.00	0.00	0.00	0.00	0.00
Endosulfan 2	0.1	ug/l				0.056	0.22	0.00	0.00	0.00	0.00	0.00
Endosulfan sulfate	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Endrin	0.1	ug/l	0.004	2	0.036	0.086	0.00	0.00	0.00	0.00	0.00	0.00
Endrin aldehyde	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Heptachlor	0.05	ug/l		0.01	0.0038	0.52	0.00	0.00	0.00	0.00	0.00	0.00
Heptachlor Epoxide	0.05	ug/l		0.01	0.0038	0.52	0.00	0.00	0.00	0.00	0.00	0.00
Methoxychlor	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Toxaphene	1	ug/l		3	0.0002	0.73	0.00	0.00	0.00	0.00	0.00	0.00
Diazinon	0.01	ug/l		0.08			0.096	0.100	0.051	0.00	0.00	0.00
Chlorpyrifos	0.05	ug/l		0.07			0.00	0.00	0.00	0.00	0.00	0.00
Diuron	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Malathion	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Prometryn	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Simazine	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Atrazine	2	ug/l		3			0.00	0.00	0.00	0.00	0.00	0.00
Cyanazine	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Molinate	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Thiobencarb	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Herbicides												
Carbofuran	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4,5-TP-Silvex	10	ug/l		70			0.00	0.00	0.00	0.00	0.00	0.00
2,4,5-TP	1	ug/l		50			0.00	0.00	0.00	0.00	0.00	0.00
Bentazon	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Glyphosate	25	ug/l		700			0.00	0.00	0.00	0.00	0.00	0.00

<sup>1</sup> CTR values for metals are hardness dependent; higher hardness gives higher WQO

<sup>2</sup> Values of 0 represent that the constituent was not detected above the PQL as defined in the Municipal Stormwater Permit. Results are presented in accordance with Method B of the permit

**Table C-2. Water Quality Results for Constituents Measured at the Coyote Creek Mass Emission Site for the 2004-2005 Monitoring Season.**

CONSTITUENT	PQL	UNITS	Water Quality Objectives				Wet Weather Monitoring <sup>2</sup>				Dry Weather Monitoring <sup>2</sup>	
			Ocean Plan	Basin Plan	Freshwater CTR (CCC) <sup>1</sup>	Freshwater CTR (CMC) <sup>1</sup>	10/17/2004	10/26/2004	12/5/2004	1/7/2005	11/16/2004	3/9/2005
General Chemistry												
Cyanide	0.01	mg/L	0.004				0.005	1.300	0.007	0.000	0.015	0.009
pH		mg/L		6.5<pH<8.5			7.18	6.61	6.79	6.94	8.18	8.30
TPH	1						0.00	0.00	0.00	0.00	0.00	0.00
Oil and Grease	1	mg/L	75				0.00	0.00	0.00	0.00	0.00	0.00
Total Phenols	0.1	mg/L					0.00	9.66	0.00	0.00	0.00	0.00
Dissolved Oxygen	1	mg/L		<5			6.83		9.30	9.20	15.19	10.90
Calcium	1	mg/L					56.10	12.00	29.70	12.80	96.20	120.00
Magnesium	1	mg/L					14.60	4.86	8.75	7.78	41.30	53.50
Potassium	1	mg/L					7.47	2.69	3.67	2.07	7.47	11.40
Sodium	1	mg/L					55.20	16.50	28.10	20.90	156.00	265.00
Bicarbonate	2	mg/L					195.00	40.30	84.50		326.00	0.00
Carbonate	2	mg/L					0.00	0.00	0.00	0.00	0.00	0.00
Chloride	2	mg/L		150			58.70	14.50	28.70	17.10	175.00	228.00
Fluoride	0.1	mg/L		2.2			0.37	0.11	0.16	0.00	0.69	0.90
Sulfate	0.1	mg/L		350			96.30	16.80	44.70	23.70	293.00	492.00
Alkalinity	0.1	mg/L					160.00	33.00	69.30	40.70	267.00	283.00
Hardness	2	mg/L					200	50	110	64	410	520
COD	10	mg/L					117.90	11.30	79.70	18.72	27.40	88.40
Specific Conductance	1	umhos/cm					607	149	349	199	1545	1,923
Total Dissolved Solids	2	mg/L		1500			364	94	192	122	966	1,354
Turbidity	0.1	NTU	225				64.90	8.43	1.38	8.67	0.81	1.24
Total Suspended Solids	2	mg/L					1312	196	105	88	74	33
Volatile Suspended Solids	1	mg/L					233	58	38	3	20	9
MBAS	0.05	mg/L					0.29	0.13	0.07	0.00	0.00	0.00
Total Organic Carbon	1	mg/L					38.20	10.07	8.70	7.45	7.22	5.59
BOD	2	mg/L					59.80	12.80	14.40	5.18	32.90	8.85
Nutrients												
Dissolved Phosphorus	0.05	mg/L					0.11	0.19	0.17	0.12	0.09	0.00
Total Phosphorus	0.05	mg/L					0.38	0.26	0.29	0.25	0.13	0.00
Ammonia	0.1	mg/L					2.83	0.00	0.64	0.16	0.76	0.14
NH3-N	0.1	mg/L					2.34	0.00	0.53	0.13	0.63	0.11
Nitrate	0.1	mg/L					1.96	4.28	4.28	4.67	13.10	23.05
Nitrate-N	0.5	mg/L		10			0.44	0.97	0.97	0.15	2.96	5.21
Nitrite-N	0.03	mg/L		1			0.68	0.00	0.17	0.07	0.36	0.17
Kjeldahl-N	0.1	mg/L					12.20	2.24	2.24	1.31	1.29	0.99
Indicator Bacteria												
Total Coliform	20	MPN/100ml		10,000			900,000	1,600,000	500,000	500,000	30,000	9,000
Fecal Coliform	20	MPN/100ml		400			110,000	30,000	300,000	14,000	11,000	800
Fecal Streptococcus	20	MPN/100ml					900,000	900,000	170,000	50,000	1,700	130
Enterococcus	20	MPN/100ml		104			900,000	300,000	170,000	22,000	1,700	130
Metals												
Dissolved Aluminum	100	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Aluminum	100	ug/l		1000			170	1,061	1,560	1,360	0	148
Dissolved Antimony	5	ug/l					2.47	0.64	1.64	0.80	0.00	0.00
Total Antimony	5	ug/l		6			2.57	1.25	2.36	1.24	0.00	0.00
Dissolved Arsenic	5	ug/l					2.74	1.37	1.66	1.13	1.70	3.58
Total Arsenic	5	ug/l	32	50			2.87	1.39	2.16	1.48	1.70	4.02
Dissolved Barium	10	ug/l					44.00	19.40	26.00	17.70	40.10	71.10
Total Barium	10	ug/l					62.90	32.90	63.10	40.90	40.10	72.20
Dissolved Beryllium	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Beryllium	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dissolved Boron	100	ug/l					330	0	0	0	447	508
Total Boron	100	ug/l					680	960	0	0	1,450	662
Dissolved Cadmium	1	ug/l			1.4-6.6	2.0-19.6	0.00	0.00	0.00	0.00	0.00	0.00
Total Cadmium	1	ug/l			1.4-7.5	2.1-22.2	0.00	0.00	0.38	0.28	0.00	0.00
Dissolved Chromium	5	ug/l			37.1-207.7	311.0-1742.8	1.30	0.69	1.48	0.73	0.84	0.98
Total Chromium	5	ug/l		50	117.3-657.4	984.3-5515.0	1.92	3.48	5.35	3.97	0.84	2.69

**Table C-2. Water Quality Results for Constituents Measured at the Coyote Creek Mass Emission Site for the 2004-2005 Monitoring Season.**

CONSTITUENT	PQL	UNITS	Water Quality Objectives				Wet Weather Monitoring <sup>2</sup>				Dry Weather Monitoring <sup>2</sup>	
			Ocean Plan	Basin Plan	Freshwater CTR (CCC) <sup>1</sup>	Freshwater CTR (CMC) <sup>1</sup>	10/17/2004	10/26/2004	12/5/2004	1/7/2005	11/16/2004	3/9/2005
Dissolved Chromium +6	10	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Chromium +6	10	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dissolved Copper	5	ug/l			5.0-29.9	7.0-50.7	7.30	7.02	5.94	6.38	4.38	5.40
Total Copper	5	ug/l	12		5.2-31.2	7.3-52.8	23.30	16.80	44.50	22.50	11.20	11.70
Dissolved Iron	100	ug/l					156	0	0	136	0	0
Total Iron	100	ug/l					698	1,874	2,050	1,355	0	103
Dissolved Lead	5	ug/l			1.2-11	30.1-288.1	0.00	0.00	0.00	1.67	0.00	0.00
Total Lead	5	ug/l	8		1.3-19.2	33.8-492.0	3.24	7.31	14.70	13.50	2.15	1.48
Dissolved Manganese	30	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Manganese	30	ug/l					395.0	40.3	64.2	57.00	0.00	0.00
Dissolved Mercury	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Mercury	1	ug/l	0.16	2			0.00	0.00	0.00	0.00	0.00	0.00
Dissolved Nickel	5	ug/l			29.0-171.8	260.5-1544.8	10.00	3.26	3.07	2.18	3.82	4.22
Total Nickel	5	ug/l	20	100	29.0-172.1	261.0-1547.9	12.20	4.44	8.04	5.35	3.82	4.29
Dissolved Selenium	5	ug/l					1.69	0.00	0.00	0.00	2.94	7.78
Total Selenium	5	ug/l	60	50			1.76	0.00	0.00	0.00	2.94	9.29
Dissolved Silver	1	ug/l				1.1-39.1	0.00	0.00	0.00	0.00	0.00	0.00
Total Silver	1	ug/l	80			1.2-46.0	0.00	0.00	0.00	0.00	0.00	0.00
Dissolved Thallium	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Total Thallium	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dissolved Zinc	50	ug/l			65.1-387.3	65.1-387.3	24.70	36.10	36.60	31.00	11.40	7.60
Total Zinc	50	ug/l			66.6-396.0	66.6-396.0	47.00	65.80	153.00	79.30	24.50	27.60
Semi-Volatiles												
Acenaphthylene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Acetophenone	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Anthracene	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Antracene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Aminobiphenyl	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzidine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzo(a)anthracene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzo(b)fluoranthene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzo(k)fluoranthene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzo(a)pyrene	0.1	ug/l		0.2			0.00	0.00	0.00	0.00	0.00	0.00
Butyl benzyl phthalate	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Bis(2-chloroethyl)ether	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Bis(2-Chloroethoxy) methane	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Bis(2-Ethylhexyl) phthalate	1	ug/l					0.00	0.00	0.00	0.00	0.00	14.20
Bis(2-chlorisopropyl) ether	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-Bromophenyl phenyl ether	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Chloroaniline	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1-Chloronaphthalene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Chloronaphthalene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-Chlorophenyl phenyl ether	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Chrysene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dimethyl phthalate	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
7,12-Dimethyl-benz(a)-anthracene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
alpha, alpha-Dimethylphenethylamine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dibenz(a,j)acridine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dibenzo(a,h)anthracene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,3-Dichlorobenzene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,2-Dichlorobenzene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,4-Dichlorobenzene	0.05	ug/l		5			0.00	0.00	0.00	0.00	0.00	0.00
3,3-Dichlorobenzidine	0.05	ug/l		600			0.00	0.00	0.00	0.00	0.00	0.00
Diethyl phthalate	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Dimethyl phthalate	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
d-n-Butyl phthalate	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4-Dinitrotoluene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,6-Dinitrotoluene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Diphenylamine	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,2-Diphenylhydrazine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00

**Table C-2. Water Quality Results for Constituents Measured at the Coyote Creek Mass Emission Site for the 2004-2005 Monitoring Season.**

CONSTITUENT	PQL	UNITS	Water Quality Objectives				Wet Weather Monitoring <sup>2</sup>				Dry Weather Monitoring <sup>2</sup>	
			Ocean Plan	Basin Plan	Freshwater CTR (CCC) <sup>1</sup>	Freshwater CTR (CMC) <sup>1</sup>	10/17/2004	10/26/2004	12/5/2004	1/7/2005	11/16/2004	3/9/2005
di-n-Octyl phthalate	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Ethyl methanesulfonate	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Endrin ketone	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Fluoranthene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Fluorene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Hexachlorobenzene	0.5	ug/l		1			0.00	0.00	0.00	0.00	0.00	0.00
Hexachlorobutadiene	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Hexachloro-cyclopentadiene	3	ug/l		50			0.00	0.00	0.00	0.00	0.00	0.00
Hexachloroethane	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Indeno(1,2,3-cd)pyrene	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Isophorone	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Methylcholanthrene	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Methylmethanesulfonate	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Naphthalene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1-Naphthylamine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Naphthylamine	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Nitroaniline	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
3-Nitroaniline	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-Nitroaniline	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Nitrobenzene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitroso-butyl amine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitroso-dimethyl amine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitroso-diphenyl amine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitroso-di-n-propyl amine	0.3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
N-Nitrosopiperidine	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Pentachlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Phenacetin	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Phenanthrene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Picoline	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Pronamide	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Pyrene	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,2,4,5-Tetra-chlorobenzene	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
1,2,4-Trichlorobenzene	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Benzoic acid	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-chloro-3-methylphenol	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-chloro 3 methylphenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Chlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4-dichlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,6-Dichlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4-dimethylphenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4-dinitrophenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4,6 Dinitro-2-methylphenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-Methylphenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-Methylphenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2-nitrophenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
4-nitrophenol	3	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Pentachlorophenol	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
Phenol	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,3,4,6-Tetrachlorophenol	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4,5-Trichlorophenol	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00
2,4,6-trichlorophenol	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00

**Table C-2. Water Quality Results for Constituents Measured at the Coyote Creek Mass Emission Site for the 2004-2005 Monitoring Season.**

CONSTITUENT	PQL	UNITS	Water Quality Objectives				Wet Weather Monitoring <sup>2</sup>				Dry Weather Monitoring <sup>2</sup>		
			Ocean Plan	Basin Plan	Freshwater CTR (CCC) <sup>1</sup>	Freshwater CTR (CMC) <sup>1</sup>	10/17/2004	10/26/2004	12/5/2004	1/7/2005	11/16/2004	3/9/2005	
PCBs													
Aroclor-1016	0.5	ug/l		0.03	0.014		0.00	0.00	0.00	0.00	0.00	0.00	
Aroclor-1221	0.5	ug/l						0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1232	0.5	ug/l						0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1242	0.5	ug/l						0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1248	0.5	ug/l						0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1254	0.5	ug/l						0.00	0.00	0.00	0.00	0.00	0.00
Aroclor-1260	0.5	ug/l						0.00	0.00	0.00	0.00	0.00	0.00
Pesticides													
Aldrin	0.05	ug/l				3	0.00	0.00	0.00	0.00	0.00	0.00	
alpha-BHC	0.05	ug/l	0.008				0.00	0.00	0.00	0.00	0.00	0.00	
beta-BHC	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
delta-BHC	0.05	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
gamma-BHC (lindane)	0.05	ug/l		0.2		0.95	0.00	0.00	0.00	0.00	0.00	0.00	
Chlordane	0.05	ug/l			0.0043	2.4	0.00	0.00	0.00	0.00	0.00	0.00	
4,4'-DDD	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
4,4'-DDE	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
4,4'-DDT	0.1	ug/l			0.001	1.1	0.00	0.00	0.00	0.00	0.00	0.00	
Dieldrin	0.1	ug/l			0.056	0.24	0.00	0.00	0.00	0.00	0.00	0.00	
Endosulfan 1	0.1	ug/l	0.018		0.056	0.22	0.00	0.00	0.00	0.00	0.00	0.00	
Endosulfan 2	0.1	ug/l			0.056	0.22	0.00	0.00	0.00	0.00	0.00	0.00	
Endosulfan sulfate	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Endrin	0.1	ug/l	0.004	2	0.036	0.086	0.00	0.00	0.00	0.00	0.00	0.00	
Endrin aldehyde	0.1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Heptachlor	0.05	ug/l		0.01	0.0038	0.52	0.00	0.00	0.00	0.00	0.00	0.00	
Heptachlor Epoxide	0.05	ug/l		0.01	0.0038	0.52	0.00	0.00	0.00	0.00	0.00	0.00	
Methoxychlor	0.5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Toxaphene	1	ug/l		3	0.0002	0.73	0.00	0.00	0.00	0.00	0.00	0.00	
Diazinon	0.01	ug/l		0.08			0.065	0.060	0.079	0.00	0.00	0.00	
Chlorpyrifos	0.05	ug/l		0.07			0.00	0.00	0.00	0.00	0.00	0.00	
Diuron	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Malathion	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Prometryn	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Simazine	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Atrazine	2	ug/l		3			0.00	0.00	0.00	0.00	0.00	0.00	
Cyanazine	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Molinate	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Thiobencarb	1	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Herbicides													
Carbofuran	5	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
2,4,5-TP-Silvex	10	ug/l		70			0.00	0.00	0.00	0.00	0.00	0.00	
2,4,5-TP	1	ug/l		50			0.00	0.00	0.00	0.00	0.00	0.00	
Bentazon	2	ug/l					0.00	0.00	0.00	0.00	0.00	0.00	
Glyphosate	25	ug/l		700			0.00	0.00	0.00	0.00	0.00	0.00	

<sup>1</sup> CTR values for metals are hardness dependent; higher hardness gives higher WQO

<sup>2</sup> Values of 0 represent that the constituent was not detected above the PQL as defined in the Municipal Stormwater Permit. Results are presented in accordance with Method B of the permit

Appendix B - 2005-2006 Sampling Results for Coyote Creek

Mass Emission Monitoring

WEATHER CONDITION				Wet				Dry			
STATION NO.	STATION NAME	EVENT NO.	DATE	S13 Coyote Creek 0506-01 10/17/2005	S13 Coyote Creek 0506-02 12/31/2005	S13 Coyote Creek 0506-03 01/14/2006	S13 Coyote Creek 0506-03 02/17/2006	S13 Coyote Creek 0506-04 03/03/2006	S13 Coyote Creek 0506-01 01/24/2006	S13 Coyote Creek 0506-02 04/25/2006	
Sample Type	EPA Method	POL	Units								
<b>Conventional</b>											
Oil and Grease	Grab	EPA413.1	1	1.10	0	0	0	0	0	0	0
Total Phenols	Grab	EPA420.1	0.10	0	0	0	0	0	0.018	0.016	
Cyanide	Grab	EPA335.2	0.01	0	0	0.014	0.014	0.01	0.018	0.016	
pH	Comp	SM4500B	0-14	7.72	7.63	7.71	8.05	7.26	8.10	8.22	
Dissolved Oxygen	Grab	SM4500B	1.00	6.05	8.16	8.57	12.26	10.97	13.90	14.38	
<b>Indicator Bacteria</b>											
Total Coliform	Grab	SM9230B	20.00		990.000	1690.000	22.000	1690.000	22.000	1790.000	
Fecal Coliform	Grab	SM9230B	20.00		300.000	920.000	2.000	50.000	0.000	600.000	
Fecal Total Coliform	Grab	SM9230B	20.00		900.000	2200.000	20.000	1690.000	0.000	1890.000	
Staphylococcus	Grab	SM9230B	20.00		900.000	900.000	170	17.000	0.000	130	
Enterococcus	Grab	SM9230B	20.00		900.000	900.000	170	86.000	3.000	139	
<b>General</b>											
Chloride	Comp	EPA300.0	2.00	70.30	75.20	53.80	210.00	13.70	202.00	196.00	
Fluoride	Comp	EPA300.1	0.10	0.4	0.34	0.29	0.67	0	0.7	0.75	
Nitrate	Comp	EPA300.0	0.10	15.5	7.74	9.41	17.5	2.21	17.7	9.57	
Sulfate	Comp	EPA300.0	0.10	135.40	137.00	95.90	309.00	25.00	367.00	350.00	
Alkalinity	Comp	EPA310.1	4.00	150.7	104.5	104.5	201	41.8	247.5	220	
Hardness	Comp	EPA130.2	2.00	210	180	170	380	88	420	370	
COD	Comp	EPA410.4	100.00	148	76.547	75.64	72	0	65.2	145.3	
Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	858	712	566	2020	208	1589	2050	
Specific Conductance	Comp	EPA160.1	2.00		434.00	350.00	1112.00	118.00	1044.00	1340.00	
Turbidity	Comp	EPA180.1	0.10	2.10	2.51	2.23	0.79	8.94	1.47	0.84	
Total Dissolved Solids	Comp	EPA160.2	2.00	967	302	259	3	368	11	5	
Volatile Suspended Solids	Comp	EPA160.4	1.00	139	63	80	1	72	5	1	
MEAS	Comp	EPA425.1	0.05	0.6892	0.126	0.261	0.005	0.154	0.066	0.087	
Total Organic Carbon	Comp	EPA415.1	1.00	29.1	9.21	17.2	6.28	4.12	4.5	7.83	
BOD	Comp	SM5210B	2.00	0	13.4	0	9.86	10.4	8.95	8.81	
Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA824	1.00	0	0	0	0	0	0	0	
<b>Nutrients</b>											
Dissolved Phosphorus	Comp	EPA365.3	0.05	0.0552	0.116	0.112	0	0.122	0	0	
Total Phosphorus	Comp	EPA365.3	0.05	0.1367	0.201	0.398	0	0.73	0	0	
NH3-N	Comp	EPA180.8	0.10	1.22	0.2162	0.524	0.11	0.33	0	0.15	
Nitrate - N	Comp	SM4110B	0.50	3.50	1.75	2.125	3.952	0.989	3.997	2.16	
Nitrite - N	Comp	SM4110B	0.03	0.00	0.155	0.268	0	0.0336	0.00	0.4534	
Ketadish-N	Comp	EPA351.4	0.10	10.9	1.206	2.425	1.48	4.24	0.825	0.92	
<b>Metals</b>											
Dissolved Aluminum	Comp	EPA200.8	100.00	0	0	0	0	0	0	0	
Total Aluminum	Comp	EPA200.8	100.00	2.490	615	214	0	15.000	0	104	
Dissolved Antimony	Comp	EPA200.8	5.00	2.56	0.5	1.65	0.51	0.82	0	0.76	
Total Antimony	Comp	EPA200.8	5.00	3.89	1.11	2.23	0.63	2.05	0.70	0.77	
Dissolved Arsenic	Comp	EPA200.8	5.00	3.15	1.63	1.63	2.66	1.14	1.74	3.19	
Total Arsenic	Comp	EPA200.8	5.00	4.92	1.91	2.19	3.3	3.67	3.77	4.42	
Dissolved Barium	Comp	EPA200.8	100.00	48.60	15.60	28.80	38.00	20.60	28.50	41.50	
Total Barium	Comp	EPA200.8	100.00	152.00	29.70	31.80	38.40	155.00	48.40	44.90	
Dissolved Beryllium	Comp	EPA200.8	1.00	0	0	0	0	0	0	0	
Total Beryllium	Comp	EPA200.8	1.00	0	0	0	0	0	0	0	
Dissolved Cadmium	Comp	EPA200.8	1.00	0.80	0.00	0	0	1.29	0	0	
Total Cadmium	Comp	EPA200.8	1.00	0.72	0.71	2.83	3.63	1.34	1.42	6.79	
Dissolved Chromium	Comp	EPA200.8	5.00	8.37	2.84	2.86	4.1	19.5	6.41	7.31	
Total Chromium	Comp	EPA200.8	10.00	0	0	0	0	0	0	0	
Dissolved Chromium +6	Comp	EPA200.8	5.00	0	0	0	0	0	0	0	
Total Chromium +6	Comp	EPA200.8	10.00	0	0	0	0	0	0	0	
Dissolved Copper	Comp	EPA200.8	5.00	10.70	6.79	12.50	5.31	4.25	6.00	5.72	
Total Copper	Comp	EPA200.8	100.00	63.20	7.52	13.70	16.7	56.9	9.13	18.8	
Dissolved Iron	Comp	EPA200.8	100.00	339	0	331	0	12980	0	172	
Total Iron	Comp	EPA200.8	5.00	4540	123	0	0	0.77	0.5	0	
Dissolved Lead	Comp	EPA200.8	5.00	0.64	0	1.87	0	54	0.52	0.78	
Total Lead	Comp	EPA200.8	1.00	23.30	0.95	0	0.77	0	0	0	
Dissolved Mercury	Comp	EPA200.8	1.00	0	0	0	0	0	0	0	
Total Mercury	Comp	EPA200.8	5.00	10.00	1.84	4.37	3.58	2.84	2.09	4.91	
Dissolved Nickel	Comp	EPA200.8	5.00	20.30	4.11	5.77	3.73	21.9	3.63	22.1	
Total Nickel	Comp	EPA200.8	5.00	2.83	1.96	2.15	0	0	6.50	5.4	
Dissolved Selenium	Comp	EPA200.8	5.00	2.83	1.96	2.15	0	0	6.50	7.57	
Total Selenium	Comp	EPA200.8	1.00	0.26	0	0	0	0.28	0	0	
Dissolved Silver	Comp	EPA200.8	1.00	0	0	0	0	0	0	0	
Total Silver	Comp	EPA200.8	5.00	0	0	0	0	0	0	0	
Dissolved Thallium	Comp	EPA200.8	5.00	0	0	0	0	0	0	0	
Total Thallium	Comp	EPA200.8	50.00	35.00	11.90	46.00	17.5	17.6	28.10	9.09	
Dissolved Zinc	Comp	EPA200.8	50.00	342.00	33.60	75.00	17.9	242	48.90	18.8	
Total Zinc	Comp	EPA200.8	50.00								
<b>Semi-Volatiles Organics (EPA 625)</b>											
2-Chlorophenol	Comp	EPA625	2.00	0	0	0	0	0	0	0	
2,4-dichlorophenol	Comp	EPA625	2.00	0	0	0	0	0	0	0	
2,4-dimethylphenol	Comp	EPA625	2.00	0	0	0	0	0	0	0	
2,4-dinitrophenol	Comp	EPA625	3.00	0	0	0	0	0	0	0	
2-nitrophenol	Comp	EPA625	3.00	0	0	0	0	0	0	0	
4-nitrophenol	Comp	EPA625	3.00	0	0	0	0	0	0	0	
4-chloro-3-methylphenol	Comp	EPA625	2.00	0	0	0	0	0	0	0	
Pentachlorophenol	Comp	EPA625	1.00	0	0	0	0	0	0	0	
2,4,6-trichlorophenol	Comp	EPA625	1.00	0	0	0	0	0	0	0	

Appendix B. 2005-2006 Sampling Results for Coyote Creek

Mass Emission Monitoring

WEATHER CONDITION		Wet					Dry	
STATION NAME	STATION NO.	S13 Coyote Creek 09/06-01 10/17/2005	S13 Coyote Creek 05/06-02 12/31/2005	S13 Coyote Creek 05/06-03 01/14/2006	S13 Coyote Creek 05/06-03 02/17/2006	S13 Coyote Creek 05/06-04 03/03/2006	S13 Coyote Creek 05/06-01 01/24/2006	S13 Coyote Creek 05/06-02 04/25/2006
EVENT NO.	DATE	Sample Type	EPA Method	POL	Units			
Base/Neutral								
Acenaphthene		Comp	EP/A625	0.05	ug/L	0	0	0
Acenaphthylene		Comp	EP/A625	0.05	ug/L	0	0	0
Anthracene		Comp	EP/A625	0.05	ug/L	0	0	0
Benztidine		Comp	EP/A625	3.00	ug/L	0	0	0
1,2-Benzanthracene		Comp	EP/A625	0.10	ug/L	0	0	0
Benzzo(a)pyrene		Comp	EP/A625	0.10	ug/L	0	0	0
Benzzo(b)fluoranthene		Comp	EP/A625	1.00	ug/L	0	0	0
3,4-Benzofluoranthene		Comp	EP/A625	2.00	ug/L	0	0	0
Benzzo(k)fluoranthene		Comp	EP/A625	0.10	ug/L	0	0	0
Big(2-Chloroethoxy)methane		Comp	EP/A625	1.00	ug/L	0	0	0
Big(2-Chloroethyl)ether		Comp	EP/A625	1.00	ug/L	0	0	0
Big(2-Ethoxy)phthalate		Comp	EP/A625	1.00	ug/L	0	0	0
4-Bromophenyl phenyl ether		Comp	EP/A625	1.00	ug/L	0	0	0
Bulky benzyl phthalate		Comp	EP/A625	0.30	ug/L	0	0	0
2-Chloroethyl vinyl ether		Comp	EP/A625	2.50	ug/L	0	0	0
2-Chlorophthalene		Comp	EP/A625	0.10	ug/L	0	0	0
4-Chlorophenyl phenyl ether		Comp	EP/A625	0.10	ug/L	0	0	0
Chrysene		Comp	EP/A625	0.10	ug/L	0	0	0
Dibenz(a,h)anthracene		Comp	EP/A625	0.10	ug/L	0	0	0
1,2-Dichlorobenzene		Comp	EP/A625	0.05	ug/L	0	0	0
1,4-Dichlorobenzene		Comp	EP/A625	0.05	ug/L	0	0	0
1,4-Dichlorobenzene		Comp	EP/A625	0.05	ug/L	0	0	0
3,3'-Dichlorobenzidine		Comp	EP/A625	3.00	ug/L	0	0	0
Diallyl phthalate		Comp	EP/A625	0.50	ug/L	0	0	0
Diallyl phthalate		Comp	EP/A625	0.50	ug/L	0	0	0
di-n-Butyl phthalate		Comp	EP/A625	1.00	ug/L	0	0	0
2,4-Dinitrotoluene		Comp	EP/A625	0.05	ug/L	0	0	0
2,6-Dinitrotoluene		Comp	EP/A625	0.05	ug/L	0	0	0
4,6-Dinitro-2-nethylphenol		Comp	EP/A625	3.00	ug/L	0	0	0
1,2-Diphenylhydrazine		Comp	EP/A625	3.00	ug/L	0	0	0
di-n-Octyl phthalate		Comp	EP/A625	1.00	ug/L	0	0	0
Fluorene		Comp	EP/A625	0.10	ug/L	0	0	0
Hexachlorobenzene		Comp	EP/A625	0.50	ug/L	0	0	0
Hexachlorocyclopentadiene		Comp	EP/A625	1.00	ug/L	0	0	0
Hexachlorocyclopentadiene		Comp	EP/A625	1.00	ug/L	0	0	0
Hexachloroethane		Comp	EP/A625	3.00	ug/L	0	0	0
Indeno (1,2,3-cd)pyrene		Comp	EP/A625	0.10	ug/L	0	0	0
Isophorone		Comp	EP/A625	0.05	ug/L	0	0	0
Naphthalene		Comp	EP/A625	0.05	ug/L	0	0	0
Nitrobenzene		Comp	EP/A625	0.30	ug/L	0	0	0
N-Nitroso-dimethyl amine		Comp	EP/A625	0.30	ug/L	0	0	0
N-Nitroso-diphenyl amine		Comp	EP/A625	0.30	ug/L	0	0	0
N-Nitroso-di-n-propyl amine		Comp	EP/A625	0.05	ug/L	0	0	0
Phenanthrene		Comp	EP/A625	0.05	ug/L	0	0	0
Pyrene		Comp	EP/A625	0.50	ug/L	0	0	0
1,2,4-Trichlorobenzene		Comp	EP/A625	0.50	ug/L	0	0	0
Chlorinated Pesticides								
Alrin		Comp	EP/A625	0.05	ug/L	0	0	0
alpha-BHC		Comp	EP/A625	0.05	ug/L	0	0	0
beta-BHC		Comp	EP/A625	0.05	ug/L	0	0	0
delta-BHC		Comp	EP/A625	0.05	ug/L	0	0	0
Gamma-BHC(Lindane)		Comp	EP/A625	0.05	ug/L	0	0	0
alpha-chlorobane		Comp	EP/A625	0.05	ug/L	0	0	0
beta-chlorobane		Comp	EP/A625	0.05	ug/L	0	0	0
gamma-chlorobane		Comp	EP/A625	0.10	ug/L	0	0	0
delta-chlorobane		Comp	EP/A625	0.10	ug/L	0	0	0
4,4'-DDE		Comp	EP/A625	0.10	ug/L	0	0	0
4,4'-DDE		Comp	EP/A625	0.10	ug/L	0	0	0
4,4'-DDT		Comp	EP/A625	0.10	ug/L	0	0	0
4,4'-DDT		Comp	EP/A625	0.10	ug/L	0	0	0
Diieldrin		Comp	EP/A625	0.10	ug/L	0	0	0
Endosulfan I (pphal)		Comp	EP/A625	0.10	ug/L	0	0	0
Endosulfan II (beta)		Comp	EP/A625	0.10	ug/L	0	0	0
Endosulfan sulfate		Comp	EP/A625	0.10	ug/L	0	0	0
Erdrin		Comp	EP/A625	0.10	ug/L	0	0	0
Erdrin aldehyde		Comp	EP/A625	0.05	ug/L	0	0	0
Heptachlor		Comp	EP/A625	0.05	ug/L	0	0	0
Heptachlor Epoxide		Comp	EP/A625	0.05	ug/L	0	0	0
Toxaphene		Comp	EP/A625	1.00	ug/L	0	0	0
Polychlorinated Biphenyls								
Accebr-1016		Comp	EP/A608	0.50	ug/L	0	0	0
Accebr-1221		Comp	EP/A608	0.50	ug/L	0	0	0
Accebr-1232		Comp	EP/A608	0.50	ug/L	0	0	0
Accebr-1242		Comp	EP/A608	0.50	ug/L	0	0	0
Accebr-1248		Comp	EP/A608	0.50	ug/L	0	0	0
Accebr-1254		Comp	EP/A608	0.50	ug/L	0	0	0
Accebr-1280		Comp	EP/A608	0.50	ug/L	0	0	0

Appendix B. 2005-2006 Sampling Results for Coyote Creek

Mass Emission Monitoring

WEATHER CONDITION				Wet				Dry		
STATION NO.	STATION NAME	EVENT NO.	DATE	S13 Coyote Creek 0906-01 10/17/2005	S13 Coyote Creek 0506-02 12/31/2005	S13 Coyote Creek 0506-03 01/14/2006	S13 Coyote Creek 0506-03 02/17/2006	S13 Coyote Creek 0506-04 0303/2006	S13 Coyote Creek 0306-01 01/24/2006	S13 Coyote Creek 0506-02 04/25/2006
Sample Type	EPA Method	POL	Units							
Organophosphate Pesticides										
Chlorpyrifos	Comp EPA507	0.05	ug/L	0	0	0	0	0	0	0
Diazinon	Comp EPA507	0.01	ug/L	0	0	0	0	0	0	0
Permethrin	Comp EPA507	2.00	ug/L	0	0	0	0	0	0	0
Atrazine	Comp EPA507	2.00	ug/L	0	0	0	0	0	0	0
Sinazoline	Comp EPA507	2.00	ug/L	0	0	0	0	0	0	0
Cyanazine	Comp EPA507	2.00	ug/L	0	0	0	0	0	0	0
Malathion	Comp EPA507	2.00	ug/L	0	0	0	0	0	0	0
Herbicides										
Glyphosate	Comp EPA547	25.00	ug/L	0	0	0	0	0	0	0
2,4-D	Comp EPA515.3	10.00	ug/L	0	0	0	0	0	0	0
2,4,5-TP-SILVEX	Comp EPA515.3	1.00	ug/L	0	0	0	0	0	0	0

- Note:  
 1) blank cell indicates sample was not analyzed  
 2) 0 indicates concentration below minimum detection level  
 3) POL = minimum level  
 4) Highlighted cells show exceedances

DRAFT

Appendix B - 2005-2006 Sampling Results for San Gabriel River

Mass Emission Monitoring

WEATHER CONDITION				Wet				Dry			
STATION NO.	STATION NAME	EVENT NO.	DATE	S14 San Gabriel River 0506-01 10/17/2005	S14 San Gabriel River 0506-02 12/31/2005	S14 San Gabriel River 0506-03 01/14/2006	S14 San Gabriel River 0506-03 02/17/2006	S14 San Gabriel River 0506-01 01/24/2006	S14 San Gabriel River 0506-02 04/29/2006		
Sample Type	EPA Method	PQL	Units								
<b>Conventional</b>											
Oil and Grease	Grab		mg/L	0	1.10	0	0	0	0		
Total Phenols	EPA413.1	1	mg/L	0	0	0	0	0	0		
Cyanide	EPA335.2	0.01	mg/L	0	0	0.017	0	0.017	0		
pH	SMA500H B	0-14		8.21	7.48	7.99	7.99	7.79	7.9		
Dissolved Oxygen	SMA5000 G	1.00	mg/L	7.12	8.31	10.2	11.00	9.49	8.40		
<b>Indicator Bacteria</b>											
Total Coliform	SMA230B	20.00	MPN/100ml	90,000,000	240,000	16,000	3,000	3,000	9,000		
Fecal Coliform	SMA230B	20.00	MPN/100ml	16,000,000	240,000	800	300	3,000	130		
Ratio Fecal Coliform/Total Coliform	SMA230B	20.00	MPN/100ml	0.18	0.100	0.05	0.10	1.00	0.21		
Enterococcus	SMA230B	20.00	MPN/100ml	240,000	90,000	700	80	1,300	210		
<b>General</b>											
Chloride	EPA300.0	2.00	mg/L	73.10	37.50	134.00	80.40	119.00	100.00		
Fluoride	EPA300.0	0.10	mg/L	0.18	0.18	0.18	0.14	0.17	0.28		
Nitrate	EPA300.0	0.10	mg/L	11.5	5.49	9.09	7.07	8.85	3.74		
Sulfate	EPA300.0	0.10	mg/L	153.00	53.20	158.00	98.40	155.00	179.00		
Alkalinity	EPA310.1	4.00	mg/L	132	69.3	145.2	122	193	193		
Hardness	EPA130.2	2.00	mg/L	250	112.5	255	220	250	345		
COD	EPA410.4	10.00	mg/L	73	37.3814	39.94	49.9	53.4	10.6		
Total Petroleum Hydrocarbons	EPA418.1	1.00	ug/L	0	1.6	0	0	0	0		
Specific Conductance	EPA120.1	1.00	umhos/cm	883	379	974	871	944	1187		
Turbidity	EPA180.1	2.00	mg/L	578.00	222.00	594.00	474.00	582.00	686.00		
Total Dissolved Solids	EPA180.1	0.10	NTU	1.32	8.07	0.59	1.33	0.68	0.68		
Total Suspended Solids	EPA180.2	2.00	mg/L	517	933	11	9	31	6		
Volatiles Suspended Solids	EPA160.4	1.00	mg/L	60	109	3	5	8	9		
MBAS	EPA425.1	0.05	mg/L	0.1919	0.106	0	0.065	0.061	0.276		
Total Organic Carbon	EPA415.1	1.00	mg/L	8.57	12.47	5.08	4.99	4.63	2.76		
BOD	SMA5210B	2.00	mg/L	6.04	39.7	8.56	7.6	21.1	4.63		
Methyl Tertiary Butyl Ether (MTBE)	EPA824	1.00	ug/L	0	0	0	0	0	0		
<b>Nutrients</b>											
Dissolved Phosphorus	EPA385.3	0.05	mg/L	0.0794	0.139	0.064	0.078	0.058	0.097		
Total Phosphorus	EPA385.3	0.05	mg/L	0.0992	0.266	0.088	0.095	0.103	0.157		
NH3-N	EPA350.3	0.10	mg/L	0.665	0.2162	0.322	0.54	0.589	0.12		
Nitrate - N	SMA4110B	0.50	mg/L	2.60	1.24	2.053	1.566	1.998	0.845		
Nitrite - N	SMA4110B	0.03	mg/L	0	0.207	0	0	0.377	0		
Kjeldahl-N	EPA351.4	0.10	mg/L	5.44	0.9982	0.871	2.72	1.448	0.44		
<b>Metals</b>											
Dissolved Aluminum	EPA200.8	100.00	ug/L	0	0	0	0	0	0		
Total Aluminum	EPA200.8	100.00	ug/L	2.140	575	112	174	0	282		
Dissolved Arsenic	EPA200.8	5.00	ug/L	0.93	0	0	0	0.00	0		
Total Arsenic	EPA200.8	5.00	ug/L	1.41	0.88	0.00	0	0.00	0		
Dissolved Barium	EPA200.8	5.00	ug/L	1.65	0	1.21	1.24	1.2	2.56		
Total Barium	EPA200.8	5.00	ug/L	2.79	1.36	1.80	1.51	1.82	3.18		
Dissolved Beryllium	EPA200.8	10.00	ug/L	46.00	12.30	43.10	50.40	39.2	71.20		
Total Beryllium	EPA200.8	1.00	ug/L	100.00	29.60	55.00	51.40	54.0	82.70		
Dissolved Cadmium	EPA200.8	1.00	ug/L	0	0	0	0	0	0		
Total Cadmium	EPA200.8	1.00	ug/L	0	0	0	0	0	0		
Dissolved Chromium	EPA200.8	5.00	ug/L	0.51	0.00	4.37	2.47	1.19	4.75		
Total Chromium	EPA200.8	5.00	ug/L	6.82	1.92	5.26	3.04	3.88	4.79		
Dissolved Chromium +6	EPA200.8	10.00	ug/L	0	0	0	0	0	0		
Total Chromium +6	EPA200.8	10.00	ug/L	0	0	0	0	0	0		
Dissolved Copper	EPA200.8	5.00	ug/L	3.19	3.04	3.55	3.69	4.67	2.6		
Total Copper	EPA200.8	5.00	ug/L	34.50	6.79	6.83	10.6	5.31	17.6		
Dissolved Iron	EPA200.8	100.00	ug/L	0	0	0	0	0	0		
Total Iron	EPA200.8	100.00	ug/L	4290	232	138	287	112	469		
Dissolved Lead	EPA200.8	5.00	ug/L	0.00	0	0.77	1.4	0.94	1.12		
Total Lead	EPA200.8	5.00	ug/L	14.20	1.01	0	0	0	0		
Dissolved Mercury	EPA200.8	1.00	ug/L	0	0	0	0	0	0		
Total Mercury	EPA200.8	1.00	ug/L	5.54	1.50	3.68	3.51	6.04	6.04		
Dissolved Nickel	EPA200.8	5.00	ug/L	12.10	3.54	4.51	4.56	4.62	21		
Total Nickel	EPA200.8	5.00	ug/L	1.97	0	1.95	0	2.31	1.42		
Dissolved Selenium	EPA200.8	5.00	ug/L	2.12	0.00	2.57	1.49	2.71	2		
Total Selenium	EPA200.8	5.00	ug/L	0	0.00	0	0	0	0		
Dissolved Silver	EPA200.8	1.00	ug/L	0	0.00	0	0	0	0		
Total Silver	EPA200.8	1.00	ug/L	0	0.00	0	0	0	0		
Dissolved Thallium	EPA200.8	5.00	ug/L	0	0	0	0	0	0		
Total Thallium	EPA200.8	5.00	ug/L	0	0	0	0	0	0		
Dissolved Zinc	EPA200.8	50.00	ug/L	24.00	9.84	19.00	17.1	29.10	4.16		
Total Zinc	EPA200.8	50.00	ug/L	175.00	32.80	36.00	23.3	55.60	19.8		
<b>Semi-Volatiles Organics (EPA 625)</b>											
2-Chlorophenol	EPA625	2.00	ug/L	0	0	0	0	0	0		
2,4-dichlorophenol	EPA625	2.00	ug/L	0	0	0	0	0	0		
2,4-dimethylphenol	EPA625	3.00	ug/L	0	0	0	0	0	0		
2,4-dinitrophenol	EPA625	3.00	ug/L	0	0	0	0	0	0		
2-nitrophenol	EPA625	3.00	ug/L	0	0	0	0	0	0		
4-nitrophenol	EPA625	3.00	ug/L	0	0	0	0	0	0		
4-chloro-3-methylphenol	EPA625	2.00	ug/L	0	0	0	0	0	0		
Pentachlorophenol	EPA625	2.00	ug/L	0	0	0	0	0	0		
Phenol	EPA625	1.00	ug/L	0	0	0	0	0	0		
2,4,6-trichlorophenol	EPA625	1.00	ug/L	0	0	22.8	0	0	0		

Appendix B - 2005-2006 Sampling Results for San Gabriel River

Mass Emission Monitoring

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE	Wet				Dry		
	S14	S14	S14	S14	S14	S14	
	San Gabriel River 0506-01 10/17/2005	San Gabriel River 0506-02 12/9/2005	San Gabriel River 0506-03 01/14/2006	San Gabriel River 0506-03 02/17/2006	San Gabriel River 0506-01 01/24/2006	San Gabriel River 0506-02 04/29/2006	
Base/Neutral	Sample Type	EPA Method	PQL	Units			
Acenaphthene	Comp	EPA625	0.05	ug/L	0	0	0
Acenaphthylene	Comp	EPA625	0.05	ug/L	0	0	0
Anthracene	Comp	EPA625	0.05	ug/L	0	0	0
Benzidine	Comp	EPA625	3.00	ug/L	0	0	0
1,2-Benzanthracene	Comp	EPA625	0.10	ug/L	0	0	0
Benz(a)pyrene	Comp	EPA625	1.00	ug/L	0	0	0
Benzofluoranthene	Comp	EPA625	1.00	ug/L	0	0	0
3,4-Benzofluoranthene	Comp	EPA625	2.00	ug/L	0	0	0
Benzofluoranthene	Comp	EPA625	0.10	ug/L	0	0	0
Benzofluoranthene	Comp	EPA625	0.10	ug/L	0	0	0
Benzofluoranthene	Comp	EPA625	1.00	ug/L	0	0	0
Bis(2-Chloroethoxy)methane	Comp	EPA625	1.00	ug/L	0	0	0
Bis(2-Chloroisopropyl)ether	Comp	EPA625	0.10	ug/L	0	0	0
Bis(2-Chloroethyl)phthalate	Comp	EPA625	1.00	ug/L	0	0	0
Bis(2-Ethylhexyl)phthalate	Comp	EPA625	1.00	ug/L	0	0	0
4-Bromophenyl phenyl ether	Comp	EPA625	0.30	ug/L	0	0	0
Butyl benzyl phthalate	Comp	EPA625	2.50	ug/L	0	0	0
2-Chloroethyl vinyl ether	Comp	EPA625	0.10	ug/L	0	0	0
2-Chlorophthalate	Comp	EPA625	0.10	ug/L	0	0	0
4-Chlorophenyl phenyl ether	Comp	EPA625	0.10	ug/L	0	0	0
Cymene	Comp	EPA625	0.05	ug/L	0	0	0
Dibenz(a,h)anthracene	Comp	EPA625	0.10	ug/L	0	0	0
1,3-Dichloroene	Comp	EPA625	0.05	ug/L	0	0	0
1,4-Dichloroene	Comp	EPA625	0.05	ug/L	0	0	0
1,2-Dichloroene	Comp	EPA625	0.05	ug/L	0	0	0
3,3-Dichloroene	Comp	EPA625	3.00	ug/L	0	0	0
Diethyl phthalate	Comp	EPA625	0.50	ug/L	0	0	0
Dimethyl phthalate	Comp	EPA625	1.00	ug/L	0	0	0
di-n-Butyl phthalate	Comp	EPA625	0.05	ug/L	0	0	0
2,4-Dinitrotoluene	Comp	EPA625	0.05	ug/L	0	0	0
2,6-Dinitrotoluene	Comp	EPA625	3.00	ug/L	0	0	0
4,6 Dinitro-2-methylphenol	Comp	EPA625	3.00	ug/L	0	0	0
1,2-Diphenylhydrazine	Comp	EPA625	1.00	ug/L	0	0	0
di-n-Octyl phthalate	Comp	EPA625	0.10	ug/L	0	0	0
Fluoranthene	Comp	EPA625	0.10	ug/L	0	0	0
Fluorene	Comp	EPA625	0.50	ug/L	0	0	0
Hexachlorobenzene	Comp	EPA625	1.00	ug/L	0	0	0
Hexachlorobutadiene	Comp	EPA625	3.00	ug/L	0	0	0
Hexachlorocyclopentadiene	Comp	EPA625	1.00	ug/L	0	0	0
Hexachlorothane	Comp	EPA625	0.10	ug/L	0	0	0
Indeno (1,2,3-cd)pyrene	Comp	EPA625	0.05	ug/L	0	0	0
Isophorone	Comp	EPA625	0.05	ug/L	0	0	0
Naphthalene	Comp	EPA625	0.05	ug/L	0	0	0
Nitrobenzene	Comp	EPA625	0.30	ug/L	0	0	0
N-Nitroso-dimethyl amine	Comp	EPA625	0.30	ug/L	0	0	0
N-Nitroso-diethyl amine	Comp	EPA625	0.30	ug/L	0	0	0
N-Nitroso-di-n-propyl amine	Comp	EPA625	0.05	ug/L	0	0	0
Phenanthrene	Comp	EPA625	0.05	ug/L	0	0	0
Pyrene	Comp	EPA625	0.50	ug/L	0	0	0
1,2,4-Trichlorobenzene	Comp	EPA625	0.05	ug/L	0	0	0
Chlorinated Pesticides							
Aldrin	Comp	EPA625	0.05	ug/L	0	0	0
alpha-BHC	Comp	EPA625	0.05	ug/L	0	0	0
beta-BHC	Comp	EPA625	0.05	ug/L	0	0	0
delta-BHC	Comp	EPA625	0.05	ug/L	0	0	0
Gamma-BHC (Lindane)	Comp	EPA625	0.05	ug/L	0	0	0
alpha-chlordane	Comp	EPA625	0.05	ug/L	0	0	0
gamma-chlordane	Comp	EPA625	0.10	ug/L	0	0	0
Chlordane	Comp	EPA625	0.10	ug/L	0	0	0
4,4'-DDD	Comp	EPA625	0.10	ug/L	0	0	0
4,4'-DDE	Comp	EPA625	0.10	ug/L	0	0	0
4,4'-DDT	Comp	EPA625	0.10	ug/L	0	0	0
Dieldrin	Comp	EPA625	0.10	ug/L	0	0	0
Endosulfan I [alpha]	Comp	EPA625	0.10	ug/L	0	0	0
Endosulfan II [beta]	Comp	EPA625	0.10	ug/L	0	0	0
Endosulfan sulfate	Comp	EPA625	0.10	ug/L	0	0	0
Endrin	Comp	EPA625	0.10	ug/L	0	0	0
Endrin aldehyde	Comp	EPA625	0.05	ug/L	0	0	0
Heptachlor	Comp	EPA625	0.05	ug/L	0	0	0
Heptachlor Epoxide	Comp	EPA625	1.00	ug/L	0	0	0
Polychlorinated Biphenyls							
Atodior-1016	Comp	EPA608	0.50	ug/L	0	0	0
Atodior-1221	Comp	EPA608	0.50	ug/L	0	0	0
Atodior-1232	Comp	EPA608	0.50	ug/L	0	0	0
Atodior-1242	Comp	EPA608	0.50	ug/L	0	0	0
Atodior-1248	Comp	EPA608	0.50	ug/L	0	0	0
Atodior-1294	Comp	EPA608	0.50	ug/L	0	0	0
Atodior-1260	Comp	EPA608	0.50	ug/L	0	0	0

Appendix B - 2005-2006 Sampling Results for San Gabriel River

Mass Emission Monitoring

WEATHER CONDITION STATION NO. STATION NAME EVENT NO. DATE	Wet				Dry	
	S14 San Gabriel River 0506-01 10/17/2005	S14 San Gabriel River 0506-02 12/9/2005	S14 San Gabriel River 0506-03 01/14/2006	S14 San Gabriel River 0506-03 02/17/2006	S14 San Gabriel River 0506-01 01/24/2006	S14 San Gabriel River 0506-02 04/29/2006
Organophosphate Pesticides	Sample Type	EPA Method	PQL	Units		
Chlorpyrifos	Comp	EPA507	0.05	ug/L	0	0
Diazinon	Comp	EPA507	0.01	ug/L	0	0
Prothioth	Comp	EPA507	2.00	ug/L	0	0
Atrazine	Comp	EPA507	2.00	ug/L	0	0
Simazine	Comp	EPA507	2.00	ug/L	0	0
Cyanazine	Comp	EPA507	2.00	ug/L	0	0
Malathion	Comp	EPA507	2.00	ug/L	0	0
Herbicides						
Glyphosate	Comp	EPA547	25.00	ug/L	0	0
2,4-D	Comp	EPA515.3	10.00	ug/L	0	0
2,4,5-T-P-SILVEX	Comp	EPA515.3	1.00	ug/L	0	0

- Note:  
 1) blank cell indicates sample was not analyzed  
 2) 0 indicates concentration below minimum detection level  
 3) PQL = minimum level  
 4) Highlighted cells show exceedances

DRAFT



Appendix B. 2006-2007 Sampling Results for Coyote Creek

Mass Emission Monitoring

WEATHER CONDITION		Wet				Dry	
STATION NO.	STATION NAME	S13 Coyote Creek	S13 Coyote Creek	S13 Coyote Creek	S13 Coyote Creek	S13 Coyote Creek	S13 Coyote Creek
EVENT CODE	DATE	2006-07/Event03 12/09/2006	2006-07/Event06 02/10/2007	2006-07/Event07 02/19/2007	2006-07/Event08 02/22/2007	2006-07/Event02 11/01/2006	2006-07/Event12 04/02/2007
Sample Type	EPA Method	PQL	Units				
Base/Neutral							
Aceaphthene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Aceaphthylene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Anthracene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Benztrene	Comp EPA625	3.00	ug/L	-99	-99	-99	-99
1,2-Benzanthracene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Benz[a]pyrene	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
Benzo[g,h]perylene	Comp EPA625	2.00	ug/L	-99	-99	-99	-99
3,4-Benzofluoranthene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Benzo[k]fluoranthene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Benzo[e]fluoranthene	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
Benzo[a]anthracene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Benzo[b]fluoranthene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Benzo[a]phenanthrene	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
Bis[2-Chloroethyl]ether	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
Bis[2-Ethylhexyl]phthalate	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
4-Bromophenyl phenyl ether	Comp EPA625	0.30	ug/L	-99	-99	-99	-99
Butyl benzyl phthalate	Grab EPA624	2.50	ug/L	-99	-99	-99	-99
2-Chloroethyl vinyl ether	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
2-Chlorophthalate	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
4-Chlorophenyl phenyl ether	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Chrysene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
1,3-Dichlorobenzene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
1,4-Dichlorobenzene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
1,2-Dichlorobenzene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
3,3-Dichlorobenzidine	Comp EPA625	3.00	ug/L	-99	-99	-99	-99
Diallyl phthalate	Comp EPA625	0.50	ug/L	-99	-99	-99	-99
Diethyl phthalate	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
Di-n-Butyl phthalate	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
2,4-Dinitrotoluene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
4,6-Dinitro-2-methylphenol	Comp EPA625	3.00	ug/L	-99	-99	-99	-99
1,2-Diphenylhydrazine	Comp EPA625	3.00	ug/L	-99	-99	-99	-99
di-n-Octyl phthalate	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
Fluorene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Fluoranthene	Comp EPA625	0.50	ug/L	-99	-99	-99	-99
Hexachlorobenzene	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
Hexachlorobutadiene	Comp EPA625	3.00	ug/L	-99	-99	-99	-99
Hexachlorocyclopentadiene	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
Hexachloroethane	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Indeno (1,2,3-cd)pyrene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Isophorone	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Naphthalene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
N-Nitroso-dimethyl amine	Comp EPA625	0.30	ug/L	-99	-99	-99	-99
N-Nitroso-dipropyl amine	Comp EPA625	0.30	ug/L	-99	-99	-99	-99
N-Nitroso-n-propyl amine	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Phenanthrene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Pyrene	Comp EPA625	0.50	ug/L	-99	-99	-99	-99
1,2,4-Trichlorobenzene	Comp EPA625	0.50	ug/L	-99	-99	-99	-99
Chlorinated Pesticides							
Aldrin	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
alpha-BHC	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
beta-BHC	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
delta-BHC	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Gamma-BHC (Lindane)	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
alpha-chlordane	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
gamma-chlordane	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Chlordane	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
4,4-DDD	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
4,4-DDE	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
4,4-DDT	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Dieldrin	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Endosulfan I [alpha]	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Endosulfan II [beta]	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Endosulfan sulfate	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Etam	Comp EPA625	0.10	ug/L	-99	-99	-99	-99
Etam aldehyde	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Heptachlor	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Heptachlor Epoxide	Comp EPA625	0.05	ug/L	-99	-99	-99	-99
Toxaphene	Comp EPA625	1.00	ug/L	-99	-99	-99	-99
Polychlorinated Biphenyls							
Aroclor-1016	Comp EPA608	0.50	ug/L	-99	-99	-99	-99
Aroclor-1221	Comp EPA608	0.50	ug/L	-99	-99	-99	-99
Aroclor-1232	Comp EPA608	0.50	ug/L	-99	-99	-99	-99
Aroclor-1242	Comp EPA608	0.50	ug/L	-99	-99	-99	-99
Aroclor-1248	Comp EPA608	0.50	ug/L	-99	-99	-99	-99
Aroclor-1254	Comp EPA608	0.50	ug/L	-99	-99	-99	-99
Aroclor-1260	Comp EPA608	0.50	ug/L	-99	-99	-99	-99

Appendix B. 2006-2007 Sampling Results for Coyote Creek

Mass Emission Monitoring

WEATHER CONDITION STATION NO. STATION NAME EVENT CODE DATE	Wet				Dry		
	S13 Coyote Creek 2006-07/Event03 12/09/2006	S13 Coyote Creek 2006-07/Event06 02/10/2007	S13 Coyote Creek 2006-07/Event07 02/19/2007	S13 Coyote Creek 2006-07/Event08 02/22/2007	S13 Coyote Creek 2006-07/Event02 11/01/2006	S13 Coyote Creek 2006-07/Event12 04/02/2007	
Sample Type	EPA Method	POL	Units				
<b>Organophosphate Pesticides</b>							
Chlorpyrifos	Comp EPA507	0.05	ug/L	-99	-99	-99	-99
Diathion	Comp EPA507	0.01	ug/L	-99	-99	-99	0.147
Prethiopyn	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
Atrazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
Simazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
Cyanazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
Malathion	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
<b>Herbicides</b>							
Slyphosate	Comp EPA547	25.00	ug/L	-99	-99	-99	-99
2,4-D	Comp EPA515.3	10.00	ug/L	-99	-99	-99	-99
2,4,5-TP-SILVEX	Comp EPA515.3	1.00	ug/L	-99	-99	-99	-99
<b>Other</b>							
Ammonia	Comp SM4500-NH3 F	0.1	mg/L	0.970	0.270	0.510	0.280
Ethrin ketone	Comp EPA625	0.1	ug/L	-99	-99	-99	-99
Methoxychlor	Comp EPA608	0.5	ug/L	-99	-99	-99	-99

- Note:  
 1) Blank cell indicates sample was not analyzed  
 2) -99 indicates concentration below minimum detection level  
 3) POL = minimum level  
 4) Highlighted cells show exceedances

DRAFT



WEATHER CONDITION STATION NO. STATION NAME EVENT CODE DATE	Wet				Dry	
	S14 San Gabriel River 2006-07-Event03 12/09/2006	S14 San Gabriel River 2006-07-Event06 02/10/2007	S14 San Gabriel River 2006-07-Event07 02/19/2007	S14 San Gabriel River 2006-07-Event08 02/22/2007	S14 San Gabriel River 2006-07-Event02 11/01/2006	S14 San Gabriel River 2006-07-Event12 04/02/2007
Sample Type	EPA Method	PCL	Units			
Base/Neutral						
Acenaphthene	EPA625	0.05	ug/L	-99	-99	-99
Aceonaphthylene	EPA625	0.05	ug/L	-99	-99	-99
Anthracene	EPA625	0.05	ug/L	-99	-99	-99
Benztidine	EPA625	3.00	ug/L	-99	-99	-99
1,2-Benzanthracene	EPA625	0.10	ug/L	-99	-99	-99
Benzo(a)pyrene	EPA625	1.00	ug/L	-99	-99	-99
Benzofluoranthene	EPA625	2.00	ug/L	-99	-99	-99
3,4-Benzofluoranthene	EPA625	0.10	ug/L	-99	-99	-99
Benzofluoranthene	EPA625	0.10	ug/L	-99	-99	-99
Bis(2-Chloroethoxy)methane	EPA625	1.00	ug/L	-99	-99	-99
Bis(2-Chloroethoxy)ether	EPA625	0.10	ug/L	-99	-99	-99
Bis(2-Ethylhexoxy)ether	EPA625	1.00	ug/L	-99	-99	-99
4-Bromophenyl phthalate	EPA625	1.00	ug/L	-99	-99	-99
4-Bromophenyl phenyl ether	EPA625	0.30	ug/L	-99	-99	-99
Bulky benzyl phthalate	EPA624	2.50	ug/L	-99	-99	-99
2-Chloroethyl vinyl ether	EPA625	0.10	ug/L	-99	-99	-99
2-Chloronaphthalene	EPA625	0.10	ug/L	-99	-99	-99
4-Chlorophenyl phenyl ether	EPA625	0.10	ug/L	-99	-99	-99
Chrysene	EPA625	0.05	ug/L	-99	-99	-99
Dibenz(a,h)anthracene	EPA625	0.05	ug/L	-99	-99	-99
1,3-Dichlorobenzene	EPA625	0.05	ug/L	-99	-99	-99
1,4-Dichlorobenzene	EPA625	0.05	ug/L	-99	-99	-99
1,2-Dichlorobenzene	EPA625	0.05	ug/L	-99	-99	-99
3,3-Dichlorobenzidine	EPA625	3.00	ug/L	-99	-99	-99
Diethyl phthalate	EPA625	0.50	ug/L	-99	-99	-99
Dimethyl phthalate	EPA625	0.50	ug/L	-99	-99	-99
di-n-Bulky phthalate	EPA625	1.00	ug/L	-99	-99	-99
2,4-Dinitrotoluene	EPA625	0.05	ug/L	-99	-99	-99
2,6-Dinitrotoluene	EPA625	0.05	ug/L	-99	-99	-99
4,6-Dinitro-2-methylphenol	EPA625	3.00	ug/L	-99	-99	-99
1,2-Diphenylhydrazine	EPA625	3.00	ug/L	-99	-99	-99
di-n-OCyI phthalate	EPA625	1.00	ug/L	-99	-99	-99
Fluoranthene	EPA625	0.10	ug/L	-99	-99	-99
Fluorene	EPA625	0.10	ug/L	-99	-99	-99
Hexachlorobenzene	EPA625	0.50	ug/L	-99	-99	-99
Hexachlorobutadiene	EPA625	1.00	ug/L	-99	-99	-99
Hexachloro-cyclopentadiene	EPA625	3.00	ug/L	-99	-99	-99
Hexachloroethane	EPA625	1.00	ug/L	-99	-99	-99
Indeno (1,2,3-cd)pyrene	EPA625	1.00	ug/L	-99	-99	-99
Isophorone	EPA625	0.05	ug/L	-99	-99	-99
Naphthalene	EPA625	0.05	ug/L	-99	-99	-99
Nitrobenzene	EPA625	0.05	ug/L	-99	-99	-99
N-Nitroso-dimethyl amine	EPA625	0.30	ug/L	-99	-99	-99
N-Nitroso-diphenyl amine	EPA625	0.30	ug/L	-99	-99	-99
N-Nitroso-di-n-propyl amine	EPA625	0.05	ug/L	-99	-99	-99
Phenanthrene	EPA625	0.05	ug/L	-99	-99	-99
Pyrene	EPA625	0.05	ug/L	-99	-99	-99
1,2,4-Trichlorobenzene	EPA625	0.50	ug/L	-99	-99	-99
Chlorinated Pesticides						
Aldrin	EPA625	0.05	ug/L	-99	-99	-99
alpha-BHC	EPA625	0.05	ug/L	-99	-99	-99
beta-BHC	EPA625	0.05	ug/L	-99	-99	-99
delta-BHC	EPA625	0.05	ug/L	-99	-99	-99
Gamma-BHC (Lindane)	EPA625	0.05	ug/L	-99	-99	-99
alpha-chlordane	EPA625	0.05	ug/L	-99	-99	-99
gamma-chlordane	EPA625	0.05	ug/L	-99	-99	-99
Chlordane	EPA625	0.10	ug/L	-99	-99	-99
4,4-DDD	EPA625	0.10	ug/L	-99	-99	-99
4,4-DDE	EPA625	0.10	ug/L	-99	-99	-99
4,4-DDT	EPA625	0.10	ug/L	-99	-99	-99
Dieldrin	EPA625	0.10	ug/L	-99	-99	-99
Endosulfan (alpha)	EPA625	0.10	ug/L	-99	-99	-99
Endosulfan II (beta)	EPA625	0.10	ug/L	-99	-99	-99
Endosulfan sulfate	EPA625	0.10	ug/L	-99	-99	-99
Endrin	EPA625	0.10	ug/L	-99	-99	-99
Endrin aldehyde	EPA625	0.10	ug/L	-99	-99	-99
Heptachlor	EPA625	0.05	ug/L	-99	-99	-99
Heptachlor Epoxide	EPA625	0.05	ug/L	-99	-99	-99
Toxaphene	EPA625	1.00	ug/L	-99	-99	-99
Polychlorinated Biphenyls						
Avodol-1016	EPA608	0.50	ug/L	-99	-99	-99
Avodol-1221	EPA608	0.50	ug/L	-99	-99	-99
Avodol-1232	EPA608	0.50	ug/L	-99	-99	-99
Avodol-1242	EPA608	0.50	ug/L	-99	-99	-99
Avodol-1248	EPA608	0.50	ug/L	-99	-99	-99
Avodol-1254	EPA608	0.50	ug/L	-99	-99	-99
Avodol-1260	EPA608	0.50	ug/L	-99	-99	-99

WEATHER CONDITION STATION NO. STATION NAME EVENT CODE DATE	Wet				Dry		
	S14 San Gabriel River 2006-07/Event03 12/09/2006	S14 San Gabriel River 2006-07/Event06 02/10/2007	S14 San Gabriel River 2006-07/Event07 02/19/2007	S14 San Gabriel River 2006-07/Event08 02/22/2007	S14 San Gabriel River 2006-07/Event02 11/01/2006	S14 San Gabriel River 2006-07/Event12 04/02/2007	
Sample Type	EPA Method	PCL	Units				
<b>Organophosphate Pesticides</b>							
Chlorpyrifos	Comp EPA507	0.05	ug/L	-99	-99	-99	-99
Diazinon	Comp EPA507	0.01	ug/L	-99	-99	-99	-99
Promethyn	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
Atrazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
Simazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
Oxamazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
Malathion	Comp EPA507	2.00	ug/L	-99	-99	-99	-99
<b>Herbicides</b>							
Glyphosate	Comp EPA457	25.00	ug/L	-99	-99	-99	-99
2,4-D	Comp EPA515.3	10.00	ug/L	-99	-99	-99	-99
2,4,5-TP-SILVEX	Comp EPA515.3	1.00	ug/L	-99	-99	-99	-99
<b>Other</b>							
Ammonia	Comp SM4500-NH3 F	0.1	mg/L	1.500	0.090	-99	0.210
Erdin ketone	Comp EPA625	0.1	ug/L	-99	-99	-99	-99
Methoxychlor	Comp EPA608	0.5	ug/L	-99	-99	-99	-99

## Note:

- 1) Blank cell indicates sample was not analyzed
- 2) -99 indicates concentration below minimum detection level
- 3) PCL = minimum level
- 4) Highlighted cells show exceedances

DRAFT





WEATHER CONDITION				Wet		Dry				
STATION NO.	STATION NAME	EVENT CODE	DATE	TS15 Upper San Jose Creek 2006-07Event03 12/09/2006	TS15 Upper San Jose Creek 2006-07Event06 02/10/2007	TS15 Upper San Jose Creek 2006-07Event07 02/19/2007	TS15 Upper San Jose Creek 2006-07Event08 02/22/2007	TS15 Upper San Jose Creek 2006-07Event09 02/27/2007	TS15 Upper San Jose Creek 2006-07Event01 10/31/2006	TS15 Upper San Jose Creek 2006-07Event15 04/09/2007
Sample Type	EPA Method	POL	Units							
Organophosphate Pesticides										
Chlorpyrifos	Comp EPA507	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99
Diazinon	Comp EPA507	0.01	ug/L	-99	-99	-99	-99	-99	-99	-99
Fenitrothyn	Comp EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Azinphos	Comp EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Striazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Malathion	Comp EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Herbicides										
Glyphosate	Comp EPA547	25.00	ug/L	-99	-99	-99	-99	-99	-99	-99
2,4-D	Comp EPA515.3	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Other										
Ammonia	Comp SM4500-NH3F	0.1	mg/L	0.640	0.240	-99	-99	0.120	0.320	0.100
Endrin ketene	Comp EPA625	0.1	ug/L	-99	-99	-99	-99	-99	-99	-99
Methoxychlor	Comp EPA608	0.5	ug/L	-99	-99	-99	-99	-99	-99	-99

- Note:  
 1) Blank cell indicates sample was not analyzed  
 2) -99 indicates concentration below minimum detection level  
 3) POL = minimum level  
 4) Highlighted cells show exceedances

DRAFT

Appendix B - 2006-2007 Sampling Results for North Fork Coyote Creek

Tributary Monitoring

WEATHER CONDITION				Wet				Dry			
STATION NO.	STATION NAME	DATE	EVENT CODE	TS17 North Fork Coyote Creek 2006-07-Event03 12/09/2006	TS17 North Fork Coyote Creek 2006-07-Event06 02/10/2007	TS17 North Fork Coyote Creek 2006-07-Event07 02/19/2007	TS17 North Fork Coyote Creek 2006-07-Event08 02/22/2007	TS17 North Fork Coyote Creek 2006-07-Event09 02/27/2007	TS17 North Fork Coyote Creek 2006-07-Event10 10/31/2006	TS17 North Fork Coyote Creek 2006-07-Event15 04/09/2007	
EVENT CODE	DATE	Sample Type	EPA Method	POI	Units	POI	Units	POI	Units	POI	Units
<b>Conventional</b>											
Oil and Grease	Grab	EPA413.1	1	-99	mgl	-99	-99	-99	-99	-99	-99
Total Phenolic	Grab	EPA420.1	0.10	-99	mgl	-99	-99	-99	-99	-99	-99
Cyanide	Grab	EPA335.2	0.01	-99	mgl	0.009	-99	-99	0.013	0.021	-99
pH	Comp	SM4500.B	1-14	7.80	mgl	7.84	7.75	7.84	8.30	8.03	-99
Dissolved Oxygen	Grab	SM4500.G	1.00	9.150	mgl	10.10	8.570	10.700	16.720	17.000	-99
<b>Indicator Bacteria</b>											
Total Coliform	Grab	SM220B	20.00	28 000 000	MPN/100ml	300 000 000	160 000 000	24 600 000	11 000 000	1 700 000	-99
Fecal Coliform	Grab	SM220B	20.00	14 000 000	MPN/100ml	16 000 000	17 000 000	16 000 000	8 600 000	70 000	-99
Fecal Total Coliform	Grab	SM220B	20.00	130 000 000	MPN/100ml	50 000 000	150 000 000	30 000 000	80 000	20 000	-99
Staphylococcus	Grab	SM220B	20.00	130 000 000	MPN/100ml	24 000 000	150 000 000	17 800 000	230 000	20 000	-99
Enterococcus	Grab	SM220B	20.00	130 000 000	MPN/100ml	24 000 000	150 000 000	17 800 000	230 000	20 000	-99
<b>General</b>											
Chloride	Comp	EPA300.0	2.00	42 700	mgl	70 600	66 400	46 900	170 000	187 000	-99
Fluoride	Comp	EPA300.0	0.10	0.190	mgl	0.277	0.318	0.276	0.320	0.330	-99
Nitrate	Comp	EPA300.0	0.10	12 300	mgl	-99	-99	-99	20 300	0.330	-99
Sulfate	Comp	EPA300.0	0.10	79 200	mgl	148 000	110 000	71 200	295 000	278 000	-99
Alkalinity	Comp	EPA310.1	4.00	99 000	mgl	115 500	110 000	83 600	200 200	179 300	-99
Hardness	Comp	EPA130.2	2.00	190 000	mgl	230 000	230 000	150 000	440 000	430 000	-99
COD	Comp	EPA10.4	10.00	435 000	mgl	152 440	76 320	43 040	57 460	18 884	-99
Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	1 800	mgl	1 800	-99	-99	-99	-99	-99
Specific Conductance	Comp	EPA120.1	1.00	540 000	umhos/cm	750 000	744 000	51 400	1775 000	1778 000	-99
Total Dissolved Solids	Comp	EPA160.1	2.00	318 000	mg/L	448 000	438 000	290 000	416 000	1066 000	-99
Turbidity	Comp	EPA160.1	0.10	4 270	NTU	5 330	2 560	2 140	11 300	8 070	-99
Total Suspended Solids	Comp	EPA160.2	2.00	886 000	mg/L	215 000	95 000	29 000	97 000	14 000	-99
Volatile Suspended Solids	Comp	EPA160.4	1.00	240 000	mg/L	68 000	29 000	5 000	31 000	6 000	-99
MEAS	Comp	EPA425.1	0.05	0.338	mg/L	0.117	0.137	0.137	0.168	-99	-99
Total Organic Carbon	Comp	EPA415.1	1.00	37 100	mg/L	19 100	18 700	10 900	14 100	6 780	-99
BOD	Comp	SM6210B	2.00	23 300	mg/L	21 300	19 800	43 900	23 900	60 800	-99
Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	-99	mg/L	-99	-99	-99	-99	-99	-99
<b>Nutrients</b>											
Dissolved Phosphorus	Comp	EPA365.3	0.05	0.270	mg/L	0.260	0.157	0.117	0.182	-99	-99
Total Phosphorus	Comp	EPA350.3	0.05	0.822	mg/L	0.633	0.228	0.158	0.566	0.089	-99
NH-N	Comp	EPA350.3	0.50	0.710	mg/L	0.210	-99	-99	0.130	0.140	-99
Nitrate - N	Comp	SM4110B	0.03	2.780	mg/L	-99	-99	-99	4.584	-99	-99
Nitrite - N	Comp	SM4110B	0.03	0.233	mg/L	0.030	-99	0.033	0.332	0.332	-99
Ketoh-N	Comp	EPA351.4	0.10	5.300	mg/L	3.980	4.100	1.680	3.540	0.960	-99
<b>Metals</b>											
Dissolved Aluminum	Comp	EPA200.8	100.00	-99	ug/L	-99	-99	-99	-99	-99	-99
Total Aluminum	Comp	EPA200.8	100.00	3360 000	ug/L	4350 000	1430 000	1120 000	2140 000	145 000	-99
Dissolved Antimony	Comp	EPA200.8	5.00	2 630	ug/L	2 110	3 010	2 290	1 990	0 650	-99
Total Antimony	Comp	EPA200.8	5.00	5 870	ug/L	3 010	3 890	2 870	3 680	0 740	-99
Dissolved Arsenic	Comp	EPA200.8	5.00	2 260	ug/L	3 300	2 870	1 890	1 810	3 550	-99
Total Arsenic	Comp	EPA200.8	5.00	4 910	ug/L	4 280	3 340	2 180	2 610	3 830	-99
Dissolved Barium	Comp	EPA200.8	100.00	40 800	ug/L	41 300	43 700	24 600	49 400	43 100	-99
Total Barium	Comp	EPA200.8	100.00	195 000	ug/L	94 300	71 700	37 100	74 400	50 800	-99
Dissolved Beryllium	Comp	EPA200.8	1.00	-99	ug/L	-99	-99	-99	-99	-99	-99
Total Beryllium	Comp	EPA200.8	1.00	-99	ug/L	-99	-99	-99	-99	-99	-99
Dissolved Cadmium	Comp	EPA200.8	1.00	-99	ug/L	-99	-99	-99	-99	-99	-99
Total Cadmium	Comp	EPA200.8	1.00	1 930	ug/L	0 740	0 340	-99	-99	-99	-99
Dissolved Chromium	Comp	EPA200.8	5.00	1 650	ug/L	1 810	3 930	2 060	2 500	4 610	-99
Total Chromium	Comp	EPA200.8	5.00	15 200	ug/L	6 050	4 610	3 040	6 340	2 750	-99
Dissolved Chromium +6	Comp	EPA200.8	10.00	-99	ug/L	0 470	1 410	1 240	1 270	0 650	-99
Total Chromium +6	Comp	EPA200.8	10.00	-99	ug/L	0 470	1 410	1 240	1 270	0 650	-99
Dissolved Copper	Comp	EPA200.8	5.00	13 600	ug/L	18 000	21 100	15 200	11 300	4 950	-99
Total Copper	Comp	EPA200.8	5.00	166 000	ug/L	66 400	48 000	32 700	48 300	23 800	-99
Dissolved Iron	Comp	EPA200.8	100.00	186 000	ug/L	136 000	36 000	-99	-99	-99	-99
Total Iron	Comp	EPA200.8	100.00	6090 000	ug/L	2350 000	1220 000	513 000	1640 000	100 000	-99
Dissolved Lead	Comp	EPA200.8	5.00	1 560	ug/L	2 880	2 710	-99	-99	-99	-99
Total Lead	Comp	EPA200.8	5.00	573 000	ug/L	13 000	8 230	4 470	14 700	0 680	-99
Dissolved Mercury	Comp	EPA200.8	1.00	0 157	ug/L	-99	-99	-99	-99	-99	-99
Total Mercury	Comp	EPA200.8	1.00	0 157	ug/L	-99	-99	-99	-99	-99	-99
Dissolved Nickel	Comp	EPA200.8	5.00	12 800	ug/L	6 550	7 200	6 220	4 760	4 450	-99
Total Nickel	Comp	EPA200.8	5.00	32 200	ug/L	12 700	10 500	8 710	9 600	4 640	-99
Dissolved Selenium	Comp	EPA200.8	5.00	1 170	ug/L	5 690	3 400	1 590	2 850	10 400	-99
Total Selenium	Comp	EPA200.8	5.00	1 590	ug/L	5 870	3 770	1 820	3 290	11 100	-99
Dissolved Silver	Comp	EPA200.8	1.00	-99	ug/L	-99	-99	-99	-99	-99	-99
Total Silver	Comp	EPA200.8	1.00	1 700	ug/L	-99	0 270	-99	-99	-99	-99
Dissolved Thallium	Comp	EPA200.8	5.00	-99	ug/L	-99	-99	-99	-99	-99	-99
Total Thallium	Comp	EPA200.8	5.00	-99	ug/L	-99	-99	-99	-99	-99	-99
Dissolved Zinc	Comp	EPA200.8	50.00	68 900	ug/L	639 000	64 200	23 600	47 200	9 060	-99
Total Zinc	Comp	EPA200.8	50.00	435 000	ug/L	803 000	735 000	58 100	169 000	15 300	-99
<b>Semi-Volatiles Organics (EPA 625)</b>											
2-Chloropheno	Comp	EPA625	2.00	-99	ug/L	-99	-99	-99	-99	-99	-99
2,4-dichloropheno	Comp	EPA625	2.00	-99	ug/L	-99	-99	-99	-99	-99	-99
2,4-dimethylpheno	Comp	EPA625	3.00	-99	ug/L	-99	-99	-99	-99	-99	-99
2,4-dinitropheno	Comp	EPA625	3.00	-99	ug/L	-99	-99	-99	-99	-99	-99
2-nitropheno	Comp	EPA625	3.00	-99	ug/L	-99	-99	-99	-99	-99	-99
4-nitropheno	Comp	EPA625	3.00	-99	ug/L	-99	-99	-99	-99	-99	-99
4-chloro-3-methylpheno	Comp	EPA625	2.00	-99	ug/L	-99	-99	-99	-99	-99	-99
Para-chloropheno	Comp	EPA625	3.00	-99	ug/L	-99	-99	-99	-99	-99	-99
Phenol	Comp	EPA625	1.00	-99	ug/L	-99	-99	-99	-99	-99	-99
2,4,6-trichloropheno	Comp	EPA625	1.00	-99	ug/L	-99	-99	-99	-99	-99	-99



WEATHER CONDITION				Wet				Dry		
STATION NO.	STATION NAME	EVENT CODE	DATE	TS17 North Fork Coyote Creek 2006-07-Event03 12/09/2006	TS17 North Fork Coyote Creek 2006-07-Event06 02/10/2007	TS17 North Fork Coyote Creek 2006-07-Event07 02/19/2007	TS17 North Fork Coyote Creek 2006-07-Event08 02/22/2007	TS17 North Fork Coyote Creek 2006-07-Event09 02/27/2007	TS17 North Fork Coyote Creek 2006-07-Event10 10/31/2006	TS17 North Fork Coyote Creek 2006-07-Event15 04/09/2007
Sample Type	EPA Method	PCL	Units							
Organophosphate Pesticides										
Chlorpyrifos	Comp EPA507	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99
Diazinon	Comp EPA507	0.01	ug/L	-99	-99	-99	-99	0.016	-99	-99
Permethrin	Comp EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Atrazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Simazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Cyanazine	Comp EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Malathion	Comp EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Herbicides										
Glyphosate	Comp EPA547	25.00	ug/L	-99	-99	-99	-99	-99	-99	-99
2,4-D	Comp EPA515.3	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99
2,4,5-TP-SILVEX	Comp EPA515.3	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99
Other										
Ammonia	Comp F	0.1	mg/L	0.860	0.250	0.110	-99	0.270	0.160	0.170
Endrin Kelone	Comp EPA625	0.1	ug/L	-99	-99	-99	-99	-99	-99	-99
Methoxychlor	Comp EPA608	0.5	ug/L	-99	-99	-99	-99	-99	-99	-99

- Note:  
 1) blank cell indicates sample was not analyze  
 2) -99 indicates concentration below minimum detection level  
 3) PCL = minimum level  
 4) Highlighted cells show exceedance

Appendix B. 2007-2008 Sampling Results for Coyote Creek

Mass Emission Monitoring

WEATHER CONDITION STATION NO.	Wet				Dry				
	S13	S13	S13	S13	S13	S13	S13	S13	
EVENT CODE	2007-08Event21 2007-08Event23 2007-08Event29 2007-08Event31				2007-08Event32 2007-08Event37				
EVENT NAME	Coyote Creek				Coyote Creek				
Conventional									
Oil and Grease	Grab	EPA413.1	1	mg/L	-99	-99	1.40	-99	-99
Total Phenols	Grab	EPA420.1	0.10	mg/L	-99	-99	0.40	-99	-99
Cyanide	Grab	EPA335.2	0.01	mg/L	0.2850	-99	-99	0.01	0.0180
pH	Comp	SM4500H B	0.14	mg/L	7.50	6.70	6.97	7.03	6.90
Dissolved Oxygen	Grab	SM4500 G	1.00	mg/L	9.66	9.64	9.10	13.33	11.80
Indicator Bacteria									
Total Coliform	Grab	SM9230B	20.00	MPN/100ml	300	160000	90000	9000	1300
Fecal Coliform	Grab	SM9230B	20.00	MPN/100ml	300	90000	17000	1300	20
Ratio Fecal Coliform/Total Coliform	Grab	SM9230B	20.00	MPN/100ml	130	50000	90000	90000	500
Streptococcus	Grab	SM9230B	20.00	MPN/100ml	130	50000	90000	90000	20
Enterococcus	Grab	SM9230B	20.00	MPN/100ml	130	50000	90000	90000	20
General									
Chloride	Comp	EPA300.0	2.00	mg/L	25	27.40	59	20.80	16
Fluoride	Comp	EPA300.0	0.10	mg/L	0.3470	0.1280	0.4950	0.2170	0.1830
Nitrate	Comp	EPA300.0	0.10	mg/L	-99	-99	-99	-99	-99
Sulfate	Comp	EPA300.0	0.10	mg/L	37.90	38.80	109	31.70	26.10
Alkalinity	Comp	EPA310.1	4.00	mg/L	116.60	50	61	47.30	33
Hardness	Comp	EPA130.2	2.00	mg/L	110	100	205	85	77
COD	Comp	EPA410.4	10.00	mg/L	179	45.40	52.60	34.60	39.81
Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	-99	1.12	2.12	-99
Specific Conductance	Comp	EPA120.1	1.00	umhos/cm	388	346	717	256	219
Total Dissolved Solids	Comp	EPA160.1	2.00	mg/L	272	202	468	160	130
Turbidity	Comp	EPA180.1	0.10	NTU	3.88	5.50	1.81	2.28	5.65
Total Suspended Solids	Comp	EPA160.2	2.00	mg/L	1566	33	35	53	84
Volatile Suspended Solids	Comp	EPA160.4	1.00	mg/L	322	33	3	14	22
MBAS	Comp	EPA425.1	0.05	mg/L	0.3090	0.17	0.10	0.18	0.20
Total Organic Carbon	Comp	EPA415.1	1.00	mg/L	25.20	13.10	8.49	6.87	6.26
BOD	Comp	SM6210B	2.00	mg/L	57.30	16.70	21.40	18.50	6.90
Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99	-99	-99
Nutrients									
Dissolved Phosphorus	Comp	EPA385.3	0.05	mg/L	0.3530	0.2360	0.15	0.23	0.15
Total Phosphorus	Comp	EPA385.3	0.05	mg/L	1.23	0.4990	0.15	0.23	0.17
NH-N	Comp	EPA350.3	0.10	mg/L	2.15	0.53	0.7030	0.2370	0.2680
Nitrate - N	Comp	SM4110B	0.50	mg/L	-99	-99	-99	-99	-99
Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.61	-99	-99	-99
Kieldahl-N	Comp	EPA351.4	0.10	mg/L	10.12	2.62	6.30	1.73	0.9060
Metals									
Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99	-99	-99
Total Aluminum	Comp	EPA200.8	100.00	ug/L	17400	6220	3430	784	1720
Dissolved Antimony	Comp	EPA200.8	5.00	ug/L	2.45	1.66	1.68	1.29	1.33
Total Antimony	Comp	EPA200.8	5.00	ug/L	9.25	2.45	3.59	1.40	2.68
Dissolved Arsenic	Comp	EPA200.8	5.00	ug/L	2.64	1.96	2.25	1.24	3.76
Total Arsenic	Comp	EPA200.8	5.00	ug/L	15.70	2.98	4.64	1.41	2.10
Dissolved Barium	Comp	EPA200.8	10.00	ug/L	43.80	29.90	28.70	18.60	16.80
Total Barium	Comp	EPA200.8	10.00	ug/L	620	93.80	111	25.90	58.20
Dissolved Beryllium	Comp	EPA200.8	1.00	ug/L	-99	-99	-99	-99	-99
Total Beryllium	Comp	EPA200.8	1.00	ug/L	0.51	-99	-99	-99	-99
Dissolved Cadmium	Comp	EPA200.8	1.00	ug/L	4.97	0.52	0.71	-99	0.45
Total Cadmium	Comp	EPA200.8	1.00	ug/L	1.11	1.56	1.37	1.23	1.17
Dissolved Chromium	Comp	EPA200.8	5.00	ug/L	43.30	8.19	7.96	1.98	5.23
Total Chromium	Comp	EPA200.8	10.00	ug/L	-99	0.29	-99	-99	-99
Dissolved Chromium +6	Comp	EPA200.8	10.00	ug/L	-99	0.29	-99	0.25	0.30
Total Chromium +6	Comp	EPA200.8	5.00	ug/L	4.03	6.92	8.22	7.29	6.75
Dissolved Copper	Comp	EPA200.8	5.00	ug/L	351	46	54.10	15.50	32.80
Total Copper	Comp	EPA200.8	5.00	ug/L	527	-99	-99	-99	-99
Dissolved Iron	Comp	EPA200.8	100.00	ug/L	31800	7390	4760	1140	2730
Total Iron	Comp	EPA200.8	100.00	ug/L	2.13	0.62	1.52	0.84	-99
Dissolved Lead	Comp	EPA200.8	5.00	ug/L	147	16.10	25.70	4.73	15.60
Total Lead	Comp	EPA200.8	5.00	ug/L	-99	-99	-99	-99	-99
Dissolved Mercury	Comp	EPA200.8	1.00	ug/L	-99	0.1260	-99	-99	-99
Total Mercury	Comp	EPA200.8	1.00	ug/L	-99	9.84	4.45	2.74	2.31
Dissolved Nickel	Comp	EPA200.8	5.00	ug/L	58	13.10	12.10	3.56	10.50
Total Nickel	Comp	EPA200.8	5.00	ug/L	1.07	-99	-99	-99	-99
Dissolved Selenium	Comp	EPA200.8	5.00	ug/L	1.94	-99	-99	-99	-99
Total Selenium	Comp	EPA200.8	5.00	ug/L	2.50	-99	-99	-99	-99
Dissolved Silver	Comp	EPA200.8	1.00	ug/L	-99	-99	-99	-99	-99
Total Silver	Comp	EPA200.8	5.00	ug/L	-99	-99	-99	-99	-99
Dissolved Thallium	Comp	EPA200.8	5.00	ug/L	-99	-99	-99	-99	-99
Total Thallium	Comp	EPA200.8	50.00	ug/L	15.80	20.50	48	41.50	38.90
Dissolved Zinc	Comp	EPA200.8	50.00	ug/L	2010	202	269	75.30	193
Semi-Volatiles Organics (EPA 625)									
2-Chlorophenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99
2,4-dichlorophenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99
2,4-dimethylphenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99







WEATHER CONDITION STATION NO.	Wet					Dry	
	S14	S14	S14	S14	S14	S14	
STATION NAME	San Gabriel River					San Gabriel River San Gabriel River	
EVENT CODE	2007-08Event121 2007-08Event123 2007-08Event129 2007-08Event131 2007-08Event132					2007-08Event127 2007-08Event147	
	Sample Type	EPA Method	POL	Units			
2,4-dinitrophenol	Comp	EPA625	3.00	ug/L	-99	-99	
2-nitrophenol	Comp	EPA625	3.00	ug/L	-99	-99	
4-nitrophenol	Comp	EPA625	3.00	ug/L	-99	-99	
4-ortho-3-methylphenol	Comp	EPA625	2.00	ug/L	-99	-99	
Pentachlorophenol	Comp	EPA625	2.00	ug/L	-99	-99	
Phenol	Comp	EPA625	1.00	ug/L	-99	-99	
2,4,6-trichlorophenol	Comp	EPA625	1.00	ug/L	-99	-99	
Base/Neutral							
Acenaphthene	Comp	EPA625	0.05	ug/L	-99	-99	
Acenaphthylene	Comp	EPA625	0.05	ug/L	-99	-99	
Anthracene	Comp	EPA625	0.05	ug/L	-99	-99	
Benztidine	Comp	EPA625	3.00	ug/L	-99	-99	
1,2-Benzanthracene	Comp	EPA625	0.10	ug/L	-99	-99	
Benzof(a)pyrene	Comp	EPA625	0.10	ug/L	-99	-99	
Benzof(g,h,i)perylene	Comp	EPA625	1.00	ug/L	-99	-99	
3,4-Benzofluoranthene	Comp	EPA625	2.00	ug/L	-99	-99	
Benzof(k)fluoranthene	Comp	EPA625	0.10	ug/L	-99	-99	
Bis(2-Chloroethoxy)methane	Comp	EPA625	0.10	ug/L	-99	-99	
Bis(2-Chloroisopropyl)ether	Comp	EPA625	1.00	ug/L	-99	-99	
Bis(2-Chloroethyl)ether	Comp	EPA625	0.10	ug/L	-99	-99	
Bis(2-Ethylhexyl)phthalate	Comp	EPA625	1.00	ug/L	-99	-99	
4-Bromophenyl phenyl ether	Comp	EPA625	1.00	ug/L	-99	-99	
Buyl benzyl phthalate	Comp	EPA625	0.30	ug/L	-99	-99	
2-Chloroethyl vinyl ether	Grab	EPA624	2.50	ug/L	-99	-99	
2-Chloronaphthalene	Comp	EPA625	0.10	ug/L	-99	-99	
4-Chlorophenyl phenyl ether	Comp	EPA625	0.10	ug/L	-99	-99	
Chrysene	Comp	EPA625	0.10	ug/L	-99	-99	
Dibenzof(a,h)anthracene	Comp	EPA625	0.50	ug/L	-99	-99	
1,3-Dichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	
1,4-Dichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	
1,2-Dichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	
3,3-Dichlorobenzidine	Comp	EPA625	3.00	ug/L	-99	-99	
Diethyl phthalate	Comp	EPA625	0.50	ug/L	-99	-99	
Dimethyl phthalate	Comp	EPA625	0.50	ug/L	-99	-99	
di-n-Buyl phthalate	Comp	EPA625	1.00	ug/L	-99	-99	
2,4-Dinitrotoluene	Comp	EPA625	0.05	ug/L	-99	-99	
2,6-Dinitrotoluene	Comp	EPA625	0.05	ug/L	-99	-99	
4,6-Dinitro-2-methylphenol	Comp	EPA625	3.00	ug/L	-99	-99	
1,2-Diphenylhydrazine	Comp	EPA625	3.00	ug/L	-99	-99	
di-n-Octyl phthalate	Comp	EPA625	1.00	ug/L	-99	-99	
Fluoranthene	Comp	EPA625	0.10	ug/L	-99	-99	
Fluorene	Comp	EPA625	0.10	ug/L	-99	-99	
Hexachlorobenzene	Comp	EPA625	1.00	ug/L	-99	-99	
Hexachlorobutadiene	Comp	EPA625	1.00	ug/L	-99	-99	
Hexachloro-cyclopentadiene	Comp	EPA625	3.00	ug/L	-99	-99	
Hexachloroethane	Comp	EPA625	1.00	ug/L	-99	-99	
Indeno (1,2,3-cd)pyrene	Comp	EPA625	0.10	ug/L	-99	-99	
Isophorone	Comp	EPA625	0.05	ug/L	-99	-99	
Naphthalene	Comp	EPA625	0.05	ug/L	-99	-99	
Nitrobenzene	Comp	EPA625	0.05	ug/L	-99	-99	
N-Nitroso-dimethyl amine	Comp	EPA625	0.30	ug/L	-99	-99	
N-Nitroso-diphenyl amine	Comp	EPA625	0.30	ug/L	-99	-99	
N-Nitroso-di-n-propyl amine	Comp	EPA625	0.30	ug/L	-99	-99	
Phenanthrene	Comp	EPA625	0.05	ug/L	-99	-99	
Pyrene	Comp	EPA625	0.05	ug/L	-99	-99	
1,2,4-Trichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	
Chlorinated Pesticides							
Adrin	Comp	EPA625	0.05	ug/L	-99	-99	
alpha-BHC	Comp	EPA625	0.05	ug/L	-99	-99	
beta-BHC	Comp	EPA625	0.05	ug/L	-99	-99	
delta-BHC	Comp	EPA625	0.05	ug/L	-99	-99	
Gamma-BHC (Lindane)	Comp	EPA625	0.05	ug/L	-99	-99	
alpha-chlordane	Comp	EPA625	0.05	ug/L	-99	-99	
gamma-chlordane	Comp	EPA625	0.05	ug/L	-99	-99	
Chlordane	Comp	EPA625	0.10	ug/L	-99	-99	
4,4'-DDD	Comp	EPA625	0.10	ug/L	-99	-99	
4,4'-DDE	Comp	EPA625	0.10	ug/L	-99	-99	
4,4'-DDT	Comp	EPA625	0.10	ug/L	-99	-99	
Dieldrin	Comp	EPA625	0.10	ug/L	-99	-99	
Endosulfan I [alpha]	Comp	EPA625	0.10	ug/L	-99	-99	
Endosulfan II [beta]	Comp	EPA625	0.10	ug/L	-99	-99	
Endosulfan sulfate	Comp	EPA625	0.10	ug/L	-99	-99	
Endrin	Comp	EPA625	0.10	ug/L	-99	-99	
Endrin aldehyde	Comp	EPA625	0.10	ug/L	-99	-99	
Heptachlor	Comp	EPA625	0.05	ug/L	-99	-99	
Heptachlor Epoxide	Comp	EPA625	0.05	ug/L	-99	-99	
Toxaphene	Comp	EPA625	1.00	ug/L	-99	-99	

WEATHER CONDITION STATION NO.	Wet					Dry	
	S14	S14	S14	S14	S14	S14	S14
STATION NAME	San Gabriel River					San Gabriel River San Gabriel River San Gabriel River	
EVENT CODE	2007-08Event121 2007-08Event123 2007-08Event129 2007-08Event131 2007-08Event132					2007-08Event127 2007-08Event147	
	Sample Type	EPA Method	PQL	Units			
Polychlorinated Biphenyls							
Acetol-1016	Comp	EPA608	0.50	ug/L	-99	-99	-99
Acetol-1221	Comp	EPA608	0.50	ug/L	-99	-99	-99
Acetol-1232	Comp	EPA608	0.50	ug/L	-99	-99	-99
Acetol-1242	Comp	EPA608	0.50	ug/L	-99	-99	-99
Acetol-1248	Comp	EPA608	0.50	ug/L	-99	-99	-99
Acetol-1254	Comp	EPA608	0.50	ug/L	-99	-99	-99
Acetol-1280	Comp	EPA608	0.50	ug/L	-99	-99	-99
Organophosphate Pesticides							
Chlorpyrifos	Comp	EPA507	0.05	ug/L	-99	-99	-99
Diazinon	Comp	EPA507	0.01	ug/L	-99	-99	-99
Prothiofyn	Comp	EPA507	2.00	ug/L	-99	-99	-99
Atrazine	Comp	EPA507	2.00	ug/L	-99	-99	-99
Simazine	Comp	EPA507	2.00	ug/L	-99	-99	-99
Cyanazine	Comp	EPA507	2.00	ug/L	-99	-99	-99
Malathion	Comp	EPA507	2.00	ug/L	-99	-99	-99
Herbicides							
Glyphosate	Comp	EPA547	25.00	ug/L	-99	-99	-99
2,4-D	Comp	EPA515.3	10.00	ug/L	-99	-99	-99
2,4,5-TP-SILVEX	Comp	EPA515.3	1.00	ug/L	-99	-99	-99
Other							
Ammonia	Comp	SM4500-NH3 F	0.1	mg/L	-99	-99	-99
Enflin ketone	Comp	EPA625	0.1	ug/L	-99	-99	-99
Methoxychlor	Comp	EPA608	0.5	ug/L	-99	-99	-99

## Note:

1) Blank cell indicates DATA is NOT AVAILABLE

2) PQL = minimum level

3) Highlighted cells show exceedances

4) -99 indicates a reported value cannot be achieved

Appendix B. 2007-2008 Sampling Results for Upper San Jose Creek

Tributary Monitoring

WEATHER CONDITION		Wet					Dry	
STATION NO.	TS15							
STATION NAME	Upper San Jose Creek							
EVENT CODE	2007-08E:evn121	2007-08E:evn123	2007-08E:evn129	2007-08E:evn131	2007-08E:evn132	2007-08E:evn128	2007-08E:evn148	
Conventional	Sample Type	EPA Method	POL	Units				
Oil and Grease	Grab	EPA413.1	1	mg/L	2.6			
Total Phenols	Grab	EPA420.1	0.10	mg/L	-99			-99
Cyanide	Grab	EPA335.2	0.01	mg/L	0.0054			-99
pH	Comp	SM4500H B	0.14		7			0.01
	Grab	SM4500 G	1.00	mg/L	7.46	7	6.78	7.39
Indicator Bacteria					6.38	10.56	9.67	16.65
Total Coliform	Grab	SM9230B	20.00	MPN/100ml	900000	160000	240000	50000
Fecal Coliform	Grab	SM9230B	20.00	MPN/100ml	300000	50000	16000	24000
Ratio Fecal Coliform/Total Coliform					0.333	0.313	0.067	0.480
Staphylococcus	Grab	SM9230B	20.00	MPN/100ml	900000	90000	50000	50000
Enterococcus	Grab	SM9230B	20.00	MPN/100ml	300000	90000	50000	50000
General								
Chloride	Comp	EPA300.0	2.00	mg/L	23.6	30.6	16.4	39.3
Fluoride	Comp	EPA300.0	0.10	mg/L	0.353	0.456	0.231	0.186
Nitrate	Comp	EPA300.0	0.10	mg/L	-99	-99	-99	-99
Sulfate	Comp	EPA300.0	0.10	mg/L	33.2	59.4	26.4	56.5
Alkalinity	Comp	EPA310.1	4.00	mg/L	146.3	72	61	46.2
Hardness	Comp	EPA130.2	2.00	mg/L	140	160	110	80
COD	Comp	EPA410.4	10.00	mg/L	84.6	40.7	52	39.4
Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	2.25	1.75	1.75	1.37
Specific Conductance	Comp	EPA120.1	1.00	umhos/cm	435	454	269	257
Total Dissolved Solids	Comp	EPA160.1	2.00	mg/L	268	250	164	152
Turbidity	Comp	EPA180.1	0.10	NTU	2.7	1.86	2.52	2.68
Total Suspended Solids	Comp	EPA160.2	2.00	mg/L	565.3	451	728	89
Volatile Suspended Solids	Comp	EPA160.4	1.00	mg/L	762	86	141	23
MBAS	Comp	EPA425.1	0.05	mg/L	0.218	0.14	0.22	0.19
Total Organic Carbon	Comp	EPA415.1	1.00	mg/L	30.5	12.1	10.5	6.84
BOD	Comp	SM6210B	2.00	mg/L	9.9	15.9	23.4	14.6
Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99	-99
Nutrients								
Dissolved Phosphorus	Comp	EPA385.3	0.05	mg/L	0.569	-99	0.22	0.17
Total Phosphorus	Comp	EPA385.3	0.05	mg/L	1.22	0.847	0.25	0.21
NH3-N	Comp	EPA350.3	0.10	mg/L	4.7	0.82	1.01	0.13
Nitrate - N	Comp	SM4110B	0.50	mg/L	-99	-99	-99	0.563
Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.47	0.05	-99
Kjeldahl-N	Comp	EPA351.4	0.10	mg/L	30.08	4.56	7.28	1.91
Metals								
Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99	-99
Total Aluminum	Comp	EPA200.8	100.00	ug/L	24.930	5.776	40.60	14.60
Dissolved Antimony	Comp	EPA200.8	5.00	ug/L	1.35	1.24	1.38	0.87
Total Antimony	Comp	EPA200.8	5.00	ug/L	4.63	2.38	3.33	1.17
Dissolved Arsenic	Comp	EPA200.8	5.00	ug/L	1.62	2.01	1.1	1.1
Total Arsenic	Comp	EPA200.8	5.00	ug/L	10.2	3.37	2.76	1.15
Dissolved Barium	Comp	EPA200.8	10.00	ug/L	38.3	30	24.6	22.2
Total Barium	Comp	EPA200.8	10.00	ug/L	87.6	108	133	31.5
Dissolved Beryllium	Comp	EPA200.8	1.00	ug/L	-99	-99	-99	-99
Total Beryllium	Comp	EPA200.8	1.00	ug/L	0.54	-99	-99	-99
Dissolved Cadmium	Comp	EPA200.8	1.00	ug/L	-99	0.47	0.47	-99
Total Cadmium	Comp	EPA200.8	1.00	ug/L	6.65	0.86	6.59	-99
Dissolved Chromium	Comp	EPA200.8	5.00	ug/L	0.76	1.88	1.72	1.11
Total Chromium	Comp	EPA200.8	5.00	ug/L	47	7.61	17.6	1.84
Dissolved Chromium +6	Comp	EPA200.8	10.00	ug/L	-99	0.25	-99	-99
Total Chromium +6	Comp	EPA200.8	10.00	ug/L	-99	0.25	-99	0.45
Dissolved Copper	Comp	EPA200.8	5.00	ug/L	1.9	2.23	6.55	5.63
Total Copper	Comp	EPA200.8	5.00	ug/L	390	48	67.1	13.5
Dissolved Iron	Comp	EPA200.8	100.00	ug/L	349	-99	110	-99
Total Iron	Comp	EPA200.8	100.00	ug/L	43400	4130	7370	711
Dissolved Lead	Comp	EPA200.8	5.00	ug/L	1.09	-99	1.52	0.77
Dissolved Mercury	Comp	EPA200.8	1.00	ug/L	0.99	23.3	29	4.77
Total Mercury	Comp	EPA200.8	1.00	ug/L	-99	-99	-99	-99
Dissolved Nickel	Comp	EPA200.8	5.00	ug/L	6.3	3.73	4.32	2.37
Total Nickel	Comp	EPA200.8	5.00	ug/L	58.2	12.5	19.7	3.3
Dissolved Selenium	Comp	EPA200.8	5.00	ug/L	-99	-99	-99	-99
Total Selenium	Comp	EPA200.8	5.00	ug/L	3.33	-99	-99	-99
Dissolved Silver	Comp	EPA200.8	1.00	ug/L	-99	-99	-99	-99
Total Silver	Comp	EPA200.8	1.00	ug/L	1.4	-99	0.68	-99
Dissolved Thallium	Comp	EPA200.8	5.00	ug/L	-99	-99	-99	-99
Total Thallium	Comp	EPA200.8	5.00	ug/L	0.56	-99	-99	-99
Dissolved Zinc	Comp	EPA200.8	50.00	ug/L	17	17.3	49.8	46.6
Total Zinc	Comp	EPA200.8	50.00	ug/L	2120	469	340	94.8
Semi-Volatiles Organics (EPA 625)								
2-Chlorophenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99
2,4-dichlorophenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99
2,4-dimethylphenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99

WEATHER CONDITION		Wet					Dry	
STATION NO.	STATION NAME	TS15						
EVENT CODE		Upper San Jose Creek 2007-08Event121	Upper San Jose Creek 2007-08Event123	Upper San Jose Creek 2007-08Event129	Upper San Jose Creek 2007-08Event131	Upper San Jose Creek 2007-08Event132	Upper San Jose Creek 2007-08Event128	Upper San Jose Creek 2007-08Event148
Sample Type	EPA Method	POL	Units					
2,4-dinitrophenol	Comp EPA625	3.00	ug/L	-99	-99	-99	-99	-99
2-nitrophenol	Comp EPA625	3.00	ug/L	-99	-99	-99	-99	-99
4-nitrophenol	Comp EPA625	3.00	ug/L	-99	-99	-99	-99	-99
4-ortho-3-methylphenol	Comp EPA625	3.00	ug/L	-99	-99	-99	-99	-99
Penta-chlorophenol	Comp EPA625	2.00	ug/L	-99	-99	-99	-99	-99
Phenol	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
2,4,6-trichlorophenol	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
Base/Neutral								
Acenaphthene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Acenaphthylene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Anthracene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Benztidine	Comp EPA625	3.00	ug/L	-99	-99	-99	-99	-99
1,2-Benzanthracene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Benzof(a)pyrene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Benzof(g)h)pyrene	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
3,4-Benzofluoranthene	Comp EPA625	2.00	ug/L	-99	-99	-99	-99	-99
Benzof(k)fluoranthene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Bis(2-Chloroethoxy)methane	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Bis(2-Chloroisopropyl)ether	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
Bis(2-Chloroethyl)ether	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Bis(2-Ethylhexyl)phthalate	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
4-Bromophenyl phenyl ether	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
Buyl benzyl phthalate	Comp EPA625	0.30	ug/L	-99	-99	-99	-99	-99
2-Chloroethyl vinyl ether	Grab EPA624	2.50	ug/L	-99	-99	-99	-99	-99
2-Chloronaphthalene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
4-Chlorophenyl phenyl ether	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Chrysene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Dibenzof(a,h)anthracene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
1,3-Dichlorobenzene	Comp EPA625	0.50	ug/L	-99	-99	-99	-99	-99
1,4-Dichlorobenzene	Comp EPA625	0.50	ug/L	-99	-99	-99	-99	-99
1,2-Dichlorobenzene	Comp EPA625	0.50	ug/L	-99	-99	-99	-99	-99
3,3-Dichlorobenzidine	Comp EPA625	3.00	ug/L	-99	-99	-99	-99	-99
Diethyl phthalate	Comp EPA625	0.50	ug/L	-99	-99	-99	-99	-99
Dimethyl phthalate	Comp EPA625	0.50	ug/L	-99	-99	-99	-99	-99
di-n-Buyl phthalate	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
2,4-Dinitrotoluene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
2,6-Dinitrotoluene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
4,6-Dinitro-2-methylphenol	Comp EPA625	3.00	ug/L	-99	-99	-99	-99	-99
1,2-Diphenylhydrazine	Comp EPA625	3.00	ug/L	-99	-99	-99	-99	-99
di-n-Octyl phthalate	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
Fluoranthene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Fluorene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Hexachlorobenzene	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
Hexachlorocyclopentadiene	Comp EPA625	3.00	ug/L	-99	-99	-99	-99	-99
Hexachlorothiane	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99
Indeno (1,2,3-cd)pyrene	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Isothronene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Naphthalene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Nitrobenzene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
N-Nitroso-dimethyl amine	Comp EPA625	0.30	ug/L	-99	-99	-99	-99	-99
N-Nitroso-diphenyl amine	Comp EPA625	0.30	ug/L	-99	-99	-99	-99	-99
N-Nitroso-di-n-propyl amine	Comp EPA625	0.30	ug/L	-99	-99	-99	-99	-99
Phenanthrene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Pyrene	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
1,2,4-Trichlorobenzene	Comp EPA625	0.50	ug/L	-99	-99	-99	-99	-99
Chlorinated Pesticides								
Adrin	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
alpha-BHC	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
beta-BHC	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
delta-BHC	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Gamma-BHC (Lindane)	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
alpha-chlordane	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
gamma-chlordane	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Chlordane	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
4,4'-DDD	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
4,4'-DDE	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
4,4'-DDT	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Dieldrin	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Endosulfan I [alpha]	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Endosulfan II [beta]	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Endosulfan sulfate	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Endrin	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Endrin aldehyde	Comp EPA625	0.10	ug/L	-99	-99	-99	-99	-99
Heptachlor	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Heptachlor Epoxide	Comp EPA625	0.05	ug/L	-99	-99	-99	-99	-99
Toxaphene	Comp EPA625	1.00	ug/L	-99	-99	-99	-99	-99

WEATHER CONDITION		Wet					Dry			
STATION NO.		TS15								
STATION NAME		Upper San Jose Creek								
EVENT CODE		2007-08Event121	2007-08Event123	2007-08Event129	2007-08Event131	2007-08Event132	2007-08Event128	2007-08Event148		
	Sample Type	EPA Method	POL	Units						
Polychlorinated Biphenyls										
Acetol-1016	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	
Acetol-1221	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	
Acetol-1232	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	
Acetol-1242	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	
Acetol-1248	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	
Acetol-1254	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	
Acetol-1280	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	
Organophosphate Pesticides										
Chlorpyrifos	Comp	EPA507	0.05	ug/L	-99	-99	-99	-99	-99	
Diazinon	Comp	EPA507	0.01	ug/L	-99	-99	-99	-99	0.017	
Promethyn	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	
Atrazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	
Simazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	
Cyanazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	
Malathion	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	
Herbicides										
Glyphosate	Comp	EPA547	25.00	ug/L	-99	-99	-99	-99	-99	
2,4-D	Comp	EPA515.3	10.00	ug/L	-99	-99	-99	-99	-99	
2,4,5-TP-SILVEX	Comp	EPA515.3	1.00	ug/L	-99	-99	-99	-99	-99	
Other										
Ammonia	Comp	SM4500-NH3 F	0.1	mg/L	5.69	0.99	1.22	0.687	0.375	0.67
Enflin ketone	Comp	EPA625	0.1	ug/L	-99	-99	-99	-99	-99	-99
Methoxychlor	Comp	EPA608	0.5	ug/L	-99	-99	-99	-99	-99	-99

## Note:

1) Blank cell indicates DATA is NOT AVAILABLE

2) PQL = minimum level

3) Highlighted cells show exceedances

4) -99 indicates a reported value cannot be achieved





Appendix B. 2007-2008 Sampling Results for North Fork Coyote Creek

Tributary Monitoring

WEATHER CONDITION		Met						Dry	
STATION NO.	STATION NAME	TS17	TS17						
EVENT CODE		North Fork Coyote Creek 2007-08Event121	North Fork Coyote Creek 2007-08Event123	North Fork Coyote Creek 2007-08Event129	North Fork Coyote Creek 2007-08Event131	North Fork Coyote Creek 2007-08Event132	North Fork Coyote Creek 2007-08Event126	North Fork Coyote Creek 2007-08Event148	

Polyhalogenated Biphenyls	Sample Type	EPA Method	POL	Units	Met						Dry		
					TS17	TS17	TS17	TS17	TS17	TS17	TS17	TS17	
Aroclor-1016	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1221	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1232	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1242	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1248	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1254	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1280	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Organophosphate Pesticides													
Chlorpyrifos	Comp	EPA507	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Diazinon	Comp	EPA507	0.01	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Propetryn	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Atrazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Simazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Cyanazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Malathion	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Herbicides													
Glyphosate	Comp	EPA547	25.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4-D	Comp	EPA515.3	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4,5-TP-SILVEX	Comp	EPA515.3	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99
Other													
Ammonia	Comp	SM4500-NH3 F	0.1	mg/L	0.39	3.46	0.121	0.264	0.319	0.16	0.344		
Enflin ketone	Comp	EPA625	0.1	ug/L	-99	-99	-99	-99	-99	-99	-99		
Methoxychlor	Comp	EPA608	0.5	ug/L	-99	-99	-99	-99	-99	-99	-99		

- Note:
- 1) Blank cell indicates DATA is NOT AVAILABLE
  - 2) PQL = minimum level
  - 3) Highlighted cells show exceedances
  - 4) -99 indicates a reported value cannot be achieved

Appendix B

2008-2009 Sampling Results for Coyote Creek

					Wet									Dry				
WEATHER CONDITION					S13													
STATION NO.					Coyote													
STATION NAME					Creek													
EVENT CODE					2008-09Event03	2008-09Event06	2008-09Event09	2008-09Event10	2008-09Event11	2008-09Event18	2008-09Event21	2008-09Event22	2008-09Event23	2008-09Event24	2008-09Event26	2008-09Event30	2008-09Event36	
DATE					11/04/2008	11/25/2008	12/15/2008	12/21/2008	12/24/2008	01/23/2009	02/05/2009	02/08/2009	02/13/2009	02/16/2009	03/04/2009	01/12/2009	03/23/2009	05/11/2009
Sample Type																		
EPA Method																		
PQL <sup>3</sup>																		
Units																		
Conventional																		
Oil and Grease	Grab	EPA1664A / EPA413.1	1	mg/L	2.1	1.1	1.1				3.6		0.7			-99	0.9	0.5
Total Phenols	Grab	EPA420.1	0.10	mg/L	-99	-99	-99				-99		-99			-99	-99	-99
Cyanide	Grab	SM4500-CNE	0.01	mg/L	-99	-99	-99				-99		-99			0.015	0.01	0.014
pH	Comp	SM4500H B	0.00	NONE	7.38	6.98	7.42				7.1		7.3			8.42	8.23	8.66
Dissolved Oxygen	Grab	SM4500 (OG)	1.00	mg/L	11.1	10.3	9.87				9.54		13.6			20.7	12.1	14.5
Indicator Bacteria																		
Total Coliform	Grab	SM9221B/SM9221E	20.00	MPN/100ml	16000000	30000	240000				160000		5000			1700	5000	3000
Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	2200000	24000	90000				5000		1300			300	230	800
Streptococcus	Grab	SM9230B	20.00	MPN/100ml	1700000	240000	240000				17000		50000			230	230	40
Enterococcus	Grab	SM9230B	20.00	MPN/100ml	1700000	240000	130000				17000		50000			80	230	40
General																		
Chloride	Comp	SM4110B	2.00	mg/L	29	31.9	20.8				21.4		19.6			153	149	193
Fluoride	Comp	SM4110B	0.10	mg/L	0.33	0.14	-99				0.1		-99			0.93	0.95	1.15
Nitrate	Comp	SM4110B	0.10	mg/L	10.4	7.51	5.34				4.1		3.59			17.2	7.33	5.28
Sulfate	Comp	SM4110B	1.00	mg/L	45.9	53.3	34.7				35.7		33			261	239	332
Alkalinity	Comp	SM2320B	1.00	mg/L	66	50	61				55		41			254	215	234
Hardness	Comp	SM2340C	2.00	mg/L	130	75	90				100		60			400	310	356
COD	Comp	SM5220D	10.00	mg/L	102	50.5	71.9				161		35.1			97.1	78.3	62
Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	1.62	1.5					1		0.87			-99	-99	-99
Specific Conductance	Comp	SM2510B	1.00	umhos/cm	367	344	252				266		231			1776	1472	1952
Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	240	222	162				164		134			1148	952	1200
Turbidity	Comp	SM2130B	0.10	NTU	5.67	9.39	44.4				6.65		14.1			2.03	1.48	0.98
Total Suspended Solids	Comp	SM2540D	1.00	mg/L	1038	159	431				235		90			9	17	6
Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	231	47	62				53		50			4	8	2
MBAS	Comp	SM5540-C	0.05	mg/L	0.36	0.3	-99				0.29		0.1			0.12	0.37	0.16
Total Organic Carbon	Comp	SM510B / EPA415.1	2.00	mg/L	27.4	10.2	10.7				10.7		4.65			5.32	17.5	28
BOD	Comp	SM5210B	2.00	mg/L	39	15.3	13.3				13.3		6.51			18.8	10.8	11.2
Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99				-99		-99			-99	-99	-99
Nutrients																		
Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.25	0.48				0.22		0.12			-99	0.05	-99
Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	1.02	0.49	1.21				0.49		0.59			-99	0.06	0.06
NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.61	0.43	1.33				-99		0.12			-99	-99	-99
Nitrate - N	Comp	SM4110B	0.50	mg/L	2.35	1.07	2.21				0.93		0.81			2.75	1.65	1.19
Nitrite - N	Comp	SM4110B	0.03	mg/L	0.08	-99	-99				-99		-99			0.13	-99	0.07
Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	7.04	1.49	0.97				0.82		0.81			0.8	1.8	1.22
Metals																		
Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99				-99		118			-99	-99	-99
Total Aluminum	Comp	EPA200.8	100.00	ug/L	872	189	2280				1020		1930			-99	-99	-99
Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	2.71	1.28	0.95				1.27		0.84			0.53	1.73	0.81
Total Antimony	Comp	EPA200.8	0.50	ug/L	5.55	2.14	1.56				3.41		1.76			0.56	1.79	0.82
Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	2.49	1.36	1.43				1.64		0.87			3.06	3.13	4.71
Total Arsenic	Comp	EPA200.8	1.00	ug/L	6.76	2.16	3.24				4.26		1.73			3.22	3.28	5.19
Dissolved Barium	Comp	EPA200.8	10.00	ug/L	34.2	25.9	34.7				21.8		20.3			48.7	48.7	45.8
Total Barium	Comp	EPA200.8	10.00	ug/L	256	62	247				125		66.4			55.6	51.1	51.4
Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99				-99		-99			-99	-99	-99
Total Beryllium	Comp	EPA200.8	0.50	ug/L	0.28	-99	0.48				0.21		0.12			-99	-99	-99
Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	0.11				-99		-99			0.23	-99	-99
Total Cadmium	Comp	EPA200.8	0.25	ug/L	1.49	2.01	2.55				0.76		0.38			0.25	-99	-99
Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	1.98	1.37	1.09				1.66		1.58			1.34	4.06	4.56
Total Chromium	Comp	EPA200.8	0.50	ug/L	21	5.43	23.8				18		8.59			2.23	4.38	5.66
Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	0.27	0.37				0.39		0.54			0.59	0.33	-99
Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	0.27	0.37				0.39		0.54			0.59	0.33	-99
Dissolved Copper	Comp	EPA200.8	0.50	ug/L	14.3	8.18	5.17				7.47		5.08			6.18	9.34	3.99
Total Copper	Comp	EPA200.8	0.50	ug/L	170	30.9	31.8				30.9		27.8			15.4	16.4	9.48
Dissolved Iron	Comp	EPA200.8	100.00	ug/L	340	58.2	58.2				-99		93.3			-99	-99	-99
Total Iron	Comp	EPA200.8	100.00	ug/L	9870	3220	19900				8470		3350			119	90.8	114
Dissolved Lead	Comp	EPA200.8	0.50	ug/L	3.19	1.12	1.45				0.74		1.07			-99	-99	-99
Total Lead	Comp	EPA200.8	0.50	ug/L	58.8	12.9	36				30.8		15.2			0.59	0.68	0.76
Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99				-99		-99			-99	-99	-99
Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99				-99		-99			-99	-99	-99
Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	7.42	3.71	2.4				2.62		3.99			3.99	5.49	3.84
Total Nickel	Comp	EPA200.8	1.00	ug/L	23.8	10.1	19.8				15.3		7.1			4.52	6.21	4.69
Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	0.95	-99	0.93				-99		-99			4.79	3.67	5.81
Total Selenium	Comp	EPA200.8	1.00	ug/L	1.67	1.01	1.19				0.54		-99			4.8	3.69	6.26
Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99				-99		-99			-99	-99	-99
Total Silver	Comp	EPA200.8	0.25	ug/L	0.57	0.52	-99				0.24		0.11			-99	-99	-99
Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99				-99		-99			-99	-99	-99
Total Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99				0.44		0.11			-99	-99	-99
Dissolved Zinc	Comp	EPA200.8	10.00	ug/L	9870	44.4	13.6				27.8		30.5			9.89	20.2	14.7
Total Zinc	Comp	EPA200.8	10.00	ug/L	774	193	173				266		128			15.6	23.5	19.6
Semi-Volatiles Organics (EPA 625)																		
2-Chlorophenol	Comp	EPA625	2.00	ug/L	-													

Appendix B

2008-2009 Sampling Results for Coyote Creek

				Wet												Dry		
WEATHER CONDITION	STATION NO.	STATION NAME		S13 Coyote Creek														
EVENT CODE	Sample Type	EPA Method	PQL <sup>3</sup>	Units	2008-09Event03	2008-09Event06	2008-09Event09	2008-09Event10	2008-09Event11	2008-09Event18	2008-09Event21	2008-09Event22	2008-09Event23	2008-09Event24	2008-09Event26	2008-09Event15	2008-09Event30	2008-09Event36
DATE					11/04/2008	11/25/2008	12/15/2008	12/21/2008	12/24/2008	01/23/2009	02/05/2009	02/08/2009	02/13/2009	02/16/2009	03/04/2009	01/12/2009	03/23/2009	05/11/2009
2,4-dinitrophenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2-nitrophenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4-nitrophenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4-chloro-3-methylphenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Pentachlorophenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Phenol	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4,6-trichlorophenol	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Base/Neutral																		
Acenaphthene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Acenaphthylene	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Anthracene	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Benzidine	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,2-Benzanthracene	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Benzo(a)pyrene	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Benzo(g,h,i)perylene	Comp	EPA625	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
3,4-Benzofluoranthene	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Benzo(k)fluoranthene	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Bis(2-Chloroethoxy)methane	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Bis(2-Chloroisopropyl)ether	Comp	EPA625	2	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Bis(2-Chloroethyl)ether	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Bis(2-Ethylhexyl)phthalate	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4-Bromophenyl phenyl ether	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Butyl benzyl phthalate	Comp	EPA625	0.30	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2-Chloroethyl vinyl ether	Comp	EPA624	2.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2-Chloronaphthalene	Comp	EPA625	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4-Chlorophenyl phenyl ether	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Chrysene	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Dibenz(a,h)anthracene	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,3-Dichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,4-Dichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,2-Dichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
3,3-Dichlorobenzidine	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Diethyl phthalate	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Dimethyl phthalate	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
di-n-Butyl phthalate	Comp	EPA625	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4-Dinitrotoluene	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,6-Dinitrotoluene	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4,6 Dinitro-2-methylphenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,2-Diphenylhydrazine	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
di-n-Octyl phthalate	Comp	EPA625	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Fluoranthene	Comp	EPA625	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Fluorene	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Hexachlorobenzene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Hexachlorobutadiene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Hexachloro-cyclopentadiene	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Hexachloroethane	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Indeno (1,2,3-cd)pyrene	Comp	EPA625	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Isophorone	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Naphthalene	Comp	EPA625	0.20	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Nitrobenzene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
N-Nitroso-dimethyl amine	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
N-Nitroso-diphenyl amine	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
N-Nitroso-di-n-propyl amine	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Phenanthrene	Comp	EPA625	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Pyrene	Comp	EPA625	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,2,4-Trichlorobenzene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Chlorinated Pesticides																		
Aldrin	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
alpha-BHC	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
beta-BHC	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
delta-BHC	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Gamma-BHC (Lindane)	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
alpha-chlordane	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
gamma-chlordane	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Chlordane	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4,4'-DDD	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4,4'-DDE	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4,4'-DDT	Comp	EPA608	0.01	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Dieldrin	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endosulfan I [alpha]	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endosulfan II [beta]	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endosulfan sulfate	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endrin	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endrin aldehyde	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Heptachlor	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99

**Appendix B**

**2008-2009 Sampling Results for Coyote Creek**

WEATHER CONDITION STATION NO. STATION NAME EVENT CODE DATE					Wet											Dry		
					S13 Coyote Creek 2008-09Event03 11/04/2008	S13 Coyote Creek 2008-09Event06 11/25/2008	S13 Coyote Creek 2008-09Event09 12/15/2008	S13 Coyote Creek 2008-09Event10 12/21/2008	S13 Coyote Creek 2008-09Event11 12/24/2008	S13 Coyote Creek 2008-09Event18 01/23/2009	S13 Coyote Creek 2008-09Event21 02/05/2009	S13 Coyote Creek 2008-09Event22 02/08/2009	S13 Coyote Creek 2008-09Event23 02/13/2009	S13 Coyote Creek 2008-09Event24 02/16/2009	S13 Coyote Creek 2008-09Event26 03/04/2009	S13 Coyote Creek 2008-09Event15 01/12/2009	S13 Coyote Creek 2008-09Event30 03/23/2009	S13 Coyote Creek 2008-09Event36 05/11/2009
Heptachlor Epoxide	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Toxaphene	Comp	EPA608	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Polychlorinated Biphenyls																		
Aroclor-1016	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Aroclor-1221	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Aroclor-1232	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Aroclor-1242	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Aroclor-1248	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Aroclor-1254	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Aroclor-1260	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Organophosphate Pesticides																		
Chlorpyrifos	Comp	EPA507	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Diazinon	Comp	EPA507	0.01	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Prometryn	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Atrazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Simazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Cyanazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Malathion	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Herbicides																		
Glyphosate	Comp	EPA547	25.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
2,4-D	Comp	EPA515.3	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
2,4,5-TP-SILVEX	Comp	EPA515.3	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Other																		
Ammonia	Comp	SM4500-NH3 F	0.1	mg/l	0.74	0.52	0.4	-99	-99	-99	0.14	-99	-99	-99	-99	-99	-99	
Endrin ketone	Comp	EPA625	1	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	
Methoxychlor	Comp	EPA608	0.5	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	

- Note:  
 1) blank cell indicates sample was not analyzed  
 2) -99 indicates concentration below minimum detection level  
 3) PQL = minimum level  
 4) Highlighted cells show exceedances  
 5) Wet weather suspension of fecal coliform objective applies to 2008-09Event06, 2008-09Event09, and 2008-09Event21

Appendix B

2008-2009 Sampling Results for San Gabriel River

					Wet										Dry																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
WEATHER CONDITION					S14																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
STATION NO.					San Gabriel																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
STATION NAME					River																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
EVENT CODE	Sample	EPA	PQL <sup>3</sup>	Units	2008-09Event03	2008-09Event06	2008-09Event09	2008-09Event11	2008-09Event18	2008-09Event21	2008-09Event22	2008-09Event23	2008-09Event24	2008-09Event26	2008-09Event15	2008-09Event30	2008-09Event36																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
DATE	Type	Method			11/04/2008	11/26/2008	12/15/2008	12/24/2008	01/23/2009	02/05/2009	02/08/2009	02/13/2009	02/16/2009	03/04/2009	01/12/2009	03/23/2009	05/11/2009																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
Conventional																		Oil and Grease	Grab	EPA1664A / EPA413.1	1	mg/L	-99	0.6	-99	-99	-99	0.7	-99	-99	-99	-99	0.5	1.3	-99	Total Phenols	Grab	EPA420.1	0.10	mg/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	Cyanide	Grab	SM4500-CNE	0.01	mg/L	0.01	-99	0.01	0.009	-99	0.009	-99	-99	-99	-99	0.015	0.01	0.013	pH	Comp	SM4500H B	0.00	NONE	8.22	6.92	7.34	7.52	7.52	7.48	7.48	7.48	7.48	7.48	8.29	7.53	8.53	Dissolved Oxygen	Grab	SM4500 (OG)	1.00	mg/L	7.83	7.84	9.29	9.29	9.44	9.44	12.7	12.7	12.7	12.7	9.36	8.18	8.03	Indicator Bacteria																		Total Coliform	Grab	SM9221B/SM9221E	20.00	MPN/100ml	1700000	240000	28000			2200		5000			9000	160000	1700	Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	900000	50000	1400			80		1300			1300	500	230	Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99
Oil and Grease	Grab	EPA1664A / EPA413.1	1	mg/L	-99	0.6	-99	-99	-99	0.7	-99	-99	-99	-99	0.5	1.3	-99	Total Phenols	Grab	EPA420.1	0.10	mg/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	Cyanide	Grab	SM4500-CNE	0.01	mg/L	0.01	-99	0.01	0.009	-99	0.009	-99	-99	-99	-99	0.015	0.01	0.013	pH	Comp	SM4500H B	0.00	NONE	8.22	6.92	7.34	7.52	7.52	7.48	7.48	7.48	7.48	7.48	8.29	7.53	8.53	Dissolved Oxygen	Grab	SM4500 (OG)	1.00	mg/L	7.83	7.84	9.29	9.29	9.44	9.44	12.7	12.7	12.7	12.7	9.36	8.18	8.03	Indicator Bacteria																		Total Coliform	Grab	SM9221B/SM9221E	20.00	MPN/100ml	1700000	240000	28000			2200		5000			9000	160000	1700	Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	900000	50000	1400			80		1300			1300	500	230	Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																		
Total Phenols	Grab	EPA420.1	0.10	mg/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	Cyanide	Grab	SM4500-CNE	0.01	mg/L	0.01	-99	0.01	0.009	-99	0.009	-99	-99	-99	-99	0.015	0.01	0.013	pH	Comp	SM4500H B	0.00	NONE	8.22	6.92	7.34	7.52	7.52	7.48	7.48	7.48	7.48	7.48	8.29	7.53	8.53	Dissolved Oxygen	Grab	SM4500 (OG)	1.00	mg/L	7.83	7.84	9.29	9.29	9.44	9.44	12.7	12.7	12.7	12.7	9.36	8.18	8.03	Indicator Bacteria																		Total Coliform	Grab	SM9221B/SM9221E	20.00	MPN/100ml	1700000	240000	28000			2200		5000			9000	160000	1700	Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	900000	50000	1400			80		1300			1300	500	230	Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																				
Cyanide	Grab	SM4500-CNE	0.01	mg/L	0.01	-99	0.01	0.009	-99	0.009	-99	-99	-99	-99	0.015	0.01	0.013	pH	Comp	SM4500H B	0.00	NONE	8.22	6.92	7.34	7.52	7.52	7.48	7.48	7.48	7.48	7.48	8.29	7.53	8.53	Dissolved Oxygen	Grab	SM4500 (OG)	1.00	mg/L	7.83	7.84	9.29	9.29	9.44	9.44	12.7	12.7	12.7	12.7	9.36	8.18	8.03	Indicator Bacteria																		Total Coliform	Grab	SM9221B/SM9221E	20.00	MPN/100ml	1700000	240000	28000			2200		5000			9000	160000	1700	Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	900000	50000	1400			80		1300			1300	500	230	Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																						
pH	Comp	SM4500H B	0.00	NONE	8.22	6.92	7.34	7.52	7.52	7.48	7.48	7.48	7.48	7.48	8.29	7.53	8.53	Dissolved Oxygen	Grab	SM4500 (OG)	1.00	mg/L	7.83	7.84	9.29	9.29	9.44	9.44	12.7	12.7	12.7	12.7	9.36	8.18	8.03	Indicator Bacteria																		Total Coliform	Grab	SM9221B/SM9221E	20.00	MPN/100ml	1700000	240000	28000			2200		5000			9000	160000	1700	Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	900000	50000	1400			80		1300			1300	500	230	Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																								
Dissolved Oxygen	Grab	SM4500 (OG)	1.00	mg/L	7.83	7.84	9.29	9.29	9.44	9.44	12.7	12.7	12.7	12.7	9.36	8.18	8.03	Indicator Bacteria																		Total Coliform	Grab	SM9221B/SM9221E	20.00	MPN/100ml	1700000	240000	28000			2200		5000			9000	160000	1700	Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	900000	50000	1400			80		1300			1300	500	230	Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																										
Indicator Bacteria																		Total Coliform	Grab	SM9221B/SM9221E	20.00	MPN/100ml	1700000	240000	28000			2200		5000			9000	160000	1700	Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	900000	50000	1400			80		1300			1300	500	230	Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																												
Total Coliform	Grab	SM9221B/SM9221E	20.00	MPN/100ml	1700000	240000	28000			2200		5000			9000	160000	1700	Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	900000	50000	1400			80		1300			1300	500	230	Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																														
Fecal Coliform	Grab	SM9221E/SM9221B	20.00	MPN/100ml	900000	50000	1400			80		1300			1300	500	230	Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																
Streptococcus	Grab	SM9230B	20.00	MPN/100ml	170000	300000	500			40		800			230	-99	-99	Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																		
Enterococcus	Grab	SM9230B	20.00	MPN/100ml	170000	240000	500			40		800			230	-99	-99	General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																				
General																		Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																						
Chloride	Comp	SM4110B	2.00	mg/L	93.7	22.8	55.1			34.1		48.5			166		108	Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																								
Fluoride	Comp	SM4110B	0.10	mg/L	0.52	-99	0.12			0.11		0.13			0.29	0.51	0.91	Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																										
Nitrate	Comp	SM4110B	0.10	mg/L	24.7	7.61	12.1			7.24		4.99			27.2	25.1	26.2	Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																												
Sulfate	Comp	SM4110B	1.00	mg/L	120	40.7	76.2			52.7		58.3			219	113	117	Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																														
Alkalinity	Comp	SM2320B	1.00	mg/L	138	50	72			57		89			172	119	151	Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																
Hardness	Comp	SM2340C	2.00	mg/L	230	90	145			105		150			325	210	236	COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																		
COD	Comp	SM5220D	10.00	mg/L	66.5	66.9				60.3		65.1			63.2	60.5	25	Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																				
Total Petroleum Hydrocarbons	Grab	EPA418.1	1.00	mg/L	-99	0.75	0.37			1.12		-99			-99	-99	-99	Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																						
Specific Conductance	Comp	SM2510B	1.00	umhos/cm	845	275	499			364		486			1241	828	1045	Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																								
Total Dissolved Solids	Comp	SM2540C	2.00	mg/L	554	180	302			214		290			764	516	620	Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																										
Turbidity	Comp	SM2130B	0.10	NTU	3.25	18.1	6.33			30.5		16.1			1.22	1.84	1.3	Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																												
Total Suspended Solids	Comp	SM2540D	1.00	mg/L	16	211	261	64	55	113	74	156	87	76	13	21	17	Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																														
Volatile Suspended Solids	Comp	SM2540E	1.00	mg/L	4	45	37			8		24			6	7	3	MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																
MBAS	Comp	SM5540-C	0.05	mg/L	0.37	0.1	0.08			-99		0.03			0.09	0.26	0.08	Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
Total Organic Carbon	Comp	SM5310B / EPA415.1		mg/L	13.2	8.94	7.11			5.68		5.33			4.91	10.1	9.5	BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
BOD	Comp	SM5210B	2.00	mg/L	13.7	11.8	8			4.56		7.42			14.8	11.7	10.6	Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
Methyl Tertiary Butyl Ether (MTBE)	Grab	EPA624	1.00	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
Nutrients																		Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
Dissolved Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.23	0.23	0.15			0.3		0.07			-99	0.33	0.28	Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
Total Phosphorus	Comp	SM4500-PE	0.05	mg/L	0.58	0.44	0.44			0.41		0.13			-99	0.42	0.47	NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
NH3-N	Comp	SM4500-NH3 F	0.10	mg/L	0.97	0.31	-99			-99		0.11			0.33	0.38	0.4	Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
Nitrate - N	Comp	SM4110B	0.50	mg/L	5.58	1.72	2.73			1.63		1.13			6.14	5.67	5.91	Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
Nitrite - N	Comp	SM4110B	0.03	mg/L	-99	0.04	-99			-99		-99			0.07	-99	0.04	Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
Kjeldahl-N	Comp	SM4500-NHorg C	0.10	mg/L	2.44	3.24	0.6			0.62		0.9			1.25	1.98	1.18	Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
Metals																		Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
Dissolved Aluminum	Comp	EPA200.8	100.00	ug/L	-99	-99	-99			-99		165			-99	-99	-99	Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
Total Aluminum	Comp	EPA200.8	100.00	ug/L	-99	635	675			2340		1360			-99	-99	292	Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
Dissolved Antimony	Comp	EPA200.8	0.50	ug/L	1.14	0.94	0.6			0.61		0.53			0.47	0.88	0.62	Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
Total Antimony	Comp	EPA200.8	0.50	ug/L	1.24	2.05	1.19			1.05		0.89			0.62	0.89	0.68	Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
Dissolved Arsenic	Comp	EPA200.8	1.00	ug/L	1.57	1.22	1.08			0.99		1.13			1.18	1.43	1.6	Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
Total Arsenic	Comp	EPA200.8	1.00	ug/L	1.7	2.87	2.24			2.8		1.9			1.23	1.51	1.61	Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
Dissolved Barium	Comp	EPA200.8	10.00	ug/L	37.7	22.3	29.1			26.2		33.3			56.4	34.3	42.3	Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
Total Barium	Comp	EPA200.8	10.00	ug/L	50.8	120	85.2			153		63.1			64.8	35.9	52	Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
Dissolved Beryllium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
Total Beryllium	Comp	EPA200.8	0.50	ug/L	-99	0.22	0.17			0.39		0.11			-99	-99	-99	Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
Dissolved Cadmium	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		0.1			0.12	-99	-99	Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
Total Cadmium	Comp	EPA200.8	0.25	ug/L	-99	0.74	0.47			0.54		0.37			0.14	-99	-99	Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
Dissolved Chromium	Comp	EPA200.8	0.50	ug/L	2.98	0.99	1.1			1.42		2.19			1.05	0.78	1.7	Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
Total Chromium	Comp	EPA200.8	0.50	ug/L	3.53	15.4	11.6			25.7		6.91			3.02	1.03	1.73	Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
Dissolved Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
Total Chromium +6	Comp	EPA218.6	0.25	ug/L	-99	-99	0.25			0.26		0.38			0.35	-99	-99	Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
Dissolved Copper	Comp	EPA200.8	0.50	ug/L	5.76	4.84	3.47			3.26		3.12			2.95	5.21	3.73	Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
Total Copper	Comp	EPA200.8	0.50	ug/L	11.4	43.8	23.9			31.4		15.7			7.11	10.7	10.5	Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
Dissolved Iron	Comp	EPA200.8	100.00	ug/L	80.7	125	-99			95.9		150			-99	52.6	-99	Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
Total Iron	Comp	EPA200.8	100.00	ug/L	452	10300	7740			17700		2970			375	119	618	Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
Dissolved Lead	Comp	EPA200.8	0.50	ug/L	0.81	1.72	1.1			1.06		1.01			0.25	0.29	0.23	Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
Total Lead	Comp	EPA200.8	0.50	ug/L	1.97	42.3	14.6			17.7		7.49			1.49	0.8	1.8	Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
Dissolved Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
Total Mercury	Comp	EPA245.1	0.10	ug/L	-99	-99	0.15			-99		-99			-99	0.11	-99	Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
Dissolved Nickel	Comp	EPA200.8	1.00	ug/L	4.42	3.01	2.66			4.53		2.38			4.32	4.2	4.69	Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
Total Nickel	Comp	EPA200.8	1.00	ug/L	5.23	15.3	9.38			18.6		6.43			5	4.82	5.82	Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
Dissolved Selenium	Comp	EPA200.8	1.00	ug/L	1.23	0.71	0.68			-99		-99			2.11	1.23	1.22	Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
Total Selenium	Comp	EPA200.8	1.00	ug/L	1.42	0.97	0.71			-99		0.6			2.36	1.4	1.41	Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
Dissolved Silver	Comp	EPA200.8	0.25	ug/L	-99	-99	-99			-99		-99			-99	-99	-99	Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
Total Silver	Comp	EPA200.8	0.25	ug/L	-99	0.24	-99			0.11		-99			-99	-99	-99	Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
Dissolved Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99			-99		-99			-99	-99	-99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						

Appendix B

2008-2009 Sampling Results for San Gabriel River

WEATHER CONDITION STATION NO. STATION NAME EVENT CODE DATE					Wet										Dry		
					S14 San Gabriel River 2008-09Event03	S14 San Gabriel River 2008-09Event06	S14 San Gabriel River 2008-09Event09	S14 San Gabriel River 2008-09Event11	S14 San Gabriel River 2008-09Event18	S14 San Gabriel River 2008-09Event21	S14 San Gabriel River 2008-09Event22	S14 San Gabriel River 2008-09Event23	S14 San Gabriel River 2008-09Event24	S14 San Gabriel River 2008-09Event26	S14 San Gabriel River 2008-09Event15	S14 San Gabriel River 2008-09Event30	S14 San Gabriel River 2008-09Event36
Sample Type	EPA Method	PQL <sup>3</sup>	Units														
Total Thallium	Comp	EPA200.8	0.50	ug/L	-99	-99	-99	-99	0.2	14.9	-99	-99	-99	-99	-99	-99	-99
Dissolved Zinc	Comp	EPA200.8	10.00	ug/L	35.7	18.5	23.2	-99	-99	16.4	-99	-99	-99	-99	-99	-99	-99
Total Zinc	Comp	EPA200.8	10.00	ug/L	48.4	223	143	-99	100	58	-99	-99	-99	-99	-99	-99	-99
Semi-Volatiles Organics (EPA 625)																	
2-Chlorophenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4-dichlorophenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4-dimethylphenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4-dinitrophenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2-nitrophenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4-nitrophenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4-chloro-3-methylphenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Pentachlorophenol	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Phenol	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4,6-trichlorophenol	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	0.89	-99	-99	-99
Base/Neutral																	
Acenaphthene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Acenaphthylene	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Anthracene	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Benzidine	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,2 Benzanthracene	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Benzo(a)pyrene	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Benzo(a,h)perylene	Comp	EPA625	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
3,4 Benzofluoranthene	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Benzo(k)fluoranthene	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Bis(2-Chloroethoxy)methane	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Bis(2-Chloroisopropyl)ether	Comp	EPA625	2	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Bis(2-Chloroethyl)ether	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Bis(2-Ethylhexyl)phthalate	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4-Bromophenyl phenyl ether	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Butyl benzyl phthalate	Comp	EPA625	0.30	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2-Chloroethyl vinyl ether	Comp	EPA624	2.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2-Chloronaphthalene	Comp	EPA625	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4-Chlorophenyl phenyl ether	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Chrysene	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Dibenzo(a,h)anthracene	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,3-Dichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,4-Dichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,2-Dichlorobenzene	Comp	EPA625	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
3,3-Dichlorobenzidine	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Diethyl phthalate	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Dimethyl phthalate	Comp	EPA625	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
di-n-Butyl phthalate	Comp	EPA625	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4-Dinitrotoluene	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,6-Dinitrotoluene	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4,6 Dinitro-2-methylphenol	Comp	EPA625	3.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,2-Diphenylhydrazine	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
di-n-Octyl phthalate	Comp	EPA625	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Fluoranthene	Comp	EPA625	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Fluorene	Comp	EPA625	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Hexachlorobenzene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Hexachlorobutadiene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Hexachloro-cyclopentadiene	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Hexachloroethane	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Indeno (1,2,3-cd)pyrene	Comp	EPA625	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Isophorone	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Naphthalene	Comp	EPA625	0.20	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Nitrobenzene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
N-Nitroso-dimethyl amine	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
N-Nitroso-diphenyl amine	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
N-Nitroso-di-n-propyl amine	Comp	EPA625	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Phenanthrene	Comp	EPA625	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Pyrene	Comp	EPA625	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
1,2,4-Trichlorobenzene	Comp	EPA625	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Chlorinated Pesticides																	
Aldrin	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
alpha-BHC	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
beta-BHC	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
delta-BHC	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99

**Appendix B**

**2008-2009 Sampling Results for San Gabriel River**

					Wet										Dry		
WEATHER CONDITION					S14												
STATION NO.					San Gabriel												
STATION NAME					River												
EVENT CODE	Sample	EPA	PQL <sup>3</sup>	Units	2008-09Event03	2008-09Event06	2008-09Event09	2008-09Event11	2008-09Event18	2008-09Event21	2008-09Event22	2008-09Event23	2008-09Event24	2008-09Event26	2008-09Event15	2008-09Event30	2008-09Event36
DATE	Type	Method			11/04/2008	11/26/2008	12/15/2008	12/24/2008	01/23/2009	02/05/2009	02/08/2009	02/13/2009	02/16/2009	03/04/2009	01/12/2009	03/23/2009	05/11/2009
Gamma-BHC (Lindane)	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
alpha-chlordane	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
gamma-chlordane	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Chlordane	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4,4'-DDD	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4,4'-DDE	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
4,4'-DDT	Comp	EPA608	0.01	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Dieldrin	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endosulfan I [alpha]	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endosulfan II [beta]	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endosulfan sulfate	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endrin	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Endrin aldehyde	Comp	EPA608	0.10	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Heptachlor	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Heptachlor Epoxide	Comp	EPA608	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Toxaphene	Comp	EPA608	1.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Polychlorinated Biphenyls																	
Aroclor-1016	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1221	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1232	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1242	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1248	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1254	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Aroclor-1260	Comp	EPA608	0.50	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Organophosphate Pesticides																	
Chlorpyrifos	Comp	EPA507	0.05	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Diazinon	Comp	EPA507	0.01	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Prometryn	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Atrazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Simazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Cyanazine	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Malathion	Comp	EPA507	2.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Herbicides																	
Glyphosate	Comp	EPA547	25.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4-D	Comp	EPA515.3	5.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
2,4,5-TP-SILVEX	Comp	EPA515.3	10.00	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Other																	
Ammonia	Comp	SM4500-NH3 F	0.1	mg/l	1.18	0.38	-99	-99	-99	-99	-99	0.13	-99	-99	0.4	0.46	0.48
Endrin ketone	Comp	EPA625	1	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99
Methoxychlor	Comp	EPA608	0.5	ug/L	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99	-99

- Note:  
 1) blank cell indicates sample was not analyzed  
 2) -99 indicates concentration below minimum detection level  
 3) PQL = minimum level  
 4) Highlighted cells show exceedances  
 5) Wet weather suspension of fecal coliform objective applies to 2008-09Event06, 2008-09Event09, and 2008-09Event21

**Appendix B.2. 2009-2010 Annual Report Mass Emission and Tributary Dry Weather Concentration**

Group	Parameter Code	Units	Analysis_Method	Coyote Creek S13 2009-10Event02 07/14/2009	Coyote Creek S13 2009-10Event12 09/15/2009	Coyote Creek S13 2009-10Event14 12/01/2009	Coyote Creek S13 2009-10Event28 03/23/2010
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	9,000*	1,300*	300	1,400*
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	40	230	300	80
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	40	230	300	80
Bacteria	Total Coliform	MPN/100mL	SM9221B	50,000	2,400	3,000	16,000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.01	<0.011	<0.011	<0.011
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	<0.002	<0.002	<0.002
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	<0.05	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	<0.006	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Endrin ketone	ug/L	EPA625	<0	NS	NS	NS
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	<0.003	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	<0.24	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.003	<0.01	<0.01	<0.01
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.04	<0.033	<0.033	<0.033
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.04	<0.033	<0.033	<0.033
Conventionals	Cyanide	mg/L	SM4500-CNE	0.034*	0.01	0.016	0.02
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	15.6	20	15.2	18
Conventionals	Oil and Grease	mg/L	EPA1664A	<0.4	<0.4	<1.44	<1.44
Conventionals	pH	pH units	SM4500H B	8.31	8.04	8.18	8.58*
General	Alkalinity as CaCO3	mg/L	SM2320B	275	220	289	275
General	Ammonia	mg/L	SM4500-NH3 F	0.55	0.121	0.121	0.133
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	14.5	14.8	12.1	24
General	Chemical Oxygen Demand	mg/L	SM5220D	368	74.8	55.8	117
General	Chloride	mg/L	SM4110B	262	205	194	237
General	Dissolved Phosphorus	mg/L	SM4500-PE	0.05	<0.05	<0.05	<0.05
General	Fluoride	mg/L	SM4110B	1.23	1.11	1.23	1.18
General	Hardness as CaCO3	mg/L	SM2340C	380	355	410	400
General	Kjeldahl-N	mg/L	SM4500-NHorg C	3.3	0.92	0.62	0.76
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<0.4	<0.4	<1	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5
General	NH3-N	mg/L	SM4500-NH3 F	0.45	0.1	0.1	0.11
General	Nitrate (NO3)	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrate (NO3)	mg/L	SM4110B	4.49	8.22	17.7	12.5
General	Nitrate-N	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrate-N	mg/L	SM4110B	1.01	2.03	4	2.82
General	Nitrite (NO2)	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrite-N	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrite-N	mg/L	SM4110B	0.06	0.058	<0.01	0.133
General	Phosphorus- Total (as P)	mg/L	SM4500-PE	0.11	<0.05	<0.05	<0.05
General	Specific Conductance	umhos/cm	SM2510B	1836	1590	1800	1830
General	Sulfate	mg/L	EPA300.1	NS	NS	NS	NS
General	Sulfate	mg/L	SM4110B	439	329	357	423
General	Total Dissolved Phosphate	mg/L	AM4500-PE	NS	NS	NS	NS
General	Total Dissolved Solids	mg/L	SM2540C	1,276	1,080	1,250	1,260
General	Total Organic Carbon	mg/L	SM5310B	11.2	NS	NS	NS
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	NS	9.74	4.7	21
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<0.4	<0.4	<1.5	<1.5
General	Total Phosphate	mg/L	SM4500-PE	NS	NS	NS	NS
General	Total Suspended Solids	mg/L	SM2540D	141	78	14	16
General	Turbidity	NTU	SM2130B	3.89	3.08	0.98	1.88
General	Volatile Suspended Solids	mg/L	SM2540E	38	25	2	5

**Appendix B.2. 2009-2010 Annual Report Mass Emission and Tributary Dry Weather Concentration**

Group	Parameter Code	Units	Analysis_Method	Coyote Creek S13 2009-10Event02 07/14/2009	Coyote Creek S13 2009-10Event12 09/15/2009	Coyote Creek S13 2009-10Event14 12/01/2009	Coyote Creek S13 2009-10Event28 03/23/2010
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.07	<0.067	<0.067	<0.067
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	<0.015	<0.015	<0.015
Herbicides	Glyphosate	ug/L	EPA547	<5	<5	<5	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	<50	<50	<50	<50
Metals	Dissolved Antimony	ug/L	EPA200.8	0.85	0.794	0.557	0.562
Metals	Dissolved Arsenic	ug/L	EPA200.8	5.92	4.58	5.35	3.77
Metals	Dissolved Barium	ug/L	EPA200.8	55	55	49.9	49.1
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	1.44	0.938	1.42	1.34
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	<0.25	<0.25	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	5.36	4.82	4.17	5.34
Metals	Dissolved Iron	ug/L	EPA200.8	<50	<50	<50	<50
Metals	Dissolved Lead	ug/L	EPA200.8	>0.28<0.5	<0.2	<0.2	<0.2
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	4.3	2.97	3.91	3.42
Metals	Dissolved Selenium	ug/L	EPA200.8	6.39	4.38	9.64	5.61
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	12.4	8.2	<1	24.3
Metals	Aluminum	ug/L	EPA200.8	303	187	<50	166
Metals	Antimony	ug/L	EPA200.8	0.93	0.875	0.663	0.644
Metals	Arsenic	ug/L	EPA200.8	6.06	4.93	5.4	4.09
Metals	Barium	ug/L	EPA200.8	73.4	74.4	59.6	61.8
Metals	Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Chromium	ug/L	EPA200.8	2.01	0.965	4.28	2.14
Metals	Chromium +6	ug/L	EPA218.6	<0.25	<0.25	<0.25	<0.25
Metals	Copper	ug/L	EPA200.8	14	13.5	9.12	11.3
Metals	Iron	ug/L	EPA200.8	700	417	118	<50
Metals	Lead	ug/L	EPA200.8	2.17	1.51	<0.2	1.17
Metals	Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	5.63	4.52	4.76	4.52
Metals	Selenium	ug/L	EPA200.8	6.49*	4.48	9.77*	6.08*
Metals	Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	46.6	71.6	38.5	40.6
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.7	<0.667	<0.667	<0.667
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	<0.02	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.7	<0.667	<0.667	<0.667
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	<0.003	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.4	<0.33	<0.67	<0.33
Organophosphate Pesticides	Malathion	ug/L	EPA625	NS	NS	NS	NS
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.7	<0.67	<0.67	<0.67
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.7	<0.67	<0.67	<0.67
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<0.4	<3.3	<3.3	<3.3
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1

**Appendix B.2. 2009-2010 Annual Report Mass Emission and Tributary Dry Weather Concentration**

Group	Parameter Code	Units	Analysis_Method	Coyote Creek S13 2009-10Event02 07/14/2009	Coyote Creek S13 2009-10Event12 09/15/2009	Coyote Creek S13 2009-10Event14 12/01/2009	Coyote Creek S13 2009-10Event28 03/23/2010
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<0.03	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.2	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.2	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.2	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA625	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.4	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<0.4	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<0.04	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benidine	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)fluoranthene	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(g-h-i)perylene	ug/L	EPA625	<0.2	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<0.1	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.04	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.02	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.04	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	<0.02	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.07	<0.067	<0.067	<0.067
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.02	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.02	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	<3.4	NS	NS	NS
Semivolatile Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	<3.4	NS	NS	NS

Values reported with a "<" are not detected (ND) at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected but not quantified (DNQ) between the method detection limit and reporting limit, they are

QNS = Quantity Not Sufficient

**Appendix B.2. 2009-2010 Annual Report Mass Emission and Tributary Dry Weather Concentration**

Group	Parameter Code	Units	Analysis_Method	San Gabriel River @ SGR Parkway S14 2009-10Event02 07/14/2009	San Gabriel River @ SGR Parkway S14 2009-10Event12 09/15/2009	San Gabriel River @ SGR Parkway S14 2009-10Event14 12/01/2009	San Gabriel River @ SGR Parkway S14 2009-10Event28 03/23/2010
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	800*	300	230	800*
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	20	800	300	<20
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	20	800	300	<20
Bacteria	Total Coliform	MPN/100mL	SM9221B	2,200	9,000	3,000	24,000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.01	<0.011	<0.011	<0.011
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	<0.002	<0.002	<0.002
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	<0.05	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	<0.006	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Endrin ketone	ug/L	EPA625	<0	NS	NS	NS
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	<0.003	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	<0.24	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.003	<0.01	<0.01	<0.01
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.04	<0.033	<0.033	<0.033
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.04	<0.033	<0.033	<0.033
Conventionals	Cyanide	mg/L	SM4500-CNE	0.021	0.02	0.025*	0.01
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	8.79	10.4	11.8	12.4
Conventionals	Oil and Grease	mg/L	EPA1664A	<0.4	<0.4	<1.44	<1.44
Conventionals	pH	pH units	SM4500H B	8.19	7.98	7.82	8.01
General	Alkalinity as CaCO3	mg/L	SM2320B	179	151	165	165
General	Ammonia	mg/L	SM4500-NH3 F	0.92	0.581	0.678	0.169
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	9.72	25.3	41.2	5.9
General	Chemical Oxygen Demand	mg/L	SM5220D	116	84.3	66.1	57.9
General	Chloride	mg/L	SM4110B	138	161*	113	118
General	Dissolved Phosphorus	mg/L	SM4500-PE	0.16	0.09	0.13	0.07
General	Fluoride	mg/L	SM4110B	0.59	0.314	0.417	0.244
General	Hardness as CaCO3	mg/L	SM2340C	260	265	280	20
General	Kjeldahl-N	mg/L	SM4500-NHorg C	1.64	1.36	1.94	0.58
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<0.4	<0.4	<1	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5
General	NH3-N	mg/L	SM4500-NH3 F	0.76	0.48	0.56	0.14
General	Nitrate (NO3)	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrate (NO3)	mg/L	SM4110B	24.3	22.1	27	6.17
General	Nitrate-N	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrate-N	mg/L	SM4110B	5.5	4.99	6.1	1.39
General	Nitrite (NO2)	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrite-N	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrite-N	mg/L	SM4110B	<0.03	0.13	0.177	<0.03
General	Phosphorus- Total (as P)	mg/L	SM4500-PE	0.18	0.1	0.19	0.08
General	Specific Conductance	umhos/cm	SM2510B	1027	1080	1010	1000
General	Sulfate	mg/L	EPA300.1	NS	NS	NS	NS
General	Sulfate	mg/L	SM4110B	443*	172	117	199
General	Total Dissolved Phosphate	mg/L	AM4500-PE	NS	NS	NS	NS
General	Total Dissolved Solids	mg/L	SM2540C	694	706	668	670
General	Total Organic Carbon	mg/L	SM5310B	6.2	NS	NS	NS
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	NS	7.79	6.64	17.9
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<0.4	<0.4	<1.5	<1.5
General	Total Phosphate	mg/L	SM4500-PE	NS	NS	NS	NS
General	Total Suspended Solids	mg/L	SM2540D	14	31	28	23
General	Turbidity	NTU	SM2130B	1.46	1.18	0.73	2.79
General	Volatile Suspended Solids	mg/L	SM2540E	3	15	4	8

**Appendix B.2. 2009-2010 Annual Report Mass Emission and Tributary Dry Weather Concentration**

Group	Parameter Code	Units	Analysis_Method	San Gabriel River @ SGR Parkway S14 2009-10Event02 07/14/2009	San Gabriel River @ SGR Parkway S14 2009-10Event12 09/15/2009	San Gabriel River @ SGR Parkway S14 2009-10Event14 12/01/2009	San Gabriel River @ SGR Parkway S14 2009-10Event28 03/23/2010
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.07	<0.067	<0.067	<0.067
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	<0.015	<0.015	<0.015
Herbicides	Glyphosate	ug/L	EPA547	<5	<5	<5	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	<50	<50	<50	<50
Metals	Dissolved Antimony	ug/L	EPA200.8	0.62	0.603	0.588	<0.2
Metals	Dissolved Arsenic	ug/L	EPA200.8	1.14	1	2.2	1.93
Metals	Dissolved Barium	ug/L	EPA200.8	44.9	50.6	52.6	73.6
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	0.95	0.808	1.74	1.19
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	<0.25	<0.25	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	3.15	3.08	4.61	2.85
Metals	Dissolved Iron	ug/L	EPA200.8	<50	<50	<50	<50
Metals	Dissolved Lead	ug/L	EPA200.8	>0.28<0.5	>0.28<0.5	<0.2	<0.2
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	4.61	3.19	3.47	4.39
Metals	Dissolved Selenium	ug/L	EPA200.8	1.53	1.35	5.27	1.2
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	42.2	43.7	56.6	22.1
Metals	Aluminum	ug/L	EPA200.8	106	116	<50	453
Metals	Antimony	ug/L	EPA200.8	0.63	0.632	0.712	0.793
Metals	Arsenic	ug/L	EPA200.8	1.21	1.09	2.34	2.31
Metals	Barium	ug/L	EPA200.8	48.1	57.3	62.2	97.1
Metals	Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	<0.1	<0.1	0.276	<0.1
Metals	Chromium	ug/L	EPA200.8	1.5	0.872	2.99	1.27
Metals	Chromium +6	ug/L	EPA218.6	<0.25	<0.25	<0.25	<0.25
Metals	Copper	ug/L	EPA200.8	8.39	10.1	9.94	9.82
Metals	Iron	ug/L	EPA200.8	200	256	229	667
Metals	Lead	ug/L	EPA200.8	0.98	1.32	0.893	2.14
Metals	Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	5.03	4.24	4.46	5.69
Metals	Selenium	ug/L	EPA200.8	1.8	1.61	5.54*	1.37
Metals	Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	61.2	103	80	45.6
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.7	<0.667	<0.667	<0.667
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	<0.02	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.7	<0.667	<0.667	<0.667
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	<0.003	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.4	<0.33	<0.67	<0.33
Organophosphate Pesticides	Malathion	ug/L	EPA625	NS	NS	NS	NS
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.7	<0.67	<0.67	<0.67
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.7	<0.67	<0.67	<0.67
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<0.4	<3.3	<3.3	<3.3
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1

**Appendix B.2. 2009-2010 Annual Report Mass Emission and Tributary Dry Weather Concentration**

Group	Parameter Code	Units	Analysis_Method	San Gabriel River @ SGR Parkway S14 2009-10Event02 07/14/2009	San Gabriel River @ SGR Parkway S14 2009-10Event12 09/15/2009	San Gabriel River @ SGR Parkway S14 2009-10Event14 12/01/2009	San Gabriel River @ SGR Parkway S14 2009-10Event28 03/23/2010
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<0.03	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.2	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.2	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.2	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA625	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.4	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<0.4	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<0.04	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benidine	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)fluoranthene	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(g-h-i)perylene	ug/L	EPA625	<0.2	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	>1.7&<5	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<0.1	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.04	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.7	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.02	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.04	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	<0.02	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.7	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.07	<0.067	<0.067	<0.067
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.4	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.02	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.02	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	<3.4	NS	NS	NS
Semivolatile Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	<3.4	NS	NS	NS

Values reported with a "<" are not detected (ND) at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected but not quantified (DNQ) between the method detection limit and reporting limit, they are

QNS = Quantity Not Sufficient

**Appendix B.1. 2009-2010 Annual Report Wet Weather Mass Emission and Tributary Stations Concentrations**

Group	Parameter Code	Units	Analysis Method	Coyote Creek @ Spring S13 2009-10Event13 10/13/2009	Coyote Creek @ Spring S13 2009-10Event15 12/07/2009	Coyote Creek @ Spring S13 2009-10Event16 12/11/2009	Coyote Creek @ Spring S13 2009-10Event19 01/17/2010
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	1,600,000**	3,000**	50,000**	90,000**
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	900,000	230	240,000	240,000
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	900,000	230	240,000	300,000
Bacteria	Total Coliform	MPN/100mL	SM9221B	5,000,000	9,000	240,000	160,000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.011	<0.011	<0.011	<0.011
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	<0.002	<0.002	<0.002
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	<0.05	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	<0.006	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Endrin ketone	ug/L	EPA625	NS	NS	NS	NS
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	<0.003	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	<0.24	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.033	<0.033	<0.033	<0.033
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.033	<0.033	<0.033	<0.033
Conventionals	Cyanide	mg/L	SM4500-CNE	0.03*	0.02	0.005	<0.005
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	6.41	7.92	11.1	10
Conventionals	Oil and Grease	mg/L	EPA1664A	<1.44	<1.44	>1.44&<5	>1.44&<5
Conventionals	pH	pH units	SM4500H B	7.52	7.33	6.96	7.35
General	Alkalinity as CaCO3	mg/L	SM2320B	55	55	55	41
General	Ammonia	mg/L	SM4500-NH3 F	0.835	0.719	0.318	0.378
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	30.3	17	9.62	5.38
General	Chemical Oxygen Demand	mg/L	SM5220D	64.1	60.7	286	28.9
General	Chloride	mg/L	SM4110B	22.5	10.2	15.4	10.1
General	Dissolved Phosphorus	mg/L	SM4500-PE	0.28	0.26	0.12	0.11
General	Fluoride	mg/L	SM4110B	0.179	0.251	0.184	0.237
General	Hardness as CaCO3	mg/L	SM2340C	110	60	70	40
General	Kjeldahl-N	mg/L	SM4500-NHorg C	4.24	2.1	1.28	2.12
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<1	<1	<1	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	0.63	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5
General	NH3-N	mg/L	SM4500-NH3 F	0.69	0.594	0.263	0.312
General	Nitrate (NO3)	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrate (NO3)	mg/L	SM4110B	3.72	4.17	3.8	2.95
General	Nitrate-N	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrate-N	mg/L	SM4110B	0.8	0.941	0.857	0.665
General	Nitrite (NO2)	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrite-N	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrite-N	mg/L	SM4110B	0.09	<0.01	<0.01	<0.01
General	Phosphorus- Total (as P)	mg/L	SM4500-PE	0.78	0.38	0.27	0.13
General	Specific Conductance	umhos/cm	SM2510B	264	138	208	105
General	Sulfate	mg/L	EPA300.1	NS	NS	NS	NS
General	Sulfate	mg/L	SM4110B	35.7	13.4	24	14
General	Total Dissolved Phosphate	mg/L	AM4500-PE	NS	NS	NS	NS
General	Total Dissolved Solids	mg/L	SM2540C	182	94	126	70
General	Total Organic Carbon	mg/L	SM5310B	NS	NS	NS	NS
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	18	15.5	8.75	7.17
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<1.5	<1.5	<1.5	<1.5
General	Total Phosphate	mg/L	SM4500-PE	NS	NS	NS	NS
General	Total Suspended Solids	mg/L	SM2540D	503	184	132	440
General	Turbidity	NTU	SM2130B	6.8	17.1	13.5	18.2
General	Volatile Suspended Solids	mg/L	SM2540E	112	49	35	138
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.067	<0.067	<0.067	<0.067
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	<0.015	<0.015	<0.015

Appendix B.1. 2009-2010 Annual Report Wet Weather Mass Emission and Tributary Stations Concentrations

Group	Parameter Code	Units	Analysis Method	Coyote Creek @ Spring S13 2009-10Event13 10/13/2009	Coyote Creek @ Spring S13 2009-10Event15 12/07/2009	Coyote Creek @ Spring S13 2009-10Event16 12/11/2009	Coyote Creek @ Spring S13 2009-10Event19 01/17/2010
Herbicides	Glyphosate	ug/L	EPA547	<5	<5	<5	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	<50	<50	<50	<50
Metals	Dissolved Antimony	ug/L	EPA200.8	2.08	1.16	1.73	0.798
Metals	Dissolved Arsenic	ug/L	EPA200.8	1.74	1.22	1.27	1.39
Metals	Dissolved Barium	ug/L	EPA200.8	27.8	17.5	20.2	17.6
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	0.879	0.964	0.791	0.807
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	<0.25	<0.25	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	10.8	9.09*	8.6	4.37
Metals	Dissolved Iron	ug/L	EPA200.8	166	<50	<50	<50
Metals	Dissolved Lead	ug/L	EPA200.8	0.951	1.29	0.623	0.86
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	6.8	4.02	3.03	1.61
Metals	Dissolved Selenium	ug/L	EPA200.8	1.14	<0.5	<0.5	1.69
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	61.8	65.1	50.1	32.9
Metals	Aluminum	ug/L	EPA200.8	236	2140	1820	4480
Metals	Antimony	ug/L	EPA200.8	2.13	3.27	3.07	2.56
Metals	Arsenic	ug/L	EPA200.8	1.81	2.8	2.13	2.97
Metals	Barium	ug/L	EPA200.8	31.9	78.7	59.5	105
Metals	Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	<0.1	0.553	0.316	0.863
Metals	Chromium	ug/L	EPA200.8	1.44	6.56	5.07	9.96
Metals	Chromium +6	ug/L	EPA218.6	<0.25	<0.25	<0.25	<0.25
Metals	Copper	ug/L	EPA200.8	21.6	49.6	35.7	38.2
Metals	Iron	ug/L	EPA200.8	240	3400	3640	6930
Metals	Lead	ug/L	EPA200.8	2.2	20.8	15.8	31.1
Metals	Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	7.59	9.63	8.86	10.6
Metals	Selenium	ug/L	EPA200.8	1.22	<0.5	<0.5	1.74
Metals	Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	62.6	257	175	258
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.667	<0.667	<0.667	<0.667
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	<0.02	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.667	<0.667	<0.667	<0.667
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	<0.003	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.67	<0.67	<0.33	<0.33
Organophosphate Pesticides	Malathion	ug/L	EPA625	NS	NS	NS	NS
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.67	<0.67	<0.67	<0.67
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.67	<0.67	<0.67	<0.67
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<3.3	<3.3	<3.3	<3.3
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33

**Appendix B.1. 2009-2010 Annual Report Wet Weather Mass Emission and Tributary Stations Concentrations**

Group	Parameter Code	Units	Analysis Method	Coyote Creek @ Spring S13 2009-10Event13 10/13/2009	Coyote Creek @ Spring S13 2009-10Event15 12/07/2009	Coyote Creek @ Spring S13 2009-10Event16 12/11/2009	Coyote Creek @ Spring S13 2009-10Event19 01/17/2010
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.33	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benidine	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)flouranthene	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(g-h-l)perylene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	<1.67	<1.67	<1.67	7.38
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<3.33	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.033	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.017	<0.017	<0.017	0.622
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.033	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	<0.017	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.067	<0.067	<0.067	<0.067
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.017	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.017	<0.017	<0.017	0.467

Values reported with a "<" are not detected (ND) at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected but not quantified (DNQ) between the method detection limit and reporting limit, they are re

QNS = Quantity Not Sufficient

\* Exceedance of Water Quality Objective

\*\* Not an exceedance due to the High Flow Suspension Basin Plan Amendment (LARQCB 2003).

**Appendix B.1. 2009-2010 Annual Report Wet Weather Mass Emission and Tributary Stations Concentrations**

Group	Parameter Code	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2009-10Event13 10/13/2009	San Gabriel River @ SGR Parkway S14 2009-10Event15 12/07/009	San Gabriel River @ SGR Parkway S14 2009-10Event16 12/11/2009	San Gabriel River @ SGR Parkway S14 2009-10Event19 01/17/2010
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	5,000,000**	300	90,000**	2,200**
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	1,600,000	500	160,000	130,000
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	1,600,000	500	160,000	240,000
Bacteria	Total Coliform	MPN/100mL	SM9221B	24,000,000	5,000	1,600,000	240,000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.011	<0.011	<0.011	<0.011
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	<0.002	<0.002	<0.002
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	<0.05	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	<0.006	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Endrin ketone	ug/L	EPA625	NS	NS	NS	NS
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	<0.003	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	<0.24	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.033	<0.033	<0.033	<0.033
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.033	<0.033	<0.033	<0.033
Conventionals	Cyanide	mg/L	SM4500-CNE	0.03*	<0.005	0.008	0.02
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	8.41	11.1	11.1	9.9
Conventionals	Oil and Grease	mg/L	EPA1664A	<1.44	<1.44	<1.44	<1.44
Conventionals	pH	pH units	SM4500H B	7.25	7.2	7.13	7.71
General	Alkalinity as CaCO3	mg/L	SM2320B	96	83	41	69
General	Ammonia	mg/L	SM4500-NH3 F	1.89	0.138	<0.1	0.807
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	32.9	15.6	7.52	12.8
General	Chemical Oxygen Demand	mg/L	SM5220D	72.1	64.8	196	36.4
General	Chloride	mg/L	SM4110B	53.4	46.7	22.8	47.7
General	Dissolved Phosphorus	mg/L	SM4500-PE	0.39	0.29	0.07	0.15
General	Fluoride	mg/L	SM4110B	0.274	0.347	0.129	0.243
General	Hardness as CaCO3	mg/L	SM2340C	160	140	80	30
General	Kjeldahl-N	mg/L	SM4500-NHorg C	5.3	0.96	0.718	1.76
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<1	<1	<1	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	0.58	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5
General	NH3-N	mg/L	SM4500-NH3 F	1.56	0.114	<0.1	0.667
General	Nitrate (NO3)	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrate (NO3)	mg/L	SM4110B	13.6	12.4	4.8	8.18
General	Nitrate-N	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrate-N	mg/L	SM4110B	3.1	2.79	1.08	1.85
General	Nitrite (NO2)	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrite-N	mg/L	EPA300.1	NS	NS	NS	NS
General	Nitrite-N	mg/L	SM4110B	0.09	<0.01	<0.01	<0.01
General	Phosphorus- Total (as P)	mg/L	SM4500-PE	0.86	0.31	0.2	0.22
General	Specific Conductance	umhos/cm	SM2510B	508	493	230	393
General	Sulfate	mg/L	EPA300.1	NS	NS	NS	NS
General	Sulfate	mg/L	SM4110B	67.1	62.3	32.7	59.4
General	Total Dissolved Phosphate	mg/L	AM4500-PE	NS	NS	NS	NS
General	Total Dissolved Solids	mg/L	SM2540C	350	314	154	266
General	Total Organic Carbon	mg/L	SM5310B	NS	NS	NS	NS
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	20.2	11.7	5.78	5.6
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<1.5	<1.5	<1.5	<1.5
General	Total Phosphate	mg/L	SM4500-PE	NS	NS	NS	NS
General	Total Suspended Solids	mg/L	SM2540D	252	57	117	400
General	Turbidity	NTU	SM2130B	6.66	11.6	16.7	197
General	Volatile Suspended Solids	mg/L	SM2540E	51	12	17	46
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.067	<0.067	<0.067	<0.067
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	<0.015	<0.015	<0.015

**Appendix B.1. 2009-2010 Annual Report Wet Weather Mass Emission and Tributary Stations Concentrations**

Group	Parameter Code	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2009-10Event13 10/13/2009	San Gabriel River @ SGR Parkway S14 2009-10Event15 12/07/09	San Gabriel River @ SGR Parkway S14 2009-10Event16 12/11/2009	San Gabriel River @ SGR Parkway S14 2009-10Event19 01/17/2010
Herbicides	Glyphosate	ug/L	EPA547	<5	<5	<5	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	<50	446	<50	<50
Metals	Dissolved Antimony	ug/L	EPA200.8	1.8	1.08	0.713	0.671
Metals	Dissolved Arsenic	ug/L	EPA200.8	1.78	1.51	<0.2	1.71
Metals	Dissolved Barium	ug/L	EPA200.8	31.5	48.5	20.5	30.5
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	1.74	2	0.673	0.995
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	<0.25	<0.25	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	7.91	11.6	4.53	3.89
Metals	Dissolved Iron	ug/L	EPA200.8	133	513	<50	114
Metals	Dissolved Lead	ug/L	EPA200.8	1.39	6.61	0.722	1.03
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	6.14	>0.5&<1	2.96	2.42
Metals	Dissolved Selenium	ug/L	EPA200.8	1.77	<0.5	<0.5	1.94
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	33.1	85.5	28.3	44.6*
Metals	Aluminum	ug/L	EPA200.8	107	1140	2490	5530
Metals	Antimony	ug/L	EPA200.8	1.86	1.52	1.24	1.37
Metals	Arsenic	ug/L	EPA200.8	1.84	1.97	1.78	3.19
Metals	Barium	ug/L	EPA200.8	35.3	62.2	57.4	116
Metals	Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	<0.1	<0.1	<0.1	0.55
Metals	Chromium	ug/L	EPA200.8	2.23	3.19	5.45	12.4
Metals	Chromium +6	ug/L	EPA218.6	<0.25	<0.25	<0.25	<0.25
Metals	Copper	ug/L	EPA200.8	12.7	21.3	20.8	24.7
Metals	Iron	ug/L	EPA200.8	201	1270	4690	9530
Metals	Lead	ug/L	EPA200.8	1.77	8.58	9.05	17.3
Metals	Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	6.81	5.91	7.47	11.8
Metals	Selenium	ug/L	EPA200.8	2.02	1.29	<0.5	2.33
Metals	Silver	ug/L	EPA200.8	0.354	<0.1	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	41.9	89.9	81.9	103
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.667	<0.667	<0.667	<0.667
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	<0.02	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.667	<0.667	<0.667	<0.667
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	<0.003	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.67	<0.67	<0.33	<0.33
Organophosphate Pesticides	Malathion	ug/L	EPA625	NS	NS	NS	NS
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.67	<0.67	<0.67	<0.67
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.67	<0.67	<0.67	<0.67
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<3.3	<3.3	<3.3	<3.3
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33

**Appendix B.1. 2009-2010 Annual Report Wet Weather Mass Emission and Tributary Stations Concentrations**

Group	Parameter Code	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2009-10Event13 10/13/2009	San Gabriel River @ SGR Parkway S14 2009-10Event15 12/07/009	San Gabriel River @ SGR Parkway S14 2009-10Event16 12/11/2009	San Gabriel River @ SGR Parkway S14 2009-10Event19 01/17/2010
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.33	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benidine	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)flouranthene	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(g-h-ij)perylene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<3.33	<3.33	>3.33&<10	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.033	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.67	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.017	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.033	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	<0.017	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.067	<0.067	<0.067	<0.067
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.33	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.017	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.017	<0.017	<0.017	<0.017

Values reported with a "<" are not detected (ND) at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected but not quantified (DNQ) between the method detection limit and reporting limit, they are re

QNS = Quantity Not Sufficient

\* Exceedance of Water Quality Objective

\*\* Not an exceedance due to the High Flow Suspension Basin Plan Amendment (LARQCB 2003).

## Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	Coyote Creek @ Spring St. S13 2010-11Event2 9/21/2010	Coyote Creek @ Spring St. S13 2010-11Event13 1/24/2011
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	16000*	230
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	24000	230
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	24000	230
Bacteria	Total Coliform	MPN/100mL	SM9221B	240000	240000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.011	<0.011
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	<0.002
Chlorinated Pesticides	Endosulfan I (alpha)	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Endosulfan II (beta)	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Methoxychlor	ug/L	EPA608	<0.5	<0.5
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.033	<0.033
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.033	<0.033
Conventionals	Cyanide	mg/L	SM4500-CNE	0.014	0.014
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	10	16.1
Conventionals	Oil and Grease	mg/L	EPA1664A	<1.44	<1.44
Conventionals	pH	pH units	SM4500H B	8.33	8.27
General	Alkalinity as CaCO3	mg/L	SM2320B	289	347
General	Ammonia	mg/L	SM4500-NH3 F	0.278	0.23
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	15	23.7
General	Chemical Oxygen Demand	mg/L	SM5220D	53.3	47.4
General	Chloride	mg/L	SM4110B	213	263
General	Dissolved Phosphorus	mg/L	SM4500-PE	<0.05	<0.05

## Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	Coyote Creek @ Spring St. S13 2010-11Event2 9/21/2010	Coyote Creek @ Spring St. S13 2010-11Event13 1/24/2011
General	Fluoride	mg/L	SM4110B	1.05	1.32
General	Hardness as CaCO <sub>3</sub>	mg/L	SM2340C	395	510
General	Kjeldahl-N	mg/L	SM4500-NHorg C	0.92	0.88
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<0.4	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	>0.01&<0.5	>0.01&<0.5
General	NH <sub>3</sub> -N	mg/L	SM4500-NH3	0.23	0.19
General	Nitrate (NO <sub>3</sub> )	mg/L	SM4110B	10.5	21.2
General	Nitrate-N	mg/L	SM4110B	2.38	4.78
General	Nitrite-N	mg/L	SM4110B	0.0392	0.0362
General	Phosphorus- Total (as P)	mg/L	SM4500-PE	<0.05	<0.05
General	Specific Conductance	umhos/cm	SM2510B	1810	2250
General	Sulfate	mg/L	SM4110B	376	519
General	Total Dissolved Solids	mg/L	SM2540C	1260	1490
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	6.47	15.4
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<1.5	<1.5
General	Total Suspended Solids	mg/L	SM2540D	46	12
General	Turbidity	NTU	SM2130B	2.4	1.22
General	Volatile Suspended Solids	mg/L	SM2540E	28	8
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.067	<0.067
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	<0.015
Herbicides	Glyphosate	ug/L	EPA547	7.2	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	<50	<50
Metals	Dissolved Antimony	ug/L	EPA200.8	0.792	<0.2
Metals	Dissolved Arsenic	ug/L	EPA200.8	3.06	3.04
Metals	Dissolved Barium	ug/L	EPA200.8	62.5	<1
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	1.1	<0.5
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	12.7	<0.5
Metals	Dissolved Iron	ug/L	EPA200.8	125	<50
Metals	Dissolved Lead	ug/L	EPA200.8	1.3	<0.2
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	4.06	<0.5

## Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	Coyote Creek @ Spring St. S13 2010-11Event2 9/21/2010	Coyote Creek @ Spring St. S13 2010-11Event13 1/24/2011
Metals	Dissolved Selenium	ug/L	EPA200.8	5.3	5.31
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	39.8	<1
Metals	Aluminum	ug/L	EPA200.8	285	105
Metals	Antimony	ug/L	EPA200.8	1.02	<0.2
Metals	Arsenic	ug/L	EPA200.8	4.33	3.08
Metals	Barium	ug/L	EPA200.8	77.2	<1
Metals	Beryllium	ug/L	EPA200.8	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	<0.1	<0.1
Metals	Chromium	ug/L	EPA200.8	5.75	<0.5
Metals	Chromium +6	ug/L	EPA218.6	<0.25	<0.25
Metals	Copper	ug/L	EPA200.8	13.2	<0.5
Metals	Iron	ug/L	EPA200.8	453	<50
Metals	Lead	ug/L	EPA200.8	1.57	<0.2
Metals	Mercury	ug/L	EPA245.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	5.75	<0.5
Metals	Selenium	ug/L	EPA200.8	6.17	7.06
Metals	Silver	ug/L	EPA200.8	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	66.3	<1
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.667	<0.667
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.667	<0.667
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.33	<0.33
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.67	<0.67
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.67	<0.67
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	<0.065

## Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	Coyote Creek @ Spring St. S13 2010-11Event2 9/21/2010	Coyote Creek @ Spring St. S13 2010-11Event13 1/24/2011
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<3.33	<3.33
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	Phenolics-Total Recoverable	mg/L	EPA625	<0.03	<0.03
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA625	<2.5	<2.5
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzidine	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(b)flouranthene	ug/L	EPA625	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)flouranthene	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo[g-h-i]perylene	ug/L	EPA625	<1.67	<1.67

Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	Coyote Creek @ Spring St. S13 2010-11Event2 9/21/2010	Coyote Creek @ Spring St. S13 2010-11Event13 1/24/2011
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.067	<0.067
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	<3.33	<3.33

Values reported with a "<" are not detected at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected between the method detection limit and reporting limit, they are reported as >MDL& <RL

NS = Not Sampled

Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	San Gabriel River @ SGR Parkway S14 2010-11Event2 9/21/2010	San Gabriel River @ SGR Parkway S14 2010-11Event13 1/24/2011
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	NS	20
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	NS	20
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	NS	20
Bacteria	Total Coliform	MPN/100mL	SM9221B	NS	800
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	NS	<0.011
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	NS	<0.004
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	NS	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	NS	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	NS	<0.002
Chlorinated Pesticides	Endosulfan I (alpha)	ug/L	EPA608	NS	<0.01
Chlorinated Pesticides	Endosulfan II (beta)	ug/L	EPA608	NS	<0.004
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	NS	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	NS	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	NS	<0.01
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	NS	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	NS	<0.01
Chlorinated Pesticides	Methoxychlor	ug/L	EPA608	NS	<0.5
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	NS	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	NS	<0.01
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	NS	<0.033
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	NS	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	NS	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	NS	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	NS	<0.033
Conventionals	Cyanide	mg/L	SM4500-CNE	NS	0.017
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	NS	10.2
Conventionals	Oil and Grease	mg/L	EPA1664A	NS	<1.44
Conventionals	pH	pH units	SM4500H B	NS	8.36
General	Alkalinity as CaCO3	mg/L	SM2320B	NS	173
General	Ammonia	mg/L	SM4500-NH3 F	NS	0.411
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	NS	19.9
General	Chemical Oxygen Demand	mg/L	SM5220D	NS	37.5
General	Chloride	mg/L	SM4110B	NS	130
General	Dissolved Phosphorus	mg/L	SM4500-PE	NS	0.11

Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	San Gabriel River @ SGR Parkway S14 2010-11Event2 9/21/2010	San Gabriel River @ SGR Parkway S14 2010-11Event13 1/24/2011
General	Fluoride	mg/L	SM4110B	NS	0.396
General	Hardness as CaCO3	mg/L	SM2340C	NS	330
General	Kjeldahl-N	mg/L	SM4500-NHorg C	NS	10.6
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	NS	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	NS	>0.01&<0.5
General	NH3-N	mg/L	SM4500-NH3	NS	0.34
General	Nitrate (NO3)	mg/L	SM4110B	NS	19.4
General	Nitrate-N	mg/L	SM4110B	NS	4.38
General	Nitrite-N	mg/L	SM4110B	NS	<0.01
General	Phosphorus- Total (as P)	mg/L	SM4500-PE	NS	0.13
General	Specific Conductance	umhos/cm	SM2510B	NS	1070
General	Sulfate	mg/L	SM4110B	NS	164
General	Total Dissolved Solids	mg/L	SM2540C	NS	736
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	NS	20
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	NS	<1.5
General	Total Suspended Solids	mg/L	SM2540D	NS	15
General	Turbidity	NTU	SM2130B	NS	2.42
General	Volatile Suspended Solids	mg/L	SM2540E	NS	7
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	NS	<0.067
Herbicides	2-4-D	ug/L	EPA515.3	NS	<0.015
Herbicides	Glyphosate	ug/L	EPA547	NS	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	NS	62.2
Metals	Dissolved Antimony	ug/L	EPA200.8	NS	<0.2
Metals	Dissolved Arsenic	ug/L	EPA200.8	NS	<0.2
Metals	Dissolved Barium	ug/L	EPA200.8	NS	<1
Metals	Dissolved Beryllium	ug/L	EPA200.8	NS	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	NS	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	NS	<0.5
Metals	Dissolved Chromium +6	ug/L	EPA218.6	NS	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	NS	<0.5
Metals	Dissolved Iron	ug/L	EPA200.8	NS	138
Metals	Dissolved Lead	ug/L	EPA200.8	NS	<0.2
Metals	Dissolved Mercury	ug/L	EPA245.1	NS	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	NS	<0.5

## Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	San Gabriel River @ SGR Parkway S14 2010-11Event2 9/21/2010	San Gabriel River @ SGR Parkway S14 2010-11Event13 1/24/2011
Metals	Dissolved Selenium	ug/L	EPA200.8	NS	<0.5
Metals	Dissolved Silver	ug/L	EPA200.8	NS	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	NS	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	NS	61.8
Metals	Aluminum	ug/L	EPA200.8	NS	255
Metals	Antimony	ug/L	EPA200.8	NS	<0.2
Metals	Arsenic	ug/L	EPA200.8	NS	<0.2
Metals	Barium	ug/L	EPA200.8	NS	<1
Metals	Beryllium	ug/L	EPA200.8	NS	<0.1
Metals	Cadmium	ug/L	EPA200.8	NS	<0.1
Metals	Chromium	ug/L	EPA200.8	NS	<0.5
Metals	Chromium +6	ug/L	EPA218.6	NS	<0.25
Metals	Copper	ug/L	EPA200.8	NS	<0.5
Metals	Iron	ug/L	EPA200.8	NS	440
Metals	Lead	ug/L	EPA200.8	NS	<0.2
Metals	Mercury	ug/L	EPA245.1	NS	<0.1
Metals	Nickel	ug/L	EPA200.8	NS	<0.5
Metals	Selenium	ug/L	EPA200.8	NS	<0.5
Metals	Silver	ug/L	EPA200.8	NS	<0.1
Metals	Thallium	ug/L	EPA200.8	NS	<0.1
Metals	Zinc	ug/L	EPA200.8	NS	65.6
Organophosphate Pesticides	Atrazine	ug/L	EPA507	NS	<0.667
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	NS	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	NS	<0.667
Organophosphate Pesticides	Diazinon	ug/L	EPA507	NS	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	NS	<0.33
Organophosphate Pesticides	Prometryn	ug/L	EPA507	NS	<0.67
Organophosphate Pesticides	Simazine	ug/L	EPA507	NS	<0.67
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	NS	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	NS	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	NS	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	NS	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	NS	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	NS	<0.065

## Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	San Gabriel River @ SGR Parkway S14 2010-11Event2 9/21/2010	San Gabriel River @ SGR Parkway S14 2010-11Event13 1/24/2011
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	NS	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	NS	<3.33
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	NS	<0.33
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	NS	<0.67
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	NS	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	NS	<0.67
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	NS	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	NS	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	NS	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	NS	<0.67
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	NS	<0.33
Semivolatile Organic Compounds (Acids)	Phenolics-Total Recoverable	mg/L	EPA625	NS	<0.03
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	NS	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	NS	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	NS	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	NS	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	NS	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	NS	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	NS	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	NS	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA625	NS	<2.5
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	NS	<3.33
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	NS	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	NS	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	NS	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	NS	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	NS	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	NS	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	NS	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzidine	ug/L	EPA625	NS	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	NS	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(b)flouranthene	ug/L	EPA625	NS	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)flouranthene	ug/L	EPA625	NS	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo[g-h-i]perylene	ug/L	EPA625	NS	<1.67

Appendix B.2. 2010-2011 Dry Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	San Gabriel River @ SGR Parkway S14 2010-11Event2 9/21/2010	San Gabriel River @ SGR Parkway S14 2010-11Event13 1/24/2011
Semivolatiles Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	NS	<1.67
Semivolatiles Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	NS	<0.33
Semivolatiles Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	NS	<0.67
Semivolatiles Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	NS	<1.67
Semivolatiles Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	NS	<3.33
Semivolatiles Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	NS	<1.67
Semivolatiles Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	NS	<0.033
Semivolatiles Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	NS	<0.67
Semivolatiles Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	NS	<0.67
Semivolatiles Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	NS	<0.017
Semivolatiles Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	NS	<0.033
Semivolatiles Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	NS	<1.67
Semivolatiles Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	NS	<0.33
Semivolatiles Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	NS	<0.33
Semivolatiles Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	NS	<0.33
Semivolatiles Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	NS	<0.017
Semivolatiles Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	NS	<0.33
Semivolatiles Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	NS	<1.67
Semivolatiles Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	NS	<1.67
Semivolatiles Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	NS	<0.33
Semivolatiles Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	NS	<0.067
Semivolatiles Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	NS	<0.33
Semivolatiles Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	NS	<0.017
Semivolatiles Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	NS	<0.017
Semivolatiles Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	NS	<3.33
Semivolatiles Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	NS	<3.33

Values reported with a "<" are not detected at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected between the method detection limit and reporting limit, they are reported as >MDL & <RL

NS = Not Sampled

Appendix B.1. 2010-2011 Wet Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	Coyote Creek @ Spring St. S13 2010-11Event3 10/5/2010	Coyote Creek @ Spring St. S13 2010-11Event4 10/30/2010	Coyote Creek @ Spring St. S13 2010-11Event6 11/19/2010	Coyote Creek @ Spring St. S13 2010-11Event8 12/17/2010	Coyote Creek @ Spring St. S13 2010-11Event14 2/16/2011
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	500000*	240000*	240000*	90000**	5000*
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	1600000	240000	28000	240000	3500
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	1600000	300000	160000	240000	3500
Bacteria	Total Coliform	MPN/100mL	SM9221B	9000000	300000	240000	1600000	50000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.011	NS	<0.011	<0.011	<0.011
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.004	NS	<0.004	<0.004	<0.004
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	NS	<0.004	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	NS	<0.002	<0.002	<0.002
Chlorinated Pesticides	Endosulfan I (alpha)	ug/L	EPA608	<0.01	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	Endosulfan II (beta)	ug/L	EPA608	<0.004	NS	<0.004	<0.004	<0.004
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	NS	<0.05	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	NS	<0.006	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	NS	<0.003	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	Methoxychlor	ug/L	EPA608	<0.5	NS	<0.5	<0.5	<0.5
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	NS	<0.24	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.01	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.033	NS	<0.033	<0.033	<0.033
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	NS	<0.005	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	NS	<0.005	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	NS	<0.004	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.033	NS	<0.033	<0.033	<0.033
Conventionals	Cyanide	mg/L	SM4500-CNE	0.012	<0.005	0.007	<0.005	<0.005
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	7.74	7.19	10	10.1	10.1
Conventionals	Oil and Grease	mg/L	EPA1664A	>1.44&<5	>1.44&<5	<1.44	>1.44&<5	>1.44&<5
Conventionals	pH	pH units	SM4500H B	7.07	NS	7.14	6.34*	6.41*
General	Alkalinity as CaCO3	mg/L	SM2320B	110	NS	60.5	38.5	132
General	Ammonia	mg/L	SM4500-NH3 F	0.617	NS	0.898	0.303	0.944
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	146	NS	11.5	7.03	27.9
General	Chemical Oxygen Demand	mg/L	SM5220D	98.8	NS	21.6	20.8	61
General	Chloride	mg/L	SM4110B	33.5	NS	28.9	10.8	65
General	Dissolved Phosphorus	mg/L	SM4500-PE	0.15	NS	0.13	0.15	0.063
General	Fluoride	mg/L	SM4110B	0.206	NS	0.327	0.246	0.434
General	Hardness as CaCO3	mg/L	SM2340C	130	NS	110	50	170
General	Kjeldahl-N	mg/L	SM4500-NHorg C	2.18	NS	3.78	0.76	5.62
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<0.4	<0.4	<0.4	<0.4	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	0.81	NS	>0.01&<0.5	>0.01&<0.5	0.73
General	NH3-N	mg/L	SM4500-NH3	0.51	NS	0.742	0.25	0.78
General	Nitrate (NO3)	mg/L	SM4110B	5.21	NS	4.35	2.63	5.35
General	Nitrate-N	mg/L	SM4110B	1.18	NS	0.982	0.594	1.21
General	Nitrite-N	mg/L	SM4110B	0.0705	NS	<0.03	<0.03	0.0395
General	Phosphorus- Total (as P)	mg/L	SM4500-PE	0.21	NS	0.18	0.17	0.076
General	Specific Conductance	umhos/cm	SM2510B	389	NS	359	152	562
General	Sulfate	mg/L	SM4110B	47.1	NS	49.6	17	110
General	Total Dissolved Solids	mg/L	SM2540C	270	NS	224	94	380
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	31.6	NS	39.5	21.6	42.2
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<1.5	<1.5	<1.5	<1.5	<1.5
General	Total Suspended Solids	mg/L	SM2540D	716	417	240	85	305

Appendix B.1. 2010-2011 Wet Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	Coyote Creek @ Spring St. S13 2010-11Event3 10/5/2010	Coyote Creek @ Spring St. S13 2010-11Event4 10/30/2010	Coyote Creek @ Spring St. S13 2010-11Event6 11/19/2010	Coyote Creek @ Spring St. S13 2010-11Event8 12/17/2010	Coyote Creek @ Spring St. S13 2010-11Event14 2/16/2011
General	Turbidity	NTU	SM2130B	25	NS	5.28	10.6	6.61
General	Volatile Suspended Solids	mg/L	SM2540E	171	NS	61	19	76
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.067	NS	<0.067	<0.067	<0.067
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	NS	<0.015	<0.015	<0.015
Herbicides	Glyphosate	ug/L	EPA547	12.3	NS	11	<5	18.1
Metals	Dissolved Aluminum	ug/L	EPA200.8	995	NS	482	380	421
Metals	Dissolved Antimony	ug/L	EPA200.8	<0.2	NS	<0.2	<0.2	<0.2
Metals	Dissolved Arsenic	ug/L	EPA200.8	2.51	NS	2.31	<0.2	2.32
Metals	Dissolved Barium	ug/L	EPA200.8	127	NS	<1	<1	<1
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	NS	<0.1	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	<0.1	NS	<0.1	<0.1	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	<0.5	NS	<0.5	<0.5	<0.5
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	NS	<0.25	<0.25	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	<0.5	NS	<0.5	<0.5	<0.5
Metals	Dissolved Iron	ug/L	EPA200.8	1760	NS	1100	592	785
Metals	Dissolved Lead	ug/L	EPA200.8	22.5	NS	10.3	7.33	11.1
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	NS	<0.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	12.8	NS	<0.5	<0.5	<0.5
Metals	Dissolved Selenium	ug/L	EPA200.8	<0.5	NS	<0.5	<0.5	<0.5
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	NS	<0.1	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	NS	<0.1	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	500*	NS	150*	115*	252*
Metals	Aluminum	ug/L	EPA200.8	4980	NS	2330	1470	1330
Metals	Antimony	ug/L	EPA200.8	6.82	NS	<0.2	<0.2	<0.2
Metals	Arsenic	ug/L	EPA200.8	2.7	NS	2.34	<0.2	2.92
Metals	Barium	ug/L	EPA200.8	218	NS	<1	<1	110
Metals	Beryllium	ug/L	EPA200.8	<0.1	NS	<0.1	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	1.41	NS	<0.1	<0.1	<0.1
Metals	Chromium	ug/L	EPA200.8	15.9	NS	10.5	<0.5	10.4
Metals	Chromium +6	ug/L	EPA218.6	<0.25	NS	<0.25	<0.25	<0.25
Metals	Copper	ug/L	EPA200.8	116	NS	<0.5	<0.5	<0.5
Metals	Iron	ug/L	EPA200.8	8030	NS	4780	2360	2490
Metals	Lead	ug/L	EPA200.8	32.9	NS	14	11.1	15.9
Metals	Mercury	ug/L	EPA245.1	<0.1	NS	<0.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	23.2	NS	<0.5	<0.5	12.1
Metals	Selenium	ug/L	EPA200.8	<0.5	NS	<0.5	<0.5	<0.5
Metals	Silver	ug/L	EPA200.8	<0.1	NS	<0.1	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	<0.1	NS	<0.1	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	640	NS	176	138	268
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.667	NS	<0.667	<0.667	<0.667
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	NS	<0.02	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.667	NS	<0.667	<0.667	<0.667
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	NS	<0.003	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.33	NS	<0.33	<0.33	<0.33
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.67	NS	<0.67	<0.67	<0.67
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.67	NS	<0.67	<0.67	<0.67
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	NS	<0.065	<0.065	<0.065

## Appendix B.1. 2010-2011 Wet Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	Coyote Creek @ Spring St. S13 2010-11Event3 10/5/2010	Coyote Creek @ Spring St. S13 2010-11Event4 10/30/2010	Coyote Creek @ Spring St. S13 2010-11Event6 11/19/2010	Coyote Creek @ Spring St. S13 2010-11Event8 12/17/2010	Coyote Creek @ Spring St. S13 2010-11Event14 2/16/2011
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	NS	<0.065	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<3.33	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	NS	<1	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	NS	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	NS	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	NS	<1	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	Phenolics-Total Recoverable	mg/L	EPA 420.1	<0.03	<0.03	>0.03&<0.1	<0.03	<0.03
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA625	<2.5	<2.5	<2.5	<2.5	<2.5
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.33	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	NS	<1	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzidine	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(b)flouranthene	ug/L	EPA625	<3.33	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)flouranthene	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo[g-h-i]perylene	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexl) phthalate	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<3.33	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.033	NS	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.67	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.017	NS	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.033	NS	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33

Appendix B.1. 2010-2011 Wet Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	Coyote Creek @ Spring St. S13 2010-11Event3 10/5/2010	Coyote Creek @ Spring St. S13 2010-11Event4 10/30/2010	Coyote Creek @ Spring St. S13 2010-11Event6 11/19/2010	Coyote Creek @ Spring St. S13 2010-11Event8 12/17/2010	Coyote Creek @ Spring St. S13 2010-11Event14 2/16/2011
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	<0.017	NS	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.67	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.067	NS	<0.067	<0.067	<0.067
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.33	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.017	NS	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.017	NS	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	<3.33	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	<3.33	NS	<3.33	<3.33	<3.33

Values reported with a "<" are not detected at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected between the method detection limit and reporting limit, they are reported as >MDL & <RL

NS = Not Sampled

\*Exceedance of Water Quality Objective

\*\*Not an exceedance due to the High Flow Suspension Basin Plan Amendment (LARQCB 2003).

Appendix B.1. 2010-2011 Wet Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	San Gabriel River @ SGR Parkway S14 2010-11Event3 10/5/2010	San Gabriel River @ SGR Parkway S14 2010-11Event4 10/30/2010	San Gabriel River @ SGR Parkway S14 2010-11Event6 11/19/2010	San Gabriel River @ SGR Parkway S14 2010-11Event8 12/17/2010	San Gabriel River @ SGR Parkway S14 2010-11Event14 2/16/2011
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	NS	30000*	3000**	170000**	800**
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	NS	160000	2400	300000	2400
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	NS	160000	2400	300000	2400
Bacteria	Total Coliform	MPN/100mL	SM9221B	NS	300000	240000	240000	90000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	NS	NS	<0.011	<0.011	<0.011
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	NS	NS	<0.004	<0.004	<0.004
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	NS	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	NS	NS	<0.004	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	NS	NS	<0.002	<0.002	<0.002
Chlorinated Pesticides	Endosulfan I (alpha)	ug/L	EPA608	NS	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	Endosulfan II (beta)	ug/L	EPA608	NS	NS	<0.004	<0.004	<0.004
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	NS	NS	<0.05	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	NS	NS	<0.006	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	NS	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	NS	NS	<0.003	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	NS	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	Methoxychlor	ug/L	EPA608	NS	NS	<0.5	<0.5	<0.5
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	NS	NS	<0.24	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	NS	NS	<0.01	<0.01	<0.01
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	NS	NS	<0.033	<0.033	<0.033
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	NS	NS	<0.005	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	NS	NS	<0.005	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	NS	NS	<0.004	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	NS	NS	<0.033	<0.033	<0.033
Conventionals	Cyanide	mg/L	SM4500-CNE	NS	<0.005	<0.005	<0.005	0.012
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	NS	8.51	9.84	10.6	11.1
Conventionals	Oil and Grease	mg/L	EPA1664A	NS	<1.44	<1.44	<1.44	<1.44
Conventionals	pH	pH units	SM4500H B	NS	NS	7.12	6.34*	6.48*
General	Alkalinity as CaCO3	mg/L	SM2320B	NS	NS	49.5	55	99
General	Ammonia	mg/L	SM4500-NH3 F	NS	NS	0.653	0.278	0.666
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	NS	NS	6.88	5.43	18.9
General	Chemical Oxygen Demand	mg/L	SM5220D	NS	NS	<10	30	33.1
General	Chloride	mg/L	SM4110B	NS	NS	31.5	35.9	71.3
General	Dissolved Phosphorus	mg/L	SM4500-PE	NS	NS	0.12	0.1	0.105
General	Fluoride	mg/L	SM4110B	NS	NS	0.17	0.203	0.345
General	Hardness as CaCO3	mg/L	SM2340C	NS	NS	100	115	175
General	Kjeldahl-N	mg/L	SM4500-NHorg C	NS	NS	2.24	0.72	1.22
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	NS	<0.4	<0.4	<0.4	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	NS	NS	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5
General	NH3-N	mg/L	SM4500-NH3	NS	NS	0.54	0.23	0.55
General	Nitrate (NO3)	mg/L	SM4110B	NS	NS	5.7	6.09	11.6
General	Nitrate-N	mg/L	SM4110B	NS	NS	1.29	1.37	2.62
General	Nitrite-N	mg/L	SM4110B	NS	NS	<0.03	<0.03	<0.01
General	Phosphorus- Total (as P)	mg/L	SM4500-PE	NS	NS	0.17	0.13	0.108
General	Specific Conductance	umhos/cm	SM2510B	NS	NS	321	345	577
General	Sulfate	mg/L	SM4110B	NS	NS	44	53.8	98
General	Total Dissolved Solids	mg/L	SM2540C	NS	NS	202	208	360
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	NS	NS	93.5	59.5	7.61
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	NS	<1.5	<1.5	<1.5	<1.5
General	Total Suspended Solids	mg/L	SM2540D	NS	122	43	61	24

Appendix B.1. 2010-2011 Wet Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	San Gabriel River @ SGR Parkway S14 2010-11Event3 10/5/2010	San Gabriel River @ SGR Parkway S14 2010-11Event4 10/30/2010	San Gabriel River @ SGR Parkway S14 2010-11Event6 11/19/2010	San Gabriel River @ SGR Parkway S14 2010-11Event8 12/17/2010	San Gabriel River @ SGR Parkway S14 2010-11Event14 2/16/2011
General	Turbidity	NTU	SM2130B	NS	NS	4.21	18.2	5.26
General	Volatile Suspended Solids	mg/L	SM2540E	NS	NS	10	8	21
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	NS	NS	<0.067	<0.067	<0.067
Herbicides	2-4-D	ug/L	EPA515.3	NS	NS	<0.015	<0.015	<0.015
Herbicides	Glyphosate	ug/L	EPA547	NS	NS	8.99	<5	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	NS	NS	183	635	125
Metals	Dissolved Antimony	ug/L	EPA200.8	NS	NS	<0.2	<0.2	<0.2
Metals	Dissolved Arsenic	ug/L	EPA200.8	NS	NS	<0.2	<0.2	<0.2
Metals	Dissolved Barium	ug/L	EPA200.8	NS	NS	<1	<1	<1
Metals	Dissolved Beryllium	ug/L	EPA200.8	NS	NS	<0.1	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	NS	NS	<0.1	<0.1	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	NS	NS	<0.5	<0.5	<0.5
Metals	Dissolved Chromium +6	ug/L	EPA218.6	NS	NS	<0.25	<0.25	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	NS	NS	<0.5	<0.5	<0.5
Metals	Dissolved Iron	ug/L	EPA200.8	NS	NS	348	875	267
Metals	Dissolved Lead	ug/L	EPA200.8	NS	NS	<0.2	<0.2	<0.2
Metals	Dissolved Mercury	ug/L	EPA245.1	NS	NS	<0.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	NS	NS	<0.5	<0.5	<0.5
Metals	Dissolved Selenium	ug/L	EPA200.8	NS	NS	<0.5	<0.5	<0.5
Metals	Dissolved Silver	ug/L	EPA200.8	NS	NS	<0.1	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	NS	NS	<0.1	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	NS	NS	71.1	69.1	<1
Metals	Aluminum	ug/L	EPA200.8	NS	NS	730	2950	483
Metals	Antimony	ug/L	EPA200.8	NS	NS	<0.2	<0.2	<0.2
Metals	Arsenic	ug/L	EPA200.8	NS	NS	<0.2	<0.2	<0.2
Metals	Barium	ug/L	EPA200.8	NS	NS	<1	<1	<1
Metals	Beryllium	ug/L	EPA200.8	NS	NS	<0.1	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	NS	NS	<0.1	<0.1	<0.1
Metals	Chromium	ug/L	EPA200.8	NS	NS	<0.5	<0.5	<0.5
Metals	Chromium +6	ug/L	EPA218.6	NS	NS	<0.25	<0.25	<0.25
Metals	Copper	ug/L	EPA200.8	NS	NS	<0.5	<0.5	<0.5
Metals	Iron	ug/L	EPA200.8	NS	NS	1510	4780	975
Metals	Lead	ug/L	EPA200.8	NS	NS	6.06	7.9	<0.2
Metals	Mercury	ug/L	EPA245.1	NS	NS	<0.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	NS	NS	<0.5	<0.5	<0.5
Metals	Selenium	ug/L	EPA200.8	NS	NS	<0.5	<0.5	<0.5
Metals	Silver	ug/L	EPA200.8	NS	NS	<0.1	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	NS	NS	<0.1	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	NS	NS	73.1	77.4	88.6
Organophosphate Pesticides	Atrazine	ug/L	EPA507	NS	NS	<0.667	<0.667	<0.667
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	NS	NS	<0.02	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	NS	NS	<0.667	<0.667	<0.667
Organophosphate Pesticides	Diazinon	ug/L	EPA507	NS	NS	<0.003	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	NS	NS	<0.33	<0.33	<0.33
Organophosphate Pesticides	Prometryn	ug/L	EPA507	NS	NS	<0.67	<0.67	<0.67
Organophosphate Pesticides	Simazine	ug/L	EPA507	NS	NS	<0.67	<0.67	<0.67
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	NS	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	NS	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	NS	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	NS	NS	<0.065	<0.065	<0.065

## Appendix B.1. 2010-2011 Wet Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	San Gabriel River @ SGR Parkway S14 2010-11Event3 10/5/2010	San Gabriel River @ SGR Parkway S14 2010-11Event4 10/30/2010	San Gabriel River @ SGR Parkway S14 2010-11Event6 11/19/2010	San Gabriel River @ SGR Parkway S14 2010-11Event8 12/17/2010	San Gabriel River @ SGR Parkway S14 2010-11Event14 2/16/2011
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	NS	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	NS	NS	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	NS	NS	<0.065	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	NS	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	NS	NS	<1	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	NS	NS	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	NS	NS	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	NS	NS	<1	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Acids)	Phenolics-Total Recoverable	mg/L	EPA 420.1	NS	<0.03	>0.03&<0.1	<0.03	<0.03
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA625	NS	<2.5	<2.5	<2.5	<2.5
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	NS	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	NS	NS	<1	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzidine	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo(b)flouranthene	ug/L	EPA625	NS	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)flouranthene	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Benzo[g-h-i]perylene	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexl) phthalate	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	NS	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	NS	NS	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	NS	NS	<0.67	<0.67	<0.67
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	NS	NS	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	NS	NS	<0.033	<0.033	<0.033
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33

Appendix B.1. 2010-2011 Wet Weather Concentrations.xls

Group	Parameter	Units	Analytical Method	San Gabriel River @ SGR Parkway S14 2010-11Event3 10/5/2010	San Gabriel River @ SGR Parkway S14 2010-11Event4 10/30/2010	San Gabriel River @ SGR Parkway S14 2010-11Event6 11/19/2010	San Gabriel River @ SGR Parkway S14 2010-11Event8 12/17/2010	San Gabriel River @ SGR Parkway S14 2010-11Event14 2/16/2011
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	NS	NS	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	NS	NS	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	NS	NS	<0.067	<0.067	<0.067
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	NS	NS	<0.33	<0.33	<0.33
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	NS	NS	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	NS	NS	<0.017	<0.017	<0.017
Semivolatile Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	NS	NS	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	NS	NS	<3.33	<3.33	<3.33

Values reported with a "<" are not detected at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected between the method detection limit and reporting limit, they are reported as >MDL & <RL

NS = Not Sampled

\*Exceedance of Water Quality Objective

\*\*Not an exceedance due to the High Flow Suspension Basin Plan Amendment (LARQCB 2003).

Appendix B.1. 2011-2012 Wet Weather Concentrations

Group	Parameter	Units	Analysis Method	Coyote Creek @ Spring Street S13 2011-12Event05 10/5/2011	Coyote Creek @ Spring Street S13 2011-12Event08 11/20/2011	Coyote Creek @ Spring Street S13 2011-12Event13 1/21/12	Coyote Creek @ Spring Street S13 2011-12Event18 3/16/2012
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	240000**	160000**	16000**	50000**
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	500000	240000	30000	240000
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	500000	240000	30000	240000
Bacteria	Total Coliform	MPN/100mL	SM9221B	300000	350000	300000	500000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.05	<0.05	<0.05	<0.05
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	<0.002	<0.002	<0.002
Chlorinated Pesticides	Endosulfan I (alpha)	ug/L	EPA608	<0.015	<0.015	<0.015	<0.015
Chlorinated Pesticides	Endosulfan II (beta)	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	<0.05	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	<0.006	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	<0.003	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Methoxychlor	ug/L	EPA608	<0.5	<0.5	<0.5	<0.5
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	<0.24	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.003	<0.003	<0.003	<0.003
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.04	<0.04	<0.04	<0.04
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.04	<0.04	<0.04	<0.04
Conventionals	Cyanide	mg/L	SM4500-CNE	0.01	0.014	0.008	<0.005
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	8.39	12.8	10.8	10.1
Conventionals	Oil and Grease	mg/L	EPA1664A	>1.44&<5	<1.44	>1.44&<5	>1.44&<5
Conventionals	pH	pH units	SM4500H B	7.51	7.99	7.24	7.68
General	Alkalinity as CaCO <sub>3</sub>	mg/L	SM2320B	52.8	62.7	49.5	66
General	Ammonia	mg/L	SM4500-NH3 D	1.17	0.339	1.25	0.23
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	27.6	24.6	8.7	16.4
General	Chemical Oxygen Demand	mg/L	SM5220D	47.1	27	22	29
General	Chloride	mg/L	EPA300.0	20.9	35.5	13.7	19.7
General	Dissolved Phosphorus	mg/L	SM4500-PE	0.263	0.13	0.0579	0.08
General	Fluoride	mg/L	EPA300.0	0.279	0.179	0.193	0.17
General	Hardness as CaCO <sub>3</sub>	mg/L	SM2340C	100	120	70	90
General	Kjeldahl-N	mg/L	SM4500-NHorg C	2.34	0.88	7.62	1.18
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<0.4	<0.4	<0.4	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	0.55	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5
General	NH <sub>3</sub> -N	mg/L	SM4500-NH3	0.97	0.28	1.03	0.19
General	Nitrate (NO <sub>3</sub> )	mg/L	EPA300.0	7.99	4.48	3.5	3.44
General	Nitrate-N	mg/L	EPA300.0	1.8	1.01	0.79	0.776
General	Nitrite-N	mg/L	EPA300.0	0.0343	<0.01	>0.01&<0.03	<0.01
General	Phosphorus - Total (as P)	mg/L	SM4500-PE	0.272	0.14	0.06	0.09
General	Specific Conductance	umhos/cm	SM2510 B	258	369	173	243
General	Sulfate	mg/L	EPA300.0	30.3	59.4	17.8	30.4
General	Total Dissolved Solids	mg/L	SM2540C	208	218	110	134
General	Total Organic Carbon	mg/L	SMS310B/EPA415.1	22.9	13.5	8.23	5.24
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<1.5	<1.5	<1.5	<1.5

Appendix B.1. 2011-2012 Wet Weather Concentrations

Group	Parameter	Units	Analysis Method	Coyote Creek @ Spring Street S13 2011-12Event05 10/5/2011	Coyote Creek @ Spring Street S13 2011-12Event08 11/20/2011	Coyote Creek @ Spring Street S13 2011-12Event13 1/21/12	Coyote Creek @ Spring Street S13 2011-12Event18 3/16/2012
General	Total Suspended Solids	mg/L	SM2540D	402	379	253	420
General	Turbidity	NTU	SM2130B	29.3	19.5	5.75	9.5
General	Volatile Suspended Solids	mg/L	SM2540E	96	109	81	126
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.07	<0.07	<0.07	<0.07
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	<0.015	<0.015	<0.015
Herbicides	Glyphosate	ug/L	EPA547	11	<5	7.83	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	910	498	348	880
Metals	Dissolved Antimony	ug/L	EPA200.8	2.09	1.41	1.01	1.38
Metals	Dissolved Arsenic	ug/L	EPA200.8	1.89	1.57	1.27	2.59
Metals	Dissolved Barium	ug/L	EPA200.8	95.6	50.2	40.1	79
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	0.619	>0.1&<0.25	>0.1&<0.25	0.542
Metals	Dissolved Chromium	ug/L	EPA200.8	3.82	2.2	1.34	2.65
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	>0.25&<5	<0.25	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	<b>39.1*</b>	<b>25.8*</b>	<b>19.5*</b>	<b>32.7*</b>
Metals	Dissolved Iron	ug/L	EPA200.8	1710	830	590	1610
Metals	Dissolved Lead	ug/L	EPA200.8	15.1	12.7	7.88	18.2
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	9.11	5.22	3.81	7.18
Metals	Dissolved Selenium	ug/L	EPA200.8	>0.5&<1	>0.5&<1	<0.5	>0.5&<1
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	<b>378*</b>	132	<b>126*</b>	<b>258*</b>
Metals	Aluminum	ug/L	EPA200.8	2010	1300	1310	2880
Metals	Antimony	ug/L	EPA200.8	3.78	2.48	2.14	3.3
Metals	Arsenic	ug/L	EPA200.8	2.13	1.96	1.36	3.41
Metals	Barium	ug/L	EPA200.8	112	66.7	56.6	107
Metals	Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	>0.1&<0.5
Metals	Cadmium	ug/L	EPA200.8	0.827	0.303	0.333	0.644
Metals	Chromium	ug/L	EPA200.8	8.98	5.19	4.85	8.03
Metals	Chromium +6	ug/L	EPA218.6	<0.25	>0.25&<5	<0.25	<0.25
Metals	Copper	ug/L	EPA200.8	50.6	36.5	29.2	49.1
Metals	Iron	ug/L	EPA200.8	3480	2650	2150	5100
Metals	Lead	ug/L	EPA200.8	20.5	16.9	10	25.5
Metals	Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	12.3	7.8	6.78	11
Metals	Selenium	ug/L	EPA200.8	1.2	>0.5&<1	>0.5&<1	1.05
Metals	Silver	ug/L	EPA200.8	0.321	>0.1&<0.25	>0.1&<0.25	>0.1&<0.25
Metals	Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	408	135	164	332
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.7	<0.7	<0.7	<0.7
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	<0.02	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.7	<0.7	<0.7	<0.7
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	<0.003	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.4	<0.4	<0.4	<0.4
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.7	<0.7	<0.7	<0.7
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.7	<0.7	<0.7	<0.7
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065

Appendix B.1. 2011-2012 Wet Weather Concentrations

Group	Parameter	Units	Analysis Method	Coyote Creek @ Spring Street S13 2011-12Event05 10/5/2011	Coyote Creek @ Spring Street S13 2011-12Event08 11/20/2011	Coyote Creek @ Spring Street S13 2011-12Event13 1/21/12	Coyote Creek @ Spring Street S13 2011-12Event18 3/16/2012
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	Phenolics - Total recoverable	mg/L	EPA420.1	0.15	0.12	<0.03	<0.03
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA624	<0.83	<0.83	<0.83	<0.83
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.4	<3.4	<3.4	<3.4
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzidine	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)fluoranthene	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(b)fluoranthene	ug/L	EPA625	<3.33	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Benzo(g-h-i)perylene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<3.33	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.04	<0.04	<0.04	<0.04
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.02	<0.02	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.04	<0.04	<0.04	<0.04

Appendix B.1. 2011-2012 Wet Weather Concentrations

Group	Parameter	Units	Analysis Method	Coyote Creek @ Spring Street S13 2011-12Event05 10/5/2011	Coyote Creek @ Spring Street S13 2011-12Event08 11/20/2011	Coyote Creek @ Spring Street S13 2011-12Event13 1/21/12	Coyote Creek @ Spring Street S13 2011-12Event18 3/16/2012
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Indeno[1-2-3-c-d]pyrene	ug/L	EPA625	<0.02	<0.02	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.07	<0.07	<0.07	<0.07
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.02	<0.02	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.02	<0.02	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	<3.4	<3.4	<3.4	<3.4
Semivolatile Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	<3.4	<3.4	<3.4	<3.4

Values reported with a "<" are not detected at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected between the method detection limit and reporting limit, they are reported as >MDL & <RL

NS = Not Sampled

\*Exceedance of Water Quality Objective

\*\*Not an exceedance due to the High Flow Suspension Basin Plan Amendment (LARQCB 2003).

^Method detection level exceeds the waer quality benchmark.

Appendix B.1. 2011-2012 Wet Weather Concentrations

Group	Parameter	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2011-12Event05 10/5/2011	San Gabriel River @ SGR Parkway S14 2011-12Event08 11/20/2011	San Gabriel River @ SGR Parkway S14 2011-12Event13 1/21/12	San Gabriel River @ SGR Parkway S14 2011-12Event18 3/16/2012
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	90000**	220000**	800**	170
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	240000	240000	800	1300
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	240000	240000	1300	1300
Bacteria	Total Coliform	MPN/100mL	SM9221B	2400000	1600000	24000	16000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.05	<0.05	<0.05	<0.05
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	<0.002	<0.002	<0.002
Chlorinated Pesticides	Endosulfan I (alpha)	ug/L	EPA608	<0.015	<0.015	<0.015	<0.015
Chlorinated Pesticides	Endosulfan II (beta)	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	<0.05	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	<0.006	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	<0.003	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	<0.01	<0.01	<0.01
Chlorinated Pesticides	Methoxychlor	ug/L	EPA608	<0.5	<0.5	<0.5	<0.5
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	<0.24	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.003	<0.003	<0.003	<0.003
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.04	<0.04	<0.04	<0.04
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	<0.005	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	<0.004	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.04	<0.04	<0.04	<0.04
Conventional	Cyanide	mg/L	SM4500-CNE	0.015	0.013	0.013	0.009
Conventional	Dissolved Oxygen	mg/L	SM4500 (OG)	6.61	9.68	10.5	10.3
Conventional	Oil and Grease	mg/L	EPA1664A	<1.44	<1.44	<1.44	<1.44
Conventional	pH	pH units	SM4500H B	7.77	7.82	7.64	7.69
General	Alkalinity as CaCO <sub>3</sub>	mg/L	SM2320B	73.7	123	97.9	105
General	Ammonia	mg/L	SM4500-NH3 D	0.532	<0.1	0.496	0.411
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	13	10.9	9.1	9.18
General	Chemical Oxygen Demand	mg/L	SM5220D	>10&<20	>10&<20	>10&<20	>10&<20
General	Chloride	mg/L	EPA300.0	47.3	93.9	79.9	83
General	Dissolved Phosphorus	mg/L	SM4500-PE	0.262	0.13	0.051	0.12
General	Fluoride	mg/L	EPA300.0	0.293	0.317	0.332	0.311
General	Hardness as CaCO <sub>3</sub>	mg/L	SM2340C	130	30	200	210
General	Kjeldahl-N	mg/L	SM4500-NHorg C	1.86	0.5	4.32	1.28
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<0.4	<0.4	<0.4	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5	>0.01&<0.5
General	NH <sub>3</sub> -N	mg/L	SM4500-NH3	0.44	<0.1	0.41	0.34
General	Nitrate (NO <sub>3</sub> )	mg/L	EPA300.0	11.6	15.3	13.5	12.8
General	Nitrate-N	mg/L	EPA300.0	2.62	3.46	3.04	2.89
General	Nitrite-N	mg/L	EPA300.0	<0.01	>0.01&<0.03	0.0498	<0.01
General	Phosphorus - Total (as P)	mg/L	SM4500-PE	0.28	0.16	0.06	0.14
General	Specific Conductance	umhos/cm	SM2510 B	454	798	636	712
General	Sulfate	mg/L	EPA300.0	57.7	119	87.7	102
General	Total Dissolved Solids	mg/L	SM2540C	298	472	408	402
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	11.9	7.11	8.03	5.06
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<1.5	<1.5	<1.5	<1.5

Appendix B.1. 2011-2012 Wet Weather Concentrations

Group	Parameter	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2011-12Event05 10/5/2011	San Gabriel River @ SGR Parkway S14 2011-12Event08 11/20/2011	San Gabriel River @ SGR Parkway S14 2011-12Event13 1/21/12	San Gabriel River @ SGR Parkway S14 2011-12Event18 3/16/2012
General	Total Suspended Solids	mg/L	SM2540D	129	100	118	42
General	Turbidity	NTU	SM2130B	21.3	12.9	5.65	6.06
General	Volatile Suspended Solids	mg/L	SM2540E	28	28	23	14
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.07	<0.07	<0.07	<0.07
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	<0.015	<0.015	<0.015
Herbicides	Glyphosate	ug/L	EPA547	6.8	<5	<5	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	660	565	337	165
Metals	Dissolved Antimony	ug/L	EPA200.8	1.14	0.842	0.597	0.899
Metals	Dissolved Arsenic	ug/L	EPA200.8	1.39	1.6	1.39	1.11
Metals	Dissolved Barium	ug/L	EPA200.8	63.9	68	55	51.8
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	>0.1&<0.25	>0.1&<0.25	>0.1&<0.25	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	2.57	2.81	1.8	1.14
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	>0.25&<5	>0.25&<5	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	15.6	13.5*	12.8	10.5
Metals	Dissolved Iron	ug/L	EPA200.8	1140	1030	622	294
Metals	Dissolved Lead	ug/L	EPA200.8	8.39	8.09	5.13	3.3
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	5.28	5.33	5.27	6.33
Metals	Dissolved Selenium	ug/L	EPA200.8	>0.5&<1	1.51	1.36	1.15
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	132	92.7*	70.2	69.3
Metals	Aluminum	ug/L	EPA200.8	1740	1340	1140	444
Metals	Antimony	ug/L	EPA200.8	1.77	1.37	1.13	1.23
Metals	Arsenic	ug/L	EPA200.8	1.91	1.83	1.43	1.41
Metals	Barium	ug/L	EPA200.8	78.4	88.9	73.3	62.7
Metals	Beryllium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	0.429	0.251	0.266	<0.1
Metals	Chromium	ug/L	EPA200.8	7.01	5.37	4.26	2.43
Metals	Chromium +6	ug/L	EPA218.6	<0.25	>0.25&<5	>0.25&<5	<0.25
Metals	Copper	ug/L	EPA200.8	19.2	23.9	18.1	12.9
Metals	Iron	ug/L	EPA200.8	3120	2910	1910	735
Metals	Lead	ug/L	EPA200.8	12.9	15.4	6.52	3.94
Metals	Mercury	ug/L	EPA245.1	<0.1	<0.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	7.07	37.1	7.68	7.74
Metals	Selenium	ug/L	EPA200.8	>0.5&<1	1.62	1.57	1.51
Metals	Silver	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	<0.1	<0.1	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	150	160	87.4	73.3
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.7	<0.7	<0.7	<0.7
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	<0.02	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.7	<0.7	<0.7	<0.7
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	<0.003	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.4	<0.4	<0.4	<0.4
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.7	<0.7	<0.7	<0.7
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.7	<0.7	<0.7	<0.7
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065

Appendix B.1. 2011-2012 Wet Weather Concentrations

Group	Parameter	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2011-12Event05 10/5/2011	San Gabriel River @ SGR Parkway S14 2011-12Event08 11/20/2011	San Gabriel River @ SGR Parkway S14 2011-12Event13 1/21/12	San Gabriel River @ SGR Parkway S14 2011-12Event18 3/16/2012
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	<0.065	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	Phenolics - Total recoverable	mg/L	EPA420.1	0.183	>0.03&<0.1	<0.03	<0.03
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA624	<0.83	<0.83	<0.83	<0.83
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.4	<3.4	<3.4	<3.4
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	<1	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzidine	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)fluoranthene	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(b)fluoranthene	ug/L	EPA625	<3.33	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Benzo(g-h-i)perylene	ug/L	EPA625	<1.67	<1.67	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<3.33	<3.33	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.04	<0.04	<0.04	<0.04
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.7	<0.7	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.02	<0.02	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.04	<0.04	<0.04	<0.04

Appendix B.1. 2011-2012 Wet Weather Concentrations

Group	Parameter	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2011-12Event05 10/5/2011	San Gabriel River @ SGR Parkway S14 2011-12Event08 11/20/2011	San Gabriel River @ SGR Parkway S14 2011-12Event13 1/21/12	San Gabriel River @ SGR Parkway S14 2011-12Event18 3/16/2012
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Indeno[1-2-3-c-d]pyrene	ug/L	EPA625	<0.02	<0.02	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.7	<1.7	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.07	<0.07	<0.07	<0.07
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.4	<0.4	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.02	<0.02	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.02	<0.02	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	<3.4	<3.4	<3.4	<3.4
Semivolatile Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	<3.4	<3.4	<3.4	<3.4

Values reported with a "<" are not detected at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected between the method detection limit and reporting limit, they are reported as >MDL & <RL

NS = Not Sampled

\*Exceedance of Water Quality Objective

\*\*Not an exceedance due to the High Flow Suspension Basin Plan Amendment (LARQCB 2003).

^Method detection level exceeds the waer quality benchmark.

Appendix B.2. 2011-2012 Dry Weather Concentrations

Group	Parameter	Units	Analysis Method	Coyote Creek @ Spring Street Rd. S13 2011-12Event04 9/20/2011	Coyote Creek @ Spring Street S13 2011-12Event12 1/9/2012
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	9000*	500
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	110	800
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	800	800
Bacteria	Total Coliform	MPN/100mL	SM9221B	90000	160000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.05	<0.05
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	<0.002
Chlorinated Pesticides	Endosulfan I (alpha)	ug/L	EPA608	<0.015	<0.015
Chlorinated Pesticides	Endosulfan II (beta)	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Methoxychlor	ug/L	EPA608	<0.5	<0.5
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.003	<0.003
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.04	<0.04
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.04	<0.04
Conventionals	Cyanide	mg/L	SM4500-CNE	0.009	0.019
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	16.2	14.1
Conventionals	Oil and Grease	mg/L	EPA1664A	<1.44	<1.44
Conventionals	pH	pH units	SM4500H B	8.51*	8.28
General	Alkalinity as CaCO <sub>3</sub>	mg/L	SM2320B	207	284
General	Ammonia	mg/L	SM4500-NH3 D	<0.1	<0.1
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	12.2	6.92
General	Chemical Oxygen Demand	mg/L	SM5220D	22	>10&<20
General	Chloride	mg/L	EPA300.0	159	229
General	Dissolved Phosphorus	mg/L	SM4500-PE	<0.05	<0.05
General	Fluoride	mg/L	EPA300.0	0.746	1.02
General	Hardness as CaCO <sub>3</sub>	mg/L	SM2340C	325	440
General	Kjeldahl-N	mg/L	SM4500-NHorg C	0.74	0.58
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<0.4	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	>0.01&<0.5	>0.01&<0.5
General	NH <sub>3</sub> -N	mg/L	SM4500-NH3	<0.1	<0.1
General	Nitrate (NO <sub>3</sub> )	mg/L	EPA300.0	6.55	16.6
General	Nitrate-N	mg/L	EPA300.0	1.48	3.75
General	Nitrite-N	mg/L	EPA300.0	>0.01&<0.03	0.112
General	Phosphorus - Total (as P)	mg/L	SM4500-PE	<0.05	<0.05
General	Specific Conductance	umhos/cm	SM2510 B	1400	1900
General	Sulfate	mg/L	EPA300.0	267	407
General	Total Dissolved Solids	mg/L	SM2540C	840	1270
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	5.42	5.45

Appendix B.2. 2011-2012 Dry Weather Concentrations

Group	Parameter	Units	Analysis Method	Coyote Creek @ Spring Street Rd. S13 2011-12Event04 9/20/2011	Coyote Creek @ Spring Street S13 2011-12Event12 1/9/2012
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<1.5	<1.5
General	Total Suspended Solids	mg/L	SM2540D	86	6
General	Turbidity	NTU	SM2130B	1.9	1.07
General	Volatile Suspended Solids	mg/L	SM2540E	31	5
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.07	<0.07
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	<0.015
Herbicides	Glyphosate	ug/L	EPA547	<5	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	>50&<100	<50
Metals	Dissolved Antimony	ug/L	EPA200.8	0.651	0.542
Metals	Dissolved Arsenic	ug/L	EPA200.8	3.14	3.13
Metals	Dissolved Barium	ug/L	EPA200.8	72.5	51.6
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Chromium	ug/L	EPA200.8	0.915	1.43
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	>0.25&<5
Metals	Dissolved Copper	ug/L	EPA200.8	9.45	11.7
Metals	Dissolved Iron	ug/L	EPA200.8	220	>50&<100
Metals	Dissolved Lead	ug/L	EPA200.8	3.97	1.12
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	3.89	3.73
Metals	Dissolved Selenium	ug/L	EPA200.8	3.45	5.98
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	108	51.9
Metals	Aluminum	ug/L	EPA200.8	265	>50&<100
Metals	Antimony	ug/L	EPA200.8	0.912	0.677
Metals	Arsenic	ug/L	EPA200.8	3.65	3.37
Metals	Barium	ug/L	EPA200.8	86.3	56.9
Metals	Beryllium	ug/L	EPA200.8	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	<0.1	<0.1
Metals	Chromium	ug/L	EPA200.8	5.01	1.54
Metals	Chromium +6	ug/L	EPA218.6	<0.25	>0.25&<5
Metals	Copper	ug/L	EPA200.8	13.5	14.4
Metals	Iron	ug/L	EPA200.8	458	148
Metals	Lead	ug/L	EPA200.8	4.7	1.55
Metals	Mercury	ug/L	EPA245.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	5.51	5.2
Metals	Selenium	ug/L	EPA200.8	4.88	7.13
Metals	Silver	ug/L	EPA200.8	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	120	63
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.7	<0.7
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.7	<0.7
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.4	<0.4
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.7	<0.7
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.7	<0.7
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	<0.065

Appendix B.2. 2011-2012 Dry Weather Concentrations

Group	Parameter	Units	Analysis Method	Coyote Creek @ Spring Street Rd. S13 2011-12Event04 9/20/2011	Coyote Creek @ Spring Street S13 2011-12Event12 1/9/2012
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	Phenolics - Total recoverable	mg/L	EPA420.1	<0.03	<0.03
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA624	<0.83	<0.83
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.4	<3.4
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzidine	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)fluoranthene	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo[b]fluoranthene	ug/L	EPA625	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Benzo[g,h-i]perylene	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.04	<0.04
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.02	<0.02

Appendix B.2. 2011-2012 Dry Weather Concentrations

Group	Parameter	Units	Analysis Method	Coyote Creek @ Spring Street Rd. S13 2011-12Event04 9/20/2011	Coyote Creek @ Spring Street S13 2011-12Event12 1/9/2012
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.04	<0.04
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.07	<0.07
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	<3.4	<3.4
Semivolatile Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	<3.4	<3.4

Values reported with a "<" are not detected at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected between the method detection limit and reporting limit, they are reported as >MDL & <RL

NS = Not Sampled

\*Exceedance of Water Quality Objective

Appendix B.2. 2011-2012 Dry Weather Concentrations

Group	Parameter	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2011-12Event04 9/20/2011	San Gabriel River @ SGR Parkway S14 2011-12Event12 1/9/2012
Bacteria	Fecal Coliform	MPN/100mL	SM9221E	20	500*
Bacteria	Fecal Enterococcus	MPN/100mL	SM9230B	20	130
Bacteria	Fecal Streptococcus	MPN/100mL	SM9230B	20	230
Bacteria	Total Coliform	MPN/100mL	SM9221B	2200	24000
Chlorinated Pesticides	4-4'-DDD	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	4-4'-DDE	ug/L	EPA608	<0.05	<0.05
Chlorinated Pesticides	4-4'-DDT	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Aldrin	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	Dieldrin	ug/L	EPA608	<0.002	<0.002
Chlorinated Pesticides	Endosulfan I (alpha)	ug/L	EPA608	<0.015	<0.015
Chlorinated Pesticides	Endosulfan II (beta)	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	Endosulfan sulfate	ug/L	EPA608	<0.05	<0.05
Chlorinated Pesticides	Endrin	ug/L	EPA608	<0.006	<0.006
Chlorinated Pesticides	Endrin aldehyde	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Heptachlor	ug/L	EPA608	<0.003	<0.003
Chlorinated Pesticides	Heptachlor Epoxide	ug/L	EPA608	<0.01	<0.01
Chlorinated Pesticides	Methoxychlor	ug/L	EPA608	<0.5	<0.5
Chlorinated Pesticides	Toxaphene	ug/L	EPA608	<0.24	<0.24
Chlorinated Pesticides	alpha-BHC	ug/L	EPA608	<0.003	<0.003
Chlorinated Pesticides	alpha-chlordane	ug/L	EPA608	<0.04	<0.04
Chlorinated Pesticides	beta-BHC	ug/L	EPA608	<0.005	<0.005
Chlorinated Pesticides	delta-BHC	ug/L	EPA608	<0.005	<0.005
Chlorinated Pesticides	gamma-BHC (lindane)	ug/L	EPA608	<0.004	<0.004
Chlorinated Pesticides	gamma-chlordane	ug/L	EPA608	<0.04	<0.04
Conventionals	Cyanide	mg/L	SM4500-CNE	<0.005	<0.005
Conventionals	Dissolved Oxygen	mg/L	SM4500 (OG)	8.96	5.8
Conventionals	Oil and Grease	mg/L	EPA1664A	<1.44	<1.44
Conventionals	pH	pH units	SM4500H B	8.2	7.85
General	Alkalinity as CaCO <sub>3</sub>	mg/L	SM2320B	189	198
General	Ammonia	mg/L	SM4500-NH3 D	<0.1	0.109
General	BioChemical Oxygen Demand- Five-Day	mg/L	SM5210B	6.06	4.23
General	Chemical Oxygen Demand	mg/L	SM5220D	>10&<20	<10
General	Chloride	mg/L	EPA300.0	107	108
General	Dissolved Phosphorus	mg/L	SM4500-PE	0.097	0.13
General	Fluoride	mg/L	EPA300.0	0.379	0.395
General	Hardness as CaCO <sub>3</sub>	mg/L	SM2340C	305	340
General	Kjeldahl-N	mg/L	SM4500-NHorg C	0.38	0.38
General	Methyl Tertiary Butyl Ether (MTBE)	ug/L	EPA624	<0.4	<0.4
General	Methylene Blue Active Substances (MBAS)	mg/L	SM5540-C	>0.01&<0.5	>0.01&<0.5
General	NH <sub>3</sub> -N	mg/L	SM4500-NH3	<0.1	<0.1
General	Nitrate (NO <sub>3</sub> )	mg/L	EPA300.0	3.34	4.86
General	Nitrate-N	mg/L	EPA300.0	0.754	1.1
General	Nitrite-N	mg/L	EPA300.0	<0.01	0.0359
General	Phosphorus - Total (as P)	mg/L	SM4500-PE	0.106	0.16
General	Specific Conductance	umhos/cm	SM2510 B	974	984
General	Sulfate	mg/L	EPA300.0	160	160
General	Total Dissolved Solids	mg/L	SM2540C	594	630
General	Total Organic Carbon	mg/L	SM5310B/EPA415.1	2.3	2.56

Appendix B.2. 2011-2012 Dry Weather Concentrations

Group	Parameter	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2011-12Event04 9/20/2011	San Gabriel River @ SGR Parkway S14 2011-12Event12 1/9/2012
General	Total Petroleum Hydrocarbons	mg/L	EPA418.1	<1.5	<1.5
General	Total Suspended Solids	mg/L	SM2540D	10	14
General	Turbidity	NTU	SM2130B	0.95	1.11
General	Volatile Suspended Solids	mg/L	SM2540E	7	4
Herbicides	2-4-5-TP-SILVEX	ug/L	EPA515.3	<0.07	<0.07
Herbicides	2-4-D	ug/L	EPA515.3	<0.015	<0.015
Herbicides	Glyphosate	ug/L	EPA547	<5	<5
Metals	Dissolved Aluminum	ug/L	EPA200.8	<50	<50
Metals	Dissolved Antimony	ug/L	EPA200.8	>0.2&<0.5	>0.2&<0.5
Metals	Dissolved Arsenic	ug/L	EPA200.8	>0.2&<1	2.48
Metals	Dissolved Barium	ug/L	EPA200.8	88.9	97.6
Metals	Dissolved Beryllium	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Cadmium	ug/L	EPA200.8	<0.1	>0.1&<0.25
Metals	Dissolved Chromium	ug/L	EPA200.8	0.57	0.709
Metals	Dissolved Chromium +6	ug/L	EPA218.6	<0.25	<0.25
Metals	Dissolved Copper	ug/L	EPA200.8	6.27	5.62
Metals	Dissolved Iron	ug/L	EPA200.8	113	133
Metals	Dissolved Lead	ug/L	EPA200.8	1.78	0.827
Metals	Dissolved Mercury	ug/L	EPA245.1	<0.1	<0.1
Metals	Dissolved Nickel	ug/L	EPA200.8	5.49	4.93
Metals	Dissolved Selenium	ug/L	EPA200.8	1.02	>0.5&<1
Metals	Dissolved Silver	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Thallium	ug/L	EPA200.8	<0.1	<0.1
Metals	Dissolved Zinc	ug/L	EPA200.8	69.8	49.6
Metals	Aluminum	ug/L	EPA200.8	174	136
Metals	Antimony	ug/L	EPA200.8	0.652	0.624
Metals	Arsenic	ug/L	EPA200.8	2.54	2.65
Metals	Barium	ug/L	EPA200.8	110	111
Metals	Beryllium	ug/L	EPA200.8	<0.1	<0.1
Metals	Cadmium	ug/L	EPA200.8	<0.1	>0.1&<0.25
Metals	Chromium	ug/L	EPA200.8	4.44	1.1
Metals	Chromium +6	ug/L	EPA218.6	<0.25	<0.25
Metals	Copper	ug/L	EPA200.8	7.94	7.62
Metals	Iron	ug/L	EPA200.8	234	333
Metals	Lead	ug/L	EPA200.8	2.91	1.52
Metals	Mercury	ug/L	EPA245.1	<0.1	<0.1
Metals	Nickel	ug/L	EPA200.8	8.22	6.66
Metals	Selenium	ug/L	EPA200.8	2.01	1.65
Metals	Silver	ug/L	EPA200.8	<0.1	<0.1
Metals	Thallium	ug/L	EPA200.8	<0.1	<0.1
Metals	Zinc	ug/L	EPA200.8	86.4	55.1
Organophosphate Pesticides	Atrazine	ug/L	EPA507	<0.7	<0.7
Organophosphate Pesticides	Chlorpyrifos	ug/L	EPA507	<0.02	<0.02
Organophosphate Pesticides	Cyanazine	ug/L	EPA507	<0.7	<0.7
Organophosphate Pesticides	Diazinon	ug/L	EPA507	<0.003	<0.003
Organophosphate Pesticides	Malathion	ug/L	EPA507	<0.4	<0.4
Organophosphate Pesticides	Prometryn	ug/L	EPA507	<0.7	<0.7
Organophosphate Pesticides	Simazine	ug/L	EPA507	<0.7	<0.7
Polychlorinated Biphenyls	PCB-1016 (Aroclor 1016)	ug/L	EPA608	<0.065	<0.065

Appendix B.2. 2011-2012 Dry Weather Concentrations

Group	Parameter	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2011-12Event04 9/20/2011	San Gabriel River @ SGR Parkway S14 2011-12Event12 1/9/2012
Polychlorinated Biphenyls	PCB-1221 (Aroclor 1221)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1232 (Aroclor 1232)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1242 (Aroclor 1242)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1248 (Aroclor 1248)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1254 (Aroclor 1254)	ug/L	EPA608	<0.065	<0.065
Polychlorinated Biphenyls	PCB-1260 (Aroclor 1260)	ug/L	EPA608	<0.065	<0.065
Semivolatile Organic Compounds (Acids)	2-4-6-Trichlorophenol	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	2-4-Dichlorophenol	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	2-4-Dimethylphenol	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	2-4-Dinitrophenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	2-Chlorophenol	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	2-Nitrophenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	4-Chloro-3-methylphenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	4-Nitrophenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Acids)	Pentachlorophenol	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Acids)	Phenol	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Acids)	Phenolics - Total recoverable	mg/L	EPA420.1	>0.03&<0.1	<0.03
Semivolatile Organic Compounds (Base/Neutral)	1-2-4-Trichlorobenzene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	1-2-Benzanthracene	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	1-2-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	1-2-Diphenylhydrazine	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	1-3-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	1-4-Dichlorobenzene	ug/L	EPA625	<0.2	<0.2
Semivolatile Organic Compounds (Base/Neutral)	2-4-Dinitrotoluene	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	2-6-Dinitrotoluene	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	2-Chloroethyl vinyl ether	ug/L	EPA624	<0.83	<0.83
Semivolatile Organic Compounds (Base/Neutral)	2-Chloronaphthalene	ug/L	EPA625	<3.4	<3.4
Semivolatile Organic Compounds (Base/Neutral)	3-3-Dichlorobenzidine	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	4-6-Dinitro-2-methylphenol	ug/L	EPA625	<1	<1
Semivolatile Organic Compounds (Base/Neutral)	4-Bromophenyl phenyl ether	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	4-Chlorophenyl phenyl ether	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Acenaphthylene	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Anthracene	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzidine	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(a)pyrene	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo(k)fluoranthene	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Benzo[b]fluoranthene	ug/L	EPA625	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Benzo[g,h-i]perylene	ug/L	EPA625	<1.67	<1.67
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethoxy) methane	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroethyl) ether	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Chloroisopropyl) ether	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Bis(2-Ethylhexyl) phthalate	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Butyl benzyl phthalate	ug/L	EPA625	<3.33	<3.33
Semivolatile Organic Compounds (Base/Neutral)	Chrysene	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Dibenzo(a-h)anthracene	ug/L	EPA625	<0.04	<0.04
Semivolatile Organic Compounds (Base/Neutral)	Diethyl phthalate	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Dimethyl phthalate	ug/L	EPA625	<0.7	<0.7
Semivolatile Organic Compounds (Base/Neutral)	Fluoranthene	ug/L	EPA625	<0.02	<0.02

Appendix B.2. 2011-2012 Dry Weather Concentrations

Group	Parameter	Units	Analysis Method	San Gabriel River @ SGR Parkway S14 2011-12Event04 9/20/2011	San Gabriel River @ SGR Parkway S14 2011-12Event12 1/9/2012
Semivolatile Organic Compounds (Base/Neutral)	Fluorene	ug/L	EPA625	<0.04	<0.04
Semivolatile Organic Compounds (Base/Neutral)	Hexachloro-cyclopentadiene	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobenzene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Hexachlorobutadiene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Hexachloroethane	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Indeno(1-2-3-c-d)pyrene	ug/L	EPA625	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Isophorone	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-di-n-propyl amine	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-dimethyl amine	ug/L	EPA625	<1.7	<1.7
Semivolatile Organic Compounds (Base/Neutral)	N-Nitroso-diphenyl amine	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Naphthalene	ug/L	EPA625	<0.07	<0.07
Semivolatile Organic Compounds (Base/Neutral)	Nitrobenzene	ug/L	EPA625	<0.4	<0.4
Semivolatile Organic Compounds (Base/Neutral)	Phenanthrene	ug/L	EPA625	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	Pyrene	ug/L	EPA625	<0.02	<0.02
Semivolatile Organic Compounds (Base/Neutral)	di-n-Butyl phthalate	ug/L	EPA625	<3.4	<3.4
Semivolatile Organic Compounds (Base/Neutral)	di-n-Octyl phthalate	ug/L	EPA625	<3.4	<3.4

Values reported with a "<" are not detected at the method detection level, and reported as <MDL

Values reported with a "<" and a ">" were detected between the method detection limit and reporting limit, they are reported as >MDL & <RL

NS = Not Sampled

\*Exceedance of Water Quality Objective

Watershed Management Program Appendix 3

# A-3-1 MCM Guidance

DRAFT

# Public Information and Participation Program

## Introduction

*Permit §VI.D.5.a (LA)/ §VII.F.1 (LB)*

Each participating city is required to develop and implement a Public Information and Participation Program (PIPP) that includes the requirements listed in Permit §VI.D.5.a (LB §VII.F). This document provides guidance that the participating cities can follow to implement a PIPP in compliance with the Permit.

The objectives of the PIPP are to:

- Measurably increase the knowledge of the target audiences about the MS4, the adverse impacts of stormwater pollution on receiving waters and potential solutions to mitigate the impacts.
- Measurably change the waste disposal and stormwater pollution generation behavior of target audiences by developing and encouraging the implementation of appropriate alternatives.
- Involve and engage a diversity of socio-economic groups and ethnic communities in Los Angeles County to participate in mitigating the impacts of stormwater pollution.

## PIPP Implementation

*Permit §VI.D.5.b (LA)/§VII.F.2 (LB)*

The PIPP is implemented using the following approaches:

- By participating in a County-wide PIPP,
- By participating in one or more Watershed Group sponsored PIPPs, and
- individually within its jurisdiction.

Cities participating in a County-wide or Watershed Group PIPP provide contact info for their staff responsible for stormwater public education activities to the designated PIPP coordinator. Changes in contact information are provided within 30 days of the date that the change occurred.

## Public Participation

*Permit §VI.D.5.c (LA)/§VII.F.3 (LB)*

### Public Reporting

The means for public reporting of clogged catch basin inlets and illicit discharges/dumping, faded or missing catch basin labels, and general stormwater and non-stormwater pollution prevention information is provided through the use of the countywide 888-CLEAN-LA hotline. In addition, each participating city:

- Includes the reporting information – updated when necessary – in public information and the government pages of the telephone book as they are developed or published.
- Identifies staff or departments who will serve as the contact person(s) and will make this information available on its website.
- Provides current, updated hotline contact information to the general public within its jurisdiction.

## Events

Events are organized to target residents and population subgroups. The purpose of the events is to educate and involve the community in stormwater and non-stormwater pollution prevention activities, such as education seminars, clean-ups, and community catch basin stenciling.

## Residential Outreach Program

*Permit §VI.D.5.d (LA)/§VII.F.4 (LB)*

With the exception of item 5, which is no longer an element of the countywide PIP Program, each city implements the following activities for the Residential Outreach Program as part of a countywide program:

1. Conduct stormwater pollution prevention public service announcements and advertising campaigns
2. Prepare public education materials that include information on the proper handling (i.e., disposal, storage and/or use) of:
  - a. Vehicle waste fluids
  - b. Household waste materials (i.e., trash and household hazardous waste, including personal care products and pharmaceuticals)
  - c. Construction waste materials
  - d. Pesticides and fertilizers (including integrated pest management (IPM) practices to promote reduced use of pesticides)
  - e. Green waste (including lawn clippings and leaves)
  - f. Animal wastes
3. Distribute activity specific stormwater pollution prevention public education materials at the following points of purchase:
  - a. Automotive parts stores
  - b. Home improvement centers / lumber yards / hardware stores/paint stores
  - c. Landscaping / gardening centers
  - d. Pet shops / feed stores
4. Maintain stormwater websites or provide links to stormwater websites via each participating city's website. This includes educational material and opportunities for the public to participate in stormwater pollution prevention and clean-up activities listed in Part VI.D.4 of the Permit.
5. Provide independent, parochial, and public schools within each participating city's jurisdiction with materials to educate school children (K-12) on stormwater pollution. Material may include videos, live presentations and other information. A useful source of materials to work with, or leverage, is other statewide agencies and associations. These associations include the State Water Board's "Erase the Waste" educational program and the California Environmental Education Interagency Network (CEEIN) to implement this requirement.
6. When implementing the above activities, use effective strategies to educate and involve ethnic communities in stormwater pollution prevention through culturally effective methods.

# Industrial/Commercial Facilities Program

Each participating city is required to implement an industrial/commercial facilities program that includes the provisions listed in Permit § VI.D.6 (LB §VII.G). This document provides guidance that the participating cities can follow to implement an industrial/commercial facilities program in compliance with the Permit.

## Introduction

*Permit § VI.D.6.a (LA)/ §VII.G.1 (LB)*

The Industrial/Commercial Facilities Program is designed to prevent illicit discharges into the MS4 and receiving waters, reduce industrial/commercial discharges of stormwater to the maximum extent practicable, and prevent industrial/commercial discharges from the MS4 from causing or contributing to a violation of receiving water limitations. The program consists of the following components:

- Track,
- Educate,
- Inspect and
- Ensure compliance with municipal ordinances at industrial/commercial facilities determined to be critical sources of pollutants in stormwater.

## Track Critical Industrial/Commercial Sources

*Permit § VI.D.6.b (LA)/ §VII.G.2 (LB)*

The critical sources to be tracked are listed in Table ICF-1.

Table ICF-1: Critical Sources

Facility Category	Facility	
Commercial Facilities	Restaurants	
	Automotive service facilities (including those located at automotive dealerships)	
	Retail Gasoline Outlets	
	Nurseries and Nursery Centers (Merchant Wholesalers, Nondurable Goods, and Retail Trade)	
Industrial Facilities	USEPA "Phase I" Facilities <sup>1</sup>	
	Other federally-mandated facilities <sup>2</sup>	Municipal landfills
		Hazardous waste treatment, disposal, and recovery facilities
Industrial facilities subject to § 313 "Toxic Release Inventory" reporting requirements of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA) <sup>3</sup>		
General Facilities	All other commercial or industrial facilities determined to potentially contribute a substantial pollutant load to the MS4.	

<sup>1</sup> as specified in 40 CFR §122.26(b)(14)(i)-(xi)

<sup>2</sup> as specified in 40 CFR §122.26(d)(2)(iv)(C)

<sup>3</sup> 42 U.S.C. § 11023

Critical source facilities are tracked in an electronic database management system. The information stored for each critical source in the inventory is listed in Table ICF-2.

Table ICF-2: Inventory Information for Critical Sources

Information Category		Information
General	Name	Facility Name
	Location	Facility address
		Facility latitude and longitude coordinates
		Receiving water
	Contact	Owner/operator name
		Mailing address
		Phone number
Email (if available)		
Business Type	Standard Industrial Classification (SIC) code and/or North American Industry Classification System (NAICS) code	
	Narrative description of the activities performed and/or principal products produced	
Water quality	Status of exposure of materials to stormwater	
	Pollutants generated by facility activities (A-ICF-1)	
	Identification of whether the facility is tributary to a waterbody segment with impairments <sup>4</sup> for pollutants that are also generated by the facility.	
Prioritization	High, medium or low. The default priority is medium.	
NPDES Permit	For applicable facilities, identify coverage under the State Water Board's General NPDES Permit for the Discharge of Stormwater Associated with Industrial Activities (Industrial General Permit) or other individual or general NPDES permits or any waiver issued by the Regional or State Water Board pertaining to stormwater discharges.	
	For Industrial General Permit facilities, identify whether the facility has filed a No Exposure Certification with the State Water Board.	

### Update Inventory

The critical sources inventory is updated at least annually. The update is accomplished through the collection of new information from sources such as field activities and readily available inter/intra-agency records (e.g. business licenses, pretreatment permits, sanitary sewer connection permits and the State Water Resources Control Board's Storm Water Multiple Application and Report Tracking System (SMARTS)).

<sup>4</sup> CWA § 303(d) listed or subject to a TMDL

### Prioritization

Prioritizing facilities by their potential water quality impact provides an excellent opportunity to optimize the effectiveness of the Industrial/Commercial Facilities Program. The three inventory fields under the “Water Quality” category of Table ICF-2 provide information that allows for such a facility prioritization. Based on these fields, the following tables establish a method to prioritize all industrial/commercial facilities into three graded tiers – High, Medium and Low. The City may follow an alternative prioritization method provided it results in a similar three-tiered scheme. In order to maintain a minimum inspection frequency equivalent to the mandates of the MS4 Permit, a condition must be applied to the prioritization process. This condition is explained on the following page.




Figure ICF-1: Industrial/Commercial Facility Prioritization Scheme

<sup>5</sup> CWA § 303(d) listed or subject to a TMDL

Step 3 may also be expressed by the relationships  $A \cdot B + C \geq 1 \rightarrow$  High,  $1 > A \cdot B + C > 0 \rightarrow$  Medium and  $A \cdot B + C = 0 \rightarrow$  Low. The purpose of multiplying A and B is to scale the impact of the presence of the pollutants at a facility (B) by the likelihood that they will be discharged to the MS4 (A). Factor C quantifies water quality concerns that are independent of A or B and as such is incorporated through addition. The purpose of this numerical approach is to provide consistency to the prioritization process. It is intended solely as a guide. The City may also prioritize facilities based on a qualitative assessment of factors A, B and C as listed in Figure ICF-1.

**Prioritization Condition**

The facility prioritization impacts the inspection frequency. In fact the main objective of prioritizing the facilities is to adjust the inspection schedule to focus efforts on water quality priorities. The intent is not to reduce the total number of inspections. In order to maintain a total number of inspections in line with the expectations of the MS4 Permit (i.e. result in the same number of average inspections per year as a semi-quinquennial frequency), one additional condition must be imposed:

***The total number of low priority facilities is less than or equal to 3 times the number of high priority facilities.***  
*Prioritization condition*

**Prioritization Frequency**

The default priority for a facility is Medium. Prioritization and reprioritization may be conducted at any time based on the discretion of the City. Figure ICF-2 is a flowchart of the prioritization process.




Figure ICF-2: Prioritization Process

**Educate Industrial/Commercial Sources**

*Permit § VI.D.6.c (LA)/ §VII.G.3 (LB)*

At least once during the five-year period of the MS4 Permit, the owner/operator of each of the inventoried critical sources is notified of the BMP requirements applicable to the facility/source.

**Business Assistance Program**

The Business Assistance Program provides technical information to businesses to facilitate their efforts to reduce the discharge of pollutants in stormwater. Assistance is targeted to select business sectors or small businesses upon a determination that their activities may be contributing substantial pollutant loads to the MS4 or receiving water. Assistance may include technical guidance and provision of educational materials. The Program includes at least one of the following components:

- **Technical Guidance** – Provide on-site technical assistance, telephone, or e-mail consultation regarding the responsibilities of businesses to reduce the discharge of pollutants, procedural requirements, and available guidance documents. Guidance methods include but are not limited to:
  - Technical guidance through the critical source inspection program. During an inspection the inspector provides to the business owner/operator 1) on-site technical assistance and 2) contact information for continued consultation. The inspector may also refer staff to relevant fact sheets from the *CASQA Industrial and Commercial BMP Handbook*.
  - Technical guidance initiated with businesses through an informational letter, email, webpage or social media. The notice provides contact information of relevant stormwater staff for business assistance as well as hyperlinks to available guidance documents such as the *CASQA Industrial and Commercial BMP Handbook*.
- **Educational Materials** – Distribute stormwater pollution prevention educational materials to operators of 1) auto repair shops, car wash facilities, restaurants and 2) mobile sources including automobile/equipment repair, washing, or detailing, power washing services, mobile carpet, drape, or upholstery cleaning services, swimming pool, water softener, and spa services, portable sanitary services and commercial applicators and distributors of pesticides, herbicides and fertilizers, if present. Material sources and distribution methods include but are not limited to:
  - Distribution method – The presence of these businesses within an agency’s jurisdiction may be determined through business licenses or other readily available inter/intra-agency records.
  - Material sources – Educational materials are available at USEPA’s Nonpoint Source (NPS) Outreach Toolbox at <http://cfpub.epa.gov/npstbx/index.html>. The toolbox is a database of nationwide public education materials that is intended for use by state and local campaigns. The toolbox contains a variety of resources to help develop an effective and targeted outreach campaign.

## Inspect Critical Industrial/Commercial Sources

*Modified from Permit §VI.D.6.d-e (LA)/ §VII.G.4-5(LB)*

### Frequency of Inspections

Following the facility prioritization method described in this guidance document, the City will inspect high priority facilities annually, medium priority facilities semi-quinquennially (once every 2.5 years) and low priority facilities quinquennially (once every five years). The frequencies may be altered by the exclusions defined in the following section. The prioritization condition on Page ICF-4 ensures at least the same average number of inspections conducted per year as the semi-quinquennial frequency defined in the MS4 Permit.

The City will conduct the first compliance inspection of industrial/commercial facilities within one year of the approval of the Watershed Management Program by the Executive Officer. There will be a minimum interval of six months between the first and the second mandatory compliance inspections.

## Exclusions to the Frequency of Industrial Inspections

### Exclusion of Facilities Previously Inspected by the Regional Water Board

The State Water Board's Stormwater Multiple Application and Report Tracking System (SMARTS) database<sup>6</sup> is reviewed at defined intervals to determine if an industrial facility has recently been inspected by the Regional Water Board. The first interval is two years after the effective date of the MS4 Permit (LA: December 28, 2014, LB: March 28,, 2016) and the second interval is four years after the effective date (LA: December 28, 2016, LB: March 28, 2018). If it is determined through the review that the Regional Water Board conducted an inspection of a facility within the prior 24 month period, then the facility does not require an inspection.

### No Exposure Verification

The initial inspection identifies those facilities that have filed a No Exposure Certification with the State Water Board. Three to four years after the effective date of the MS4 Permit, a second inspection is performed for at least 25% of the facilities identified to have filed a No Exposure Certification. The purpose of this inspection is to verify the continuity of the no exposure status.

## Scope of Inspections

A template inspection form is included as Attachment ICF-A.

### **Scope of Commercial Inspections**

Commercial critical source facilities are inspected to confirm that stormwater and non-stormwater BMPs are effectively implemented in compliance with municipal ordinances. At each facility, inspectors verify that the operator is implementing effective source control BMPs for each corresponding activity. The implementation of additional BMPs is required where stormwater from the MS4 discharges to a significant ecological area (SEA), a water body subject to TMDL provisions<sup>7</sup>, or a CWA §303(d) listed impaired water body. For those BMPs that are not adequately protective of water quality standards, additional site-specific controls may be required.

### **Scope of Mandatory Industrial Facility Inspections**

At each industrial critical source the inspector confirms that the facility

- Has a current Waste Discharge Identification (WDID) number for coverage under the Industrial General Permit, and that a Storm Water Pollution Prevention Plan (SWPPP) is available on-site; or
- Has applied for, and has received a current No Exposure Certification for facilities subject to this requirement;
- Is effectively implementing BMPs in compliance with municipal ordinances. Facilities must implement the source control BMPs identified in Table ICF-3, unless the pollutant generating activity does not occur. Additional BMPs must be implemented where stormwater from the MS4 discharges to a water body subject to TMDL Provisions in Part VI.E of the MS4 Permit, or a CWA § 303(d) listed impaired water body. If the specified BMPs are not adequately protective of water quality standards, additional site-specific controls may be required. For critical sources that discharge to MS4s that discharge to SEAs, operators must implement additional pollutant-specific controls to reduce pollutants in stormwater runoff that are causing or contributing to

<sup>6</sup> SMARTS is accessible at <https://smarts.waterboards.ca.gov/smarts/faces/SwSmartsLogin.jsp>

<sup>7</sup> As described in Part VI.E of the MS4 Permit

exceedances of water quality standards.

- Applicable industrial facilities identified as not having either a current WDID or No Exposure Certification are notified that they must obtain coverage under the Industrial General Permit and will be referred to the Regional Water Board per the Progressive Enforcement Policy procedures identified in Part VI.D.2 of the MS4 Permit.

### **Source Control BMPs**

*Permit § VI.D.6.f (LA)/ §VII.G.6 (LB)*

Effective source control BMPs for the activities listed in Table ICF-3 are implemented at commercial and industrial facilities, unless the pollutant generating activity does not occur:

### **Significant Ecological Areas (SEAs)**

*Permit § VI.D.6.g (LA)/ §VII.H (LB)*

For critical sources that discharge to MS4s that discharge to SEAs, each Permittee will require operators to implement additional pollutant-specific controls to reduce pollutants in stormwater runoff that are causing or contributing to exceedances of water quality standards.

### **Progressive Enforcement**

*Permit § VI.D.6.h (LA)/ §VII.I (LB)*

Each Permittee will implement its Progressive Enforcement Policy to ensure that Industrial / Commercial facilities are brought into compliance with all stormwater requirements within a reasonable time period. See Part VI.D.2 of the MS4 Permit for requirements for the development and implementation of a Progressive Enforcement Policy.

Table ICF-3: Source Control BMPs at Commercial and Industrial Facilities

<b>Pollutant-Generating Activity</b>	<b>BMP Description</b>	<b>BMP Fact Sheet*</b>
Unauthorized Non-Storm water Discharges	Effective elimination of non-stormwater discharges	SC-10
Accidental Spills/ Leaks	Implementation of effective spills/ leaks prevention and response procedures	SC-11
Vehicle/ Equipment Fueling	Implementation of effective fueling source control devices and practices	SC-20
Vehicle/ Equipment Cleaning	Implementation of effective equipment/vehicle cleaning practices and appropriate wash water management practices	SC-21
Vehicle/ Equipment Repair	Implementation of effective vehicle/ equipment repair practices and source control devices	SC-22
Outdoor Liquid Storage	Implementation of effective outdoor liquid storage source controls and practices	SC-31
Outdoor Equipment Operations	Implementation of effective outdoor equipment source control devices and practices	SC-32
Outdoor Storage of Raw Materials	Implementation of effective source control practices and structural devices	SC-33
Storage and Handling of Solid Waste	Implementation of effective solid waste storage/ handling practices and appropriate control measures	SC-34
Building and Grounds Maintenance	Implementation of effective facility maintenance practices	SC-41
Parking/ Storage Area Maintenance	Implementation of effective parking/ storage area designs and housekeeping/ maintenance practices	SC-43
Stormwater Conveyance System Maintenance	Implementation of proper conveyance system operation and maintenance protocols	SC-44
<b>Pollutant-Generating Activity</b>	<b>BMP Description from Regional Water Board Resolution No. 98-08</b>	
Sidewalk Washing	1. Remove trash, debris, and free standing oil/grease spills/leaks (use absorbent material, if necessary) from the area before washing; and 2. Use high pressure, low volume spray washing using only potable water with no cleaning agents at an average usage of 0.006 gallons per square feet of sidewalk area.	
Street Washing	Collect and divert wash water to the sanitary sewer – publically owned treatment works (POTW). Note: POTW approval may be needed.	

\* Source: CASQA Industrial and Commercial Stormwater BMP Handbook, 2003

Table ICF-4: Potential Pollutants from Industrial Activities\*

Activity or Facility Type	Potential Pollutants								
	Sediments	Nutrients	Metals	Organics and Toxicants**	Floatable Materials	Oxygen-Demanding Substances	Oil and Grease	Bacteria	Pesticides
Vehicle & Equipment Fueling			X	X					
Vehicle & Equipment Washing and Steam Cleaning	X	X	X	X		X	X		
Vehicle & Equipment Maintenance and Repair			X	X			X		
Outdoor Loading & Unloading of Materials	X	X	X	X	X	X	X		
Outdoor Container Storage of Liquids		X	X	X		X	X		X
Outdoor Process Equipment Operations and Maintenance	X		X	X			X		
Outdoor Storage of Raw Materials, Products, and Byproducts	X	X	X	X	X	X	X		
Waste Handling & Disposal			X	X	X	X	X	X	
Contaminated or Erodible Surface Areas	X	X	X	X	X	X	X	X	
Building and Grounds Maintenance	X	X	X		X	X		X	X
Building Repair, Remodeling, and Construction	X		X		X	X			
Parking/Storage Area Maintenance			X	X	X		X		

\* Source: CASQA Industrial and Commercial Stormwater BMP Handbook, 2003

\*\* This includes all toxic pollutants other than pesticides

Table ICF-5: Potential Pollutants by Industrial/Commercial Facility Type\*

Activity or Facility Type	Potential Pollutants								
	Sediments	Nutrients	Metals	Organics and Toxicants**	Floatable Materials	Oxygen-Demanding Substances	Oil and Grease	Bacteria	Pesticides
Vehicle mechanical repair, maintenance, fueling, or cleaning	X	X	X	X		X	X		
Airplane mechanical repair, maintenance, fueling, or cleaning	X	X	X	X		X	X		
Boat mechanical repair, maintenance, fueling, or cleaning	X	X	X	X		X	X		
Equipment repair, maintenance, fueling, or cleaning	X	X	X	X		X	X		
Automobile and other vehicle body repair or painting			X	X			X		
Mobile automobile or other vehicle washing	X	X	X			X	X		
Automobile (or other vehicle) parking lots and storage			X		X		X		
Retail or wholesale fueling			X	X	X		X		
Pest control services									X
Eating or drinking establishments		X		X	X	X	X	X	X
Mobile carpet, drape or furniture cleaning	X			X					
Cement mixing or cutting	X								
Masonry	X								
Painting and coating			X	X			X		
Botanical or zoological gardens and exhibits	X	X			X	X		X	X
Landscaping	X	X			X	X		X	X
Nurseries and greenhouses	X	X			X	X		X	X
Golf courses, parks and other recreational areas/facilities	X	X			X	X		X	X
Cemeteries	X	X			X	X		X	X
Pool and fountain cleaning		X	X	X	X	X		X	
Marinas			X	X	X	X	X	X	
Port-a-Potty servicing		X			X	X		X	

\* Source: Orange County Drainage Area Management Plan, 2003

\*\* This includes all toxic pollutants other than pesticides

# Planning and Land Development Program

The Cities are required to implement a Planning and Land Development program that includes the provisions listed in the MS4 Permit (LA MS4 Permit §VI.D.7, LB MS4 Permit §VII.J). This document provides guidance that the participating cities can follow to implement a Planning and Land Development program in compliance with the MS4 Permit.

## Introduction

*Permit §VI.D.7.a (LA)/§VII.J.1 (LB)*

The Planning and Land Development Program for all New Development and Redevelopment projects subject to the MS4 Permit includes measures to:

- Lessen the water quality impacts of development by using smart growth practices such as compact development, directing development towards existing communities via infill or redevelopment, and safeguarding of environmentally sensitive areas.
- Minimize the adverse impacts from stormwater runoff on the biological integrity of Natural Drainage Systems and the beneficial uses of water bodies in accordance with requirements under CEQA (Cal. Pub. Resources Code §21000 et seq.).
- Minimize the percentage of impervious surfaces on land developments by minimizing soil compaction during construction, designing projects to minimize the impervious area footprint, and employing Low Impact Development (LID) design principles to mimic pre-development hydrology through infiltration, evapotranspiration and rainfall harvest and use.
- Maintain existing riparian buffers and enhance riparian buffers when possible.
- Minimize pollutant loadings from impervious surfaces such as roof tops, parking lots, and roadways through the use of properly designed, technically appropriate BMPs (including Source Control BMPs such as good housekeeping practices), LID Strategies, and Treatment Control BMPs.
- Properly select, design and maintain LID and Hydromodification Control BMPs to address pollutants that are likely to be generated, reduce changes to pre-development hydrology, assure long-term function, and avoid the breeding of vectors.<sup>1</sup>
- Prioritize the selection of BMPs to remove stormwater pollutants, reduce stormwater runoff volume, and beneficially use stormwater to support an integrated approach to protecting water quality and managing water resources in the following order of preference:
  - On-site infiltration, bioretention and/or rainfall harvest and use.
  - On-site biofiltration, off-site groundwater replenishment, and/or off-site retrofit.

---

<sup>1</sup> Treatment BMPs when designed to drain within 96 hours of the end of rainfall minimize the potential for the breeding of vectors. See California Department of Public Health *Best Management Practices for Mosquito Control in California* (2012) at <http://www.westnile.ca.gov/resources.php>

**Applicability***Permit §VI.D.7.b (LA)/§VII.J.2-3 (LB)***New Development Projects**

The New Development and Redevelopment categories below will require a Standard Urban Stormwater Mitigation Plan (SUSMP), also known as a Low Impact Development (LID) Plan, containing stormwater mitigation measures in compliance with MS4 Permit requirements. Development projects subject to conditioning and approval for the design and implementation of post-construction controls to mitigate stormwater pollution, prior to completion of the project(s), are listed below:

1. All development projects (including single family hillside homes) equal to 1 acre or greater of disturbed area and adding more than 10,000 square feet of impervious surface area
2. Industrial parks with 10,000 square feet or more of surface area
3. Commercial malls with 10,000 square feet or more surface area
4. Retail gasoline outlets with 5,000 square feet or more of surface area
5. Restaurants (SIC 5812) with 5,000 square feet or more of surface area
6. Parking lots with 5,000 square feet or more of impervious surface area, or with 25 or more parking spaces
7. Automotive service facilities (SIC 5013, 5014, 5511, 5541, 7532-7534 and 7536-7539) with 5,000 square feet or more of surface area
8. Projects located in or directly adjacent to, or discharging directly to a Significant Ecological Area (SEA), where the development will:
  - a. Discharge stormwater runoff that is likely to impact a sensitive biological species or habitat; and
  - b. Create 2,500 square feet or more of impervious surface area
9. Redevelopment projects in subject categories that meet Redevelopment thresholds identified below

**Redevelopment Projects**

Redevelopment projects subject to agency conditioning and approval for the design and implementation of post-construction controls to mitigate stormwater pollution, prior to completion of the project(s), are:

1. Land-disturbing activity that results in the creation or addition or replacement of 5,000 square feet or more of impervious surface area on an already developed site on development categories identified above.
2. Where Redevelopment results in an alteration to more than fifty percent of impervious surfaces of a previously existing development, and the existing development was not subject to post-construction stormwater quality control requirements, the entire project must be mitigated.
3. Where Redevelopment results in an alteration of less than fifty percent of impervious surfaces of a previously existing development, and the existing development was not subject to post-construction stormwater quality control requirements, only the alteration must be mitigated, and not the entire

development.

4. Redevelopment does not include routine maintenance activities that are conducted to maintain original line and grade, hydraulic capacity, original purpose of facility or emergency Redevelopment activity required to protect public health and safety. Impervious surface replacement, such as the reconstruction of parking lots and roadways which does not disturb additional area and maintains the original grade and alignment, is considered a routine maintenance activity. Redevelopment does not include the repaving of existing roads to maintain original line and grade.
5. Existing single-family dwelling and accessory structures are exempt from the Redevelopment requirements unless such projects create, add, or replace 10,000 square feet of impervious surface area.

### **Special Provisions**

1. Street and road construction of 10,000 square feet or more of impervious surface area
  - a. These projects will follow an approved green streets manual to the maximum extent practicable. Street and road construction applies to standalone streets, roads, highways, and freeway projects, and also applies to streets within larger projects. The Cities will require a Standard Urban Mitigation Plan (SUSMP), also known as a Low Impact Development (LID) Plan, containing stormwater mitigation measures in compliance with the approved green streets manual requirements.
2. Single family hillside homes will require a less extensive plan. To the extent that an agency may lawfully impose conditions, mitigation measures or other requirements on the development or construction of a single-family home in a hillside area as defined in the applicable agency's Code and Ordinances, the Cities will require that during the construction of a single-family hillside home, the following measures are implemented:
  - a. Conserve natural areas
  - b. Protect slopes and channels
  - c. Provide storm drain system stenciling and signage
  - d. Divert roof runoff to vegetated areas before discharge unless the diversion would result in slope instability
  - e. Direct surface flow to vegetated areas before discharge unless the diversion would result in slope instability.

New Development/ Redevelopment  
Project Performance Criteria

Permit §VI.D.7.c (LA)/§VII.J.4 (LB)

**Integrated Water Quality/Flow Reduction/Resources Management Criteria**

All New Development and Redevelopment projects identified above will control pollutants, pollutant loads, and runoff volume emanating from the project site by: (1) minimizing the impervious surface area and (2) controlling runoff from impervious surfaces through infiltration, bioretention and/or rainfall harvest and use.

Projects will retain on-site the Stormwater Quality Design Volume (SWQDv) defined as the runoff from the 0.75-inch, 24-hour rain event or the 85th percentile, 24-hour rain event, as determined from the Los Angeles County 85th percentile precipitation isohyetal map<sup>2</sup>, *whichever is greater*. Exceptions include technical infeasibility, opportunity for regional groundwater replenishment, local ordinance equivalence, or hydromodification, as described in the sections below.

When evaluating the potential for on-site retention, the Cities will consider the maximum potential for evapotranspiration from green roofs and rainfall harvest and use.

**Alternative Compliance for Technical Infeasibility or Opportunity for Regional Groundwater Replenishment**

In instances of technical infeasibility or where a project has been determined to provide an opportunity to replenish regional groundwater supplies at an offsite location, the Cities may allow projects to comply with the MS4 Permit through the alternative compliance measures as described below:

1. To demonstrate technical infeasibility, the project applicant must demonstrate that the project cannot reliably retain 100 percent of the SWQDv on-site, even with the maximum application of green roofs and rainwater harvest and use, and that compliance with the applicable post-construction requirements would be technically infeasible by submitting a site-specific hydrologic and/or design analysis conducted and endorsed by a registered professional engineer, geologist, architect, and/or landscape architect. Conditions where technical infeasibility may result including those indicated in

---

<sup>2</sup> Found at <[http://ladpw.org/wrd/publication/engineering/Final\\_Report-Probability\\_Analysis\\_of\\_85th\\_Percentile\\_24-hr\\_Rainfall1.pdf](http://ladpw.org/wrd/publication/engineering/Final_Report-Probability_Analysis_of_85th_Percentile_24-hr_Rainfall1.pdf)>

2. Table PLD- 1 below. To utilize alternative compliance measures to replenish groundwater at an offsite location, the project applicant will demonstrate (i) why it is not advantageous to replenish groundwater at the project site, (ii) that groundwater can be used for beneficial purposes at the offsite location, and (iii) that the alternative measures will also provide equal or greater water quality benefits to the receiving surface water than the Water Quality/Flow Reduction/Resource Management Criteria.

DRAFT

Table PLD- 1: Technical Infeasibility Criteria

1. The infiltration rate of saturated in-situ soils is less than 0.3 inch per hour and it is not technically feasible to amend the in-situ soils to attain an infiltration rate necessary to achieve reliable performance of infiltration or bioretention BMPs in retaining the SWQDv on-site.
2. Locations where seasonal high groundwater is within 5 to 10 feet of the surface,
3. Locations within 100 feet of a groundwater well used for drinking water,
4. Brownfield development sites where infiltration poses a risk of causing pollutant mobilization,
5. Other locations where pollutant mobilization is a documented concern. Pollutant mobilization is considered a documented concern at or near properties that are contaminated or store hazardous substances underground.
6. Locations with potential geotechnical hazards
7. Smart growth and infill or Redevelopment locations where the density and/ or nature of the project would create significant difficulty for compliance with the on-site volume retention requirement.

**Alternative Compliance Measures**

When a project applicant has demonstrated that it is technically infeasible to retain 100 percent of the SWQDv on-site, or is proposing an alternative offsite project to replenish regional groundwater supplies, the agency will require one of the following mitigation options:

1. On-site Biofiltration

If using biofiltration due to demonstrated technical infeasibility, then the project must biofiltrate 1.5 times the portion of the SWQDv that is not reliably retained on-site, as calculated by Equation 1 below.

$$B_v = 1.5 * [SWQD_v - R_v] \tag{Equation 1}$$

Where:

Bv = biofiltration volume

SWQDv = the stormwater runoff from a 0.75 inch, 24-hour storm or the 85th percentile storm<sup>3</sup>, whichever is greater.

Rv = volume reliably retained on-site

The MS4 Permit does not mention flowrate based biotreatment BMPs; however, proprietary biotreatment systems are often sized using flowrate rather than volume. Additionally, in cases where a pump is needed prior to entering the biotreatment BMP, the system requires sizing based on the controlled flow from the pump. Therefore, if it is infeasible to size a biotreatment BMP with volume-based calculations, the flowrate may be substituted in lieu of volume. Similarly, the flow rate must be determined using the design storm of 0.75 inch, 24-hour storm event or the 85th percentile storm<sup>1</sup>, whichever is greater.

Conditions for On-site Biofiltration include the following:

- a. Biofiltration systems will meet the design specifications provided in Attachment H to the MS4 Permit unless otherwise approved by the Regional Water Board Executive Officer.

<sup>3</sup> Found at <[http://ladpw.org/wrd/publication/engineering/Final\\_Report-Probability\\_Analysis\\_of\\_85th\\_Percentile\\_24-hr\\_Rainfall1.pdf](http://ladpw.org/wrd/publication/engineering/Final_Report-Probability_Analysis_of_85th_Percentile_24-hr_Rainfall1.pdf)>

- b. Biofiltration systems discharging to a receiving water that is included on the Clean Water Act section 303(d) list of impaired water quality-limited water bodies due to nitrogen compounds or related effects will be designed and maintained to achieve enhanced nitrogen removal capability. See Attachment H of the MS4 Permit for design criteria for underdrain placement to achieve enhanced nitrogen removal.

## 2. Offsite Infiltration

Offsite infiltration when implemented will use infiltration or bioretention BMPs to intercept a volume of stormwater runoff equal to the SWQD<sub>v</sub>, less the volume of stormwater runoff reliably retained on-site, at an approved offsite project and provide pollutant reduction (treatment) of the stormwater runoff discharged from the project site in accordance with the Water Quality Mitigation Criteria. The required offsite mitigation volume will be calculated by Equation 2 below.

$$M_v = 1.0 * [SWQD_v - R_v] \quad \text{Equation 2}$$

Where:

$M_v$  = mitigation volume

$SWQD_v$  = runoff from the 0.75 inch, 24-hour storm event or the 85<sup>th</sup> percentile storm<sup>4</sup>,  
whichever is greater

$R_v$  = the volume of stormwater runoff reliably retained on-site.

## 3. Groundwater Replenishment Projects

Regional projects to replenish regional groundwater supplies at offsite locations may be proposed, provided the groundwater supply has a designated beneficial use in the Basin Plan. Regional groundwater replenishment projects must use infiltration, groundwater replenishment, or bioretention BMPs to intercept a volume of stormwater runoff equal to the SWQD<sub>v</sub> for New Development and Redevelopment projects, subject to conditioning and approval for the design and implementation of post-construction controls, within the approved project area. The projects must provide pollutant reduction (treatment) of the stormwater runoff discharged from development projects, within the project area, subject to conditioning and approval for the design and implementation of post-construction controls to mitigate stormwater pollution in accordance with the Water Quality Mitigation Criteria.

Regional groundwater replenishment projects being implemented in lieu of onsite controls will mitigate the volume as calculated using Equation 2 above.

Regional groundwater replenishment projects will be located in the same sub-watershed (defined as draining to the same HUC-12 hydrologic area in the Basin Plan) as the New Development or Redevelopment projects which did not implement on-site retention BMPs. Locations outside of the HUC-12 but within the HUC-10 subwatershed area may be considered if there are no opportunities within the HUC-12 subwatershed or if greater pollutant reductions and/or groundwater

---

<sup>4</sup> Found at <[http://ladpw.org/wrd/publication/engineering/Final\\_Report-Probability\\_Analysis\\_of\\_85th\\_Percentile\\_24-hr\\_Rainfall1.pdf](http://ladpw.org/wrd/publication/engineering/Final_Report-Probability_Analysis_of_85th_Percentile_24-hr_Rainfall1.pdf)>

replenishment can be achieved at a location within the expanded HUC-10 subwatershed. *The use of a mitigation, groundwater replenishment, or retrofit project outside of the HUC-12 subwatershed is subject to the approval of the Executive Officer of the Regional Water Board.*

#### 4. Offsite Project -Retrofit Existing Development

Use infiltration, bioretention, rainfall harvest and use and/or biofiltration BMPs to retrofit an existing development, with similar land uses as the New Development or land uses associated with comparable or higher stormwater runoff event mean concentrations (EMCs) than the new development. Comparison of EMCs for different land uses will be based on published data from studies performed in southern California. The retrofit plan will be designed and constructed to:

- a. Intercept a volume of stormwater runoff equal to the mitigation volume (Mv) as described above in Equation 2, except biofiltration BMPs will be designed to meet the biofiltration volume or flowrate as described in Equation 1, and
- b. Provide pollutant reduction (treatment) of the stormwater runoff from the project site as described in the Water Quality Mitigation Criteria.

#### 5. Conditions for Offsite Projects

Project applicants seeking to utilize these alternative compliance provisions may propose other offsite projects, which the agency in which the project is located may approve if they meet the requirements of this subpart.

- a. Location of offsite projects. Offsite projects will be located in the same sub-watershed (defined as draining to the same HUC-12 hydrologic area in the Basin Plan) as the New Development or Redevelopment project. Locations outside of the HUC-12 but within the HUC-10 subwatershed area may be considered if there are no opportunities within the HUC-12 subwatershed or if greater pollutant reductions and/or groundwater replenishment can be achieved at a location within the expanded HUC-10 subwatershed. *The use of a mitigation, groundwater replenishment, or retrofit project outside of the HUC-12 subwatershed is subject to the approval of the Executive Officer of the Regional Water Board.*
- b. Project applicant must demonstrate that equal benefits to groundwater recharge can be met on the project site.
- c. A prioritized list of potential offsite mitigation, groundwater replenishment and/or retrofit projects will be developed within each agency, and when feasible, the mitigation will be directed to the highest priority project within the same HUC-12 or if approved by the Regional Water Board Executive Officer, the HUC-10 drainage area, as the New Development project.
- d. Infiltration/bioretention will be the preferred LID BMP for offsite mitigation or groundwater replenishment projects. Offsite retrofit projects may include green streets, parking lot retrofits, green roofs, and rainfall harvest and use. Biofiltration BMPs may be considered for retrofit projects when infiltration, bioretention or rainfall harvest and use is technically infeasible.
- e. The agency in which the project is located will develop a schedule for the completion of offsite projects, including milestone dates to identify, fund, design, and construct the projects. Offsite

projects will be completed as soon as possible, and at the latest, within 4 years of the certificate of occupancy for the first project that contributed funds toward the construction of the offsite project, unless a longer period is otherwise authorized by the Executive Officer of the Regional Water Board. For public offsite projects, the agency in which the project is located must provide in their annual reports a summary of total offsite project funds raised to date and a description (including location, general design concept, volume of water expected to be retained, and total estimated budget) of all pending public offsite projects. Funding sufficient to address the offsite volume must be transferred to the agency (for public offsite mitigation projects) or to an escrow account (for private offsite mitigation projects) within one year of the initiation of construction.

- f. Offsite projects must be approved by the agency in which the project is located and may be subject to approval by the Regional Water Board Executive Officer, if a third-party petitions the Executive Officer to review the project. Offsite projects will be publicly noticed on the Regional Water Board's website for 30 days prior to approval.
- g. The project applicant must perform the offsite projects as approved by either the agency or the Regional Water Board Executive Officer or provide sufficient funding for public or private offsite projects to achieve the equivalent mitigation stormwater volume.

#### 6. Regional Stormwater Mitigation Program

An agency or agency group may apply to the Regional Water Board for approval of a regional or sub-regional stormwater mitigation program to substitute in part or wholly for New and Redevelopment requirements for the area covered by the regional or sub-regional stormwater mitigation program. Upon review and a determination by the Regional Water Board Executive Officer that the proposal is technically valid and appropriate, the Regional Water Board may consider for approval such a program if its implementation meets all of the following requirements:

- a. Retains the runoff from the 85th percentile, 24-hour rain event or the 0.75 inch, 24-hour rain event, whichever is greater;
- b. Results in improved stormwater quality;
- c. Protects stream habitat;
- d. Promotes cooperative problem solving by diverse interests;
- e. Is fiscally sustainable and has secure funding; and
- f. Is completed in five years including the construction and start-up of treatment facilities.

#### 7. Water Quality Mitigation Criteria

All New Development and Redevelopment projects that have been approved for offsite mitigation or groundwater replenishment projects will also provide treatment of stormwater runoff from the project site. These projects will design and implement post-construction stormwater BMPs and control measures to reduce pollutant loading as necessary to:

- a. Meet the pollutant specific benchmarks listed in Table PLD2 at the treatment systems outlet or prior to the discharge to the MS4, and

- b. Ensure that the discharge does not cause or contribute to an exceedance of water quality standards at the agency’s downstream MS4 outfall.

The project proponent may be allowed to install flow-through modular treatment systems including sand filters, or other proprietary BMP treatment systems with a demonstrated efficiency at least equivalent to a sand filter. The sizing of the flow through treatment device will be based on a rainfall intensity of 0.2 inches per hour, or the one year, one-hour rainfall intensity as determined from the most recent Los Angeles County isohyetal map, *whichever is greater*.

Table PLD- 2: Benchmarks Applicable to New Development Treatment BMPs.

Conventional Pollutants					
Pollutant	Suspended Solids mg/L	Total P mg/L	Total N mg/L	TKN mg/L	
<b>Effluent Concentration</b>	14	0.13	1.28	1.09	
Metals					
Pollutant	Total Cd µg/L	Total Cu µg/L	Total Cr µg/L	Total Pb µg/L	Total Zn µg/L
<b>Effluent Concentration</b>	0.3	6	2.8	2.5	23

New developments and redevelopments will not cause or contribute to an exceedance of applicable water quality-based effluent limitations established in the MS4 Permit pursuant to Total Maximum Daily Loads (TMDLs).

8. Hydromodification (Flow/ Volume/ Duration) Control Criteria

All New Development and Redevelopment projects located within natural drainage systems will implement hydrologic control measures, to prevent accelerated downstream erosion and to protect stream habitat in natural drainage systems. The purpose of the hydrologic controls is to minimize changes in post-development hydrologic stormwater runoff discharge rates, velocities, and duration. This will be achieved by maintaining the project’s pre-project stormwater runoff flow rates and durations.

Description

Hydromodification control in natural drainage systems will be achieved by maintaining the Erosion Potential (Ep) in streams at a value of 1, unless an alternative value can be shown to be protective of the natural drainage systems from erosion, incision, and sedimentation that can occur as a result of flow increases from impervious surfaces and prevent damage to stream habitat in natural drainage system tributaries<sup>5</sup>. Hydromodification mitigation approaches should meet the criteria below:

- a. Hydromodification control may include one, or a combination of on-site, regional or sub-regional hydromodification control BMPs, LID strategies, or stream and riparian buffer restoration measures. Any in-stream restoration measure shall not adversely affect the beneficial uses of the natural drainage systems.
- b. Natural drainage systems that are subject to the hydromodification assessments and controls,

<sup>5</sup> See Attachment J of the MS4 Permit, “Determination of Erosion Potential”

as described in this section, include all drainages that have not been improved (e.g., channelized or armored with concrete, shotcrete, or rip-rap) or drainage systems that are tributary to a natural drainage system, except as provided in Exemptions to Hydromodification Controls, see below. The clearing or dredging of a natural drainage system does not constitute an “improvement.”

- c. Until the State Water Board or the Regional Water Board adopts a final Hydromodification Policy or criteria, the Hydromodification Control Criteria described in this section will be implemented to control the potential adverse impacts of changes in hydrology that may result from New Development and Redevelopment projects located within natural drainage systems.

### **Exemptions to Hydromodification Controls**

New Development and Redevelopment projects may be exempt from implementation of hydromodification controls where assessments of downstream channel conditions and proposed discharge hydrology indicate that adverse hydromodification effects to beneficial uses of Natural Drainage Systems are unlikely. Conditions for exemptions include the following:

- a. Projects involving replacement, maintenance or repair of an agency’s existing flood control facility, storm drain, or transportation network.
- b. Redevelopment Projects in the center of urban areas that do not increase the effective impervious area or decrease the infiltration capacity of pervious areas compared to the pre-project conditions.
- c. Projects that have any increased discharge directly or via a storm drain to a sump, lake, area under tidal influence, into a waterway that has a 100-year peak flow (Q100) of 25,000 cfs or more, or other receiving water that is not susceptible to hydromodification impacts.
- d. Projects that discharge directly or via a storm drain into concrete or otherwise engineered (not natural) channels (e.g., channelized or armored with rip rap, shotcrete, etc.), which, in turn, discharge into receiving water that is not susceptible to hydromodification impacts.
- e. LID BMPs implemented on single family homes are sufficient to comply with hydromodification criteria.

### **Hydromodification Control Criteria**

The Hydromodification Control Criteria to protect natural drainage systems are as follows:

- a. Except for exemptions described above, projects disturbing an area greater than 1 acre but less than 50 acres within natural drainage systems will be presumed to meet pre-development hydrology if one of the following demonstrations is made:
  - i. The project is designed to retain on-site, through infiltration, evapotranspiration, and/or harvest and use, the stormwater volume from the runoff of the 95<sup>th</sup> percentile, 24-hour storm, or

- ii. The runoff flow rate, volume, and velocity for the post-development condition do not exceed the pre-development condition for the 2-year, 24-hour rainfall event and the duration for the post-development condition is not less than the pre-development condition for the 2-year, 24-hour rainfall event. This condition may be substantiated by simple screening models, including those described in Hydromodification Effects on Flow Peaks and Durations in Southern California Urbanizing Watersheds (Hawley et al., 2011) or other models acceptable to the Executive Officer of the Regional Water Board, or
- iii. The Erosion Potential (Ep) in the receiving water channel will approximate 1, as determined by a Hydromodification Analysis Study and the equation presented in Attachment J of the MS4 Permit. Alternatively, agencies can opt to use other work equations to calculate Erosion Potential with Executive Officer approval.
- b. Projects disturbing 50 acres or more within natural drainage systems will be presumed to meet pre-development hydrology based on the successful demonstration of one of the following conditions:
- i. The site infiltrates on-site at least the runoff from a 2-year, 24-hour storm event, or
  - ii. The runoff flow rate, volume, and velocity for the post-development condition does not exceed the pre-development condition for the 2-year, 24-hour rainfall event and the duration for the post-development condition is not less than the pre-development condition for the 2-year, 24-hour rainfall event. These conditions must be substantiated by hydrologic modeling acceptable to the Regional Water Board Executive Officer, or
  - iii. The Erosion Potential (Ep) in the receiving water channel will approximate 1, as determined by a Hydromodification Analysis Study and the equation presented in Attachment J of the MS4 Permit.

The MS4 Permit states projects will meet Hydromodification Control Criteria if "The...duration for the post-development condition **does** not exceed the pre-development condition for the 2-year, 24-hour rainfall event." The runoff duration (Tc) is generally associated with longer values resulting in lower concern for hydromodification impacts. Implementation of LID BMPs generally results in runoff not immediately (or not at all) discharging from the site, increasing the time of concentration. Thus, the interpretation presented herein is that Hydromodification Control Criteria would be met if the runoff duration for the post-development condition is **not less than** the pre-development condition for the 2-year, 24-hour rainfall event.

### Alternative Hydromodification Criteria

The requirement for Hydromodification Controls will be satisfied by implementing the hydromodification requirements in the County of Los Angeles Low Impact Development Manual (2009) for all projects disturbing an area greater than 1 acre within natural drainage systems.

### 3. Watershed Equivalence

Regardless of the methods through which applicants implement alternative compliance measures,

the subwatershed-wide (defined as draining to the same HUC-12 hydrologic area in the Basin Plan) result of all development must be at least the same level of water quality protection as would have been achieved if all projects utilizing these alternative compliance provisions had complied with the Integrated Water Quality/Flow Reduction/Resource Management Criteria, described herein.

#### 4. Annual Report

Annual Reports will be provided to the Regional Water Board to include a list of mitigation project descriptions and estimated pollutant and flow reduction analyses (compiled from design specifications submitted by project applicants, as approved. Within 4 years of the MS4 Permit adoption, the Annual Reports will include a comparison of the expected aggregate results of alternative compliance projects to the results that would otherwise have been achieved by retaining on site the SWQDv.

#### Implementation

*Permit §VI.D.7.d (LA)/§VII.J.5 (LB)*

#### **Local Ordinance Equivalence**

Alternative requirements in the local ordinances for the agencies of this WMP will provide equal or greater reduction in stormwater discharge pollutant loading and volume as would have been obtained through strict conformance with the Integrated Water Quality/Flow Reduction Resources Management Criteria, Alternative Compliance Measures for Technical Infeasibility, or Opportunity for Regional Groundwater Replenishment sections herein and, if applicable, the Hydromodification (Flow/Volume Duration) Control Criteria section herein.

#### **Project Coordination**

A process for effective approval of post-construction stormwater control measures will be developed to include:

- a. Detailed LID site design and BMP review including review of BMP sizing calculations, BMP pollutant removal performance, and municipal approval; and
- b. An established structure for communication and delineated authority between and among municipal departments that have jurisdiction over project review, plan approval, and project construction through memoranda of understanding or an equivalent agreement.

#### **Maintenance Agreement and Transfer**

Prior to issuing approval for final occupancy, the Cities will require that all New Development and Redevelopment projects subject to post-construction BMP requirements, with the exception of simple LID BMPs implemented on single family residences, provide an operation and maintenance plan, monitoring plan, where required, and verification of ongoing maintenance provisions for LID practices, Treatment Control BMPs, and Hydromodification Control BMPs including but not limited to: final map conditions, legal agreements, covenants, conditions or restrictions, CEQA mitigation requirements, conditional use permits, and/ or other legally binding maintenance agreements (see Attachments PLD-A and PLD-B for MCA and MCA Termination sample templates, respectively). Agencies will require maintenance records be kept on site.

Verification at a minimum will include the developer's signed statement accepting responsibility for maintenance until the responsibility is legally transferred; and either:

- a. A signed statement from the public entity assuming responsibility for BMP maintenance; or
- b. Written conditions in the sales or lease agreement, which require the property owner or tenant to assume responsibility for BMP maintenance and conduct a maintenance inspection at least once a year; or
- c. Written text in project covenants, conditions, and restrictions (CCRs) for residential properties assigning BMP maintenance responsibilities to the Home Owners Association; or
- d. Any other legally enforceable agreement or mechanism that assigns responsibility for the maintenance of BMPs.

All development projects subject to post-construction BMP requirements will provide a plan for the operation and maintenance of all structural and treatment controls. The plan will be submitted for examination of relevance to keeping the BMPs in proper working order. Where BMPs are transferred to agency for ownership and maintenance, the plan will also include all relevant costs for upkeep of BMPs in the transfer. Operation and Maintenance plans for private BMPs will be kept on-site for periodic review by agency inspectors.

A tracking system and an inspection and enforcement program will be maintained for New Development and Redevelopment post-construction stormwater as shown in Table PLC-3. Enforcement action will be taken per the established Progressive Enforcement Policy as appropriate based on the results of the inspection. See Section for requirements for the development and implementation of a Progressive Enforcement Policy (Appendix A-3-1\_PEP).

Table PLD-3: Tracking, Inspection, and Enforcement Program Components

Program	Description	Components	
GIS or other Electronic System	A GIS or other electronic system will be implemented for tracking projects that have been conditioned for post-construction BMPs.	<ul style="list-style-type: none"> <li>- Municipal Project ID</li> <li>- State WDID No.</li> <li>- Project Acreage</li> <li>- BMP Type and Description</li> <li>- BMP Location (coordinates)</li> <li>- Date of Maintenance Agreement</li> <li>- Date of Acceptance</li> </ul>	<ul style="list-style-type: none"> <li>- Maintenance Records</li> <li>- Inspection Date and Summary</li> <li>- Corrective Action</li> <li>- Date Certificate of Occupancy Issued</li> <li>- Replacement or Repair Date</li> </ul>
Inspections <sup>6</sup>	Inspect all development sites upon completion of construction and prior to the issuance of occupancy	Proper installation of: <ul style="list-style-type: none"> <li>- LID measures,</li> <li>- Structural BMPs,</li> </ul>	

<sup>6</sup> The inspection may be combined with other inspections provided it is conducted by trained personnel.

	certificates.	<ul style="list-style-type: none"> <li>- Treatment control BMPs, and</li> <li>- Hydromodification control BMPs.</li> </ul>
Operation and Maintenance <sup>7</sup>	Verify proper operation and maintenance of post-construction BMPs. Inspection at least once every 2 years after project completion.	<ul style="list-style-type: none"> <li>- Follow a Post-construction BMP Maintenance Inspection checklist (See Attachment PLD-C)</li> <li>- Assess operation and maintenance conditions relating to post-construction BMPs, including BMP repair, replacement, or re-vegetation.</li> </ul>

**Plan Certification**

Each SUSMP/LID Plan should contain proper certifications. The following approach is suggested for SUSMP/LID Plan submittals:

- Form signed by the property owner/applicant stating the category in which the project falls under to easily define the NPDES requirements (see Attachment PLD-D for Form PC sample template).
- Form signed by the property owner/applicant certifying that the BMPs will be implemented, monitored, and maintained per SUSMP/LID Plan requirements (see Attachment PLD-E for Form P1 sample template).
- Form signed and stamped by a California registered civil engineer stating the proposed structural BMPs and certifying the methods and requirements are in compliance with the MS4 Permit requirements (see Attachment PLD-F for Form P2 sample template).

<sup>7</sup> For post-construction BMPs operated and maintained by parties other than the agency in which the BMP(s) is located, the agency will require the other parties to document proper maintenance and operations.

# Development Construction Program

The Cities are required to develop, implement and enforce a construction program that includes the provisions listed in MS4 Permit §VI.D.8 (LB §VII.K). This document provides guidance to assist the Cities in implementing a construction program in compliance with the MS4 Permit.

## Objectives

*Permit §VI.D.8.a (LA)/§VII.K.1 (LB)*

The objectives of the construction program are to:

- Prevent illicit construction-related discharges of pollutants into the MS4 and receiving waters.
- Implement and maintain structural and non-structural BMPs to reduce pollutants in stormwater runoff from construction sites.
- Reduce construction site discharges of pollutants to the MS4 to the MEP.
- Prevent construction site discharges to the MS4 from causing or contributing to a violation of water quality standards.

## Erosion and Sediment Control Ordinance

*Permit §VI.D.8.b (LA)/ §VII.K.1 (LB)*

The construction program requires an established, enforceable erosion and sediment control ordinance for all construction sites that disturb soil.

## Applicability

*Permit §VI.D.8.c (LA)/ §VII.K.1.v (LB)*

The construction program addresses construction activity as defined in Table DC-1.

Table DC-1: Definitions

<b>Construction Activity</b>	
Definition	Any construction or demolition activity, clearing, grading, grubbing, or excavation or any other activity that results in land disturbance.
Examples	Grading, vegetation clearing, soil compaction, paving, repaving and linear underground/overhead projects (LUPs) that result in land disturbance.
Exclusions	Emergency construction required to immediately protect public health and safety, <i>routine maintenance</i> as defined below and agricultural activities.
<b>Routine Maintenance (construction program exclusion)</b>	
Definition	Projects required to maintain the integrity of structures, including but not limited to the following:
Examples	Maintaining the original line and grade, hydraulic capacity, or original purpose of the facility.
	Performing restoration work to preserve the original design grade, integrity and hydraulic capacity of flood control facilities.
	Performing road shoulder work, regrading dirt/gravel roadways/shoulders and cleaning out ditches.
	Update existing lines (includes replacing with new materials or pipe) and facilities to comply with applicable codes, standards, and regulations regardless if such projects result in increased capacity.
	Repair leaks
Exclusion	New lines (i.e. not associated with existing facilities and not part of a project to update or replace existing lines) or facilities constructed to comply with applicable codes, standards and regulations.

The greater part of the construction program is dedicated to construction sites that disturb one acre or more of soil (with the exception of agricultural activities). This coincides with the size threshold for coverage under the State Water Resources Control Board's NPDES General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activities. The program provisions exclusive to sites less than one acre are addressed first.

## Construction Sites Less than One Acre

*Permit §VI.D.8.d (LA)/§VII.K.1.vi (LB)*

### BMPs (< 1 acre)

Through the use of the erosion and sediment control ordinance and/or building permit, construction sites are required have in place an effective combination of erosion and sediment control BMPs from Table DC-2 to prevent erosion and sediment loss and the discharge of construction wastes.

Table DC-2: Applicable Set of BMPs for All Construction Sites

BMP Type	BMP
Erosion Controls	Scheduling
	Preservation of Existing Vegetation
Sediment Controls	Silt Fence
	Sand Bag Barrier
	Stabilized Construction Site Entrance/Exit
Nonstormwater Management	Water Conservation Practices
	Dewatering Operations
Waste Management	Material Delivery and Storage
	Stockpile Management
	Spill Prevention and Control
	Solid Waste Management
	Concrete Waste Management
	Sanitary/Septic Waste Management

### Inventory (< 1 acre)

All construction sites with soil disturbing activities that require a permit, regardless of size, are identified and stored in an inventory. Existing permit databases or other tracking systems may be used to file this information. The list of permitted sites is provided to the Regional Water Board upon request.

### Inspections (< 1 acre)

Construction sites are inspected on as needed based on the evaluation of the factors that are a threat to water quality. In evaluating the threat to water quality, the following factors are considered: soil erosion potential, site slope, project size and type, sensitivity of receiving water bodies, proximity to receiving water bodies, nonstormwater discharges, past record of noncompliance by the operators of the construction site and any water quality issues relevant to the particular MS4.

### Enforcement (< 1 acre)

The Progressive Enforcement Policy (MS4 Permit §VI.D.2) is implemented to ensure that construction sites are brought into compliance with the erosion and sediment control ordinance within a reasonable time period.

**Construction Sites One Acre or Greater**

Operators of public and private construction sites within a city’s jurisdiction are required to select, install, implement, and maintain BMPs that comply with the erosion and sediment control ordinance.

**Construction Site Inventory / Electronic Tracking System**

*Permit §VI.D.8.g (LA)/§VII.K.1.ix (LB)*

An electronic system is used to inventory all issued grading permits, encroachment permits, demolition permits, building permits, or construction permits (and any other municipal authorization to move soil and/ or construct or destruct that involves land disturbance). A database management system or GIS system is recommended. This inventory is continuously updated as new sites are permitted and sites are completed. The inventory / tracking system contains at a minimum the items listed in Table DC-3.

Table DC-3: Inventory Information for Constructions Sites

Information Type		Information
General	Name	Project Name
	Location	Site address and/or latitude and longitude coordinates
		Receiving water
	Contact	Names of owner and contractor
		Mailing addresses of owner and contractor
		Phone numbers of owner and contractor
		Emails (if available) of owner and contractor
Status	Start and end dates	
	Permit approval date and anticipated completion date	
	Erosion and Sediment Control Plan (ESCP) approval date	
	Status of NOI submittal and CGP coverage	
	Current construction phase (where feasible)	
Size	Size of project and area of disturbance	
Water quality	Proximity to waterbodies listed as impaired <sup>1</sup> by sediment related pollutants	
	Proximity to waterbodies for which a sediment-related TMDL has been adopted and approved by USEPA	
	Status as a significant threat to water quality (based on a consideration of factors listed in Appendix 1 to the CGP)	
Inspection	Inspection frequency	
Post construction	List of post-construction structural BMPs subject to O&M requirements	

**Construction Plan Review and Approval Procedures**

*Permit §VI.D.8.h (LA)/§VII.K.1.x (LB)*

Plan review procedures are developed and implemented such that the following minimum requirements are met:

- Prior to issuing a grading or building permit, each operator of a construction activity within the city’s jurisdiction of which the project is located is required to prepare and submit an ESCP prior to the disturbance of land for review and written approval. The construction site operator is prohibited from commencing construction activity prior to receipt of written approval by the city of which the project is located. An ESCP is not approved unless it contains appropriate site-

<sup>1</sup> CWA §303(d) listed or subject to a TMDL

specific construction site BMPs that meet the minimum requirements of the erosion and sediment control ordinance.

- ESCPs must include the elements of a Storm Water Pollution Prevention Plan (SWPPP). SWPPPs prepared in accordance with the requirements of the Construction General Permit can be accepted as ESCPs.
- At a minimum, the ESCP must address the following elements:
  - Methods to minimize the footprint of the disturbed area and to prevent soil compaction outside of the disturbed area.
  - Methods used to protect native vegetation and trees.
  - Sediment/Erosion Control.
  - Controls to prevent tracking on and off the site.
  - Nonstormwater controls (e.g., vehicle washing, dewatering, etc.).
  - Materials Management (delivery and storage).
  - Spill Prevention and Control.
  - Waste Management (e.g., concrete washout/waste management; sanitary waste management).
  - Identification of site Risk Level as identified per the requirements in Appendix 1 of the Construction General Permit.
- The ESCP must include the rationale for the selection and design of the proposed BMPs, including quantifying the expected soil loss from different BMPs.
- The ESCP must be developed and certified by a Qualified SWPPP Developer (QSD).
- All structural BMPs must be designed by a licensed California Engineer.
- The landowner or the landowner's agent must sign a statement on the ESCP as follows (see Attachment DC-A for sample OC-1 template):

*"I certify that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is true, accurate, and complete. I am aware that submitting false and/ or inaccurate information, failing to update the ESCP to reflect current conditions, or failing to properly and/ or adequately implement the ESCP may result in revocation of grading and/ or other permits or other sanctions provided by law."*

- Prior to issuing a grading or building permit, the city of which the project is located verifies that the construction site operators have existing coverage under applicable permits, including, but not limited to the State Water Board's Construction General Permit, and State Water Board 401 Water Quality Certification.
- A checklist is used to conduct and document review of each ESCP (see Attachment DC-B for the ESCP Checklist sample template).

### **BMP Implementation Level**

*Permit §VI.D.8.i (LA)/§VII.K.1.xi (LB)*

The Cities will implement technical standards for the selection, installation and maintenance of construction BMPs for all construction sites within its jurisdiction.

The BMP technical standards require:

- The use of BMPs that are tailored to the risks posed by the project. Sites are ranked from Low Risk (Risk 1) to High Risk (Risk 3). Project risks are calculated based on the potential for erosion from the site and the sensitivity of the receiving water body. Receiving water bodies that are listed on the Clean Water Act (CWA) Section 303(d) list for sediment or siltation are considered High Risk. Likewise, water bodies with designated beneficial uses of SPWN, COLD, and MIGR are also considered High Risk. The combined (sediment/receiving water) site risk is calculated using the methods provided in Appendix 1 of the Construction General Permit. At a minimum, the BMP technical standards include requirements for High Risk sites as defined in Table DC-7.
- The use of BMPs for all construction sites, sites equal or greater to 1 acre, and for paving projects per Table DC-6 and Table DC-8.
- Detailed installation designs and cut sheets for use within ESCPs.
- Maintenance expectations for each BMP, or category of BMPs, as appropriate.

Permittees are encouraged to adopt respective BMPs from latest versions of the California BMP Handbook, Construction or Caltrans Stormwater Quality Handbooks, Construction Site Best Management Practices (BMPs) Manual and addenda. Alternatively, Permittees are authorized to develop or adopt equivalent BMP standards consistent for Southern California and for the range of activities presented in Tables DC-5 through DC-8.

The local BMP technical standards are readily available to the development community and are clearly referenced within the Cities' stormwater or development services websites, ordinances, permit approval processes and/or ESCP review forms. The local BMP technical standards are also readily available to the Regional Water Board upon request.

Local BMP technical standards are available for the BMPs listed in Tables DC-5 through DC-8.

Table DC-4: Minimum Set of BMPs for All Construction Sites

BMP Type	BMP
Erosion Controls	Scheduling
	Preservation of Existing Vegetation
Sediment Controls	Silt Fence
	Sand Bag Barrier
	Stabilized Construction Site Entrance/Exit
Nonstormwater Management	Water Conservation Practices
	Dewatering Operations
Waste Management	Material Delivery and Storage
	Stockpile Management
	Spill Prevention and Control
	Solid Waste Management
	Concrete Waste Management
	Sanitary/Septic Waste Management

Table DC-5: Additional BMPs Applicable to Construction Sites Disturbing 1 Acre or More

BMP Type	BMP
Erosion Controls	Hydraulic Mulch
	Hydroseeding
	Soil Binders
	Straw Mulch
	Geotextiles and Mats
	Wood Mulching
Sediment Controls	Fiber Rolls
	Gravel Bag Berm
	Street Sweeping and/ or Vacuum
	Storm Drain Inlet Protection
	Scheduling
Additional Controls	Check Dam
	Wind Erosion Controls
	Stabilized Construction Entrance/ Exit
	Stabilized Construction Roadway
Non-Storm Management	Entrance/ Exit Tire Wash
	Vehicle and Equipment Washing
	Vehicle and Equipment Fueling
Waste Management	Vehicle and Equipment Maintenance
	Material Delivery and Storage
	Spill Prevention and Control

Table DC-6: Additional Enhanced BMPs for High Risk Sites

BMP Type	BMP
Erosion Controls	Hydraulic Mulch
	Hydroseeding
	Soil Binders
	Straw Mulch
	Geotextiles and Mats
	Wood Mulching
	Slope Drains
Sediment Controls	Silt Fence
	Fiber Rolls
	Sediment Basin
	Check Dam
	Gravel Bag Berm
	Street Sweeping and/or Vacuum
	Sand Bag Barrier
	Storm Drain Inlet Protection
Additional Controls	Wind Erosion Controls
	Stabilized Construction Entrance/Exit
	Stabilized Construction Roadway
	Entrance/Exit Tire Wash
	Advanced Treatment Systems*
Nonstormwater Management	Water Conservation Practices
	Dewatering Operations (Ground water dewatering only under NPDES Permit No. CAG994004)
	Vehicle and Equipment Washing
	Vehicle and Equipment Fueling
	Vehicle and Equipment Maintenance
Waste Management	Material Delivery and Storage
	Stockpile Management
	Spill Prevention and Control
	Solid Waste Management

\*Applies to public roadway projects.

Table DC-7: Minimum Required BMPs for Roadway Paving or Repair Operation (For Private or Public Projects)

#	BMP
1.	Restrict paving and repaving activity to exclude periods of rainfall or predicted rainfall unless required by emergency conditions.
2.	Install gravel bags and filter fabric or other equivalent inlet protection at all susceptible storm drain inlets and at manholes to prevent spills of paving products and tack coat.
3.	Prevent the discharge of release agents including soybean oil, other oils, or diesel to the stormwater drainage system or receiving waters.
4.	Minimize non stormwater runoff from water use for the roller and for evaporative cooling of the asphalt.
5.	Clean equipment over absorbent pads, drip pans, plastic sheeting or other material to capture all spillage and dispose of properly.
6.	Collect liquid waste in a container, with a secure lid, for transport to a maintenance facility to be reused, recycled or disposed of properly.
7.	Collect solid waste by vacuuming or sweeping and securing in an appropriate container for transport to a maintenance facility to be reused, recycled or disposed of properly.
8.	Cover the "cold-mix" asphalt (i.e., pre-mixed aggregate and asphalt binder) with protective sheeting during a rainstorm.
9.	Cover loads with tarp before haul-off to a storage site, and do not overload trucks.
10.	Minimize airborne dust by using water spray or other approved dust suppressant during grinding.
11.	Avoid stockpiling soil, sand, sediment, asphalt material and asphalt grindings materials or rubble in or near stormwater drainage system or receiving waters.
12.	Protect stockpiles with a cover or sediment barriers during a rain.

### Construction Site Inspection

*Permit §VI.D.8.j (LA)/§VII.K.1.xii (LB)*

The Cities' legal authority is used to implement procedures for inspecting public and private construction sites. The inspection procedures are implemented as follows:

#### Inspection Frequency

- Inspect the public and private construction sites as specified in Table DC-8.
- All phases of construction are inspected as follows:
  - Prior to Land Disturbance – Prior to allowing an operator to commence land disturbance, each Permittee shall perform an inspection to ensure all necessary erosion and sediment structural and non-structural BMP materials and procedures are available per the erosion and sediment control plan.
  - During Active Construction, including Land Development<sup>2</sup> and Vertical Construction<sup>3</sup> – In accordance with the frequencies specified in Table DC-8, inspections are performed to ensure all necessary erosion and sediment structural and non-structural BMP materials and procedures are available per the erosion and sediment control plan throughout the construction process.
  - Final Landscaping / Site Stabilization<sup>4</sup> – At the conclusion of the project and as a condition of approving and/or issuing a Certificate of Occupancy, the constructed site is inspected to ensure that all graded areas have reached final stabilization and that all

<sup>2</sup> Activities include cuts and fills, rough and finished grading; alluvium removals; canyon cleanouts; rock undercuts; keyway excavations; stockpiling of select material for capping operations; and excavation and street paving, lot grading, curbs, gutters and sidewalks, public utilities, public water facilities including fire hydrants, public sanitary sewer systems, storm sewer system and/or other drainage improvement.

<sup>3</sup> The build out of structures from foundations to roofing, including rough landscaping.

<sup>4</sup> All soil disturbing activities at each individual parcel within the site have been completed.

trash, debris, and construction materials, and temporary erosion and sediment BMPs are removed.

- Based on the required frequencies above, each construction project is inspected a minimum of three times.

Table DC-8: Inspection Frequencies for Sites One Acre or Greater

Site	Inspection Frequency Shall Occur
All sites 1 acre or larger that discharge to a tributary listed by the state as an impaired water for sediment or turbidity under the CWA §303(d)	(1) when two or more consecutive days with greater than 50% chance of rainfall are predicted by NOAA <sup>5</sup> , (2) within 48 hours of a ½-inch rain event and at (3) least once every two weeks
Other sites 1 acre or more determined to be a significant threat to water quality <sup>6</sup>	
All other construction sites with 1 acre or more of soil disturbance not meeting the criteria above	At least monthly

**Inspection Standard Operating Procedures**

Standard operating procedures are implemented, and revised as necessary, that identify the inspection procedures followed by the Cities’ inspectors (see Attachment DC-C for suggested standard operating procedures). Inspections of construction sites – and the standard operating procedures – include, but are not limited to:

1. Verification of active coverage under the Construction General Permit for sites disturbing 1 acre or more, or that are part of a planned development that will disturb 1 acre or more and a process for referring non-filers to the Regional Water Board.
2. Review of the applicable ESCP and inspection of the construction site to determine whether all BMPs have been selected, installed, implemented, and maintained according to the approved plan and subsequent approved revisions (see Attachment DC-B for the ESCP Checklist sample template).
3. Assessment of the appropriateness of the planned and installed BMPs and their effectiveness.
4. Visual observation and record keeping of nonstormwater discharges, potential illicit discharges and connections, and potential discharge of pollutants in stormwater runoff.
5. Development of a written or electronic inspection report generated from an inspection checklist used in the field (see Attachment DC-D and DC-E for the Large Site and Small Site<sup>7</sup> Inspection Forms, respectively).
6. Tracking of the number of inspections for the inventoried construction sites throughout the reporting period to verify that the sites are inspected at the minimum frequencies listed in Table DC-8.

**Enforcement**

*Permit §VI.D.8.k (LA)/§VII.K.1.xiii (LB)*

The Progressive Enforcement Policy is implemented to ensure that construction sites are brought into compliance with all stormwater requirements within a reasonable time period.

<sup>5</sup> www.srh.noaa.gov/forecast

<sup>6</sup> In evaluating the threat to water quality, the following factors shall be considered: soil erosion potential; site slope; project size and type; sensitivity of receiving water bodies; proximity to receiving water bodies; nonstormwater discharges; past record of non-compliance by the operators of the construction site; and any water quality issues relevant to the particular MS4.

<sup>7</sup> A “large site” refers to a site greater than or equal to 1 acre while a “small site” refers to a site less than one acre.

**Permittee Staff Training***Permit §VI.D.8.l(LA)/§VII.K.1.xiv(LB)*

Staff whose primary job duties are related to implementing the construction stormwater program are adequately trained.

The Cities may conduct in-house training or contract with consultants. Training is provided to the following staff positions of the MS4:

- Plan Reviewers and Permitting Staff – Staff and consultants are trained as qualified individuals, knowledgeable in the technical review of local erosion and sediment control ordinance, local BMP technical standards, ESCP requirements, and the key objectives of the State Water Board QSD program. The training is provided either internally to staff or staff is required to obtain QSD certification.
- Erosion Sediment Control/Stormwater Inspectors – Inspectors are either 1) knowledgeable in inspection procedures consistent with the State Water Board sponsored program QSD, 2) a Qualified SWPPP Practitioner (QSP) or 3) a designated person on staff trained in the key objectives of the QSD/QSP programs supervises inspection operations. The training is provided either provided internally to staff or staff is required to obtain QSD/QSP certification. Each inspector is knowledgeable of the local BMP technical standards and ESCP requirements.
- Third-Party Plan Reviewers, Permitting Staff, and Inspectors – If outside parties are utilized to conduct inspections and/or review plans, these staff are trained per the requirements listed above. Outside contractors can self-certify, providing they certify they have received all applicable training required in MS4 Permit §VI.D.8 and have documentation to that effect.

# Public Agency Activities Program

Each participating city is required to develop and implement a program for public agency facilities and activities that includes the requirements listed in MS4 Permit §VI.D.9 (LB §VII.L). This document provides guidance to assist the Cities in implementing a public agency activities program in compliance with the MS4 Permit.

## Objectives

*Permit §VI.D.9.a (LA)/§VII.L.1 (LB)*

The objectives of the Public Agency Activities program are to:

- Minimize stormwater pollution impacts from Permittee-owned or operated facilities.
- Minimize stormwater pollution impacts from public agency activities.
- Identify opportunities to reduce stormwater pollution impacts from areas of existing development.

MS4 Permit requirements for Public Agency Facilities and Activities consist of the following components which will be discussed in more detail in the sections below:

- Public Construction Activities Management
- Public Facility Inventory
- Inventory of Existing Development for Retrofitting Opportunities
- Public Facility and Activity Management
- Vehicle and Equipment Wash Areas
- Landscape, Park, and Recreational Facilities Management
- Storm Drain Operation and Maintenance
- Streets, Roads, and Parking Facilities Maintenance
- Emergency Procedures
- Municipal Employee and Contractor Training

## 1. Public Construction Activities Management

*Permit §VI.D.9.b (LA)/§VII.L.2 (LB)*

Each participating city is required to develop and implement a Development Construction Program that meets the requirements the Development Construction Section of this WMP, and Part VI.D.8 of the LA MS4 Permit at municipally owned or operated (i.e., public or Permittee sponsored) construction projects. In addition, each participating city is required to develop and implement a Planning and Land Development Program that meets the requirements in the Planning and Land Development Section of this WMP, and the MS4 Permit at municipally owned or operated (i.e., public or Permittee sponsored) construction projects.

## 2. Public Facility Inventory

*Permit §VI.D.9.c (LA)/§VII.L.3 (LB)*

The Public Agency Activities Program requires the maintenance of an inventory of all Permittee-owned or operated (i.e., public) facilities that are potential sources of stormwater pollution. The incorporation of facility information into a GIS is recommended. Sources that are tracked include but are not limited to the following:

- Animal control facilities
- Chemical storage facilities
- Composting facilities

- Equipment storage and maintenance facilities (including landscape maintenance-related operations)
- Fueling or fuel storage facilities (including municipal airports)
- Hazardous waste disposal facilities
- Hazardous waste handling and transfer facilities
- Incinerators
- Landfills
- Materials storage yards
- Pesticide storage facilities
- Fire stations
- Public restrooms
- Public parking lots
- Public golf courses
- Public swimming pools
- Public parks
- Public works yards
- Public marinas
- Recycling facilities
- Solid waste handling and transfer facilities
- Vehicle storage and maintenance yards
- Stormwater management facilities (e.g., detention basins)
- All other Permittee-owned or operated facilities or activities that are determined to contribute a substantial pollutant load to the MS4.

The following minimum fields of information are included in the inventory for each Permittee-owned or operated facility:

- Name of facility
- Name of facility manager and contact information
- Address of facility (physical and mailing)
- A narrative description of activities performed and potential pollution sources.
- Coverage under the Industrial General Permit or other individual or general NPDES permits or any applicable waiver issued by the Regional or State Water Board pertaining to stormwater discharges.

The inventory is updated at least once during the 5-year MS4 Permit term. The update are accomplished through collection of new information obtained through field activities or through other readily available inter and intra-agency informational databases (e.g., property management, land-use approvals, accounting and depreciation ledger account, and similar information).

### **3. Inventory of Existing Development for Retrofit Opportunities**

*Permit §VI.D.9.d (LA)/§VII.L.4 (LB)*

The Public Agency Activities Program requires the development of an inventory of retrofitting opportunities. Retrofit opportunities are identified within the public right-of-way or in coordination with a TMDL implementation plan(s). The goals of the existing development retrofitting inventory are to address the impacts of existing development through regional or sub-regional retrofit projects that

reduce the discharges of stormwater pollutants into the MS4 and prevent discharges from the MS4 from causing or contributing to a violation of water quality standards as defined in the MS4 Permit.

Existing areas of development are screened to identify candidate areas for retrofitting using watershed models or other screening level tools. The areas of existing development identified during the screening process are then evaluated and ranked to prioritize retrofitting candidates. Criteria for this evaluation may include, but is not limited to the following:

- Feasibility, including general private and public land availability;
- Cost effectiveness;
- Pollutant removal effectiveness;
- Tributary area potentially treated;
- Maintenance requirements;
- Landowner cooperation;
- Neighborhood acceptance;
- Aesthetic qualities;
- Efficacy at addressing concern; and
- Potential improvements to public health and safety.

The results of this evaluation are considered in the following programs:

- Highly feasible projects expected to benefit water quality are given a high priority to implement source control and treatment control BMPs in the WMP.
- High priority retrofit projects are considered as candidates for off-site mitigation projects per LA MS4 Permit §VI.D.7.c.iii(4)(d) (LB §VII.J.4.iii(4)).
- Where feasible, the existing development retrofit program is coordinated with flood control projects and other infrastructure improvement programs per LA MS4 Permit §VI.D.9.e.ii(2) (LB §VII.L.5.ii(2)).

Site specific retrofit projects are encouraged through cooperation with private landowners. The following practices are considered in cooperating with private landowners to retrofit existing development:

- Demonstration retrofit projects;
- Retrofits on public land and easements that treat runoff from private developments;
- Education and outreach;
- Subsidies for retrofit projects;
- Requiring retrofit projects as enforcement, mitigation or ordinance compliance;
- Public and private partnerships;
- Fees for existing discharges to the MS4 and reduction of fees for retrofit implementation.

#### **4. Public Facility and Activity Management**

*Permit §VI.D.9.e (LA)/§VII.L.5 (LB)*

##### **4.1. Industrial General Permitted Facilities**

*Permit §VI.D.9.e.i & §VI.D.9.e.v (LA)/§VII.L.5.i (LB)*

All Permittee owned or operated facilities where industrial activities are conducted that require coverage are required to obtain coverage under the Industrial General Permit by submitting a Notice of Intent (NOI) to the State Water Resources Control Board (State Board) and preparing a Stormwater

Pollution Prevention Plan (SWPPP). Facilities that may require coverage are listed by category in 40 Code of Federal Regulations (CFR) Section 122.26(b)(14), and include:

- Facilities subject to stormwater effluent limitations guidelines, new source performance standards, or toxic pollutant effluent standards (40 CFR Subchapter N)
- Manufacturing facilities
- Mining and oil and gas facilities
- Hazardous waste treatment, storage, or disposal facilities
- Landfills, land application sites, and open dumps that receive industrial waste
- Recycling facilities
- Steam electric generating facilities
- Transportation facilities
- Sewage treatment plants
- Certain facilities if materials are exposed to stormwater

Municipally owned or operated facilities that have obtained coverage under the IGP implement and maintain BMPs consistent with the associated SWPPP, and are therefore not required to implement and maintain the activity specific BMPs as described in the sections below.

#### **4.2. Flood Management Projects**

*Permit §VI.D.9.e.ii (LA)/§VII.L.5.ii (LB)*

The following measures are implemented for municipally owned or operated flood management projects:

- Procedures are developed to assess the impacts of flood management projects on the water quality of receiving water bodies;
- Existing structural flood control facilities area evaluated to determine if retrofitting the facility to provide additional pollutant removal from stormwater is feasible.

#### **4.3. Contracted Public Agency Activities**

*Permit §VI.D.9.e.iv (LA)/§VII.L.5.iv (LB)*

Any contractors hired to conduct Public Agency Activities, including, but not limited to the following must be contractually obligated to implement and maintain the activity specific BMPs outlined in the sections below:

- Storm and/or sanitary sewer system inspection and repair,
- Street sweeping,
- Trash pick-up and disposal, and
- Street and right-of-way construction and repair

It is the responsibility of each Permittee to ensure that these BMPs are being properly implemented and maintained through oversight of contracted activities. Example contractor/lessor contract language is provided in attachment PA-A.

#### 4.4. BMPS for Municipal Activities

*Permit §VI.D.9.e.iii & Permit §VI.D.9.e.vi (LA)/§VII.L.5.iii & VII.L.5.vi (LB)*

Municipal maintenance and field staff are the ones responsible for implementing effective source control BMPs<sup>1</sup>, such as those described in Table PA-1 (or an equivalent set of BMPs) when such activities occur at municipally owned or operated facilities and field operations (i.e. project sites). These sites include, but are not limited to the facility types identified in the Public Facility Inventory, and at any area that includes the activities described in Table PA-1, or that have the potential to discharge pollutants in stormwater. The Caltrans Stormwater Quality Handbook Maintenance Staff Guide (Caltrans Handbook)<sup>2</sup> is an additional resource that describes BMPs to prevent the stormwater-related pollutants most likely to come from common maintenance facility operations and field activities. It provides a straightforward working-level approach to implementing BMPs for common maintenance activities by categorizing these activities into Families, and associating each Family with certain types of BMPs in Activity Cut Sheets. The activities described in Sections 5-10 below are representative of typical municipal operations, and correspond to the activities and BMPs listed in Table PA-1. Where appropriate, each section will identify the appropriate Maintenance Activity Family and corresponding Caltrans Activity Cut Sheets from this table for ease of reference.

Although Table PA-1 and the CalTrans Handbook are excellent references for selecting BMPs for some of the most common municipal activities, they may not represent a comprehensive inventory of activities encountered by maintenance staff and field personnel. Likewise, for those BMPs that are not adequately protective of water quality standards, additional site-specific BMPS may be needed. For example, the implementation of additional BMPs is required where stormwater from the storm drain system discharges to a water body subject to a TMDL, a Clean Water Act §303(d) listed water body, or a significant ecological area (SEA). Attachment PA-B contains a map of SEAs in LA County and Attachment K of the LA MS4 Permit contains a matrix of Permittees and TMDLs.

---

<sup>1</sup> BMP is defined by the California Stormwater Quality Association as “any program, technology, process, siting criteria, operating method, measure, or device which controls, prevents, removes, or reduces pollution”. Source Control BMPs are operational practices that prevent pollution by reducing potential pollutants at the source. They typically do not require maintenance or construction, and may consist of programmatic controls such as street sweeping. Treatment Control BMPs are methods of treatment to remove pollutants from stormwater, and can include constructed treatment devices such as an infiltration basin.

<sup>2</sup> The handbook is available at

[http://www.dot.ca.gov/hq/env/stormwater/special/newsetup/pdfs/management\\_ar\\_rwp/CTSW-RT-02-057.pdf](http://www.dot.ca.gov/hq/env/stormwater/special/newsetup/pdfs/management_ar_rwp/CTSW-RT-02-057.pdf) and may also be found by entering the words “Caltrans Stormwater Quality Handbook Maintenance Staff Guide” in a web search engine.

Table PA-1: General and Activity Specific BMPs and Their Associated Caltrans Handbook Activity Cut Sheet

Maintenance Activity Family	BMP	Caltrans Activity Cut Sheet Number
<b>General BMPs</b>	Scheduling and Planning	B-4
	Spill Prevention and Control	
	Sanitary/Septic Waste Management	
	Material Use	
	Safer Alternative Products	
	Vehicle/Equipment Cleaning, Fueling and Maintenance	
	Illicit Connection Detection, Reporting and Removal	
	Illegal Spill Discharge Control	
<b>Flexible Pavement</b>	Maintenance Facility Housekeeping Practices	
	Asphalt Cement Crack and Joint Grinding/ Sealing	B-9
	Asphalt Paving	B-10
	Structural Pavement Failure (Digouts) Grinding and Paving	B-11
	Emergency Pothole Repairs	B-13
<b>Rigid Pavement</b>	Sealing Operations	B-14
	Portland Cement Crack and Joint Sealing	B-15
	Mudjacking and Drilling	B-16
<b>Slope/ Drains/ Vegetation</b>	Concrete Slab and Spall Repair	B-17
	Shoulder Grading	B-19
	Nonlandscaped Chemical Vegetation Control	B-21
	Nonlandscaped Mechanical Vegetation Control/Mowing	B-23
	Nonlandscaped Tree and Shrub Pruning, Removal	B-24
	Fence Repair	B-25
	Drainage Ditch and Channel Maintenance	B-26
	Drain and Culvert Maintenance	B-28
<b>Litter/ Debris/ Graffiti</b>	Curb and Sidewalk Repair	B-30
	Sweeping Operations	B-32
	Litter and Debris Removal	B-33
	Emergency Response and Cleanup Practices	B-34
<b>Landscaping</b>	Graffiti Removal	B-36
	Chemical Vegetation Control	B-37
	Manual Vegetation Control	B-39
	Landscaped Mechanical Vegetation Control/ Mowing	B-40
	Landscaped Tree and Shrub Pruning, Removal	B-41
	Irrigation Line Repairs	B-42
<b>Environmental</b>	Irrigation (Watering), Potable and Nonpotable	B-43
	Storm Drain Stenciling	B-44
	Roadside Slope Inspection	B-45
	Roadside Stabilization	B-46
	Stormwater Treatment Devices	B-48
<b>Public Facilities</b>	Traction Sand Trap Devices	B-49
	Public Facilities	B-50
<b>Bridges</b>	Welding and Grinding	B-52
	Sandblasting, Wet Blast with Sand Injection, Hydroblasting	B-54
	Painting	B-56
	Bridge Repairs	B-57
<b>Other Structures</b>	Pump Station Cleaning	B-59
	Tube and Tunnel Maintenance and Repair	B-61
	Tow Truck Operations	B-63
	Toll Booth Lane Scrubbing Operations	B-64
<b>Electrical &amp;</b>	Sawcutting for Loop Installation	B-65
<b>Traffic Guidance</b>	Thermoplastic Striping and Marking	B-67
	Paint Striping and Marking	B-68
	Raised/ Recessed Pavement Marker Application/Removal	B-70

	Sign Repair and Maintenance	B-71
	Median Barrier and Guard Rail Repair	B-73
	Emergency Vehicle Energy Attenuation Repair	B-75
<b>Storm Maintenance</b>	Minor Slides and Slipouts Cleanup/ Repair	B-78
<b>Management and Support</b>	Building and Grounds Maintenance	B-80
	Storage of Hazardous Materials (Working Stock)	B-82
	Material Storage Control (Hazardous Waste)	B-84
	Outdoor Storage of Raw Materials	B-85
	Vehicle and Equipment Fueling	B-86
	Vehicle and Equipment Cleaning	B-87
	Vehicle and Equipment Maintenance and Repair	B-88
	Aboveground and Underground Tank Leak and Spill Control	B-90

**5. Vehicle and Equipment Wash Areas**

*Permit §VI.D.9.f (LA)/§VII.L.6 (LB)*

*This section corresponds to Maintenance Activity Family Management and Support and corresponding Caltrans Activity Cut Sheet B-87.*

Vehicle and equipment cleaning at a municipal facility may introduce a number of potential pollutants into the storm drain system. Municipal maintenance and field staff are responsible for implementing and maintaining the activity specific BMPs listed in Table PA-1 for all fixed vehicle and equipment washing; including fire fighting and emergency response vehicles. In addition, maintenance and field staff are responsible for preventing discharges of wash water from entering the storm drain system. Table PA-2 shows the potential pollutants associated with vehicle and equipment cleaning.

Table PA-2: Potential Pollutants Generated from Cleaning Activities

Activity	Potential Pollutants					
Vehicle and Equipment Cleaning	Sediment	Nutrients	Trash	Metals	Oil & Grease	Organics

Discharges of wash waters to the storm drain system are prevented by implementing the following measures at existing facilities with vehicle or equipment wash areas:

- Wash water is self-contained and hauled away for proper disposal offsite.
- Wash areas are equipped with a clarifier, or an alternative pre-treatment device, and water is plumbed to the sanitary sewer in accordance with applicable waste water provider regulations.
- Wastewater from all new vehicle and equipment wash facilities, or redeveloped or replaced existing facilities is prevented from discharging to the MS4 by equipping the facility with a clarifier, or an alternative pre-treatment device, and plumbing water to the sanitary sewer in accordance with applicable waste water provider regulations, or by self-containing all water wash water and hauling to a point of legal disposal.

**6. Landscape, Park, and Recreational Facilities Management**

*Permit §VI.D.9.g (LA)/ §VII.L.7 (LB)*

*This section corresponds to multiple Activity Cut Sheets within the Slope/Drains/Vegetation, Landscape, Environmental, and Management and Support Families.*

Maintenance practices at parks and recreational facilities generally include fertilizer and pesticide applications, vegetation maintenance and disposal, irrigation, swimming pool chemical maintenance and draining, and trash and debris management. All of these maintenance practices have the potential to contribute pollutants to the storm drain system. Municipal maintenance and field staff are responsible for implementing and maintaining the activity specific BMPs listed in Table PA-1 for all public right-of-

ways, flood control facilities and open channels, lakes and reservoirs, and landscape, park, and recreational facilities and activities. Table PA-3 shows the potential pollutants associated with recreational facilities..

Table PA-3: Potential Pollutants Generated from Recreational Facilities

Activity	Potential Pollutants				
Vehicle and Equipment Cleaning	Sediment	Nutrients	Trash	Bacteria	Pesticides

**6.1 Model Integrated Pest Management Program**

*Permit §VI.D.9.g.ii & VI.D.9.g.iii (LA)/§VII.L.7.ii & VII.L.7.iii (LB)*

An IPM policy is in place to minimize pesticide and fertilizer use, and encourage the use of IPM techniques for Public Agency facilities and activities. The attached IPM Program template (Attachment PA-C), adapted from the Orange County Drainage Area Management Plan (DAMP) IPM Policy developed by the University of California, Division of Agriculture and Natural Resources, provides an example of an effective IPM program. This IPM Program template is based on regulations, management guidelines, and research-based recommendations established by federal, state and local agencies and universities with particular expertise in pest management.

As part of the IPM policy, a commitment and schedule to reduce the use of pesticides that cause impairment t of surface waters is implemented through the following procedures:

- An inventory of all pesticides used by municipal departments, divisions, and operational units is prepared and updated annually.
- Pesticides used by staff and hired contractors are quantified.
- The use of IPM alternatives is demonstrated, where feasible, to reduce pesticide use.

Municipal maintenance and field staff applying pesticides are certified in the appropriate category by the California Department of Pesticide Regulation, or are under the direct supervision of a pesticide applicator certified in the appropriate category.

**7. Storm Drain Operation and Maintenance**

*Permit §VI.D.9.h (LA)/ §VII.L.8 (LB)*

*This section corresponds to the Litter/Debris/Graffiti Family: Litter and Debris Removal Cut Sheet, pg. B-33, and the Environmental Family: Storm Drain Stenciling Cut Sheet, pg. B-44*

The storm drain system functions primarily to collect and convey surface runoff to receiving waters during storms in order to prevent flooding. It is a common municipal activity to maintain the storm drain system so that it functions hydraulically as intended during storms. Municipal maintenance and field staff are responsible for implementing and maintaining the activity specific BMPs listed in Table PA-1 for storm drain operation and maintenance, and ensuring that all material removed from the MS4 does not reenter the system by dewatering solid material in a contained area and disposing of liquid material in accordance with any of the following measures:

- Self-containing and hauling off for legal disposal; or
- Applying to the land without runoff; or
- Equipping with a clarifier or alternative pre-treatment device and plumbing to the sanitary sewer in accordance with applicable waste water provider regulations.

Table PA-4 shows potential pollutants generated during storm drain operation and maintenance.

Table PA-4: Potential Pollutants Generated from Storm Drain Operation and Maintenance

Activity	Potential Pollutants								
	Sediment	Nutrients	Trash	Metals	Bacteria	Oil & Grease	Organics	Pesticides	Oxygen Demanding Substances
Inspection and Cleaning of Conveyance Structures	X	X	X		X		X		X
Controlling Illicit Connections and Discharges	X	X	X	X	X	X	X	X	X
Controlling Illegal Dumping	X	X	X	X	X	X	X	X	X
Maintenance of Inlet and Outlet Structures	X		X		X	X			

**7.1 Catch Basin Cleaning**

*Permit §VI.D.9.h.iii (LA)/ §VII.L.8.iii (LB)*

There is no preferred method for cleaning catch basins as long as the method used is successful in removing accumulated sediment and debris. The methods used are determined in the field with the goal of minimizing the amount of escaped material, and preventing this material from entering the storm drain system. A template catch basin cleaning log is provided in Attachment PA-D.

**7.1.1 Catch Basins Cleaning in Areas not Subject to a Trash TMDL**

In areas that are not subject to a trash TMDL, catch basin inlets are prioritized based on the amount of trash generated, and inspected according to the schedule in Table PA-5.

Table PA-5: Inspection Frequencies for Catch Basin Inlets

Trash Generating Frequency	Priority	Inspection Frequency
Consistently generates the highest volumes of trash and/or debris	A	A minimum of three times during the wet season (October-April) and once during the dry season every year
Consistently generates moderate volumes of trash and/or debris	B	A minimum of once during the wet season and once during the dry season every year
Generates low volumes of trash and/or debris	C	A minimum of once per year

An inventory of catch basins is maintained and updated regularly. This inventory includes the following components:

- GPS coordinates of each catch basin
- Priorities for inspection
- Rationale or data to support catch basin priority designations
- Inspection and cleaning records

Catch basins are cleaned as necessary based on the inspections conducted. At a minimum, catch basins determined to be at least 25% full of trash are cleaned out.

### **7.1.2 Catch Basin Cleaning in Areas Subject to a Trash TMDL**

In areas subject to a Trash TMDL, all applicable provisions of LA MS4 Permit Section VI.E (LB Part Part VIII) in conformance with the appropriate TMDL implementation schedule, are implemented. This includes an effective combination of full capture, partial capture, institutional controls, or minimum frequency of assessment and collection as described in LA MS4 Permit Section VI.E (LB Part Part VIII).

### **7.2 Catch Basin Labels and Open Channel Signage**

*Permit §VI.D.9.h.vi (LA)/ §VII.L.8.vi (LB)*

All municipally owned storm drain inlets are labeled with a “No Dumping, Drains to Ocean” message, and inspected for legibility prior to the wet season (October-April) every year. Catch basins with illegible labels are recorded and re-stenciled or re-labeled within 180 days of inspection. In addition, signs referencing local code(s) that prohibit littering and illegal dumping are posted at designated public access points to open channels, creeks, urban lakes, and other relevant water bodies.

### **7.3 Trash Management**

*Permit §VI.D.9.h.iv-v & Permit §VI.D.9.h.vii (LA)/§VII.L.8.iv-v (LB)*

The following Trash Management BMPs described below are employed to mitigate the impacts of anthropogenic trash on receiving waters.

#### **7.3.1 Trash Management at Public Events**

The following measures are implemented for any event in the public right of way or wherever it is foreseeable that substantial quantities of trash and litter may be generated, including events located in areas that are subject to a trash TMDL:

- Proper management of trash and litter generated; and
- Arrangement for temporary screens to be placed on catch basins; or
- Provide clean out of catch basins, trash receptacles, and grounds in the event area within one business day subsequent to the event.

#### **7.3.2 Trash Receptacles**

Covered trash receptacles are located in areas identified as high trash generation areas and maintained and cleaned out as necessary to prevent trash overflow. Examples of areas that may be considered high trash generating areas include:

- High vehicle or pedestrian traffic areas
- Commercial areas
- Industrial areas
- Construction areas
- High density residential areas
- Areas adjacent to vacant lots

#### **7.3.3 Additional Trash Management Practices**

In areas that are not subject to a trash TMDL, additional trash management practices will be employed no later than five years after the effective date of the LA MS4 Permit (4 years after the effective date of the LB MS4 Permit). Trash excluders or equivalent devices must be installed on or in catch basins or outfalls to prevent the discharge of trash to the MS4 or receiving waters, unless the installation of such BMP(s) alone will cause flooding (not due to lack of maintenance). Alternatively, additional trash BMPs

that provide substantially equivalent removal of trash may be implemented. Additional BMPs may include, but are not limited to:

- Increased street sweeping
- Adding trash cans near trash generation sites
- Prompt enforcement of trash accumulation
- Increased trash collection on public property
- Increased litter prevention messages or trash nets within the MS4

The BMPs chosen will provide equivalent trash removal performance as excluders, and will be demonstrated through the annual report. When outfall trash capture is provided, revision of the schedule for inspection and cleanout of catch basins will also be reported in the annual report.

The State Water Resources Control Board (State Water Board) is considering the adoption of amendments to the Water Quality Control Plans for Ocean Waters of California and for the Inland Surface Water, Enclosed Bays, and Estuaries of California for Trash (Trash Amendments) citing a strong need for statewide consistency in trash management. The proposed Trash Amendments will include five elements: (1) Water Quality Objective, (2) Prohibition of Discharge, (3) Implementation, (4) Compliance Schedule, and (5) Monitoring, which will outline NPDES Permittee requirements for trash management. The development of the Trash Amendments will continue to be monitored, and any additional required trash management practices in areas not subject to a trash TMDL will be implemented per the guidance provided by these amendments.

#### **7.4 Storm Drain Maintenance**

*Permit §VI.D.9.h.viii (LA)/§VII.L.8.viii (LB)*

The following BMPs constitute the Storm Drain Maintenance Program:

- Municipally-owned open channels and drainage structures are visually inspected for debris at least annually.
- Trash and debris from is removed from open channel storm drains a minimum of once per year, before the storm season.
- The discharge of contaminants is minimized during MS4 maintenance and clean outs;
- Material removed is properly disposed of by containing and hauling away for legal disposal

#### **7.5 Infiltration from Sanitary Sewer to MS4/Preventive Maintenance**

*Permit §VI.D.9.h.ix (LA)/§VII.L.8.ix (LB)*

Thorough, routine, preventive surveys and maintenance of both municipally owned and operated Storm Drain Systems as well as Sanitary Sewer Systems infiltration and seepage of contaminants from the sanitary sewer system into the storm drain system is prevented. Sanitary Sewer System routine preventative maintenance is described in the Sewer System Management Plan (SSMP), which is a component of the Statewide General Waste Discharge Requirements (WDR) for Sanitary Sewer Systems.

Where necessary, controls implemented to limit infiltration of seepage from sanitary sewers to the MS4 include:

- Adequate plan checking for construction and new development;
- Incident response training for its municipal employees that identify sanitary sewer spills;
- Code enforcement inspections;
- MS4 maintenance and inspections;
- Interagency coordination with sewer agencies; and

- Proper education of its municipal staff and contractors conducting field operations on the MS4 or its municipal sanitary sewer (if applicable).

**7.6 Permittee Owned Treatment Control BMPs** *Permit §VI.D.9.h.x (LA)/§VII.L.8.x (LB)*

All municipally owned treatment control BMPs, including post-construction BMPs, are regularly inspected and maintained to ensure their proper operation.

Any residual water generated during BMP maintenance is disposed of using one of the following procedures:

- Hauled away and legally disposed of; or
- Applied to the land without runoff; or
- Discharged to the sanitary sewer system; or
- Treated or filtered to remove bacteria, sediments, nutrients, and meet the limitations set in Table PA-6 below prior to discharge to the storm drain system.

Table PA-6: Discharge Limitations for Dewatering Treatment BMPs

Parameter	Units	Limitation
Total Suspended Solids	Mg/L	100
Turbidity	NTU	50
Oil and Grease	Mg/L	10

**8. Streets, Roads, and Parking Facilities Maintenance**

*Permit §VI.D.9.i(LA)/§VII.L.9 (LB)*

*This section corresponds to multiple Activity Cut Sheets within the Flexible Pavement, Rigid Pavement, Litter/Debris/Graffiti, Traffic Guidance, and Management and Support Families.*

Streets and roads may collect litter and debris from nearby activities, as well as from vehicular traffic. They also require routine maintenance that may generate waste materials. Table PA-7 shows potential pollutants generated from street, road, and parking facilities maintenance.

Table PA-7: Potential Pollutants Generated from Street, Road, and Parking Facility Maintenance

Activity	Potential Pollutants						
	Sediment	Trash	Metals	Bacteria	Oil & Grease	Organics	Oxygen Demanding Substances
Street and Road Maintenance	✗	✗	✗		✗	✗	
Parking Facility Maintenance	✗	✗	✗	✗	✗	✗	✗

**8.1 Street Sweeping**

*Permit §VI.D.9.i.i-ii(LA)/§VII.L.9.i-ii (LB)*

Streets and/or street segments are swept according to the following designations:

- Priority A: Streets and/or street segments that are designated as consistently generating the highest volumes of trash and/or debris should be swept at least two times per month.
- Priority B: Streets and/or street segments that are designated as consistently generating moderate volumes of trash and/or debris should be swept at least once per month.
- Priority C: Streets and/or street segments that are designated as generating low volumes of trash and/or debris shall be swept as necessary but in no case less than once per year.

## 8.2 Road Reconstruction

*Permit §VI.D.9.iii (LA)/§VII.L.9.iii (LB)*

Projects that include roadbed or street paving, repaving, patching, digouts, or resurfacing roadbed surfaces implement the following BMPS:

- Restricting paving and repaving activities to exclude periods of rainfall or predicted rainfall unless required by emergency conditions.
- Installing sand bags or gravel bags and filter fabric at all susceptible storm drain inlets and at manholes to prevent spills of paving products and tack coat;
- Preventing the discharge of release agents including soybean oil, other oils, or diesel into the MS4 or receiving waters.
- Preventing non-stormwater runoff from water use for the roller and for evaporative cooling of the asphalt.
- Cleaning equipment over absorbent pads, drip pans, plastic sheeting or other material to capture all spillage and dispose of properly.
- Collecting liquid waste in a container, with a secure lid, for transport to a maintenance facility to be reused, recycled or disposed of properly.
- Collecting solid waste by vacuuming or sweeping and securing in an appropriate container for transport to a maintenance facility to be reused, recycled or disposed of properly.
- Covering the “cold-mix” asphalt (i.e., pre-mixed aggregate and asphalt binder) with protective sheeting during a rainstorm.
- Covering loads with tarp before haul-off to a storage site, and not overloading trucks.
- Minimizing airborne dust by using water spray during grinding.
- Avoiding the stockpiling of soil, sand, sediment, asphalt material and asphalt grindings materials or rubble in or near MS4 or receiving waters.
- Protecting stockpiles with a cover or sediment barriers during a rain.

## 8.3 Parking Facilities Maintenance

*Permit §VI.D.9.iv (LA)/ §VII.L.9.iv (LB)*

Municipally owned parking lots that are uncovered and exposed to stormwater are kept clear of debris and excessive oil buildup by inspecting lots at least 2 times per month and cleaning at least once per month.

## 9. Emergency Procedures

*Permit §VI.D.9.j (LA)/ §VII.L.10 (LB)*

Participating Agencies may conduct repairs of essential public service systems and infrastructure in emergency situations with a self-waiver of the provisions of the MS4 Permit as follows:

- Cities will abide by all other regulatory requirements, including notification to other agencies as appropriate.
- Where the self-waiver has been invoked, Cities will submit to the Regional Water Board Executive Officer a statement of the occurrence of the emergency, an explanation of the

circumstances, and the measures that were implemented to reduce the threat to water quality, no later than 30 business days after the situation of emergency has passed.

Minor repairs of essential public service systems and infrastructure in emergency situations (that can be completed in less than one week) are not subject to the notification provisions. Appropriate BMPs to reduce the threat to water quality will be implemented.

#### **10. Municipal Employee and Contractor Training** *Permit §VI.D.9.k (LA)/Permit §VII.L.11 (LB)*

An annual training program on the requirements of the overall stormwater management program is implemented for all municipal field staff whose interactions, jobs, and activities affect stormwater quality prior to June 30 every year. The Cities also ensure that contractors performing privatized/contracted municipal services have appropriate training in the stormwater management program. The goals of the annual training are to:

- Promote a clear understanding of the potential for municipal activities to pollute stormwater
- Identify opportunities to require, implement, and maintain appropriate BMPs in their line of work

In addition to the annual stormwater program training, the Cities implement an annual training program to train all of their employees and contractors who use or have the potential to use pesticides or fertilizers (whether or not they normally apply these as part of their work). Training programs address:

- The potential for pesticide-related surface water toxicity
- Proper use, handling, and disposal of pesticides
- Least toxic methods of pest prevention and control, including IPM
- Reduction of pesticide use

Outside contractors can self-certify, providing they certify they have received all applicable training required in the MS4 Permit and have documentation to that effect.

# Illicit Connections & Illicit Discharges Elimination Program

Each participating city is required to develop and implement an Illicit Connections & Illicit Discharge Elimination (IC/ID) Program that includes the requirements listed in Permit §VI.D.10.a (LB §VII.M). This document provides guidance to assist the Cities in implementing an IC/ID program in compliance with the Permit.

## Introduction

*Permit §VI.D.10.a (LA)/§VII.M.1 (LB)*

Illicit connections and illicit discharges (IC/IDs) as defined in Table ICID-1 are potential significant sources of pollutants into and from the MS4. The Illicit Connection and Illicit Discharge (IC/ID) Program provides a comprehensive process for detecting, investigating and eliminating IC/IDs in an efficient and timely manner. The program consists of the following components:

- Procedures for conducting source investigations for IC/IDs
- Procedures for eliminating the source of IC/IDs
- Procedures for public reporting of illicit discharges
- Spill response plan and
- IC/ID education and training for City staff.

The purpose of this program is to effectively prohibit illicit discharges into the MS4.

Table ICID-1: IC/IDs Defined

Prohibition	Definition	Examples
Illicit Connections	Any man-made conveyance that is connected to the MS4 without a permit, excluding roof drains and other similar type connections.	Unpermitted channels, pipelines, conduits, inlets or outlets that are connected directly to the MS4.
Illicit Discharges	Any discharge into the MS4 or from the MS4 into a receiving water that is prohibited under local, state, or federal statutes, ordinances, codes or regulations. This includes any non-stormwater discharge, except those authorized in MS4 Permit §III.A.10.2.	Sanitary wastewater, Vehicle wash water, wash-down from grease traps, motor oil, antifreeze and fuel spills into or from the MS4.

## Legal Authority

Adequate Legal Authority is required to prohibit IC/IDs to the MS4 and enable enforcement capabilities to eliminate the sources of IC/IDs.

## Illicit Discharge Source Investigation and Elimination

*Permit §VI.D.10.b (LA)/ §VII.M.2 (LB)*

The purpose of the IC/ID Program is accomplished in part by developing clear, step-by-step written procedures for conducting investigations of illicit discharges.

## Investigation

Standardized procedures for conducting investigations to identify the source of all suspected illicit discharges are included in as an attachment (Illicit Discharge Investigation and Elimination Guidance). Procedures include the following:

- **Initiation** – Investigate the source of all observed discharges. After becoming aware of an illicit discharge, conduct an investigation to identify and locate the source within 72 hours.
- **Prioritization** – Investigate illicit discharges suspected of being sanitary sewage and/or significantly contaminated first.
- **Tracking** – Track all investigations and document the information listed in Table ICID-2.

Table ICID-2: Recorded Information for Illicit Discharge Investigations

Item	Information
1	Date(s) the illicit discharge was observed
2	Results of the investigation
3	Follow-up of the investigation
4	Date the investigation was closed

## Elimination

Standardized procedures to eliminate illicit discharges once the sources are located are included as an attachment. Procedures include the following:

- **Notification** – Immediately notify the responsible party (RP)/parties of the problem and require the responsible party to initiate all necessary corrective actions to eliminate the illicit discharge.
  - If it is determined that an illicit discharge originates within an upstream jurisdiction, notify the upstream jurisdiction and the Regional Board. The Notification is conducted within 30 days of determination and information is collected regarding combined efforts to identify the source.
- **Spill response** – The Spill Response Plan is implemented when the source for illicit discharges cannot be traced to a suspected RP. Permanent solutions to such discharges are described in the following section (Flow Diversion).
- **Follow-up** – Conduct and document follow-up investigations upon notification that an illicit discharge has been eliminated to verify that it has been satisfactorily eliminated and cleaned-up.
- **Enforcement** – Enforcement procedures are included in the Progressive Enforcement Policy. The Progressive Enforcement Policy includes a list of enforcement actions.

## Progressive Enforcement Policy

The Progressive Enforcement Policy is implemented to ensure that illicit discharges/ illicit connections are eliminated within a reasonable time period. The procedures are followed when the source of the nature of the discharges is known. Procedures typically include:

- Written warnings for minor violations
- Formal notice of violation with specific actions and time frames for compliance
- Compensation from the RP for any costs related to remediation, inspection, investigation, clean-up and oversight activities
- Cease and desist orders

- Civil penalties (infractions), or referral for criminal penalties or further legal action.

### Flow Diversion

In the event that an ongoing illicit discharge cannot be eliminated (following the full execution of legal authority and in accordance with the Progressive Enforcement Policy) or the RPs cannot be identified, the discharge is either treated or diverted to the sanitary sewer. In either instance, the Regional Board is notified within 30 days of such determination. Notification includes the following information:

- Written plan that describes the efforts that have been undertaken to eliminate the discharge.
- Description of actions to be undertaken.
- Anticipated cost and
- Schedule for completion.

### Identification and Response to Illicit Connections

*Permit §VI.D.10.c (LA)/§VII.M.3 (LB)*

Illicit connections can be concentrated sources of pollutants either through direct discharge or infiltration of sewage or other prohibited discharges into the MS4. To reduce this source of pollutants, the following program is implemented for the identification of illicit connections. Key components of this program include investigating and responding in order to actively prevent and eliminate illicit connections.

#### Investigation

Standardized procedures for identifying illicit connections are included as an attachment (Illicit Connection Investigation Guidance). Procedures include the following:

- **Initiation** – Investigate within 21 days from the discovery or upon receiving a report of a suspected illicit connection. The elements of the investigation are listed in Table ICID-3.
- **Tracking** – Track all investigations and document the information listed in Table ICID-3.

#### Response

If the source investigation concludes that a connection to the MS4 is both 1) permitted or documented and 2) discharging only stormwater or nonstormwater allowed under WMP NSW SECTION or other individual or general NPDES Permits/WDRs, then the investigation is closed and no further action is taken. Upon confirmation of a connection to the MS4 is illicit, one of two options is taken:

1. **Permit or document the connection.** The permitted or documented connection may only discharge stormwater and nonstormwater allowed under WMP NSW SECTION or other individual or general NPDES Permits/WDRs. Retaining a record of the connection and its investigation qualifies as documentation.
2. **Eliminate the connection.** The connection is eliminated within 180 days of completion of the investigation, using formal enforcement authority if necessary.

Table ICID-3: Recorded Information for Illicit Connection Investigations

Item	Information
1	Any relevant illicit discharge information from Table ICID-2
2	Source of the connection
3	Nature and volume of the discharge through the connection
4	RP for the connection (if identified)
5	Response including any formal enforcement taken

### **Public Reporting of Non-Stormwater Discharges and Spills** *Permit §VI.D.10.d (LA)/§VII.M.4 (LB)*

#### **Central Point of Contact**

Public reporting of illicit discharges or water quality impacts associated with discharges into or from MS4s through a central contact point are promoted, publicized, and facilitated. This includes phone numbers and an internet site for complaints and spill reporting. The reporting hotline is provided to staff to leverage the field staff that has direct contact with the MS4 in detecting and eliminating illicit discharges.

The LACFCD, in collaboration with the County, provides the central point of contact and through the 888-CLEAN-LA reporting hotline and internet site.

#### **Open Channels**

Signage is posted adjacent to open channels (see MS4 Permit IV.D.9.h.vi.(4)). The signage includes information regarding dumping prohibitions and public reporting of illicit discharges.

#### **Complaints**

Written procedures are maintained that document how complaint calls are received, and tracked to ensure that all complaints are adequately addressed in the attached form (Record Keeping & Documentation). Following the adaptive management process outlined in the MS4 Permit, the procedures are periodically evaluated to determine whether changes or updates are needed to ensure that the procedures accurately document the employed methods. After the evaluation, any identified changes will be made to the procedures.

Documentation is maintained for all complaint calls. This includes recording the location of the reported spill or IC/ ID and the actions undertaken in response the complaint, including referrals to other agencies.

### **Spill Response Plan**

*Permit §VI.D.10.e (LA)/§VII.M.5 (LB)*

A spill response plan (Attachment ICID-E) is implemented for all sewage and other spills that may discharge into its MS4. The spill response plan identifies agencies responsible for spill response and cleanup, telephone numbers and e-mail address for contacts, and contains the following:

- **Agency Coordination** – Coordinate with spill response teams throughout all appropriate departments, programs and agencies so that maximum water quality protection is provided.
- **Spill Response** – Respond to spills for containment within 4 hours of becoming aware of the

spill, except where such spills occur on private property, in which case respond within 2 hours of gaining legal access to the property. Initiate investigation of all public and employee spill complaints within one business day of receiving the complaint to assess validity.

- **Reporting** – Spills that may endanger health or the environment are reported to appropriate public health agencies and the California Emergency Management Agency (Cal EMA).

### **Illicit Connection and Illicit Discharge Education and Training** *Permit §VI.D.10.f (LA)/§VII.M.6 (LB)*

A training program regarding the identification of IC/IDs is implemented for all municipal field staff, who, as part of their normal job responsibilities (e.g., street sweeping, storm drain maintenance, collection system maintenance, road maintenance), may come into contact with or otherwise observe an illicit discharge or illicit connection to the MS4. Contact information, including the procedure for reporting an illicit discharge, is readily available to field staff.

#### **Applicable Staff**

Table ICID-4 is a list of field programs where program staff may come into contact with or otherwise observe an illicit discharge or illicit connection to the MS4. Appropriate field staff, supervising staff and contractors involved in these programs require training in IC/ID identification and reporting following the schedule provided in Table ICID-5.

#### Contracted Staff

Contractors that provide these municipal services may attend city training or certify to the participating city and retain documentation that staff has received applicable training. Otherwise this provision is accomplished through a contractual requirement for contracted staff to receive the training.

Table ICID-4: Municipal Field Programs

Main Field Program Types	Sub-Category Types/Activities
Lake Management	Fertilizer & Pesticide Management
	Mowing, Trimming/Weeding, Planting
	Managing Landscape Waste
	Controlling Litter
	Erosion Control
	Controlling Illegal Dumping
	Bacteria Control
	Monitoring
Landscape Maintenance	Mowing, Trimming/Weeding, Planting
	Irrigation
	Fertilizer & Pesticide
	Managing Landscape Waste
	Erosion Control
Roads, Streets, and Highways Operations and Maintenance	Sweeping & Cleaning
	Street Repair & Maintenance
	Bridge & Structure Maintenance
Fountains, Plazas, and Sidewalk Maintenance and Cleaning	Surface Cleaning
	Graffiti Cleaning
	Sidewalk Repair
	Controlling Litter
	Fountain Maintenance
Solid Waste Handling	Solid Waste Collection
	Waste Reduction & Recycling
	Hazardous Waste Collection
	Litter Control
Water and Sewer Utility O&M	Water Line Maintenance
	Sanitary Sewer Maintenance
	Spill/Leak/Overflow Control
Fire Department Activities	Emergency/Post-Emergency Fire Fighting Activities
	Fire Fighting Training
	Fire Station Activities

**Training Schedule**

The training schedule for all applicable staff is listed in Table ICID-5.

Table ICID-5: IC/ID Program Training Schedule

Category	Schedule
Current Staff	Twice during the term of the MS4 Permit
New Staff	Within 180 days of starting employment

**Training Elements**

The IC/ID elements addressed by the training program are listed in Table ICID-6.

Table ICID-6: Minimum IC/ID Training Program Elements

<b>Item</b>	<b>Information</b>
1	IC/ID identification, including definitions and examples
2	Investigation
3	Elimination
4	Clean-up
5	Reporting
6	Documentation

**Documentation**

Documentation of training program activities and training modules are retained and made available for review by the Regional Board.

# PROGRESSIVE ENFORCEMENT POLICY

2014

Stormwater Enforcement Guide

*Insert  
City  
Seal*

**TABLE OF CONTENTS**

**INTRODUCTION**..... 2

**PROGRESSIVE ENFORCEMENT** ..... 2

**COMPLIANCE CRITERIA** ..... 2

    Complaint Response..... 3

**PROGRESSIVE ENFORCEMENT GUIDELINES**..... 3

    Informal Enforcement ..... 3

        Written Warning/ Inspection Report..... 3

    Formal Enforcement / Administrative Enforcement..... 3

        Notice of Violations..... 3

        Failure to Return to Compliance/ Second Notice of Violation ..... 4

        Cease and Desist Order ..... 4

        Misdemeanors ..... 4

        Issuance of Citation/Infractions..... 4

        Cost Recovery ..... 4

        Abatement ..... 4

        Permit Revocation..... 4

        City's/District Attorney ..... 4

**TIMEFRAMES FOR CORRECTING DEFICIENCIES/VIOLATIONS** ..... 5

**EXTENSIONS OF COMPLIANCE DEADLINES**..... 5

**REFERRALS TO THE REGIONAL BOARD**..... 6

    Referral of Violations of the General Industrial/Construction Permits..... 6

**RECORDS RETENTION** ..... 6

**Attachments**

- Deficiencies/Violation Degrees Table
- Progressive Enforcement Flow Chart

# PROGRESSIVE ENFORCEMENT POLICY

## STORMWATER ENFORCEMENT GUIDE

### INTRODUCTION

This Stormwater Progressive Enforcement Policy (PEP) provides procedures to enforce provisions of the Waste Discharge Requirements for Municipal Separate Storm Sewer System (MS4) Discharges within the Coastal Watersheds of Los Angeles County, except those Discharges Originating from the City of Long Beach MS4 Order No. R4-2012-0175. Pursuant to Section VI.D.2.a of the Order, Permittees are required to develop and implement a PEP to ensure that (1) regulated Industrial/ Commercial facilities, (2) construction sites, (3) development and redevelopment sites with post-construction controls, and (4) illicit discharges are each brought into compliance with all storm water and non-storm water requirements. The PEP provides the City with a guidance for enforcing the MS4 Permit Provisions and identifies enforcement procedures designed to encourage a timely response.

### PROGRESSIVE ENFORCEMENT

Progressive enforcement is an escalating series of actions that allows for the efficient and effective use of enforcement. In some situations, an informal response (written warning/inspection report) is sufficient to inform the responsible party that there is a deficiency and to require the responsible party to return to compliance. If violations continue, the enforcement response should be quickly escalated to increasingly more formal and serious actions until compliance is achieved. Progressive enforcement is not appropriate in all circumstances. For example, where there is a situation needing immediate response, immediate issuance of a cleanup and abatement order may be appropriate.

### COMPLIANCE CRITERIA

The City conducts on-site compliance inspections and conducts investigations, in response to complaints, under their authority provided in their municipal code and ordinances to verify compliance. Typical noncompliance issues related to stormwater may include:

- Prohibited discharges to the storm drain system.
- Site's existing condition is likely to result in exposure of pollutants to stormwater contact and possible pollutant discharge to the storm drain system such as:
  - Poor housekeeping activities that results in pollutant exposure.
  - Unattended spills and leaks.
  - Uncovered or improperly stored wastes, materials, or other items of concern.
  - Open waste receptacles such as tallow bins, compactors, and trash bins.
  - Leaky or contaminated equipment stored or used outdoors.
  - Track-out of dirt and sediment or other materials to street or outdoor areas.
- Illicit connections to the storm drain system.
- Best Management Practices (BMPs) are not in place to address pollutant generating activities, which may include erosion and sediment controls and post construction controls.

## Complaint Response

The City may receive complaints regarding stormwater ordinance from their staff members, public, local agencies, or the Regional Water Board. The City initiates, within one business day,<sup>1</sup> investigation of complaints from facilities within its jurisdiction. The initial investigation includes, at minimum, a limited inspection of the facility to confirm validity of the complaint and to determine if the facility is in compliance with municipal storm water ordinance and, if necessary, to oversee corrective action. Emergency complaints are investigated immediately.

## PROGRESSIVE ENFORCEMENT GUIDELINES

### Informal Enforcement

The City implements professional judgment regarding the circumstances surrounding an enforcement action and chooses to resolve routine noncompliance quickly and efficiently through informal means that are not accompanied by sanctions (e.g., civil charges or penalties). When deemed appropriate, the City employs the procedures described below to correct noncompliance informally.

#### Written Warning/ Inspection Report

Under circumstances where an inspection reveals routine noncompliance that can be corrected within a reasonably short time, staff may choose to issue a written warning/inspection report that describes the minor deficiencies/violations and includes a schedule for correcting the noncompliance<sup>2</sup>. The purpose of the written warning is to give the responsible party an opportunity to comply voluntarily and thus avoid sanctions that might be imposed by an escalated enforcement response.

For residential zones, the City employs an informal enforcement process and escalates to formal enforcement actions for those residents that do not comply with stormwater regulations.

### Formal Enforcement / Administrative Enforcement

In the event that the City determines, based on an inspection or illicit discharge investigation conducted, that a responsible party has failed to adequately comply with the informal enforcement process within the required timeframe, the City may initiate administrative enforcement actions or will implement enforcement actions as established through authority in its municipal code. The City's goal is to achieve compliance through an extensive inspection program, educational outreach efforts and, if necessary, the initiation of appropriate enforcement action(s). The goal of any enforcement action is to: (1) return the facility to compliance in a timely manner; (2) eliminate economic benefit realized by the noncompliant facility; and (3) punish violators and prevent future noncompliance.

#### Notice of Violations

Under circumstances where the responsible party has failed to comply with the informal enforcement process or where the violations are significant, the City may choose to issue a Notice of Violation (NOV). The purpose of an NOV is to inform the responsible party of the observed violations, the applicable stormwater municipal codes that the responsible party has failed to comply with and the

---

<sup>1</sup> The City may comply with the Permit by taking initial steps (such as logging, prioritizing, and tasking) to "initiate" the investigation within that one business day. However, the Regional Water Board would expect that the initial investigation, including a site visit, to occur within four business days (per MS4 Order No.R4-2012-0175 Section VI.D.2.b)

<sup>2</sup> The City may choose to issue/write inspection report on site or provide to the responsible party at a later time.

potential consequences of failing to correct the violations. The NOV also gives the responsible party an opportunity to correct the violations described in the NOV within a specified time. Under circumstances where the responsible party fails to adequately respond to the NOV by failing to address or correct the violations noted in the NOV, the severity of the enforcement response will continue to escalate as described below.

### **Failure to Return to Compliance/ Second Notice of Violation**

The City's municipal code stormwater ordinance authorizes assessment of administrative penalties which can be carried out by issuing a Failure to Return to Compliance Notice or second NOV. The second NOV is a stronger enforcement option which may be used in circumstances where the responsible party has failed to comply with the requirements as indicated on the first NOV.

### **Cease and Desist Order**

In the event the City's municipal code stormwater ordinance authorizes a Cease and Desist Order (CDO), the City may issue a CDO, as an alternative to the second NOV, when immediate action by the responsible party is necessary to eliminate a continuing or threatened serious violation of the stormwater ordinance.

### **Misdemeanors**

The City's may escalate enforcement when evidence of noncompliance indicates that the violator of the stormwater ordinance has acted intentionally with intent to cause, allow to continue or conceal a discharge in violation of the ordinance.

### **Issuance of Citation/Infractions**

At the discretion of the City's, and as established through authority in its municipal code, the City may issue citations and/or infractions.

### **Cost Recovery**

In the event that a complaint response or violation requires clean-up and or extensive investigation, the City has the authority, as established in the municipal code, to require the responsible party to reimburse the city or County for all costs incurred by the related violation. Cost recovery fees that may be collected include, but are not limited to, investigation, enforcement, compliance assistance, damage, control, and clean-up.

### **Abatement**

When a responsible party fails to cease or control a nuisance condition that results in or is likely to result in further or continuing violations, the City's may request abatement of conditions on private property if necessary, or in the event of imminent danger to public safety or the environment, the City itself may abate the nuisance condition.

### **Permit Revocation**

Sites violating the stormwater permit may be subject to permit revocation procedures as authorized in the City's municipal code.

### **City's/District Attorney**

---

Severe or continuing violations should be referred to the City's or District Attorney for consideration of criminal charges.

## TIMEFRAMES FOR CORRECTING DEFICIENCIES/VIOLATIONS

Depending upon the nature of the deficiencies/violations observed, City's may specify compliance deadlines for the responsible party in the inspection report or NOV.

- Prohibited discharges: discharges are to be stopped immediately and up to two weeks. The City may require the responsible party to provide a written description of correction, long-term compliance plan.
- Illicit connection: discharge via the illicit connection are to be stopped immediately and up to two weeks. The City may require the responsible party to provide proof that connection was permanently terminated. Re-inspection typically is required.
- Pollutant exposure/prohibited conditions violations: Up to two weeks to correct violations. The City may require the responsible party to provide proof of compliance for the observed violations.

## EXTENSIONS OF COMPLIANCE DEADLINES

There are instances when a responsible party is not able to comply with requirements within the time frame specified. The City may grant a reasonable extension to the responsible party if the City determines that an extension is warranted, as follows:

- A request for extension must be received in writing (mail, e-mail, fax, hand delivered, etc.) by the City no later than the last day of the initial specified compliance deadline date.
- The extension request must explain why the extension is needed and warranted, as well as include a summary of actions taken to date by the responsible party to comply with requirements of the NOV.
- No more time is provided than should reasonably be needed for the responsible party to competently correct the noted deficiencies/violations. The City grants shorter extensions during the wet season.

Appropriate reasons to grant an extension may include, but are not limited to:

- Confirmed delays due to contractor or other service provider outside of responsible party's control.
- Extensive corrections involving work that would conceivably take longer than the time frame provided.
- In general, extensions should not be granted to allow the continuation of unauthorized non-storwater discharges.

The City may require an action plan or statement to be submitted by the responsible party within the initial compliance time frame, as a condition of granting an extension. The action plan or statement should specify the corrections that are to be made and specify an anticipated time frame for completion. The action plan or statement should be signed and dated by the responsible party.

## REFERRALS TO THE REGIONAL BOARD

The City may refer violations of its municipal storm water ordinance and/or California Water Code section 13260 by industrial and commercial facilities and construction site operators to the Regional Water Board provided that the City has made a good faith effort of applying enforcement procedures to achieve compliance with its own ordinance. At a minimum, the City's good faith effort must be documented with:

- Two follow-up inspections, and
- Two warning letters or notices of violation.

### **Referral of Violations of the General Industrial/Construction Permits**

For those facilities or site operators in violation of municipal stormwater ordinances and subject to the Industrial and/or Construction General Permits (IGP/CGP), the City may escalate referral of such violations to the Regional Water Board (promptly via telephone or electronically) after one inspection and one written notice of violation (copied to the Regional Water Board) to the facility or site operator regarding the violation. In making such referrals, the City shall include, at a minimum, the following documentation:<sup>3</sup>

- Name of the facility or site,
- Operator of the facility or site,
- Owner of the facility or site,
- WDID Number (if applicable),
- Records of communication with the facility/site operator regarding the violation, which shall include at least one inspection report,
- The written notice of violation (copied to the Regional Water Board),
- For industrial sites, the industrial activity being conducted at the facility that is subject to the Industrial General Permit, and
- For construction sites, site acreage and Risk Factor rating.

## RECORDS RETENTION

City shall maintain records, per their existing record retention policies, and make them available on request to the Regional Water Board, including inspection reports, warning letters, notices of violations, and other enforcement records, demonstrating a good faith effort to bring facilities into compliance.<sup>4</sup>

<sup>3</sup> Pursuant to Order No. R4-2012-0175 Section VI.D.2.a.v

<sup>4</sup> Pursuant to Order No. R4-2012-0175 Section VI.D.2.a.iii

### Sources

Los Angeles County Stormwater Quality Management Program (2001)

Orange County Municipal Storm Water Drainage Area Management Plan (2003)


Sacramento County Environmental Management Department. Inspection & Enforcement Policy - Commercial/Industrial Stormwater Compliance Program (2012).

DRAFT

### Deficiencies/ Violation Degrees

Minor	Moderate	Major
<p>Typically involves conditions that threaten to result in pollutant discharge to the storm system and/or waterways, if not corrected. The immediate threat to human health or the environment is low.</p> <p><b>Examples:</b></p> <ol style="list-style-type: none"> <li>1. Unattended automotive fluid drips and spills likely to result in moderate discharges to the storm drain system.</li> <li>2. Discharge of a moderate amount of car body wet sanding effluent from a single vehicle to outdoor pavement that has not yet impacted the storm drain system.</li> <li>3. Unattended spilled restaurant grease on outdoor pavement. Spill appears to be recent, is less than a quart, has not yet impacted the storm drain system and poor housekeeping do not appear to be habitual.</li> <li>4. Oily, uncovered engines, or other oily, possibly leaky items stored outside.</li> <li>5. Open and missing dumpster and tallow bin lids.</li> </ol>	<p>Typically involves less significant pollutant discharges to the storm system and/or receiving waters or conditions that threaten to result in minor to moderate pollutant discharges to the storm system and/or receiving waters.</p> <p>May include small or incidental discharges of hazardous or toxic substances. The violation does not present a major threat to human health and safety, but is likely to result in degradation of receiving water quality.</p> <p><b>Examples:</b></p> <ol style="list-style-type: none"> <li>1. Discharge of moderate amounts of automotive fluids to storm drain system results from neglected spills and poor housekeeping.</li> <li>2. Discharge of moderate amount (less than 20 gallons of diluted effluent) of auto body wet sanding effluent to storm drain system.</li> <li>3. More than a quart of spilled restaurant grease on outdoor pavement is neglected, possibly getting tracked out of trash enclosure. Neglect appears to be habitual but so far, impact to storm drain is moderate.</li> <li>4. Moderate amount of Oil/fluids leaking from improperly stored engines and parts discharge to storm drain system.</li> <li>5. Repeat minor violations may be considered moderate.</li> </ol>	<p>Includes significant pollutant discharges to the storm system and/or receiving waters as well as creation of conditions that threaten imminent discharge of significant pollutants to the storm system and/or receiving waters. This also includes, but is not limited to, significant discharges of hazardous or toxic substances.</p> <p>Major violations have the potential to present a major threat to human health or safety and/or the environment. The intent of the violator should be considered: Patterns of willful disregard for safety and the environment, recalcitrance, and repeat violations should contribute to designation of a violation as major, but are not necessary.</p> <p><b>Examples:</b></p> <ol style="list-style-type: none"> <li>1. Intentional discharge of waste oil to the storm drain.</li> <li>2. Discharge of significant volumes of auto body wet sanding effluent to storm drain from work on multiple vehicles, as practice. Especially where repeat violations or evidence of habitual discharge is evident.</li> <li>3. Significant amount of spilled restaurant grease is intentionally washed into storm drain, especially if hazardous degreasing agent is used.</li> <li>4. Significant amount of Oil/fluids leaking from improperly stored engines and parts discharge to storm drain system, especially if repeat violation.</li> <li>5. Repeat moderate violations may be considered major.</li> </ol>

# PROGRESSIVE ENFORCEMENT FLOW CHART



Watershed Management Program Appendix 3

# Attachments to MCM Guidance

DRAFT

**CITY STORMWATER PROGRAM INDUSTRIAL/COMMERCIAL FACILITY INSPECTION REPORT**

Facility:	Address:
Contact:	Title:
Email:	Phone:
Inspector:	Date:
Inspection Type: <input type="checkbox"/> Routine <input type="checkbox"/> Follow-up <input type="checkbox"/> Response to Complaint	BMP materials provided and explained: <input type="checkbox"/> Yes <input type="checkbox"/> No
SIC/NAICS code and/or business type:	

**Industrial Facilities Only**

(1) Covered under IGP (WDID is current) or other NPDES Permit:  Yes  No      (2) NEC filed:  Yes  No      SWPPP on-site:  Yes  No

If (1) and (2) above are "No", notified contact of need for IGP coverage and will refer facility to Regional Board:  Yes  No

**CHECKLIST FOR STORMWATER BMP (BEST MANAGEMENT PRACTICE) COMPLIANCE**

BMP		Yes	No	N/A	BMP		Yes	No	N/A
Vehicle & Equipment Maintenance	<b>Fueling</b> - Effective fueling source control devices & practices	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Facility Maintenance	<b>Building &amp; grounds maintenance</b> – Effective maintenance practices	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<b>Cleaning</b> – Effective cleaning practices & wash water management practices	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<b>Parking &amp; storage area maintenance</b> – Effective designs & housekeeping/maintenance practices	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<b>Repair</b> – Effective repair practices & source control devices	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<b>Stormwater conveyance system maintenance</b> – Proper operation & maintenance protocols	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Equipment Operations	<b>Outdoor equipment operations</b> – Effective source control devices & practices	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Spills, Leaks & Discharges	<b>Sidewalk washing</b> – Remove debris & free standing oil/grease. Use high pressure/low volume spray washing with potable water, no cleaning agents & average rate of 0.006 gal/ft <sup>2</sup> .	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Storage & Handling	<b>Outdoor liquids</b> – Effective source controls & practices	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<b>Accidental spills/leaks</b> – Effective spill/leak prevention & response procedures	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<b>Outdoor raw materials</b> – Effective source control practices & structural devices	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<b>Unauthorized nonstormwater discharges</b> – Effective elimination	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<b>Solid waste</b> – Effective storage & handling practices & appropriate control measures	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>					

**COMMENTS AND CORRECTIVE ACTIONS (IF REQUIRED)**

Include description of activities performed and/or principal products produced

**ENFORCEMENT:**       None required       Corrective Action Notice (complete section below)       Other (see comments)

**CORRECTIVE ACTION NOTICE (IF REQUIRED)**

If corrective actions have been noted above, then the responsible party (facility owner, occupant or person responsible) is in noncompliance with the City's Stormwater Quality Ordinance. The responsible party may be subject to enforcement actions under this ordinance if the corrective actions are not implemented by:

\_\_\_\_\_ Corrective Action Due Date

**ACKNOWLEDGEMENT OF RECEIPT OF CORRECTIVE ACTION NOTICE**

\_\_\_\_\_  
Site Representative Signature

\_\_\_\_\_  
Printed Name

\_\_\_\_\_  
Date

**Recording requested by and mail to:**

Name: City of [Insert City]  
Department of Public Works  
**ATTN: Director of Public Works**  
Address: [Insert City Address Line1]  
[Insert City Address Line2]



\*\*\*\*\* Space Above This Line For Recorder's Use \*\*\*\*\*

**MASTER COVENANT AND AGREEMENT**  
REGARDING ON-SITE BMP MAINTENANCE

The undersigned hereby certifies I am (we are) the owner(s) of the hereinafter legally described real property located in the City of [Insert City], County of Los Angeles, State of California (please give legal description: assessor's ID, tract no., lot no., etc.):

Site Address \_\_\_\_\_

Owner(s) do hereby covenant and agree to and with the City of [Insert City] to maintain all on-site structural Best Management Practices (BMPs) in accordance with the Site Map and the Operations & Maintenance (O&M) Plan set forth in Attachment 1 hereto and incorporated herein by this reference. The specific structural BMPs are listed as follows:

\_\_\_\_\_  
\_\_\_\_\_

Owner(s) shall maintain the listed drainage devices above on the property indicated and as shown on plans permitted by the City of [Insert City] in a good and functional condition to safeguard the property owners and adjoining properties from damage and pollution.

Owner(s) hereby consent to inspection of the Property by an inspector authorized by the City Manager, or his or her designee, for the purpose for verifying compliance with the provisions of this Agreement.

Owner(s) shall provide printed educational materials with any sale of the property which provide information on what stormwater management facilities are present, the type(s) and location(s) of maintenance signs that are required, and how the necessary maintenance can be performed.

Owner(s) shall provide actual notice of this Agreement and its terms to any respective successor(s) in interest to the Property prior to transfer of said interest to such successor(s) in interest. This covenant and agreement shall run with the land and shall be binding upon any future owners, encumbrances, their successors, heirs or assigns and shall continue in effect until the City of [Insert City] approves its termination.

\_\_\_\_\_  
(Print Name of Property Owner) (Print Name of Property Owner)

\_\_\_\_\_  
(Signature of Property Owner) (Signature of Property Owner)

Dated this \_\_\_\_\_ day of \_\_\_\_\_ 20 \_\_\_\_\_.

\*\*\*\*\* Space Below This Line For Notary's Use \*\*\*\*\*

ALL PURPOSE ACKNOWLEDGEMENT

State of \_\_\_\_\_ }  
County of \_\_\_\_\_ }

On \_\_\_\_\_ before me, \_\_\_\_\_ personally appeared  
(Insert Name of Notary Public and Title)

\_\_\_\_\_, who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf on which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature \_\_\_\_\_ (Seal)

**Recording requested by and mail to:**

Name: City of [Insert City]  
Public Works Department  
**ATTN: Director of Public Works**



Address: [Insert City Address Line1]  
[Insert City Address Line2]

\*\*\*\*\* Space Above This Line For Recorder's Use \*\*\*\*\*

**MASTER TERMINATION OF COVENANT AND AGREEMENT**

**REGARDING ON-SITE BMP MAINTENANCE**

The undersigned hereby certifies I am (we are) the owner(s) of the hereinafter legally described real property located in the City of [Insert City], County of Los Angeles, State of California (please give legal description: assessor's ID, tract no, lot not, etc.):

Site Address \_\_\_\_\_

We do hereby, with approval of the City of [Insert City], Engineering Division, terminate the covenant and agreement entered into with the City of [Insert City] as recorded on the \_\_\_\_\_ day of \_\_\_\_\_ 20\_\_\_\_\_, as Document No.

This covenant and agreement is terminated for the reason that:

\_\_\_\_\_  
(Print Name of Property Owner) (Print Name of Property Owner)

\_\_\_\_\_  
(Signature of Property Owner) (Signature of Property Owner)

Dated this \_\_\_\_\_ day of \_\_\_\_\_ 20\_\_\_\_\_.

Termination approved by: \_\_\_\_\_ Date: \_\_\_\_\_  
(Authorized City Representative)

\*\*\*\*\* Space Below This Line For Notary's Use \*\*\*\*\*

**ALL PURPOSE ACKNOWLEDGEMENT**

State of \_\_\_\_\_ }  
County of \_\_\_\_\_ }

On \_\_\_\_\_ before me, \_\_\_\_\_ personally appeared  
(Insert Name of Notary Public and Title)

\_\_\_\_\_, who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf on which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature \_\_\_\_\_ (Seal)



**City of [Insert City]NPDES Program  
POST-CONSTRUCTION BMP VERIFICATION & INSPECTION FORM**

<b>PROJECT INFORMATION</b>	
Facility/Project Name:	Inspection Date:
Address:	Inspector:
Contact Name:	Contact Phone:

**Project Category**

Priority Project   
  Small Site LID Project   
  Single Family Residence   
  Green Street  
 Public Project   
  Private Project

**Project Type:**

Commercial   
  Industrial   
  Residential   
  Multi-Use  
 Road/Street   
  Parking Lot   
  Automotive repair   
  Restaurant   
 Other:

**Operation/Maintenance:**

Reviewed   
  Not Reviewed   
  Not Available

Preparer's Name: \_\_\_\_\_   
 Preparer's Title: \_\_\_\_\_  
 Address: \_\_\_\_\_   
 City: \_\_\_\_\_   
 Zip: \_\_\_\_\_   
 Phone: \_\_\_\_\_

**Inspection Type**

Prior to Certificate of Occupancy   
 Special Investigation   
 Response to Complaint  
 Routine Inspection (Annual)   
 Follow-up Inspection

**CHECKLIST FOR ROUTINE SOURCE CONTROL BMPs**

Requirement	No. of BMPs (if Applicable)	BMP in place per approved LID Plan/SUSMP?	Corrective Action Required
Storm Drain System Stenciling/Signage		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Outdoor Material Storage Areas		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Trash Storage Areas		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Efficient Irrigation Systems & Landscape Design		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Protect Slopes & Channels		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Loading Dock Areas		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Maintenance Bays		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Vehicle Wash Areas		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Outdoor Process Areas		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Equipment Wash Areas		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Fueling Areas		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Hillside Landscaping		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Wash-water Controls for Food Prep Areas		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Community Car Wash Racks		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No

**CHECKLIST FOR STRUCTURAL BMPs**

Requirement	No. of BMPs (if Applicable)	BMP in place per approved LID Plan/SUSMP?	Corrective Action Required
Infiltration Trench/Basin		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Infiltration Well/Dry Well		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Detention Basin		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Porous Pavement		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Bio-infiltration		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Vegetated Swale		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Bio-filtration		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Proprietary Control Measure (describe):		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Media Filtration		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Filter Insert		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Regional or Watershed BMPs		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Other (describe):		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No

**INSPECTION RESULTS:**

- Visible / No Apparent Problems
- BMP Failure
- Significant Engineering / Design Flaws
- Unauthorized Modifications
- BMP Missing / Removed / Not Located
- Trash / Debris Exceeding Cap. (bypass)
- Evidence of Pollution / Dumping
- Vector Control Issues (Mosquitoes)
- Inadequate Maintenance

**DESCRIPTION OF CORRECTIVE ACTION(S) REQUIRED:**

**CORRECTIVE ACTION NOTICE (IF REQUIRED)**

If any corrective actions have been noted above, then based on this verification inspection, you are in noncompliance with Municipal Code Chapter [       -       ]. You must implement the required corrective action(s) by:

\_\_\_\_\_   
 Corrective Action Due Date

**After this date, your facility will be re-inspected to verify that all necessary corrective measures have been taken. FAILURE TO IMPLEMENT THE CORRECTIVE ACTION(S) WILL SUBJECT YOU TO ELEVATED ENFORCEMENT, WHICH CAN INCLUDE INFRACTION OR MISDEMEANOR PENALTIES.**

**ACKNOWLEDGEMENT OF RECEIPT OF CORRECTIVE ACTION NOTICE**


\_\_\_\_\_   
 Contact Signature

\_\_\_\_\_   
 Printed Name

\_\_\_\_\_   
 Date



# STORMWATER PLANNING PROGRAM PRIORITY PROJECT CHECKLIST



Project Name	Owner Name	Developer Name
Project Address	Owner Address	Developer Address
Plan Check #	Owner Phone	Developer Phone

## TYPE OF PROJECT

Does the proposed project fall into one of the following categories? Please check Yes/No	YES	NO
--	-----	----

### PRIORITY PROJECTS

1. A new project equal to 1 acre or greater of disturbed area and adding more than 10,000 square feet of impervious* surface area		
2. A new industrial park with 10,000 square feet or more of surface area		
3. A new commercial mall with 10,000 square feet or more surface area		
4. A new retail gasoline outlet with 5,000 square feet or more of surface area		
5. A new restaurant (SIC 5812) with 5,000 square feet or more of surface area		
6. A new parking lot with either 5,000 ft <sup>2</sup> or more of impervious* surface or with 25 or more parking spaces		
7. A new automotive service facility (SIC 5013, 5014, 5511, 5541, 7532-7534 and 7536-7539) with 5,000 square feet or more of surface area		
8. Projects located in or directly adjacent to, or discharging directly to a Significant Ecological Area (SEA)*, where the development will: <ul style="list-style-type: none"> <li>a. Discharge stormwater runoff that is likely to impact a sensitive biological species or habitat; and</li> <li>b. Create 2,500 square feet or more of impervious surface area</li> </ul>		
9. Redevelopment*		

### SPECIAL PROVISION PROJECTS

10. Green street* project		
11. Single family hillside* home		

If checked YES, numerical criteria will apply to items 1,2,6-9 and items 3-5 (for project areas of 5,000 ft<sup>2</sup> or more of surface area.) If any of the boxes are checked YES, this project will require the preparation of a Low Impact Development (LID) Plan and a Maintenance Agreement Transfer\*

\* Defined on back.

\_\_\_\_\_

Applicant Name

\_\_\_\_\_

Applicant Signature

\_\_\_\_\_

Applicant Title

\_\_\_\_\_

Date

## DEFINITIONS:

**Impervious** are those surfaces that do not allow stormwater runoff to percolate into the ground. Typical impervious surfaces include: concrete, asphalt, roofing materials, etc. However, some specially designed concrete/asphalt do allow water to percolate (pervious).

**Hillside** means property where the slope is 25% or greater and where grading contemplates cut or fill slopes. Single family hillside homes will require a less extensive plan. During the construction of a single-family hillside home, the following measures are implemented:

- a. Conserve natural areas
- b. Protect slopes and channels
- c. Provide storm drain system stenciling and signage
- d. Divert roof runoff to vegetated areas before discharge unless the diversion would result in slope instability
- e. Direct surface flow to vegetated areas before discharge unless the diversion would result in slope instability.

**Green Streets** means any street and road construction of 10,000 square feet or more of impervious surface area

- a. These projects will follow an approved green streets manual to the maximum extent practicable. Street and road construction applies to standalone streets, roads, highways, and freeway projects, and also applies to streets within larger projects. Stormwater mitigation measures must be in compliance with the approved green streets manual requirements.

**Redevelopment** means land-disturbing activities that result in the creation, addition, or replacement of 5,000 ft<sup>2</sup> or more of impervious surface area on an already developed site.

Redevelopment does not include routine maintenance activities that are conducted to maintain the original line and grade, hydraulic capacity, or original purpose of facility, nor does it include modifications to existing single family structures, or emergency construction activities required to immediately protect public health and safety.

**Significant Ecological Area** means an area in which plant or animal life or their habitats are either rare or especially valuable because of their special nature or role in an ecosystem and would be disturbed or degraded by human activities and developments. Also, an area designated by the City as approved by the Regional Water Quality Control Board.

**Maintenance Agreement and Transfer:** All developments subject to LID and site specific plan requirements provide verification of maintenance provisions for Structural and Treatment Control BMPs, including but not limited to legal agreements, covenants, CEQA mitigation requirements, and/or conditional use permits. Verification at a minimum shall include:

- The developer's and/or owner's signed statement accepting responsibility for maintenance until the responsibility is legally transferred; and
- A signed statement from the public entity assuming responsibility for Structural or Treatment Control BMP maintenance and conduct a maintenance inspection at least once a year; or
- Written conditions in the sales or lease agreement, which requires the recipient to assume responsibility for maintenance and conduct a maintenance inspection at least once a year; or
- Written text in project conditions, covenants and restrictions (CCRs) for residential properties assigning maintenance responsibilities to the Home Owners Association for maintenance of the Structural and Treatment Control BMPs; or
- Any other legally enforceable agreement that assigns responsibility for the maintenance of post-construction Structural or Treatment Control BMPs.



**STORMWATER PLANNING PROGRAM**  
**PRIORITY DEVELOPMENT & REDEVELOPMENT PROJECTS**  
**PLAN CHECK # \_\_\_\_\_**

**FORM**  
**P1**

Project Name _____
Project Location _____
Company Name _____
Address _____
Contact Name / Title _____
Phone / FAX / Email _____

**GENERAL PROJECT CERTIFICATION**

*A completed original of this form must accompany all LID Plan submittals.*

**Best Management Practices (BMPs) have been incorporated into the design/maintenance/construction of this project to accomplish the following:**

1. Minimize impacts from stormwater runoff on the biological integrity of Natural Drainage Systems and water bodies in accordance with requirements under CEQA (Cal. Pub. Resources Code § 21100), CWC § 13369, CWA § 319, CWA § 402(p), CWA § 404, CZARA § 6217(g), ESA § 7, and local government ordinances.
2. Maximize the percentage of pervious surfaces to allow more percolation of stormwater into the ground.
3. Minimize the amount of stormwater directed to impermeable surfaces and to the MS4.
4. Minimize pollution emanating from parking lots through the use of appropriate Treatment Control BMPs and good housekeeping practices.
5. Minimize breeding of Vectors
6. Reduce pollutant loads in stormwater from the development site.

I certify that this Low Impact Development Plan and all attachments were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gathered/evaluated the information submitted.

**Post Construction / Maintenance Certification**

As the responsible party, I certify that the proposed BMPs will be implemented, monitored and maintained to ensure their continued effectiveness. In the event of a property transfer, the new owner/lessee will be notified of the BMPs in use at this site and I will include written conditions in the sales or lease agreement, which requires the new owner (or lessee) to assume responsibility for maintenance and conduct a maintenance inspection at least once a year. The information contained herein is, to the best of my knowledge and belief, true, accurate, and complete.

In consideration of the execution of City of [Insert City] approval of the proposed Low Impact Development (LID) Plan including any proposed treatment system, the applicant hereby agrees to indemnify, save and keep the City of [Insert City], its officers, agents and employees free and harmless from and against any and all claims for injury, damage, loss, liability, cost and expense of any nature whatsoever, which the City of [Insert City], its officers, agents, or employees may suffer, sustain, incur, pay out as a result of any and all actions, suits, proceedings, claims and demands which may be brought, made, or filed against the City of [Insert City], its officers, agents or employees by reason of or arising out of, or in any manner connected with any and all operations permitted by this approval. This indemnification extends to further agree that the City of [Insert City] is not responsible for any additional requirements or restrictions due to changes in regulations, policies or enforcement practices of the California Regional Water Quality Control Board, or any other applicable regulatory agencies.

\_\_\_\_\_  
 Property Owner Name

\_\_\_\_\_  
 Property Owner Signature

\_\_\_\_\_  
 Applicant Title

\_\_\_\_\_  
 Date

## PLANNING BEST MANAGEMENT PRACTICES

BMP Name	BMP Identification Number and Name	✓ if to be used
Car Wash Facility	<a href="#">SC-21</a> : Vehicle and Equipment Cleaning	
Constructed Wetlands	<a href="#">MP-20</a> : Wetlands	
Control of Impervious Runoff	-N/A-	
Efficient Irrigation	-N/A-	
Energy Dissipaters	<a href="#">EC-10</a> : Velocity Dissipation Devices	
Extended Detention Basins	<a href="#">TC-22</a> : Extended Detention Basin	
Infiltration Basins	<a href="#">TC-11</a> : Infiltration Basins	
Infiltration Trenches	<a href="#">TC-10</a> : Infiltration Trenches	
Inlet Trash Racks	-N/A-	
Landscape Design	<a href="#">EC-2</a> : Preservation of Existing Vegetation <a href="#">EC-4</a> : Hydro seeding <a href="#">EC-6</a> & <a href="#">EC-8</a> : Straw & Wood Mulching	
Linings for Urban Runoff Conveyance Channels	-N/A-	
Materials Management	<a href="#">SC-30</a> : Outdoor Loading/Unloading	
Media Filtration	<a href="#">TC-40</a> : Media Filter	
Motor Fuel Concrete Dispensing Areas	<a href="#">SC-20</a> : Vehicle and Equipment Fueling	
Motor Fuel Dispensing Area Canopy	<a href="#">SC-20</a> : Vehicle and Equipment Fueling	
Water Quality Inlets	<a href="#">TC-50</a> : Water Quality Inlet	
Outdoor Storage	<a href="#">SC-31</a> : Outdoor Liquid Container Storage <a href="#">SC-33</a> : Outdoor Storage of Raw Materials	
Porous Pavement and/or Alternative Surfaces	-N/A-	
Protect Slopes and Channels	<a href="#">EC-11</a> : Slope Drains <a href="#">EC-12</a> : Streambank Stabilization	
Self-Contained Areas for Vehicle or Equipment Washing, Steam Cleaning, Maintenance, Repair, or Material Processing	<a href="#">SC-21</a> : Vehicle and Equipment Cleaning <a href="#">SC-22</a> : Vehicle and Equipment Repair <a href="#">SC-32</a> : Outdoor Equipment Operations	
Storm Drain System Stenciling and Signage	<a href="#">SC-34</a> : Waste Handling and Disposal (Signage Section)	
Trash Container Areas	<a href="#">SC-34</a> : Waste Handling and Disposal	
Vegetated Swales and Strips	<a href="#">TC-32</a> : Bioretention	
Wet Ponds	<a href="#">TC-20</a> : Wet Ponds	
Other:	<ul style="list-style-type: none"> <li>•</li> <li>•</li> <li>•</li> <li>•</li> <li>•</li> </ul>	

**Please refer to the California Storm Water Best Management Practice Handbooks for more information.**



# STORMWATER TREATMENT CERTIFICATION

FORM  
**P2**

**SITE NAME and ADDRESS**

**APPROXIMATE PROJECT CHARACTERISTICS**

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Plan Check # \_\_\_\_\_

Planning # \_\_\_\_\_

Roofed Area \_\_\_\_\_ ft<sup>2</sup>

Roadway/Parking Area (exposed) \_\_\_\_\_ ft<sup>2</sup>

Landscaped/Vegetation \_\_\_\_\_ ft<sup>2</sup>

Other Ground Level Impervious Areas  
(Ex: Outdoor work or storage areas) \_\_\_\_\_ ft<sup>2</sup>

Other: \_\_\_\_\_ ft<sup>2</sup>

**TOTAL** \_\_\_\_\_ ft<sup>2</sup>

## STRUCTURAL/TREATMENT BMPs

(attach additional sheets as necessary) or see back

Area Designation (must correspond with plans)	Tributary Area (ft <sup>2</sup> )	Average Impervious Factor	Estimated Flow Rate or Volume*	Anticipated Potential Pollutants	Type of BMP (include size, make, and model, if any)	BMP Location (briefly describe)	Design Treatment Flow Rate or Volume Capacity

**By stamping this form, I acknowledge that each treatment BMP is provided with adequate bypass or overflow so as not to contribute to localized flooding or soil instability.**

\*Flow rates and volumes based on the 0.75 inch, 24-hour rain event or the 85th percentile, 24-hour rain event, whichever is greater.

**I certify that I am a Professional Civil Engineer registered in the State of California, and that the treatment methods and capacities herein comply with the requirements established by the California Regional Water Quality Control Board, Los Angeles Region, and the State Water Resources Control Board for Low Impact Development (LID) Plans.**

**Affix Registered Engineer Wet Ink Stamp Here:**



\_\_\_\_\_

**Print Name**                      **Signature**                      **Date**





# OWNER'S CERTIFICATION MINIMUM BMPs FOR ALL CONSTRUCTION SITES



PLAN CHECK # \_\_\_\_\_

Project Name _____ Project Location _____	BUILDING/GRADING PERMIT NUMBER _____
Owner Name _____ Address _____ Phone _____ FAX/Email _____	Contractor Name _____ Address _____ Phone _____ FAX/Email _____

The National Pollutant Discharge Elimination System (NPDES) is the portion of the Clean Water Act that applies to the protection of receiving waters. Under permits from the Los Angeles Regional Water Quality Control Board (RWQCB), certain activities are subject to RWQCB enforcement. To meet the requirements of the Los Angeles County Municipal Stormwater Permit (CAS004001), minimum requirements for sediment control, erosion control and construction activities must be implemented on each project site. Minimum requirements include:

- **EROSION CONTROL:** Erosion from slopes and channels shall be controlled by implementing an effective combination of BMPs, such as the limiting of grading activities during the wet season; inspecting graded areas during rain events; planting and maintenance of vegetation on slopes; and covering erosion susceptible slopes.
- **SEDIMENT CONTROL:** Eroded sediments from areas disturbed by construction and from stockpiles of soil shall be retained on site to minimize sediment transport from the site to streets, drainage facilities and/or adjacent properties via runoff, vehicle tracking or wind.
- **NON-STORMWATER MANAGEMENT:** Non-stormwater runoff from equipment and vehicle washing and any other activity shall be contained at the project site.
- **WASTE MANAGEMENT:** Construction related materials, wastes, spills or residues shall be retained on site to minimize transport from the site to streets, drainage facilities or adjoining properties by wind or runoff. Runoff from equipment and vehicle washing shall be contained at construction sites unless treated to remove sediment and pollutants.

*Examples of Minimum BMPs include: (1) Soil piles must be covered with tarps or plastic, (2) leaking equipment must be repaired immediately, (3) refueling must be conducted away from catch basins, (4) catch basins must be protected when working nearby, (5) vacuum all concrete saw cutting, (6) never wash concrete waste into the street, (7) keep the site clean, sweep the gutters at the end of each working day and keep a trash receptacle on site.*

As the architect/engineer of record, I have selected appropriate BMPs to effectively minimize the negative impacts of this project's construction activities on stormwater quality. The project owner and contractor are aware that the selected BMPs shall be installed, monitored, and maintained to ensure their effectiveness. The BMPs not selected for implementation are redundant or deemed not applicable to the proposed construction activity.

\_\_\_\_\_  
Architect/Engineer of Record Name  
\_\_\_\_\_  
Title

\_\_\_\_\_  
Architect/Engineer of Record Signature  
\_\_\_\_\_  
Date

I certify that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is true, accurate, and complete. I am aware that submitting false and/ or inaccurate information, failing to update the ESCP to reflect current conditions, or failing to properly and/ or adequately implement the ESCP may result in revocation of grading and/ or other permits or other sanctions provided by law.

\_\_\_\_\_  
Landowner or Landowner's Agent Name  
\_\_\_\_\_  
Title

\_\_\_\_\_  
Landowner or Landowner's Agent Signature  
\_\_\_\_\_  
Date



# EROSION AND SEDIMENT CONTROL PLAN (ESCP) REVIEW CHECKLIST

These requirements apply to all activities involving soil disturbance with the exception of agricultural activities. Applicable activities include but are not limited to grading, vegetation clearing, soil compaction, paving, re-paving and linear underground/overhead projects (LUPs).

Prior to issuing a grading or building permit, each operator of a construction activity within its jurisdiction must prepare and submit an ESCP prior to the disturbance of land.

Contact Name:	Tracking #:
Contact Title:	Site Name:
Company Name:	Site Address:
Mailing Address:	Type of Facility:
City, State, Zip:	Submittal Date:
Phone Number:	Plan Return Date:
Fax Number:	Disturbed Area:

First Review

ESCP Received on:

Review Completed on:

Second Review

ESCP Received on:

Review Completed on:

Third Review

ESCP Received on:

Review Completed on:

Fourth Review

ESCP Received on:

Review Completed on:

Fifth Review

ESCP Received on:

Review Completed on:

Sixth Review

ESCP Received on:

Review Completed on:

ESCP Review Checklist

ESCP REQUIREMENT	SATISFACTION			COMMENTS
	YES	NO	N/A	
<b>General Information</b>				
Contact information (e.g., name, address, phone, email, etc.) provided for the owner and contractor.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Basic site information including location, status, size of the project and area of disturbance is provided.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Proof of existing coverage under applicable permits, including, but not limited to the State Water Board's Construction General Permit, and State Water Board 401 Water Quality Certification.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Meets the minimum requirements of the jurisdictional erosion and sediment control ordinance.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes the elements of a Storm Water Pollution Prevention Plan (SWPPP) prepared in accordance with the requirements of the Construction General Permit.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Developed and certified by a Qualified SWPPP Developer (QSD).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Identifies the proximity all water bodies, water bodies listed as impaired by sediment-related pollutants, and water bodies for which a sediment-related TMDL has been adopted and approved by the USEPA.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Identifies any significant threat to water quality status, based on consideration of factors listed in Appendix 1 to the Construction General Permit.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
The project start date and anticipated completion date is provided.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes Identification of site Risk Level as identified per the requirements in Appendix 1 of the Construction General Permit.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Contains a language signed by the landowner or the landowner's agent stating as follows:  <i>"I certify that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is true, accurate, and complete. I am aware that submitting false and/ or inaccurate information, failing to update the ESCP to reflect current conditions, or failing to properly and/ or adequately implement the ESCP may result in revocation of grading and/ or other permits or other sanctions provided by law."</i>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

ESCP REQUIREMENT	SATISFACTION			COMMENTS
	YES	NO	N/A	
<b>Best Management Practices</b>				
All structural BMPs are designed by a licensed California Engineer.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes Sediment/Erosion Control.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes controls to prevent tracking on and off the site.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes non-stormwater controls (e.g., vehicle washing, dewatering, etc.).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes Materials Management (delivery and storage).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes Spill Prevention and Control.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes Waste Management (e.g., concrete washout/waste management; sanitary waste management).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes methods to minimize the footprint of the disturbed area and to prevent soil compaction outside of the disturbed area.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes methods used to protect native vegetation and trees.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Includes the rationale for the selection and design of the proposed BMPs, including quantifying the expected soil loss from different BMPs.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Post-Construction Structural BMPs subject to Operation and Maintenance Requirements are identified.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
<b>Site Plan</b>				
Full sized plans showing the site with all proposed BMPs and water quality notes have been signed and stamped with wet ink application by the appropriate individual.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Plan includes a title block containing at least the project name, address, and owner.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
All figures, maps, plot plans, etc. have a legend, including a North arrow and scale.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
All facilities are labeled for the intended function.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
All areas of outdoor activity are labeled.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
All structural BMPs are indicated.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Drainage flow information depicted.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Project location shown.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Site boundary indicated.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

# Agency Standard Operating Procedures

Each agency will use the suggested language below to develop, implement, and revise as necessary agency-specific Standard Operating Procedures (SOPs) that identify the procedures each agency will follow.

## CGP Coverage Verification

- Verification of active coverage under the Construction General Permit for sites disturbing 1 acre or more, or that are part of a planned development that will disturb 1 acre or more and a process for referring non-filers to the Regional Water Board.

Prior to releasing any permits relating to and/or allowing for construction activities on a site resulting in one (1) acre or more of soil disturbance, a Notice of Intent (NOI), a Storm Water Pollution Prevention Plan (SWPPP), and all other Permit Registration Documents (PRDs) must be filed with the Regional Water Resources Control Board (Regional Board) through the State Water Board's Storm water Multi-Application and Report Tracking System (SMARTS) website and a Waste Discharge ID (WDID) number must be obtained from the Regional Board. This requirement will be included as a condition of approval. In cases where construction activities have commenced on a qualifying site and the project has not yet filed all PRDs (along with an explanation for filing late) with the Regional Board, a Notice of Violation (NOV) will be sent to the responsible person. Any work orders released will be stopped and fines may be enforced. The Regional Board will be notified of the discharger's non-compliance. Work will not be allowed to commence until the NOI has been accepted by the Regional Board and WDID number issued.

## ESCP Review

- Review of the applicable ESCP and inspection of the construction site to determine whether all BMPs have been selected, installed, implemented, and maintained according to the approved plan and subsequent approved revisions.

Prior to issuing a grading or building permit, each operator of a construction activity within its jurisdiction must prepare and submit an Erosion and Sediment Control Plan (ESCP) prior to the disturbance of land. The ESCP Requirement Checklist will be used to ensure required information is submitted by the responsible person. These requirements apply to all activities involving soil disturbance with the exception of agricultural activities. Applicable activities include but are not limited to grading, vegetation clearing, soil compaction, paving, re-paving and linear underground/overhead projects (LUPs).

## BMP Assessment

- Assessment of the appropriateness of the planned and installed BMPs and their effectiveness.

Prior to releasing any permits relating to and/or allowing for construction activities on a site resulting in one (1) acre or more of soil disturbance a Qualified SWPPP Practitioner (QSP) must be identified by the developer. Prior to beginning any construction activities, the QSP must review the ESCP and determine if the following requirements are being met:

1. Erosion and sediment controls are incorporated to provide effective reduction or elimination of sediment related pollutants in stormwater discharges and authorized non-stormwater discharges from the site.

2. Sediment controls are designed to intercept and settle out soil particles that have been detached and transported by the force of water.
3. Non-stormwater control BMPs are selected to control sediment on the construction site.
4. Materials and waste management pollution control BMPs are incorporated to minimize stormwater contact with construction materials, wastes and service areas; and to prevent materials and wastes from being discharged off-site.

If the QSP identifies potential problematic areas of the ESCP, a revision to the ESCP must be submitted for review and approval.

Once the BMPs are installed, inspections must be conducted at the frequency identified in the Watershed Management Program (WMP). All BMPs not functioning as intended must be repaired, replaced, or changed to a more effective BMP. Inspection and maintenance procedures must be in accordance with the CASQA handbook.

### **Discharge Reporting**

- Visual observation and record keeping of non-stormwater discharges, potential illicit discharges and connections, and potential discharge of pollutants in stormwater runoff.

Any non-stormwater discharges, potential illicit discharges and connections, and potential discharge of pollutants in stormwater runoff will be tracked and kept on record.

Public reporting of illicit discharges or water quality impacts associated with discharges into or from MS4s within this jurisdiction will be conducted. Multiple modes of communication are in place to allow for complaints and spill reporting. When a complaint is received it will be documented and tracked to ensure that all complaints are adequately addressed.

A Spill Response Plan will be implemented for all sewage and other spills that may discharge into the MS4 within this jurisdiction. Coordination with spill response teams will be observed throughout all appropriate departments, programs, and agencies so that maximum water quality protection is provided. All spill complaints will be investigated within one business day of receiving the complaint and a response to spills for containment will be conducted within 4 hours of becoming aware of the spill, except where such spills occur on private property, in which case the response should be within 2 hours of gaining legal access to the property. Spills that may endanger health or the environment will be reported to appropriate public health agencies and the Office of Emergency Services (OES).

A training program regarding the identification of illicit connections/illicit discharges (IC/IDs) for all municipal field staff, who, as part of their normal job responsibilities (e.g., street sweeping, storm drain maintenance, collection system maintenance, road maintenance), may come into contact with or otherwise observe an illicit discharge or illicit connection to the MS4 will be provided.

### **Construction Inspection Reporting and Tracking**

- Development of a written or electronic inspection report generated from an inspection checklist used in the field.
- Tracking of the number of inspections for the inventoried construction sites throughout the reporting period to verify that the sites are inspected at the minimum frequencies required.

Inspections will be conducted at a frequency listed in the Watershed Management Program (WMP). Inspection checklists and/or reports will be utilized to determine and keep record of whether or not all

BMPs have been selected, installed, implemented, and maintained according to the approved plan and subsequent approved revisions. These checklists/reports will be retained for at least three (3) years following NOT approval.

DRAFT

**(CITY NAME) STORMWATER INSPECTION REPORT FOR CONSTRUCTION SITES**

SITES ONE ACRE OR GREATER

Project Name:		Address:	
Area disturbed:		WDID:	SWPPP on-site: <input type="checkbox"/> Yes <input type="checkbox"/> No
Risk level: <input type="checkbox"/> Low (Risk 1) <input type="checkbox"/> Medium (Risk 2) <input type="checkbox"/> High (Risk 3)	Erosion & Sediment Control Plan (ESCP) on-site: <input type="checkbox"/> Yes <input type="checkbox"/> No		
Phase: <input type="checkbox"/> Prior to Land Disturbance <input type="checkbox"/> Active construction <input type="checkbox"/> Site stabilization			
Developer/Contractor:		Phone number:	
Contact:		Title:	
Inspector:		Date:	
Inspection: <input type="checkbox"/> Routine (monthly and for each phase of construction) <input type="checkbox"/> Follow-up <input type="checkbox"/> Response to complaint		For sites discharging to a waterbody impaired for sediment/turbidity: <input type="checkbox"/> Routine biweekly <input type="checkbox"/> Predicted rainfall <input type="checkbox"/> Recent rainfall	

**CHECKLIST FOR STORMWATER BMP (BEST MANAGEMENT PRACTICE) COMPLIANCE**

**PHASE 1 AND 2: PRIOR TO LAND DISTURBANCE AND DURING ACTIVE CONSTRUCTION**

Comment		Yes	No	N/A	Comment		Yes	No	N/A
Erosion Control	1. Erosion controls are implemented in accordance with the ESCP	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Waste Management	9. Effective material delivery and storage practices are implemented	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	2. Erosion observed	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		10. Spill prevention and control practices are implemented	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Sediment Control	3. Sediment controls are implemented in accordance with the ESCP	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		11. Stockpile controls are implemented in accordance with the ESCP	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	4. Sediment discharge observed	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		12. Solid waste controls are implemented in accordance with the ESCP	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Additional Controls	5. Tracking controls (tire washout, stabilized entrances, exits and roadways) are implemented in accordance with the ESCP	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Nonstormwater Management	13. Vehicle and equipment washing, fueling and maintenance controls are implemented in accordance with the ESCP	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	6. Sediment in roads observed	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		14. Nonstormwater discharges observed	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	7. Wind erosion controls are implemented in accordance with the ESCP	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		15. Dewatering operations covered under NPDES Permit CAG994004	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	8. Wind erosion observed	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		16. Water conservation practices are implemented	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**PHASE 3: FINAL LANDSCAPING/SITE STABILIZATION**

Comment	Yes	No	N/A	Comment	Yes	No	N/A
1. Graded areas have reached final stabilization	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	3. Temporary erosion and sediment BMPs are removed	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. Trash, debris and construction materials are removed	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	4. Post-construction BMPs are installed	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**COMMENTS AND CORRECTIVE ACTIONS (IF REQUIRED):**


**ENFORCEMENT:**  None required  Corrective Action Notice (complete section below)  Other (see comments)

**CORRECTIVE ACTION NOTICE (IF REQUIRED)**

If corrective actions have been noted above, then the responsible party (facility owner, occupant or person responsible) is in noncompliance with the City's Stormwater Quality Ordinance. The responsible party may be subject to enforcement actions under this program if the corrective actions are not implemented by:

\_\_\_\_\_ Corrective Action Due Date

**ACKNOWLEDGEMENT OF RECEIPT OF CORRECTIVE ACTION NOTICE**

\_\_\_\_\_ Site Representative Signature

\_\_\_\_\_ Printed Name

\_\_\_\_\_ Date

---

<sup>i</sup> For sites discharging to a tributary listed by the state as an impaired waterbody for sediment or turbidity under CWA § 303(d), or determined to be a threat to water quality, inspections must be conducted (1) when two or more consecutive days with greater than 50% chance of rainfall are predicted by NOAA and (2) within 48 hours of a ½-inch rain event and (3) at least once every two weeks.

DRAFT



**CITY STORMWATER QUALITY PROGRAM  
CONSTRUCTION SITE INSPECTION REPORT**

FOR SITES LESS THAN ONE ACRE

Project:	Address:
Contact:	Title:
Contractor:	Phone:
Inspector:	Date:

**CHECKLIST FOR STORMWATER BMP (BEST MANAGEMENT PRACTICE) COMPLIANCE**

Question		Yes	No	N/A	Question		Yes	No	N/A
Erosion Control	1. Effective erosion controls implemented.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Non-Stormwater Management	5. Water conservation practices are implemented.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	2. Erosion observed.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		6. Dewatering operations covered under NPDES Permit CAG994004	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Sediment Control	3. Effective sediment controls implemented.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Waste Management	7. Effective material delivery/storage practices and spill prevention/control practices are implemented.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	4. Sediment discharge observed.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		8. Effective waste management controls are implemented.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**COMMENTS AND CORRECTIVE ACTIONS (IF REQUIRED):**


**ENFORCEMENT:**     None required     Corrective Action Notice (complete section below)     Other (see comments)

**CORRECTIVE ACTION NOTICE (IF REQUIRED)**

If corrective actions have been noted above, then the responsible party (facility owner, occupant or person responsible) is in noncompliance with the City's Stormwater Quality Ordinance. The responsible party may be subject to enforcement actions under this program if the corrective actions are not implemented by:

\_\_\_\_\_ Corrective Action Due Date

**ACKNOWLEDGEMENT OF RECEIPT OF CORRECTIVE ACTION NOTICE**

_____ Site Representative Signature	_____ Printed Name	_____ Date
-------------------------------------	--------------------	------------

### **Example Lease Language for Fixed Facilities**

The following is example language that can be inserted into municipal leases:

*The Los Angeles Regional Water Quality Control Board (RWQCB) has issued permits which govern stormwater and non-stormwater discharges resulting from municipal activities performed by or for the Coastal Watersheds of Los Angeles County, including the Los Angeles County Flood Control District, the County of Los Angeles, and 84 incorporated cities within the coastal watersheds of Los Angeles County with the exception of Long Beach (collectively referred to as Permittees). The RWQCB Permit is a National Pollutant Discharge Elimination System (NPDES) Permit No. R4-2023-0175. A Copy of the RWQCB Permit is available for review.*

*In order to comply with the Permit requirements, the Permittees have developed a Watershed Management Program (WMP) which contains Public Agency Facilities and Activities Maintenance Procedures (Maintenance Procedures) with Best Management Practices (BMPs) adopted from the Caltrans Storm Water Quality Handbook Maintenance Staff Guide (Caltrans Handbook) that parties leasing municipally owned properties must adhere to. These Maintenance Procedures contain pollution prevention and source control techniques to minimize the impact of those activities upon dry-weather urban runoff, stormwater runoff, and receiving water quality.*

*Activities performed at the facility leased under this agreement shall conform to the RWQCB NPDES Permit, the WMP, and the CalTrans Handbook, and must be performed as described within all applicable Maintenance Procedures. The holder of this agreement shall fully understand the Maintenance Procedures applicable to activities conducted at the facility leased under this agreement prior to conducting them and maintain copies of the Maintenance Procedures at the leased facility throughout the agreement duration. The applicable Maintenance Procedures are included as Exhibit  of this agreement.*

*Evaluation of activities subject to WMP requirements performed at the facility leased under this agreement will be conducted by the city to verify compliance with Maintenance Procedures, and may be required through lessor self-evaluation as determined by the city.*

### **Example Contract Language for Field Programs**

The following is example language that can be inserted into municipal field program contracts:

*The Los Angeles Regional Water Quality Control Board (RWQCB) has issued permits which govern stormwater and non-stormwater discharges resulting from municipal activities performed by or for the Coastal Watersheds of Los Angeles County, including the Los Angeles County Flood Control District, the County of Los Angeles, and 84 incorporated cities within the coastal watersheds of Los Angeles County with the exception of Long Beach (collectively referred to as Permittees). The RWQCB Permit is a National Pollutant Discharge Elimination System (NPDES) Permit No. R4-2023-0175. A Copy of the RWQCB Permit is available for review.*

*In order to comply with the Permit requirements, the Permittees have developed a Watershed Management Program (WMP) which contains Public Agency Facilities and Activities Maintenance Procedures (Maintenance Procedures) with Best Management Practices (BMPs) adopted from the Caltrans Storm Water Quality Handbook Maintenance Staff Guide (Caltrans Handbook) that parties leasing municipally owned properties must adhere to. These Maintenance Procedures contain pollution prevention and source control techniques to minimize the impact of those activities upon dry-weather urban runoff, stormwater runoff, and receiving water quality.*

*Work performed under this CONTRACT shall conform to the RWQCB NPDES Permit, the WMP, and the CalTrans Handbook, and must be performed as described within all applicable Maintenance Procedures. The CONTRACTOR shall fully understand the Maintenance Procedures applicable to activities that are being conducted under this CONTRACT prior to conducting them and maintain copies of the Maintenance Procedures throughout the CONTRACT duration. The applicable Model Maintenance Procedures are included as Exhibit      of this CONTRACT.*

*Evaluation of activities subject to WMP requirements performed under this CONTRACT will be conducted to verify compliance with the Maintenance Procedures, and may be required through CONTRACTOR self-evaluation as determined by the city.*

# Significant Ecological Areas

December 2009

### LEGEND:

- Freeway
- Significant Ecological Area (SEA)
- National Forest Boundary
- Unincorporated Area
- Incorporated City

### Significant Ecological Areas

- |   |   |
|---|---|
| SEA-1 Malibu Coastline                    | SEA-32 Agua Arriaga Canyon                  |
| SEA-2 Point Dume                          | SEA-33 Terman Island                        |
| SEA-3 Santa Monica                        | SEA-34 Palms Vistas Canyons                 |
| SEA-4 Upper La Brea Canyon                | SEA-35 Harbor Lake Regional Park            |
| SEA-5 Malibu Canyon and Lagoon            | SEA-36 Malibu Island                        |
| SEA-6 Los Angeles                         | SEA-37 Griffith Park                        |
| SEA-7 Hollywood                           | SEA-38 Santa Monica                         |
| SEA-8 Malibu Coast State Park Buffer Area | SEA-39 Verdugo Mountains                    |
| SEA-9 Cold Creek                          | SEA-40 Inglewood Mountains Dam County       |
| SEA-10 Santa Monica                       | SEA-41 Inglewood Mountains Dam County       |
| SEA-11 Terman Road-Sullivan Canyons       | SEA-42 Inglewood Mountains Dam County       |
| SEA-12 Path-Camacho Canyon                | SEA-43 Rio Hondo College Wildlife Sanctuary |
| SEA-13 Chatsworth Reservoir               | SEA-44 Sylmar and Tulevil Canyons           |
| SEA-14 San Hills                          | SEA-45 Chatsworth Reservoir                 |
| SEA-15 Tujunga Canyon (San Jose Hills)    | SEA-46 Chatsworth Reservoir                 |
| SEA-16 Inglewood Peak-San Jose Hills      | SEA-47 Chatsworth Reservoir                 |
| SEA-17 Chatsworth Canyon-Puebla Hills     | SEA-48 Chatsworth Reservoir                 |
| SEA-18 San Francisco Canyon               | SEA-49 Chatsworth Reservoir                 |
| SEA-19 San Gabriel Mountains              | SEA-50 Chatsworth Reservoir                 |
| SEA-20 Santa Monica Mountains             | SEA-51 Chatsworth Reservoir                 |
| SEA-21 Santa Monica Mountains             | SEA-52 Chatsworth Reservoir                 |
| SEA-22 Santa Monica Mountains             | SEA-53 Chatsworth Reservoir                 |
| SEA-23 Santa Monica Mountains             | SEA-54 Chatsworth Reservoir                 |
| SEA-24 Santa Monica Mountains             | SEA-55 Chatsworth Reservoir                 |
| SEA-25 Santa Monica Mountains             | SEA-56 Chatsworth Reservoir                 |
| SEA-26 Santa Monica Mountains             | SEA-57 Chatsworth Reservoir                 |
| SEA-27 Santa Monica Mountains             | SEA-58 Chatsworth Reservoir                 |
| SEA-28 Santa Monica Mountains             | SEA-59 Chatsworth Reservoir                 |
| SEA-29 Santa Monica Mountains             | SEA-60 Chatsworth Reservoir                 |
| SEA-30 Santa Monica Mountains             | SEA-61 Chatsworth Reservoir                 |
| SEA-31 Santa Monica Mountains             | SEA-62 Chatsworth Reservoir                 |
| SEA-32 Santa Monica Mountains             | SEA-63 Chatsworth Reservoir                 |
| SEA-33 Santa Monica Mountains             | SEA-64 Chatsworth Reservoir                 |
| SEA-34 Santa Monica Mountains             | SEA-65 Chatsworth Reservoir                 |
| SEA-35 Santa Monica Mountains             | SEA-66 Chatsworth Reservoir                 |
| SEA-36 Santa Monica Mountains             | SEA-67 Chatsworth Reservoir                 |
| SEA-37 Santa Monica Mountains             | SEA-68 Chatsworth Reservoir                 |
| SEA-38 Santa Monica Mountains             | SEA-69 Chatsworth Reservoir                 |
| SEA-39 Santa Monica Mountains             | SEA-70 Chatsworth Reservoir                 |
| SEA-40 Santa Monica Mountains             | SEA-71 Chatsworth Reservoir                 |
| SEA-41 Santa Monica Mountains             | SEA-72 Chatsworth Reservoir                 |
| SEA-42 Santa Monica Mountains             | SEA-73 Chatsworth Reservoir                 |
| SEA-43 Santa Monica Mountains             | SEA-74 Chatsworth Reservoir                 |
| SEA-44 Santa Monica Mountains             | SEA-75 Chatsworth Reservoir                 |
| SEA-45 Santa Monica Mountains             | SEA-76 Chatsworth Reservoir                 |
| SEA-46 Santa Monica Mountains             | SEA-77 Chatsworth Reservoir                 |
| SEA-47 Santa Monica Mountains             | SEA-78 Chatsworth Reservoir                 |
| SEA-48 Santa Monica Mountains             | SEA-79 Chatsworth Reservoir                 |
| SEA-49 Santa Monica Mountains             | SEA-80 Chatsworth Reservoir                 |
| SEA-50 Santa Monica Mountains             | SEA-81 Chatsworth Reservoir                 |
| SEA-51 Santa Monica Mountains             | SEA-82 Chatsworth Reservoir                 |
| SEA-52 Santa Monica Mountains             | SEA-83 Chatsworth Reservoir                 |
| SEA-53 Santa Monica Mountains             | SEA-84 Chatsworth Reservoir                 |
| SEA-54 Santa Monica Mountains             | SEA-85 Chatsworth Reservoir                 |
| SEA-55 Santa Monica Mountains             | SEA-86 Chatsworth Reservoir                 |
| SEA-56 Santa Monica Mountains             | SEA-87 Chatsworth Reservoir                 |
| SEA-57 Santa Monica Mountains             | SEA-88 Chatsworth Reservoir                 |
| SEA-58 Santa Monica Mountains             | SEA-89 Chatsworth Reservoir                 |
| SEA-59 Santa Monica Mountains             | SEA-90 Chatsworth Reservoir                 |
| SEA-60 Santa Monica Mountains             | SEA-91 Chatsworth Reservoir                 |
| SEA-61 Santa Monica Mountains             | SEA-92 Chatsworth Reservoir                 |
| SEA-62 Santa Monica Mountains             | SEA-93 Chatsworth Reservoir                 |
| SEA-63 Santa Monica Mountains             | SEA-94 Chatsworth Reservoir                 |
| SEA-64 Santa Monica Mountains             | SEA-95 Chatsworth Reservoir                 |
| SEA-65 Santa Monica Mountains             | SEA-96 Chatsworth Reservoir                 |
| SEA-66 Santa Monica Mountains             | SEA-97 Chatsworth Reservoir                 |
| SEA-67 Santa Monica Mountains             | SEA-98 Chatsworth Reservoir                 |
| SEA-68 Santa Monica Mountains             | SEA-99 Chatsworth Reservoir                 |
| SEA-69 Santa Monica Mountains             | SEA-100 Chatsworth Reservoir                |

**NOTE:**  
 Names for unincorporated SEAs are the names adopted with the 1999 General Plan. Identified areas of State Canyons are preserved along 1/2 mile wide and 1/2 mile high.  
 This map is a component of the Los Angeles County General Plan Update Program. It is a working draft subject to revision. This map will not be official until adopted by the Board of Supervisors. Modification will occur as the information changes. Suggestions for modifications to this map will be accepted by County staff under review by the map for public review by the Regional Planning Commission. All comments and supporting documentation should be submitted to the Department of Regional Planning General Plan Development Section address: 229 W. Temple Street, Los Angeles, CA 90012. Tel: 213-488-8424. E-mail: generalplan@planning.lacounty.gov.  
 This map was produced in whole or in part from THE GIS SOURCE. Digital data and symbols were generated from THE GIS SOURCE. All rights reserved.

VENTURA COUNTY

SAN BERNARDINO COUNTY

RIVERSIDE COUNTY

ORANGE COUNTY



NOTE: This island is not shown in its true location.

LOS ANGELES REGION  
 Department of Regional Planning  
 229 W. Temple St.  
 Los Angeles, CA 90012

2014

Integrated Pest Management Program



Developed for the City of

---

# Table of Contents

---

General IPM Policy.....	3
Implementation Guidelines .....	6
Components of an Effective IPM Program .....	8
Pest Identification .....	8
Prevention.....	8
Monitoring .....	8
Injury Levels and Action Thresholds .....	9
Pest Control Tactics.....	9
Appendix A.....	12
Appendix B .....	23

## List of Figures

Figure 1 Components of an Integrated Pest Management Program.....	4
Figure 2 Example of Secondary Pest Outbreak Caused By Use of a Broad Spectrum Insecticide .....	11

## List of Tables

Table 1 Advantages and Disadvantages of a Pesticide-Based Program Versus An IPM-Based Pest Control Program.....	5
---	---

# INTEGRATED PEST MANAGEMENT (IPM) PROGRAM IMPLEMENTATION GUIDELINES<sup>1</sup> FOR THE CITY OF [REDACTED]

---

## General IPM Policy

For the past few decades, the trend in pest management has been to increasingly rely on synthetic chemical pesticides. This management strategy results in the increased use of dangerous chemicals, an increase in the number of pests that can become resistant to the pesticides, as well as lead to new organisms becoming pests. Additionally, some pesticides used for terrestrial pest management have been found in waterways causing problems in the aquatic environment.


Pest control managers are now moving away from their reliance on pesticides and toward an integrated approach that combines limited pesticide use with more environmentally friendly pest control techniques. This system is known as integrated pest management (IPM), a strategy that focuses on the long-term prevention of pests through a combination of techniques, including preventative, cultural, mechanical, environmental, biological, and chemical control tactics (**Figure 1**). Multiple IPM techniques can be utilized simultaneously to control pest populations in the most effective manner possible.

A comprehensive IPM Program and Approach allows for primary focus on pollution prevention by monitoring and preventing pests as well as minimizing heavy pest infestations, which reduces the need for chemicals and/or multiple applications. The goal of the IPM Program is not to eliminate all pests, but to keep their populations at tolerable levels. In an IPM program, pesticides should be applied only when it is determined that pests are approaching damaging levels. Because this requires early detection of the pests, IPM programs utilize monitoring techniques and economic thresholds to determine when to implement control strategies. If possible, a person should be trained and assigned to scout the sites on a regular basis. Pesticides may be part of an IPM program, but they should preferably be used only after pests exceed established thresholds and applied only to the affected area (in the case of disease prevention, some modifications may be allowed). In general, all pest control strategies should be those that are least disruptive to biological control organisms (natural enemies), least hazardous to humans and the environment (including non-target organisms), and have the best likelihood of long-term effectiveness.

---

<sup>1</sup>Adapted from the Orange County Drainage Area Management Plan Integrated Pest Management Policy Developed by the University of California, Division of Agriculture and Natural Resources

IPM practices are encouraged over the sole use of pesticides as the primary means of pest management (**Table 1**). As a part of their Municipal Activities Program, public agencies and their contractors evaluate the ability to use non-chemical IPM techniques before intensive use of pesticides. This IPM Program template outlines baseline IPM procedures that are required by the Los Angeles County Municipal Separate Storm System Permit (MS4 Permit)<sup>2</sup> along with additional optional IPM techniques that can be employed to implement an effective IPM program.



**Figure 1 Components of an Integrated Pest Management Program**

<sup>2</sup>California Regional Water Quality Control Board Los Angeles Region. 2012. Order No. R4-2012-0175 NPDES Permit No. CAS004001 Waste Discharge Requirements for Municipal Separate Storm Sewer System (MS4) Discharges within the Coastal Watersheds of Los Angeles County, except those Discharges Originating from the City of Long Beach MS4.

**Table 1 Advantages and Disadvantages of a Pesticide-Based Program Versus An IPM-Based Pest Control Program**

Pesticide Based Pest Control		IPM Based Pest Control	
Advantages	Disadvantages	Advantages	Disadvantages
Quick suppression of pests	Not long-term	Long-term control	It may take longer to see results
	Pest control is reactive	Can be proactive in pest control actions.	Must establish thresholds
	Loss of natural controls.	Reduces disruption of natural enemies	
	Often get outbreaks of other pests		
		Pesticides can be used (only used as a last resort)	Must have knowledge of pesticides and their effects on other organisms.
Labor is only for spraying	Extra work in cleanup	Staff becomes more knowledgeable of pests and injury symptoms	Labor is required for monitoring and regular scouting  Training is required to identify pests and natural enemies
Not much preparation or follow-up needed	Need a PCA recommendation	Pest management is more organized	Must maintain a record-keeping system.
	Pesticide safety issues for applicators, public, animals	Less exposure to pesticides	
	More pesticides in environment	Safer to the environment	
	Contamination of water bodies from runoff	Reduces contamination from runoff	

## Implementation Guidelines

Enter Designated IPM Coordinator or IPM Contact Information in Box Below:

IPM Coordinator:

Contact Info:

Personnel responsible for the care and maintenance of facilities under the City of \_\_\_\_\_ agree to implement a suite of basic integrated pest management procedures to meet MS4 Permit requirements<sup>3</sup>. The fundamental basis for the IPM program must include the following as outlined in Permit Part VI.D.9.g:

1. Pesticides are to be used if monitoring indicates they are needed, and pesticides are applied according to applicable permits and established guidelines.
2. Treatments are made with the goal of removing only the target organism.
3. Pest controls are selected and applied in a manner that minimizes risks to human health, beneficial non-target organisms, and the environment.
4. The use of pesticides, including Organophosphates and Pyrethroids, does not threaten water quality.
5. Partnerships with other agencies and organizations are established to encourage the use of IPM.
6. A standardized protocol is to be used for the routine and non-routine application of pesticides (including pre-emergents), and fertilizers.
7. There is to be no application of pesticides or fertilizers (1) when two or more consecutive days with greater than 50% chance of rainfall are predicted by NOAA34, (2) within 48 hours of a ½-inch rain event, or (3) when water is flowing off the area where the application is to occur. This requirement does not apply to the application of aquatic pesticides or pesticides which require water for activation.
8. No banned or unregistered pesticides are stored or applied.
9. All staff applying pesticides are certified in the appropriate category by the California Department of Pesticide Regulation, or are under the direct supervision of a pesticide applicator certified in the appropriate category.
10. Procedures to encourage the retention and planting of native vegetation to

<sup>3</sup> In addition to MS4 Permit compliance, there are extensive federal and state laws and regulations that all public agencies must be in compliance with at all times, including the California Food and Agricultural Code (FAC) and the California Code of Regulations, Title 3 (3CCR).

- reduce water, pesticide and fertilizer needs are implemented; and
- 11. Pesticides and fertilizers are stored indoors or under cover on paved surfaces, or use secondary containment.**
- a. The use, storage, and handling of hazardous materials are reduced to decrease the potential for spills.**
  - b. Storage areas are regularly inspected.**

In order to implement the above required minimum practices, the following section describes components of an effective IPM Program that can be employed:

- Pest and Symptom Identification
- Prevention
- Monitoring
- Injury Levels and Action Thresholds
- Pest Control Tactics

A number of useful IPM techniques are outlined under each component and further described in Appendix A. These techniques are known to be effective and methods can be selected from each component as necessary to achieve the IPM goals and meet MS4 Permit requirements.

Additional information on the latest IPM techniques including management of new pests in the landscape can be obtained from local UC Cooperative Extension Advisors, UC IPM Regional Advisor, or the Statewide UC IPM Web Site at [www.ipm.ucdavis.edu](http://www.ipm.ucdavis.edu).

## Components of an Effective IPM Program

An IPM program is a long-term, multi-faceted system to manage pests (**Figure 1**). Use of pesticides is a short-term solution to pest problems, and should be used only when the other components fail to maintain the pests or their damage below an acceptable level. Successful IPM practitioners are knowledgeable about the biology of the plants and pests, and successful IPM programs primarily use combinations of cultural practices as well as a combination of physical, mechanical and biological controls.

### Pest Identification

It is important to learn to identify all stages of common pests at each site. For example, if you can identify weed seedlings, you can control them before they become larger and more difficult to control and before they flower, disseminating seeds throughout the site. It is also important to be sure that a pest is actually causing the problem. Often damage such as wilting is attributed to root disease but may actually be caused by under watering or wind damage. Appendix A lists specific techniques that can be employed to identify pests.

### Prevention

Good pest prevention practices are critical to any IPM program, and can be very effective in reducing pest incidence. Numerous practices can be used to prevent pest incidence and reduce pest population buildup such as the use of resistant varieties, good sanitary practices and proper plant culture. Examples of prevention include choosing an appropriate location for planting, making sure the root system is able to grow adequately and selecting plants that are compatible with the site's environment. Appendix A lists specific techniques that can be employed to achieve pest prevention.

### Monitoring

The basis of an effective IPM Program is the development and use of a regular monitoring or scouting program. Monitoring involves examining plants and surrounding areas for pests, examining tools such as sticky traps for insect pests and quantitatively or qualitatively measuring the pest population size or injury. This information can be used to determine if pest populations are increasing, decreasing, or staying the same and to determine when to use a control tactic. Weather and other environmental conditions may also play a factor in whether a pest outbreak may occur so it is important to monitor temperature and soil moisture as well.

It is important to use a systematic approach when monitoring, for example you should examine leaves of a similar age each time you check for pests, rather than looking at the older leaves on some plants and younger ones on others. Randomly looking at a plant and its leaves does not allow you to track changes in pest population or damage over time.

It is important to establish and maintain a record-keeping system to evaluate and improve your IPM program. Records should include information such as date of examination, pests found, size and extent of the infestation, location of the infestation, control options utilized, effectiveness of the control options, labor and material costs. Appendix A lists specific techniques that can be employed to in the monitoring of pests.

### **Injury Levels and Action Thresholds**

In order to have a way to determine when a control measure should be taken, injury levels and action thresholds must be set for each pest. An injury level is the level of unacceptable damage. For example, the injury level for a leaf-feeding beetle may be set at 30% of the leaves being damaged. Action thresholds are the set of conditions required to trigger a control action. An example of this would be finding an average of 5 or more beetles on 10 shrubs in a location. Action thresholds are set from previous experience or published recommendations and based on expected injury levels. Injury levels are often set by the public's comments. Appendix A lists specific techniques that can be employed to determine injury levels and action thresholds.

### **Pest Control Tactics**

Integrated pest management programs use a variety of pest control tactics in a compatible manner that minimizes adverse effects to the environment. A combination of several control tactics is usually more effective in minimizing pest damage than any single control method. The type of control that an agency selects will likely vary on a case-by-case basis due to the varying site conditions.

The primary pest control tactics to choose from include:

- Cultural
- Mechanical/Physical
- Biological
- Pesticide

Appendix A lists specific pest control techniques that can be employed.

#### ***Cultural Controls***

Cultural controls are modifications of normal plant care activities that reduce or prevent pests. In addition to those methods used in the pest preventions, other cultural control methods include adjusting the frequency and amount of irrigation, fertilization, and mowing height. For example, spider mite infestations are worse on water-stressed plants, over-fertilization may cause succulent growth which then encourages aphids, too low of a mowing height may thin turf and allow weeds to become established.

#### ***Mechanical/Physical Controls***

Mechanical control tactics involve the use of manual labor and machinery to reduce or

eliminate pest problems using methods such as handpicking, physical barriers, or machinery to reduce pest abundance indirectly. Examples include hand-pulling or hoeing and applying mulch to control weeds, using trap boards for snails and slugs, and use of traps for gophers.

The use of physical manipulations that indirectly control or prevent pests by altering temperature, light, and humidity can be effective in controlling pests. Although in outdoor situations these tactics are difficult to use for most pests, they can be effective in controlling birds and mammals if their habitat can be modified such that they do not choose to live or roost in the area. Examples include removing garbage in a timely manner and using netting or wire to prevent bird from roosting.

### *Biological Controls*


Biological control practices use living organisms to reduce pest populations. These organisms are often also referred to as beneficials, natural enemies or biocontrols. They act to keep pest populations low enough to prevent significant economic damage. Biocontrols include pathogens, parasites, predators, competitive species, and antagonistic organisms. Beneficial organisms can occur naturally or can be purchased and released.

The most common organisms used for biological control in landscapes are predators, parasites, pathogens and herbivores.


- Predators are organisms that eat their prey (e.g. Ladybugs).
- Parasites spend part or all of their life cycle associated with their host. Common parasites lay their eggs in or on their host and then the eggs hatch, the larvae feed on the host, killing it (e.g. Tiny stingless wasps for aphids and whiteflies).
- Pathogens are microscopic organisms, such as bacteria, viruses, and fungi that cause diseases in pest insects, mites, nematodes, or weeds (e.g. *Bacillus thuringiensis* or BT).
- Herbivores are insects or animals that feed on plants. These are effective for weed control. Biocontrols for weeds eat seeds, leaves, or tunnel into plant stems (e.g. goats and some seed and stem borers).

In order to conserve naturally occurring beneficials, broad-spectrum pesticides should be avoided since the use of these types of pesticides may result in secondary pest outbreak due to the mortality of natural enemies that may be keeping other pests under control (Figure 2).

A. Aphids and mites controlled by predators



B. After a broad spectrum spray for aphids, predators for mites and aphids are also killed, resulting in an outbreak of mites.



**Figure 2 Example of Secondary Pest Outbreak Caused By Use of a Broad Spectrum Insecticide**

### *Pesticide Controls*

Any substance used for defoliating plants, regulating plant growth or preventing, destroying, repelling or mitigating any pest, is a pesticide. Insecticides, miticides, herbicides, fungicides, rodenticides and molluscides are all pesticides. Anything with an EPA or DPR registration number on the label is a non-exempt pesticide.

Pesticides should only be used when other methods fail to provide adequate control of pests and just before pest populations cause unacceptable damage. The overuse of pesticides can cause beneficial organisms to be killed and pest resistance to develop. When pesticides must be used, considerations should be made for how to use them most successfully. Avoid pesticides that are broad-spectrum and relatively persistent since these are the ones that can cause the most environmental damage and increase the likelihood of pesticide resistance. Always choose the most specific but least toxic to non-target organisms method.

In addition, considerations should be given to the proximity to water bodies, irrigation schedules, weather (rain or wind), etc. that are secondary factors that may result in the pesticide being moved off-site into the environment. Consideration should be made of the temporary loss of use of an area (application in a park may result in the area being sectioned off).

## Appendix A: Optional IPM Techniques to Integrate into IPM Program

---

The following practices are generally accepted to be effective IPM techniques. These procedures increase the long-term prevention and suppression of pest problems (insects, weeds, diseases, and vertebrates) with the minimum impact on human health, the environment, and non-target organisms. Emphasis is placed on improving cultural practices to prevent problems and utilize alternative control measures instead of broad spectrum pesticides. The following IPM techniques are divided into the following categories:

- General Pesticide Management Practices
- Pest and Symptom Identification
- Prevention
- Monitoring
- Injury Levels and Action Thresholds
- Pest Control Tactics

### GENERAL PESTICIDE MANAGEMENT PRACTICES

- Maintain a complete inventory of all pesticides used and the use sites. This inventory should be updated annually.
- If pesticides are necessary, CAUTION-labeled pesticides should be considered before more toxic alternatives.
- Ensure that no banned or unregulated pesticides are stored or applied.
- Restricted use pesticides should only be used when no other alternatives are practical.
- Only small quantities of pesticides should be purchased eliminating the need for stockpiling.
- MSDSs should be regularly updated to reflect new pesticides or label changes to pesticides in storage.
- Pesticides should be used only according to label instructions.
- Weather conditions that could affect application should be considered. For example, wind conditions affect spray drift; rain may wash pesticide off of leaves.
- Pesticides should not be applied where there is a high chance of movement into water bodies; for example, they should not be applied near wetlands, streams, lakes, ponds or storm drains unless it is for an approved maintenance activity.
- In most cases, empty pesticide containers should be triple-rinsed before disposal. Particular information on the proper disposal of the pesticide and its container can be found on the label.

- Pesticide equipment and containers should not be cleaned or rinsed in the vicinity of storm drains or other open water areas.
- Pesticides should be stored in covered areas with cement floors and in areas insulated from temperature extremes.
- Chemicals and equipment should be secured during transportation to prevent tipping or excess jarring.
- Pesticides should be transported completely isolated from people, food and clothing, for example, in the bed of the truck rather than in the passenger compartment.
- Pesticide equipment, storage containers and transportation vehicles should be inspected frequently.
- A plan for dealing with pesticide spills and accidents should be developed.
- Unless their safety is compromised, workers should immediately clean up any chemical spills according to label instructions and notify the appropriate supervisors and agencies.
- Pesticide applications on public property, which take place on school grounds, parks, or other public rights-of-way where public exposure is possible, should be posted with warning signs. The specific criteria for the signage can be found in FAC, section 12978. Pesticide applications by the Department of Transportation on public highway rights-of-way are exempt.

## PEST AND SYMPTOM IDENTIFICATION

### *Insects, Mites, and Snails and Slugs*

- Field personnel should be trained to recognize basic pests found in the landscape in the following groups: insects, mites, and mollusks.
- A licensed Pest Control Adviser can be on staff or hired to properly identify a pest and the symptoms caused by the pest.
- Field personnel can be trained to utilize disease life cycles to apply treatments when the organism can be controlled most effectively.
- Field personnel can be trained to distinguish between beneficial insects and actual pests found in the landscape (e.g. parasitizing wasps).
- Unknown samples can be submitted to the Orange County Agricultural Commissioner for identification by the county entomologist or plant pathologist.
- Abiotic or nonliving factors (wind, sunburn, air pollution, etc...) should be considered as possible causes of observed symptoms as well as biotic (living) factors.

### *Weeds*

- Field personnel can be trained to identify common weeds in the landscape.
- Field personnel can be trained to utilize weed life cycles to properly control

weeds such as controlling crabgrass utilizing a pre-emergent herbicide applied in mid-January.

- A licensed Pest Control Adviser can be on staff or contracted to properly identify the pest.

### *Diseases*

- Field personnel can be trained to recognize common diseases or their signs/symptoms in the landscape.
- Field personnel can be trained to utilize disease life cycles to apply treatments when the organism can be controlled most effectively.
- Field personnel can be trained to recognize the difference between biotic and abiotic problems.
- Field personnel can be trained to understand how common diseases are spread throughout the landscape.
- Disease signs and symptoms can be sampled and submitted to the Orange County Agricultural Commissioner for identification by the county plant pathologist.
- A licensed Pest Control Adviser can be on staff or contracted to properly identify the pest.
- Photographs of disease signs and symptoms can be taken and compared to reference guides such as UC IPM's *Pests of Landscape Trees and Shrubs*.

### *Vertebrates*

- Field personnel can be trained to recognize vertebrate pests and the damage they cause in the landscape.
- Field personnel can be trained to utilize vertebrate behavior to properly control the pest most effectively.
- Field personnel can be trained in vertebrate baiting and trapping.
- A licensed Pest Control Adviser can be on staff or contracted to properly identify vertebrate pest.

## **PREVENTION**

### *Landscape Design Procedures*

- Drainage, soil characteristics, water quality and availability should be considered during plant selection.
- Sun exposure, heat, and high temperature conditions should be considered during plant selection.
- Plant material should be selected based on adaptability to local climate conditions, such as those conditions common to a Mediterranean climate.
- Adequate space should be allowed for root growth, especially trees.

- Nursery stock should be inspected and rejected if not healthy (injuries, diseased, circling roots/potbound, poor staking and/or pruning).
- Pest resistant species and cultivars should be selected.
- Plants with similar growth characteristics and irrigation requirements should be grouped together.
- Landscape design should match available irrigation technology to avoid excess water use and to minimize surface runoff.

#### *Site Preparation and Planting Procedures*

- Soil drainage properties can be assessed and compacted soils improved prior to planting.
- A soil analysis can be conducted to determine the chemical and physical properties of the existing soil and then appropriate amendments such as organic matter can be added.
- Irrigation should be installed as designed in order to avoid poor uniformity once plants are in place.
- Proper planting procedures should be followed for particular plant species to avoid planting too deeply or too shallow.
- Nursery tree stakes can be removed at planting and replaced with staking that allows trunk to flex; removing these stakes after 1 to 1.5 years.
- A soil probe or other soil moisture measurement device can be utilized to monitor soil moisture levels in existing root ball and surrounding soil during establishment period.

#### *Water Management*

- Plants should be examined weekly for symptoms of water stress and to assist in determining irrigation scheduling.
- Soil moisture can be monitored with a soil probe or soil moisture sensors to assist in scheduling irrigation.
- Evapotranspiration (ET) data or 'smart' clock technology can be utilized to schedule irrigation.
- Cyclic irrigation (short-multiple run times) can be employed to minimize surface runoff.
- Low precipitation sprinklers or low-volume systems can be utilized to reduce surface runoff.
- Systems should be inspected monthly to check for leaks, broken pipes, and clogged or broken sprinkler heads.
- Adjust sprinklers to avoid application of water directly to the trunk of trees (can promote disease) or on to concrete surfaces where it can enter storm drains.
- A hotline, email, or other dedicated method can be established for citizens to

report leaks and broken sprinkler heads

### *Fertilizing Procedures*

- To avoid nutrient losses below the root zone, fertilize only when plants are actively growing.
- Fertilizer should not be applied within 48 hours of a rain event to avoid losses below the root zone and in surface runoff.
- Soil analyses can be conducted in order to determine existing nutrient levels in the soil prior to fertilizing.
- Turf grass fertilizer maintenance schedules can be based on UC recommendations found online at UC Guide for Healthy Lawns: <http://www.ipm.ucdavis.edu/TOOLS/TURF/MAINTAIN/fertilize.html>
- Sports turf grass fertilizer maintenance guidelines can be based on UC recommendations found in *Establishing and Maintaining the Natural Turf Athletic Field* (UCR ANR Publication Number: 21617).
- Overfertilization, especially of trees and shrubs, should be avoided to ensure plant growth is not excessively succulent making it more susceptible to pest infestations.
- Off-target fertilizer applications or spills should be cleaned up immediately by sweeping up and applying to landscape or turf or replacing in spreader or bag to ensure material does not enter storm drains.

### *Pruning Procedures*

- Damaged or diseased wood should be regularly pruned from landscape plants.
- Trees should be pruned according to standards set forth by a professional tree care organization such as the International Society of Arboriculture.
- Plants too large for a space should be replaced instead of pruning them severely.
- Unnecessary pruning should be avoided as wounds are entry sites for decay and disease organisms.
- The age and species of the plant should be taken into account when determining the time of year to prune. For example, eucalyptus should be pruned in December and January when long-horned beetles are not active.
- Tree height reduction should be discouraged. When deemed necessary by a licensed arborist, the crown reduction method approved by a professional tree care organization should be utilized. Topping should not be done to reduce tree size.

## **MONITORING FOR PESTS AND PROBLEMS**

### *Insect/Mollusk Monitoring Procedures*

- Monthly visual inspections of plants for insects, mites, snail and slug damage,

and recording results is an effective method for tracking changes and easy recall of data.

- Yellow sticky traps can be utilized to assess populations of insects.
- Insects can be dislodged from plants by shaking over a collection surface usually consisting of a clipboard with a white sheet of paper.
- If available for a particular insect, pheromone-baited traps can be utilized.
- Soil-dwelling turf insects can be brought to the surface for monitoring by flushing a specific area of soil (i.e. 2' x 2' grid) with plain water or a soapy water mixture.
- The amount of honeydew (aphids) and frass (caterpillars) present can be utilized as an indicator of population levels.

#### *Weed Monitoring Procedures*

- Landscapes can be inspected at least 4 times a year (early winter, early spring, summer and early fall) for weeds in order to determine if and when a weed problem exists.
- Site surveys can be utilized to record the location, date, and severity of weed problem for an effective method of tracking changes and easy recall of data.
  - The number of weeds encountered at periodic intervals (e.g. every 1 to 2 feet) can be counted and recorded along a straight line transecting a landscaped area or within a selected area, for example 4 sq. ft. samples done in random places in a bed or turf area.

#### *Disease Monitoring Procedures*

- Landscapes should be regularly checked for conditions, such as overwatering and injuries, which promote disease.
- Landscapes should be checked monthly for disease symptoms and signs. Disease prone plants should be checked more frequently.
- Landscape inspections should note date when disease signs and symptoms were first noticed and the current environmental conditions and soil moisture levels as an effective method of tracking changes and easy recall of data.

#### *Vertebrate Monitoring Procedures*

- Landscapes can be regularly inspected for vertebrate presence either by damage caused by animal, actual animal sightings, and/or droppings.
- Records can be kept of the absence or presence of actual vertebrates, the damage caused, and/or the presence or absence of droppings.
- Maps can be created and updated at least twice a year, recording areas of high vertebrate damage or signs (such as gopher mounds).

## **INJURY LEVELS AND ACTION THRESHOLDS**

### *Insect/Mollusk Thresholds and Guidelines*

- Insect tolerance levels can be established based on the public's acceptance of damage to the landscape or a certain level of nuisance pests (i.e. ants), the actual plant species in the landscape, and long-term monitoring and knowledge of pests causing the damage.
- Thresholds can be based on levels where reasonable control of the pest can be achieved with minimum impact on the environment.
- Insect monitoring records can be utilized to establish threshold levels for the implementation of control strategies. For example, the threshold for the presence of aphids on a rose garden at City Hall is low, while in a native shrub border it might be considerably higher.

#### *Weed Thresholds and Guidelines*

- Weed tolerance levels can be established based on public safety or the public's acceptance and the resources available to manage the landscape at that level.
- Weed monitoring records can be utilized to rank the percentage of the landscape area infested (none, light, moderate, heavy, or very heavy) with weeds.
- Public areas can be ranked according to high, medium, or low level of weed control and management conducted according to levels set for each rank (see Appendix B)

#### *Disease Thresholds and Guidelines*

- Disease tolerance levels can be established based on the public's acceptance and the resources available to manage the landscape at the level required.
- Disease monitoring records can be utilized to establish threshold levels for the implementation of control strategies. For example, the threshold for the presence of powdery mildew on roses at City Hall is much lower than the threshold for its presence on Euonymus in a parking lot at a city sports park.

#### *Vertebrate Thresholds and Guidelines*

- Vertebrate tolerance levels can be established based on public safety, the public's acceptance and the resources available to manage the landscape at the level required.
- Vertebrate monitoring records can be utilized to establish threshold levels for the implementation of control strategies. For example, the threshold for the presence of gopher mounds in a sport field is zero, while in a native shrub border it might be two before a trapping strategy is implemented.

## **PEST CONTROL TACTICS**

### **Insect/Mollusk Management Methods**

#### *Cultural/Mechanical/Physical Control Methods*

- Sticky barriers can be applied to trunks of trees and large shrubs to prevent ants and other wingless invertebrates from plant canopies.
- Small insect infestations can be removed by pruning infested plant parts.
- Copper bands can be installed around base of trees or planting areas where snail and slug infestations are prevalent.
- Plant canopies can be thinned to increase light penetration to expose certain soft-bodied insects (soft-scale) as well as snails and slugs to heat.
- Strong streams of water can be used to dislodge insects such as aphids and whiteflies, from leaves.
- The use of plants that snails and slugs use for shelter should be avoided.
- Avoid irrigating between 5pm and 5am when moisture remains on plant material for several hours.

### *Biological Control Methods*

- Persistent broad-spectrum pesticides should be avoided, especially if biological control of an insect has been established by UC researchers. Examples include parasitoid wasps controlling Eugenia Psyllids, Giant Whitefly, and Ash Whitefly.
- Natural predators (beneficial insects) can be augmented with purchases of additional predators from commercially available resources.

### *Pesticide Control Methods*

- The most selective, rather than broad-spectrum, pesticide should be used.
- If available for controlling a particular insect, biological and botanical pesticides should be selected.
- Insecticidal soaps can be utilized to control infestations of soft-bodied insects such as aphids, thrips, and immature scales.
- Horticultural oils (neem oil and narrow-range refined oils) can be utilized to control infestations of soft-bodied immature and adult insects such as aphids, scales, and whiteflies.
- Pesticides should only be utilized when the potential for impacts to the environment, especially water quality, are minimized.
- Equipment should be calibrated prior to the application of the insecticide to avoid excess material being applied to the landscape environment.
- Applicators should be trained to not apply pesticides to hard surfaces and to not allow any pesticide to enter the storm drain system.
- Spot treatments should be utilized rather than broadcast methods.
- Insecticide/fertilizer combinations should only be used if it is appropriate timing for BOTH the insecticide application and the fertilizer application.

### *Weed Management Methods*

#### *Cultural, Mechanical, and Physical Control Methods*

- Timers can be set to avoid overwatering as weeds establish in areas where soil moisture is excessive.
- Drainage can be managed to avoid wet areas.
- Weeds can be removed from a site prior to planting.
- Mower height can be adjusted to turf species and time of year.
- Mower should be washed after mowing a weedy site.
- Hand-pulling, mowing, trimmers/brushcutters, flaming, hoeing, and rototilling around landscape plants should be the main methods utilized to control annual weeds and young perennial weeds.
- Soil solarization can be utilized to control some annual and perennial weed species.
- Bare soil areas can be covered with a thick layer of mulch to suppress weeds and conserve soil moisture.
- Soil, mulch, and plant material should be weed-free before it is introduced into the landscape.

#### *Pesticide Control Methods*

- Spot treatments can be utilized rather than broadcast methods.
- Herbicide/fertilizer combinations should only be used if it is appropriate timing for BOTH the herbicide application and the fertilizer application.
- Herbicides should be utilized according to established thresholds (see Appendix B).
- Organically acceptable herbicides (shown to be effective through science-based research) should be used where appropriate.
- Herbicides can be applied to the stage of weed growth most susceptible to the chemical.
- Equipment should be calibrated prior to the application of the herbicide to avoid excess material being applied to the landscape environment.

#### **Disease Management Methods**

##### *Cultural, Mechanical, and Physical Control Methods*

- Localized areas of diseased plants should be pruned out and disposed of.
- Pathogen-infested plant parts can be removed from the soil surface area to reduce certain pathogens (e.g. Camellia Petal Blight).
- Pruning tools can be sterilized (e.g. a diluted bleach solution) between plants to prevent the spread of pathogen to other plants.
- Proper irrigation and fertilization can be maintained to prevent plant stress, waterlogging, and subsequent susceptibility to disease.
- Soil solarization can be utilized to control soil pathogens in annual beds where it

is most effective.

- Mulch can be kept at least 6" from base of plants to avoid excessive moisture around crown possibly resulting in crown rots and is no deeper than 4"
- Disease-prone plants can be replaced with non-susceptible species.

#### *Pesticide Control Methods*

- Preventative fungicides and bactericides should only be used where diseases can be predicted from environmental conditions and applied prior to infection or the appearance of symptoms.
- Synthetic fungicides should be used sparingly in the landscape and only in high visibility areas in order to minimize development of resistance.
- Organic fungicides and bactericides should be utilized in combination with cultural, mechanical, and physical control methods in order to improve their effectiveness.
- Copper-based fungicides should only be utilized in situations where its entry into surface runoff and storm drains is virtually impossible and after consultation with PCA and IPM coordinator.
- Mycopesticides, commercially available beneficial microorganisms, should be used where appropriate.
- Fungicides classes can be rotated to avoid resistance.

#### *Vertebrate Management Methods*

##### *Cultural and Physical Control Methods*

- Groundcovers can be maintained such that they do not harbor rats.
  - Shrubs pruned at least 1 foot from the ground (rats).
  - Sources of drinking water removed (leaky faucets, puddles).
  - Trash cans have lids and are emptied daily (rats).
  - Screens or other barriers installed under structures that have a space between soil and floor (rabbits).
- Habitat modification, based on pest biology can be used to reduce shelter. Trapping can be used for gophers when safe and practical.
- Kill traps used for ground squirrels and rabbits, should be checked daily, and put in places not accessible by children or non-target animals.
- Gas cartridges can be used for ground squirrels according to UC recommendations.

##### *Pesticide Control Methods*

- Anti-coagulant baits can be used and applied according to label and UC recommendations.
- Bait should be applied in a manner that non-target animals do not have access to

- it.
- Restricted use pesticides should only be applied by or under the direct supervision of an individual with a qualified applicators certificate (QAC). To receive a QAC, a person must take a test administered by Department of Pesticide Regulation (DPR). To obtain test materials, test schedules, and an application, see <http://www.cdpr.ca.gov/docs/license/liccert.htm>.

DRAFT

## Appendix B

---

### **Ranking public areas for weeds (or other pest) management:**

Areas ranked as **HIGH** may include areas that the public sees and expects to be well-maintained. Examples are entrances to public buildings such as city hall and libraries.

*These areas are allowed to use pesticides based on established thresholds.*

Areas ranked as **MEDIUM** may include areas the public sees but does not expect a high level of maintenance. Examples are landscaped areas away from the entrance, recreational and picnic areas. These areas can tolerate a higher level of weeds.

*These areas are allowed to use pesticides but the threshold is much higher and pesticides are used infrequently and only after consultation with IPM coordinator.*

Areas ranked as **LOW** may include areas the public rarely sees or does not expect a high level of maintenance. Examples are medians, landscaped areas in parking lots, wildlands. These areas can tolerate a higher level of weeds.

*These areas are not allowed to use pesticides except in extreme cases and only after consultation with IPM coordinator.*



**Example Catch Basin Cleaning Log**

Catch Basin Cleaning Log			
Date	Location	Number of Catch Basins Cleaned	Total Amount Removed
Notes:			

**Example of Completed Catch Basin Cleaning Log**

Catch Basin Cleaning Log			
Date	Location	Number of Catch Basins Cleaned	Total Amount Removed
7/1/13	Street #1	20	55 cu. ft.
	Intersection #1	10	
	Street #2	5	
Notes:			

<b>Drainage Inlet/Catch Basin Information</b>		
<b>Location</b>		
Street:	Cross Street:	Side (N,S,E,W)
Distance:	Direction (N,S,E,W):	Inlet #:
Map #:	Grid:	
<b>Condition</b>		
Length of Opening:	Height of Opening:	Stencil Legible (Y/N):
Bicycle Bars (Y/N):	Grate Size:	Inlet Protection Bar (Y/N):
Treatment Control BMP (Y/N):	Type of BMP:	
<b>Repairs Required:</b>		

# Illicit Connection Investigations Guidance

## Field Screening Techniques

If evidence of an illicit discharge is detected, as described in Section 2, and the source does not appear to be evident or above ground, investigations will be conducted to determine if the discharge is being conveyed through an illicit connection. A good source of information includes *Investigation of Inappropriate Pollutant Entries into Storm Drainage Systems* (EPA/600/R-92/238.1993, Pitt et al). General guidance follows below. These techniques can also be used if a Permittee elects to survey sections of their system for illicit connections.

## Document Research

Maps of drainage facilities can be reviewed to locate upstream connections and drainage basins as an initial step to locate potential illicit connections. Other records, such as connection permits and discharge permits, can also be reviewed to determine if legal connections may be the source.

## Physical Inspections

Catch basins, manholes and other facilities that can be safely investigated from the surface should be physically checked for evidence of connections. This may be a hard pipe connection, or could be a hose or other conveyance that directs a discharge into the storm drain facility. Identification of connections that exhibit evidence of suspected illicit discharges during routine site inspection (e.g., industrial, commercial or construction). Investigation is conducted to determine if the discharge is being conveyed through an illicit connection when evidence of illicit discharge is detected, and the source does not appear to be evident or above ground.

Facilities that are large enough for personnel to enter can also be physically inspected, however, entry into facilities requires strict adherence to health and safety procedures, including confined space entry procedures. In general, a space is “confined” if it is not intended for human occupancy, has limited openings for entry or exit, and has insufficient natural or mechanical ventilation. Information on safety procedures can be found in many documents, including the *Occupational Safety and Health Guidance Manual*, National Institute for Occupational Safety and Health; *OSHA Safety and Health Standards 29 CFR 1910 (General Industry)*, US Department of Labor, and *Title 8 of the California Code of Regulations, General Industry Safety Order*.

## Dye Tests

Dye tests can reveal illicit connections in areas where storm drain flows are unexplained and the Permittee has access to suspect facilities. Typical dye tests consist of the addition of fluorescent dye to a floor drain or waste line from a domestic, commercial or industrial process, followed by monitoring for the dye in downstream storm drains. Permittees should conduct dye testing facility by facility (in each area where unexplained flow exists) until all facilities in the area are tested.

## Smoke Tests

Smoke tests can reveal if illicit connections exist, and can reveal their source. Storm drains are sealed via sandbags or other sealing devices (plugs, etc.) and smoking incendiary devices are ignited upstream of the seal. Simultaneous inspections inside area facilities should reveal illicit connections even in the

absence of flow. As illicit discharges are intermittent, smoke tests offer real advantages over other types of illicit discharge source identification methods. However, as many legitimate connections to a storm drain may exist (roof drains, street drains, etc.) smoke may be observed extensively. This may cause some illicit connections to be missed, and create a problem with area businesses and residents as excessive smoke begins to enter private property.

### **T.V. Inspections**

T.V. inspections can reveal if illicit connections exist, but cannot be used to view up the connection to determine the source. Robotized or otherwise mobile television cameras allow visual inspection of storm drains (pipes) too small or dangerous for personnel to enter. Although an excellent method of identifying and documenting illicit connections, T.V. inspections have high costs unless the equipment is already owned or can be borrowed from neighboring agencies.

### **Guidance Source**

Los Angeles County Model Stormwater Quality Management Program, 2003.

DRAFT

# Illicit Discharge Investigation and Elimination Guidance

## Introduction

Once illicit discharges/disposal are detected and identified, they must be eliminated. Sometimes the source of the spill or discharge/disposal is apparent. The incident can be removed through voluntary cleanup/termination or enforcement procedures, and steps can be taken to prevent its recurrence. These prevention methods can include education and outreach materials for residents and businesses, preventive maintenance practices for infrastructure, vehicles and equipment or additional enforcement.

When the source of the discharge is not apparent, further investigation will be necessary to eliminate it and prevent it from recurring. The following discusses methods that can be used to document the incident, determine the nature of the material, and investigate the source.

## Advance Planning

An effective investigation program requires good advance planning. Sufficient staff should be trained to conduct investigations so that qualified staff are available whenever investigations are necessary. Staff should become familiar with illicit discharge investigation and sampling procedures. General guidance follows below to assist with overall planning, but should not be considered complete for proper sampling quality assurance purposes.

## Equipment

Appropriate equipment for field investigations may include:

Table 1: Typical Equipment for Investigations

Equipment Type	Equipment
General	Inspection checklist
	Field data log book
	Camera
	Tape measure
	Storm drain system map
	Flashlight
Flow measurement	Ping pong ball or other light floatable
	Stopwatch
Laboratory	Graduated container
	Temperature/pH/conductivity (EC) probe
	Field test kits (e.g., Lamotte test kit)
	12 1-liter amber glass sample bottles
	12 1-liter HDPE sample bottles
	Cooler with ice for sample preservation
	Gloves
	Splash goggles/safety glasses
Deionized water in wash bottle	
First Aid	First aid kit

### **Data Collection**

Before entering the field, the inspection crew should locate information such as the following on a storm drain/street map for areas that will be investigated:

- All known or suspected pollutant generating activities
- Locations of NPDES dischargers
- All locations where storm drains enter open channels
- Catch basins and storm drain manholes

### **Visual Observation**

Visual observation of the storm drain system and/or of activities on the surface can provide information on the source of illicit discharges. It is the simplest method to begin with and the least costly. Evidence of illicit discharges may only consist of visual observations because most illicit discharges are intermittent and will probably not be flowing when inspected. A field inspection crew should investigate the surface drainage system in the vicinity of suspected illicit discharges. This may include accessible areas in the public right-of-way adjacent to residences and businesses, catch basins, open channels near known points of discharge, and upstream manholes.

Photos of visual observations should be taken to aid subsequent data analysis and follow up planning. The following types of visual observations should be recorded on an investigation checklist, such as the one attached:

- Location
- General site description
- Amount, appearance of discharge/disposal
- Stains
- Structural cracking and corrosion
- Vegetative growth
- Nearby facilities with poor outside housekeeping practices
- Pipes/hoses connected to/directed toward drainage system

If the source of the discharge is determined, appropriate methods should be used to eliminate it through voluntary cleanup/termination or enforcement procedures, and steps should be taken to prevent its recurrence.

### **Sampling and Testing**

If flow is observed, and the source of the discharge is not apparent, the crew should collect a sample and measure flow. Several tests should be conducted to determine the nature of the material. This can be compared to records of local facilities and possible pollutant generating activities as an aid in determining the possible sources of the flow.

The sample should be measured for pH, temperature and conductivity (EC). If any of these parameters are abnormal, or strong odors or flow discoloration are detected, the sample should be analyzed. This can be done with a field test kit, which will detect the presence of copper, phenols, detergents, and chlorine. Findings should be recorded on the inspection checklist.

If visual observations are abnormal and/or the field tests detect high concentrations of any constituent, the crew should consider collecting samples for laboratory analysis. The laboratory can usually supply properly cleaned sample bottles and specify either amber glass or plastic (HDPE) bottles depending on the analyses required. If there is enough flow, the field crew should fill several of each type of bottle to obtain enough sample volume for a range of analyses. If there is a limited quantity or sampling is difficult, the field crew should collect as much sample as possible so that the laboratory can run a limited set of analyses. The samples should be placed in a cooler filled with ice and transported to the lab(s) on the same day. Arrangements should be made prior to the field inspection with an analytical laboratory capable of performing the required analyses.

The laboratory analyses run on each sample should be carefully considered. Given the potential high cost for laboratory work, it is prudent to limit the number of analytical parameters (or analytes) tested for each sample. Tests may be selected based on the findings of indicator analyses, visual observations, field tests, and information collected about the types of materials processed, stored and/or spilled within each drainage area.

### **Guidance Source**

Los Angeles County Model Stormwater Quality Management Program, 2003.



# ILLICIT CONNECTION/ ILLICIT DISCHARGE INVESTIGATION REPORT

Response Time:

- 1-6 hrs.   
 13 hrs.   
 24 hrs.   
 48 hrs.

## RESPONSE

Date:	Time:	Inspector:
-------	-------	------------

## INVESTIGATION

Location/ Address:	
Reason for Investigation: <input type="checkbox"/> Complaint <input type="checkbox"/> Discharge/Spill Response <input type="checkbox"/> Visual Monitoring <input type="checkbox"/> Other: _____	
Type of Material: <input type="checkbox"/> Hazardous <input type="checkbox"/> Wastewater <input type="checkbox"/> Oil/Grease <input type="checkbox"/> Soil/ Sediment <input type="checkbox"/> Trash <input type="checkbox"/> Sewage <input type="checkbox"/> Fuel (Gas/Diesel) <input type="checkbox"/> Chemicals <input type="checkbox"/> Other _____	
Estimated Quantity: <input type="checkbox"/> Gallons <input type="checkbox"/> Lbs.	
Entered Storm Drain System: <input type="checkbox"/> Yes <input type="checkbox"/> No	Entered Receiving Waters: <input type="checkbox"/> Yes <input type="checkbox"/> No
Storm Drain Location: _____	Name of Receiving Water: _____

<b>Observations</b>	
---------------------	--

Field Testing: <input type="checkbox"/> Yes <input type="checkbox"/> No	Sample Collected: <input type="checkbox"/> Yes <input type="checkbox"/> No
Details:	Details:
Direct/ Constructed Connections Found: <input type="checkbox"/> Yes <input type="checkbox"/> No	
Details:	

## RESPONSIBLE PARTY

Name:	
Address:	Phone/ email:
Repeat Violation? <input type="checkbox"/> Yes <input type="checkbox"/> No	

## OUTREACH MATERIAL

Outreach Material Distributed: <input type="checkbox"/> None <input type="checkbox"/> General Information <input type="checkbox"/> BMP Brochure <input type="checkbox"/> Other _____
--

## ENFORCEMENT

Enforcement: <input type="checkbox"/> None <input type="checkbox"/> Written Warning <input type="checkbox"/> Notice of Violation <input type="checkbox"/> Citation/Infraction <input type="checkbox"/> Cease and Desist Order
---

<b>Other Actions</b>	
----------------------	--

## FOLLOW-UP VISIT

Date:	Time:	Inspector:
Discharge Stopped? <input type="checkbox"/> Yes <input type="checkbox"/> No	Proper Clean-Up Action Taken: <input type="checkbox"/> Yes <input type="checkbox"/> No	
Further Action Required: <input type="checkbox"/> Yes <input type="checkbox"/> No		
Details:		



# ILLICIT CONNECTION/ ILLICIT DISCHARGE REPORTING & RESPONSE

Received by:	
Date:	Time Received:

REPORTING PARTY	
Name:	Anonymous: <input type="checkbox"/> Yes <input type="checkbox"/> No
Address:	Phone/email:

INCIDENT	
Date:	Time:
Location/ Address:	
Land Use: <input type="checkbox"/> Residential <input type="checkbox"/> Commercial <input type="checkbox"/> Industrial <input type="checkbox"/> Public	
Type of Material: <input type="checkbox"/> Hazardous <input type="checkbox"/> Wastewater <input type="checkbox"/> Oil/Grease <input type="checkbox"/> Sediment <input type="checkbox"/> Trash <input type="checkbox"/> Other _____ <input type="checkbox"/> Unknown	
Estimated Quantity: <input type="checkbox"/> Gallons <input type="checkbox"/> Lbs.	
Entered Storm Drain System/ Receiving Waters? <input type="checkbox"/> Yes <input type="checkbox"/> No	

<b>Description / Details</b>	

Agencies Contacted:	
<input type="checkbox"/> Office of Emergency Services <input type="checkbox"/> HazMat Team <input type="checkbox"/> LA County <input type="checkbox"/> Regional Board <input type="checkbox"/> Other	
Source Investigation Conducted?	Source Identified?
<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
Direct/ Constructed Connections Found? <input type="checkbox"/> Yes <input type="checkbox"/> No	

ALLEGED RESPONSIBLE PARTY	
Name:	
Address:	Phone/ email:
Vehicle License No:	

ACTION & CLOSURE	
Referred to:	Date:
Department:	Phone/ email:

<b>Actions Taken/ Details</b>	

<b>Date Closed:</b>
---------------------

# Spill Prevention Coordination

## Procedures

This attachment discusses spill prevention coordination procedures that identify:

- Divisions or sections responsible for responding to reports of spills
- General and specific spill response procedures including responsible division or section
- Spill response training activities
- Activities conducted to improve spill response procedures and equipment

## Divisions or Sections Responsible for Responding to Reports of Spills

Identify the divisions or sections responsible for responding to reports of spills and note divisions or sections that respond to specific types of spills such as hazardous materials spills or sewage spills. Also indicate the specific field staff who respond to spills and the level of support they provide to lead emergency response agencies and source of spill investigations.

## General and Specific Spill Response Procedures

Describe or reference general spill response procedures involved in responding to complaints and identifying spills through inspections. Include the spill response process from the spill identification stage through clean up and report preparation. Copies of the forms and reports prepared to document spills should also be included. Specific procedures for hazardous materials spills, floods, and sewage spills should be referenced. Contractor support for spill events, if applicable, should also be noted.

## Spill Response Training Activities

Provide an overview of all spill response training that is conducted within the various divisions and sections of the agencies.

## Activities to Improve Spill Response Procedures and Equipment

List all activities conducted within the implementing agency to improve spill response procedures and update equipment. Explain how improvements are identified, prioritized, and implemented. Include a schedule of how often spill response procedures and equipment are evaluate.

# Spill Investigation, Containment and Cleanup

## Investigation

Depending on the location of the spill and the type of material, the appropriate department/ agency should be notified. This may include:

- Storm drain maintenance, if the spill reaches the storm drain system
- Street and road maintenance, if the spill is in the public right-of-ways
- Sewer system maintenance, if the material is from the sewage system
- Industrial waste inspection, if the material is from industrial facilities
- Fire Departments/"first responders," if the material may be hazardous
- Contractors for hazardous materials, if the material is hazardous

These departments/agencies should determine the nature of the material and the extent of the spill. If any agency determines there is a chance that the spill involves hazardous materials, then the local Administering Agency will be notified. An example of spill investigation procedures is depicted in Figure D-1. Reporting procedures for hazardous substances are discussed further in Section 5 of this Illicit Connection/Illicit Discharge Elimination model program.

## **Containment and Cleanup**

Once the nature and extent of the spill is determined, the appropriate departments and field superintendents will be notified to contain and clean up the spill. The three types of cleanup scenarios are (1) hazardous, (2) wastewater, and (3) other non-hazardous materials.

### **Hazardous**

Handling procedures regarding releases of hazardous or potentially hazardous substances into the environment are covered in a number of federal and state regulations, including: Comprehensive Environmental Response, Compensation and Liability Act (CERCLA); Superfund Amendments and Reauthorization Act (SARA); Resource Conservation and Recovery Act (RCRA); and multiple bills codified under Division 20 of the California Health and Safety Code. These procedures are well established and are practiced by local hazardous materials response teams - generally a local Fire Department.

Material determined to be hazardous will be contained by the appropriate hazardous material response team. The team will contact an approved contractor for cleanup. Details are contained in the local *Emergency Response Procedures* manual.

### **Wastewater**

Field crews responding to a sewage spill or overflow should contain the spill to prevent entry of the sewage into the storm drain system or natural watercourse. This will involve a coordinated effort between the sewer, street, and storm drain maintenance crews.

To the maximum extent possible, sewage should be prevented from entering the storm drain system by covering or blocking storm drain inlets and catch basins or by containing or diverting the overflow away from open channels and other storm drain fixtures (using sandbags, inflatable dams, etc.).

In the event that raw sewage enters a storm drain catch basin, where possible the sewage should be vacuumed or pumped out of the catch basin. If a sewage overflow enters a storm drain channel, where possible the downstream channel area should be blocked, flushed with potable water and the captured water pumped to a nearby sewer manhole. Any time a sewage spill enters the storm drain system and has the potential to reach coastal waterways, the local agency and L.A. County Dept. of Health Services, Bureau of Environmental Protection must be notified (323) 881-4147.

Once the spill is contained, it should be removed and the area disinfected. Every effort should be made to ensure that the disinfectant is not discharged to the storm drain system, using methods such as those described above.

### **Other Non-hazardous Materials**

Non-hazardous materials should generally be removed by appropriate crews with knowledge of or jurisdiction over the location of the spill, as indicated in Section D.1. Because the situations and materials will vary widely, procedures will vary as well.

All materials should be prevented from entering waterways to the maximum extent possible. Many materials in sufficient quantities can deplete the oxygen level in receiving waters, or smother benthic communities. Typical examples of these materials include landscape waste, milk, flour, and many other organic liquids and solids or fine powders. These materials should generally be removed by first collecting and/or sweeping up all solids and disposing them in a landfill or other approved location. Liquids should be diverted to an area away from waterways where they may be removed with a vacuum truck or can soak into the ground.

**Guidance Source**

Los Angeles County Model Stormwater Quality Management Program, 2003.

DRAFT

Watershed Management Program Appendix 3

# A-3-2 Example Vacant Lot Ordinance

For the TSS Reduction Strategy

# EXAMPLE VACANT LOT ORDINANCE

*For the TSS Reduction Strategy (City of Whittier Municipal Code § 8.08.026)*

## 8.08.026 VACANT LOTS

For the purpose of this section, a vacant lot shall mean any property which is either undeveloped or has an existing on-site building/structure that is either abandoned, vacant and/or is un-leased by the property owner for more than thirty days.

All vacant lots within the city (except those that do not immediately front onto a public street, are less than five feet wide in width or depth, are identified on the city's zoning map as "open space," are used as designated habitat conservation or for active agricultural production) shall be maintained in accordance with the following provisions of this section within thirty days of becoming vacant:

- A. Unimproved Vacant Lot Types. Lots that are unimproved due to never having been developed or having become vacant subsequent to the removal of any pre-existing buildings, structures or impervious surfaces shall be subject to the approval of a vacant lot landscape and irrigation plan by the director of parks, recreation and community services and shall be improved and maintained at all times in accordance with the following provisions:
  1. Lots That Are Less Than One-Half Acre. For unimproved vacant lots that are less than one-half acre in size (21,780 square feet), the entire lot shall be improved and maintained in the following manner:
    - a) The property owner shall landscape the entire lot using drought tolerate or xeriscape material that requires little to no water after the first three years of growth. Durable, high quality, synthetic turf may also be used as an alternative. The landscape material selected shall be reviewed and approved to the satisfaction of the director of parks, recreation and community services prior to installation, per [Section 13.42.120](#) of the Whittier Municipal Code. The ground cover shall be maintained in good condition at all times.
    - b) The lot shall be improved with an operable automatic irrigation system for the ground cover which shall be installed and maintained in good condition by the property owner at all times.
    - c) The lot shall be maintained free of litter, weeds, graffiti, debris, including the stockpiling of any material, at all times. Any on-site litter, weeds, debris or stockpiling of material shall be immediately removed by the property owner, upon discovery. The property owner or their designated representative shall be responsible for inspecting the property at reasonable intervals or take other steps to reasonably ensure that no litter, weeds, graffiti, debris or material stockpiling collects or is maintained on the lot.

- d) Any dead or dying vegetation as well as any broken, malfunctioning or non-functioning irrigation components on the lot shall be replaced by the property owner within seventy-two hours of their discovery or notification. The property owner shall be responsible for inspecting the property at reasonable intervals, or take other steps to reasonably ensure that there is no dead or dying vegetation nor any broken, malfunctioning or non-functioning irrigation components on the lot.
  - e) At the discretion of the director of parks, recreation and community services the standards contained in Section 8.08.026(A)(2) (Lots that are one-half acre or greater) may be applied to vacant lots that are one-half acre or less if deemed appropriate to mitigate any one or more of the following circumstances:
    - i. To adequately secure the property from illegal dumping or other such illicit activities.
    - ii. Because of public safety concerns or hazards associated with the property.
    - iii. A declared state or regional drought.
2. Lots That Are One-Half Acre or Greater. For unimproved vacant lots that are one-half acre (21,780 square feet) or greater in size, the entire lot shall be improved and maintained in the following manner:
- a) The property owner shall provide a minimum five-foot wide landscape planter adjacent to all public rights-of-way (except those property lines located immediately adjacent to an alley) that abut their vacant lot.
  - b) All landscape planters shall be improved with an operable automatic irrigation system. The landscape material selected shall consist of drought tolerate or xeriscape material that requires little to no water after the first three years of growth. Durable, high quality, synthetic turf may also be used as an alternative. The landscape material selected shall be reviewed and approved to the satisfaction of the director of parks, recreation and community services prior to installation, per [Section 13.42.120](#) of the Whittier Municipal Code. The ground cover shall be maintained in good condition at all times.
  - c) All on-site landscaping and irrigation shall be maintained in good condition at all times by the property owner of the lot. Any dead or dying landscaping shall be replaced by the property owner within seventy-two hours of their discovery or notification, including any broken, malfunctioning or non-functioning irrigation components. The property owner shall be responsible for inspecting the property at reasonable intervals or take other steps to reasonably ensure that all of the landscaping and irrigation on the lot is maintained in good condition and there are no broken, malfunctioning or non-functioning irrigation components on the lot.
  - d) A six-foot high, view obscuring, decorative perimeter barrier shall be erected around the entire vacant lot, with a minimum five-foot wide perimeter

landscape planter in front of the fencing. In circumstances where the director of parks, recreation and community services finds that a higher perimeter barrier is warranted for adequate security of the site and/or because of unusual topographical circumstances associated with the vacant lot, the perimeter barrier may be constructed up to a maximum of eight feet high. All perimeter barriers shall include a gravel pathway leading to a security gate to provide accessibility to the interior of the lot for the police department or other emergency personnel. A key or security code for the gate shall be provided to the Whittier Police Department by the property owner upon installation and shall be kept up-to-date at all times.

- e) All decorative, view obscuring, perimeter barriers shall consist of either painted wood, redwood, woodcrete, green vinyl chain-link fencing with a green windscreen securely attached (along the interior of the fence), or any other durable, aesthetically attractive, material deemed acceptable to the director of parks, recreation and community services. On corner or reversed corner lots, all fencing shall comply with [Section 18.64.050](#) for visual safety.
  - f) All perimeter barriers shall be maintained in good condition at all times by the property owner. Any on-site graffiti shall be removed by the property owner within seventy-two hours of its discovery or notification. The property owner shall be responsible for inspecting the property at reasonable intervals.
- B. Improved Vacant Lots. Vacant lots improved with existing on-site buildings or structures that are vacant, abandoned, or un-leased for thirty days or more (as determined by the director of parks) shall be maintained by the property owner as follows:
- 1. All existing on-site landscaping and irrigation shall be maintained in good condition at all times and in accordance with the provisions contained in Chapters 8.08, 8.22 and [8.24](#) of this code, including any conditions of approval applied to the site as part of the approved vacant lot landscape and irrigation plan under Section 8.08.026(C).
  - 2. Any dead or dying vegetation as well as any broken, malfunctioning or non-functioning irrigation components for the lot shall be replaced by the property owner within seventy-two hours of their discovery or notification. The property owner or their designated representative shall be responsible for inspecting the property at reasonable intervals, or take other steps to reasonably ensure that there is no dead or dying vegetation nor any broken, malfunctioning or non-functioning irrigation components on the lot.
  - 3. The lot shall be maintained free of litter, weeds, and debris, including the stockpiling of any material, at all times. Any on-site litter, debris or stockpiling of material shall be immediately removed by the property owner, upon discovery or notification. The property owner or their designated representative shall be responsible for inspecting the property at reasonable intervals, or take other steps to reasonably ensure that no litter, weeds, graffiti, debris or material stockpiling collects or is maintained on the lot.

4. All on-site structures shall be maintained in good condition at all times. Damage to any on-site buildings or structures shall be abated within ten days by the property owner upon discovery. An alternative abatement period shall be required, if deemed necessary by the building official, to protect the public health, safety and welfare.
  5. The lot shall be adequately secured at all times to prevent illegal dumping, criminal activity, vandalism, graffiti, on-site loitering by the homeless and any/all other attractive nuisances to the satisfaction of the director of parks, recreation and community services and the chief of police.
- C. Vacant Lot Landscape and Irrigation Plan. Prior to the issuance of a demolition permit on any lot in which the construction of a new building, structure, parking lot, or impervious surface will not commence within thirty days after demolition, the property owner shall submit a vacant lot landscape and irrigation plan for review and approval of the director of parks, recreation and community services (with the appropriate plan check fees). The director of parks, recreation and community services may impose any reasonable conditions of approval on the vacant lot landscape and irrigation plan to ensure that the lot will be adequately maintained during the time that it is vacant. Upon approval of the plan, the landscape and irrigation improvements to the lot, as specified in the plan, shall be completed to the satisfaction of the director of parks, recreation and community services within thirty days after demolition. A reasonable extension of time may be granted by the director of parks, recreation and community services in those situations when the director, in his or her sole discretion, determines that a good faith effort is being made by the property owner to comply with the provisions of this section.
1. Appeal of Decision.
    - a) The decision of the director of parks, recreation and community services to approve, conditionally approve or deny any vacant lot landscape and irrigation plan may be appealed in writing to the city manager within fifteen calendar days. The decision of the city manager shall be final, unless appealed in writing to the city council within fifteen calendar days of the city manager's decision. All decisions of the city council shall be final.
    - b) At the sole discretion of the city council, the provisions contained within this ordinance may be made modified, as deemed appropriate, if a finding is made that the legal property owner has demonstrated an extreme financial hardship such as, but not limited to, the filing of bankruptcy, property tax default, their exists over six months of outstanding arrears to the monthly mortgage payment on the property, or any other extreme/unique hardship the city council believes is contrary to the purpose and intent of this ordinance.
- D. View Obscuring Barriers and Fencing on Vacant Lots. There shall be no on-site fencing or view obscuring perimeter barriers that screen any vacant lot in any manner that obstructs vehicular and/or pedestrian visibility of the public right-of-way, or interferes with the public's use of the public right-of-way, as determined by the director of public works. The directors of public works and parks, recreation and community services shall approve the location and design of all vacant lot fencing and perimeter barriers prior to the construction of any such fencing or barriers on a vacant lot.

- E. The director of parks, recreation and community services shall implement all applicable sections of Chapter 13.42 (Water Conservation in Landscaping), regardless of the size of the vacant lot, to ensure that the approved vacant lot landscape and irrigation plan conserves water to greatest extent possible, while preserving the health of the landscaping approved on the vacant lot.
- F. Where a recorded easement on vacant lot exists, the director of parks, recreation and community services may require and/or permit the property owner to use an appropriate ground cover over the easement (i.e., gravel, turf block, paving or some other acceptable material) that would enable a vehicle to drive over the easement. Any impervious surface approved over an easement shall be subject to the prior written approval of the easement holder.
- G. Implementation. All vacant lots, regardless of how they became vacant, that are existing at the time of the adoption of the ordinance shall be brought into immediate compliance with all applicable provisions of this section, unless currently landscaped and irrigated under a previously approved vacant lot and landscape and irrigation plan approved by the director of community development or director of parks, recreation and community services prior to the adoption of this current ordinance. A reasonable extension of time may be granted by the director of parks, recreation and community services in those situations when the director, at his or her sole discretion, determines that a good faith effort is being made by the property owner to comply with this section.
- H. Noncompliance Declared Nuisance. Failure to comply with any of the applicable requirements in this section shall constitute a public nuisance, as designated in Section 8.08.030, and the city attorney or the district attorney may commence an action or proceeding for civil abatement, removal and enjoinder thereof, in the manner proscribed by law; and shall take other steps and apply to such courts as may have jurisdiction to grant such relief as well as abate or remove the nuisance, including abatement in accordance with the provisions of this chapter.

(Ord. 2906 § 1, 2008)

(Ord. No. 2928, § 1, 6-23-09; Ord. No. 2958, § 3, 10-12-10)

Watershed Management Program Appendix 3

# A-3-3 Example Street Sweeping Municipal Code

For the TSS Reduction Strategy

DRAFT

# EXAMPLE MUNICIPAL CODE LANGUAGE FOR PRIVATE PARKING LOT SWEEPING

*For the TSS Reduction Program (City of Signal Hill Municipal Code § 12.16.060)*

## 12.16.060 ILLICIT DISCHARGES

- A. Except as otherwise permitted herein, all non-storm water discharges to the municipal storm drain system are prohibited.
- B. No person shall cause, facilitate or permit any illicit discharge to the municipal storm drain system.
- C. No person shall cause, facilitate or permit a discharge into an MS4 that causes or contributes to an exceedence of any water quality standard.
- D. No person shall cause, facilitate or permit any discharge into an MS4 that causes or threatens to cause a condition of pollution, contamination, or nuisance (as defined in California Water Code § 13050).
- E. No person shall cause, facilitate or permit any discharge into an MS4 containing pollutants which have not been reduced to the Maximum Extent Practicable.

⋮

⋮

⋮

⋮

⋮

⋮

**Q. All owners and operators of industrial and/or commercial motor vehicle parking lots containing more than twenty-five parking spaces shall conduct regular sweeping and other similar measures to minimize the discharge of pollutants and other debris in the municipal storm drain system.**

⋮

⋮

⋮

⋮

⋮

⋮

**V. Any person who violates the terms of this section shall immediately commence all appropriate response action to investigate, assess, remove and/or remediate any pollutants discharged as a result of such violation, and shall reimburse the City or other appropriate governmental agency, for all costs incurred in investigating, assessing, monitoring and/or removing, cleaning up, treating or remediating any pollutants resulting from such violation, including all reasonable attorneys' fees and environmental and related consulting fees incurred in connection therewith.**

⋮

⋮

⋮

⋮

⋮

⋮

(Ord. 2013-11-1462 § 1; Ord. 2003-02-1316 § 1; Ord. 2002-07-1304 § 2; Ord. 96-12-1215 § 1)

# Reasonable Assurance Analysis for Lower Los Angeles River, Los Cerritos Creek, and Lower San Gabriel River

---

***Submitted to:***

LLAR WMP Group

LCC WMP Group

LSGR WMP Group

***Submitted by:***



Tetra Tech  
9444 Balboa Ave., Suite 215  
San Diego, CA 92123



Paradigm Environmental  
4797 Seminole Dr  
San Diego, CA 92115

**June 6, 2014**



## Contents

<b>1. Introduction.....</b>	<b>6</b>
<b>2. Applicable Interim and Final Requirements.....</b>	<b>7</b>
<b>3. Modeling System used for the RAA.....</b>	<b>12</b>
3.1. Watershed Model - LSPC.....	12
3.2. Small-Scale BMP Model – SUSTAIN.....	17
3.3. Large-Scale BMP Optimization Tool – NIMS/SUSTAIN.....	17
<b>4. Current/Baseline Pollutant Loading.....</b>	<b>18</b>
4.1. Model Calibration to Existing Conditions.....	18
4.1.1. Hydrology Calibration.....	20
4.1.2. Water Quality Calibration.....	21
4.2. Current Best Management Practices/Minimum Control Measures.....	23
<b>5. Estimated Required Pollutant Load Reductions.....</b>	<b>24</b>
5.1. Selected Average (Interim) and Critical (Final) Conditions.....	24
5.2. Representative Conditions for Wet Weather.....	24
5.2.1. Average and 90 <sup>th</sup> Percentile Wet Years.....	24
5.2.2. 85 <sup>th</sup> Percentile, 24-hour Storm.....	25
5.2.3. Representative Conditions for Dry Weather.....	33
5.3. Calculated Required Pollutant Reductions to Achieve Final Limits.....	36
5.3.1. Wet-Weather Required Pollutant Reductions.....	38
5.3.2. Dry-Weather Pollutant Reduction Targets.....	43
<b>6. Determination of Potential BMP Capacity for RAA.....</b>	<b>45</b>
<b>7. Cumulative Volume Reduction Goals to Achieve Required Pollutant Reductions.....</b>	<b>46</b>
7.1. Volume Reductions for Structural BMPs.....	46
7.1.1. Wet Weather.....	46
7.1.2. Dry Weather.....	51
<b>8. MS4 Volume Reduction Goals to Achieve Required Pollutant Reductions.....</b>	<b>52</b>
8.1. Summary of MS4 Responsible Reduction Goals.....	52
<b>9. Pollutant Reduction Plan.....</b>	<b>54</b>
9.1. Existing/Planned Regional Control Measures.....	54
9.2. Future Control Measures for Attainment of Interim and Final Limits.....	55
9.2.1. Wet Weather.....	55
9.2.2. Dry Weather.....	66
<b>10. References.....</b>	<b>70</b>



## Tables

Table 2-1. Summary of schedule for interim and final milestones .....8

Table 2-2. Schedule of TMDL milestones for the Lower LA River .....9

Table 2-3. Schedule of TMDL milestones for Los Cerritos Channel WMP .....10

Table 2-4. Schedule of TMDL milestones for the Lower San Gabriel River WMP .....11

Table 4-1. Model assessment criteria from the RAA Guidelines .....20

Table 4-2. Summary of model hydrology calibration performance for Lower Los Angeles River .....20

Table 4-3. Summary of model hydrology calibration performance for Lower San Gabriel River .....20

Table 4-4. Summary of model performance by constituent at the Los Angeles River (S10) monitoring location ....21

Table 4-5. Summary of model performance by constituent at Los Cerritos Channel (Stearns St.) monitoring location .....21

Table 4-6. Summary of model performance by constituent at the San Gabriel River (S14) monitoring location.....22

Table 4-7. Summary of model performance by constituent at the Coyote Creek (S13) monitoring location .....22

Table 4-8. 90<sup>th</sup> percentile concentrations assumed for non-modeled pollutants .....23

Table 5-1. Average Rainfall Volumes (Water Years 2002–2011 vs. 25-year Average and 90<sup>th</sup> Percentile).....26

Table 5-2. Average Rainfall Intensity (Water Years 2002–2011 vs. 25-year Average and 90<sup>th</sup> Percentile) .....26

Table 5-3. Consecutive 30-day Dry Periods per month by WMP and rainfall gage (10/1/1987 – 9/30/2011) .....34

Table 5-4. Applicable wet weather TMDL targets for Category 1 WQ Priorities .....36

Table 5-5. Applicable dry weather TMDL targets for Category 1 WQ Priorities .....37

Table 5-6. Wet-weather pollutant reduction targets by WMP area with analysis of limiting pollutants **Error! Bookmark not defined.**

Table 5-7. Existing condition dry-weather loads by water body .....43

Table 5-8. Allowable TMDL dry-weather loads by water body .....44

Table 5-9. Required dry-weather percent reductions by water body .....44

Table 7-1. Annual volume reduction goals to achieve interim and final milestones for Lower Los Angeles River WMP by jurisdiction .....47

Table 7-2. Annual volume reduction goals to achieve interim and final milestones for Los Cerritos Channel WMP by jurisdiction .....48

Table 7-3. Annual volume reduction goals to achieve interim and final milestones for Lower San Gabriel River WMP .....49

Table 7-4. Annual volume reduction goals to achieve interim and final milestones for the Coyote Creek portion of Lower San Gabriel River WMP by jurisdiction.....50

Table 7-5. Projected dry weather reductions from non-structural control measures .....51

Table 8-1. Lower Los Angeles River Critical Year Runoff Volume from MS4 and Non-MS4 Facilities .....52

Table 8-2. Los Cerritos Channel Critical Year Runoff Volume from MS4 and Non-MS4 Facilities .....52

Table 8-3. San Gabriel River Critical Year Runoff Volume from MS4 and Non-MS4 Facilities .....53

Table 8-4. Coyote Creek Critical Year Runoff Volume from MS4 and Non-MS4 Facilities.....53

Table 9-1. Lower Los Angeles River Critical Year Existing/Planned Regional BMP Runoff Volume Reductions ...54

Table 9-2. Lower San Gabriel River Critical Year Existing/Planned Regional BMP Runoff Volume Reductions ...54



Table 9-3. Jurisdictional Final Target BMP Volumes by WMP Group.....56

Table 9-4. Lower Los Angeles River Pollutant Reduction Plan for Attainment of Interim and Final Limits.....60

Table 9-5. Los Cerritos Channel Pollutant Reduction Plan for Attainment of Interim and Final Limits .....61

Table 9-6. San Gabriel River Pollutant Reduction Plan for Attainment of Interim and Final Limits .....62

Table 9-7. Coyote Creek Pollutant Reduction Plan for Attainment of Interim and Final Limits.....64

Table 9-8. Lower Los Angeles River Dry Weather Pollutant Reduction Plan for Attainment of Interim and Final Limits .....66

Table 9-9. Los Cerritos Channel Dry Weather Pollutant Reduction Plan for Attainment of Interim and Final Limits67

Table 9-10. San Gabriel River Dry Weather Pollutant Reduction Plan for Attainment of Interim and Final Limits ..68

Table 9-11. Coyote Creek Dry Weather Pollutant Reduction Plan for Attainment of Interim and Final Limits .....69

DRAFT



## Figures

Figure 3-1. WMMS model domain and represented land uses and slopes by subwatershed .....	13
Figure 3-2. Lower LA River WMP Area subwatersheds represented by WMMS.....	14
Figure 3-3. Los Cerritos WMP Area subwatersheds represented by WMMS .....	15
Figure 3-4. Lower San Gabriel River WMP Area subwatersheds represented by WMMS .....	16
Figure 4-1. WMP groups hydrology and water quality calibration sites. ....	19
Figure 5-1. Two Types of Numeric Goals and WMP Compliance Paths according to the Permits .....	24
Figure 5-2. Rainfall depths associated with the 85 <sup>th</sup> percentile, 24-hour storm. ....	27
Figure 5-3. Temporal Distribution for 85th Percentile 24-hour Storm for LSPC Simulation.....	28
Figure 5-4. Rainfall and Runoff Depths Associated with 85th Percentile Rainfall in the WMP subwatersheds.....	28
Figure 5-5. Runoff Volume Associated with the 85th Percentile, 24-hour Storm (by jurisdiction).....	29
Figure 5-6. Runoff Associated with the 85th Percentile, 24-hour Storm for Lower Los Angeles River.....	30
Figure 5-7. Runoff Associated with the 85th Percentile, 24-hour Storm for Los Cerritos Channel .....	31
Figure 5-8. Runoff Associated with the 85th Percentile, 24-hour Storm for Lower San Gabriel River. ....	32
Figure 5-9. Spatiotemporal summary of non-wet weather conditions in the Lower Los Angeles River WMP area.	35
Figure 5-10. Analysis of summary of non-wet weather conditions in the Los Cerritos Channel WMP area.....	35
Figure 5-11. Spatiotemporal summary of non-wet weather conditions in the Lower San Gabriel River WMP area.	35
Figure 5-12. Wet-weather pollutant reduction targets and limiting pollutant for Lower Los Angeles River WMP. ....	40
Figure 5-13. Wet-weather pollutant reduction targets and limiting pollutant for Los Cerritos Chanel WMP. ....	40
Figure 5-14. Wet-weather pollutant reduction targets and limiting pollutant for Lower San Gabriel River. ....	41
Figure 5-15. Wet-weather pollutant reduction targets and limiting pollutant for Coyote Creek.....	41
Figure 6-1. Illustration of Process for Determining Required BMP Capacities for the WMP using Volume-Based (top panel) and Load-Based (bottom panel) Numeric Goals.....	45
Figure 9-1. LLAR implementation areas associated with Interim and final milestones.....	57
Figure 9-2. LCC implementation areas associated with Interim and final milestones.....	58
Figure 9-3. LSGR implementation areas associated with Interim and final milestones.....	59

# 1. Introduction

---

The Municipal Separate Storm Sewer System Permit (Permits) for Los Angeles County<sup>1</sup> and the City of Long Beach<sup>2</sup> includes optional provisions for a Watershed Management Program (WMP) that allows permittees the flexibility to customize their stormwater programs to achieve compliance with applicable receiving water limitations (RWLs) and water quality based effluent limitations (WQBELs) through implementation of control measures. A key element of each WMP is the Reasonable Assurance Analysis (RAA), which is used to demonstrate “that the activities and control measures...will achieve applicable WQBELs and/or RWLs with compliance deadlines during the Permit term” (NPDES Permit Order No. R4-2012-0175, Section C.5.b.iv.[5], page 64; NPDES Permit Order No. R4-2014-0024, Section C.5.h.vii.[2]). This report presents the Reasonable Assurance Analysis (RAA) for the Lower Los Angeles River (LLAR), Los Cerritos Channel (LCC), and Lower San Gabriel River (LSGR) WMPs.

While the Permits prescribe the RAA as a quantitative demonstration that control measures (best management practices [BMPs]) will be effective, the RAA also promotes a modeling process to identify and prioritize potential control measures to be implemented by the WMP. In other words, the RAA not only demonstrates the cumulative effectiveness of BMPs to be implemented, it also supports their *selection*. Furthermore, the RAA incorporates the applicable compliance dates and milestones for attainment of the WQBELs and RWLs, and therefore supports BMP scheduling.

On March 25, 2014, the Los Angeles Regional Water Quality Control Board (Regional Board) issued “RAA Guidelines” (LARWQCB 2014) to provide information and guidance to assist permittees in development of the RAA. The approach herein is consistent with the RAA Guidelines.

This report is organized in nine sections, as follows:

- Section 1: Introduction
- Section 2: Applicable Interim and Final Requirements
- Section 3: Modeling System to be used for the RAA
- Section 4: Current/Baseline Pollutant Loading
- Section 5: Estimated Required Pollutant Reductions
- Section 6: Determination of BMP Capacity for RAA
- Section 7: Cumulative Volume Reduction Goals to Achieve Required Reductions
- Section 8: Pollutant Reduction Plan
- Section 9: References

---

<sup>1</sup> National Pollutant Discharge Elimination System Permit Order No. R4-2012-0175

<sup>2</sup> National Pollutant Discharge Elimination System Permit Order No. R4-2014-0024



## 2. Applicable Interim and Final Requirements

The WMPs for LLAR, LCC, and LSGR follow the process in the Permits and identify the Water Quality Priorities (WQ Priorities) including the highest (Category 1) Water Quality Priorities which are subject to Total Maximum Daily Loads (TMDLs) and WQBELs. Practically all of these TMDLs include associated compliance schedules that are considered in this RAA. The TMDL and WMP milestones/compliance dates establish the pace at which BMPs must be implemented. Traditionally, the approach of TMDL implementation plans has been focused on *final* TMDL compliance, whereas the Permit compliance paths offered to WMPs increase emphasis on *milestones*. In line with the RAA Guidelines, for all final TMDL and TMDL/WMP milestones that occur in the next two Permit cycles, the combination of BMPs expected to result in attainment of the corresponding Permit limits are identified.

The TMDL milestones for the LLAR, LCC, and LSGR WMP areas are shown in Table 2-2 through Table 2-4. The Permits require each WMP to provide reasonable assurance for the TMDL milestones that occur in the current Permit term. If applicable TMDLs do not prescribe a milestone in the current Permits, a milestone must be established. The array of TMDLs creates a potentially complicated sequence based on multiple pollutants, and thus this RAA includes a limiting pollutant analysis. As described in Section 5, the identified limiting pollutant for wet weather is zinc for LLAR, LCC, and LSGR. As such, the wet weather milestones for the Los Angeles River, Los Cerritos Channel, and San Gabriel River Metals TMDLs establish the pace of stormwater BMP implementation. The wet weather milestones established for the current Permits include the following:

- **Lower Los Angeles River:** Achieve 31% of the required reduction by September 30, 2017. This milestone was created for the WMP, as the metals TMDL includes a 25% milestone in 2012 (prior to the current Permit term) and a 50% milestone in 2024 (beyond the current Permit term). Achievement of this milestone for zinc provides reasonable assurance of achieving a similar or greater reduction for other WQ Priorities.
- **Los Cerritos Channel:** Achieve 10% of the required reduction<sup>3</sup> by September 30, 2017. This milestone is directly from the metals TMDL. Achievement of this milestone for zinc provides reasonable assurance of achieving a similar or greater reduction for other WQ Priorities.
- **Lower San Gabriel River:** Achieve 10% of the required reduction by September 30, 2017. This milestone is directly from the metals TMDL. Achievement of this milestone for zinc provides reasonable assurance of achieving a similar or greater reduction for other WQ Priorities.

The pollutant reduction plan to achieve these milestones is described in Section 8, along with the plan to achieve the milestones for the next Permit term (achieve 35% of the required reduction in LCC and LSGR and achieve 50% of the required reduction in LLAR). A summary of the milestones within the current and next Permit terms and final milestone based on final TMDLs are summarized in Table 2-1. The required reductions that form the basis of the milestones are calculated in Section 5.

---

<sup>3</sup> The interim milestones are expressed in terms of the *required* reduction not total reduction (e.g., if the required reduction to attain final limits is 50%, then the 10% milestone equates to a 5% reduction). These reductions are calculated in Section 5.



**Table 2-1. Summary of schedule for interim and final milestones**

<b>WMP Area</b>	<b>Milestone 1 (2017)</b>	<b>Milestone 2 (interim date of applicable metals TMDL)</b>	<b>Milestone 3 (final date of applicable metals TMDL)</b>
LLAR	31%	50%	100%
LCC	10%	35%	100%
LSGR	10%	35%	100%

DRAFT



Table 2-2. Schedule of TMDL milestones for the Lower LA River

TMDL	Constituents	Compliance Goal	Weather Condition	Compliance Dates and Compliance Milestone (Bolded numbers indicated milestone deadlines within the current Permit term) <sup>1</sup>										
				2012	2013	2014	2015	2016	2020	2024	2028	2032	2037	
LAR Nutrients	Ammonia-N, Nitrate-N, Nitrite-N, Nitrate-N+Nitrite-N	Meet WQBELs	All	Pre 2012										
				Final										
LAR Trash	Trash	% Reduction	All	9/30	9/30	9/30	9/30	9/30						
				70%	80%	<b>90%</b>	<b>96.70%</b>	<b>100%</b>						
LAR Metals	Copper, Lead	% of MS4 area Meets WQBELs	Dry	1/11					1/11	1/11				
				50%					75%	100%				
	Copper, Lead, Zinc, Cadmium	% of MS4 area Meets WQBELs	Wet	1/11						1/11	1/11			
				25%						50%	100%			
LA River Bacteria	<i>E. coli</i>	Meet WQBELs	Wet and Dry <sup>2</sup>										3/23	
													Final	
Dominguez Channel and LA/LB Harbors Toxics	Sediment: DDTs, PCBs, Copper, Lead, Zinc, PAHs	Meet WQBELs	All	12/28									3/23	
				Interim									Final	
Long Beach City Beaches and LAR Estuary Bacteria	Total Coliform, Fecal Coliform, Enterococcus	Meet WLAs	All	USEPA TMDLs, which do not contain interim milestones or implementation schedule. The Permits allow MS4 Permittees to propose a schedule in a WMP.										

<sup>1</sup>The Permit term is assumed to be five years from the Los Angeles County Permit effective date or December 27, 2017.

<sup>2</sup>The schedule for attaining the dry weather Bacteria TMDL is not shown in Table 3-2, which is stepwise by reach/segment and depends on whether a Load Reduction Strategy is developed for implementation.



**Table 2-3. Schedule of TMDL milestones for Los Cerritos Channel WMP**

TMDL	Constituents	Compliance Goal	Weather Condition	Compliance Dates and Compliance Milestone										
				(Bolded numbers indicated milestone deadlines within the current Permit term) <sup>1</sup>										
				2012	2013	2014	2015	2016	2017	2020	2023	2026	2032	
Los Cerritos Channel Metals	Copper	% Load Reduction <u>or</u> % of MS4 area Meets WQBELs	Dry							9/30	9/30			
										<b>30%</b>	70%	100%		
	Copper, Lead, Zinc	% Load Reduction <u>or</u> % of MS4 area Meets WQBELs	Wet							9/30	9/30			
										<b>10%</b>	35%	70%	100%	
Dominguez Channel and LA/LB Harbors Toxics	Sediment: DDTs, PCBs, Copper, Lead, Zinc, PAHs	Meet WQBELs	All	12/28										3/23
				Interim										Final

<sup>1</sup> The Permit term is assumed to be five years from the Los Angeles County Permit effective date or December 27, 2017.



Table 2-4. Schedule of TMDL milestones for the Lower San Gabriel River WMP

TMDL	Constituents	Compliance Goal	Weather Condition	Compliance Dates and Compliance Milestone (Bolded numbers indicated milestone deadlines within the current Permit term) <sup>1</sup>										
				2012	2013	2014	2015	2016	2017	2020	2023	2026	2032	
San Gabriel River Metals	Copper, Selenium	% Load Reduction <u>or</u> % of MS4 area Meets WQBELs	Dry							9/30	9/30			
										<b>30%</b>	70%	100%		
San Gabriel River Metals	Copper, Lead, Zinc	% Load Reduction <u>or</u> % of MS4 area Meets WQBELs	Wet							9/30	9/30			
										<b>10%</b>	35%	70%	100%	
Dominguez Channel and LA/LB Harbors Toxics	Sediment: DDTs, PCBs, Copper, Lead, Zinc, PAHs	Meet WQBELs	All	12/28										3/23
				Interim										Final

<sup>1</sup>The Permit term is assumed to be five years from the Los Angeles County Permit effective date or December 27, 2017.

## 3. Modeling System used for the RAA

The Watershed Management Modeling System (WMMS) was used to develop this RAA. WMMS is specified in the Permits as a potential tool to conduct the RAA. The Los Angeles County Flood Control District (LACFCD), through a joint effort with U.S. Environmental Protection Agency (USEPA), developed WMMS specifically to support informed decisions associated with managing stormwater. The ultimate goal of WMMS is to identify cost-effective water quality improvement projects through an integrated, watershed-based approach. The WMMS encompasses Los Angeles County's coastal watersheds of approximately 3,100 square miles, representing 2,566 subwatersheds (Figure 3-1). As described in the following subsections, WMMS is a modeling system that incorporates three tools: (1) the watershed model for prediction of long-term hydrology and pollutant loading, (2) a BMP model, and (3) a BMP optimization tool to support regional, cost-effective planning efforts. A version of WMMS is available for public download from LACFCD.

The version of WMMS to be used for the RAA in the LLAR, LLC, and LSGR WMPs is customized from the public download version, including the following modification/enhancements:

- Updates to meteorological records to represent the last 10 years (per the RAA Guidelines) and to allow for simulation of the design storm;
- Calibration adjustments to incorporate the most recent 10 years of water quality data collected at the nearby mass emission station;
- Application of a second-tier of BMP optimization using System for Urban Stormwater Treatment and Analysis INtegration (SUSTAIN), which replaces the Nonlinearity-Interval Mapping Scheme (NIMS) component of WMMS.
- Optimization of BMP effectiveness for removal of bacteria pollutants (rather than metals only); and
- Updates to Geographic Information System (GIS) layers, as available.

The subwatersheds in the LLAR, LLC, and LSGR WMP areas that are represented by WMMS are shown in Figure 3-2 through Figure 3-4, which include modifications to confine to jurisdictional boundaries included in these WMP areas. Also shown are the "RAA assessment points", which are used to calculate required load reductions (described in Section 5).

### 3.1. Watershed Model - LSPC

The watershed model included within WMMS is the Loading Simulation Program C++ (LSPC) (Shen et al. 2004; Tetra Tech and USEPA 2002; USEPA 2003). LSPC is a watershed modeling system for simulating watershed hydrology, erosion, and water quality processes, as well as in-stream transport processes. LSPC also integrates a geographic information system (GIS), comprehensive data storage and management capabilities, and a data analysis/post-processing system into a convenient PC-based Windows environment. The algorithms of LSPC are identical to a subset of those in the Hydrologic Simulation Program-FORTRAN (HSPF) model with selected additions, such as algorithms to dynamically address land use change over time. Another advantage of LSPC is that there is no inherent limit to the size and resolution of the model than can be developed, making it an attractive option for modeling the Los Angeles region watersheds. USEPA's Office of Research and Development (Athens, Georgia) first made LSPC available as a component of USEPA's National TMDL Toolbox (<http://www.epa.gov/athens/wwqtsc/index.html>). LSPC has been further enhanced with expanded capabilities since its original public release.

The WMMS development effort culminated in a comprehensive watershed model of the Los Angeles County Flood Control District that includes the unique hydrology and hydraulics of the system and characterization of water quality loading, fate, and transport for all the key TMDL constituents (LACDPW 2010a, 2010b). Since the original development of the WMMS LSPC model, Los Angeles County personnel have independently updated the model with meteorological data through April 2012.

To support the objectives of the WMPs, jurisdictional boundaries were also intersected with the WMMS LSPC model subwatersheds resulting in a finer resolution spatial unit for modeling. Model land use was then resampled using this subwatershed-jurisdiction intersect, properly distributing land use categories at the jurisdictional level for attributing sources, while maintaining hydrologic connectivity within the watershed model. This refinement introduced a new layer of resolution, facilitating the rollup of modeled results by jurisdiction to better support source attribution and implementation responsibilities among the participating entities.



Figure 3-1. WMMS model domain and represented land uses and slopes by subwatershed




Figure 3-2. Lower LA River WMP Area subwatersheds represented by WMMs




Figure 3-3. Los Cerritos WMP Area subwatersheds represented by WMMS




Figure 3-4. Lower San Gabriel River WMP Area subwatersheds represented by WMMS

### 3.2. Small-Scale BMP Model – SUSTAIN

The System for Urban Stormwater Treatment and Analysis INtegration (SUSTAIN) was developed by USEPA to support practitioners in developing cost-effective management plans for municipal storm water programs and evaluating and selecting BMPs to achieve water resource goals (USEPA, 2009). It was specifically developed as a decision-support system for selection and placement of BMPs at strategic locations in urban watersheds. It includes a process-based continuous simulation BMP module for representing flow and pollutant transport routing through various types of structural BMPs. Users are given the option to select from various algorithms for certain processes (e.g., flow routing, infiltration, etc.) depending on available data, consistency with coupled modeling assumptions, and the level of detail required. Figure 2-3 shows images from the SUSTAIN model user interface and documentation depicting some of the available BMP simulation options in a watershed context.




Figure 2-3. SUSTAIN model interface illustrating some available BMPs in watershed settings

SUSTAIN extends the capabilities and functionality of traditionally available models by providing integrated analysis of water quantity, quality, and *cost factors*. The SUSTAIN model in WMMS includes a cost database comprised of typical BMP component cost data from a number of published sources including BMPs constructed and maintained in Los Angeles County. SUSTAIN considers certain BMP properties as “decision variables,” meaning that they are permitted to change within a given range during model simulation to support BMP selection and placement optimization. As BMP size changes, so do cost and performance. SUSTAIN runs iteratively to generate a cost-effectiveness curve comprised of optimized BMP combinations within the modeled study area (e.g., the model evaluates the optimal width and depth of certain BMPs to determine the most cost-effective configurations for planning purposes).

### 3.3. Large-Scale BMP Optimization Tool – NIMS/SUSTAIN

WMMS was specifically designed to dynamically evaluate effectiveness of BMPs implemented in subwatersheds for meeting downstream RWLs while maximizing cost-benefit. WMMS employs optimization based on an algorithm names Nonlinearity-Interval Mapping Scheme (NIMS) to navigate through the many potential scenarios of BMP strategies and identify the strategies that are the most cost effective (Zou et al. 2010). Given the relatively small spatial scale of the WMP area, NIMS was not applied for this study. Instead, a two-tiered approach was applied using the NSGA-II solution technique available in SUSTAIN. For Tier 1, treatment capacities were optimized for each contributing segment, which resulted in unique cost-effectiveness curves for each segment based on available opportunities therein. For Tier 2, the search space was composed of Tier 1 solutions, thereby streamlining the search process. The resulting Tier 2 curve represents the optimal large scale solution because it is comprised of optimized Tier 1 solutions. This approach is especially useful for prioritizing areas for management for scheduling implementation milestones as described in Section 8.

## 4. Current/Baseline Pollutant Loading

The LSPC model within WMMS was reconfigured and recalibrated specifically for the WMP areas to provide an estimate of current/existing pollutant loads from jurisdictions within the WMPs. Reconfiguration of model subwatersheds was performed to provide specific accounting of loadings from individual jurisdictions. Calibrations were performed to meet specifications of the RAA Guidelines (LARWQCB 2014).

### 4.1. Model Calibration to Existing Conditions

The LSPC watershed model was originally calibrated for hydrology using a regional approach relying on USGS observed daily streamflow datasets through Water Year (WY) 2006 (LACDPW 2010a). Water Quality was then calibrated using small-scale, land use level water quality monitoring data to develop representative event mean concentrations by land use (LACDPW 2010b). Model performance was also validated at the mass emissions monitoring stations in the context of a county-wide modeling effort. The calibration period for the original WMMS LSPC model began in 1996 and ended in 2006. For the RAA, an analysis was performed to evaluate performance of the LSPC model as it relates to the LLAR, LCC, and LSGR watersheds to understand and benchmark its applicability for use as a baseline condition. The evaluation of monitoring data was extended beyond the original WMMS-LSPC calibration to include the period from 10/1/2001 through 9/30/2011 incorporating both the average year (WY 2008) and 90<sup>th</sup> percentile (WY 2003) year.

Data available for the LACDPW water quality and hydrologic monitoring stations, S10 and F319 were used to reexamine simulated water quality and hydrology conditions in LA River. The two stations are co-located just south of the West Wardlow Road overpass and drain approximately 800 square miles, or nearly the entire LA River watershed. The monitoring stations were selected for comparison due to their location near the outlet of the LA River watershed, which encompasses the aggregate contributions of all upstream pollutant sources. The selected flow gage, F319, was also used to calibrate the WMMS LSPC model and, therefore, links the current and previous efforts. Water quality and hydrologic records for WYs 2003–2011 were compared to the simulated watershed model output to determine the necessary model parameter adjustments to establish an up-to-date model calibration. The locations of these two gages are presented in Figure 4-1. Statistical summaries and flow regime analysis of the water quality monitoring datasets from the Los Angeles River mass emission station S10 are presented in Attachment E.

Watershed model simulation of existing water quality conditions for the LCC watershed were evaluated for WYs 2003–2011 using data collected at the City of Long Beach Stearns Street monitoring location, just north of interstate 405. The water quality monitoring location is positioned at the WMP hydrologic outlet and captures the cumulative watershed loading effects impacting water quality conditions in this 27 square mile portion of the LCC watershed. No flow monitoring data are available in the watershed, thus simulated flow conditions could not be evaluated against observed data for LCC. The location of the water quality monitoring is presented in Figure 4-1 below and statistical summaries of the monitoring dataset are presented in Attachment E.

For the LSGR, hydrology was re-assessed at two monitoring locations using available data from WYs 2001-2011. The two monitoring locations selected include USGS 11087020 San Gabriel River at Whittier Narrows Dam CA and the LACDPW streamflow gage F354 located along Coyote Creek south of Spring Street (coincident with mass emission station S13). The USGS gage was selected for continuity with the development and calibration of the original WMMS LSPC modeling system. The primary monitoring location selected to calibrate water quality for LSGR was the LA County mass emission station S14. The San Gabriel River Monitoring Station is located below San Gabriel River Parkway in Pico Rivera. At this location the upstream tributary area is 450 square miles (LACDPW 2013). A second mass emission station, the Coyote Creek Monitoring Station (S13) located below Spring Street in the lower San Gabriel River watershed was also used to validate the water quality calibration. The locations of these two gages are presented below in Figure 4-1. Statistical summaries and flow regime analysis of the water quality monitoring datasets from the San Gabriel River and Coyote Creek mass emission stations S14 and S13 are presented in Attachment E.




Figure 4-1. WMP groups hydrology and water quality calibration sites.

To demonstrate the ability to predict the effect of watershed processes and management actions, model calibration and validation are necessary and critical steps in any model application. Acceptable model calibration criteria for

benchmarking an RAA were developed by the Regional Board and are listed below in Table 4-1 (LARWQCB 2014). The objectives of establishing model assessment criteria are to ensure the calibrated model reflects all the model conditions and properly utilizes the available modeling parameters, thus yielding meaningful results. The lower bound of “Fair” level of agreement listed in Table 4-1 is considered a target tolerance for the model calibration process.

**Table 4-1. Model assessment criteria from the RAA Guidelines**

Constituent Group	Percent Difference Between Modeled and Observed		
	Very Good	Good	Fair
Hydrology / Flow	0 – 10	>10 – 15	>15 – 25
Sediment	0 – 20	>20 – 30	>30 – 40
Water Quality	0 – 15	>15 – 25	>25 – 35
Pesticides / Toxics	0 – 20	>20 – 30	>30 – 40

#### 4.1.1. Hydrology Calibration

Table 4-2 and Table 4-3 present the hydrology calibration assessment for the Lower Los Angeles River and Lower San Gabriel River gages, respectively. Nash-Sutcliffe efficiency is a correlation coefficient commonly used in hydrological modeling to measure how well a model predicts temporal variation. A value of 1.0 means a perfect match between modeled and observed. A value of 0 means that the computed mean of observed data is as good a predictor as the model. A negative value means that the data-mean is a better predictor than the model. Because the Regional Board guidance only required annual average flow volume metric, evaluating Nash-Sutcliffe helped to demonstrate that the model also performed well at predicting *intra-annual* flow variability.

**Table 4-2. Summary of model hydrology calibration performance for Lower Los Angeles River**

Water Quality Parameter	Model Period	Hydrology Parameter	Modeled vs. Observed Volume (% Error)	Regional Board Guidance Assessment
In-stream flow at Los Angeles River below Wardlow Road (LA DPW F319)	10/1/2002 – 9/30/2011	Flow Volume	11.88	Good
		Nash-Sutcliffe	0.678	n/a

**Table 4-3. Summary of model hydrology calibration performance for Lower San Gabriel River**

Water Quality Parameter	Model Period	Hydrology Parameter	Modeled vs. Observed Volume (% Error)	Regional Board Guidance Assessment
In-stream flow at SAN GABRIEL R AB WHITTIER NARROWS DAM CA (USGS 1108702)	10/1/2001 – 9/30/2011	Flow Volume	-19.0	Fair
		Nash-Sutcliffe	0.74	n/a
Coyote Creek near Spring Street (LA DPW F354)	10/1/2003 – 9/30/2011	Flow Volume	4.9	Very Good
		Nash-Sutcliffe	0.61	n/a



#### 4.1.2. Water Quality Calibration

Water quality calibration for the LLAR, LCC, and LSGR incorporated sampling from LA County mass emission stations at S10 (LA River), Stearns Street (LCC), and S13 and S14 along Coyote Creek and the San Gabriel River, respectively. The updated observed concentration data collected at these sites were used to refine the calibration and benchmark model performance. Daily observed loads were calculated by multiplying observed concentration and daily observed flow. Daily loads were estimated for LCC using simulated flows due to the lack of observed data. The percent error between this daily observed load and the daily modeled load was then calculated for each constituent. The results of this evaluation at the two gages are presented in Table 4-4 through Table 4-7.

**Table 4-4. Summary of model performance by constituent at the Los Angeles River (S10) monitoring location**

Water Quality Parameter	Sample Count	Modeled vs. Observed Load (% Error)	Regional Board Guidance Assessment
Total Sediment	91	-6.8	Very Good
Total Copper	58	-3.4	Very Good
Total Zinc	58	-18.1	Good
Total Lead	52	-0.1	Very Good
Fecal Coliform	57	-5.1	Very Good
Total Nitrogen	58	-4.0	Very Good
Total Phosphorous	57	6.9	Very Good

**Table 4-5. Summary of model performance by constituent at Los Cerritos Channel (Stearns St.) monitoring location**

Water Quality Parameter	Sample Count	Modeled vs. Observed Load (% Error)	Regional Board Guidance Assessment
Total Sediment	85	2.7	Very Good
Total Copper	57	-2.1	Very Good
Total Zinc	56	1.5	Very Good
Total Lead	57	2.2	Very Good
Fecal Coliform	55	1.0	Very Good
Total Nitrogen	56	17.5	Good
Total Phosphorous	56	-0.4	Very Good

**Table 4-6. Summary of model performance by constituent at the San Gabriel River (S14) monitoring location**

Water Quality Parameter	Sample Count	Modeled vs. Observed Load (% Error)	Regional Board Guidance Assessment
Total Sediment	45	8.57	Very Good
Total Copper	42	-9	Very Good
Total Zinc	44	16.1	Very Good
Total Lead	44	-3.97	Very Good
Fecal Coliform	43	1.85	Very Good
Total Nitrogen	<i>Not evaluated at this location</i>		
Total Phosphorous	44	-2.27	Very Good

**Table 4-7. Summary of model performance by constituent at the Coyote Creek (S13) monitoring location**

Water Quality Parameter	Sample Count	Modeled vs. Observed Load (% Error)	Regional Board Guidance Assessment
Total Sediment	42	1.28	Very Good
Total Copper	27	-28.9	Fair
Total Zinc	27	-32.44	Fair
Total Lead	25	-1.58	Very Good
Fecal Coliform	24	-34.48	Fair
Total Nitrogen	<i>Not evaluated at this location</i>		
Total Phosphorous			

Two fecal coliform samples were removed from the observed dataset at the San Gabriel River S14 mass emission station prior to performing the load calculation. These two samples appear to be outliers in the dataset with concentration values 10-100x greater than the remaining samples. These observations occurred on 10/17/2005 and 10/13/2009.

For pollutants not explicitly represented in the WMMS LSPC model, and for dry weather analysis, 90th percentile concentrations were calculated based on observed monitoring data at the LACDPW mass emission sites. The 90th percentile concentration was used for compliance with the Regional Board RAA guidelines (LARWQCB 2014). A summary of the 90th percentile concentrations for each constituent and waterbody are presented below in Table 4-8. For subsequent load reduction analyses, these concentrations were assumed for all wet or dry weather conditions they were assigned to represent existing conditions within their respective watersheds.

**Table 4-8. 90<sup>th</sup> percentile concentrations assumed for non-modeled pollutants**

Waterbody	Pollutant	Wet Weather	Dry Weather	90th Percentile Concentration	Units
Los Angeles River (S10)	DDT	•		0.005 <sup>1</sup>	ug/L
	PCBs	•		0.0325 <sup>1</sup>	ug/L
	PAHs	•		0.835 <sup>1</sup>	ug/L
	Cadmium	•		4.8	ug/l
	Copper		•	25.68	ug/l
	Lead		•	3.43	ug/l
	<i>E. coli</i>		•	19,600	MPN/100 mL
Los Cerritos Channel (Stearns)	DDT	•		0.005 <sup>1</sup>	ug/L
	PCBs	•		0.0325 <sup>1</sup>	ug/L
	PAHs	•		0.835 <sup>1</sup>	ug/L
	Copper		•	25.4	ug/l
	<i>E. coli</i>		•	14,200	MPN/100 mL
San Gabriel River (S14)	DDT	•		0.005 <sup>1</sup>	ug/L
	PCBs	•		0.0325 <sup>1</sup>	ug/L
	PAHs	•		0.835 <sup>1</sup>	ug/L
	Copper		•	29.89	ug/l
	Selenium		•	4.77	ug/l
	<i>E. coli</i>		•	2,190	MPN/100 mL
Coyote Creek (S13)	DDT	•		0.005 <sup>1</sup>	ug/L
	PCBs	•		0.0325 <sup>1</sup>	ug/L
	PAHs	•		0.835 <sup>1</sup>	ug/L
	Copper		•	28.54	ug/l
	<i>E. coli</i>		•	11,500	MPN/100 mL

<sup>1</sup> DDT, PCBs and PAHs were below MDL, so concentrations were assumed half MDL.

## 4.2. Current Best Management Practices/Minimum Control Measures

It is important to note the model calibration incorporates local stormwater BMPs implemented through late 2012 into the baseline condition. The only BMPs/control devices that were explicitly incorporated into the baseline model were the Dominguez Gap basins. All other BMPs, which individually were assumed to have a small effect on water quality at the watershed scale, are implicitly represented in the baseline condition. BMPs implemented in 2013 can be categorized as WMP implementation measures and their volume/load reductions are a component of the pollutant reduction plan for attaining interim and final milestones.

## 5. Estimated Required Pollutant Load Reductions

This section provides a description of the process for identifying critical conditions and calculating required load reductions to meet interim and final limitations.

### 5.1. Selected Average (Interim) and Critical (Final) Conditions

The RAA Guidelines specify that average conditions shall be used to establish load reductions for interim milestones and critical conditions shall be used to establish load reductions for final limits. In addition, the Permits provide two pathways for addressing WQ Priorities (see Figure 5-1):

- Volume-based: Retain the standard runoff volume from the 85<sup>th</sup> percentile, 24-hour storm
- Load-based: Achieve the necessary pollutant load reductions to attain Permit limits

Both types of numeric goals were evaluated as part of this RAA.




Figure 5-1. Two Types of Numeric Goals and WMP Compliance Paths according to the Permits

### 5.2. Representative Conditions for Wet Weather

Two approaches were considered and ultimately used in the RAA to represent wet weather critical conditions: the 90<sup>th</sup> percentile wet year and 85<sup>th</sup> percentile, 24-hour (design) storm, as described in the following subsections.

#### 5.2.1. Average and 90<sup>th</sup> Percentile Wet Years

This RAA is based on continuous simulation, and a “representative” year-long time period was selected to represent average and critical conditions, which allows the modeling to capture the variability of rainfall and storm sizes/conditions. For LLAR, LCC, and LSGR, WY2008 was selected as the representative year for average conditions and WY2003 was selected as the representative year for the 90<sup>th</sup> percentile critical wet conditions.

To select these average and critical years for the RAA, the following steps were taken:

1. **Calculated key rainfall metrics for the last 25-years:** the average and critical years were identified by aggregating data from available rain gages across the entire Los Angeles River and San Gabriel River watersheds (LCC is in between, so the analysis for LLAR and LSGR also applies to LLC). For



comparison, other regional watersheds were also analyzed and presented. The two key metrics evaluated were: (1) total annual rainfall, and (2) average rainfall per wet day (with wet days defined as days with rainfall totals greater than 0.1 inches). The first is clearly an indicator of volume, while the second is an indicator of rainfall intensity. To evaluate long-term conditions, the analysis covered 25 water years (WY) from 1987 through 2011—the total rainfall for each precipitation gage was area-weighted and aggregated into annual totals by water year (i.e. previous October through current September).

- 2. Selected years from the most recent 10-years that are most representative of average and 90th percentile:** per the RAA Guidelines, the most recent 10-year period represented in the available data were used to develop the RAA. Table 5-1 and Table 5-2 show average rainfall volumes and intensities (inches per wet day), respectively, for the most recent 10 years compared against the entire 25-years. Both the average and 90th percentile values were compared across the 10- and 25-year records. For the San Gabriel River, 2007-08 is a representative average year based on both the rainfall volume (Table 5-1) and intensity (Table 5-2) metrics. Because BMP performance is typically intensity-dependent, average rainfall per wet day (Table 5-2) was selected as a better metric for use in determining the 90<sup>th</sup> percentile than annual average rainfall (Table 5-1), which led to selection of 2002-03 as the critical year.

It should be noted that wet weather conditions were also reflective on the definition of dry/wet days. As described in Section 5, for analysis of non-bacteria pollutants (including the limiting pollutant zinc) days with greater than 90<sup>th</sup> percentile daily average flow were flagged as “wet,” which aligns with the critical condition used for the LAR and LSGR metals TMDLs.

### 5.2.2. 85<sup>th</sup> Percentile, 24-hour Storm

The design storm is identified in the RAA Guidelines as an acceptable critical condition, and capture of design storm volumes by BMPs is a specified compliance metric in the Permits for TMDLs. The design storm was evaluated and used as a wet weather critical condition for the RAA. As described above, the design storm is a volume-based standard. Each subwatershed within each WMP area has a unique 85th percentile runoff volume, due to varying rainfall amounts and land characteristics (imperviousness, soils, slope, and the like). The rainfall depths associated with the 85th percentile, 24-hour storm are shown in Figure 5-2, based on rolling 24-hour intervals for the 25-year period between October 1, 1987 and September 30, 2011. Within the WMP area, the 85th percentile rainfall depth values range between 0.72 and 1.08 inches.

To determine the “standard volume” associated the design storm, initial conditions were set in LSPC to reflect representative conditions at the start of the simulation, along with regionally derived infiltration rates, and 85th percentile rainfall depths were used as rainfall boundary conditions. At each location the storm distribution presented in Figure 5-3 was used to temporally distribute the 24-hour rainfall volumes (LACDPW 2006). The model was then run to predict the associated runoff volumes for each subwatershed in the WMP area. Those runoff volumes represent the volumes that would need to be retained in order to attain the numeric goals associated with the 85th percentile, 24-hour storm.

Shown in Figure 5-4 are the rainfall depths and runoff depths (runoff volume divided by subwatershed area) associated with the design storm for each subwatershed in the WMP areas. About 50 percent of the subwatersheds in all three WMP areas experiences 0.4 inches or more of runoff under the 85th percentile, 24-hour storm, while about 10 percent of the area experiences about 0.55 inches or more of runoff. Figure 5-5 summarizes the total design storm volumes (in acre-feet) for each jurisdiction. The runoff depths for each subwatershed in the WMP area are graphically shown in Figure 5-6, Figure 5-7, and Figure 5-8.


**Table 5-1. Average Rainfall Depths (Water Years 2002–2011 vs. 25-year Average and 90<sup>th</sup> Percentile)**

Year	Average Rainfall Totals (in./year)				
	Ballona Creek	Dominguez Channel	Malibu Creek	San Gabriel River	Los Angeles River
2001-02	25.4	19.1	28.1	30.6	30.5
2002-03	17.1	13.9	20.8	23	20.4
2003-04	10.2	8.1	9.2	13.7	11.2
2004-05	39.3	28.4	42.6	49.6	46.7
2005-06	14.1	9.8	16.9	17.9	17.5
2006-07	4.3	3.1	6.8	6.4	5.8
2007-08	13.2	11.9	18.6	19.4	17.5
2008-09	9.6	8.5	12.3	14.6	12.5
2009-10	16.8	14.9	20.3	24.1	20.5
2010-11	21.2	18.5	25.3	28.5	25.7
Avg. (1987-2011)	15.9	12.5	18.4	20.7	19.2
90th %ile (1987-2011)	30.8	22.9	34.7	37.8	36.9

**Red Box:** WMP Watersheds. **Blue** highlighted cells are the two years in each basin with the smallest difference from the 25-year average. **Orange** cells have the smallest difference from the 90th percentile of the 25-year record.

**Table 5-2. Average Rainfall Intensity (Water Years 2002–2011 vs. 25-year Average and 90<sup>th</sup> Percentile)**

Year	Average Rainfall Per Wet Day (in./wet day)				
	Ballona Creek	Dominguez Channel	Malibu Creek	San Gabriel River	Los Angeles River
2001-02	0.36	0.32	0.41	0.42	0.36
2002-03	0.79	0.66	0.88	0.92	0.84
2003-04	0.61	0.48	0.61	0.66	0.58
2004-05	0.98	0.69	1.03	1.07	1.03
2005-06	0.53	0.41	0.61	0.64	0.61
2006-07	0.31	0.27	0.39	0.41	0.37
2007-08	0.56	0.52	0.68	0.76	0.71
2008-09	0.49	0.48	0.56	0.65	0.57
2009-10	0.64	0.6	0.71	0.82	0.72
2010-11	0.62	0.58	0.73	0.76	0.7
Avg. (1987-2011)	0.59	0.52	0.67	0.72	0.66
90th %ile (1987-2011)	0.78	0.66	0.91	0.97	0.89

**Red Box:** WMP Watersheds. **Blue** highlighted cells are the two years in each basin with the smallest difference from the 25-year average. **Orange** cells have the smallest difference from the 90th percentile of the 25-year record.




Figure 5-2. Rainfall depths associated with the 85<sup>th</sup> percentile, 24-hour storm.




Figure 5-3. Temporal Distribution for 85th Percentile 24-hour Storm for LSPC Simulation.




Figure 5-4. Rainfall and Runoff Depths Associated with 85th Percentile Rainfall in the WMP subwatersheds.




Figure 5-5. Runoff Volume Associated with the 85th Percentile, 24-hour Storm (by jurisdiction).

DRAFT




Figure 5-6. Runoff Associated with the 85th Percentile, 24-hour Storm for Lower Los Angeles River.




Figure 5-7. Runoff Associated with the 85th Percentile, 24-hour Storm for Los Cerritos Channel.




Figure 5-8. Runoff Associated with the 85th Percentile, 24-hour Storm for Lower San Gabriel River.

### 5.2.3. Representative Conditions for Dry Weather

Although clearly defined definitions exist for wet periods, definitions for dry periods are less clearly defined. Wet weather periods are either defined in terms of rainfall or instream flow. For bacteria, a wet day is one with a rainfall total greater than 0.1 inches plus the three subsequent days, while metals criteria define wet days as those with instream flow above the 90<sup>th</sup> percentile. One seemingly intuitive way of defining a dry period is simply to use the “non-wet” days represented as the inverse of wet days. However, summary of model results indicate some residual influence of wet weather among the “non-wet” days. This presents some challenges for estimating loads and evaluating dry weather compliance because BMP planning would be better served by choosing design conditions that are more influenced by natural background baseflow and/or anthropogenic activities such as point source discharges or dry weather runoff from irrigation (instead of post-rain event interflow).

The RAA Guidelines recommend using the most recent 10 years of data for modeling scenarios to ensure that the plans are based on a representative range of wet and dry conditions. Regional precipitation and instream flow patterns are highly variable; therefore, a representative dry period is one that consistently represents minimal influence to wet weather conditions. To identify a representative dry period, the analysis covered 25 WYs from 1987 through 2011. The following steps were taken:

1. The total rainfall for each precipitation gage in the study area was summarized and classified into wet and non-wet periods according to the bacteria criteria definition for wet weather (i.e. days with rainfall > 0.1 inches plus the three subsequent days).
2. Dry periods were evaluated on a monthly time scale. Table 5-3 shows the average number of consecutive 30-day dry periods, counted by month of the associated mid-interval date, for each of the rainfall gages within the three WMP areas over the 25 years of rainfall evaluated. The color-ramp indicates relative dryness, with red being driest. Table 5-3 indicates that on average, the months of June, July, and August are the driest months in the year, averaging 24-30 consecutive dry intervals. Note that because this table counts mid-interval dates by month, values approaching 30 actually indicate continuous dry intervals approaching 60 days (15 days on either side of the 30 day interval).
3. Select periods within the average and critical year were identified for dry weather simulations. The areal coverage or non-wet intervals in the two selected representative years (2008 and 2003) were compared against the 10-year period (2001-2011) and the long-term 25-year period (1998-2011). Figure 5-9, Figure 5-10, and Figure 5-11 show the selected representative dry period against summaries of non-wet weather conditions in the LLAR, LCC, and LSGR WMP areas, respectively. Within the two selected years, the 45-day period between 8/17 and 9/30 was found to be the most representative of dry weather conditions because (1) no rainfall occurred at any of the gages throughout all three WMP areas, (2) it was during a time of the year that was historically shown to experience the least amount of spatially-weighted rainfall in a year, and (3) it was late in the summer following an extended period of no rainfall for both 2003 and 2008.

The identified periods between 8/17 and 9/20 during the average and critical years were used for subsequent dry weather simulations for the dry weather component of the RAA.



**Table 5-3. Consecutive 30-day Dry Periods per month by WMP and rainfall gage (10/1/1987 – 9/30/2011)**

WMP	StaID	Average Number of Consecutive 30-Day Dry Intervals Per Month (10/1/1987 – 9/30/2011)											
		Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Los Cerritos Channel	D1254	2.2	1.9	6.2	11.9	22.3	25.2	28.9	28.9	21.4	12.7	7.8	4.4
	D1255	2.8	1.8	4.4	8.8	20.3	25.1	29.7	29.8	21.8	13.0	7.3	2.9
	D225	3.0	2.3	6.3	10.5	20.6	24.7	28.8	29.5	21.4	13.1	9.1	3.6
	D388	2.1	1.3	3.8	8.5	18.6	24.0	27.6	29.2	21.0	12.3	5.1	3.2
	D415	1.9	1.2	5.7	9.6	19.0	24.0	28.1	29.1	23.4	13.1	8.9	3.7
Lower Los Angeles River	D1113	4.2	2.5	8.3	9.8	19.5	24.4	28.1	27.8	23.6	13.7	8.8	4.5
	D1114	1.6	1.1	4.0	8.9	19.6	25.1	29.7	29.6	20.8	12.3	5.5	3.0
	D1256	2.1	1.4	4.8	10.4	20.5	24.6	28.8	29.8	23.5	14.2	6.2	3.1
	D291	3.3	1.1	5.0	8.8	19.4	24.4	28.7	28.4	21.9	11.6	4.6	3.5
	D388	2.1	1.3	3.8	8.5	18.6	24.0	27.6	29.2	21.0	12.3	5.1	3.2
	D415	1.9	1.2	5.7	9.6	19.0	24.0	28.1	29.1	23.4	13.1	8.9	3.7
Lower San Gabriel River	D106	4.2	0.6	6.0	10.9	19.7	24.6	28.6	29.0	23.9	14.0	8.2	4.0
	D1088	2.2	1.0	3.8	9.0	17.6	24.1	28.5	29.0	20.9	12.6	5.9	2.7
	D1095	2.4	0.5	4.4	10.0	19.2	24.6	28.6	29.1	21.2	14.2	7.1	4.2
	D1114	1.6	1.1	4.0	8.9	19.6	25.1	29.7	29.6	20.8	12.3	5.5	3.0
	D1254	2.2	1.9	6.2	11.9	22.3	25.2	28.9	28.9	21.4	12.7	7.8	4.4
	D1255	2.8	1.8	4.4	8.8	20.3	25.1	29.7	29.8	21.8	13.0	7.3	2.9
	D1256	2.1	1.4	4.8	10.4	20.5	24.6	28.8	29.8	23.5	14.2	6.2	3.1
	D1257	2.0	0.5	4.5	10.6	18.9	24.4	28.6	29.8	21.2	10.3	5.7	3.0
	D1271	1.8	1.6	3.9	9.4	18.1	24.4	28.6	29.7	21.6	11.7	7.3	3.4
	D156	3.0	1.5	5.2	10.1	19.2	24.6	28.5	29.3	21.0	13.4	7.2	5.0
	D17	1.7	1.2	5.2	9.1	17.5	22.4	28.6	29.0	22.6	11.3	5.2	3.7
	D225	3.0	2.3	6.3	10.5	20.6	24.7	28.8	29.5	21.4	13.1	9.1	3.6
	D269	1.8	0.5	4.2	8.1	18.0	24.2	28.6	29.1	22.2	13.0	6.7	3.2

<b>Legend:</b>	<b>Wet</b>			<b>Dry</b>
----------------	------------	--	--	------------




Figure 5-9. Spatiotemporal summary of non-wet weather conditions in the Lower Los Angeles River WMP area.




Figure 5-10. Analysis of summary of non-wet weather conditions in the Los Cerritos Channel WMP area.




Figure 5-11. Spatiotemporal summary of non-wet weather conditions in the Lower San Gabriel River WMP area.

### 5.3. Calculated Required Pollutant Reductions to Achieve Final Limits

Using the average storm year (2007-08) and 90<sup>th</sup> percentile storm year (2002-03), required pollutant reductions were calculated for attainment of interim and final limitations, respectively, applicable to each WMP area. Per the RAA Guidelines, the percent reduction used to determine the control measures necessary to attain interim milestones shall be based on the average year, while the control measures for attainment of the final limits are based on the 90<sup>th</sup> percentile year.

Required load reductions were evaluated at RAA Assessment Points located at the bottom-most discharge from each WMP areas (shown in Figure 3-2 through Figure 3-4). The RAA Assessment Points represent locations where the collective discharge from each jurisdiction with each WMP area can be assessed to contribute to pollutant loads to the receiving waters. Pollutant loads outside of the WMP areas are not considered in this loading analysis at the RAA Assessment Points, although in reality other loads exist. However, transport of pollutant loads from individual jurisdictions within the WMP areas are considered, including the effect of LACFCD infrastructure and other hydraulic features that can impede flows and associated pollutant loads to the location of the RAA Assessment Points. The result is an accounting system that provides reasonable tracking and estimation of required load reductions throughout each individual WMP area so that meaningful goals can be set for BMP implementation planning.

Applicable targets for wet and dry conditions for Category 1 WQ Priorities (corresponding to the TMDLs within each watershed) are listed in Table 5-4 and Table 5-5, respectively. These targets were used to establish the daily “exceedance load” and daily “allowable load”. The differences in these loads, as predicted by LSPC, were tracked across the average year and 90<sup>th</sup> percentile year and used to calculate the required pollutant reduction. While Category 1 WQ Priorities were emphasized, targets were also applied for Category 2 and Category 3 WQ Priorities. In particular, to provide a comprehensive WMP planning approach, copper, lead, zinc and *E. coli* were assessed for all RAA assessment points (even if a TMDL is not applicable).

For bacteria targets, it should be noted that Allowable Exceedance Days and high flow suspension (HFS) days were incorporated (if applicable) into the percent reduction calculation. The approach of the LA River Bacteria TMDL was used to align Exceedance Days and HFS days. The HFS applies to LLAR and LSGR but not LCC (and thus HFS days were not incorporated into the required reduction calculation for LCC). For LSGR and LCC, a bacteria TMDL has not been adopted but the RAA Guidelines state that targets and critical conditions from other TMDLs in the region should be utilized. If the Allowable Exceedance Days were removed from the percent reduction calculations for LSGR and LCC, the required reductions would increase.

**Table 5-4. Applicable wet weather TMDL targets for Category 1 WQ Priorities**

WMP Area	Waterbody	Pollutant	Target	Source
LLAR	LAR Reach 1 (freshwater)	Cd kg/d	$2.8 \times 10^{-9}$ X daily storm volume (L) - 1.8	WQBEL
	LAR Reach 1 (freshwater)	Cu kg/d	$1.5 \times 10^{-8}$ X daily storm volume (L) - 9.5	WQBEL
	LAR Reach 1 (freshwater)	Pb kg/d	$5.6 \times 10^{-8}$ X daily storm volume (L) - 3.85	WQBEL
	LAR Reach 1 (freshwater)	Zn kg/d	$1.4 \times 10^{-7}$ X daily storm volume (L) - 83	WQBEL
	All LLAR	DDT ug/kg TSS	1.58	Harbor Toxics TMDL
	All LLAR	PCBs ug/kg TSS	22.7	Harbor Toxics TMDL
	All LLAR	PAHs ug/kg TSS	4,022	Harbor Toxics TMDL
	LAR Reach 1 (freshwater)	<i>E-coli</i> MPN/100mL	235 (exceedances allowed during HFS days and 10 exceedance days)	WQBEL



WMP Area	Waterbody	Pollutant	Target	Source
LCC	All LCC	Cu g/d	$4.709 \times 10^{-6}$ X daily storm volume (L)	WQBEL
	All LCC	Pb g/d	$26.852 \times 10^{-6}$ X daily storm volume (L)	WQBEL
	All LCC	Zn g/d	$46.027 \times 10^{-6}$ X daily storm volume (L)	WQBEL
	All LCC	DDT ug/kg TSS	1.58	Harbor Toxics TMDL
	All LCC	PCBs ug/kg TSS	22.7	Harbor Toxics TMDL
	All LCC	PAHs ug/kg TSS	4,022	Harbor Toxics TMDL
LSGR	SG Reach 2	Pb ug/L	81.34	WQBEL
	Coyote Cr.	Cu ug/L	24.71	WQBEL
	Coyote Cr.	Pb ug/L	96.99	WQBEL
	Coyote Cr.	Zn ug/L	144.57	WQBEL
	SG Reach 1 & Coyote Cr.	DDT ug/kg TSS	1.58	Harbor Toxics TMDL
	SG Reach 1 & Coyote Cr.	PCBs ug/kg TSS	22.7	Harbor Toxics TMDL
	SG Reach 1 & Coyote Cr.	PAHs ug/kg TSS	4,022	Harbor Toxics TMDL

Table 5-5. Applicable dry weather TMDL targets for Category 1 WQ Priorities

WMP Area	Waterbody	Pollutant	Target	Source
LLAR	LAR Reach 1 (freshwater)	Cu ug/L	23	WQBEL
	LAR Reach 1 (freshwater)	Pb ug/L	12	WQBEL
	LAR Reach 1 (freshwater)	<i>E-coli</i> MPN/100mL	126	WQBEL
LCC	All LCC	Cu g/d	67.2	WQBEL
	All LCC	<i>E-coli</i> MPN/100mL	126	WQBEL
LSGR	SG Reach 1	Cu ug/L	18	WQBEL
	SG Reach 1	<i>E-coli</i> MPN/100mL	126	WQBEL
	San Jose Cr. Reach 1&2	Se ug/L	5	WQBEL
	San Jose Cr. Reach 1&2	<i>E-coli</i> MPN/100mL	126	WQBEL
	Coyote Cr.	Cu kg/d	0.941	WQBEL
	Coyote Cr.	<i>E-coli</i> MPN/100mL	126	WQBEL

### 5.3.1. Wet-Weather Required Pollutant Reductions

The wet weather pollutant reduction targets for average and critical conditions are summarized in **Error! Reference source not found.** (all WMP areas) and shown graphically in Figure 5-12 through Figure 5-15 (individual WMP areas). These analyses were used to determine the limiting pollutant. The limiting pollutant is defined as the pollutant requiring the greatest load reduction, and BMPs implemented to achieve the limiting pollutant reductions are protective of other pollutant reductions (e.g., sediment or volume reductions). In **Error! Reference source not found.**, the red color gradient highlights limiting pollutants, with a deeper red generally indicating a more limiting pollutant. Zinc was identified as the limiting pollutant for each WMP area<sup>4</sup>. The determination of limiting pollutant considered implementation actions to control the pollutant – for example, State Bill 346 will result in significant reductions of copper loading from brake pads. Because total source control measures are not on the horizon for zinc, it becomes the limiting pollutant instead of copper. The evaluation of copper and organics as limiting pollutants and rationale for their exclusion is described below.

Although DDT and PCBs were estimated to have high load reduction requirements to meet WQBELs, they were not identified as limiting pollutants because the maximum detection limits (MDLs) used for the analysis heavily affected the calculated required reductions. Rather than use LSPC for reduction calculations, monitoring data were used directly and many reported concentrations for DDT, PCBs, and PAHs were below MDLs, so concentrations were assumed in the model to equal half the MDL. The MDL is above the target leading to non-detects requiring reductions. Of course, toxics will be addressed by control measures implemented for zinc. The Dominguez Channel and Greater Los Angeles and Long Beach Harbor Waters Toxic Pollutants TMDL states that “implementation of other TMDLs in the watershed may contribute to the implementation of this TMDL,” and implementation of the effective TMDLs in Los Angeles River and San Gabriel River are integrated within Phase I of the implementation of the toxics TMDL (LARWQCB and USEPA 2011). As a result, DDT, PCBs, and PAHs were not represented in Figure 5-12 through Figure 5-15.

Although copper was calculated to have a higher required reduction than zinc, the effect of Senate Bill 346 is expected to reduce those reductions without any implementation of structural control measures. The Brake Pad Partnership was formed in 1999 as a collaboration of cities, industry, and other entities to address the lack of information and research regarding the impact of brake debris material in the environment. After its formation, the Brake Pad Partnership commissioned several technical studies to better quantify the fate and transport of copper to San Francisco Bay including a detailed source assessment. Overall findings of the study estimated that of the anthropogenic sources of copper, approximately 35 percent are attributed to brake pad releases (BPP 2010). Even if the reduction was only half of this amount, the adjustment to the required copper reduction would still result in zinc being the limiting pollutant in LLAR, LCC, and LSGR.

After excluding organics and total copper for the reasons described previously, total zinc becomes the limiting pollutant in each of the WMP areas during the 90<sup>th</sup> percentile year. In other words, reductions of zinc during WMP implementation will drive reduction of other pollutants, particularly because the pollutant reduction plan emphasizes sediment control (other pollutants are typically transported with sediment) and retention/infiltration rather than pollutant treatment.

---

<sup>4</sup> In LSGR, a higher percent reduction for bacteria was calculated for the average year than the 90<sup>th</sup> percentile (see Figure 5-14). Although total annual rainfall in 2008 and 2003 were virtually identical over the entire SGR watershed (20.5 and 20.4 inches/year, respectively), 2003 had fewer wet days than 2008, resulting in relatively more intense events on average (about 18 percent higher). As a result, 2003 had more HFS days than 2008—exceedances during HFS days are not considered when computing the required load reduction, lowering the required reduction.



**Table 5-6. Wet-weather pollutant reduction targets by WMP area with analysis of limiting pollutants<sup>5</sup>**

WMP	Year	Organics				Metals		Bacteria
		DDT	PCB	PAH	TCu <sup>2</sup>	TPb	TZn <sup>3</sup>	E-Coli
Lower Los Angeles River (LLAR)	2003	87.3%	72.0%	0.0%	84.1%	38.6%	67.4%	23.4%
	2008	90.0%	77.9%	0.0%	82.8%	32.9%	64.9%	45.1%
Los Cerritos Channel (LCC)	2003	86.6%	70.3%	0.0%	95.6%	76.7%	90.8%	40.4%
	2008	89.6%	77.1%	0.0%	87.1%	3.6%	75.6%	47.9%
Lower San Gabriel River (LSGR)	2003	79.5%	54.6%	0.0%	40.1%	0.0%	29.3%	22.9%
	2008	91.4%	80.7%	0.0%	18.0%	0.0%	25.0% <sup>4</sup>	53.0%
Coyote Creek (CC)	2003	75.9%	46.8%	0.0%	37.5%	0.0%	28.3%	19.1%
	2008	91.3%	76.8%	0.0%	22.7%	0.0%	30.4% <sup>4</sup>	59.2%

Color ramps highlight potentially limiting (Red) vs. pollutants determined to be non-limiting for this analysis (Blue)

1. Average year is 2008 and 90<sup>th</sup> percentile year is 2003
2. **Red box:** Organics managed through sediment and associated metals reduction. Organic load reductions above influenced by assigned concentrations at half the MDLs (monitoring data below MDLs), and therefore are suspect and not considered limiting. Cu is not limiting after brake-pad reductions
3. **Blue Box:** Zinc is limiting pollutant for the 90<sup>th</sup> percentile year
4. Bacteria reduction target is lower in 2003 than 2008 because more days were classified as high-flow suspension (HFS)

<sup>5</sup> For the Diamond Bar jurisdiction of the San Gabriel River WMP area, a portion flows to the Santa Ana River. Since this area is open space and therefore not associated with MS4 runoff, no reductions were determined necessary. Loadings for the 90<sup>th</sup> percentile year from this area are 1.16 kg/year of total Cu, 0.87 kg/year of total Pb, 5.21 kg/year of total Zn, and 4.91x10<sup>12</sup> #/year of E-coli.




Figure 5-12. Wet-weather pollutant reduction targets and limiting pollutant for Lower Los Angeles River WMP.<sup>6</sup>






Figure 5-13. Wet-weather pollutant reduction targets and limiting pollutant for Los Cerritos Channel WMP.

<sup>6</sup> Note that the Los Cerritos Channel TMDLs for Metals requires no reduction of Pb.



\* Cu not limiting after brake pad reductions.

Figure 5-14. Wet-weather pollutant reduction targets and limiting pollutant for Lower San Gabriel River.



\* Cu not limiting after brake pad reductions.

Figure 5-15. Wet-weather pollutant reduction targets and limiting pollutant for Coyote Creek.



DRAFT



### 5.3.2. Dry-Weather Pollutant Reduction Targets

Using the representative dry-weather period of August 17 through September 30, as defined in Section 5.2.3, modeled instream flow was multiplied by the observed dry weather concentrations to get existing conditions loads, which are shown in Table 5-7. Likewise, target concentrations were also multiplied by modeled instream flow to get allowable load for each waterbody, which is shown in Table 5-8. Finally, Table 5-9 summarizes dry-weather reduction targets for each listed segment for both the average year and the 90<sup>th</sup> percentile year.

For dry weather, bacteria is the limiting pollutant (not zinc) because the required reductions are much higher than other pollutants. Reductions of bacteria during WMP implementation will drive reductions of other pollutants.

**Table 5-7. Existing condition dry-weather loads by water body**

Existing Condition		Dry Weather Flow (cfs)		Existing Load (kg/day or MPN/day)		
Waterbody	Pollutant	2003	2008	2003	2008	Mean
LAR Reach 1 (freshwater)	Cu ug/L	99.97	65.63	6.28	4.12	5.20
LAR Reach 1 (freshwater)	Pb ug/L	99.97	65.63	0.84	0.55	0.69
LAR Reach 1 (freshwater)	<i>E. coli</i> MPN/100ml	99.97	65.63	4.79E+13	3.15E+13	3.97E+13
LCC	Cu ug/L	4.65	2.20	0.29	0.14	0.21
LCC	<i>E. coli</i> MPN/100ml	4.65	2.20	1.62E+12	7.64E+11	1.19E+12
SG Reach 1	Cu ug/L	69.04	75.36	5.05	5.51	5.28
SG Reach 1	<i>E. coli</i> MPN/100ml	69.04	75.36	3.70E+12	4.04E+12	3.87E+12
San Jose Cr. Reach 1 & 2	Se ug/L	12.54	19.62	0.06	0.09	0.07
San Jose Cr. Reach 1 & 2	<i>E. coli</i> MPN/100ml	12.54	19.62	6.72E+11	1.05E+12	8.62E+11
Coyote Cr.	Cu ug/L	19.65	15.69	1.37	1.10	1.23
Coyote Cr.	<i>E. coli</i> MPN/100ml	19.65	15.69	5.53E+12	4.41E+12	4.97E+12



**Table 5-8. Allowable TMDL dry-weather loads by water body**

Existing Condition		Dry Weather Flow (cfs)		Allowable Load (kg/day or MPN/day)		
Waterbody	Pollutant	2003	2008	2003	2008	Mean
LAR Reach 1 (freshwater)	Cu ug/L	99.97	65.63	5.63	3.69	4.66
LAR Reach 1 (freshwater)	Pb ug/L	99.97	65.63	2.94*	1.93*	2.43*
LAR Reach 1 (freshwater)	<i>E. coli</i> MPN/100ml	99.97	65.63	3.08E+11	2.02E+11	2.55E+11
LCC	Cu ug/L	4.65	2.20	0.07	0.07	0.07
LCC	<i>E. coli</i> MPN/100ml	4.65	2.20	1.43E+10	6.78E+09	1.06E+10
SG Reach 1	Cu ug/L	69.04	75.36	3.04	3.32	3.18
SG Reach 1	<i>E. coli</i> MPN/100ml	69.04	75.36	2.13E+11	2.32E+11	2.23E+11
San Jose Cr. Reach 1 & 2	Se ug/L	12.54	19.62	0.15*	0.24*	0.20*
San Jose Cr. Reach 1 & 2	<i>E. coli</i> MPN/100ml	12.54	19.62	3.87E+10	6.05E+10	4.96E+10
Coyote Cr.	Cu ug/L	19.65	15.69	0.94	0.94	0.94
Coyote Cr.	<i>E. coli</i> MPN/100ml	19.65	15.69	6.06E+10	4.48E+10	5.45E+10

\*Existing dry-weather loads are currently below the allowable loads thus showing compliance for this pollutant.

**Table 5-9. Required dry-weather percent reductions by water body**

WMP	Waterbody	Pollutant	Required Dry-Weather Percent Reductions		
			2003	2008	Mean
LLAR	LAR Reach 1 (freshwater)	Cu	10%	10%	10%
	LAR Reach 1 (freshwater)	Pb	0%	0%	0%
	LAR Reach 1 (freshwater)	<i>E. coli</i>	99.36%	99.36%	99.36%
LCC	LCC	Cu	76.74%	50.85%	68.43%
	LCC	<i>E. coli</i>	99.11%	99.11%	99.11%
LSGR	Coyote Cr.	Cu	31.42%	14.11%	23.73%
	Coyote Cr.	<i>E. coli</i>	98.90%	98.90%	98.90%
	SG Reach 1	Cu	39.78%	39.78%	39.78%
	SG Reach 1	<i>E. coli</i>	94.25%	94.25%	94.25%
	San Jose Cr. Reach 1 & 2	Se	0%	0%	0%
	San Jose Cr. Reach 1 & 2	<i>E. coli</i>	94.25%	94.25%	94.25%

Color Ramp shows relative magnitude of reductions—darker means higher reductions

## 6. Determination of Potential BMP Capacity for RAA

The process for determining the necessary cumulative BMP capacity depends on the type of numeric goal being addressed. As shown in Figure 6-1, the volume-based (design storm) approach, necessary BMP capacity was determined through a design storm analysis. For the load-based (pollutant reduction), the analysis leveraged the optimization routines in the customized WMMS. An initial step in the RAA was a comparison of the volume reductions required by the load-based and volume-based numeric goals, to support selection of the wet weather critical conditions.

For LLAR, LCC, and LSGR, the 90<sup>th</sup> percentile WY (2002-03) weather was selected as the critical condition for wet weather.

Details on the analyses performed to determine potential BMP treatment capacity are provided in Attachment A. The attachment describes the approach for incorporating nonstructural BMPs, accounting for the effect of LACFCD infrastructure, and separating the contribution from non-MS4 sources.




Figure 6-1. Illustration of Process for Determining Required BMP Capacities for the WMP using Volume-Based (top panel) and Load-Based (bottom panel) Numeric Goals.

## 7. Cumulative Volume Reduction Goals to Achieve Required Pollutant Reductions

The first output of the RAA is a series of “volume reduction goals” for each subwatershed and jurisdiction in the WMP area. WMMS was used to determine the stormwater retention volumes for each subwatershed that would achieve the required load reductions, as reported in this section. These calculated runoff reduction volumes for each subwatershed are a surrogate compliance metric for the responsible agencies. It should be noted that upon implementation, opportunities may arise where flow-through BMPs may provide similar ultimate pollutant load reduction, and may replace the need to implement volume-based reduction BMPs.

These volumes also form the basis for selection of BMPs to achieve those volume reductions, as described in Section 9 and Attachment A.

### 7.1. Volume Reductions for Structural BMPs

Structural BMPs were modeled using the assumptions outlined in Attachment A. BMP capacities were optimized across the entire study area to achieve the final milestone pollutant reduction requirements at each of the assessment points. Instead of summarizing optimization results in terms of BMP capacity, which is really specific to the network described in Attachment A, the results were summarized as required *annual* wet-weather retention volume (in acre-feet). This provides a volumetric basis that is (1) closely related to load reduction and (2) readily transferable as a control target for parallel BMP modeling at a finer resolution. Because the volumes were isolated to wet days, it is also not skewed by dry-weather runoff retention. The following subsections provide more details about the wet- and dry-weather analysis components.

#### 7.1.1. Wet Weather

Using the structural BMP routing network in WMMS (described in Attachment A), the required *annual* wet-weather retention volume (in acre-feet) were calculated using the critical year time series. For milestones, the percent reduction was based on average year targets while final limits were based on critical year targets. The reported annual volumes are (1) based on required load reductions and (2) ready for BMP modeling at a finer resolution. A 10 percent load reduction was assumed to result from implementation of all nonstructural control measures outlined in the WMPs, setting the foundation of WMP implementation, and structural control measures provide additional load reduction.

Table 7-1 through Table 7-4 present incremental and cumulative retention volumes required to achieve each load reduction milestone by jurisdiction. The milestones are based on the metals TMDLs as described in Section 2. In order to calculate the incremental volume reductions for each milestone, optimization was performed for each jurisdiction to (1) emphasize BMP implementation in subwatersheds that volume reduction could most cost effectively reduce pollutants and (2) establish a cost-effective sequence of subwatersheds for each jurisdiction to achieve the milestones over time. In other words, WMMS was used to develop an implementation schedule that provides early gains in receiving water quality.



**Table 7-1. Annual volume reduction goals to achieve interim and final milestones for Lower Los Angeles River WMP by jurisdiction**

Jurisdiction	Total Critical Year Storm Volume Target (acre-ft/year)		
	Milestone	Incremental	Cumulative <sup>1</sup>
Downey	31%	143.8	143.8
	50%	221.7	365.5
	Final	360.5	726.0
Lakewood	31%	14.3	14.3
	50%	0.0	14.3
	Final	0.0	14.3
Long Beach	31%	540.7	540.7
	50%	1090.8	1,631.5
	Final	2270.1	3,901.7
Lynwood	31%	303.3	303.3
	50%	185.2	488.6
	Final	619.6	1,108.1
Paramount	31%	181.8	181.8
	50%	227.8	409.6
	Final	579.2	988.8
Pico Rivera	31%	365.3	365.3
	50%	0.0	365.3
	Final	12.0	377.3
Signal Hill	31%	32.8	32.8
	50%	106.6	139.4
	Final	58.4	197.9
South Gate	31%	229.3	229.3
	50%	343.2	572.6
	Final	940.0	1,512.6

1: Color Ramp highlights relative amount of required retention volume for milestones: darker is more, lighter is less  
 2: Includes full implementation of planned non-structural practices



**Table 7-2. Annual volume reduction goals to achieve interim and final milestones for Los Cerritos Channel WMP by jurisdiction**

Jurisdiction	Total Critical Year Storm Volume Target (acre-ft/year)		
	Milestone	Incremental	Cumulative <sup>1</sup>
Bellflower	10%	NS	NS
	35%	336.1	336.1
	Final	801.3	1,137.4
Cerritos	10%	NS	NS
	35%	9.7	9.7
	Final	3.2	12.9
Downey	10%	NS	NS
	35%	77.0	77.0
	Final	35.8	112.8
Lakewood	10%	NS	NS
	35%	282.4	282.4
	Final	874.8	1,157.2
Long Beach	10%	NS	NS
	35%	560.9	560.9
	Final	2115.2	2,676.1
Paramount	10%	NS	NS
	35%	278.8	278.8
	Final	353.1	631.9
Signal Hill	10%	NS	NS
	35%	269.9	269.9
	Final	52.7	322.6

1: Color Ramp highlights relative amount of required retention volume for milestones: darker is more, lighter is less  
 NS: Non-structural practices achieve 10% milestone



**Table 7-3. Annual volume reduction goals to achieve interim and final milestones for Lower San Gabriel River WMP**

Jurisdiction	Total Critical Year Storm Volume Target (acre-ft/year)		
	Milestone	Incremental	Cumulative <sup>1</sup>
Artesia	10%	NS	NS
	35%	1.1	1.1
	Final	0.0	1.1
Bellflower	10%	NS	NS
	35%	1.3	1.3
	Final	61.5	62.8
Cerritos	10%	NS	NS
	35%	6.6	6.6
	Final	52.8	59.4
Diamond Bar	10%	NS	NS
	35%	0.3	0.3
	Final	32.8	33.0
Downey	10%	NS	NS
	35%	4.3	4.3
	Final	259.6	263.9
Lakewood	10%	NS	NS
	35%	7.4	7.4
	Final	2.2	9.6
Long Beach	10%	NS	NS
	35%	26.9	26.9
	Final	2.3	29.2
Norwalk	10%	NS	NS
	35%	0.8	0.8
	Final	136.1	136.9
Pico Rivera	10%	NS	NS
	35%	0.2	0.2
	Final	74.8	75.1
Santa Fe Springs	10%	NS	NS
	35%	0.0	0.0
	Final	106.0	106.0
Whittier	10%	NS	NS
	35%	0.0	0.0
	Final	7.5	7.5

1: Color Ramp highlights relative amount of required retention volume for milestones: darker is more, lighter is less  
 NS: Non-structural practices achieve 10% milestone



**Table 7-4. Annual volume reduction goals to achieve interim and final milestones for the Coyote Creek portion of Lower San Gabriel River WMP by jurisdiction**

Jurisdiction	Total Critical Year Storm Volume Target (acre-ft/year)		
	Milestone	Incremental	Cumulative <sup>1</sup>
Artesia	10%	NS	NS
	35%	47.9	47.9
	Final	0.0	47.9
Cerritos	10%	NS	NS
	35%	0.1	0.1
	Final	194.2	194.3
Diamond Bar	10%	NS	NS
	35%	1.0	1.0
	Final	73.0	74.0
Hawaiian Gardens	10%	NS	NS
	35%	27.0	27.0
	Final	3.4	30.4
La Mirada	10%	NS	NS
	35%	0.8	0.8
	Final	174.9	175.7
Lakewood	10%	NS	NS
	35%	17.5	17.5
	Final	8.2	25.7
Long Beach	10%	NS	NS
	35%	37.5	37.5
	Final	0.0	37.5
Norwalk	10%	NS	NS
	35%	3.0	3.0
	Final	149.5	152.5
Santa Fe Springs	10%	NS	NS
	35%	0.4	0.4
	Final	260.3	260.7
Whittier	10%	NS	NS
	35%	2.1	2.1
	Final	252.6	254.7

1: Color Ramp highlights relative amount of required retention volume for milestones: darker is more, lighter is less  
 NS: Non-structural practices achieve 10% milestone

### 7.1.2. Dry Weather

Dry-weather reductions from non-structural BMPs were calculated using flow from representative dry period (Section 5.2) of 8/17/2003 through 9/30/2003 and 90<sup>th</sup> percentile concentrations calculated from observed data (Section 5.2.1). Similar to wet weather, a 10% load reduction is assumed to result from the cumulative effect of nonstructural BMPs. Also, the effects of a 25% reduction in irrigation of urban grass was explicitly simulated in the model to estimate the resulting associated reduction of dry weather flows at the RAA Assessment Points. Irrigation was modeled as artificial rainfall within the LSPC model as a function of the potential evapotranspiration of urban grass. Once irrigation was reduced 25%, this directly impacted a large portion of the nonstormwater discharges driven primarily from over irrigation and impacts on dry weather flows were significant. The projected effect of non-structural and irrigation controls on dry weather flow and loads is presented in Table 7-5. Since *E. Coli* is the limiting dry weather pollutant with required reductions in excess of 90%, the remaining volume reduction not controlled by non-structural measures will be treated by the structural BMPs described in the previous section.

**Table 7-5. Projected dry weather reductions from non-structural control measures**

Watershed	Constituent	Quantity (Volume or Mass)			Percent Reduction Achieved	
		Baseline	NM	NS	NM	NS
Lower Los Angeles River	Flow (M Gal.)	198.3	178.5	86.6	10.0%	56.4%
	Copper (kg)	19.28	17.35	8.42	10.0%	56.4%
	Lead (kg)	2.58	2.32	1.12	10.0%	56.4%
	<i>E. Coli</i> (Billion MPN)	147,166	132,449	64,230	10.0%	56.4%
Los Cerritos Channel	Flow (M Gal.)	133.6	120.2	56.3	10.0%	57.8%
	Copper (kg)	12.84	11.56	5.42	10.0%	57.8%
	<i>E. Coli</i> (Billion MPN)	71,808	64,627	30,277	10.0%	57.8%
Lower San Gabriel River	Flow (M Gal.)	163.3	147.0	71.2	10.0%	56.4%
	Copper (kg)	18.48	16.63	8.06	10.0%	56.4%
	Selenium (kg)	2.95	2.65	1.29	10.0%	56.4%
	<i>E. Coli</i> (Billion MPN)	13,540	12,186	5,903	10.0%	56.4%
Coyote Creek	Flow (M Gal.)	213.4	192.0	88.4	10.0%	58.6%
	Copper (kg)	23.05	20.75	9.55	10.0%	58.6%
	<i>E. Coli</i> (Billion MPN)	92,887	83,599	38,491	10.0%	58.6%

NM: Non-modeled non-structural practices achieve 10% reduction

NS: Non-structural 25% irrigation reduction practices achieve an additional approximately 60% reduction

## 8. MS4 Volume Reduction Goals to Achieve Required Pollutant Reductions

Each jurisdiction in the Group's WMP area is subject to stormwater runoff from non-MS4 facilities. In particular, Caltrans roads and facilities regulated by nontraditional or general industrial permits contribute to the runoff volume for each subwatershed. It will be important for these entities to retain their runoff and/or eliminate their cause/contribution to receiving water exceedances. The runoff from these non-MS4 facilities was therefore estimated and subtracted from the cumulative volume reduction goal (Section 7) to establish the MS4 responsible targets as described in Attachment A.

### 8.1. Summary of MS4 Responsible Reduction Goals

Runoff volumes estimated for non-MS4 permitted areas and Caltrans were subtracted from the reduction target to generate the required MS4 treatment capacity shown in Table 8-1 through Table 8-4.

**Table 8-1. Lower Los Angeles River Critical Year Runoff Volume from MS4 and Non-MS4 Facilities**

Jurisdiction	COMPLIANCE TARGET – FINAL MILESTONE		
	Total Critical Year Storm Volume Target (acre-ft/year)	MS4 Responsible Critical Year Storm Volume Runoff (acre-ft/year)	Non-MS4 Runoff – Industrial Permitted & Caltrans (acre-ft/year)
Downey	726.0	654.7	71.2
Lakewood	14.3	14.3	-
Long Beach	3,901.7	3,039.6	862.1
Lynwood	1,108.1	667.9	440.2
Paramount	988.8	606.1	382.7
Pico Rivera	377.3	287.2	90.0
Signal Hill	197.9	188.9	9.0
South Gate	1,512.6	1,174.3	338.2
TOTAL	8,826.5	6,633.1	2,193.5

**Table 8-2. Los Cerritos Channel Critical Year Runoff Volume from MS4 and Non-MS4 Facilities**

Jurisdiction	COMPLIANCE TARGET – FINAL MILESTONE		
	Total Critical Year Storm Volume Target (acre-ft/year)	MS4 Responsible Critical Year Storm Volume Runoff (acre-ft/year)	Non-MS4 Runoff – Industrial Permitted & Caltrans (acre-ft/year)
Bellflower	1,137.4	990.4	147.0
Cerritos	12.9	12.9	0.0
Downey	112.8	93.0	19.8
Lakewood	1,157.2	1,152.1	5.1
Long Beach	2,676.1	1,629.8	1,046.2
Paramount	631.9	525.5	106.4
Signal Hill	322.6	284.3	38.3
TOTAL	6,050.9	4,688.0	1,364.8

**Table 8-3. San Gabriel River Critical Year Runoff Volume from MS4 and Non-MS4 Facilities**

Jurisdiction	COMPLIANCE TARGET – FINAL MILESTONE		
	Total Critical Year Storm Volume Target (acre-ft/year)	MS4 Responsible Critical Year Storm Volume Runoff (acre-ft/year)	Non-MS4 Runoff – Industrial Permitted & Caltrans (acre-ft/year)
Artesia	1.1	1.1	0.0
Bellflower	62.8	57.4	5.4
Cerritos	59.4	4.1	55.3
Diamond Bar	33.0	1.1	32.0
Downey	263.9	87.3	176.7
Lakewood	9.6	2.2	7.4
Long Beach	29.2	29.2	0.0
Norwalk	136.9	4.8	132.1
Pico Rivera	75.1	60.4	14.7
Santa Fe Springs	106.0	30.3	75.8
Whittier	7.5	7.1	0.4
TOTAL	784.6	284.9	499.7

**Table 8-4. Coyote Creek Critical Year Runoff Volume from MS4 and Non-MS4 Facilities**

Jurisdiction	COMPLIANCE TARGET – FINAL MILESTONE		
	Total Critical Year Storm Volume Target (acre-ft/year)	MS4 Responsible Critical Year Storm Volume Runoff (acre-ft/year)	Non-MS4 Runoff – Industrial Permitted & Caltrans (acre-ft/year)
Artesia	47.9	15.9	32.0
Cerritos	194.3	56.7	137.6
Diamond Bar	74.0	36.7	37.4
Hawaiian Gardens	30.4	27.1	3.4
La Mirada	175.7	124.9	50.8
Lakewood	25.7	19.7	6.0
Long Beach	37.5	0.0	37.5
Norwalk	152.5	52.5	99.9
Santa Fe Springs	260.7	12.6	248.1
Whittier	254.7	200.1	54.6
TOTAL	1,253.4	546.1	707.3

## 9. Pollutant Reduction Plan

The BMPs used to achieve the MS4 volume reduction goals in Section 8 are not, per se, a component of the Permit compliance determination. Instead, over time each agency will report and demonstrate that the *cumulative* effect of projects implemented over time add up to the required reductions for interim milestones and final targets (reported as “MS4 Compliance Target”). However, the initial scenario of BMPs for WMP implementation (referred to as a Pollutant Reduction Plan in the RAA Guidelines) and their costs may be the most beneficial outcome of the WMP. A detailed WMP implementation scenario is presented in Attachment B, broken down by jurisdiction and subwatershed. The volume reductions are separated among right-of-way (ROW) BMPs and Low Impact Development (LID) on public parcels (in combination with nonstructural BMPs).

The Pollutant Reduction Plan is considered an “initial” scenario because over time, through adaptive management, the responsible agencies will likely “shift” among different types of BMPs (e.g., increase implementation of green streets and reduce implementation of regional BMPs) or substitute alternative BMPs altogether (e.g., implement dry wells instead of green streets). These shifts will be supported by analyses to show the substituted BMPs provide an equivalent volume reduction as the replaced BMPs.

### 9.1. Existing/Planned Regional Control Measures

Existing regional BMPs play an integral part in measuring the current reductions and need for future control measures. The annual volume or load removed from the existing and planned regional control measures were subtracted from the MS4 responsible runoff to determine the remaining treatment volume required. Detailed information for the existing and planned regional control measures is found in Attachment A.

The existing and planned regional control measure information was provided for the Lower Los Angeles River and Lower San Gabriel River. The jurisdictions that were impacted are listed with the associated annual reduction provided by these facilities in Table 9-1 and Table 9-2.

**Table 9-1. Lower Los Angeles River Critical Year Existing/Planned Regional BMP Runoff Volume Reductions**

Jurisdiction	COMPLIANCE TARGET		
	MS4 Responsible Critical Year Storm Volume Runoff (acre-ft/year)	Existing/Planned Regional BMP Reductions (acre-ft/year)	Remaining MS4 Responsible Critical Year Storm Volume (acre-ft/year)
Lakewood	14.3	6.4	7.9
Long Beach	3,039.6	633.4	2,406.2
Signal Hill	188.9	22.7	166.2

**Table 9-2. Lower San Gabriel River Critical Year Existing/Planned Regional BMP Runoff Volume Reductions**

Jurisdiction	COMPLIANCE TARGET		
	MS4 Responsible Critical Year Storm Volume Runoff (acre-ft/year)	Existing/Planned Regional BMP Reductions (acre-ft/year)	Remaining MS4 Responsible Critical Year Storm Volume (acre-ft/year)
Downey	87.3	24.0	63.3



## 9.2. Future Control Measures for Attainment of Interim and Final Limits

The Pollutant Reduction Plans for wet and dry weather illustrate the sequential BMP implementation strategy to attain all interim and final limits. Within each of the jurisdictions, the subwatershed subareas were individually prioritized and associated with milestones on the basis of cost-effectiveness for zinc removal. The optimization modeling results presented in Section 7 and Figure 9-1, Figure 9-2 and Figure 9-3 shown below identify the prioritization of subwatershed implementation based on the most effective combination of BMPs. The implementation schedule outlined in the Pollutant Reduction Plans for wet and dry weather are based upon this prioritization. The plans are presented in the following subsections.

### 9.2.1. Wet Weather

The interim and final targets are presented in total acre-feet per year that requires treatment through structural BMPs (less the non-MS4 and existing regional volumes as described in Sections 8 and 9.1). To properly capture the annual volume, BMPs are sized to the minimum volume needed to capture the target annual volume. Thus, the BMPs are presented as a volume (acre-feet) that has the ability to capture the required annual total to meet compliance.

An overall jurisdictional summary table is presented in Table 9-3 that outlines the required BMP volume to achieve compliance in the associated WMP group. The BMP volumes are the sum of existing distributed BMPs, potential green street BMPs, LID on public parcels, and remaining BMP volume that must be implemented as regional (or other) projects as necessary to meet the annual volume reduction target.

Table 9-4 through Table 9-7 outlines the jurisdiction-wide BMP volume targets necessary to meet the annual volume interim and final limits established in Section 8. Each distributed BMP was associated with a jurisdictional subwatershed and the associated implementation schedule, thus summing their impact across different interim goals. The remaining BMP volume after accounting for existing distributed BMPs is spread across right-of-way BMPs, LID on public parcels, and remaining BMP volume including potential regional projects. Priority was given to LID on public parcels, followed by right-of-way BMPs and finally other BMPs. Detailed discussion on how the BMPs in the right-of-way and LID on public parcels were determined is found in Attachment A. Detailed tables are provided in Attachment B for each jurisdiction and associated subwatersheds. Detailed tables describing the existing distributed BMPs are found in Attachment D.

Table 9-3. Jurisdictional Final Target BMP Volumes by WMP Group

	LLAR	LCC	LSGR - SGR	LSGR - CC	
Jurisdiction	Total BMP Volume to Achieve Compliance (acre-ft)	TOTAL			
Artesia	-	-	0.1	1.1	1.2
Bellflower	-	118.2	5.5	-	123.7
Cerritos	-	1.6	0.6	6.4	8.6
Diamond Bar	-	-	0.2	8.9	9.1
Downey	83.4	10.2	17.5	-	111.2
Hawaiian Gardens	-	-	-	2.2	2.2
La Mirada	-	-	-	15.2	15.2
Lakewood	1.2	169.5	0.4	1.9	173.0
Long Beach	319.1	208.7	2.7	0.0	530.5
Lynwood	95.5	-	-	-	95.5
Norwalk	-	-	0.3	4.7	5.0
Paramount	76.6	55.1	-	-	131.7
Pico Rivera	41.2	-	10.8	-	52.0
Santa Fe Springs	-	-	4.9	2.1	7.0
Signal Hill	22.3	28.6	-	-	50.9
South Gate	173.0	-	-	-	173.0
Whittier	-	-	1.4	39.1	40.5
<b>TOTAL</b>	<b>812.3</b>	<b>591.9</b>	<b>44.4</b>	<b>81.6</b>	<b>1,530.2</b>




Figure 9-1. LLAR implementation areas associated with Interim and final milestones.




Figure 9-2. LCC implementation areas associated with Interim and final milestones.




Figure 9-3. LSGR implementation areas associated with Interim and final milestones.

**Table 9-4. Lower Los Angeles River Pollutant Reduction Plan for Attainment of Interim and Final Limits**

Jurisdiction	Milestone	COMPLIANCE TARGET		POLLUTANT REDUCTION PLAN						
		Remaining MS4 Responsible Critical Year Storm Volume* (acre-ft/year)		Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)		Estimated Potential LID on Public Parcels Volume (acre-ft)		Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	
		Incremental	Cumulative		Incremental	Cumulative	Incremental	Cumulative	Incremental	Cumulative
Downey	31%	143.8	143.8	1.1	12.2	12.2	0.7	0.7	7.1	7.1
	50%	187.1	330.9	0.7	2.5	14.7	10.1	10.8	0.6	7.7
	Final	323.9	654.7	2.0	31.2	45.9	4.4	15.3	10.7	18.4
Lakewood	31%	7.9	7.9	NA	1.1	1.1	0.0	0.0	-	-
	50%	-	7.9		-	1.1	-	0.0	-	-
	Final	-	7.9		-	1.1	-	0.0	-	-
Long Beach	31%	6.5	6.5	NA	1.0	1.0	0.0	0.0	-	-
	50%	567.0	573.5		40.3	41.3	7.5	7.5	24.7	24.7
	Final	1,832.7	2,406.2		113.4	154.6	20.8	28.3	111.5	136.2
Lynwood	31%	235.9	235.9	NA	18.4	18.4	2.7	2.7	13.1	13.1
	50%	134.9	370.8		12.8	31.2	3.8	6.5	0.1	13.2
	Final	297.2	667.9		22.7	53.9	4.5	11.1	17.3	30.5
Paramount	31%	163.7	163.7	0.1	9.0	9.0	1.7	1.7	10.2	10.2
	50%	65.7	229.4		7.4	16.4	0.8	2.5	0.3	10.4
	Final	376.6	606.1		14.9	31.2	2.1	4.7	30.2	40.6
Pico Rivera	31%	275.3	275.2	NA	11.5	11.5	0.5	0.5	27.4	27.4
	50%	-	275.2		-	11.5	-	0.5	-	27.4
	Final	12.0	287.2		1.3	12.8	0.0	0.5	0.5	27.9
Signal Hill	31%	8.5	8.5	0.2	0.8	0.8	0.2	0.2	0.2	0.2
	50%	105.8	114.3		7.0	7.8	0.9	1.1	5.9	6.1
	Final	51.9	166.2		2.2	10.0	0.0	1.1	4.9	11.0
South Gate	31%	229.3	229.3	4.7	23.2	23.2	0.9	0.9	6.5	6.5
	50%	198.1	427.4		15.0	38.3	0.8	1.7	12.6	19.1
	Final	746.9	1,174.3		49.3	87.5	5.1	6.8	54.7	73.8

**Table 9-5. Los Cerritos Channel Pollutant Reduction Plan for Attainment of Interim and Final Limits**

Jurisdiction	Milestone	COMPLIANCE TARGET		Existing Distributed BMP Volume (acre-ft)	POLLUTANT REDUCTION PLAN					
		Remaining MS4 Responsible Critical Year Storm Volume* (acre-ft/year)			Total Estimated Right-of-Way BMP Volume (acre-ft)		Estimated Potential LID on Public Parcels Volume (acre-ft)		Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	
		Incremental	Cumulative		Incremental	Cumulative	Incremental	Cumulative	Incremental	Cumulative
Bellflower	10%	NS	NS		-	-	-	-	-	-
	35%	244.4	244.4	NA	15.1	15.1	1.2	1.2	16.2	16.2
	Final	746.0	990.4		43.0	58.1	3.2	4.5	39.4	55.6
Cerritos	10%	NS	NS		-	-	-	-	-	-
	35%	9.7	9.7	NA	1.0	1.0	0.0	0.0	0.5	0.5
	Final	3.2	12.9		-	1.0	-	0.0	0.1	0.6
Downey	10%	NS	NS		-	-	-	-	-	-
	35%	57.2	57.2	0.1	5.3	5.3	0.0	0.0	2.7	2.7
	Final	35.8	93.0		-	5.3	-	0.0	2.1	4.8
Lakewood	10%	NS	NS		-	-	-	-	-	-
	35%	282.4	282.4	NA	31.5	31.5	4.7	4.7	6.9	6.9
	Final	869.7	1,152.1		90.0	121.5	7.0	11.8	29.3	36.2
Long Beach	10%	NS	NS		-	-	-	-	-	-
	35%	473.5	473.5	NA	33.8	33.8	12.3	12.3	16.4	16.4
	Final	1,156.3	1,629.8		87.9	121.7	9.5	21.8	48.9	65.3
Paramount	10%	NS	NS		-	-	-	-	-	-
	35%	267.0	267.0	NA	14.3	14.3	3.0	3.0	17.1	17.1
	Final	258.5	525.5		8.5	22.8	3.5	6.4	8.7	25.8
Signal Hill	10%	NS	NS		-	-	-	-	-	-
	35%	231.6	231.6	0.0	11.2	11.2	1.2	1.2	14.2	14.2
	Final	52.7	284.3		-	11.2	-	1.2	2.0	16.2

NS: Non-structural practices achieve 10% milestone

NA: No information/not enough information provided

\*Runoff from non-MS4 sources and reductions from existing regional BMPs are excluded from compliance target (see Attachment A)

**Table 9-6. San Gabriel River Pollutant Reduction Plan for Attainment of Interim and Final Limits**

Jurisdiction	Milestone	COMPLIANCE TARGET		Existing Distributed BMP Volume (acre-ft)	POLLUTANT REDUCTION PLAN					
		Remaining MS4 Responsible Critical Year Storm Volume* (acre-ft/year)			Total Estimated Right-of-Way BMP Volume (acre-ft)		Estimated Potential LID on Public Parcels Volume (acre-ft)		Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	
		Incremental	Cumulative		Incremental	Cumulative	Incremental	Cumulative	Incremental	Cumulative
Artesia	10%	NS	NS	NA	-	-	-	-	-	-
	35%	1.1	1.1		-	-	0.1	0.1	-	-
	Final	-	1.1		-	-	-	0.1	-	-
Bellflower	10%	NS	NS	NA	-	-	-	-	-	-
	35%	1.3	1.3		0.2	0.2	0.0	0.0	-	-
	Final	56.1	57.4		1.5	1.8	3.7	3.7	0.0	0.0
Cerritos	10%	NS	NS	NA	-	-	-	-	-	-
	35%	-	-		-	-	-	-	-	-
	Final	4.1	4.1		0.6	0.6	0.0	0.0	-	-
Diamond Bar	10%	NS	NS	NA	-	-	-	-	-	-
	35%	-	-		-	-	-	-	-	-
	Final	1.1	1.1		0.2	0.2	-	-	-	-
Downey	10%	NS	NS		-	-	-	-	-	-
	35%	-	-		-	-	-	-	-	-
	Final	63.3	63.3	7.1	10.0	10.0	0.4	0.4	-	-
Lakewood	10%	NS	NS	NA	-	-	-	-	-	-
	35%	-	-		-	-	-	-	-	-
	Final	2.2	2.2		0.2	0.2	0.0	0.0	0.1	0.1
Long Beach	10%	NS	NS	NA	-	-	-	-	-	-
	35%	26.9	26.9		1.1	1.1	1.3	1.3	-	-
	Final	2.3	29.2		0.3	1.4	-	1.3	0.0	0.0

Jurisdiction	Milestone	COMPLIANCE TARGET		Existing Distributed BMP Volume (acre-ft)	POLLUTANT REDUCTION PLAN					
		Remaining MS4 Responsible Critical Year Storm Volume* (acre-ft/year)			Total Estimated Right-of-Way BMP Volume (acre-ft)		Estimated Potential LID on Public Parcels Volume (acre-ft)		Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	
		Incremental	Cumulative		Incremental	Cumulative	Incremental	Cumulative	Incremental	Cumulative
Norwalk	10%	NS	NS	NA	-	-	-	-	-	-
	35%	0.8	0.8		-	-	0.1	0.1	-	-
	Final	4.0	4.8		-	-	0.3	0.3	-	-
Pico Rivera	10%	NS	NS	NA	-	-	-	-	-	-
	35%	0.2	0.2		0.0	0.0	-	-	-	-
	Final	60.2	60.4		10.7	10.8	-	-	0.0	0.0
Santa Fe Springs	10%	NS	NS	NA	-	-	-	-	-	-
	35%	-	-		-	-	-	-	-	-
	Final	30.3	30.3		4.6	4.6	-	-	0.3	0.3
Whittier	10%	NS	NS	NA	-	-	-	-	-	-
	35%	0.0	0.0		-	-	-	-	0.0	0.0
	Final	7.1	7.1		1.4	1.4	-	-	-	0.0

NS: Non-structural practices achieve 10% milestone

NA: No information/not enough information provided

\*Runoff from non-MS4 sources and reductions from existing regional BMPs are excluded from compliance target (see Attachment A)

Table 9-7. Coyote Creek Pollutant Reduction Plan for Attainment of Interim and Final Limits

Jurisdiction	Milestone	COMPLIANCE TARGET		Existing Distributed BMP Volume (acre-ft)	POLLUTANT REDUCTION PLAN					
		Remaining MS4 Responsible Critical Year Storm Volume* (acre-ft/year)			Total Estimated Right-of-Way BMP Volume (acre-ft)		Estimated Potential LID on Public Parcels Volume (acre-ft)		Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	
		Incremental	Cumulative		Incremental	Cumulative	Incremental	Cumulative	Incremental	Cumulative
Artesia	10%	NS	NS	NA	-	-	-	-	-	-
	35%	15.9	15.9		-	-	1.1	1.1	-	-
	Final	-	15.9		-	-	-	1.1	-	-
Cerritos	10%	NS	NS	NA	-	-	-	-	-	-
	35%	0.1	0.1		0.0	0.0	-	-	-	-
	Final	56.6	56.7		3.0	3.1	3.4	3.4	-	-
Diamond Bar	10%	NS	NS	NA	-	-	-	-	-	-
	35%	1.0	1.0		0.3	0.3	-	-	-	-
	Final	35.6	36.7		8.0	8.2	-	-	0.7	0.7
Hawaiian Gardens	10%	NS	NS	NA	-	-	-	-	-	-
	35%	23.6	23.6		0.3	0.3	1.5	1.5	-	-
	Final	3.4	27.1		0.2	0.6	0.1	1.6	0.0	0.0
La Mirada	10%	NS	NS	NA	-	-	-	-	-	-
	35%	-	-		-	-	-	-	-	-
	Final	124.9	124.9		9.6	9.6	5.6	5.6	-	-
Lakewood	10%	NS	NS	NA	-	-	-	-	-	-
	35%	17.5	17.5		0.9	0.9	0.7	0.7	-	-
	Final	2.3	19.7		-	0.9	0.3	0.9	-	-
Long Beach	10%	NS	NS	NA	-	-	-	-	-	-
	35%	-	-		-	-	-	-	-	-
	Final	0.0	0.0		-	-	0.0	0.0	-	-

Jurisdiction	Milestone	COMPLIANCE TARGET		Existing Distributed BMP Volume (acre-ft)	POLLUTANT REDUCTION PLAN					
		Remaining MS4 Responsible Critical Year Storm Volume* (acre-ft/year)			Total Estimated Right-of-Way BMP Volume (acre-ft)		Estimated Potential LID on Public Parcels Volume (acre-ft)		Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	
		Incremental	Cumulative		Incremental	Cumulative	Incremental	Cumulative	Incremental	Cumulative
Norwalk	10%	NS	NS	NA	-	-	-	-	-	-
	35%	1.6	1.6		-	-	0.2	0.2	-	-
	Final	50.9	52.5		1.4	1.4	3.2	3.4	-	-
Santa Fe Springs	10%	NS	NS	NA	-	-	-	-	-	-
	35%	-	-		-	-	-	-	-	-
	Final	12.6	12.6		1.0	1.0	-	-	1.1	1.1
Whittier	10%	NS	NS	NA	-	-	-	-	-	-
	35%	-	-		-	-	-	-	-	-
	Final	200.1	200.1		39.0	39.0	-	-	0.0	0.0

NS: Non-structural practices achieve 10% milestone

NA: No information/not enough information provided

\*Runoff from non-MS4 sources and reductions from existing regional BMPs are excluded from compliance target (see Attachment A)

## 9.2.2. Dry Weather

Dry weather reductions are attained through a combination of non-structural practices and structural BMPs as they are implemented as part of the wet weather attainment of limits. As wet-weather BMPs are implemented, they serve to remove the dry-weather flows thus meeting the compliance set forth to achieve dry-weather reductions. As a summary of the dry weather analysis, Table 9-8 through Table 9-11 outline the jurisdiction-wide attainment of interim and final milestones for dry weather. The reduction from implemented BMPs compares the actual dry-weather reduction versus the compliance target.

**Table 9-8. Lower Los Angeles River Dry Weather Pollutant Reduction Plan for Attainment of Interim and Final Limits**

Jurisdiction	Milestone	Dry Weather <i>E. coli</i> Load Reduction	
		Compliance Target	Reduction from Implemented BMPs
Downey	31%	30.8%	65.9%
	50%	49.7%	76.9%
	Final	99.4%	99.4%
Lakewood	31%	30.8%	99.4%
	50%	49.7%	99.4%
	Final	99.4%	99.4%
Long Beach	31%	30.8%	62.1%
	50%	49.7%	74.3%
	Final	99.4%	99.4%
Lynwood	31%	30.8%	71.8%
	50%	49.7%	80.2%
	Final	99.4%	99.4%
Paramount	31%	30.8%	51.0%
	50%	49.7%	72.4%
	Final	99.4%	99.4%
Pico Rivera	31%	30.8%	71.8%
	50%	49.7%	71.8%
	Final	99.4%	99.4%
Signal Hill	31%	30.8%	69.3%
	50%	49.7%	94.9%
	Final	99.4%	99.4%
South Gate	31%	30.8%	62.8%
	50%	49.7%	75.9%
	Final	99.4%	99.4%



Table 9-9. Los Cerritos Channel Dry Weather Pollutant Reduction Plan for Attainment of Interim and Final Limits

Jurisdiction	Milestone	Dry Weather <i>E. coli</i> Load Reduction	
		Compliance Target	Reduction from Implemented BMPs
Bellflower	10%	9.9%	58.1%
	35%	34.7%	71.4%
	Final	99.1%	99.1%
Cerritos	10%	9.9%	56.4%
	35%	34.7%	99.1%
	Final	99.1%	99.1%
Downey	10%	9.9%	59.8%
	35%	34.7%	99.1%
	Final	99.1%	99.1%
Lakewood	10%	9.9%	55.6%
	35%	34.7%	69.6%
	Final	99.1%	99.1%
Long Beach	10%	9.9%	60.1%
	35%	34.7%	76.9%
	Final	99.1%	99.1%
Paramount	10%	9.9%	52.8%
	35%	34.7%	79.8%
	Final	99.1%	99.1%
Signal Hill	10%	9.9%	60.8%
	35%	34.7%	99.1%
	Final	99.1%	99.1%



**Table 9-10. San Gabriel River Dry Weather Pollutant Reduction Plan for Attainment of Interim and Final Limits**

Jurisdiction	Milestone	Dry Weather <i>E. coli</i> Load Reduction	
		Compliance Target	Reduction from Implemented BMPs
Artesia	10%	9.4%	57.6%
	35%	33.0%	94.3%
	Final	94.25%	94.25%
Bellflower	10%	9.4%	49.9%
	35%	33.0%	57.6%
	Final	94.25%	94.25%
Cerritos	10%	9.4%	43.7%
	35%	33.0%	48.1%
	Final	94.25%	94.25%
Diamond Bar	10%	9.4%	58.2%
	35%	33.0%	58.8%
	Final	94.25%	94.25%
Downey	10%	9.4%	57.4%
	35%	33.0%	58.1%
	Final	94.25%	94.25%
Lakewood	10%	9.4%	43.1%
	35%	33.0%	73.7%
	Final	94.25%	94.25%
Long Beach	10%	9.4%	46.6%
	35%	33.0%	91.6%
	Final	94.25%	94.25%
Norwalk	10%	9.4%	54.8%
	35%	33.0%	55.7%
	Final	94.25%	94.25%
Pico Rivera	10%	9.4%	51.8%
	35%	33.0%	51.9%
	Final	94.25%	94.25%
Santa Fe Springs	10%	9.4%	54.4%
	35%	33.0%	57.9%
	Final	94.25%	94.25%
Whittier	10%	9.4%	57.9%
	35%	33.0%	58.0%
	Final	94.25%	94.25%



**Table 9-11. Coyote Creek Dry Weather Pollutant Reduction Plan for Attainment of Interim and Final Limits**

Jurisdiction	Milestone	Dry Weather <i>E. coli</i> Load Reduction	
		Compliance Target	Reduction from Implemented BMPs
Artesia	10%	9.9%	60.9%
	35%	34.6%	85.1%
	Final	98.9%	98.9%
Cerritos	10%	9.9%	56.3%
	35%	34.6%	56.3%
	Final	98.9%	98.9%
Diamond Bar	10%	9.9%	61.3%
	35%	34.6%	65.9%
	Final	98.9%	98.9%
Hawaiian Gardens	10%	9.9%	59.7%
	35%	34.6%	96.9%
	Final	98.9%	98.9%
La Mirada	10%	9.9%	57.4%
	35%	34.6%	58.7%
	Final	98.9%	98.9%
Lakewood	10%	9.9%	60.7%
	35%	34.6%	76.5%
	Final	98.9%	98.9%
Long Beach	10%	9.9%	54.5%
	35%	34.6%	91.9%
	Final	98.9%	98.9%
Norwalk	10%	9.9%	59.2%
	35%	34.6%	60.8%
	Final	98.9%	98.9%
Santa Fe Springs	10%	9.9%	51.7%
	35%	34.6%	52.0%
	Final	98.9%	98.9%
Whittier	10%	9.9%	60.7%
	35%	34.6%	61.4%
	Final	98.9%	98.9%

## 10. References

---

- BPP (Brake Pad Partnership). 2010. Brake Pad Partnership Technical Studies – Copper Releases in the San Francisco Bay Watershed. < <http://www.suscon.org/bpp/pdfs/CopperSourcesSummary.pdf>>. Accessed May 21, 2014.
- CREST Consulting Team. 2010. Los Angeles River Watershed Bacteria TMDL – Technical Report Section 3: Numeric Targets. Prepared for CREST (Cleaner Rivers Through Effective Stakeholder-Led TMDLs)
- Donigian, A.S., and J.T. Love, 2003. Sediment Calibration Procedures and Guidelines for Watershed Modeling. Aqua Terra Consultants, Mountain View, California.
- Donigian, A.S., Jr. 2000. HSPF Training Workshop Handbook and CD. Lecture #19: Calibration and Verification Issues. Prepared for and presented to the U.S. Environmental Protection Agency, Office of Water, Office of Science and Technology, Washington, DC.
- Donigian, A.S., Jr., J.C. Imhoff, B.R. Bicknell, and J.L. Kittle, Jr. 1984. Application Guide for Hydrological Simulation Program – FORTRAN (HSPF). EPA-600 / 3-84-965. U.S. Environmental Protection Agency, Environmental Research Laboratory, Athens, GA.
- LACDPW (Los Angeles County Department of Public Works). 2006. *Hydrology Manual*. January 2006.
- LACDPW (Los Angeles County Department of Public Works). 2010a. *Los Angeles County Watershed Model Configuration and Calibration—Part I: Hydrology*. Prepared for County of Los Angeles Department of Public Works, Watershed Management Division, Los Angeles County, CA, by Tetra Tech, Pasadena, CA.
- LACDPW (Los Angeles County Department of Public Works). 2010b. *Los Angeles County Watershed Model Configuration and Calibration—Part II: Water Quality*. Prepared for County of Los Angeles Department of Public Works, Watershed Management Division, Los Angeles County, CA, by Tetra Tech, Pasadena, CA.
- LACDPW (Los Angeles County Department of Public Works). 2011a. *Evaluation of Water Quality Design Storms*. Prepared for County of Los Angeles Department of Public Works, Watershed Management Division, Los Angeles County, CA, by Tetra Tech, Pasadena, CA.
- LACDPW (Los Angeles County Department of Public Works). 2011b. *Phase II Report: Development of the Framework for Watershed-Scale Optimization Modeling*. Prepared for County of Los Angeles Department of Public Works, Watershed Management Division, Los Angeles County, CA, by Tetra Tech, Pasadena, CA.
- LACDPW (Los Angeles County Department of Public Works). 2013. *Los Angeles County 2012-2013 Annual Stormwater Monitoring*. December 12, 2013.
- LARWQCB (Los Angeles Regional Water Quality Control Board). 2002. Amendment to the Water Quality Control Plan for the Los Angeles Region to Incorporate Implementation Provisions for the Region’s Bacteria Objectives and to Incorporate a Wet-Weather Total Maximum Daily Load for Bacteria at Santa Monica Bay Beaches. Resolution No. 2003-10. December 12, 2002.
- LARWQCB (Los Angeles Regional Water Quality Control Board). 2014. Guidelines for Conducting Reasonable Assurance Analysis in a Watershed Management Program, Including an Enhanced Watershed Management Program. LARWQCB, Los Angeles, CA.



- LARWQCB (Los Angeles Regional Water Quality Control Board) and USEPA. 2011. Dominguez Channel and Greater Los Angeles and Long Beach Harbor Waters Toxics Total Maximum Daily Loads. LARWQCB, Los Angeles, CA.
- Lumb, A.M., R.B. McCammon, and J.L. Kittle, Jr. 1994. User's Manual for an Expert System (HSPEXP) for Calibration of the Hydrological Simulation Program – FORTRAN. Water-Resources Investigation Report 94-4168. U.S. Geological Survey, Reston, VA.
- Shen, J., A. Parker, and J. Riverson. 2004. *A New Approach for a Windows-based Watershed Modeling System Based on a Database-supporting Architecture*. Environmental Modeling and Software, July 2004.
- Tetra Tech and USEPA (U.S. Environmental Protection Agency). 2002. *The Loading Simulation Program in C++ (LSPC) Watershed Modeling System – User's Manual*. Tetra Tech, Fairfax, VA, and U.S. Environmental Protection Agency, Washington, DC.
- USEPA (U.S. Environmental Protection Agency). 2003. *Fact Sheet: Loading Simulation Program in C++*. USEPA, Watershed and Water Quality Modeling Technical Support Center, Athens, GA. Available at: <http://www.epa.gov/athens/wwqtsc/LSPC.pdf>
- USEPA (U.S. Environmental Protection Agency). 2009. *SUSTAIN—A Framework for Placement of Best Management Practices in Urban Watersheds to Protect Water Quality*. EPA/600/R-09/095. U.S. Environmental Protection Agency, Office of Research and Development, Edison, NJ.
- Zou, R., Liu, Y., Riverson, J., Parker, A. and S. Carter. 2010. A nonlinearity interval mapping scheme for efficient waste load allocation simulation-optimization analysis. Water Resources Research, August 2010.

# Attachment A: DETERMINATION OF BMP TREATMENT CAPACITY

---

***Submitted to:***

LLAR WMP Group

LCC WMP Group

LSGR WMP Group

***Submitted by:***



Tetra Tech  
9444 Balboa Ave., Suite 215  
San Diego, CA 92123

**June 6, 2014**



## Contents

<b>1. Determination of BMP Treatment Capacity</b> .....	<b>4</b>
1.1. Load Reduction Optimization Modeling Analysis .....	5
1.2. BMP Capacity Analysis for the Rights-of-Way .....	6
1.2.1. Data Used .....	7
1.2.2. ROW BMP Screening .....	8
1.2.3. ROW BMP Configuration .....	9
1.2.4. BMP Assumptions Based on Green Streets .....	9
1.3. LID on Public Parcels Assessment.....	16
1.4. Existing, Planned, and Potential BMPs .....	17
1.4.1. Modeled Existing/Planned Subwatershed-Scale Regional BMPs .....	17
1.4.2. Identified Parcel-Scale Regional and Distributed BMPs.....	20
1.5. Non-MS4 Facility Runoff.....	21
1.5.1. Non-MS4 Permitted Areas .....	21
1.5.2. Caltrans .....	21
1.6. Institutional BMPs and Minimum Control Measures.....	21

DRAFT



## Tables

Table 1-1. BMP parameters used in the load reduction modeling analysis .....	6
Table 1-2. Summary of Data .....	8
Table 1-3. ROW BMP MTFCC .....	8
Table 1-4. BMP Design and Modeling Parameters for Subsequent Analyses .....	10
Table 1-5. Typical parcel area, road area, and frontage length .....	12
Table 1-6. Contributing area percentage by land use .....	13
Table 1-7. DeForest Wetlands Project details .....	17
Table 1-8. Dominguez Gap East Wetlands Project – East Basin details .....	18
Table 1-9. Dominguez Gap Wetlands Project – West Basin details .....	19
Table 1-10. Willow Springs Park details .....	19
Table 1-11. Discovery Park Infiltration Basin details .....	20

## Figures

Figure 1-1. Illustration of Process for Determining Required BMP Capacities for the WMP using Volume-Based (top panel) and Load-Based (bottom panel) Numeric Goals.....	4
Figure 1-2. Conceptual schematic of the WMMS aggregate BMP treatment train (LACDPW 2011b). .....	5
Figure 1-3. Conceptual schematic of ROW BMPs with an underdrain (Arrows indicate water pathways). .....	7
Figure 1-4. Typical bioretention section view (City of San Diego 2011).....	10
Figure 1-5. Green streets model schematic (arrows denote direction of runoff routing; figure not to scale). .....	11
Figure 1-6. Typical parcel area, road width, road area, and frontage length schematic (figure not to scale) .....	12
Figure 1-7. Parcel contributing area to ROW (impervious varies by land use; arrows denote direction of runoff routing; figure not to scale). .....	13
Figure 1-8. Schematic depicting untreated parcel and untreated road runoff routing (arrows denote direction of runoff routing; figure not to scale).....	14
Figure 1-9. Schematic characterizing approximate distribution of routing to BMPs in the ROW for all WMP areas (arrows denote direction of runoff routing; figure not to scale). .....	15
Figure 1-10. Example determination of runoff coefficient inflection point for an arbitrary soil type in Appendix C of LACDPW (2006). .....	16

# 1. Determination of BMP Treatment Capacity

The process for determining the necessary cumulative BMP capacity depends on the type of numeric goal being addressed. As shown in Figure 1-1, the volume-based (design storm) approach, necessary BMP capacity was determined through a design storm analysis. For the load-based (pollutant reduction), the analysis leveraged the optimization routines in the customized WMMS. An initial step in the RAA was a comparison of the volume reductions required by the load-based and volume-based numeric goals, to support selection of the wet weather critical conditions.

This appendix describes key analyses conducted to determine the potential capacity of different BMPs including non-structural BMPs. In addition, it describes the approach for non-MS4 sources.




Figure 1-1. Illustration of Process for Determining Required BMP Capacities for the WMP using Volume-Based (top panel) and Load-Based (bottom panel) Numeric Goals.

## 1.1. Load Reduction Optimization Modeling Analysis

During development of WMMS, distributed BMPs were modeled at the subwatershed-scale using a generalized BMP treatment train. Depending on the land use type, different types of BMPs were applied. The three generalized BMP pathways were: (1) transportation, (2) residential, and (3) commercial/industrial/institutional. A conceptual schematic of the BMP network and pathways is presented in Figure 1-2 (LACDPW 2011).

For the RAA, subwatershed-scale SUSTAIN models were developed using the WMMS modeling assumptions. Each BMP from the treatment train described in Figure 1-2 was configured consistently with modeling performed during development of the WMMS system and followed the Regional Board RAA guidelines. A summary of key BMP parameters used for RAA modeling are presented in Table 1-1. Background infiltration rates were changed from those used during WMMS development (0.5 inches per hour) to site-specific infiltration rates provided in the Los Angeles County Hydrology Manual and associated spatial datasets (LACDPW 2006). These rates also deviate somewhat from the values suggested in the RAA Guidelines (0.1 – 0.3 inches per hour); however, the data are locally-derived, published and reliable which provides adequate justification for their use.

First, SUSTAIN models were configured using the existing condition watershed model runoff timeseries and land use distributions as inputs, and benchmarked against the aggregated LSPC model results to establish baseline consistency. Second, using the SUSTAIN configuration with the respective BMP opportunities per pathway (as presented in Figure 1-2) in each subwatershed, optimization runs were formulated to maximize zinc reduction (i.e. the limiting target pollutant) while minimizing total estimated implementation cost. This resulted in a matrix of high-resolution cost-effectiveness curves for each subwatershed. Finally, a Tier-II optimization framework was configured to collectively optimize target load reductions at the downstream assessment point, with an added equitability constraint to ensure that each jurisdiction shared proportionally in the reduction effort. For the Tier-II optimization, instead of the decision variables being individual BMPs within a network like before, they were comprised of individual solutions taken off the cost-effectiveness curves at each subwatershed. The primary objective was to quantify the stormwater retention volume and load reductions provided by the collective actions occurring within each contributing jurisdiction tributary to the assessment point.




Figure 1-2. Conceptual schematic of the WMMS aggregate BMP treatment train (LACDPW 2011b).

**Table 1-1. BMP parameters used in the load reduction modeling analysis**

Constituent Group	Rain Barrel	Bioretention	Porous Pavement
Media Infiltration Rate (in/hr)	n/a	0.1 – 0.9	0.1 – 0.9
Substrate Layer Porosity (fraction)	n/a	0.4	0.4
Substrate Layer Field Capacity (fraction)	n/a	0.3	0.055
Substrate Layer Wilting Point (fraction)	n/a	0.1	0.05
Underdrain Gravel Porosity (fraction)	n/a	0.5	0.45
Vegetative Parameter, A (unitless)	n/a	0.6	1.0
Background Infiltration Rate (in/hr)	n/a	0.1 – 0.9	0.1 – 0.9
First Order Decay Rate (1/day) <sup>1</sup>	0.2 – 0.8	0.2 – 0.8	0.2 – 0.8
Underdrain Filtration Rate (%) <sup>1</sup>	n/a	0.5 – 0.9	0.5 – 0.9


1. Rates vary by pollutant and the type of BMP soil media

## 1.2. BMP Capacity Analysis for the Rights-of-Way

A key consideration for WMP implementation is the potential BMP capacity that could be provided by rights-of-way (ROW). In order to highlight the potential structural BMP implementation approaches to meet the volume targets, a BMP opportunity analysis was conducted. Two broad categories of BMPs – ROW BMPs and LID on public parcels – were used to describe the networks of BMPs needed to meet the target reductions.

This section describes how right-of-ways were evaluated for opportunities to locate BMPs and evaluate the key components that affect the ability of the ROW BMP networks to be effective: space available in the ROW, types of BMPs to site in the ROW, drainage areas that could potentially be treated by ROW BMPs, and estimated BMP infiltration rates.

Stormwater BMPs in the ROW are treatment systems arranged linearly within the street ROW and are designed to reduce runoff volumes and improve runoff water quality from the roadway and adjacent parcels. Implementing BMPs in the ROW provides an opportunity to meet water quality goals by locating BMPs in areas owned or controlled by a municipality to avoid the cost of land acquisition or establishing an easement. Implementing BMPs in the ROW allows for direct control of construction, maintenance, and monitoring activities by the responsible jurisdiction. Bioretention and permeable pavement are typically best suited for implementation in the ROW



**Figure 1-3. Conceptual schematic of ROW BMPs with an underdrain (Arrows indicate water pathways).**

Not all roads are suited for ROW BMP retrofits; therefore, screening is required to eliminate roads where ROW BMP retrofits are impractical or infeasible due to physical constraints. While ROW BMP retrofits can be implemented in a variety of settings, the physical characteristics of the road itself such as the road type, local topography, and depth to groundwater can significantly influence the practicality of designing and constructing these features. A screening protocol was established to identify realistic opportunities for retrofits based on the best available GIS data. The opportunities identified during this process provide the foundation for the engineering analysis to determine the volume of stormwater that can be treated by ROW BMP retrofits in the subject watersheds. This section describes the data and the screening process used to identify the best available roads for ROW BMP retrofits.

### 1.2.1. Data Used

To evaluate BMP opportunities and available implementation areas, several key data sets were processed and formatted. Table 1-2 outlines the data set names, formats, descriptions, and sources.



**Table 1-2. Summary of Data**

Data Set	Format	Description	Source
Parcels	GIS Shapefile	Outlines property boundaries and sizes	Los Angeles County (LAC) Assessor
Roads	GIS Shapefile	Shows street centerline network & classification by Topologically Integrated Geographic Encoding and Reference (TIGER)	LAC GIS Portal
Land Use	GIS Shapefile	Subdivides the region into predefined land use categories with similar runoff properties. Each individual land use feature identifies the associated percent impervious coverage.	LAC WMMS Model
Subwatersheds	GIS Shapefile	Defines drainage areas to selected outlet points	LAC WMMS Model
Slopes	GIS Shapefile	Classifies regions by the slope category	LAC WMMS Model
Soils	GIS Shapefile	Outlines spatial extents of dominant soil types	LAC GIS Portal
Jurisdictions	GIS Shapefile	Establishes city and county boundaries	LAC GIS Portal
Drainage Network	GIS Shapefile	Identifies stormwater structure layout and conveyance methods	LAC GIS Portal
Groundwater Contours	GIS Shapefile	Illustrates groundwater depth as measured from the surface	LAC BOS
Soil Runoff Coefficient Curves	PDF File	Curves characterize effect of rainfall intensity on runoff coefficient per soil type	Hydrology Manual Appendix C (LADPW 2006)
Aerial Imagery	Layer File	Orthoimage of entire region	ESRI Maps & Data Imagery
Runoff Rates	Time Series	Hourly runoff for land uses for the continuous simulation model	LAC WMMS Model

### 1.2.2. ROW BMP Screening

High traffic volumes, speed limits, slopes, and groundwater tables, impact the feasibility of ROW BMP implementation. Road classification data contains information typically useful for determining if the street is subject to high traffic volumes and speeds, and Census TIGER road data provides the best available road classification information for the study area. Table 1-3 shows the Master Address File (MAF)/TIGER Feature Classification Codes (MTFCC) deemed appropriate for ROW BMP retrofit opportunities. Only roads with the MTFCCs listed in Table 1-3 can be considered for ROW BMP retrofits in this screening analysis. All other roads are screened out.

**Table 1-3. ROW BMP MTFCC**

MTFCC	Description
S1400	Local neighborhood road, rural road, city street
S1730	Alley
S1780	Parking lot road

In addition to the screening of road types, opportunities were further screened to remove segments that have steep slopes. BMP implementation on streets with grades greater than 10 percent present engineering challenges that substantially reduce the cost effectiveness of the retrofit opportunity. From the available slope information, roads were considered as retrofit opportunities if the slope was less than 10 percent.

The final screen applied to the roads is the depth to groundwater. Implementing ROW BMPs in areas where the groundwater table is high is not recommended due to the fact that the BMPs are rendered ineffective due to their storage capacity being seriously diminished with groundwater inflow. From the groundwater contours provided, roads were eliminated as opportunities if the depth to groundwater was less than 10 feet. Attachment C highlights the areas identified with groundwater depths of 10 feet or less. The highlighted areas provide a starting point for elimination, however it should be noted that further evaluation may be necessary based on local knowledge of areas with high groundwater tables or daylighting of perched groundwater layers as identified by the jurisdictions.

The results of the ROW BMP screening are presented in Attachment C. Attachment C shows the roads available for retrofit (highlighted in green) versus all of the roads within the study area. An overall watershed map and individual jurisdictional maps for each watershed show all the identified retrofit opportunities. The maps indicate that a majority of the roads within each jurisdiction pass through the screening as potential retrofits. It should be noted that due to the coarse nature of the road classification data, only freeways, highways, and major roads were eliminated in the classification screening process. In practice, retrofitting every street that passed through the screening will likely not be feasible and adaptive management strategies will be necessary in the future to further refine the road classification data layer to more accurately identify road types suitable for ROW BMP retrofits.

The screened opportunities were used as the basis to evaluate the potential runoff volume reduction provided by ROW BMP implementations. In the following section, an engineering assessment is presented that determines the ROW BMP contributing drainage areas and the overall volume reductions achieved through ROW BMP implementation.

### 1.2.3. ROW BMP Configuration

The three most important assumptions necessary to evaluate BMP volume reduction performance are (1) the physical BMP configuration assumptions, (2) the contributing drainage area characteristics, and (3) the in-situ soil infiltration rates. By understanding the area draining to the BMPs and the volume capacity and function of the BMPs, an assessment can be performed to evaluate the potential of ROW retrofit BMPs to capture the required runoff volume in each subwatershed. This section summarizes the information and processes used to establish BMP configuration assumptions to be used for the runoff analysis presented in the following section.

### 1.2.4. BMP Assumptions Based on Green Streets

ROW BMPs consists of multiple types and combinations of stormwater treatment options. A well-established and often utilized ROW BMP is green streets. Green streets provide multiple benefits for pollutant and volume reduction and have been implemented in locations throughout the nation. In the future and as updates are made to the WMP, other ROW BMPs may be incorporated to achieve the required volume reductions.

Green streets typically consist of bioretention areas between the curb and sidewalk (herein referred to as the parkway) and/or permeable pavement within the parking lane. Prior to evaluating green street BMP treatment capacity, it is imperative to establish a configuration that can be assumed for typical implementation watershed-wide. This establishes the parkway space needed for the BMPs (plan view) and also determines the hydraulic function and storage capacity of the subsurface systems.

Bioretention systems are surface and subsurface water filtration systems, which use vegetation and underlying soils to store, filter, and reduce runoff volume while removing pollutants. Figure 1-4 represents a typical bioretention system incorporated into a green street design. Bioretention systems consist of a ponding depth and engineered soil media depth to treat runoff. Table 1-4 outlines typical widths, depths, and soil parameters associated with green street bioretention cells. Green streets were assumed to have no underdrains because the


WMP emphasizes low impact development and stormwater volume reduction to achieve pollutant load reductions.

Driveways and utilities limit the road length that can be converted into a green street. From past experience and aerial imagery review in the local watersheds, it was determined that 30 percent of the road length could be considered as the maximum possibility for conversion into bioretention area. This factor was used to limit the total length of potential green street bioretention areas. The parameters outlined above and in the table below were assumed to be the typical green street BMP implementation configuration for the screening analysis and the BMP treatment capacity evaluation described in the next section.

**Table 1-4. BMP Design and Modeling Parameters for Subsequent Analyses**

Component	Design Parameter	Value
Ponding Area	Depth	0.8 feet
	Width	4.0 feet
Media Layer	Depth	3.0 feet
	Porosity	0.4
Overall Profile	Effective Depth <sup>1</sup>	2.0 feet

<sup>1</sup> Effective depth is the maximum equivalent depth of water stored within the bioretention area less the depth displaced by soil media (vertical summation of surface ponding depth and void storage depth)



**Figure 1-4. Typical bioretention section view (City of San Diego 2011).**

## Contributing Drainage Area Analysis

The purpose of this analysis was to realistically represent the area, type, and impervious coverage of land draining to potential green streets throughout the entire watershed. This is a critical step in WMP development because it predicts what volume of runoff can be assumed treated by green streets and what remaining (untreated) runoff must be routed to regional BMPs or addressed in other ways. The following engineering analyses were performed at a subwatershed-scale within the limits of available data and resources to estimate the maximum potential green street treatment capacity; given more detailed street-by-street drainage area data, the assumptions and results presented herein could be refined in future efforts to optimize green street treatment capacity. Figure 1-5 illustrates a simplified routing schematic used to represent the available runoff flow pathways to green street and regional BMPs throughout the watershed. The following subsections explain how each representative drainage area illustrated in Figure 1-5 was characterized.




Figure 1-5. Green streets model schematic (arrows denote direction of runoff routing; figure not to scale).

## Typical Parcel Size & Street Frontage Analysis

The nature of the green street analysis requires an understanding of typical parcel sizes and how much of the parcel drains to the ROW. Much of the runoff from parcels and the road drains to the ROW and is conveyed downstream through curb, gutter, and pipes. By identifying the typical parcel size, frontage length, and associated road area that drains to a candidate right-of-way area (Figure 1-6) the total area draining to potential green street retrofit opportunities was extrapolated throughout the watershed. For purposes of this study, only the high-density residential, multifamily residential, commercial, institutional, and industrial land uses were considered as contributing substantial runoff to the ROW (all other land uses contain minimal impervious area and thus contribute insubstantial runoff to the ROW).

The typical parcel size for each land use was determined by identifying all parcels for each land use. Once all the parcels were selected, the median parcel size for each land use was calculated and tabulated. This method evaluated thousands of parcels throughout the entire watershed and provided the most accurate depiction of the typical parcel size for each land use based on available data. Results are shown in Table 1-5.

Each parcel is adjacent to a portion of the ROW where the green street would be implemented. A subset of parcels approximate to the median parcel size for each land use was selected to determine the average frontage length. The portion of the selected parcels that was in contact with the ROW was measured using desktop analysis tools and averaged between all parcels of the same land use. Results are shown in Table 1-5.

Road area draining to green streets constitutes a substantial component of the total impervious drainage area. To establish road drainage areas, typical road widths were defined by sampling representative road segments located in each land use. Widths were measured from curb-to-curb using aerial orthoimagery and reported to the nearest even integer. The median sampled road width for each land use was calculated and compared with the City of Los Angeles Standard Street Dimensions (City of Los Angeles Bureau of Engineering 1999) for validation. To predict the resulting contributing road areas, the previously measured frontage length was multiplied by half the road width. Roads were assumed to be crowned; therefore, only half of the width would drain to one side of the road. Results are shown in Table 1-5.

As discussed in Section 1.2.4, only 30 percent of the frontage length could be converted into bioretention area. This factor was multiplied by the frontage length and used in limiting the total length of bioretention available within the model, as presented in Table 1-5.




Figure 1-6. Typical parcel area, road width, road area, and frontage length schematic (figure not to scale)

Table 1-5. Typical parcel area, road area, and frontage length

Land Use	Typical Parcel Area (ft <sup>2</sup> )	Frontage Length (ft)	Typical Road Width (ft)	Typical Road Area (ft <sup>2</sup> )	BMP Length (ft)
High-density Residential	6,528	57	38	1,083	17
Multifamily Residential	13,526	60	30	900	18
Commercial	12,429	100	63	3,150	30
Institutional	38,215	143	37	2,646	43
Industrial	26,467	117	46	2,691	35
Other Land Use (Open Space, Vacant, etc.)	n/a <sup>1</sup>	100	40	2,000	30

<sup>1</sup> assumed not draining to ROW

### Contributing Parcel Area Analysis

Many parcels will not always entirely drain to the ROW because portions can be retained on-site or flow onto an adjacent property. The actual volume of water that can be treated by a green street BMP was determined by identifying the typical proportion of the parcel that drains to the ROW (as shown in context of the model

schematic in Figure 1-7). This step also determines the area, and associated runoff, that is *not* expected to drain to green streets and is routed directly to downstream regional facilities or other practices (herein referred to as non-contributing parcel area).

The contributing areas to the green street BMPs were found using random sampling and identifying the surrounding parcel drainage patterns. Parcels were selected using a random number generator and drainage areas were determined on a desktop analysis using topography, aerial imagery, and drainage infrastructure features. The average contributing percentage was identified by evaluating multiple sites. Table 1-6 shows the percent contributing areas by land use that were determined from this analysis.

The impervious coverage of contributing parcel areas was also characterized during this step so that runoff could be simulated and routed to green streets in each land use. This was performed by tabulating the imperviousness data from the WMMS Model for each individual land use feature. The area-weighted mean impervious coverage was then calculated for each land use type. Results are tabulated for each land use in Table 1-6.




Figure 1-7. Parcel contributing area to ROW (impervious varies by land use; arrows denote direction of runoff routing; figure not to scale).

Table 1-6. Contributing area percentage by land use

Land Use	Contributing to ROW	Non-contributing to ROW	Percent Impervious
High-density Residential	80%	20%	36%
Multifamily Residential	80%	20%	60%
Commercial	80%	20%	90%
Institutional	80%	20%	72%
Industrial	35%	65%	66%
Other Land Use (Open Space, Vacant, etc.)	0%	100%	n/a

## Untreated Roads Tabulation

Untreated roads consist of roadways with steep slopes, classifications not suited for green street implementation, or adjacent to open space or vacant parcels. Untreated road and associated adjacent parcel area that will ultimately drain to other BMPs was tabulated using available GIS data and screening results from Section 1.2.2 (conceptually illustrated in Figure 1-8).

Because green streets are implemented in the linear environment of the transportation corridor, it was assumed that the percentage of parcel area draining to green streets would be proportional to the percentage of suitable roads for green streets (as identified in Section 1.2.2) in each subwatershed. In other words, parcels associated with unsuitable roads were assumed to bypass green street treatment and routed directly to other facilities (these areas are defined herein as *untreated parcels*). The total treated and untreated parcel areas were reconciled with the total areas of each land use (per subwatershed) in the WMMS Model for validation and consistency.





Figure 1-8. Schematic depicting untreated parcel and untreated road runoff routing (arrows denote direction of runoff routing; figure not to scale).

## Summary of Contributing Drainage Areas

Results of the preceding analyses are presented in Figure 1-9. Areas that were assumed *untreated* by green streets include unsuitable roads and adjacent parcels, portions of suitable parcels that do not drain to the ROW, and predominantly pervious parcels (Open Space, Vacant, etc.), as discussed in preceding subsections; runoff from these untreated areas is assumed routed directly to regional facilities. Note that contributing areas are not necessarily proportional to contributing runoff due to variation in impervious coverage; runoff routing resulting from the preceding analyses is presented in the following section.

Given more detailed street-by-street engineering analyses, the potential area treated by green streets could be optimized, but the results below represent realistic estimates based on sound engineering judgment and currently available data and resources. Adaptive management strategies could target specific land uses that tend to bypass green street treatment (e.g. runoff, and associated treatment capacity, generated by industrial areas could be addressed through relevant industrial permits or onsite BMPs). Additional discussion on adaptive management strategies is provided in Section 8 of the main report.



**Figure 1-9. Schematic characterizing approximate distribution of routing to BMPs in the ROW for all WMP areas (arrows denote direction of runoff routing; figure not to scale).**

### BMP Infiltration Rates by Subwatershed

The purpose of performing the subwatershed infiltration rate analysis was to assign an average green street BMP infiltration rate to each subwatershed using soils data. Infiltration rates were assigned at the subwatershed level, which is the finest resolution at which the model performs hydrologic and water quality computations.

Soil data coverage provided through the LACDPW categorized soil unit areas into soil types. Runoff coefficient curves reported in the Hydrology Manual were developed by LACDPW for each soil type using double ring infiltrometer tests performed on areas of homogeneous runoff characteristics (LACDPW 2006). LADPW employed a sprinkling-type infiltrometer to perform the tests in each homogeneous area.

Runoff coefficient curves represent the response of the runoff coefficient (defined as the ratio of runoff to rainfall from a land area) to varying rainfall intensities. Each curve displays an inflection point representing the rainfall intensity at which substantial runoff initiates. According to LADPW (2006), each curve was assigned a minimum runoff coefficient of 0.1, “indicating that there is some runoff even at the smallest rainfall intensities.” If it is assumed that substantial runoff initiates when the intensity of rainfall is greater than the soil’s inherent infiltration rate, then the infiltration rate can be assumed equal to the rainfall intensity at the inflection point (less the assumed minimum runoff).

As demonstrated conceptually in Figure 1-10, the inflection point, and subsequently calculated infiltration rate, for each unique soil type in the WMP areas were identified using the runoff coefficient curves in Appendix C of the *Hydrology Manual* (LADPW 2006). Subwatershed areas were then intersected with the soil type coverage to calculate an area-weighted infiltration rate. Attachment C shows the distribution of the infiltration rates.




Figure 1-10. Example determination of runoff coefficient inflection point for an arbitrary soil type in Appendix C of LACDPW (2006).

### 1.3. LID on Public Parcels Assessment

Retrofitting public parcels with LID can be an efficient strategy for reducing stormwater runoff. This method allows municipalities the flexibility to prioritize and schedule stormwater projects to coincide with improvements that are already on the books (such as scheduled parking lot resurfacing, utility work, and public park improvements). Implementing LID on public parcels also allows municipalities the freedom to construct, inspect, and maintain BMPs without the need to purchase private property or to create stormwater easements.

The spatial extent of public parcels in each subwatershed was identified by selecting all parcels labeled as public by their assessors identification number (AIN). A total of 7,052 acres of public land was identified during this process (7% of the total WMP area). Each public parcel was assumed to implement BMPs that would treat the 85<sup>th</sup> percentile, 24-hour storm. The BMP volume was assumed to equal the 85<sup>th</sup> percentile, 24-hour storm depth times the impervious area.

LID retrofits are not feasible in all locations due to steep slopes, soil contamination hazards, and other constraints. The total runoff to be retained on public parcels was therefore discounted by 30% in order to provide a more realistic goal; this estimate was made in the lack of more detailed data, based on past LID screening exercises performed in Los Angeles County. The discount factor should be refined as actual public project sites are screened and prioritized.



## 1.4. Existing, Planned, and Potential BMPs

Existing and planned BMPs throughout the WMP areas were identified by the jurisdictions. These BMPs will provide capacity to reduce the annual storm runoff volume and demonstrate progress towards achieving the target runoff volume reduction.

### 1.4.1. Modeled Existing/Planned Subwatershed-Scale Regional BMPs

Regional BMPs that treat large portions of, or entire, subwatersheds (i.e. those with drainage areas larger than 50 acres) were modeled to quantify the impact to the upstream jurisdictions. The modeling approach and predicted performance for these specific sites is detailed in the following subsections. It is important to note that modeling was performed at a planning level coincident with the resolution of the subwatershed-scale WMMS model. Limited data were available to represent the sites, so conservative engineering assumptions were applied where appropriate. The calculated equivalent volume reductions from the BMPs can be refined during the adaptive management process once detailed design and monitoring data become available for the sites.

#### DeForest Wetlands Project

The DeForest Wetlands Project is located along the east bank of the Los Angeles River in the City of Long Beach and is comprised of approximately 34 acres of restored terrestrial and freshwater habitat and recreational amenities. The Project provides both groundwater recharge and surface water quality improvement. Site and modeling details are listed in Table 1-7.

**Table 1-7. DeForest Wetlands Project details**

Parameter	Value	Unit	Notes, Assumptions
<i>Site Overview</i>			
WMP Area	Lower Los Angeles River		
Location	City of Long Beach		
Status	In Development		
<b>Compliance Targets for Contributing Subwatersheds<sup>1</sup></b>	<b>248.7</b>	<b>ac-ft/yr</b>	Subwatershed 486066
	<b>247.6</b>	<b>ac-ft/yr</b>	Subwatershed 486068
<i>Given Details</i>			
Drainage Area	1490	ac	Delineated in GIS using WMMS subwatershed boundaries
Average Annual Infiltration Volume	15-35	ac-ft/yr	Per Section 3 of the WMP
Average Annual Treated Volume	800-1000	ac-ft/yr	Per Section 3 of the WMP; assumed volume is fully treated by wetland pollutant removal mechanisms prior to discharge; assumed treated volume is in addition to infiltration volume
Annual Runoff Volume Entering Wetland <sup>1</sup>	1589	ac-ft/yr	WMMS output
Annual Zinc Load Entering Wetland <sup>1</sup>	1808	lb Zn/yr	WMMS output
Wetland Zinc Effluent Concentration	20	µg/L	Upper limit of 95% confidence interval for wetland channels, per RAA Guidelines (LARWQCB 2014)
<i>Modeling Results</i>			
Estimated Annual Zinc Load Reduced by Infiltration <sup>1</sup>	17.1	lb Zn/yr	Assumed loading associated with minimum average infiltrated runoff; assumed load sequestered in sediments and/or sorbed to underlying soils
Estimated Annual Zinc Load Reduced by Wetland Functions <sup>1</sup>	535	lb Zn/yr	Reduction associated with treated volume; calculated by subtracting average effluent load associated with minimum treated volume from annual influent loading
Estimated Zinc Load Reduction	30.5%		



Relative to Annual Runoff <sup>1</sup>			
Estimated Zinc Load Reduction Relative to Compliance Target <sup>1</sup>	97.7%		
<b>Estimated Equivalent Annual Volume Reduction<sup>1</sup></b>	<b>243.1</b>	<b>ac-ft/yr</b>	Subwatershed 486066
	<b>242.0</b>	<b>ac-ft/yr</b>	Subwatershed 486068

<sup>1</sup> Indicated annual volumes are referenced to the critical year

### Dominguez Gap Wetlands Project

The Dominguez Gap Wetlands Project consists of two treatment wetlands situated on the east and west banks of the Los Angeles River that features habitat and recreational amenities. The East Basin is a 37-ac facility that is dewatered manually by a pump. The West Basin primarily functions as an infiltration basin and is approximately 15 acres. Table 1-8 and Table 1-10 characterize the site and modeling details of the East and West Basins, respectively.

**Table 1-8. Dominguez Gap East Wetlands Project – East Basin details**

Parameter	Value	Unit	Notes, Assumptions
<i>Site Overview</i>			
WMP Area	Lower Los Angeles River		
Location	City of Long Beach		
Status	Complete		
<b>Compliance Targets for Contributing Subwatersheds<sup>1</sup></b>	<b>346.9</b>	<b>ac-ft/yr</b>	Subwatershed 486014
	<b>14.3</b>	<b>ac-ft/yr</b>	Subwatershed 446014
<i>Given Details</i>			
Drainage Area	2075	ac	Delineated in GIS using WMMS subwatershed boundaries
Maximum Volume Treated per Storm Event	71	ac-ft	Per Section 3 of the WMP; assumed volume is fully treated by wetland pollutant removal mechanisms prior to discharge
Maximum Annual Volume Treated <sup>1</sup>	526	ac-ft/yr	Based on storm events recorded for critical year; assumed all storm event runoff volume treated up to 71 ac-ft
Annual Runoff Volume Entering Wetland <sup>1</sup>	913	ac-ft/yr	WMMS output
Annual Zinc Load Entering Wetland <sup>1</sup>	934	lb Zn/yr	WMMS output
Wetland Zinc Effluent Concentration	20	µg/L	Upper limit of 95% confidence interval for wetland channels, per RAA Guidelines (LARWQCB 2014)
<i>Modeling Results</i>			
Annual Zinc Load Reduced by Infiltration <sup>1</sup>	unknown	lb Zn/yr	Site soil information or monitored data required
Annual Zinc Load Reduced by Wetland Functions <sup>1</sup>	202	lb Zn/yr	Reduction associated with treated volume; calculated by subtracting average effluent load associated with minimum treated volume from annual influent loading
Zinc Load Reduction Relative to Annual Runoff <sup>1</sup>	22%		
Zinc Load Reduction Relative to Compliance Target <sup>1</sup>	55%		
<b>Equivalent Annual Volume Reduction<sup>1</sup></b>	<b>191.7</b>	<b>ac-ft/yr</b>	Subwatershed 486014
	<b>6.4</b>	<b>ac-ft/yr</b>	Subwatershed 446014

<sup>1</sup> Indicated annual volumes are referenced to the critical year



**Table 1-9. Dominguez Gap Wetlands Project – West Basin details**

Parameter	Value	Unit	Notes, Assumptions
<i>Site Overview</i>			
WMP Area	Lower Los Angeles River		
Location	City of Long Beach		
Status	Complete		
<b>Compliance Targets for Contributing Subwatersheds<sup>1</sup></b>	<b>152.0</b>	<b>ac-ft/yr</b>	Subwatershed 486013 (41% contributes to West Basin)
	<b>7.4</b>	<b>ac-ft/yr</b>	Subwatershed 486015
<i>Given Details</i>			
Drainage Area	299	ac	Delineated in GIS using WMMS subwatershed boundaries
Annual Runoff Volume Infiltrated	All	ac-ft/yr	Per Section 3 of the WMP, no connection to Los Angeles River
<i>Modeling Results</i>			
Subwatershed 486013 Annual Runoff Volume Infiltrated <sup>1</sup>	47%		41% of subwatershed area contributes 47% of runoff volume to the basin
Subwatershed 446015 Annual Runoff Volume Infiltrated	100%		100% of subwatershed area contributing
<b>Equivalent Annual Volume Reduction<sup>1</sup></b>	<b>152.0</b>	<b>ac-ft/yr</b>	Subwatershed 486013 (compliance target is 43% annual reduction, so meets target)
	<b>7.4</b>	<b>ac-ft/yr</b>	Subwatershed 446015

<sup>1</sup> Indicated annual volumes are referenced to the critical year

### Willow Springs Park

The Willow Springs Park project will convert a public parcel to a 47-acre park. The park will contain bioswales and a water feature integrated into a recreational spaces. Table 1-10 Characterizes the site and modeling details.

**Table 1-10. Willow Springs Park details**

Parameter	Value	Unit	Notes, Assumptions
<i>Site Overview</i>			
WMP Area	Lower Los Angeles River		
Location	City of Long Beach		
Status	In Development		
<b>Compliance Targets for Contributing Subwatersheds<sup>1</sup></b>	<b>26.5</b>	<b>ac-ft/yr</b>	Subwatershed 776012
	<b>7.2</b>	<b>ac-ft/yr</b>	Subwatershed 486012
<i>Given Details</i>			
Drainage Area	211	ac	Delineated in GIS using WMMS subwatershed boundaries
Total BMP Footprint	11	Ac	Per Section 3 of the WMP; natural channels/bioswales with very high infiltration rates
Underlying soil infiltration rates	0.9	In/hr	WMMS
Subwatershed area contributing	95%		
<i>Modeling Results</i>			
Maximum infiltration rate over footprint of BMP	0.83	ac-ft/hr	Assumed constant infiltration over entire footprint, applied to each time step of model runoff output draining to park – meets compliance target via infiltration
<b>Equivalent Annual Volume Reduction<sup>1</sup></b>	<b>26.5</b>	<b>ac-ft/yr</b>	Subwatershed 776012
	<b>7.2</b>	<b>ac-ft/yr</b>	Subwatershed 446012

<sup>1</sup> Indicated annual volumes are referenced to the critical year



### Discovery Park Infiltration Basin

An existing infiltration basin located at 12400 Columbia Way in the City of Downey treats runoff from approximately 51 acres (5% of the subwatershed in which the site is located). Field observations indicate that the facility has capacity to infiltration runoff at a rate of 2 in/hr (equivalent to approximately 4 ac-ft/day) in addition to detention storage. Table 1-11 reports the simplified modeling assumptions for this BMP – upon further evaluation of as-built conditions, the associated volume reduction can be refined during the adaptive management process.

**Table 1-11. Discovery Park Infiltration Basin details**

Parameter	Value	Unit	Notes, Assumptions
<i>Site Overview</i>			
WMP Area	Lower San Gabriel River		
Location	City of Downey		
Status	Complete		
<b>Compliance Targets for Treated Subwatersheds<sup>1</sup></b>	<b>80.6</b>	<b>ac-ft/yr</b>	Subwatershed 245115
<i>Given Details</i>			
Drainage Area	51	ac	
Observed Infiltration Rate	4	ac-ft/day	Per Gerald Green, personal communication, 2014, February 2
Percentage of Subwatershed Contributing to BMP	5%		
Approximate Runoff Volume Draining to BMP <sup>1</sup>	44	ac-ft/yr	WMMS
<i>Modeling Results</i>			
<b>Equivalent Annual Volume Reduction<sup>1</sup></b>	<b>24</b>	<b>ac-ft/yr</b>	Assumed constant infiltration over entire footprint, applied to each time step of model runoff output draining to park

<sup>1</sup> Indicated annual volumes are referenced to the critical year

### Parque Dos Rios

Parque Dos Rios is located at the confluence of the Los Angeles River and Rio Hondo River. An approximately 30-ac area between the freeway and the Los Angeles River will be converted to an infiltration basin to treat additional upstream area. Currently, the site is self-retaining open space and is characterized in the baseline model as such. No further runoff volume reductions were calculated for this site; as design details are finalized for the infiltration basin improvements, associated volume reductions can be applied towards upstream jurisdictional compliance targets.

#### 1.4.2. Identified Parcel-Scale Regional and Distributed BMPs

The jurisdictions within the WMP areas compiled detailed lists of BMPs intended to treat areas smaller than 50 acres. As with the preceding regional BMPs, these strategies represent progress towards achieving the compliance target in each respective jurisdiction. The distributed BMPs are listed in Attachment D and can be applied towards meeting the compliance targets in each jurisdiction.

The WMP groups have identified additional potential regional BMPs and these are listed in Section 3 for LCC and Section 4 for LLAR and LSGR of the respective WMP.

## 1.5. Non-MS4 Facility Runoff

---

Each jurisdiction in the Group's WMP area is subject to stormwater runoff from non-MS4 facilities. In particular, Caltrans roads and facilities regulated by nontraditional or general industrial permits contribute to the runoff volume for each subwatershed. It will be important for these entities to retain their runoff and/or eliminate their cause/contribution to receiving water exceedances. The runoff from these non-MS4 facilities was therefore estimated and subtracted from the treatment target as described below.

### 1.5.1. Non-MS4 Permitted Areas

Non-MS4 permitted areas were identified based on the address list of permittees on the State Water Resources Control Board (SWRCB) website. Using the address information, corresponding parcel areas were selected using the LA County Assessor Parcel Viewer and the associated GIS Shapefile. The percentage of permitted land use area relative to the total land use area was calculated and the associated non-MS4 permitted area runoff as extracted from the WMMS runoff response output.

### 1.5.2. Caltrans

The design storm runoff generated by Caltrans facilities was estimated using WMMS land use data. Areas labeled as Transportation consist of freeways and other extensive transportation facilities that tend to fall under Caltrans jurisdiction (versus areas labeled as Secondary Roads, which are managed by local transportation departments); these areas were assumed to be Caltrans facilities. Runoff from Transportation land uses, less runoff from any overlapping non-MS4 permitted areas identified above, was extracted from the WMMS model output for each subwatershed.

## 1.6. Institutional BMPs and Minimum Control Measures

---

It is challenging to accurately quantify most institutional BMP and minimum control measure (MCM) benefits in terms of pollutant load reductions because they generally require extensive survey and monitoring information to quantify. In addition, nonstructural BMPs may target pollutants, land uses, or populations, resulting in different load reductions depending on the implementation technique. A number of MCMs are outlined in each WMP, representing an array of practices to most effectively address pollutants at their source or affect their transport. For the purposes of the RAA, a 10% reduction was assumed to represent the cumulative impact of these practices during both wet and dry conditions. Another explicitly modeled nonstructural BMP was a goal to reduce 25% of irrigation of urban vegetation, a goal that can result from a myriad of practices ranging from public education, enforcement, incentive programs, creative water rate structures, etc. The 25% reduction in irrigation was modeled directly in LSPC and is the primary driver for dry weather flow reductions. Pollutant load reductions from these nonstructural BMPs were subtracted from loads simulated in the baseline model to quantify progress towards meeting the watershed numeric goals. Results of both the 10% reduction for collective MCMs, in addition to irrigation reduction, are presented in Section 7 of the main RAA report for both wet and dry conditions.

# Attachment B: Detailed Jurisdictional Compliance Tables

---

***Submitted to:***

LLAR WMP Group

LCC WMP Group

LSGR WMP Group

***Submitted by:***



Tetra Tech  
9444 Balboa Ave., Suite 215  
San Diego, CA 92123

**June 6, 2014**



## Contents

<b>B1. Lower Los Angeles River WMP Detailed Tables.....</b>	<b>3</b>
B1.1. City of Downey.....	3
B1.2. City of Lakewood .....	3
B1.3. City of Long Beach .....	4
B1.4. City of Lynwood .....	5
B1.5. City of Paramount .....	5
B1.6. City of Pico Rivera .....	6
B1.7. City of Signal Hill.....	6
B1.8. City of South Gate .....	7
<b>B2. Los Cerritos Channel WMP Detailed Tables .....</b>	<b>8</b>
B2.1. City of Bellflower .....	8
B2.2. City of Cerritos .....	8
B2.3. City of Downey.....	9
B2.4. City of Lakewood .....	9
B2.5. City of Long Beach .....	10
B2.6. City of Paramount .....	11
B2.7. City of Signal Hill.....	11
<b>B3. Lower San Gabriel River (San Gabriel River) WMP Detailed Tables .....</b>	<b>12</b>
B3.1. City of Artesia .....	12
B3.2. City of Bellflower .....	12
B3.3. City of Cerritos .....	13
B3.4. City of Diamond Bar.....	13
B3.5. City of Downey.....	14
B3.6. City of Lakewood .....	14
B3.7. City of Long Beach .....	15
B3.8. City of Norwalk.....	15
B3.9. City of Pico Rivera .....	16
B3.10. City of Santa Fe Springs.....	17
B3.11. City of Whittier .....	18
<b>B4. Lower San Gabriel River WMP (Coyote Creek) Detailed Tables .....</b>	<b>19</b>
B4.1. City of Artesia .....	19
B4.2. City of Cerritos .....	19
B4.3. City of Diamond Bar.....	20
B4.4. City of Hawaiian Gardens .....	20
B4.5. City of La Mirada.....	21
B4.6. City of Lakewood .....	22
B4.7. City of Long Beach .....	22
B4.8. City of Norwalk.....	23
B4.9. City of Santa Fe Springs.....	24
B4.10. City of Whittier .....	25

## B1. Lower Los Angeles River WMP Detailed Tables

### B1.1. City of Downey

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
6076	Final	17.0	-	-	1.2	-	1.2
6077	Final	123.0	0.3	11.8	1.2	6.4	19.6
6079	50%	176.4	0.7	1.7	10.1	-	12.5
6082	Final	0.3	-	-	0.0	0.0	0.0
6100	50%	10.7	0.0	0.8	0.0	0.6	1.4
6102	31%	143.8	1.1	12.2	0.7	7.1	21.1
6103	Final	-	0.7	-	-	-	0.7
6104	Final	37.1	0.3	3.2	0.0	0.9	4.5
6106	Final	76.4	0.4	9.1	1.6	-	11.1
6111	Final	69.5	0.3	7.1	0.5	3.3	11.2
6113	Final	0.6	-	0.0	-	0.1	0.1
Grand Total		654.7	3.8	45.9	15.3	18.4	83.4

### B1.2. City of Lakewood

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
6014	31%	7.9	-	1.1	0.0	-	1.2
Grand Total		7.9	-	1.1	0.0	-	1.2



### B1.3. City of Long Beach

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
6001	Final	-	-	-	-	-	-
6002	50%	378.7	-	23.8	5.2	19.3	48.3
6003	Final	429.9	-	22.4	1.4	32.8	56.5
6004	50%	2.4	-	0.1	-	0.3	0.3
6005	31%	6.6	-	1.0	0.0	-	1.0
6006	Final	35.9	-	0.3	0.1	4.1	4.5
6007	Final	67.0	-	6.4	0.1	4.0	10.6
6008	Final	144.0	-	13.9	2.0	3.5	19.4
6009	Final	159.5	-	11.5	0.7	9.2	21.4
6010	Final	100.8	-	8.2	0.9	4.8	13.9
6011	Final	184.8	-	14.4	0.9	9.6	24.9
6012	31%	-	-	-	-	-	-
6013	50%	-	-	-	-	-	-
6014	Final	155.2	-	15.0	7.9	-	22.9
6015	31%	-	-	-	-	-	-
6016	Final	-	-	-	-	-	-
6017	50%	1.1	-	-	-	0.1	0.1
6018	Final	45.8	-	4.3	-	2.6	6.9
6065	Final	36.7	-	0.4	0.0	4.6	5.0
6066	31%	-	-	-	-	-	-
6067	50%	25.3	-	2.6	0.3	0.5	3.3
6068	31%	-	-	-	-	-	-
6069	50%	42.6	-	0.6	0.0	3.5	4.1
6070	50%	22.2	-	2.7	0.4	-	3.1
6071	50%	94.4	-	10.5	1.6	1.0	13.1
6072	50%	0.3	-	0.0	-	0.0	0.0
7016	Final	473.3	-	16.5	6.9	36.3	59.7
Grand Total		2,406.2	-	154.6	28.3	136.2	319.1



### B1.4. City of Lynwood

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
6023	Final	26.3	-	1.0	0.7	1.6	3.3
6024	Final	10.6	-	0.4	-	1.1	1.4
6028	31%	11.2	-	0.8	-	0.9	1.7
6030	Final	45.2	-	4.0	2.4	-	6.4
6031	31%	133.0	-	9.9	2.0	7.5	19.4
6032	Final	60.5	-	6.0	0.4	3.4	9.8
6033	Final	113.3	-	7.4	0.2	10.7	18.2
6074	50%	134.9	-	12.8	3.8	0.1	16.8
6078	Final	-	-	-	-	-	-
6080	31%	91.7	-	7.7	0.7	4.7	13.2
6081	Final	41.3	-	4.0	0.8	0.5	5.3
6082	Final	-	-	-	-	-	-
Grand Total		667.9	-	53.9	11.1	30.5	95.5

### B1.5. City of Paramount

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
6069	31%	0.0	-	-	-	-	-
6071	Final	120.7	0.0	4.9	0.9	9.9	15.6
6072	Final	172.9	0.0	7.6	1.1	13.9	22.6
6073	Final	61.4	-	1.9	0.2	4.6	6.6
6075	31%	163.7	-	9.0	1.7	10.2	20.9
6076	50%	65.7	-	7.4	0.8	0.3	8.6
6078	Final	21.7	-	0.5	0.0	1.8	2.3
6080	Final	-	-	-	-	-	-
Grand Total		606.1	0.1	31.2	4.7	40.6	76.6



## B1.6. City of Pico Rivera

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
6106	31%	44.3	-	5.9	0.5	0.2	6.5
6111	Final	-	-	-	-	-	-
6112	31%	1.4	-	0.0	-	0.1	0.2
6113	31%	229.5	-	5.6	0.0	27.0	32.7
6114	Final	-	-	-	-	-	-
6115	Final	0.0	-	-	-	0.0	0.0
6116	Final	-	-	-	-	-	-
6117	Final	-	-	-	-	-	-
6126	Final	12.0	-	1.3	0.0	0.5	1.8
6129	Final	-	-	-	-	-	-
Grand Total		287.2	-	12.8	0.5	27.9	41.2

## B1.7. City of Signal Hill

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
6002	50%	105.8	-	7.0	0.9	5.9	13.9
6003	Final	43.7	-	1.9	0.0	4.2	6.0
6007	Final	-	-	-	-	-	-
6009	Final	8.2	0.1	0.3	-	0.7	1.1
6011	31%	6.0	0.1	0.8	-	0.2	1.1
6012	31%	2.5	-	0.0	0.2	-	0.2
Grand Total		166.2	0.2	10.0	1.1	11.0	22.3



## B1.8. City of South Gate

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
6031	31%	148.6	-	16.9	0.8	5.3	22.9
6033	Final	61.9	-	4.5	0.3	4.8	9.5
6034	Final	416.7	-	30.0	3.8	25.3	59.0
6076	50%	92.5	-	7.5	0.7	5.1	13.2
6078	Final	-	-	-	-	-	-
6079	50%	54.4	-	4.9	0.1	3.4	8.4
6080	31%	48.7	-	5.8	-	2.5	8.3
6082	Final	82.8	0.0	4.3	0.1	9.4	13.8
6083	Final	11.5	-	0.7	-	0.9	1.6
6084	Final	137.8	4.7	8.3	0.8	5.9	19.8
6085	50%	-	-	-	-	-	-
6089	Final	18.3	-	0.8	0.2	1.8	2.7
6090	Final	3.4	-	0.6	-	-	0.6
6096	31%	0.6	-	0.0	0.0	0.0	0.1
6098	31%	0.1	-	-	0.0	-	0.0
6100	50%	51.2	-	2.6	0.0	4.2	6.8
6101	31%	25.0	-	0.5	0.1	2.6	3.3
6102	31%	6.3	-	-	-	0.8	0.8
6104	Final	7.4	-	0.0	0.0	0.9	1.0
6350	Final	-	-	-	-	-	-
6351	Final	7.1	-	0.0	0.0	1.1	1.1
Grand Total		1,174.3	4.7	87.5	6.8	73.8	173.0



## B2. Los Cerritos Channel WMP Detailed Tables

### B2.1. City of Bellflower

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5507	Final	268.1	-	16.7	1.2	13.2	31.1
5517	Final	137.7	-	9.3	0.8	9.3	19.4
5518	Final	233.5	-	16.8	1.2	10.2	28.2
5519	35%	176.3	-	11.4	0.9	12.1	24.4
	Final	59.5	-	-	-	3.6	3.6
5523	35%	68.0	-	3.7	0.4	4.1	8.2
	Final	32.3	-	-	-	2.0	2.0
5524	Final	14.8	-	0.2	-	1.2	1.4
Grand Total		990.4	-	58.1	4.5	55.6	118.2

### B2.2. City of Cerritos

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5506	Final	0.0	-	-	-	0.0	0.0
5507	35%	9.7	-	1.0	0.0	0.5	1.4
	Final	3.2	-	-	-	0.1	0.1
Grand Total		12.9	-	1.0	0.0	0.6	1.6



### B2.3. City of Downey

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5524	35%	57.2	0.1	5.3	0.0	2.7	8.1
	Final	35.8	-	-	-	2.1	2.1
Grand Total		93.0	0.1	5.3	0.0	4.8	10.2

### B2.4. City of Lakewood

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5506	Final	226.5	-	31.4	2.1	5.1	38.5
5507	35%	131.0	-	15.4	2.6	1.5	19.5
	Final	45.2	-	-	-	3.6	3.6
5510	Final	19.9	-	0.4	-	1.5	1.9
5512	Final	138.8	-	7.7	0.2	7.0	14.9
5514	Final	35.3	-	3.7	1.3	0.4	5.4
5515	Final	26.6	-	3.9	0.2	0.5	4.6
5516	Final	31.9	-	4.0	0.4	0.8	5.3
5517	Final	134.4	-	18.6	1.4	2.8	22.9
5519	35%	3.1	-	0.2	-	0.2	0.4
	Final	6.4	-	-	-	0.1	0.1
5520	35%	130.9	-	14.0	2.1	4.4	20.6
	Final	33.5	-	-	-	3.3	3.3
5521	Final	95.2	-	11.6	0.6	2.2	14.3
5522	Final	71.9	-	8.7	0.8	1.6	11.1
5523	35%	17.4	-	1.9	-	0.7	2.6
	Final	4.0	-	-	-	0.3	0.3
Grand Total		1,152.1	-	121.5	11.8	36.2	169.5



## B2.5. City of Long Beach

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5501	35%	0.1	-	0.0	0.0	0.0	0.0
	Final	0.1	-	-	-	0.0	0.0
5502	35%	0.1	-	0.0	0.0	0.0	0.0
	Final	0.2	-	-	-	0.0	0.0
5503	35%	57.7	-	4.2	2.3	2.0	8.5
	Final	20.1	-	-	-	1.7	1.7
5504	35%	196.6	-	10.2	3.3	8.7	22.2
	Final	104.4	-	-	-	5.5	5.5
5505	Final	130.5	-	15.9	1.6	3.2	20.7
5506	Final	8.6	-	0.1	0.2	0.4	0.7
5508	Final	65.6	-	7.7	0.9	1.7	10.3
5509	Final	25.6	-	-	2.2	-	2.2
5510	Final	152.2	-	9.8	0.9	6.1	16.8
5511	Final	48.5	-	6.7	0.2	1.3	8.1
5512	Final	329.5	-	22.2	1.7	16.8	40.7
5513	35%	23.9	-	1.5	0.1	2.1	3.7
	Final	6.6	-	-	-	0.4	0.4
5514	35%	106.0	-	10.9	5.9	-	16.7
	Final	46.8	-	3.7	-	2.8	6.5
5515	Final	91.0	-	10.8	1.7	2.3	14.9
5520	Final	7.4	-	0.8	-	0.3	1.2
5521	Final	49.2	-	6.0	0.1	1.8	7.9
5522	Final	48.6	-	4.2	0.0	3.1	7.3
5523	35%	89.3	-	7.0	0.8	3.5	11.3
	Final	21.4	-	-	-	1.6	1.6
Grand Total		1,629.8	-	121.7	21.8	65.3	208.7



## B2.6. City of Paramount

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5519	35%	24.0	-	1.9	0.2	1.4	3.5
	Final	11.4	-	-	-	0.6	0.6
5523	35%	243.0	-	12.4	2.8	15.7	30.9
	Final	89.6	-	-	-	4.1	4.1
5524	Final	157.5	-	8.5	3.5	4.0	16.0
Grand Total		525.5	-	22.8	6.4	25.9	55.1

## B2.7. City of Signal Hill

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5510	35%	231.6	0.0	11.2	1.2	14.2	26.6
	Final	52.7	-	-	-	2.0	2.0
Grand Total		284.3	0.0	11.2	1.2	16.2	28.6



## B3. Lower San Gabriel River (San Gabriel River) WMP Detailed Tables

### B3.1. City of Artesia

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5109	35%	1.1	-	-	0.1	-	0.1
Grand Total		1.1	-	-	0.1	-	0.1

### B3.2. City of Bellflower

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5110	Final	0.0	-	-	-	0.0	0.0
5112	Final	0.6	-	0.1	0.0	-	0.1
5113	Final	51.5	-	0.9	3.4	-	4.3
5114	Final	-	-	-	-	-	-
5115	35%	1.3	-	0.2	0.0	-	0.2
5116	Final	0.1	-	-	-	0.0	0.0
5118	Final	3.9	-	0.6	0.3	-	0.9
Grand Total		57.4	-	1.8	3.7	0.0	5.5



### B3.3. City of Cerritos

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5107	Final	-	-	-	-	-	-
5108	Final	-	-	-	-	-	-
5109	Final	-	-	-	-	-	-
5110	Final	2.9	-	0.4	0.0	-	0.4
5111	Final	-	-	-	-	-	-
5112	Final	1.2	-	0.2	0.0	-	0.2
5113	Final	-	-	-	-	-	-
5116	35%	-	-	-	-	-	-
Grand Total		4.1	-	0.6	0.0	-	0.6

### B3.4. City of Diamond Bar

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5197	Final	0.0	-	0.0	-	-	0.0
5198	Final	-	-	-	-	-	-
5203	Final	-	-	-	-	-	-
5204	Final	-	-	-	-	-	-
5205	Final	1.0	-	0.2	-	-	0.2
5212	Final	-	-	-	-	-	-
5213	35%	-	-	-	-	-	-
Grand Total		1.1	-	0.2	-	-	0.2



### B3.5. City of Downey

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5113	Final	-	1.0	-	-	-	1.0
5114	Final	22.4	0.8	2.1	0.4	-	3.3
5115	Final	-	0.6	-	-	-	0.6
5118	Final	-	0.6	-	-	-	0.6
5119	Final	52.5	3.3	6.4	-	-	9.7
5122	35%	-	0.0	-	-	-	0.0
5124	Final	-	0.0	-	-	-	0.0
5125	Final	2.5	0.4	0.1	-	-	0.5
5126	Final	9.8	0.3	1.4	-	-	1.7
5127	Final	-	0.1	-	-	-	0.1
5128	Final	-	0.0	-	-	-	0.0
Grand Total		87.3	7.1	10.0	0.4	-	17.5

### B3.6. City of Lakewood

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5105	Final	0.8	-	-	0.0	0.1	0.1
5106	35%	-	-	-	-	-	-
5107	Final	-	-	-	-	-	-
5108	Final	1.4	-	0.2	0.0	-	0.2
5110	Final	-	-	-	-	-	-
Grand Total		2.2	-	0.2	0.0	0.1	0.4



### B3.7. City of Long Beach

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5102	Final	-	-	-	-	-	-
5103	35%	26.9	-	1.1	1.3	-	2.4
5104	Final	2.3	-	0.3	-	-	0.3
5105	Final	-	-	-	-	-	-
5106	Final	0.0	-	-	-	0.0	0.0
Grand Total		29.2	-	1.4	1.3	0.0	2.7

### B3.8. City of Norwalk

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5109	35%	0.8	-	-	0.1	-	0.1
5116	Final	-	-	-	-	-	-
5117	Final	-	-	-	-	-	-
5118	Final	0.1	-	-	0.0	-	0.0
5120	Final	-	-	-	-	-	-
5121	Final	3.9	-	-	0.3	-	0.3
5122	Final	-	-	-	-	-	-
5124	Final	-	-	-	-	-	-
Grand Total		4.8	-	-	0.3	-	0.3



### B3.9. City of Pico Rivera

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5127	Final	0.0	-	-	-	0.0	0.0
5128	Final	6.4	-	1.2	-	-	1.2
5130	Final	6.1	-	1.1	-	-	1.1
5131	Final	11.7	-	2.0	-	-	2.0
5132	Final	0.0	-	-	-	0.0	0.0
5135	Final	4.3	-	0.8	-	-	0.8
5136	Final	7.2	-	1.3	-	-	1.3
5137	35%	0.2	-	0.0	-	-	0.0
5139	Final	7.8	-	1.4	-	-	1.4
5140	Final	-	-	-	-	-	-
5141	Final	4.9	-	0.8	-	-	0.8
5142	Final	-	-	-	-	-	-
5143	Final	8.9	-	1.6	-	-	1.6
5144	Final	-	-	-	-	-	-
5145	Final	1.7	-	0.3	-	-	0.3
5147	Final	-	-	-	-	-	-
5148	Final	0.2	-	0.0	-	-	0.0
5149	Final	0.0	-	-	-	-	-
5150	Final	-	-	-	-	-	-
5151	Final	-	-	-	-	-	-
5153	Final	1.0	-	0.2	-	-	0.2
5154	Final	-	-	-	-	-	-
Grand Total		60.4	-	10.8	-	0.0	10.8



### B3.10. City of Santa Fe Springs

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5120	Final	3.1	-	0.2	-	0.3	0.5
5122	Final	-	-	-	-	-	-
5123	Final	23.9	-	3.8	-	-	3.8
5127	35%	-	-	-	-	-	-
5129	Final	-	-	-	-	-	-
5130	Final	-	-	-	-	-	-
5132	Final	-	-	-	-	-	-
5133	Final	-	-	-	-	-	-
5134	Final	3.3	-	0.6	-	-	0.6
5135	Final	0.0	-	0.0	-	0.0	0.0
Grand Total		30.3	-	4.6	-	0.3	4.9



### B3.11. City of Whittier

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5138	Final	7.1	-	1.4	-	-	1.4
5142	Final	-	-	-	-	-	-
5146	Final	-	-	-	-	-	-
5147	Final	-	-	-	-	-	-
5148	Final	-	-	-	-	-	-
5153	35%	0.0	-	-	-	0.0	0.0
5173	Final	-	-	-	-	-	-
Grand Total		7.1	-	1.4	-	0.0	1.4

DRAFT



## B4. Lower San Gabriel River WMP (Coyote Creek) Detailed Tables

### B4.1. City of Artesia

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5008	Final	-	-	-	-	-	-
5018	35%	15.9	-	-	1.1	-	1.1
Grand Total		15.9	-	-	1.1	-	1.1

### B4.2. City of Cerritos

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5008	Final	7.7	-	-	0.9	-	0.9
5016	Final	-	-	-	-	-	-
5017	Final	4.3	-	-	0.5	-	0.5
5018	Final	14.9	-	-	1.1	-	1.1
5023	Final	-	-	-	-	-	-
5024	Final	-	-	-	-	-	-
5026	Final	5.8	-	1.0	0.0	-	1.0
5028	Final	-	-	-	-	-	-
5029	Final	4.9	-	0.3	0.2	-	0.6
5030	35%	0.1	-	0.0	-	-	0.0
5035	Final	-	-	-	-	-	-
5036	Final	1.2	-	0.2	0.0	-	0.2
5038	Final	-	-	-	-	-	-
5059	Final	15.1	-	1.6	0.5	-	2.0
5060	Final	-	-	-	-	-	-
5061	Final	2.6	-	-	0.2	-	0.2
Grand Total		56.7	-	3.1	3.4	-	6.4



### B4.3. City of Diamond Bar

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5053	Final	-	-	-	-	-	-
5054	35%	1.0	-	0.3	-	-	0.3
5055	Final	8.4	-	1.2	-	0.7	1.9
5056	Final	-	-	-	-	-	-
5057	Final	-	-	-	-	-	-
5058	Final	27.2	-	6.7	-	-	6.7
Grand Total		36.7	-	8.2	-	0.7	8.9

### B4.4. City of Hawaiian Gardens

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5004	Final	-	-	-	-	-	-
5007	35%	23.6	-	0.3	1.5	-	1.8
5009	Final	0.1	-	-	-	0.0	0.0
5013	Final	1.3	-	-	0.1	-	0.1
5014	Final	2.1	-	0.2	0.0	-	0.3
Grand Total		27.1	-	0.6	1.6	0.0	2.2



## B4.5. City of La Mirada

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5037	Final	-	-	-	-	-	-
5038	Final	-	-	-	-	-	-
5039	Final	-	-	-	-	-	-
5040	Final	-	-	-	-	-	-
5041	Final	-	-	-	-	-	-
5042	Final	-	-	-	-	-	-
5043	Final	19.1	-	1.9	0.6	-	2.5
5044	Final	-	-	-	-	-	-
5045	35%	-	-	-	-	-	-
5059	Final	1.4	-	0.3	-	-	0.3
5060	Final	-	-	-	-	-	-
5062	Final	20.5	-	1.0	1.1	-	2.1
5063	Final	37.0	-	-	3.0	-	3.0
5064	Final	-	-	-	-	-	-
5067	Final	-	-	-	-	-	-
5069	Final	40.3	-	5.3	0.9	-	6.2
5070	Final	-	-	-	-	-	-
5073	Final	5.7	-	1.0	-	-	1.0
5074	Final	0.8	-	0.1	-	-	0.1
5080	Final	-	-	-	-	-	-
Grand Total		124.9	-	9.6	5.6	-	15.2



### B4.6. City of Lakewood

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5004	Final	-	-	-	-	-	-
5007	35%	17.5	-	0.9	0.7	-	1.6
5008	Final	2.3	-	-	0.3	-	0.3
5014	Final	-	-	-	-	-	-
5015	Final	-	-	-	-	-	-
5016	Final	-	-	-	-	-	-
5017	Final	-	-	-	-	-	-
Grand Total		19.7	-	0.9	0.9	-	1.9

### B4.7. City of Long Beach

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5003	Final	-	-	-	-	-	-
5004	35%	-	-	-	-	-	-
5005	Final	-	-	-	-	-	-
5007	Final	-	-	-	-	-	-
5009	Final	-	-	-	-	-	-
5013	Final	0.0	-	-	0.0	-	0.0
Grand Total		0.0	-	-	0.0	-	0.0



## B4.8. City of Norwalk

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5008	35%	1.6	-	-	0.2	-	0.2
5018	Final	2.0	-	-	0.2	-	0.2
5019	Final	24.3	-	-	1.8	-	1.8
5020	Final	-	-	-	-	-	-
5021	Final	16.9	-	-	1.3	-	1.3
5022	Final	7.7	-	1.4	-	-	1.4
5024	Final	-	-	-	-	-	-
5025	Final	-	-	-	-	-	-
5060	Final	-	-	-	-	-	-
5068	Final	-	-	-	-	-	-
5071	Final	-	-	-	-	-	-
5073	Final	-	-	-	-	-	-
Grand Total		52.5	-	1.4	3.4	-	4.7



## B4.9. City of Santa Fe Springs

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5019	Final	0.0	-	-	-	0.0	0.0
5020	Final	-	-	-	-	-	-
5022	Final	-	-	-	-	-	-
5024	Final	-	-	-	-	-	-
5025	Final	-	-	-	-	-	-
5060	Final	-	-	-	-	-	-
5061	Final	-	-	-	-	-	-
5062	Final	-	-	-	-	-	-
5067	Final	-	-	-	-	-	-
5068	Final	-	-	-	-	-	-
5069	Final	-	-	-	-	-	-
5071	Final	-	-	-	-	-	-
5072	Final	2.6	-	0.3	-	0.1	0.4
5073	Final	-	-	-	-	-	-
5084	Final	1.4	-	0.2	-	-	0.2
5089	Final	-	-	-	-	-	-
5092	Final	1.1	-	0.1	-	0.2	0.2
5093	Final	-	-	-	-	-	-
5094	Final	7.4	-	0.4	-	0.9	1.2
5095	35%	-	-	-	-	-	-
Grand Total		12.6	-	1.0	-	1.1	2.1



## B4.10. City of Whittier

Subwatershed	Milestone	COMPLIANCE TARGET	POLLUTANT REDUCTION PLAN				
		Remaining MS4 Responsible Critical Year Volume (acre-ft/year)	Existing Distributed BMP Volume (acre-ft)	Total Estimated Right-of-Way BMP Volume (acre-ft)	Estimated Potential LID on Public Parcels Volume (acre-ft)	Remaining BMP Volume (Potentially Regional BMPs) (acre-ft)	Total BMP Volume to Achieve Compliance (acre-ft)
5045	Final	0.0	-	-	-	0.0	0.0
5064	Final	-	-	-	-	-	-
5065	Final	3.7	-	0.8	-	-	0.8
5070	Final	0.0	-	-	-	0.0	0.0
5079	Final	11.7	-	2.5	-	-	2.5
5080	Final	26.0	-	5.5	-	-	5.5
5081	35%	-	-	-	-	-	-
5082	Final	0.2	-	0.0	-	-	0.0
5083	Final	-	-	-	-	-	-
5086	Final	-	-	-	-	-	-
5087	Final	20.8	-	4.1	-	-	4.1
5088	Final	24.7	-	5.4	-	-	5.4
5089	Final	0.5	-	0.1	-	-	0.1
5090	Final	0.8	-	0.2	-	-	0.2
5091	Final	5.7	-	1.1	-	-	1.1
5092	Final	8.9	-	1.7	-	-	1.7
5093	Final	0.0	-	-	-	0.0	0.0
5094	Final	0.6	-	0.1	-	0.0	0.1
5095	Final	21.1	-	3.9	-	-	3.9
5096	Final	3.8	-	0.7	-	-	0.7
5097	Final	5.2	-	1.0	-	-	1.0
5098	Final	47.9	-	8.7	-	-	8.7
5099	Final	10.6	-	1.9	-	-	1.9
5100	Final	7.3	-	1.4	-	-	1.4
5101	Final	0.6	-	0.1	-	-	0.1
Grand Total		200.1	-	39.0	-	0.0	39.1

# Attachment C: Supporting Figures for Watershed Control Measures

---

***Submitted to:***

LLAR WMP Group

LCC WMP Group

LSGR WMP Group

***Submitted by:***



Tetra Tech  
9444 Balboa Ave., Suite 215  
San Diego, CA 92123

**June 6, 2014**




Figure 1. LLAR ROW BMP Potential Opportunities




Figure 2. LLAR Subwatershed Infiltration Rates




Figure 3. LLAR Non-MS4 Permittees




Figure 4. LLAR identified public parcels




Figure 5. LLAR ROW BMP Volume Reduction




Figure 6. LLAR BMP capacity outside of the right-of-way




Figure 7. LCC ROW BMP Potential Opportunities




Figure 8. LCC Subwatershed Infiltration Rates




Figure 9. LCC Non-MS4 Permittees




Figure 10. LCC identified public parcels




Figure 11. LCC ROW BMP Volume Reduction




Figure 12. LCC BMP capacity outside of the right-of-way




Figure 13. LSGR ROW BMP Potential Opportunities




Figure 14. LSGR Subwatershed Infiltration Rates




Figure 15. LSGR Non-MS4 Permittees




Figure 16. LSGR identified public parcels




Figure 17. LSGR ROW BMP Volume Reduction




Figure 18. LSGR BMP capacity outside of the right-of-way

# Attachment D: Existing and Planned BMPs

---

***Submitted to:***

LLAR WMP Group

LCC WMP Group

LSGR WMP Group

***Submitted by:***



Tetra Tech  
9444 Balboa Ave., Suite 215  
San Diego, CA 92123

**June 6, 2014**

## Contents

<b>D1. Existing and Planned BMPs</b> .....	<b>3</b>
D1.1. City of Bellflower .....	3
D1.2. City of Downey.....	4
D1.3. City of Lakewood .....	85
D1.4. City of Paramount .....	86
D1.5. City of Pico Rivera .....	87
D1.6. City of Signal Hill.....	88
D1.7. City of South Gate .....	95
D1.8. City of Whittier .....	100

DRAFT



## D1. Existing and Planned BMPs

The following tables summarize existing and planned BMPs in each jurisdiction.

### D1.1. City of Bellflower

Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Bioretention / Biofiltration	Existing	Riverview Park Infiltration Trenches	2012	10500 Somerset Blvd.	33.896662	-118.11016	105113	16	ac		
Bioretention / Biofiltration	Existing	Riverview Park Infiltration Trenches	2012	10500 Somerset Blvd.	33.896662	-118.11016	105113	16	ac		
Flow-Through Treatment BMP	Existing	Commercial Gas Station and mart	2008	14300 Bellflower Blvd	33.901581	-118.124915	105114	0.42	ac		
Flow-Through Treatment BMP	Existing	Commercial Storage	2005	10526 Rosecrans	33.902009	-118.108102	575118	19.5	ac		
Infiltration BMPs	Existing	St George Church	2012	15725 Cornuta	33.890539	-118.120735	105113	1.36	ac		
Infiltration BMPs	Existing	Autozone	2012	10239 Rosecrans	33.902265	-118.114834	105113	0.78	ac		



## D1.2. City of Downey

Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Flow Through Treatment BMP	Existing	8314 SECOND ST	2/14/2014		33.9409	-118.13243	245114	1322	sf	0.153	cfs
Flow Through Treatment BMP	Existing	10030 LAKEWOOD	8/17/2007		33.9477	-118.11664	245125	24560	sf	0.17	cfs
Infiltration BMP	Existing	12327 WOODRUFF AV	2/14/2014		33.91989	-118.11706	245113	6894.4	sf	430.9	cf
Infiltration BMP	Existing	12145 WOODRUFF	7/8/2008		33.92338	-118.11805	245113	3200	sf	200	cf
Infiltration BMP	Existing	9500 WASHBURN	2/14/2014		33.92366	-118.1172	245113	342000	sf	9500	cf
Infiltration BMP	Existing	9236 HALL	4/17/2007		33.92972	-118.12155	245113	411840	sf	25740	cf
Infiltration BMP	Existing	9737 IMPERIAL	6/22/2010		33.91761	-118.11961	245114	5600	sf	350	cf
Infiltration BMP	Existing	12254 BELLFLOWER	9/13/2003		33.9214	-118.1239	245114	57600	sf	3600	cf
Infiltration BMP	Existing	11904 BELLFLOWER	2/14/2014		33.92607	-118.12515	245114	5400	sf	300	cf
Infiltration BMP	Existing	11610 LAKEWOOD	9/28/2007		33.93101	-118.12594	245114	91520	sf	5720	cf
Infiltration BMP	Existing	8329 DAVIS	6/15/2010		33.9366	-118.13379	245114	12608	sf	788	cf
Infiltration BMP	Existing	8522 FIRESTONE	2/16/2005		33.93678	-118.12978	245114	105456	sf	6591	cf
Infiltration BMP	Existing	8320 FIRESTONE BLVD	1/1/2010		33.9387	-118.13176	245114	90660	sf	525	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9060 IMPERIAL	4/15/2005		33.91646	-118.13532	245115	7056	sf	441	cf
Infiltration BMP	Existing	8141 DE PALMAQ	6/30/2003		33.93618	-118.1402	245115	443008	sf	27688	cf
Infiltration BMP	Existing	8317 DAVIS ST	2/14/2014		33.93683	-118.13441	245115	13920	sf	870	cf
Infiltration BMP	Existing	8333 IOWA	10/11/2001		33.93756	-118.13356	245115	9808	sf	613	cf
Infiltration BMP	Existing	8100 PHLOX	5/20/2004		33.93956	-118.13854	245115	14400	sf	900	cf
Infiltration BMP	Existing	11040 BROOKSHIRE	1/1/2014		33.93932	-118.12496	245119	1923616	sf	120226	cf
Infiltration BMP	Existing	11136 DOLLISON	6/22/2010		33.93448	-118.09613	245122	13824	sf	864	cf
Infiltration BMP	Existing	10239 PICO VISTA	4/7/2003		33.939	-118.10316	245126	2176	sf	136	cf
Infiltration BMP	Existing	10233 PICO VISTA	4/7/2003		33.93914	-118.10305	245126	2176	sf	136	cf
Infiltration BMP	Existing	10228 PICO VISTA	4/7/2003		33.93919	-118.10235	245126	5856	sf	366	cf
Infiltration BMP	Existing	10229 PICO VISTA	4/7/2003		33.93928	-118.10295	245126	2176	sf	136	cf
Infiltration BMP	Existing	10223 PICO VISTA	4/7/2003		33.93946	-118.10289	245126	2048	sf	128	cf
Infiltration BMP	Existing	10218 PICO VISTA	4/7/2003		33.93947	-118.10223	245126	5952	sf	372	cf
Infiltration BMP	Existing	10215 PICO VISTA	4/7/2003		33.93962	-118.10237	245126	2112	sf	132	cf
Infiltration BMP	Existing	10211 PICO VISTA	4/7/2003		33.93969	-118.10255	245126	2304	sf	144	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	10219 PICO VISTA	4/7/2003		33.93975	-118.10273	245126	2304	sf	144	cf
Infiltration BMP	Existing	12800 PARAMOUNT	9/16/2008		33.92108	-118.15383	246077	3168	sf	198	cf
Infiltration BMP	Existing	7930 STEWARD & GRAY	11/18/2004		33.93539	-118.14527	246077	1600	sf	100	cf
Infiltration BMP	Existing	12229 JULIUS	1/1/2006		33.93343	-118.1561	246079	944	sf	59	cf
Infiltration BMP	Existing	7845 BENARES ST	6/14/2001		33.93839	-118.14549	246079	3568	sf	223	cf
Infiltration BMP	Existing	7841 BENARES ST	6/14/2001		33.93851	-118.14537	246079	1760	sf	110	cf
Infiltration BMP	Existing	7837 BENARES ST	6/14/2001		33.93863	-118.14528	246079	1760	sf	110	cf
Infiltration BMP	Existing	7848 BENARES ST	6/14/2001		33.93863	-118.14598	246079	10640	sf	665	cf
Infiltration BMP	Existing	7833 BENARES ST	6/14/2001		33.93875	-118.14518	246079	1760	sf	110	cf
Infiltration BMP	Existing	7844 BENARES ST	6/14/2001		33.93876	-118.14591	246079	2000	sf	125	cf
Infiltration BMP	Existing	7840 BENARES ST	6/14/2001		33.93886	-118.14578	246079	2000	sf	125	cf
Infiltration BMP	Existing	11706 RIVES	6/14/2001		33.93888	-118.14506	246079	1760	sf	110	cf
Infiltration BMP	Existing	7816 BENARES ST	6/14/2001		33.93896	-118.14553	246079	9600	sf	600	cf
Infiltration BMP	Existing	7812 BENARES ST	6/14/2001		33.93904	-118.14568	246079	1760	sf	110	cf
Infiltration BMP	Existing	11726 RIVES	6/14/2001		33.93904	-118.14614	246079	1920	sf	120	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7808 BENARES ST	6/14/2001		33.93911	-118.14583	246079	1760	sf	110	cf
Infiltration BMP	Existing	7808 BENARES ST	6/14/2001		33.93919	-118.14598	246079	1760	sf	110	cf
Infiltration BMP	Existing	7821 BENARES ST	6/14/2001		33.93921	-118.14506	246079	1872	sf	117	cf
Infiltration BMP	Existing	7804 BENARES ST	6/14/2001		33.93926	-118.14613	246079	9760	sf	610	cf
Infiltration BMP	Existing	7817 BENARES ST	6/14/2001		33.93931	-118.14525	246079	1760	sf	110	cf
Infiltration BMP	Existing	7813 BENARES ST	6/14/2001		33.93938	-118.14542	246079	1760	sf	110	cf
Infiltration BMP	Existing	7809 BENARES ST	6/14/2001		33.93945	-118.14557	246079	1760	sf	110	cf
Infiltration BMP	Existing	7805 BENARES ST	6/14/2001		33.93953	-118.14572	246079	1760	sf	110	cf
Infiltration BMP	Existing	7801 BENARES ST	6/14/2001		33.93961	-118.14587	246079	9600	sf	600	cf
Infiltration BMP	Existing	7140 FIRESTONE	10/3/2005		33.94707	-118.15469	246079	24048	sf	1503	cf
Infiltration BMP	Existing	8233 FIRESTONE	6/21/2010		33.94076	-118.13358	246102	91648	sf	5728	cf
Infiltration BMP	Existing	7814 FIRESTONE	2/14/2014		33.94418	-118.14232	246102	3000	sf	125	cf
Infiltration BMP	Existing	7676 FIRESTONE	2/26/2004		33.94527	-118.144	246102	213824	sf	13364	cf
Infiltration BMP	Existing	7201 FIRESTONE	4/19/2007		33.94821	-118.15273	246102	34352	sf	2147	cf
Infiltration BMP	Existing	7360 FLORENCE	6/21/2010		33.95872	-118.141	246102	14496	sf	906	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8129 FLORENCE	6/23/2010		33.95231	-118.12677	246103	8880	sf	555	cf
Infiltration BMP	Existing	8605 GALLATIN ROAD	2/14/2014		33.95768	-118.11432	246103	85792	sf	5362	cf
Infiltration BMP	Existing	9276 DOWNEY	1/4/2007		33.95901	-118.11926	246103	6400	sf	400	cf
Infiltration BMP	Existing	8801 LAKEWOOD	7/14/2006		33.96317	-118.11498	246106	18352	sf	1147	cf
Infiltration BMP	Existing	7880 TELEGRAPH	11/14/2004		33.97112	-118.12113	246111	123104	sf	7694	cf
Permeable Pavement	Existing	9449 IMPERIAL	6/22/2010		33.91809	-118.12656	245115	32160	sf	2010	cf
Permeable Pavement	Existing	9565 FIRESTONE	6/3/2008		33.93043	-118.11175	245119	18928	sf	1183	cf
Permeable Pavement	Existing	12628 PARAMOUNT	2/14/2014		33.92329	-118.15283	246077	15000	sf	284	cf
Permeable Pavement	Existing	11555 PARAMOUNT	2/14/2014		33.94116	-118.14067	246077	8125	sf	400	cf
Permeable Pavement	Existing	8043 SECOND ST	1/1/2009		33.94254	-118.13737	246102	105023	sf	6787	cf
Permeable Pavement	Existing	9250 LAKEWOOD	2/14/2014		33.95768	-118.1153	246103	24662	sf	939	cf
Regional Detention Facility	Existing	9341 IMPERIAL	5/6/2004		33.91918	-118.12898	245115	664624	sf	41539	cf
Regional Infiltration Facility	Existing	12074 LAKEWOOD	5/22/2005		33.9257	-118.13203	245115	960800	sf	60050	cf
Regional Infiltration Facility	Existing	12002 LAKEWOOD	5/22/2005		33.9261	-118.13169	245115	605264	sf	37829	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8764 FIRESTONE	8/14/2008	6523923.595890	6523923.595890	1798908.496460	245119	20064	sf	1254	cf
Infiltration BMP	Existing	9915 DOWNEY	9/27/2005	6523909.682530	6523909.682530	1805554.600030	246103	2265	sf	142	cf
Infiltration BMP	Existing	7602 RUNDELL	1/27/2006	6514863.657960	6514863.657960	1798182.489930	246079	2265	sf	142	cf
Infiltration BMP	Existing	10403 SAMOLINE	10/3/2005	6521224.982130	6521224.982130	1804890.047210	246102	2265	sf	142	cf
Infiltration BMP	Existing	12516 DOLAN	11/18/2005	6518146.741440	6518146.741440	1794105.551200	245115	1698	sf	106	cf
Infiltration BMP	Existing	7845 QUILL	3/28/2006	6515351.811960	6515351.811960	1796427.555720	246079	1698	sf	106	cf
Infiltration BMP	Existing	10435 BIRCHDALE	5/19/2005	6524444.362750	6524444.362750	1802478.415410	245119	1132	sf	71	cf
Infiltration BMP	Existing	8538 ALBIA	9/23/2005	6520089.101510	6520089.101510	1795567.094110	245115	566	sf	35	cf
Infiltration BMP	Existing	12159 CORNUTA	9/16/2005	6525392.928460	6525392.928460	1794233.560240	245114	566	sf	35	cf
Infiltration BMP	Existing	8064 DACOSTA	7/7/2005	6523365.354910	6523365.354910	1805913.806160	246103	566	sf	35	cf
Infiltration BMP	Existing	8551 DALEN	10/6/2005	6518205.327280	6518205.327280	1792517.271110	245115	566	sf	35	cf
Infiltration BMP	Existing	8318 DINSDALE	6/15/2006	6523907.628300	6523907.628300	1804895.972630	246103	566	sf	35	cf
Infiltration BMP	Existing	12641 DOLAN	9/2/2005	6517370.498610	6517370.498610	1793094.154440	245115	566	sf	35	cf
Infiltration BMP	Existing	12837 DOWNEY	6/13/2008	6516221.544620	6516221.544620	1792552.216840	246077	566	sf	35	cf
Infiltration BMP	Existing	12608 DUNROBIN	1/1/2007	6525044.715110	6525044.715110	1792041.222140	245114	566	sf	35	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7715 GAINFORD	5/9/2006	6521302.031220	6521302.031220	1807578.393730	246106	566	sf	35	cf
Infiltration BMP	Existing	12337 HORLEY	6/20/2007	6514828.837130	6514828.837130	1797233.894880	246079	566	sf	35	cf
Infiltration BMP	Existing	12619 IBBETSON	4/7/2008	6525826.717640	6525826.717640	1791950.694670	245114	566	sf	35	cf
Infiltration BMP	Existing	12142 MARBEL	5/5/2008	6521265.537710	6521265.537710	1794924.230550	245115	566	sf	35	cf
Infiltration BMP	Existing	12228 NORLAIN	6/24/2005	6513924.473210	6513924.473210	1798288.206130	246079	566	sf	35	cf
Infiltration BMP	Existing	11733 PATTON	12/9/2005	6521629.388810	6521629.388810	1797656.681610	245114	566	sf	35	cf
Infiltration BMP	Existing	11712 PRUESS	3/29/2006	6518005.349510	6518005.349510	1799785.098800	246077	566	sf	35	cf
Infiltration BMP	Existing	8605 SAMOLINE	10/23/2006	6525562.919850	6525562.919850	1810382.622670	246106	566	sf	35	cf
Infiltration BMP	Existing	7814 SPRINGER	7/20/2005	6515325.745000	6515325.745000	1796943.250000	246079	566	sf	35	cf
Infiltration BMP	Existing	7406 THIRD	9/23/2005	6517102.209740	6517102.209740	1803992.224080	246102	566	sf	35	cf
Infiltration BMP	Existing	8836 TWEEDY	8/21/2006	6524333.205540	6524333.205540	1809897.996880	246106	566	sf	35	cf
Infiltration BMP	Existing	9702 TWEEDY	8/30/2005	6522704.033740	6522704.033740	1807211.824630	246103	566	sf	35	cf
Infiltration BMP	Existing	11414 PARAMOUNT	11/17/2006	6519592.558830	6519592.558830	1800943.348310	245115	37135	sf	2321	cf
Infiltration BMP	Existing	8077 FLORENCE AV	1/1/2009	6523000.000000	6523000.000000	1805200.000000	246103	31872	sf	1992	cf
Infiltration BMP	Existing	8351 FLORENCE	11/29/2005	6524092.726100	6524092.726100	1804613.455750	246103	8252	sf	516	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	11003 LAKEWOOD	1/1/2006	6524400.000000	6524400.000000	1799800.000000	245119	8252	sf	516	cf
Infiltration BMP	Existing	9288 LUBEC	6/21/2010	6528705.843900	6528705.843900	1803218.787040	245125	8252	sf	516	cf
Infiltration BMP	Existing	13240 BARLIN	6/24/2005	6517118.017720	6517118.017720	1789361.126310	245524	6189	sf	387	cf
Infiltration BMP	Existing	9802 BROOKSHIRE	4/24/2007	6525737.765210	6525737.765210	1805415.750650	246103	6189	sf	387	cf
Infiltration BMP	Existing	9026 SUVA	10/5/2006	6527186.692380	6527186.692380	1804858.393970	245125	6189	sf	387	cf
Infiltration BMP	Existing	7325 IRWINGROVE	4/27/2005	6518419.969630	6518419.969630	1807291.337240	246102	5158	sf	322	cf
Infiltration BMP	Existing	10064 PANGBORN	8/16/2005	6529846.676910	6529846.676910	1801177.429270	245125	5158	sf	322	cf
Infiltration BMP	Existing	8102 THIRD	3/4/2009	6520617.238210	6520617.238210	1801805.039980	246103	7616	sf	476	cf
Infiltration BMP	Existing	12200 BELLFLOWER	11/4/2008	6524061.916580	6524061.916580	1794195.827920	245114	4126	sf	258	cf
Infiltration BMP	Existing	9818 BIRCHDALE	12/28/2005	6526194.448530	6526194.448530	1804634.814020	245125	4126	sf	258	cf
Infiltration BMP	Existing	10419 BROOKSHIRE	7/30/2007	6523842.460000	6523842.460000	1803179.994160	245119	4126	sf	258	cf
Infiltration BMP	Existing	10432 BROOKSHIRE	2/14/2007	6523911.001360	6523911.001360	1803018.354450	245119	4126	sf	258	cf
Infiltration BMP	Existing	10329 CASANES	1/1/2006	6528565.218740	6528565.218740	1800358.453120	245126	4126	sf	258	cf
Infiltration BMP	Existing	13221 CORRIGAN	3/9/2006	6523120.117490	6523120.117490	1789965.324450	245114	4126	sf	258	cf
Infiltration BMP	Existing	8816 ELSTON	12/28/2005	6526840.850650	6526840.850650	1808666.263650	246103	4126	sf	258	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9278 GAINFORD	6/15/2005	6528421.969980	6528421.969980	1803000.469050	245125	4126	sf	258	cf
Infiltration BMP	Existing	7340 IRWINGROVE	12/6/2005	6518415.507880	6518415.507880	1806990.616650	246102	4126	sf	258	cf
Infiltration BMP	Existing	9055 IRWINGROVE	10/17/2006	6526414.238800	6526414.238800	1802422.724820	245119	4126	sf	258	cf
Infiltration BMP	Existing	9005 KRISTIN	1/1/2006	6524171.005660	6524171.005660	1809376.398810	246106	4126	sf	258	cf
Infiltration BMP	Existing	9015 KRISTIN	1/1/2006	6524137.396040	6524137.396040	1809320.713720	246106	4126	sf	258	cf
Infiltration BMP	Existing	10014 LA REINA	11/3/2005	6523603.973220	6523603.973220	1805275.605180	246103	4126	sf	258	cf
Infiltration BMP	Existing	8334 LEXINGTON	3/20/2006	6523900.000000	6523900.000000	1804200.000000	246103	4126	sf	258	cf
Infiltration BMP	Existing	7114 LUXOR	7/27/2005	6513446.571340	6513446.571340	1802395.175860	246100	4126	sf	258	cf
Infiltration BMP	Existing	10348 PANGBORN	10/12/2006	6529020.867850	6529020.867850	1800144.106260	245126	4126	sf	258	cf
Infiltration BMP	Existing	7268 PELLET	12/8/2005	6516203.991240	6516203.991240	1804244.566160	246104	4126	sf	258	cf
Infiltration BMP	Existing	9821 RIVES	9/12/2005	6521261.613640	6521261.613640	1807221.725140	246106	4126	sf	258	cf
Infiltration BMP	Existing	10427 STAMPS	2/27/2006	6523141.588150	6523141.588150	1803526.008280	246103	4126	sf	258	cf
Infiltration BMP	Existing	8325 TEXAS	8/30/2007	6520789.744350	6520789.744350	1799109.948610	245114	4126	sf	258	cf
Infiltration BMP	Existing	9211 ARRINGTON	6/21/2010	6527822.609270	6527822.609270	1805896.813180	245125	3095	sf	193	cf
Infiltration BMP	Existing	10372 BIRCHDALE	1/17/2006	6524786.108330	6524786.108330	1802711.833690	245119	2660	sf	166	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9509 BROCK	10/6/2005	6524084.133490	6524084.133490	1807438.122200	246103	3095	sf	193	cf
Infiltration BMP	Existing	9600 CORD	5/12/2008	6529842.639410	6529842.639410	1803668.379590	245125	3095	sf	193	cf
Infiltration BMP	Existing	10943 CORD	3/13/2007	6526539.555830	6526539.555830	1798046.595190	245119	3095	sf	193	cf
Infiltration BMP	Existing	12569 DOLAN	9/27/2006	6517675.526540	6517675.526540	1793796.546690	245115	3095	sf	193	cf
Infiltration BMP	Existing	9252A ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	3095	sf	193	cf
Infiltration BMP	Existing	9252B ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	3095	sf	193	cf
Infiltration BMP	Existing	9258A ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	3095	sf	193	cf
Infiltration BMP	Existing	9258B ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	3095	sf	193	cf
Infiltration BMP	Existing	9258C ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	3095	sf	193	cf
Infiltration BMP	Existing	9622 HALEDON	3/16/2006	6528283.868130	6528283.868130	1804260.791520	245125	3095	sf	193	cf
Infiltration BMP	Existing	11442 JULIUS	7/26/2007	6517126.240320	6517126.240320	1802109.297720	246079	3095	sf	193	cf
Infiltration BMP	Existing	10026 MATTOCK	1/1/2006	6530326.462180	6530326.462180	1801330.602850	245125	3095	sf	193	cf
Infiltration BMP	Existing	9303 PARAMOUNT	3/14/2006	6523934.101920	6523934.101920	1808355.150660	246106	3095	sf	193	cf
Infiltration BMP	Existing	8739 PARKCLIFF	1/23/2006	6516653.896010	6516653.896010	1788072.265990	245524	2063	sf	129	cf
Infiltration BMP	Existing	9303 PARROT	1/4/2007	6524270.384450	6524270.384450	1808221.036420	246106	3095	sf	193	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7313 PELLET	6/22/2010	6516478.702600	6516478.702600	1804386.841100	246104	3095	sf	193	cf
Infiltration BMP	Existing	10473 PICO VISTA	1/21/2009	6529579.260180	6529579.260180	1798825.132300	245126	3095	sf	193	cf
Infiltration BMP	Existing	7840 THIRD	8/29/2007	6519254.945150	6519254.945150	1802616.251380	246102	3095	sf	193	cf
Infiltration BMP	Existing	8347 VISTA DEL ROSA	7/26/2007	6527061.884710	6527061.884710	1808864.927170	246106	3095	sf	193	cf
Infiltration BMP	Existing	11632 ADENMOOR	6/15/2005	6524141.212380	6524141.212380	1797138.142940	245114	2063	sf	129	cf
Infiltration BMP	Existing	7124 ADWEN	12/20/2007	6513937.816490	6513937.816490	1803059.644840	246100	2063	sf	129	cf
Infiltration BMP	Existing	7258 ADWEN	1/3/2008	6515068.905460	6515068.905460	1802384.347520	246079	2063	sf	129	cf
Infiltration BMP	Existing	7646 ADWEN	10/6/2005	6517037.957040	6517037.957040	1801170.785850	246079	2063	sf	129	cf
Infiltration BMP	Existing	7702 ADWEN	5/11/2006	6517121.727310	6517121.727310	1801116.179360	246079	2063	sf	129	cf
Infiltration BMP	Existing	13032 AIRPOINT	5/14/2007	6517972.459000	6517972.459000	1790335.341940	245115	2063	sf	129	cf
Infiltration BMP	Existing	8455 ALAMEDA	8/7/2008	6519558.018350	6519558.018350	1795721.453060	245115	2063	sf	129	cf
Infiltration BMP	Existing	8632 ALAMEDA	11/2/2006	6520500.318510	6520500.318510	1795019.322380	245115	2063	sf	129	cf
Infiltration BMP	Existing	7945 ALBIA	10/11/2005	6516993.544600	6516993.544600	1797608.073070	246079	2063	sf	129	cf
Infiltration BMP	Existing	8704 ALBIA	5/28/2008	6520928.243910	6520928.243910	1795073.644330	245115	2063	sf	129	cf
Infiltration BMP	Existing	7845 ARNETT	6/18/2010	6518353.322440	6518353.322440	1801165.354440	246079	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9217 ARRINGTON	3/27/2006	6527795.727670	6527795.727670	1805838.303240	245125	2063	sf	129	cf
Infiltration BMP	Existing	7870 BAYSINGER	2/8/2008	6521311.922790	6521311.922790	1805484.679070	246102	2063	sf	129	cf
Infiltration BMP	Existing	9964 BELCHER	5/16/2007	6525622.979960	6525622.979960	1789815.793090	245113	2063	sf	129	cf
Infiltration BMP	Existing	12556 BELDER	8/17/2007	6518567.857140	6518567.857140	1793310.793680	245115	2063	sf	129	cf
Infiltration BMP	Existing	11614 BELLFLOWER	11/7/2008	6523771.271210	6523771.271210	1797348.312220	245114	2063	sf	129	cf
Infiltration BMP	Existing	11802 BELLMAN	3/9/2007	6521898.080850	6521898.080850	1797268.375540	245114	2063	sf	129	cf
Infiltration BMP	Existing	7502 BENARES	1/30/2009	6515952.395710	6515952.395710	1801162.932420	246079	2063	sf	129	cf
Infiltration BMP	Existing	7824 BORSON	5/24/2007	6514090.231790	6514090.231790	1794571.039330	246077	2063	sf	129	cf
Infiltration BMP	Existing	7442 BROOKMILL	2/6/2006	6515991.568850	6515991.568850	1801492.813950	246079	2063	sf	129	cf
Infiltration BMP	Existing	9202 BUELL	7/21/2008	6526325.599230	6526325.599230	1799668.061170	245119	2063	sf	129	cf
Infiltration BMP	Existing	9340 BUELL	8/9/2006	6527287.659290	6527287.659290	1799162.594770	245126	2063	sf	129	cf
Infiltration BMP	Existing	8707 BYERS	3/15/2006	6521183.641890	6521183.641890	1796053.567730	245115	2063	sf	129	cf
Infiltration BMP	Existing	10446 CASANES	10/26/2006	6528470.793910	6528470.793910	1799828.787480	245126	2063	sf	129	cf
Infiltration BMP	Existing	10932 CASANES	11/17/2005	6527225.467210	6527225.467210	1797760.272650	245119	2063	sf	129	cf
Infiltration BMP	Existing	13341 CASTANA	10/28/2005	6517576.502130	6517576.502130	1788949.477410	245524	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7408 CECILIA	10/27/2005	6517829.130300	6517829.130300	1804625.827460	246102	2063	sf	129	cf
Infiltration BMP	Existing	7604 CECILIA	5/14/2007	6518455.494160	6518455.494160	1804215.794590	246102	2063	sf	129	cf
Infiltration BMP	Existing	9116 CHANEY	12/19/2005	6529189.877980	6529189.877980	1805493.817150	245125	2063	sf	129	cf
Infiltration BMP	Existing	8210 CHEYENNE	3/18/2008	6515440.785260	6515440.785260	1792057.306890	246077	2063	sf	129	cf
Infiltration BMP	Existing	9663 CLANCEY	8/17/2005	6527712.819630	6527712.819630	1804149.908320	245125	2063	sf	129	cf
Infiltration BMP	Existing	10708 CLANCEY	12/9/2005	6525546.299290	6525546.299290	1800088.746900	245119	2063	sf	129	cf
Infiltration BMP	Existing	8336 CLETA	5/8/2006	6520552.025180	6520552.025180	1798452.238760	245114	2063	sf	129	cf
Infiltration BMP	Existing	8557 CLETA	7/24/2006	6521804.225790	6521804.225790	1798033.515210	245114	2063	sf	129	cf
Infiltration BMP	Existing	8532 COLE	11/7/2005	6521000.000000	6521000.000000	1796400.000000	245115	2063	sf	129	cf
Infiltration BMP	Existing	9003 CORD	6/23/2010	6530731.156250	6530731.156250	1805583.409840	245127	2063	sf	129	cf
Infiltration BMP	Existing	9203 CORD	11/14/2008	6530209.591170	6530209.591170	1804419.169900	245125	2063	sf	129	cf
Infiltration BMP	Existing	13029 CORNUTA	5/17/2007	6525511.407030	6525511.407030	1790564.440990	245113	2063	sf	129	cf
Infiltration BMP	Existing	13102 CORNUTA	8/2/2007	6525701.503660	6525701.503660	1790504.914950	245113	2063	sf	129	cf
Infiltration BMP	Existing	13130 CORNUTA	6/25/2007	6525701.486250	6525701.486250	1790230.251310	245113	2063	sf	129	cf
Infiltration BMP	Existing	9245 DALEWOOD	9/23/2005	6532196.615620	6532196.615620	1804345.945760	245127	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	13440 DEMPSTER	10/26/2006	6516234.168650	6516234.168650	1789111.153470	245524	2063	sf	129	cf
Infiltration BMP	Existing	13448 DEMPSTER	5/10/2007	6516184.596670	6516184.596670	1789023.378330	245524	2063	sf	129	cf
Infiltration BMP	Existing	8125 DINSDALE	12/20/2005	6523223.693140	6523223.693140	1805447.514320	246103	2063	sf	129	cf
Infiltration BMP	Existing	10343 DOLAN	3/7/2007	6523688.489440	6523688.489440	1803733.392340	246103	2063	sf	129	cf
Infiltration BMP	Existing	10616 DOLAN	12/8/2005	6523091.688370	6523091.688370	1802186.196180	246103	2063	sf	129	cf
Infiltration BMP	Existing	8451 DONOVAN	10/20/2006	6518824.326830	6518824.326830	1794831.678890	245115	2063	sf	129	cf
Infiltration BMP	Existing	11915 DOWNEY	9/26/2007	6519404.158310	6519404.158310	1797577.606330	245115	2063	sf	129	cf
Infiltration BMP	Existing	12269 DOWNEY	3/16/2006	6518129.427940	6518129.427940	1795616.200900	246077	2063	sf	129	cf
Infiltration BMP	Existing	12631 DUNROBIN	1/14/2009	6524865.692630	6524865.692630	1791809.740080	245114	2063	sf	129	cf
Infiltration BMP	Existing	12644 DUNROBIN	12/27/2006	6525045.107610	6525045.107610	1791670.201830	245114	2063	sf	129	cf
Infiltration BMP	Existing	13212 DUNROBIN	3/6/2008	6525046.199690	6525046.199690	1790094.955960	245114	2063	sf	129	cf
Infiltration BMP	Existing	9018 EGLISE	6/18/2010	6530595.364130	6530595.364130	1805560.296250	245127	2063	sf	129	cf
Infiltration BMP	Existing	9252C ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9252D ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9252E ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9254A ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9254B ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9254C ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9254D ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9254E ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9258D ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9258E ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9260E ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9260A ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9260B ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9260C ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9260D ELM VISTA	4/5/2006	6524400.000000	6524400.000000	1795600.000000	245114	2063	sf	129	cf
Infiltration BMP	Existing	8902 ELSTON	6/22/2010	6526760.905110	6526760.905110	1808606.155990	246103	2063	sf	129	cf
Infiltration BMP	Existing	8420 EUCALYPTUS	11/1/2007	6518268.185230	6518268.185230	1794519.531140	245115	2063	sf	129	cf
Infiltration BMP	Existing	8543 FARM	7/14/2008	6524366.648200	6524366.648200	1802748.102990	245119	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7963 FIFTH	4/13/2007	6520492.297340	6520492.297340	1803181.748460	246103	2063	sf	129	cf
Infiltration BMP	Existing	7606 FINEVALE	7/23/2007	6522317.087820	6522317.087820	1809781.757910	246111	2063	sf	129	cf
Infiltration BMP	Existing	8740 FIRESTONE	2/5/2008	6523707.154590	6523707.154590	1799037.579000	245119	2063	sf	129	cf
Infiltration BMP	Existing	8663 FONTANA	8/11/2005	6522041.808010	6522041.808010	1796935.622550	245114	2063	sf	129	cf
Infiltration BMP	Existing	7435 FOSTORIA	8/30/2005	6517713.795360	6517713.795360	1804555.032870	246102	2063	sf	129	cf
Infiltration BMP	Existing	7611 FOSTORIA	7/5/2007	6518456.715640	6518456.715640	1804071.041810	246102	2063	sf	129	cf
Infiltration BMP	Existing	8029 FOURTH	6/15/2006	6520786.200710	6520786.200710	1802533.409070	246103	2063	sf	129	cf
Infiltration BMP	Existing	8524 GAINFORD	6/27/2008	6525485.453790	6525485.453790	1804820.431910	245125	2063	sf	129	cf
Infiltration BMP	Existing	9332 GAINFORD	7/20/2006	6528750.550820	6528750.550820	1802746.272930	245125	2063	sf	129	cf
Infiltration BMP	Existing	9330 GALLATIN	8/2/2007	6529116.628720	6529116.628720	1804180.197000	245125	2063	sf	129	cf
Infiltration BMP	Existing	12271 GLYNN	10/18/2005	6518435.603700	6518435.603700	1795389.616520	245115	2063	sf	129	cf
Infiltration BMP	Existing	9123 HALEDON	1/23/2006	6528738.408770	6528738.408770	1805747.051990	245125	2063	sf	129	cf
Infiltration BMP	Existing	7915 HARPER	2/7/2006	6520609.146350	6520609.146350	1804298.454990	246102	2063	sf	129	cf
Infiltration BMP	Existing	9108 HASTY	8/23/2006	6531133.870830	6531133.870830	1805211.202040	245127	2063	sf	129	cf
Infiltration BMP	Existing	10840 HASTY	1/16/2008	6527245.272860	6527245.272860	1798387.513250	245119	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7468 HONDO	12/31/2008	6513888.485770	6513888.485770	1797503.008930	246079	2063	sf	129	cf
Infiltration BMP	Existing	7838 HONDO	2/26/2008	6515366.533450	6515366.533450	1796561.911100	246079	2063	sf	129	cf
Infiltration BMP	Existing	7926 HONDO	7/25/2006	6515828.269550	6515828.269550	1796282.236280	246079	2063	sf	129	cf
Infiltration BMP	Existing	12023 HORTON	10/5/2005	6515547.066470	6515547.066470	1799512.855270	246079	1032	sf	64	cf
Infiltration BMP	Existing	10234 JULIUS	11/5/2009	6519723.348540	6519723.348540	1806551.787860	246102	2063	sf	129	cf
Infiltration BMP	Existing	11828 JULIUS	1/3/2008	6515976.382140	6515976.382140	1800524.752810	246079	2063	sf	129	cf
Infiltration BMP	Existing	9256 KLINEDALE	12/4/2007	6531745.367500	6531745.367500	1804500.031620	245127	2063	sf	129	cf
Infiltration BMP	Existing	9452 KLINEDALE	4/24/2008	6531257.497660	6531257.497660	1803653.019950	245127	2063	sf	129	cf
Infiltration BMP	Existing	9031 LEMORAN	1/30/2009	6529792.995960	6529792.995960	1806045.812140	245125	2063	sf	129	cf
Infiltration BMP	Existing	9910 LESTERFORD	8/3/2005	6531140.582200	6531140.582200	1801442.142180	245125	2063	sf	129	cf
Infiltration BMP	Existing	8533 LOWMAN	1/3/2008	6525796.079270	6525796.079270	1810845.309540	246106	2063	sf	129	cf
Infiltration BMP	Existing	8349 LUBEC	12/27/2006	6524776.248350	6524776.248350	1805794.753990	246103	2063	sf	129	cf
Infiltration BMP	Existing	7630 LUXOR	6/27/2005	6516552.896900	6516552.896900	1800452.817120	246079	2063	sf	129	cf
Infiltration BMP	Existing	12342 MARBEL	3/23/2006	6520586.635090	6520586.635090	1793799.804370	245115	2063	sf	129	cf
Infiltration BMP	Existing	9045 MARGARET ST	1/1/2006	6524143.176440	6524143.176440	1798109.987740	245114	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	10410 MATTOCK	10/2/2007	6529164.649420	6529164.649420	1799820.803610	245126	2063	sf	129	cf
Infiltration BMP	Existing	10615 MATTOCK	2/22/2006	6528479.681880	6528479.681880	1798952.207590	245126	2063	sf	129	cf
Infiltration BMP	Existing	9136 MELDAR	3/1/2007	6526738.891530	6526738.891530	1807241.651780	246103	2063	sf	129	cf
Infiltration BMP	Existing	7437 MULLER	10/3/2005	6518230.115820	6518230.115820	1805283.479580	246102	1032	sf	64	cf
Infiltration BMP	Existing	7452 MULLER	10/3/2005	6518271.461030	6518271.461030	1805049.518080	246102	2063	sf	129	cf
Infiltration BMP	Existing	10715 NEW	8/9/2007	6521988.945450	6521988.945450	1802370.638520	246103	2063	sf	129	cf
Infiltration BMP	Existing	10715 NEW	7/14/2008	6521988.945450	6521988.945450	1802370.638520	246103	2063	sf	129	cf
Infiltration BMP	Existing	10261 NEWVILLE	10/30/2007	6529641.666020	6529641.666020	1800383.942770	245126	2063	sf	129	cf
Infiltration BMP	Existing	10311 NEWVILLE	1/29/2009	6529538.574620	6529538.574620	1800214.882210	245126	2063	sf	129	cf
Infiltration BMP	Existing	10420 NEWVILLE	4/11/2008	6529346.061190	6529346.061190	1799529.176420	245126	2063	sf	129	cf
Infiltration BMP	Existing	10524 NEWVILLE	6/11/2007	6529062.272820	6529062.272820	1798916.257500	245126	2063	sf	129	cf
Infiltration BMP	Existing	9842 NORLAIN	3/9/2007	6519878.070320	6519878.070320	1807987.575840	246111	2063	sf	129	cf
Infiltration BMP	Existing	10403 PANGBORN	9/16/2005	6528806.561730	6528806.561730	1800136.574080	245126	2063	sf	129	cf
Infiltration BMP	Existing	10421 PANGBORN	6/5/2006	6528710.057740	6528710.057740	1799977.600600	245126	2063	sf	129	cf
Infiltration BMP	Existing	10903 PANGBORN	5/12/2008	6527497.056040	6527497.056040	1797964.159830	245119	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9508 PARAMOUNT	7/23/2007	6523724.334180	6523724.33 4180	1807653.5183 30	246106	2063	sf	129	cf
Infiltration BMP	Existing	9709 PARROT	6/20/2008	6523336.123150	6523336.12 3150	1806770.8311 50	246103	2063	sf	129	cf
Infiltration BMP	Existing	7107 PELLET	10/26/2005	6515228.221140	6515228.22 1140	1805197.0907 30	246104	2063	sf	129	cf
Infiltration BMP	Existing	10316 PICO VISTA	6/22/2010	6530326.941520	6530326.94 1520	1799752.7394 80	245126	2063	sf	129	cf
Infiltration BMP	Existing	10459 PICO VISTA	8/20/2008	6529643.308750	6529643.30 8750	1798930.2911 80	245126	2063	sf	129	cf
Infiltration BMP	Existing	11809 POMERING	1/25/2008	6515588.727520	6515588.72 7520	1800891.8510 40	246079	2063	sf	129	cf
Infiltration BMP	Existing	11821 POMERING	11/20/2008	6515535.205010	6515535.20 5010	1800794.0724 00	246079	2063	sf	129	cf
Infiltration BMP	Existing	9050 PRISCILLA	2/21/2007	6519218.937330	6519218.93 7330	1790014.5325 10	245115	2063	sf	129	cf
Infiltration BMP	Existing	8230 PURITAN	7/12/2007	6515756.650110	6515756.65 0110	1792196.3887 50	246077	2063	sf	129	cf
Infiltration BMP	Existing	8107 RAVILLER	6/22/2010	6524405.759790	6524405.75 9790	1808219.1108 40	246106	2063	sf	129	cf
Infiltration BMP	Existing	9940 RICHEON	12/26/2007	6520640.158150	6520640.15 8150	1807053.5976 90	246106	2063	sf	129	cf
Infiltration BMP	Existing	12015 RICHEON	6/21/2010	6515852.443580	6515852.44 3580	1799404.2568 70	246079	2063	sf	129	cf
Infiltration BMP	Existing	7336 RIO HONDO PL	12/26/2007	6516915.991390	6516915.99 1390	1804928.3342 60	246104	2063	sf	129	cf
Infiltration BMP	Existing	8418 RIVES	9/30/2005	6525367.917230	6525367.91 7230	1811575.8634 60	246106	1032	sf	64	cf
Infiltration BMP	Existing	11638 RIVES	11/2/2006	6517541.202300	6517541.20 2300	1800577.7411 60	246079	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	11706 RIVES	10/16/2006	6517702.333530	6517702.333530	1800238.435400	246079	2063	sf	129	cf
Infiltration BMP	Existing	12436 ROSE	11/6/2006	6520776.455000	6520776.455000	1793075.765000	245115	2063	sf	129	cf
Infiltration BMP	Existing	12033 SAMOLINE	2/22/2008	6517025.771360	6517025.771360	1798249.691900	246079	2063	sf	129	cf
Infiltration BMP	Existing	12051 SAMOLINE	9/3/2008	6516919.542440	6516919.542440	1798077.846870	246079	2063	sf	129	cf
Infiltration BMP	Existing	12302 SAMOLINE	6/22/2010	6516399.204110	6516399.204110	1796321.463670	246077	2063	sf	129	cf
Infiltration BMP	Existing	7921 SECOND	2/15/2006	6519427.915180	6519427.915180	1802349.970040	246102	2063	sf	129	cf
Infiltration BMP	Existing	9700 SHELLEYFIELD	7/17/2008	6527622.312900	6527622.312900	1804250.399390	245125	2063	sf	129	cf
Infiltration BMP	Existing	10553 SHELLEYFIELD	6/11/2008	6525493.222190	6525493.222190	1800845.190450	245119	2063	sf	129	cf
Infiltration BMP	Existing	8732 SMALLWOOD	2/16/2006	6524307.398160	6524307.398160	1810444.440300	246106	2063	sf	129	cf
Infiltration BMP	Existing	8816 SMALLWOOD	10/11/2005	6524123.348010	6524123.348010	1810138.117570	246106	2063	sf	129	cf
Infiltration BMP	Existing	9127 SONGFEST	12/1/2005	6531508.595900	6531508.595900	1805094.820630	245127	2063	sf	129	cf
Infiltration BMP	Existing	9143 STEWART & GRAY	11/30/2005	6523803.019500	6523803.019500	1796254.085000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9211 STEWART & GRAY	11/27/2006	6524190.537790	6524190.537790	1796254.765000	245114	2063	sf	129	cf
Infiltration BMP	Existing	9112 STOAKES	8/23/2006	6526782.391540	6526782.391540	1807626.036510	246103	2063	sf	129	cf
Infiltration BMP	Existing	9533 SUVA	6/27/2006	6530409.847860	6530409.847860	1802701.771860	245125	2063	sf	129	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9729 TRISTAN	10/18/2005	6526617.474570	6526617.47 4570	1804798.2838 70	245125	2063	sf	129	cf
Infiltration BMP	Existing	9216 TWEEDY	12/9/2005	6523630.155980	6523630.15 5980	1808715.3974 90	246106	2063	sf	129	cf
Infiltration BMP	Existing	13602 VERDURA	6/28/2007	6516296.473820	6516296.47 3820	1788728.2351 50	245524	2063	sf	129	cf
Infiltration BMP	Existing	10305 VULTEE	10/9/2006	6525949.622700	6525949.62 2700	1802510.2507 80	245119	2063	sf	129	cf
Infiltration BMP	Existing	10017 WILEY BURKE	6/22/2010	6520091.056520	6520091.05 6520	1807145.8681 60	246106	2063	sf	129	cf
Infiltration BMP	Existing	8538 ADOREE	9/26/2007	6517768.216360	6517768.21 6360	1792006.5034 70	245115	1032	sf	64	cf
Infiltration BMP	Existing	9407 ADOREE	1/1/2006	6522413.313750	6522413.31 3750	1791106.0174 30	245115	1032	sf	64	cf
Infiltration BMP	Existing	7134 ADWEN	1/1/2005	6514021.670500	6514021.67 0500	1803005.1648 70	246100	1032	sf	64	cf
Infiltration BMP	Existing	7343 ADWEN	9/4/2007	6515521.914470	6515521.91 4470	1802266.8582 80	246079	1032	sf	64	cf
Infiltration BMP	Existing	7743 ADWEN	12/5/2006	6517543.195590	6517543.19 5590	1801041.5615 20	246079	1032	sf	64	cf
Infiltration BMP	Existing	7802 ADWEN	10/18/2005	6517699.212930	6517699.21 2930	1800872.2809 90	246079	1032	sf	64	cf
Infiltration BMP	Existing	7828 ADWEN	8/4/2005	6517918.117250	6517918.11 7250	1800738.5119 70	246079	1032	sf	64	cf
Infiltration BMP	Existing	7852 ADWEN	1/9/2009	6518131.432520	6518131.43 2520	1800607.9745 20	246079	1032	sf	64	cf
Infiltration BMP	Existing	7855 ADWEN	11/23/2005	6518235.708380	6518235.70 8380	1800774.9630 10	246079	1032	sf	64	cf
Infiltration BMP	Existing	12823 AIRPOINT	6/29/2007	6518348.749200	6518348.74 9200	1791281.4301 70	245115	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8441 ALAMEDA	10/31/2005	6519442.769190	6519442.769190	1795780.926380	245115	1032	sf	64	cf
Infiltration BMP	Existing	8549 ALAMEDA	6/23/2010	6520129.148230	6520129.148230	1795426.542360	245115	1032	sf	64	cf
Infiltration BMP	Existing	8448 ALBIA	1/1/2007	6519556.734390	6519556.734390	1795840.452920	245115	1032	sf	64	cf
Infiltration BMP	Existing	8528 ALBIA	2/27/2007	6520000.245000	6520000.245000	1795612.955000	245115	1032	sf	64	cf
Infiltration BMP	Existing	9718 ALIWIN	8/2/2005	6532030.038780	6532030.038780	1804115.104340	245127	1032	sf	64	cf
Infiltration BMP	Existing	7936 ALLENGROVE	1/22/2007	6524421.678930	6524421.678930	1809567.173140	246106	1032	sf	64	cf
Infiltration BMP	Existing	8116 ALLENGROVE	12/5/2005	6525137.825210	6525137.825210	1808747.451430	246106	1032	sf	64	cf
Infiltration BMP	Existing	9166 ANGELL	9/2/2008	6520625.089300	6520625.089300	1790394.866750	245115	1032	sf	64	cf
Infiltration BMP	Existing	9351 APPLEBY	1/3/2008	6529580.566170	6529580.566170	1804445.997380	245125	1032	sf	64	cf
Infiltration BMP	Existing	9520 ARDINE	10/6/2005	6527613.323800	6527613.323800	1797533.903060	245119	1032	sf	64	cf
Infiltration BMP	Existing	7814 ARNETT	6/22/2010	6517981.553910	6517981.553910	1801095.347060	246079	1032	sf	64	cf
Infiltration BMP	Existing	7815 ARNETT	6/22/2010	6518066.490340	6518066.490340	1801237.713920	246079	1032	sf	64	cf
Infiltration BMP	Existing	7832 ARNETT	1/11/2007	6518132.684800	6518132.684800	1801021.243050	246079	1032	sf	64	cf
Infiltration BMP	Existing	8241 ARNETT	11/29/2006	6520442.071210	6520442.071210	1799867.842140	245115	1032	sf	64	cf
Infiltration BMP	Existing	7743 BAIRNSDALE	5/16/2006	6523474.546480	6523474.546480	1810551.323320	246106	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	12904 BARLIN	1/15/2009	6518150.890370	6518150.890370	1791163.941140	245115	1032	sf	64	cf
Infiltration BMP	Existing	13247 BARLIN	5/5/2005	6516868.829160	6516868.829160	1789428.146200	245524	1032	sf	64	cf
Infiltration BMP	Existing	7871 BAYSINGER	1/10/2007	6521422.493960	6521422.493960	1805635.813480	246102	1032	sf	64	cf
Infiltration BMP	Existing	8607 BAYSINGER	1/1/2005	6525304.240800	6525304.240800	1803291.716200	245119	1032	sf	64	cf
Infiltration BMP	Existing	9131 BAYSINGER	9/10/2008	6526918.982970	6526918.982970	1802474.767100	245119	1032	sf	64	cf
Infiltration BMP	Existing	9411 BAYSINGER	9/24/2007	6528736.042510	6528736.042510	1801262.782730	245126	1032	sf	64	cf
Infiltration BMP	Existing	9320 BELCHER	4/10/2007	6520600.361450	6520600.361450	1789754.109890	245115	1032	sf	64	cf
Infiltration BMP	Existing	9969 BELCHER	7/29/2009	6525669.288070	6525669.288070	1789992.480470	245113	1032	sf	64	cf
Infiltration BMP	Existing	10375 BELDER	6/22/2010	6522812.240000	6522812.240000	1803043.757460	246103	1032	sf	64	cf
Infiltration BMP	Existing	7441 BENARES	10/25/2005	6515921.019300	6515921.019300	1801396.174500	246079	1032	sf	64	cf
Infiltration BMP	Existing	7503 BENARES	1/16/2008	6516046.045620	6516046.045620	1801313.189720	246079	1032	sf	64	cf
Infiltration BMP	Existing	11014 BENFIELD	12/19/2005	6531918.630750	6531918.630750	1797937.959120	245122	1032	sf	64	cf
Infiltration BMP	Existing	8555 BIGBY	8/22/2005	6524606.668030	6524606.668030	1802914.545010	245119	1032	sf	64	cf
Infiltration BMP	Existing	9308 BIGBY	12/18/2008	6527591.908660	6527591.908660	1800839.109380	245126	1032	sf	64	cf
Infiltration BMP	Existing	9345 BIGBY	5/16/2006	6527999.312020	6527999.312020	1800803.102000	245126	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9389 BIGBY	9/20/2007	6528361.925530	6528361.925530	1800582.426270	245126	1032	sf	64	cf
Infiltration BMP	Existing	8246 BIRCHCREST	11/28/2005	6526713.325530	6526713.325530	1809350.628180	246106	1032	sf	64	cf
Infiltration BMP	Existing	10434 BIRCHDALE	12/2/2008	6524586.579650	6524586.579650	1802390.820140	245119	1032	sf	64	cf
Infiltration BMP	Existing	8812 BIRCHLEAF	5/3/2007	6527457.897210	6527457.897210	1808468.377860	246103	1032	sf	64	cf
Infiltration BMP	Existing	8912 BIRCHLEAF	10/9/2007	6527209.329660	6527209.329660	1808281.543500	246103	1032	sf	64	cf
Infiltration BMP	Existing	13330 BIXLER	3/21/2007	6516259.886220	6516259.886220	1789972.109000	245524	1032	sf	64	cf
Infiltration BMP	Existing	13411 BIXLER	9/30/2008	6515914.285010	6515914.285010	1789635.314360	245524	1032	sf	64	cf
Infiltration BMP	Existing	13425 BIXLER	8/17/2005	6515841.147610	6515841.147610	1789505.869380	245524	1032	sf	64	cf
Infiltration BMP	Existing	13454 BIXLER	5/10/2007	6515808.905200	6515808.905200	1789174.120800	245524	1032	sf	64	cf
Infiltration BMP	Existing	8220 BLANDWOOD	6/22/2010	6526086.691350	6526086.691350	1808873.058080	246103	1032	sf	64	cf
Infiltration BMP	Existing	12809 BLODGETT	1/1/2006	6518629.647540	6518629.647540	1791208.759970	245115	1032	sf	64	cf
Infiltration BMP	Existing	13026 BLODGETT	1/1/2005	6518225.401930	6518225.401930	1790248.943990	245115	1032	sf	64	cf
Infiltration BMP	Existing	13045 BLODGETT	10/6/2005	6517990.284020	6517990.284020	1790176.483690	245115	1032	sf	64	cf
Infiltration BMP	Existing	13114 BLODGETT	10/6/2005	6517888.613290	6517888.613290	1789931.616790	245115	1032	sf	64	cf
Infiltration BMP	Existing	7931 BORSON	9/6/2006	6514752.824370	6514752.824370	1794266.718830	246077	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8202 BORSON	6/5/2006	6516202.097710	6516202.097710	1793267.543860	246077	1032	sf	64	cf
Infiltration BMP	Existing	8428 BORSON	11/21/2008	6517449.915190	6517449.915190	1792528.167220	245115	1032	sf	64	cf
Infiltration BMP	Existing	8515 BORSON	3/14/2005	6517771.929480	6517771.929480	1792500.505870	245115	1032	sf	64	cf
Infiltration BMP	Existing	8345 BOYNE	6/18/2010	6519344.143470	6519344.143470	1796446.421390	245115	1032	sf	64	cf
Infiltration BMP	Existing	8402 BOYNE	1/1/2005	6519302.113240	6519302.113240	1796279.573520	245115	1032	sf	64	cf
Infiltration BMP	Existing	8525 BOYNE	7/20/2006	6520189.715440	6520189.715440	1796009.699660	245115	1032	sf	64	cf
Infiltration BMP	Existing	8528 BOYNE	2/22/2007	6520138.661540	6520138.661540	1795848.718800	245115	1032	sf	64	cf
Infiltration BMP	Existing	8613 BOYSON	1/1/2006	6520167.899980	6520167.899980	1794794.451220	245115	1032	sf	64	cf
Infiltration BMP	Existing	8647 BOYSON	7/29/2008	6520447.155570	6520447.155570	1794619.557270	245115	1032	sf	64	cf
Infiltration BMP	Existing	10216 BRANSCOMB	2/21/2007	6526794.108720	6526794.108720	1790310.156040	245113	1032	sf	64	cf
Infiltration BMP	Existing	10291 BRANSCOMB	7/25/2006	6527529.378260	6527529.378260	1790458.207730	245118	1032	sf	64	cf
Infiltration BMP	Existing	9624 BROCK	4/22/2005	6523849.153810	6523849.153810	1806723.688440	246103	1032	sf	64	cf
Infiltration BMP	Existing	12351 BROCK	9/3/2008	6516676.858850	6516676.858850	1795612.256100	246077	1032	sf	64	cf
Infiltration BMP	Existing	12608 BROCK	2/11/2005	6516008.590090	6516008.590090	1794308.259250	246077	1032	sf	64	cf
Infiltration BMP	Existing	8269 BROOKGREEN	1/1/2006	6526709.836510	6526709.836510	1808858.860970	246103	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7847 BROOKMILL	6/21/2010	6518005.266020	6518005.266020	1800484.266850	246079	1032	sf	64	cf
Infiltration BMP	Existing	8025 BROOKPARK	1/1/2005	6525207.617130	6525207.617130	1809814.105880	246106	1032	sf	64	cf
Infiltration BMP	Existing	9707 BROOKSHIRE	3/14/2005	6525762.512240	6525762.512240	1805795.982660	246103	1032	sf	64	cf
Infiltration BMP	Existing	10429 BROOKSHIRE	1/19/2005	6523911.001360	6523911.001360	1803018.354450	245119	1032	sf	64	cf
Infiltration BMP	Existing	12404 BROOKSHIRE	6/25/2007	6518808.785660	6518808.785660	1794169.944640	245115	1032	sf	64	cf
Infiltration BMP	Existing	7622 BRUNACHE	10/31/2007	6515665.309920	6515665.309920	1799097.073030	246079	1032	sf	64	cf
Infiltration BMP	Existing	8216 BRUNACHE	11/6/2007	6518414.904440	6518414.904440	1797242.748270	245115	1032	sf	64	cf
Infiltration BMP	Existing	9033 BUCKLES	6/21/2010	6523179.898540	6523179.898540	1796909.863810	245114	1032	sf	64	cf
Infiltration BMP	Existing	7540 BUELL	1/1/2004	6518499.698980	6518499.698980	1804545.470300	246102	1032	sf	64	cf
Infiltration BMP	Existing	9330 BUELL	2/15/2006	6527195.126160	6527195.126160	1799219.087810	245126	1032	sf	64	cf
Infiltration BMP	Existing	9351 BUELL	6/21/2010	6527484.251630	6527484.251630	1799288.621620	245126	1032	sf	64	cf
Infiltration BMP	Existing	9634 BUELL	3/16/2006	6528774.281270	6528774.281270	1798139.573770	245126	1032	sf	64	cf
Infiltration BMP	Existing	9067 BUHMAN	11/20/2007	6530056.595350	6530056.595350	1805336.923900	245125	1032	sf	64	cf
Infiltration BMP	Existing	9208 BUHMAN	6/16/2008	6529799.831660	6529799.831660	1804544.819190	245125	1032	sf	64	cf
Infiltration BMP	Existing	10237 CASANES	3/23/2006	6528975.248660	6528975.248660	1801017.460740	245126	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	10321 CASANES	1/1/2007	6528597.524650	6528597.524650	1800411.412530	245126	1032	sf	64	cf
Infiltration BMP	Existing	10403 CASANES	12/21/2005	6528532.829940	6528532.829940	1800305.536240	245126	1032	sf	64	cf
Infiltration BMP	Existing	10408 CASANES	1/1/2005	6528665.671960	6528665.671960	1800149.799930	245126	1032	sf	64	cf
Infiltration BMP	Existing	10812 CASANES	3/14/2005	6527610.698650	6527610.698650	1798391.295520	245119	1032	sf	64	cf
Infiltration BMP	Existing	10835 CASANES	4/1/2008	6527345.484730	6527345.484730	1798305.683780	245119	1032	sf	64	cf
Infiltration BMP	Existing	10944 CASANES	1/1/2006	6527151.352860	6527151.352860	1797710.972890	245119	1032	sf	64	cf
Infiltration BMP	Existing	8457 CAVEL	9/24/2007	6519984.576530	6519984.576530	1796420.555450	245115	1032	sf	64	cf
Infiltration BMP	Existing	9502 CECILIA	10/11/2007	6527927.079440	6527927.079440	1798327.652080	245126	1032	sf	64	cf
Infiltration BMP	Existing	9531 CECILIA	8/23/2006	6528208.236430	6528208.236430	1798317.933420	245126	1032	sf	64	cf
Infiltration BMP	Existing	9435 CEDARTREE	6/22/2010	6530636.457520	6530636.457520	1805866.234670	245127	1032	sf	64	cf
Infiltration BMP	Existing	9010 CHANEY	11/30/2005	6529789.693370	6529789.693370	1806340.793150	245125	1032	sf	64	cf
Infiltration BMP	Existing	9011 CHANEY	1/31/2006	6529640.900410	6529640.900410	1806424.653160	245125	1032	sf	64	cf
Infiltration BMP	Existing	9134 CHANEY	1/1/2005	6529119.825860	6529119.825860	1805332.958450	245125	1032	sf	64	cf
Infiltration BMP	Existing	10252 CHANEY	1/1/2006	6527373.631100	6527373.631100	1801932.130180	245119	1032	sf	64	cf
Infiltration BMP	Existing	10530 CHANEY	6/3/2008	6526461.472620	6526461.472620	1800532.795270	245119	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8355 CHARLOMA	9/16/2005	6524931.861530	6524931.861530	1806017.636180	246103	1032	sf	64	cf
Infiltration BMP	Existing	9037 CHARLOMA	9/25/2007	6527230.271760	6527230.271760	1804669.291940	245125	1032	sf	64	cf
Infiltration BMP	Existing	8565 CHEROKEE	2/14/2008	6524386.530150	6524386.530150	1802386.701010	245119	1032	sf	64	cf
Infiltration BMP	Existing	8030 CHEYENNE	1/1/2005	6514573.751210	6514573.751210	1792580.925090	246077	1032	sf	64	cf
Infiltration BMP	Existing	8117 CHEYENNE	4/10/2006	6515045.470000	6515045.470000	1792480.065000	246077	1032	sf	64	cf
Infiltration BMP	Existing	8418 CHEYENNE	1/1/2006	6516589.334020	6516589.334020	1791278.419980	245524	1032	sf	64	cf
Infiltration BMP	Existing	9303 CLANCEY	4/3/2006	6528228.489510	6528228.489510	1805319.961840	245125	1032	sf	64	cf
Infiltration BMP	Existing	10518 CLANCEY	3/9/2007	6526045.670270	6526045.670270	1800904.969960	245119	1032	sf	64	cf
Infiltration BMP	Existing	8316 CLETA	4/3/2007	6520383.826830	6520383.826830	1798544.940710	245114	1032	sf	64	cf
Infiltration BMP	Existing	8529 CLETA	1/1/2004	6521562.602410	6521562.602410	1798134.090240	245114	1032	sf	64	cf
Infiltration BMP	Existing	13113 COLDBROOK	6/13/2007	6524340.025750	6524340.025750	1790440.866070	245114	3095	sf	193	cf
Infiltration BMP	Existing	13227 COLDBROOK	2/22/2008	6524428.823880	6524428.823880	1789883.562480	245114	1032	sf	64	cf
Infiltration BMP	Existing	8554 COMOLETTE	6/21/2010	6517765.395020	6517765.395020	1791693.915800	245115	1032	sf	64	cf
Infiltration BMP	Existing	8417 CONKLIN	1/1/2006	6516931.143420	6516931.143420	1791819.671020	245524	1032	sf	64	cf
Infiltration BMP	Existing	7219 COOLGROVE	4/25/2006	6521787.460350	6521787.460350	1811479.001950	246111	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7605 COOLGROVE	6/22/2010	6522636.872680	6522636.872680	1810413.845850	246111	1032	sf	64	cf
Infiltration BMP	Existing	10210 CORD	2/12/2009	6528662.670970	6528662.670970	1801499.064930	245126	1032	sf	64	cf
Infiltration BMP	Existing	7706 COREY	6/22/2010	6515304.522120	6515304.522120	1798247.325380	246079	1032	sf	64	cf
Infiltration BMP	Existing	11708 CORRIGAN	5/30/2006	6523410.919990	6523410.919990	1796690.721900	245114	1032	sf	64	cf
Infiltration BMP	Existing	13227 CORRIGAN	4/11/2006	6523118.258510	6523118.258510	1789898.574120	245114	1032	sf	64	cf
Infiltration BMP	Existing	10809 CROSSDALE	1/30/2006	6532012.269030	6532012.269030	1798722.436870	245122	1032	sf	64	cf
Infiltration BMP	Existing	7803 DACOSTA	1/1/2006	6521705.534400	6521705.534400	1807011.928190	246106	1032	sf	64	cf
Infiltration BMP	Existing	7808 DACOSTA	3/29/2007	6521675.640660	6521675.640660	1806840.332210	246106	1032	sf	64	cf
Infiltration BMP	Existing	7826 DACOSTA	3/23/2007	6521825.889640	6521825.889640	1806744.301550	246106	1032	sf	64	cf
Infiltration BMP	Existing	8064 DACOSTA	1/6/2009	6523365.354910	6523365.354910	1805913.806160	246103	1032	sf	64	cf
Infiltration BMP	Existing	9242 DALEWOOD	5/17/2007	6532339.520890	6532339.520890	1804239.830010	245127	1032	sf	64	cf
Infiltration BMP	Existing	7044 DE PALMA	1/30/2006	6513058.006240	6513058.006240	1802286.102090	246100	1032	sf	64	cf
Infiltration BMP	Existing	7956 DE PALMA	7/28/2005	6517915.235930	6517915.235930	1799223.139650	246077	1032	sf	64	cf
Infiltration BMP	Existing	8232 DE PALMA	12/10/2008	6519342.730110	6519342.730110	1798392.424410	245115	1032	sf	64	cf
Infiltration BMP	Existing	13134 DEMING	2/6/2007	6518053.947000	6518053.947000	1789691.993030	245115	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	13240 DEMING	8/12/2005	6518068.820530	6518068.820530	1789032.682680	245115	1032	sf	64	cf
Infiltration BMP	Existing	13415 DEMPSTER	1/1/2007	6516194.546390	6516194.546390	1789419.790430	245524	1032	sf	64	cf
Infiltration BMP	Existing	13434 DEMPSTER	1/12/2006	6516258.965410	6516258.965410	1789155.039770	245524	1032	sf	64	cf
Infiltration BMP	Existing	13452 DEMPSTER	9/20/2005	6516159.819690	6516159.819690	1788979.483200	245524	1032	sf	64	cf
Infiltration BMP	Existing	7324 DINSDALE	6/21/2010	6518936.024560	6518936.024560	1807958.155410	246106	1032	sf	64	cf
Infiltration BMP	Existing	8352 DINSDALE	12/19/2005	6524191.795240	6524191.795240	1804722.231880	246103	1032	sf	64	cf
Infiltration BMP	Existing	9325 DINSDALE	7/3/2007	6528635.640220	6528635.640220	1802187.000380	245125	1032	sf	64	cf
Infiltration BMP	Existing	9812 DOLAN	1/10/2007	6524918.033470	6524918.033470	1805427.859430	246103	1032	sf	64	cf
Infiltration BMP	Existing	10410 DOLAN	9/19/2007	6523686.660150	6523686.660150	1803351.652190	245119	1032	sf	64	cf
Infiltration BMP	Existing	12522 DOLAN	12/9/2005	6518109.498100	6518109.498100	1794046.260040	245115	1032	sf	64	cf
Infiltration BMP	Existing	12634 DOLAN	4/11/2006	6517527.198260	6517527.198260	1793053.966010	245115	1032	sf	64	cf
Infiltration BMP	Existing	12712 DOLAN	4/27/2005	6517393.756980	6517393.756980	1792842.640770	245115	1032	sf	64	cf
Infiltration BMP	Existing	8740 DONOVAN	11/2/2006	6520467.711390	6520467.711390	1793463.175520	245115	1032	sf	64	cf
Infiltration BMP	Existing	6408 DOS RIOS	3/7/2007	6523246.583700	6523246.583700	1811462.058000	246111	1032	sf	64	cf
Infiltration BMP	Existing	6420 DOS RIOS	7/14/2008	6523082.430580	6523082.430580	1811381.024700	246111	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	6449 DOS RIOS	8/23/2005	6522675.424950	6522675.424950	1811505.638050	246111	1032	sf	64	cf
Infiltration BMP	Existing	6481 DOS RIOS	8/8/2007	6522296.417970	6522296.417970	1811546.494500	246111	1032	sf	64	cf
Infiltration BMP	Existing	9532 DOWNEY	9/21/2007	6524828.225510	6524828.225510	1806555.186060	246103	1032	sf	64	cf
Infiltration BMP	Existing	12115 DOWNEY	8/12/2005	6518801.058860	6518801.058860	1796628.276370	245115	1032	sf	64	cf
Infiltration BMP	Existing	12116 DOWNEY	7/24/2008	6518985.048760	6518985.048760	1796501.621880	245115	1032	sf	64	cf
Infiltration BMP	Existing	12545 DOWNEY	7/7/2005	6517126.997680	6517126.997680	1794204.833310	246077	1032	sf	64	cf
Infiltration BMP	Existing	13620 DOWNEY	10/24/2007	6515777.167020	6515777.167020	1788934.803130	245524	1032	sf	64	cf
Infiltration BMP	Existing	9756 DOWNEY SANFORD BRIDGE	11/6/2008	6530232.905320	6530232.905320	1802732.275270	245125	1032	sf	64	cf
Infiltration BMP	Existing	12109 DUNROBIN	5/27/2008	6524849.554990	6524849.554990	1794742.565720	245114	1032	sf	64	cf
Infiltration BMP	Existing	12602 DUNROBIN	4/21/2008	6525045.021790	6525045.021790	1792096.938130	245114	1032	sf	64	cf
Infiltration BMP	Existing	13118 DUNROBIN	8/1/2008	6525045.611060	6525045.611060	1790357.500340	245114	1032	sf	64	cf
Infiltration BMP	Existing	13447 EARNSHAW	3/4/2005	6516486.580000	6516486.580000	1788881.960000	245524	1032	sf	64	cf
Infiltration BMP	Existing	12246 EASTBROOK	7/3/2007	6525290.855020	6525290.855020	1793729.113600	245114	1032	sf	64	cf
Infiltration BMP	Existing	13102 EASTBROOK	5/30/2006	6525376.065000	6525376.065000	1790509.718450	245114	1032	sf	64	cf
Infiltration BMP	Existing	13207 EASTBROOK	1/1/2006	6525181.215010	6525181.215010	1790147.343800	245114	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9010 EGLISE	6/22/2010	6530616.481070	6530616.481070	1805612.930940	245127	1032	sf	64	cf
Infiltration BMP	Existing	9124 EGLISE	1/1/2006	6530099.347460	6530099.347460	1804464.036140	245125	1032	sf	64	cf
Infiltration BMP	Existing	10228 EGLISE	6/16/2008	6528317.527320	6528317.527320	1801552.496190	245126	1032	sf	64	cf
Infiltration BMP	Existing	8432 EUCALYPTUS	6/21/2010	6518375.883890	6518375.883890	1794450.252220	245115	1032	sf	64	cf
Infiltration BMP	Existing	8451 EUCALYPTUS	11/5/2008	6518648.903650	6518648.903650	1794509.449160	245115	1032	sf	64	cf
Infiltration BMP	Existing	8449 EVEREST	9/20/2006	6518402.636450	6518402.636450	1794253.840980	245115	1032	sf	64	cf
Infiltration BMP	Existing	9036 FARM	1/1/2005	6525791.032450	6525791.032450	1801568.335890	245119	1032	sf	64	cf
Infiltration BMP	Existing	9068 FARM	1/1/2005	6526062.157630	6526062.157630	1801402.977290	245119	1032	sf	64	cf
Infiltration BMP	Existing	8334 FIFTH	6/24/2005	6522409.331110	6522409.331110	1801742.536430	245114	1032	sf	64	cf
Infiltration BMP	Existing	8540 FIFTH	1/1/2005	6523591.182480	6523591.182480	1801021.450470	245114	1032	sf	64	cf
Infiltration BMP	Existing	7238 FLORENCE	11/14/2005	6518231.298960	6518231.298960	1807648.949310	246104	1032	sf	64	cf
Infiltration BMP	Existing	8324 FONTANA	1/1/2006	6519936.868340	6519936.868340	1797701.691440	245115	1032	sf	64	cf
Infiltration BMP	Existing	7322 FOSTER BRIDGE	6/18/2010	6520302.817760	6520302.817760	1810322.849060	246111	1032	sf	64	cf
Infiltration BMP	Existing	7441 FOSTORIA	10/25/2005	6517764.674110	6517764.674110	1804520.953030	246102	1032	sf	64	cf
Infiltration BMP	Existing	7520 FOSTORIA	1/20/2006	6517974.460950	6517974.460950	1804167.759820	246102	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7639 FOSTORIA	7/27/2007	6518691.469740	6518691.469740	1803918.676960	246102	1032	sf	64	cf
Infiltration BMP	Existing	7915 FOURTH	5/29/2007	6519890.537430	6519890.537430	1803170.158590	246102	1032	sf	64	cf
Infiltration BMP	Existing	7922 FOURTH	1/1/2005	6519878.319950	6519878.319950	1802959.531390	246102	1032	sf	64	cf
Infiltration BMP	Existing	7411 FOURTH PL	9/10/2007	6517375.746060	6517375.746060	1804408.156270	246102	1032	sf	64	cf
Infiltration BMP	Existing	7519 FOURTH PL	6/23/2005	6517868.488420	6517868.488420	1804088.501010	246102	1032	sf	64	cf
Infiltration BMP	Existing	7329 GAINFORD	9/20/2007	6519599.973200	6519599.973200	1808409.397520	246111	1032	sf	64	cf
Infiltration BMP	Existing	7725 GAINFORD	6/21/2010	6521357.607460	6521357.607460	1807543.814610	246106	1032	sf	64	cf
Infiltration BMP	Existing	7735 GAINFORD	12/15/2006	6521461.236080	6521461.236080	1807480.220630	246106	1032	sf	64	cf
Infiltration BMP	Existing	7771 GAINFORD	12/3/2007	6521758.954890	6521758.954890	1807297.289390	246106	1032	sf	64	cf
Infiltration BMP	Existing	8353 GAINFORD	1/4/2007	6524689.963810	6524689.963810	1805534.024270	246103	1032	sf	64	cf
Infiltration BMP	Existing	8553 GAINFORD	4/7/2008	6525875.670020	6525875.670020	1804802.065800	245125	1032	sf	64	cf
Infiltration BMP	Existing	9114 GAINFORD	6/23/2010	6527375.967240	6527375.967240	1803418.253090	245125	1032	sf	64	cf
Infiltration BMP	Existing	8319 GALLATIN	6/23/2010	6525634.222480	6525634.222480	1807445.394810	246103	1032	sf	64	cf
Infiltration BMP	Existing	9069 GALLATIN	3/1/2005	6527846.830170	6527846.830170	1805432.059660	245125	1032	sf	64	cf
Infiltration BMP	Existing	9243 GALLATIN	6/19/2006	6528915.102070	6528915.102070	1804595.777040	245125	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8408 GALT	6/18/2010	6520848.594160	6520848.594160	1798562.646220	245114	1032	sf	64	cf
Infiltration BMP	Existing	8435 GALT	12/27/2005	6521154.530230	6521154.530230	1798569.782020	245114	1032	sf	64	cf
Infiltration BMP	Existing	9119 GARNISH	6/22/2010	6529517.516530	6529517.516530	1805110.082900	245125	1032	sf	64	cf
Infiltration BMP	Existing	9136 GARNISH	2/5/2007	6529607.954040	6529607.954040	1804869.027300	245125	1032	sf	64	cf
Infiltration BMP	Existing	9024 GAYMONT	8/28/2007	6523451.624790	6523451.624790	1809501.434890	246111	1032	sf	64	cf
Infiltration BMP	Existing	12636 GLYNN	10/25/2005	6517337.921050	6517337.921050	1793251.757000	245524	1032	sf	64	cf
Infiltration BMP	Existing	12751 GLYNN	1/1/2005	6516780.406550	6516780.406550	1792749.927780	245524	1032	sf	64	cf
Infiltration BMP	Existing	12755 GLYNN	6/18/2010	6516753.778610	6516753.778610	1792707.557200	245524	1032	sf	64	cf
Infiltration BMP	Existing	12912 GLYNN	1/1/2005	6516567.905690	6516567.905690	1791996.175300	245524	1032	sf	64	cf
Infiltration BMP	Existing	8731 GUATEMALA	10/30/2008	6523507.693960	6523507.693960	1811098.218950	246106	1032	sf	64	cf
Infiltration BMP	Existing	9203 GUATEMALA	3/23/2006	6521893.308510	6521893.308510	1810154.570390	246111	1032	sf	64	cf
Infiltration BMP	Existing	9959 GUATEMALA	6/23/2010	6518699.649950	6518699.649950	1808234.818150	246111	1032	sf	64	cf
Infiltration BMP	Existing	13537 GUNDERSON	3/3/2008	6517350.406160	6517350.406160	1787757.556610	245524	1032	sf	64	cf
Infiltration BMP	Existing	13547 GUNDERSON	6/19/2006	6517298.502270	6517298.502270	1787667.099660	245524	1032	sf	64	cf
Infiltration BMP	Existing	11538 GURLEY	5/3/2005	6520211.328840	6520211.328840	1799382.602480	245115	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	11935 GURLEY	6/18/2010	6519051.777570	6519051.777570	1797582.114550	245115	1032	sf	64	cf
Infiltration BMP	Existing	12019 GURLEY	6/18/2010	6518869.145640	6518869.145640	1797295.091770	245115	1032	sf	64	cf
Infiltration BMP	Existing	12052 GURLEY	1/10/2006	6518841.793230	6518841.793230	1796925.916150	245115	1032	sf	64	cf
Infiltration BMP	Existing	12117 GURLEY	1/1/2007	6518497.250390	6518497.250390	1796711.283370	245115	1032	sf	64	cf
Infiltration BMP	Existing	9117 HALEDON	7/31/2006	6528761.573350	6528761.573350	1805801.190120	245125	1032	sf	64	cf
Infiltration BMP	Existing	10341 HALEDON	5/1/2006	6526657.457480	6526657.457480	1801653.926760	245119	1032	sf	64	cf
Infiltration BMP	Existing	10349 HALEDON	2/8/2005	6526618.690140	6526618.690140	1801591.635520	245119	1032	sf	64	cf
Infiltration BMP	Existing	10425 HALEDON	4/14/2005	6526424.760130	6526424.760130	1801280.406410	245119	1032	sf	64	cf
Infiltration BMP	Existing	10439 HALEDON	9/30/2005	6526346.747570	6526346.747570	1801155.573630	245119	1032	sf	64	cf
Infiltration BMP	Existing	10525 HALEDON	1/28/2005	6526113.410380	6526113.410380	1800804.505840	245119	1032	sf	64	cf
Infiltration BMP	Existing	10550 HALEDON	12/19/2005	6526112.578950	6526112.578950	1800485.376650	245119	1032	sf	64	cf
Infiltration BMP	Existing	9049 HALL ROAD	4/30/2008	6523684.587500	6523684.587500	1797586.831540	245114	1032	sf	64	cf
Infiltration BMP	Existing	7215 HANNON	12/19/2008	6521498.261440	6521498.261440	1811442.204100	246111	1032	sf	64	cf
Infiltration BMP	Existing	13005 HANWELL	2/11/2009	6519590.457150	6519590.457150	1789492.134120	245115	1032	sf	64	cf
Infiltration BMP	Existing	9022 HASTY	10/13/2005	6531232.650260	6531232.650260	1805433.916070	245127	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9205 HASTY	6/22/2010	6530848.690890	6530848.690890	1804978.371330	245127	1032	sf	64	cf
Infiltration BMP	Existing	9206 HASTY	1/1/2005	6531000.691980	6531000.691980	1804885.411940	245127	1032	sf	64	cf
Infiltration BMP	Existing	9241 HASTY	1/1/2006	6530719.487200	6530719.487200	1804649.180550	245127	1032	sf	64	cf
Infiltration BMP	Existing	7736 HONDO	2/8/2005	6514830.078530	6514830.078530	1796886.774430	246079	1032	sf	64	cf
Infiltration BMP	Existing	7753 HONDO	1/24/2007	6515005.269000	6515005.269000	1796951.957630	246079	1032	sf	64	cf
Infiltration BMP	Existing	7803 HONDO	10/11/2005	6515156.509020	6515156.509020	1796903.351830	246079	1032	sf	64	cf
Infiltration BMP	Existing	7808 HONDO	6/22/2010	6515109.805390	6515109.805390	1796717.393590	246079	1032	sf	64	cf
Infiltration BMP	Existing	7814 HONDO	7/25/2008	6515161.093050	6515161.093050	1796686.379320	246079	1032	sf	64	cf
Infiltration BMP	Existing	7920 HONDO	8/21/2006	6515777.018460	6515777.018460	1796313.217950	246079	1032	sf	64	cf
Infiltration BMP	Existing	7932 HONDO	1/1/2006	6515879.568480	6515879.568480	1796251.099580	246079	1032	sf	64	cf
Infiltration BMP	Existing	9008 HORLEY	7/19/2007	6523080.991430	6523080.991430	1809910.740800	246111	1032	sf	64	cf
Infiltration BMP	Existing	9838 HORLEY	7/3/2008	6521155.061500	6521155.061500	1807271.870840	246106	1032	sf	64	cf
Infiltration BMP	Existing	12307 HORLEY	1/1/2005	6514989.782150	6514989.782150	1797487.116040	246079	1032	sf	64	cf
Infiltration BMP	Existing	11427 HORTON	11/23/2005	6517266.456490	6517266.456490	1802136.009270	246079	1032	sf	64	cf
Infiltration BMP	Existing	11553 HORTON	4/21/2005	6516872.120940	6516872.120940	1801498.085040	246079	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	11708 HORTON	10/25/2005	6516455.941870	6516455.941870	1800783.417100	246079	1032	sf	64	cf
Infiltration BMP	Existing	12646 IBBETSON	5/6/2005	6526008.756240	6526008.756240	1791650.535870	245114	1032	sf	64	cf
Infiltration BMP	Existing	8217 IMPERIAL	1/5/2009	6516889.628840	6516889.628840	1794092.786860	246077	1032	sf	64	cf
Infiltration BMP	Existing	7320 IRWINGROVE	1/1/2006	6518255.802480	6518255.802480	1807084.876440	246102	1032	sf	64	cf
Infiltration BMP	Existing	7710 IRWINGROVE	12/11/2007	6520151.425540	6520151.425540	1805902.138310	246102	1032	sf	64	cf
Infiltration BMP	Existing	12208 IZETTA	1/1/2006	6524718.745010	6524718.745010	1794118.344290	245114	1032	sf	64	cf
Infiltration BMP	Existing	12252 IZETTA	7/10/2008	6524718.900100	6524718.900100	1793666.382200	245114	1032	sf	64	cf
Infiltration BMP	Existing	12631 IZETTA	8/28/2007	6524602.625920	6524602.625920	1791809.267080	245114	1032	sf	64	cf
Infiltration BMP	Existing	10228 JULIUS	5/20/2008	6519748.327880	6519748.327880	1806603.074440	246102	1032	sf	64	cf
Infiltration BMP	Existing	10234 JULIUS	6/22/2010	6519723.348540	6519723.348540	1806551.787860	246102	1032	sf	64	cf
Infiltration BMP	Existing	11848 JULIUS	6/23/2010	6515875.825190	6515875.825190	1800351.825190	246079	1032	sf	64	cf
Infiltration BMP	Existing	11859 JULIUS	8/23/2005	6515676.490910	6515676.490910	1800355.137490	246079	1032	sf	64	cf
Infiltration BMP	Existing	11865 JULIUS	11/13/2006	6515650.173870	6515650.173870	1800309.916770	246079	1032	sf	64	cf
Infiltration BMP	Existing	12129 JULIUS	9/29/2005	6514728.334670	6514728.334670	1798846.683770	246079	1032	sf	64	cf
Infiltration BMP	Existing	9263 KLINEDALE	6/21/2010	6531573.525950	6531573.525950	1804517.918460	245127	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9205 LA REINA	11/27/2006	6525690.537020	6525690.537020	1808255.600740	246103	1032	sf	64	cf
Infiltration BMP	Existing	9251 LA REINA	8/10/2007	6525325.121400	6525325.121400	1807968.316200	246103	1032	sf	64	cf
Infiltration BMP	Existing	9260 LA REINA	6/14/2007	6525343.506110	6525343.506110	1807785.350080	246103	1032	sf	64	cf
Infiltration BMP	Existing	9633 LA REINA	9/24/2007	6524180.010720	6524180.010720	1806496.849820	246103	1032	sf	64	cf
Infiltration BMP	Existing	10026 LA REINA	1/1/2005	6523542.730590	6523542.730590	1805175.247470	246103	1032	sf	64	cf
Infiltration BMP	Existing	10219 LA REINA	5/25/2006	6522978.941790	6522978.941790	1804778.433210	246103	1032	sf	64	cf
Infiltration BMP	Existing	8346 LA VILLA	8/29/2005	6522426.709000	6522426.709000	1801414.465390	245114	1032	sf	64	cf
Infiltration BMP	Existing	9524 LA VILLA	9/27/2005	6527942.492070	6527942.492070	1797972.664540	245119	1032	sf	64	cf
Infiltration BMP	Existing	14305 LAKEWOOD	1/1/2006	6518183.322800	6518183.322800	1787270.059950	245524	1032	sf	64	cf
Infiltration BMP	Existing	8218 LANKIN	3/28/2006	6516908.705740	6516908.705740	1794755.893760	246077	1032	sf	64	cf
Infiltration BMP	Existing	13407 LAURELDALE	10/25/2005	6516128.982330	6516128.982330	1789557.891060	245524	1032	sf	64	cf
Infiltration BMP	Existing	11034 LE FLOSS	3/21/2008	6531318.633350	6531318.633350	1797718.334360	245124	1032	sf	64	cf
Infiltration BMP	Existing	9013 LEMORAN	3/16/2006	6529860.990680	6529860.990680	1806212.694780	245125	1032	sf	64	cf
Infiltration BMP	Existing	10036 LESTERFORD	1/11/2006	6530911.516090	6530911.516090	1801094.347740	245125	1032	sf	64	cf
Infiltration BMP	Existing	8355 LEXINGTON	6/15/2005	6523932.891700	6523932.891700	1804236.927600	246103	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7432 LUBEC	7/8/2005	6519806.105180	6519806.105180	1808430.037290	246111	1032	sf	64	cf
Infiltration BMP	Existing	9318 LUBEC	1/1/2006	6528946.832250	6528946.832250	1803071.454980	245125	1032	sf	64	cf
Infiltration BMP	Existing	7341 LUXOR	9/30/2005	6515165.173860	6515165.173860	1801559.243950	246079	1032	sf	64	cf
Infiltration BMP	Existing	7743 LUXOR	8/18/2006	6517197.964320	6517197.964320	1800308.569440	246079	1032	sf	64	cf
Infiltration BMP	Existing	7809 LUXOR	1/1/2006	6517239.593210	6517239.593210	1799986.863830	246079	1032	sf	64	cf
Infiltration BMP	Existing	7982 LUXOR	7/3/2007	6518306.219270	6518306.219270	1799333.376300	246077	1032	sf	64	cf
Infiltration BMP	Existing	8509 LUXOR	12/31/2008	6521183.510000	6521183.510000	1797885.775000	245114	1032	sf	64	cf
Infiltration BMP	Existing	11505 MAC GOVERN	5/1/2006	6519990.708800	6519990.708800	1799977.759420	245115	1032	sf	64	cf
Infiltration BMP	Existing	11527 MAC GOVERN	11/19/2007	6519889.562820	6519889.562820	1799806.361750	245115	1032	sf	64	cf
Infiltration BMP	Existing	8518 MANATEE	4/27/2005	6521541.591450	6521541.591450	1798287.495050	245114	1032	sf	64	cf
Infiltration BMP	Existing	12306 MARBEL	12/29/2005	6520780.434840	6520780.434840	1794110.003960	245115	1032	sf	64	cf
Infiltration BMP	Existing	12322 MARBEL	8/24/2005	6520697.258530	6520697.258530	1793976.926170	245115	1032	sf	64	cf
Infiltration BMP	Existing	10423 MATTOCK	11/21/2008	6528946.576280	6528946.576280	1799798.739650	245126	1032	sf	64	cf
Infiltration BMP	Existing	10527 MATTOCK	1/11/2007	6528618.163260	6528618.163260	1799183.483330	245126	1032	sf	64	cf
Infiltration BMP	Existing	8602 MEADOW	2/28/2008	6519007.155950	6519007.155950	1793158.643900	245115	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8606 MEADOW	10/26/2006	6519050.372960	6519050.372960	1793129.529230	245115	1032	sf	64	cf
Infiltration BMP	Existing	8739 MEADOW	12/17/2007	6520051.313480	6520051.313480	1792689.390880	245115	1032	sf	64	cf
Infiltration BMP	Existing	9106 MELDAR	4/23/2007	6526980.004600	6526980.004600	1807421.893550	246103	1032	sf	64	cf
Infiltration BMP	Existing	7819 MELVA	1/1/2005	6515811.952890	6515811.952890	1797638.263460	246079	1032	sf	64	cf
Infiltration BMP	Existing	8609 MELVA	4/6/2007	6520260.479750	6520260.479750	1795043.474460	245115	1032	sf	64	cf
Infiltration BMP	Existing	9558 METRO	4/3/2008	6531485.802060	6531485.802060	1804114.777900	245127	1032	sf	64	cf
Infiltration BMP	Existing	11711 MITLA	7/13/2005	6513453.724060	6513453.724060	1802912.278240	246100	1032	sf	64	cf
Infiltration BMP	Existing	11819 MORNING	6/21/2010	6517496.555960	6517496.555960	1799723.226450	246077	1032	sf	64	cf
Infiltration BMP	Existing	12070 MORNING	9/13/2006	6516788.931410	6516788.931410	1797957.975300	246079	1032	sf	64	cf
Infiltration BMP	Existing	8637 MORY	1/1/2005	6520217.929830	6520217.929830	1794453.857040	245115	1032	sf	64	cf
Infiltration BMP	Existing	10903 MYRTLE	10/25/2005	6520809.999180	6520809.999180	1802308.735020	246103	1032	sf	64	cf
Infiltration BMP	Existing	8208 NADA	6/29/2005	6518679.653960	6518679.653960	1797804.552950	245115	1032	sf	64	cf
Infiltration BMP	Existing	8249 NADA	2/12/2008	6519111.183860	6519111.183860	1797730.010570	245115	1032	sf	64	cf
Infiltration BMP	Existing	9458 NANCE	6/20/2005	6526752.832360	6526752.832360	1796717.105850	245119	1032	sf	64	cf
Infiltration BMP	Existing	10609 NEDRA	6/3/2005	6522752.614640	6522752.614640	1802538.434710	246103	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	10850 NEWVILLE	7/3/2007	6528159.933410	6528159.933410	1797635.549950	245119	1032	sf	64	cf
Infiltration BMP	Existing	7510 NOREN	5/23/2006	6520838.348300	6520838.348300	1809064.222230	246111	1032	sf	64	cf
Infiltration BMP	Existing	11720 NORLAIN	9/22/2006	6515696.110230	6515696.110230	1801264.632180	246079	1032	sf	64	cf
Infiltration BMP	Existing	12336 NORLAIN	8/1/2007	6513658.838460	6513658.838460	1797875.767390	246079	1032	sf	64	cf
Infiltration BMP	Existing	11628 OLD RIVER SCHOOL	1/1/2006	6515797.838400	6515797.838400	1801876.521840	246079	1032	sf	64	cf
Infiltration BMP	Existing	8521 ORANGE	3/9/2007	6519427.831130	6519427.831130	1794911.101980	245115	1032	sf	64	cf
Infiltration BMP	Existing	9255 ORIZABA	2/15/2006	6525108.451310	6525108.451310	1808168.208600	246103	1032	sf	64	cf
Infiltration BMP	Existing	9719 ORIZABA	8/8/2007	6523780.810110	6523780.810110	1806377.528150	246103	1032	sf	64	cf
Infiltration BMP	Existing	12615 ORIZABA	1/27/2006	6516062.877730	6516062.877730	1794206.618320	246077	1032	sf	64	cf
Infiltration BMP	Existing	8511 OTTO	4/12/2005	6525130.700850	6525130.700850	1804530.864040	245125	1032	sf	64	cf
Infiltration BMP	Existing	9933 PANGBORN	6/29/2006	6530067.434760	6530067.434760	1801915.181390	245125	1032	sf	64	cf
Infiltration BMP	Existing	10202 PANGBORN	1/1/2006	6529571.236640	6529571.236640	1801045.668670	245125	1032	sf	64	cf
Infiltration BMP	Existing	11009 PANGBORN	1/31/2007	6527339.080190	6527339.080190	1797691.116980	245119	1032	sf	64	cf
Infiltration BMP	Existing	9530 PARAMOUNT	7/14/2005	6523601.663290	6523601.663290	1807461.311510	246103	1032	sf	64	cf
Infiltration BMP	Existing	9624 PARAMOUNT	5/9/2005	6523328.526550	6523328.526550	1807031.980170	246103	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8603 PARROT	3/14/2006	6526080.240790	6526080.240790	1809719.746830	246106	1032	sf	64	cf
Infiltration BMP	Existing	9625 PARROT	1/1/2005	6523451.735380	6523451.735380	1806960.011690	246103	1032	sf	64	cf
Infiltration BMP	Existing	9708 PARROT	6/29/2006	6523491.321500	6523491.321500	1806678.668660	246103	1032	sf	64	cf
Infiltration BMP	Existing	12045 PARROT	6/22/2010	6517861.439330	6517861.439330	1797868.798060	246077	1032	sf	64	cf
Infiltration BMP	Existing	12751 PARROT	12/14/2006	6515222.728500	6515222.728500	1793830.999240	246077	1032	sf	64	cf
Infiltration BMP	Existing	7130 PELLET	1/27/2005	6515276.387650	6515276.387650	1804845.311440	246104	1032	sf	64	cf
Infiltration BMP	Existing	7323 PELLET	1/1/2005	6516571.171210	6516571.171210	1804327.110650	246104	1032	sf	64	cf
Infiltration BMP	Existing	7354 PELLET	1/1/2006	6516665.448760	6516665.448760	1803945.359790	246102	1032	sf	64	cf
Infiltration BMP	Existing	7861 PHLOX	9/17/2007	6518688.116640	6518688.116640	1801430.417420	246079	1032	sf	64	cf
Infiltration BMP	Existing	10620 PICO VISTA	3/7/2007	6529428.403390	6529428.403390	1798283.402620	245126	1032	sf	64	cf
Infiltration BMP	Existing	10635 PICO VISTA	8/28/2007	6529197.816790	6529197.816790	1798270.093070	245126	1032	sf	64	cf
Infiltration BMP	Existing	7530 PIVOT	11/23/2005	6516899.016370	6516899.016370	1802660.318910	246079	1032	sf	64	cf
Infiltration BMP	Existing	7709 PIVOT	10/11/2005	6517859.569570	6517859.569570	1802212.124870	246079	1032	sf	64	cf
Infiltration BMP	Existing	7753 PIVOT	6/14/2005	6518241.212950	6518241.212950	1801966.921690	246079	1032	sf	64	cf
Infiltration BMP	Existing	11974 POMERING	6/18/2010	6515116.938670	6515116.938670	1799645.797070	246079	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8732 PRICHARD ST	1/12/2009	6516786.371080	6516786.371080	1788406.289900	245524	1032	sf	64	cf
Infiltration BMP	Existing	8734 PRICHARD ST	1/12/2009	6516831.574810	6516831.574810	1788380.860770	245524	1032	sf	64	cf
Infiltration BMP	Existing	8738 PRICHARD ST	1/12/2009	6516876.454020	6516876.454020	1788355.597890	245524	1032	sf	64	cf
Infiltration BMP	Existing	8740 PRICHARD ST	1/12/2009	6516921.333860	6516921.333860	1788330.343610	245524	1032	sf	64	cf
Infiltration BMP	Existing	8240 PRISCILLA	9/13/2007	6515555.844810	6515555.844810	1791697.292180	246077	1032	sf	64	cf
Infiltration BMP	Existing	9044 PRISCILLA	8/18/2005	6519169.042140	6519169.042140	1790017.667840	245115	1032	sf	64	cf
Infiltration BMP	Existing	9060 PRISCILLA	6/21/2010	6519318.719160	6519318.719160	1790008.270400	245115	1032	sf	64	cf
Infiltration BMP	Existing	11448 PRUESS	1/1/2006	6518742.114860	6518742.114860	1801046.878700	246077	1032	sf	64	cf
Infiltration BMP	Existing	11609 PRUESS	11/16/2006	6518299.675980	6518299.675980	1800455.121300	246077	1032	sf	64	cf
Infiltration BMP	Existing	11619 PRUESS	6/10/2005	6518270.484730	6518270.484730	1800355.677990	246077	1032	sf	64	cf
Infiltration BMP	Existing	11708 PRUESS	1/18/2005	6518033.994760	6518033.994760	1799832.073440	246077	1032	sf	64	cf
Infiltration BMP	Existing	8121 PURITAN	6/5/2006	6515245.448070	6515245.448070	1792698.037730	246077	1032	sf	64	cf
Infiltration BMP	Existing	7707 QUILL	6/1/2007	6514508.683200	6514508.683200	1796937.770200	246079	1032	sf	64	cf
Infiltration BMP	Existing	8108 QUOIT	6/5/2008	6516594.034560	6516594.034560	1795288.918170	246077	1032	sf	64	cf
Infiltration BMP	Existing	9109 RAVILLER	2/6/2007	6527953.464140	6527953.464140	1804924.402110	245125	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9367 RAVILLER	1/1/2006	6529435.914270	6529435.914270	1803746.913820	245125	1032	sf	64	cf
Infiltration BMP	Existing	9728 RICHEON	6/18/2010	6521201.804800	6521201.804800	1807962.626360	246106	1032	sf	64	cf
Infiltration BMP	Existing	12217 RICHEON	1/1/2005	6514937.033870	6514937.033870	1797986.477150	246079	1032	sf	64	cf
Infiltration BMP	Existing	12336 RICHEON	1/10/2007	6514721.816510	6514721.816510	1797298.695230	246079	1032	sf	64	cf
Infiltration BMP	Existing	12342 RICHEON	1/1/2005	6514694.932100	6514694.932100	1797256.523880	246079	1032	sf	64	cf
Infiltration BMP	Existing	12352 RICHEON	10/30/2008	6514641.834370	6514641.834370	1797172.034360	246079	1032	sf	64	cf
Infiltration BMP	Existing	11010 RIO HONDO	2/6/2006	6514511.989690	6514511.989690	1805412.886430	246104	1032	sf	64	cf
Infiltration BMP	Existing	8515 RIVES	2/6/2006	6524958.575190	6524958.575190	1811619.081610	246111	1032	sf	64	cf
Infiltration BMP	Existing	8546 RIVES	6/14/2010	6524726.063490	6524726.063490	1811337.492550	246106	1032	sf	64	cf
Infiltration BMP	Existing	11828 RIVES	1/1/2006	6517020.372820	6517020.372820	1799741.223590	246079	1032	sf	64	cf
Infiltration BMP	Existing	12056 RIVES	10/7/2005	6516252.097820	6516252.097820	1798479.870770	246079	1032	sf	64	cf
Infiltration BMP	Existing	12213 RIVES	6/7/2007	6515544.034920	6515544.034920	1797794.303030	246079	1032	sf	64	cf
Infiltration BMP	Existing	12301 RIVES	1/27/2006	6515274.134590	6515274.134590	1797373.251430	246079	1032	sf	64	cf
Infiltration BMP	Existing	12542 ROSE	6/18/2010	6520775.320830	6520775.320830	1792425.734550	245115	1032	sf	64	cf
Infiltration BMP	Existing	7444 RUNDELL	9/28/2006	6514195.392880	6514195.392880	1798477.819400	246079	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7458 RUNDELL	1/1/2006	6514328.036950	6514328.036950	1798395.544300	246079	1032	sf	64	cf
Infiltration BMP	Existing	8734 RUPP	5/24/2007	6518769.625610	6518769.625610	1791861.464390	245115	1032	sf	64	cf
Infiltration BMP	Existing	9206 SAMOLINE	9/20/2006	6524105.922670	6524105.922670	1808777.784250	246106	1032	sf	64	cf
Infiltration BMP	Existing	9363 SAMOLINE	2/12/2009	6523342.697990	6523342.697990	1808041.206940	246106	1032	sf	64	cf
Infiltration BMP	Existing	9630 SAMOLINE	1/1/2006	6523000.405210	6523000.405210	1807164.143360	246103	1032	sf	64	cf
Infiltration BMP	Existing	12041 SAMOLINE	6/23/2010	6516971.702030	6516971.702030	1798170.274910	246079	1032	sf	64	cf
Infiltration BMP	Existing	10629 SHELLEYFIELD	6/21/2010	6525284.582980	6525284.582980	1800508.363190	245119	1032	sf	64	cf
Infiltration BMP	Existing	9118 SHERIDELL	6/22/2010	6528683.896100	6528683.896100	1805941.227670	245125	1032	sf	64	cf
Infiltration BMP	Existing	10042 SIDEVIEW	6/21/2010	6529464.806690	6529464.806690	1801729.923910	245125	1032	sf	64	cf
Infiltration BMP	Existing	8349 SIXTH	6/21/2010	6522706.066860	6522706.066860	1802231.249170	245114	1032	sf	64	cf
Infiltration BMP	Existing	8363 SIXTH	6/18/2010	6522832.335670	6522832.335670	1802150.209500	245114	1032	sf	64	cf
Infiltration BMP	Existing	8532 SIXTH	6/23/2010	6523697.106090	6523697.106090	1801388.440460	245119	1032	sf	64	cf
Infiltration BMP	Existing	8514 SMALLWOOD	8/24/2006	6525167.581560	6525167.581560	1811228.866910	246106	1032	sf	64	cf
Infiltration BMP	Existing	12007 SMALLWOOD	1/1/2005	6516682.861570	6516682.861570	1798786.226940	246079	1032	sf	64	cf
Infiltration BMP	Existing	12936 SMALLWOOD	7/31/2006	6513688.714060	6513688.714060	1793540.982580	246077	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9235 SONGFEST	6/14/2006	6531351.855720	6531351.855720	1804709.858310	245127	1032	sf	64	cf
Infiltration BMP	Existing	7939 SPRINGER	10/6/2006	6516193.792450	6516193.792450	1796630.732180	246079	1032	sf	64	cf
Infiltration BMP	Existing	9306 STAMPS	6/21/2010	6525546.826990	6525546.826990	1807197.501010	246103	1032	sf	64	cf
Infiltration BMP	Existing	10446 STAMPS	1/1/2005	6523214.650320	6523214.650320	1803242.228000	246103	1032	sf	64	cf
Infiltration BMP	Existing	10536 STAMPS	6/1/2006	6522871.528480	6522871.528480	1802783.838380	246103	1032	sf	64	cf
Infiltration BMP	Existing	13219 STANBRIDGE	9/17/2007	6522806.618420	6522806.618420	1790045.381220	245114	1032	sf	64	cf
Infiltration BMP	Existing	8723 STEWART & GRAY	2/11/2009	6522100.372490	6522100.372490	1796545.507760	245114	1032	sf	64	cf
Infiltration BMP	Existing	9028 STOAKES	8/17/2007	6527221.634250	6527221.634250	1807951.198320	246103	1032	sf	64	cf
Infiltration BMP	Existing	7809 SUVA	1/13/2009	6522703.875430	6522703.875430	1808490.998990	246106	1032	sf	64	cf
Infiltration BMP	Existing	7827 SUVA	1/1/2006	6522849.829890	6522849.829890	1808368.560310	246106	1032	sf	64	cf
Infiltration BMP	Existing	8564 SUVA	1/1/2006	6526403.328390	6526403.328390	1805373.281490	245125	1032	sf	64	cf
Infiltration BMP	Existing	9943 TECUM	4/11/2008	6519363.349470	6519363.349470	1808047.658450	246111	1032	sf	64	cf
Infiltration BMP	Existing	9636 TELEGRAPH	5/8/2006	6531995.042290	6531995.042290	1804929.677680	245128	1032	sf	64	cf
Infiltration BMP	Existing	7968 THIRD	6/21/2005	6519929.169700	6519929.169700	1802199.016820	246102	1032	sf	64	cf
Infiltration BMP	Existing	9819 TRISTAN	10/7/2005	6526302.584780	6526302.584780	1804524.383680	245125	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9253 TRUE	1/1/2005	6531891.994890	6531891.994890	1804462.821310	245127	1032	sf	64	cf
Infiltration BMP	Existing	8843 TWEEDY	9/12/2006	6524140.679400	6524140.679400	1809940.135780	246106	1032	sf	64	cf
Infiltration BMP	Existing	9012 TWEEDY	1/1/2005	6523977.735950	6523977.735950	1809300.273240	246106	1032	sf	64	cf
Infiltration BMP	Existing	9029 TWEEDY	1/1/2006	6523763.012330	6523763.012330	1809288.681880	246106	1032	sf	64	cf
Infiltration BMP	Existing	9612 TWEEDY	6/22/2010	6522847.016620	6522847.016620	1807449.028980	246106	1032	sf	64	cf
Infiltration BMP	Existing	9636 TWEEDY	10/11/2005	6522732.626430	6522732.626430	1807259.266340	246103	1032	sf	64	cf
Infiltration BMP	Existing	9714 TWEEDY	7/24/2006	6522647.237500	6522647.237500	1807116.822930	246103	1032	sf	64	cf
Infiltration BMP	Existing	9718 TWEEDY	9/22/2008	6522619.325230	6522619.325230	1807068.990310	246103	1032	sf	64	cf
Infiltration BMP	Existing	9730 TWEEDY	6/18/2010	6522565.360970	6522565.360970	1806976.155270	246103	1032	sf	64	cf
Infiltration BMP	Existing	13409 VERDURA	1/1/2006	6516484.588360	6516484.588360	1789346.159960	245524	1032	sf	64	cf
Infiltration BMP	Existing	8607 VIA AMORITA	1/19/2006	6524994.226680	6524994.226680	1803003.226520	245119	1032	sf	64	cf
Infiltration BMP	Existing	9356 VIA AMORITA	4/27/2005	6528170.664540	6528170.664540	1800850.979140	245126	1032	sf	64	cf
Infiltration BMP	Existing	7402 VIA RIO NIDO	2/10/2005	6518371.376580	6518371.376580	1806186.704160	246102	1032	sf	64	cf
Infiltration BMP	Existing	8303 VISTA DEL RIO	5/1/2007	6526003.249760	6526003.249760	1808077.011440	246103	1032	sf	64	cf
Infiltration BMP	Existing	8303 VISTA DEL ROSA	4/26/2007	6526763.242710	6526763.242710	1809159.607970	246106	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8351 VISTA DEL ROSA	12/19/2005	6527091.635630	6527091.635630	1808824.632820	246106	2063	sf	129	cf
Infiltration BMP	Existing	10265 VULTEE	4/24/2006	6525980.530560	6525980.530560	1802568.772980	245119	1032	sf	64	cf
Infiltration BMP	Existing	10339 VULTEE	6/18/2010	6525804.209560	6525804.209560	1802209.879860	245119	1032	sf	64	cf
Infiltration BMP	Existing	12709 VULTEE	3/9/2007	6519587.948000	6519587.948000	1791264.714830	245115	1032	sf	64	cf
Infiltration BMP	Existing	12725 WHITEWOOD	7/26/2005	6520341.668580	6520341.668580	1791179.460770	245115	1032	sf	64	cf
Infiltration BMP	Existing	9702 WILEY BURKE	6/21/2010	6521126.099980	6521126.099980	1808337.656530	246106	1032	sf	64	cf
Infiltration BMP	Existing	9750 WILEY BURKE	12/11/2006	6520822.729060	6520822.729060	1807995.132410	246106	1032	sf	64	cf
Infiltration BMP	Existing	9925 WILEY BURKE	1/10/2007	6520271.299840	6520271.299840	1807447.007570	246106	1032	sf	64	cf
Infiltration BMP	Existing	10540 WILEY BURKE	6/21/2007	6519089.326110	6519089.326110	1805048.306870	246102	1032	sf	64	cf
Infiltration BMP	Existing	10643 WOODRUFF	1/1/2006	6526887.322420	6526887.322420	1799535.375650	245119	1032	sf	64	cf
Infiltration BMP	Existing	7515 YANKEY	10/24/2006	6515115.108440	6515115.108440	1798924.389740	246079	1032	sf	64	cf
Infiltration BMP	Existing	10047 CASANES	1/1/2006	6529512.635540	6529512.635540	1801587.658100	245125	1032	sf	64	cf
Infiltration BMP	Existing	9220 CORD	1/1/2004	6530296.778820	6530296.778820	1804178.901350	245125	1032	sf	64	cf
Infiltration BMP	Existing	10040 MATTOCK	1/1/2006	6530247.042350	6530247.042350	1801200.601240	245125	1032	sf	64	cf
Infiltration BMP	Existing	10018 PANGBORN	1/1/2006	6530084.251260	6530084.251260	1801567.525640	245125	1032	sf	64	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	12053 PATTON	10/19/2004	6520642.037410	6520642.037410	1796050.004800	245115	1032	sf	64	cf
Infiltration BMP	Existing	12048 SAMOLINE	3/20/2007	6517021.712450	6517021.712450	1798014.455830	246079	2063	sf	129	cf
Infiltration BMP	Existing	7879 FLORENCE	2/14/2014	6521700.000000	6521700.000000	1806100.000000	246103	16504	sf	1032	cf
Infiltration BMP	Existing	9020 FIRESTONE	9/12/2008	6524113.023390	6524113.023390	1798572.164290	245119	70288	sf	4393	cf
Infiltration BMP	Existing	7910 FIRESTONE	6/28/2005	6519165.968790	6519165.968790	1801736.513180	246102	55686	sf	3480	cf
Infiltration BMP	Existing	7252 FIRESTONE	5/19/2004	6515489.000650	6515489.000650	1803082.633110	246079	36224	sf	2264	cf
Infiltration BMP	Existing	12256 PARAMOUNT	3/13/2006	6516813.225030	6516813.225030	1796497.685630	246077	34112	sf	2132	cf
Infiltration BMP	Existing	9462 FIRESTONE BL	2/14/2014	6526885.862260	6526885.862260	1797100.585140	245119	35437	sf	2215	cf
Infiltration BMP	Existing	8250 FIRESTONE BLVD	2/14/2014	6521000.000000	6521000.000000	1800300.000000	245115	59085	sf	3693	cf
Infiltration BMP	Existing	8018 TELEGRAPH	8/20/2004	6526800.000000	6526800.000000	1809400.000000	246106	35437	sf	2215	cf
Infiltration BMP	Existing	7447 FIRESTONE BLVD	7/9/2009	6516971.590923	6516971.590923	1803474.089243	246102	43124	sf	2192	cf
Infiltration BMP	Existing	9126 FLORENCE	4/25/2008	6526980.883730	6526980.883730	1802613.015890	245119	29248	sf	1828	cf
Infiltration BMP	Existing	11111 OLD RIVER SCHOOL	6/15/2004	6515500.000000	6515500.000000	1803800.000000	246102	27843	sf	1740	cf
Infiltration BMP	Existing	9634 WASHBURN	5/25/2004	6526574.558590	6526574.558590	1794738.334020	245118	35712	sf	2232	cf
Infiltration BMP	Existing	9475 FIRESTONE	9/20/2004	6527102.470060	6527102.470060	1797292.175990	245119	25078	sf	1567	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9125 IMPERIAL	9/17/2007	6520700.000000	6520700.000000	1792100.000000	245115	53104	sf	3319	cf
Infiltration BMP	Existing	11231 RIVES	4/25/2006	6518392.506170	6518392.506170	1802335.247680	246102	20250	sf	1266	cf
Infiltration BMP	Existing	7936 QUILL	8/23/2006	6515830.400000	6515830.400000	1795880.196930	246079	18984	sf	1187	cf
Infiltration BMP	Existing	8337 FONTANA	8/11/2005	6520206.194620	6520206.194620	1797870.434810	245114	36672	sf	2292	cf
Infiltration BMP	Existing	10225 LESTERFORD	6/22/2010	6530244.844140	6530244.844140	1800567.187010	245126	17718	sf	1107	cf
Infiltration BMP	Existing	7915 FLORENCE	8/11/2009	6522019.025220	6522019.025220	1805973.779210	246103	20192	sf	1262	cf
Infiltration BMP	Existing	11229 PARAMOUNT	3/16/2004	6519482.925030	6519482.925030	1801457.806750	246102	16453	sf	1028	cf
Infiltration BMP	Existing	8103 COLE	5/1/2007	6518213.448370	6518213.448370	1798049.118910	246077	0	sf	0	cf
Infiltration BMP	Existing	8722 BOYNE	7/1/2008	6521213.643060	6521213.643060	1795216.473800	245115	11390	sf	712	cf
Infiltration BMP	Existing	10612 LESTERFORD	6/14/2006	6529218.389270	6529218.389270	1798513.115960	245126	11390	sf	712	cf
Infiltration BMP	Existing	8444 LEXINGTON	4/24/2006	6524361.433930	6524361.433930	1803767.599820	246103	11390	sf	712	cf
Infiltration BMP	Existing	13221 BARLIN	10/10/2006	6516992.431610	6516992.431610	1789646.610200	245524	10125	sf	633	cf
Infiltration BMP	Existing	9611 GARNISH	6/7/2007	6529217.309540	6529217.309540	1803965.758960	245125	10125	sf	633	cf
Infiltration BMP	Existing	7118 PELLET	12/3/2008	6515184.074160	6515184.074160	1804905.113850	246104	10125	sf	633	cf
Infiltration BMP	Existing	9325 RIVES AM	2/14/2014	6522517.375370	6522517.375370	1808878.723180	246111	10125	sf	633	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9371 SUVA	3/13/2007	6529247.009310	6529247.009310	1803484.685240	245125	10125	sf	633	cf
Infiltration BMP	Existing	8556 FLORENCE	1/1/2006	6525137.675720	6525137.675720	1803770.147850	245125	8859	sf	554	cf
Infiltration BMP	Existing	9755 IMPERIAL	3/29/2006	6525700.000000	6525700.000000	1792200.000000	245114	8859	sf	554	cf
Infiltration BMP	Existing	10000 IMPERIAL	3/29/2006	6527246.839530	6527246.839530	1791706.604350	245118	8859	sf	554	cf
Infiltration BMP	Existing	10030 LESTERFORD	6/21/2010	6530953.991420	6530953.991420	1801165.004470	245125	8859	sf	554	cf
Infiltration BMP	Existing	7235 LUXOR	12/12/2005	6514593.326010	6514593.326010	1801941.887350	246079	8859	sf	554	cf
Infiltration BMP	Existing	8115 STEWART & GRAY	3/25/2009	6518648.406750	6518648.406750	1798495.150040	246077	11760	sf	735	cf
Infiltration BMP	Existing	9804 BROOKSHIRE	5/2/2007	6525737.765210	6525737.765210	1805415.750650	246103	7594	sf	475	cf
Infiltration BMP	Existing	7830 DANVERS	12/18/2008	6523967.248740	6523967.248740	1810379.348050	246106	7594	sf	475	cf
Infiltration BMP	Existing	8357 FLORENCE	11/29/2005	6524137.162990	6524137.162990	1804589.285090	246103	7594	sf	475	cf
Infiltration BMP	Existing	8562 FLORENCE	1/1/2006	6525210.620820	6525210.620820	1803736.004200	245125	7594	sf	475	cf
Infiltration BMP	Existing	10735 LAKEWOOD	1/19/2007	6524698.379320	6524698.379320	1800460.893140	245119	8640	sf	540	cf
Infiltration BMP	Existing	9732 ORIZABA	6/5/2008	6523842.356050	6523842.356050	1806158.297200	246103	7594	sf	475	cf
Infiltration BMP	Existing	12066 SAMOLINE	6/18/2010	6517119.562750	6517119.562750	1797806.070750	246079	7594	sf	475	cf
Infiltration BMP	Existing	7711 SECOND	6/21/2010	6518493.103400	6518493.103400	1802942.740750	246102	7594	sf	475	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9517 STOAKES	6/21/2010	6525287.319840	6525287.319840	1806612.266920	246103	7594	sf	475	cf
Infiltration BMP	Existing	12133 ANDERBERG	6/26/2009	6518010.879310	6518010.879310	1796818.463370	245115	6328	sf	396	cf
Infiltration BMP	Existing	9115 BROCK	6/21/2010	6524898.717190	6524898.717190	1808433.166330	246106	6328	sf	396	cf
Infiltration BMP	Existing	9541 CECILIA	6/23/2010	6528302.087900	6528302.087900	1798262.111790	245126	6328	sf	396	cf
Infiltration BMP	Existing	10243 CORD	11/4/2008	6528334.164460	6528334.164460	1801344.678940	245126	6328	sf	396	cf
Infiltration BMP	Existing	13108 CORNUTA	6/21/2010	6525701.475550	6525701.475550	1790449.882450	245113	6328	sf	396	cf
Infiltration BMP	Existing	8129 DACOSTA	8/5/2008	6523736.839560	6523736.839560	1805716.362640	246103	6328	sf	396	cf
Infiltration BMP	Existing	7247 DINWIDDIE	6/22/2010	6515896.418780	6515896.418780	1804170.223670	246104	6328	sf	396	cf
Infiltration BMP	Existing	12002A DOWNEY	8/24/2005	6519100.000000	6519100.000000	1797100.000000	245115	6328	sf	396	cf
Infiltration BMP	Existing	12002C DOWNEY	8/24/2005	6519100.000000	6519100.000000	1797100.000000	245115	6328	sf	396	cf
Infiltration BMP	Existing	8529 EUCALYPTUS	6/18/2010	6519136.171020	6519136.171020	1794210.333930	245115	6328	sf	396	cf
Infiltration BMP	Existing	9204 LA REINA	6/22/2010	6525799.255250	6525799.255250	1808110.827020	246103	6328	sf	396	cf
Infiltration BMP	Existing	9241 LUBEC	6/21/2010	6528410.398740	6528410.398740	1803633.947240	245125	6328	sf	396	cf
Infiltration BMP	Existing	10051 MATTOCK	9/25/2008	6530040.953970	6530040.953970	1801237.222590	245125	6328	sf	396	cf
Infiltration BMP	Existing	12273 PLANETT	6/21/2010	6518942.439290	6518942.439290	1795136.426680	245115	6328	sf	396	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9075 RAVILLER	4/9/2007	6527819.498980	6527819.498980	1805031.907810	245125	6328	sf	396	cf
Infiltration BMP	Existing	7149 ADWEN	5/31/2006	6514275.907390	6514275.907390	1803122.312290	246079	5062	sf	316	cf
Infiltration BMP	Existing	8703 ALAMEDA	9/14/2005	6520830.700880	6520830.700880	1795016.469260	245115	4594	sf	287	cf
Infiltration BMP	Existing	9242 APPLEBY	11/21/2008	6528866.478730	6528866.478730	1804798.824690	245125	5062	sf	316	cf
Infiltration BMP	Existing	9926 BELLDER	3/19/2007	6525715.329050	6525715.329050	1804487.716960	245125	5062	sf	316	cf
Infiltration BMP	Existing	11715 BELLFLOWER	6/15/2009	6523530.688010	6523530.688010	1796655.823230	245114	5062	sf	316	cf
Infiltration BMP	Existing	8019 BERGMAN	10/22/2008	6517711.829130	6517711.829130	1797726.503570	246077	5062	sf	316	cf
Infiltration BMP	Existing	8417 BIGBY	7/23/2007	6523908.146010	6523908.146010	1803525.055670	245119	5062	sf	316	cf
Infiltration BMP	Existing	10004 BIRCHDALE	1/23/2006	6525798.638290	6525798.638290	1803985.957400	245125	5062	sf	316	cf
Infiltration BMP	Existing	9951 BROOKSHIRE	6/18/2010	6525004.036100	6525004.036100	1804835.952720	246103	5062	sf	316	cf
Infiltration BMP	Existing	10927 BROOKSHIRE AV	2/14/2014	6522640.981090	6522640.981090	1800949.695110	245114	5062	sf	316	cf
Infiltration BMP	Existing	10304 CLANCEY	9/19/2008	6526762.243870	6526762.243870	1802017.295250	245119	5062	sf	316	cf
Infiltration BMP	Existing	7213 DINWIDDIE	6/21/2010	6515644.523280	6515644.523280	1804333.457340	246104	5062	sf	316	cf
Infiltration BMP	Existing	9245 DOWNEY	9/19/2007	6525582.317560	6525582.317560	1807792.114420	246103	5062	sf	316	cf
Infiltration BMP	Existing	12002B DOWNEY	8/24/2005	6519100.000000	6519100.000000	1797100.000000	245115	5062	sf	316	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	12002D DOWNEY	8/24/2005	6519100.000000	6519100.000000	1797100.000000	245115	5062	sf	316	cf
Infiltration BMP	Existing	10250 EGLISE AV	2/14/2014	6528202.138900	6528202.138900	1801366.096440	245126	5062	sf	316	cf
Infiltration BMP	Existing	8719 ELMONT	6/18/2010	6526144.563940	6526144.563940	1809393.110180	246106	5062	sf	316	cf
Infiltration BMP	Existing	9355 FLORENCE	7/30/2007	6528769.559400	6528769.559400	1801814.385750	245125	5062	sf	316	cf
Infiltration BMP	Existing	9252 GALLATIN	3/29/2006	6528859.757520	6528859.757520	1804394.594600	245125	5062	sf	316	cf
Infiltration BMP	Existing	9553 GALLATIN	7/28/2004	6530910.776140	6530910.776140	1803037.898220	245125	5062	sf	316	cf
Infiltration BMP	Existing	9724 GARNISH	1/14/2008	6529062.109120	6529062.109120	1803453.035240	245125	5062	sf	316	cf
Infiltration BMP	Existing	8610 GUATEMALA	10/24/2006	6524386.905480	6524386.905480	1811339.167280	246106	5062	sf	316	cf
Infiltration BMP	Existing	10214 HORLEY	8/14/2007	6520372.544870	6520372.544870	1806355.591210	246102	5062	sf	316	cf
Infiltration BMP	Existing	10513 JULIUS	1/22/2009	6518877.932890	6518877.932890	1805532.376750	246102	5062	sf	316	cf
Infiltration BMP	Existing	9204 LA REINA	4/18/2007	6525799.255250	6525799.255250	1808110.827020	246103	5062	sf	316	cf
Infiltration BMP	Existing	9528 LEMORAN	8/29/2008	6529000.799820	6529000.799820	1804066.473220	245125	5062	sf	316	cf
Infiltration BMP	Existing	7334 LUXOR	4/25/2007	6514999.892740	6514999.892740	1801407.207050	246079	5062	sf	316	cf
Infiltration BMP	Existing	9226 MANZANAR	7/8/2005	6526470.419470	6526470.419470	1806685.422630	246103	5062	sf	316	cf
Infiltration BMP	Existing	10524 MATTOCK	2/5/2009	6528788.349750	6528788.349750	1799096.345380	245126	5062	sf	316	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	12123 ORIZABA	12/28/2005	6517943.193960	6517943.19 3960	1797041.7527 50	245115	5062	sf	316	cf
Infiltration BMP	Existing	7130 PELLET	6/4/2008	6515276.387650	6515276.38 7650	1804845.3114 40	246104	5062	sf	316	cf
Infiltration BMP	Existing	8322 PURITAN	6/14/2007	6516164.281440	6516164.28 1440	1791774.5588 40	245524	5062	sf	316	cf
Infiltration BMP	Existing	7312 RIO FLORA	6/18/2010	6516577.089870	6516577.08 9870	1804589.0403 90	246104	5062	sf	316	cf
Infiltration BMP	Existing	9331 SAMOLINE	2/17/2006	6523511.819100	6523511.81 9100	1808307.8190 60	246106	5062	sf	316	cf
Infiltration BMP	Existing	8015 SEVENTH	8/16/2005	6521322.893520	6521322.89 3520	1803640.9492 60	246103	5062	sf	316	cf
Infiltration BMP	Existing	7821 SIXTH	12/6/2005	6519846.881130	6519846.88 1130	1804004.4368 00	246102	5062	sf	316	cf
Infiltration BMP	Existing	8409 SIXTH	12/10/2008	6523050.669740	6523050.66 9740	1802016.6687 00	245114	5062	sf	316	cf
Infiltration BMP	Existing	9317 STAMPS	1/30/2007	6525356.702810	6525356.70 2810	1807182.8054 60	246103	5062	sf	316	cf
Infiltration BMP	Existing	9322 STAMPS	3/16/2006	6525453.602600	6525453.60 2600	1807062.9342 60	246103	5062	sf	316	cf
Infiltration BMP	Existing	10443 STAMPS	5/21/2008	6523061.022110	6523061.02 2110	1803394.2488 60	246103	5062	sf	316	cf
Infiltration BMP	Existing	10517 STAMPS	6/18/2010	6522812.240000	6522812.24 0000	1803043.7574 60	246103	5062	sf	316	cf
Infiltration BMP	Existing	9444 STOAKES	5/22/2007	6525587.983230	6525587.98 3230	1806625.5514 90	246103	5062	sf	316	cf
Infiltration BMP	Existing	8329 VISTA DEL RIO	6/18/2010	6526300.133280	6526300.13 3280	1808123.1165 20	246103	5062	sf	316	cf
Infiltration BMP	Existing	8368 VISTA DEL RIO	6/1/2007	6526427.553640	6526427.55 3640	1807729.5966 30	246103	5062	sf	316	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8543 ALBIA	1/1/2006	6520215.566510	6520215.56 6510	1795689.2129 70	245115	3797	sf	237	cf
Infiltration BMP	Existing	7162 BENARES	1/1/2008	6514067.610360	6514067.61 0360	1802493.2171 60	246079	3797	sf	237	cf
Infiltration BMP	Existing	12812 BLODGETT	6/8/2009	6518629.647540	6518629.64 7540	1791208.7599 70	245115	3797	sf	237	cf
Infiltration BMP	Existing	9503 BROCK AV	2/14/2014	6524115.247920	6524115.24 7920	1807488.0103 30	246106	3797	sf	237	cf
Infiltration BMP	Existing	9045 BUCKLES	12/11/2008	6523278.581350	6523278.58 1350	1796905.3004 70	245114	3797	sf	237	cf
Infiltration BMP	Existing	10045 CHANEY	7/5/2007	6527656.534860	6527656.53 4860	1802672.8718 00	245125	3797	sf	237	cf
Infiltration BMP	Existing	8714 CHEROKEE	5/1/2007	6525056.428300	6525056.42 8300	1801833.4891 70	245119	3797	sf	237	cf
Infiltration BMP	Existing	10729 CLANCEY	7/5/2007	6525292.127080	6525292.12 7080	1799996.4603 70	245119	3797	sf	237	cf
Infiltration BMP	Existing	8215 COMOLETTE	5/18/2006	6516024.585540	6516024.58 5540	1792904.8960 40	246077	3563	sf	223	cf
Infiltration BMP	Existing	7809 DACOSTA	10/5/2007	6521756.096640	6521756.09 6640	1806979.8841 60	246106	3797	sf	237	cf
Infiltration BMP	Existing	10424 DOLAN AV	2/14/2014	6523609.999510	6523609.99 9510	1803226.0994 70	245119	3797	sf	237	cf
Infiltration BMP	Existing	12337 DUNROBIN	6/21/2010	6524854.924990	6524854.92 4990	1793158.9107 10	245114	3797	sf	237	cf
Infiltration BMP	Existing	13234 DUNROBIN	9/30/2005	6525046.618370	6525046.61 8370	1789885.6308 70	245114	3797	sf	237	cf
Infiltration BMP	Existing	12612 EASTBROOK	5/30/2006	6525374.680490	6525374.68 0490	1791988.6293 20	245114	3797	sf	237	cf
Infiltration BMP	Existing	9400 FLORENCE	7/8/2005	6528900.299250	6528900.29 9250	1801380.0029 80	245126	3797	sf	237	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7823 FOURTH PL	9/16/2005	6519381.530610	6519381.530610	1803107.418050	246102	3797	sf	237	cf
Infiltration BMP	Existing	7826 GAINFORD	10/13/2005	6521963.408230	6521963.408230	1806968.662960	246106	3797	sf	237	cf
Infiltration BMP	Existing	7909 GALLATIN	4/27/2006	6523955.572760	6523955.572760	1809190.106160	246106	3797	sf	237	cf
Infiltration BMP	Existing	9118 GARNISH	6/21/2010	6529677.777690	6529677.777690	1805040.238300	245125	3797	sf	237	cf
Infiltration BMP	Existing	12752 GLYNN	6/18/2010	6516929.257070	6516929.257070	1792615.717350	245524	3797	sf	237	cf
Infiltration BMP	Existing	9116 HALEDON	3/2/2006	6528925.738880	6528925.738880	1805732.953010	245125	3797	sf	237	cf
Infiltration BMP	Existing	12819 IBBETSON	11/23/2005	6525827.025010	6525827.025010	1791350.711010	245114	3797	sf	237	cf
Infiltration BMP	Existing	9528 LEMORAN	8/26/2008	6528914.390000	6528914.390000	1804053.870620	245125	3797	sf	237	cf
Infiltration BMP	Existing	10514 LESTERFORD	2/14/2006	6529382.491640	6529382.491640	1798787.162960	245126	3797	sf	237	cf
Infiltration BMP	Existing	9030 LUBEC	2/9/2006	6526996.357320	6526996.357320	1804242.372880	245125	3797	sf	237	cf
Infiltration BMP	Existing	9264 LUBEC	4/19/2006	6528519.099740	6528519.099740	1803331.221940	245125	3797	sf	237	cf
Infiltration BMP	Existing	8545 LUBEC ST	2/14/2014	6525866.355120	6525866.355120	1805123.134500	246103	3797	sf	237	cf
Infiltration BMP	Existing	9247 MANZANAR	10/30/2006	6526227.935330	6526227.935330	1806695.994430	246103	3797	sf	237	cf
Infiltration BMP	Existing	7866 MELVA	6/20/2006	6516126.027390	6516126.027390	1797191.628010	246079	3797	sf	237	cf
Infiltration BMP	Existing	12109 MORNING	5/16/2006	6516408.716280	6516408.716280	1797765.727430	246079	3797	sf	237	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7332 NADA	6/18/2007	6514319.703850	6514319.703850	1800394.247560	246079	3797	sf	237	cf
Infiltration BMP	Existing	7334 NADA	6/18/2007	6514319.703850	6514319.703850	1800394.247560	246079	3797	sf	237	cf
Infiltration BMP	Existing	9821 NEWVILLE	7/30/2007	6530987.438110	6530987.438110	1802116.080780	245125	3797	sf	237	cf
Infiltration BMP	Existing	10268 NEWVILLE	4/24/2007	6529747.604150	6529747.604150	1800228.046080	245126	3797	sf	237	cf
Infiltration BMP	Existing	12280 ORIZABA	6/18/2010	6517505.248620	6517505.248620	1795784.740290	246077	3797	sf	237	cf
Infiltration BMP	Existing	10404 PANGBORN	6/18/2010	6528952.556500	6528952.556500	1800031.154520	245126	3797	sf	237	cf
Infiltration BMP	Existing	12531 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	3797	sf	237	cf
Infiltration BMP	Existing	12537 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	3797	sf	237	cf
Infiltration BMP	Existing	11994 POMERING	2/23/2005	6514993.390330	6514993.390330	1799517.781680	246079	3797	sf	237	cf
Infiltration BMP	Existing	9525 QUINN	2/8/2007	6528803.711540	6528803.711540	1799421.544220	245126	3797	sf	237	cf
Infiltration BMP	Existing	8048 QUOIT	1/21/2009	6516443.407630	6516443.407630	1795348.218010	246077	3797	sf	237	cf
Infiltration BMP	Existing	12326 SAMOLINE	8/29/2008	6516269.535370	6516269.535370	1796118.615320	246077	3797	sf	237	cf
Infiltration BMP	Existing	12504 SMALLWOOD	9/30/2008	6515227.996100	6515227.996100	1795705.820110	246079	3797	sf	237	cf
Infiltration BMP	Existing	9520 STEWART & GRAY	4/10/2008	6526628.650930	6526628.650930	1796061.800920	245118	3797	sf	237	cf
Infiltration BMP	Existing	7411 THIRD	6/2/2006	6517216.302090	6517216.302090	1804140.837740	246102	3797	sf	237	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	12706 WHITEWOOD	9/20/2007	6520505.791550	6520505.791550	1791390.733010	245115	3797	sf	237	cf
Infiltration BMP	Existing	9049 HALL ROAD	2/9/2007	6523684.587500	6523684.587500	1797586.831540	245114	2531	sf	158	cf
Infiltration BMP	Existing	7118 ADWEN	1/27/2006	6513895.884030	6513895.884030	1803086.756410	246100	2531	sf	158	cf
Infiltration BMP	Existing	13202 BARLIN	2/14/2007	6517303.317510	6517303.317510	1789688.349400	245524	2531	sf	158	cf
Infiltration BMP	Existing	10216 BELLMAN	1/5/2009	6525703.110200	6525703.110200	1803293.056930	245119	2531	sf	158	cf
Infiltration BMP	Existing	11809 BELLMAN	2/8/2006	6521732.804620	6521732.804620	1797303.369450	245114	2531	sf	158	cf
Infiltration BMP	Existing	7117 BENARES	8/10/2006	6513814.981610	6513814.981610	1802936.506930	246079	2531	sf	158	cf
Infiltration BMP	Existing	9108 BIGBY	11/23/2005	6526215.785230	6526215.785230	1801649.270450	245119	2531	sf	158	cf
Infiltration BMP	Existing	10213 BIRCHDALE	4/19/2006	6525304.414970	6525304.414970	1803562.084330	245119	2531	sf	158	cf
Infiltration BMP	Existing	9004 BIRCHLEAF	3/7/2007	6527047.235450	6527047.235450	1808159.837050	246103	2531	sf	158	cf
Infiltration BMP	Existing	13126 BLODGETT	8/18/2005	6517829.686700	6517829.686700	1789824.186060	245115	2531	sf	158	cf
Infiltration BMP	Existing	9508 BROCK	2/27/2006	6524228.012180	6524228.012180	1807355.118100	246103	2531	sf	158	cf
Infiltration BMP	Existing	7418 BROOKMILL	7/25/2008	6515791.043440	6515791.043440	1801624.672750	246079	2531	sf	158	cf
Infiltration BMP	Existing	12201 BROOKSHIRE	6/22/2010	6519506.452440	6519506.452440	1795585.950880	245115	2531	sf	158	cf
Infiltration BMP	Existing	7942 BRUNACHE	11/28/2005	6517219.149000	6517219.149000	1798061.073260	246079	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9349 CECILIA	9/25/2008	6527282.306940	6527282.306940	1798988.874460	245126	2531	sf	158	cf
Infiltration BMP	Existing	9365 CECILIA	6/18/2010	6527411.791310	6527411.791310	1798910.665650	245126	2531	sf	158	cf
Infiltration BMP	Existing	9608 CECILIA	1/1/2007	6528406.351870	6528406.351870	1798010.127160	245126	2531	sf	158	cf
Infiltration BMP	Existing	9624 CEDARTREE	8/8/2005	6531911.946630	6531911.946630	1804673.812930	245127	2531	sf	158	cf
Infiltration BMP	Existing	8519 CLETA	9/10/2007	6521470.081710	6521470.081710	1798172.541560	245114	2531	sf	158	cf
Infiltration BMP	Existing	7803 CONKLIN	9/2/2005	6513317.560580	6513317.560580	1793980.901190	246077	2297	sf	144	cf
Infiltration BMP	Existing	12816 CORNUTA	10/9/2006	6525701.592160	6525701.592160	1791350.505200	245114	2531	sf	158	cf
Infiltration BMP	Existing	8018 DANVERS	1/26/2009	6524882.345060	6524882.345060	1809453.159850	246106	2531	sf	158	cf
Infiltration BMP	Existing	8517 DEVENIR	10/11/2005	6517399.640210	6517399.640210	1791811.493450	245115	2531	sf	158	cf
Infiltration BMP	Existing	8049 DINSDALE	6/15/2006	6522974.989820	6522974.989820	1805624.556380	246103	2531	sf	158	cf
Infiltration BMP	Existing	9317 DINSDALE	11/5/2008	6528560.545810	6528560.545810	1802232.852640	245125	2531	sf	158	cf
Infiltration BMP	Existing	8510 DONOVAN	7/5/2005	6519046.837890	6519046.837890	1794446.597550	245115	2531	sf	158	cf
Infiltration BMP	Existing	8415 DONOVAN ST	2/14/2014	6518508.946270	6518508.946270	1795018.898890	245115	2531	sf	158	cf
Infiltration BMP	Existing	9635 DOWNEY	7/15/2004	6524420.085960	6524420.085960	1806308.452290	246103	2531	sf	158	cf
Infiltration BMP	Existing	9830 DOWNEY	1/1/2006	6524176.121770	6524176.121770	1805651.929490	246103	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	12718 DOWNEY	8/30/2007	6516814.229160	6516814.229160	1793075.140590	245524	2531	sf	158	cf
Infiltration BMP	Existing	12650 DUNROBIN	7/27/2007	6525045.587920	6525045.587920	1791614.482510	245114	2531	sf	158	cf
Infiltration BMP	Existing	9067 EGLISE	9/30/2005	6530265.716940	6530265.716940	1805184.414240	245127	2531	sf	158	cf
Infiltration BMP	Existing	9131 EGLISE	1/16/2009	6529904.336320	6529904.336320	1804464.041860	245125	2531	sf	158	cf
Infiltration BMP	Existing	8573 ELEVENTH	4/24/2006	6525253.900610	6525253.900610	1803595.328980	245119	2531	sf	158	cf
Infiltration BMP	Existing	9061 FARM ST	2/14/2014	6526099.027600	6526099.027600	1801582.141470	245119	2531	sf	158	cf
Infiltration BMP	Existing	7936 FOURTH	1/26/2006	6520005.666040	6520005.666040	1802880.634680	246103	2531	sf	158	cf
Infiltration BMP	Existing	7829 FOURTH PL	2/14/2014	6519381.530610	6519381.530610	1803107.418050	246102	2531	sf	158	cf
Infiltration BMP	Existing	7528 GAINFORD	6/18/2010	6520331.076350	6520331.076350	1807734.704270	246106	1266	sf	79	cf
Infiltration BMP	Existing	8150 GALLATIN	1/14/2008	6524851.065410	6524851.065410	1807922.731550	246103	2531	sf	158	cf
Infiltration BMP	Existing	9068 GALLATIN	7/18/2005	6527754.167230	6527754.167230	1805244.499940	245125	2531	sf	158	cf
Infiltration BMP	Existing	12703 GLENSHIRE	8/18/2006	6520090.968440	6520090.968440	1791341.816710	245115	2531	sf	158	cf
Infiltration BMP	Existing	8703 GUATEMALA	6/18/2010	6523747.929510	6523747.929510	1811239.685330	246111	2531	sf	158	cf
Infiltration BMP	Existing	9903 GUATEMALA	6/21/2010	6519189.043810	6519189.043810	1808530.913060	246111	2531	sf	158	cf
Infiltration BMP	Existing	9208 HALEDON	3/29/2007	6528788.981770	6528788.981770	1805412.621690	245125	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9083 HALL	12/8/2005	6524025.781090	6524025.781090	1797583.104370	245114	2531	sf	158	cf
Infiltration BMP	Existing	10348 HASTY	9/14/2006	6528480.545700	6528480.545700	1800482.839460	245126	2531	sf	158	cf
Infiltration BMP	Existing	7844 HONDO	7/8/2005	6515417.898670	6515417.898670	1796530.778030	246079	2531	sf	158	cf
Infiltration BMP	Existing	9244 HORLEY	6/22/2006	6522498.248530	6522498.248530	1809199.750130	246111	2531	sf	158	cf
Infiltration BMP	Existing	12612 IBBETSON	2/9/2007	6526008.655610	6526008.655610	1792000.536540	245114	2531	sf	158	cf
Infiltration BMP	Existing	7214 IRWINGROVE	8/17/2007	6517736.835580	6517736.835580	1807424.228480	246104	2531	sf	158	cf
Infiltration BMP	Existing	10209 JULIUS	6/21/2010	6519702.452650	6519702.452650	1806880.883230	246102	2531	sf	158	cf
Infiltration BMP	Existing	10341 JULIUS	6/4/2008	6519700.000000	6519700.000000	1806100.000000	246102	2531	sf	158	cf
Infiltration BMP	Existing	12313 JULIUS	6/21/2010	6514155.209020	6514155.209020	1797936.932020	246079	2531	sf	158	cf
Infiltration BMP	Existing	7944 KINGBEE	5/31/2007	6516311.045420	6516311.045420	1796702.710410	246079	2531	sf	158	cf
Infiltration BMP	Existing	9605 LA REINA	6/18/2010	6524325.141120	6524325.141120	1806744.664340	246103	2531	sf	158	cf
Infiltration BMP	Existing	10074 LESTERFORD	4/12/2006	6530716.286370	6530716.286370	1800772.683680	245125	2531	sf	158	cf
Infiltration BMP	Existing	9626 LUBEC	6/21/2005	6530889.535260	6530889.535260	1801910.718740	245125	2531	sf	158	cf
Infiltration BMP	Existing	7156 LUXOR	10/28/2005	6513800.826420	6513800.826420	1802169.595300	246100	2531	sf	158	cf
Infiltration BMP	Existing	9202 MANZANAR	4/13/2004	6526663.177850	6526663.177850	1806830.315690	246103	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9020 MARGARET	10/2/2006	6523822.925930	6523822.925930	1798066.530690	245114	2531	sf	158	cf
Infiltration BMP	Existing	9127 MELDAR	4/29/2004	6526710.714590	6526710.714590	1807437.827920	246103	2531	sf	158	cf
Infiltration BMP	Existing	11814 MORNING	9/2/2005	6517648.916460	6517648.916460	1799680.107480	246077	2531	sf	158	cf
Infiltration BMP	Existing	7440 MULLER	11/7/2006	6518162.654940	6518162.654940	1805120.460880	246102	2531	sf	158	cf
Infiltration BMP	Existing	12334 ORIZABA	5/5/2005	6517231.678930	6517231.678930	1795384.927500	246077	2531	sf	158	cf
Infiltration BMP	Existing	9311 OTTO	2/2/2008	6528809.245500	6528809.245500	1802513.951810	245125	2531	sf	158	cf
Infiltration BMP	Existing	10436 PANGBORN	7/6/2006	6528781.443840	6528781.443840	1799746.387720	245126	2531	sf	158	cf
Infiltration BMP	Existing	12533 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12531 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12531 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12533 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12533 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12533 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12535 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12535 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	12535 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12535 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12537 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	12537 PARAMOUNT	9/11/2003	6515510.297280	6515510.297280	1795114.190420	246079	2531	sf	158	cf
Infiltration BMP	Existing	9008 PARROT	6/22/2010	6524997.125330	6524997.125330	1808680.720210	246106	2531	sf	158	cf
Infiltration BMP	Existing	9530 PARROT	10/11/2006	6523866.950960	6523866.950960	1807305.627380	246103	2531	sf	158	cf
Infiltration BMP	Existing	7125 PELLET	11/21/2005	6515366.521160	6515366.521160	1805107.133170	246104	2531	sf	158	cf
Infiltration BMP	Existing	7335 PELLET	2/15/2007	6516661.302200	6516661.302200	1804268.401510	246104	2531	sf	158	cf
Infiltration BMP	Existing	7348 PELLET	6/22/2010	6516619.400060	6516619.400060	1803975.379460	246102	2531	sf	158	cf
Infiltration BMP	Existing	10433 PICO VISTA	6/21/2010	6529704.381130	6529704.381130	1799155.408730	245126	2531	sf	158	cf
Infiltration BMP	Existing	7629 PIVOT	6/4/2008	6517523.064870	6517523.064870	1802428.507060	246079	2531	sf	158	cf
Infiltration BMP	Existing	11962 POMERING	2/24/2006	6515175.131420	6515175.131420	1799743.806870	246079	2531	sf	158	cf
Infiltration BMP	Existing	8133 PRISCILLA	6/22/2010	6515078.400000	6515078.400000	1792153.440000	246077	2531	sf	158	cf
Infiltration BMP	Existing	7603 QUILL	2/28/2007	6514155.935840	6514155.935840	1797151.984960	246079	2531	sf	158	cf
Infiltration BMP	Existing	11539 RICHEON	7/8/2005	6517174.382020	6517174.382020	1801464.078770	246079	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	6545 RIVERGROVE	10/11/2005	6520696.757140	6520696.757140	1811248.378990	246111	2531	sf	158	cf
Infiltration BMP	Existing	9320 SAMOLINE	11/3/2006	6523716.410960	6523716.410960	1808296.703240	246106	2531	sf	158	cf
Infiltration BMP	Existing	9602 SAMOLINE	11/23/2005	6523146.135200	6523146.135200	1807399.732010	246103	2531	sf	158	cf
Infiltration BMP	Existing	12015 SAMOLINE	9/29/2008	6517129.601540	6517129.601540	1798409.043860	246079	2531	sf	158	cf
Infiltration BMP	Existing	12048 SAMOLINE	6/22/2010	6517021.712450	6517021.712450	1798014.455830	246079	2531	sf	158	cf
Infiltration BMP	Existing	7962 SECOND	10/3/2007	6519694.108620	6519694.108620	1801968.426700	246102	2531	sf	158	cf
Infiltration BMP	Existing	7712 SEVERY ST	1/1/2008	6524575.222650	6524575.222650	1807124.160130	246103	2531	sf	158	cf
Infiltration BMP	Existing	7331 SHADYOAK	1/16/2009	6521597.847660	6521597.847660	1810725.646550	246111	2531	sf	158	cf
Infiltration BMP	Existing	9103 SHERIDELL	10/29/2007	6528594.889520	6528594.889520	1806159.584670	245125	2531	sf	158	cf
Infiltration BMP	Existing	8345 SIXTH	4/23/2008	6522663.428460	6522663.428460	1802257.170290	245114	2531	sf	158	cf
Infiltration BMP	Existing	9124 STOAKES	4/29/2004	6526659.033140	6526659.033140	1807538.875170	246103	2531	sf	158	cf
Infiltration BMP	Existing	9906 TECUM	8/26/2008	6519710.324270	6519710.324270	1808196.223590	246111	2531	sf	158	cf
Infiltration BMP	Existing	9520 TELEGRAPH	12/4/2008	6531301.476840	6531301.476840	1805512.099740	245127	2531	sf	158	cf
Infiltration BMP	Existing	8302 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	1840	sf	115	cf
Infiltration BMP	Existing	8304 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8306 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8308 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8310 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8312 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8314 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8316 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8318 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8320 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8322 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8324 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8326 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8328 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8330 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8332 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8334 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8336 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8338 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8340 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8342 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8344 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8346 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8348 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8350 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	8352 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	2531	sf	158	cf
Infiltration BMP	Existing	7438 THIRD	11/10/2005	6517353.808450	6517353.808450	1803828.489190	246102	2531	sf	158	cf
Infiltration BMP	Existing	7955 THIRD	1/30/2006	6519871.299810	6519871.299810	1802440.525110	246103	2531	sf	158	cf
Infiltration BMP	Existing	9819 TRISTAN	11/19/2007	6526302.584780	6526302.584780	1804524.383680	245125	2531	sf	158	cf
Infiltration BMP	Existing	8555 VIA AMORITA	10/27/2008	6524751.467620	6524751.467620	1803150.610950	245119	2531	sf	158	cf
Infiltration BMP	Existing	9631 WILEY BURKE	3/27/2006	6521095.475640	6521095.475640	1808618.175130	246106	2531	sf	158	cf
Infiltration BMP	Existing	10419 WILEY BURKE	3/7/2008	6519382.492080	6519382.492080	1805731.311650	246102	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7319 ADWEN	2/22/2006	6515346.754980	6515346.754980	1802425.342900	246079	1266	sf	79	cf
Infiltration BMP	Existing	13033 AIRPOINT	6/14/2010	6517837.198260	6517837.198260	1790420.981040	245115	1266	sf	79	cf
Infiltration BMP	Existing	8446 ALAMEDA	6/24/2005	6519341.878190	6519341.878190	1795502.737620	245115	1266	sf	79	cf
Infiltration BMP	Existing	9336 APPLEBY	3/9/2006	6529377.514420	6529377.514420	1804389.744220	245125	1266	sf	79	cf
Infiltration BMP	Existing	9540 ARDINE	1/1/2006	6527800.346060	6527800.346060	1797420.079620	245119	1266	sf	79	cf
Infiltration BMP	Existing	7849 ARNETT	7/8/2005	6518395.700160	6518395.700160	1801138.921810	246079	1266	sf	79	cf
Infiltration BMP	Existing	8645 BAYSINGER	11/10/2005	6525612.031290	6525612.031290	1803108.706240	245119	1266	sf	79	cf
Infiltration BMP	Existing	9210 BELCHER	10/12/2006	6519891.840050	6519891.840050	1789806.904790	245115	1266	sf	79	cf
Infiltration BMP	Existing	9245 BELCHER	9/4/2007	6520247.532430	6520247.532430	1789967.036150	245115	1266	sf	79	cf
Infiltration BMP	Existing	10234 BELCHER	6/18/2010	6527119.239350	6527119.239350	1789810.183210	245113	1266	sf	79	cf
Infiltration BMP	Existing	10285 BELCHER	6/21/2010	6527612.081010	6527612.081010	1789959.646450	245118	1266	sf	79	cf
Infiltration BMP	Existing	10028 BELDER	1/1/2006	6525360.965940	6525360.965940	1803913.208580	245125	1266	sf	79	cf
Infiltration BMP	Existing	10304 BELLMAN	6/1/2005	6525418.498520	6525418.498520	1803041.069680	245119	1266	sf	79	cf
Infiltration BMP	Existing	11014 BENFIELD	6/24/2008	6531918.630750	6531918.630750	1797937.959120	245122	1266	sf	79	cf
Infiltration BMP	Existing	9324 BIRCHBARK	10/7/2005	6524879.129350	6524879.129350	1807661.831210	246103	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7847 BLANDWOOD	6/29/2006	6525016.522210	6525016.522210	1811074.341940	246106	1266	sf	79	cf
Infiltration BMP	Existing	8415 BORSON	10/9/2006	6517421.536650	6517421.536650	1792735.849280	245115	1266	sf	79	cf
Infiltration BMP	Existing	8710 BOYNE	6/29/2006	6521119.595500	6521119.595500	1795272.757840	245115	1266	sf	79	cf
Infiltration BMP	Existing	8910 BROCK	2/3/2009	6525582.226600	6525582.226600	1808734.892600	246106	1266	sf	79	cf
Infiltration BMP	Existing	9702 BROCK	9/25/2006	6523765.203820	6523765.203820	1806580.253440	246103	1266	sf	79	cf
Infiltration BMP	Existing	9730 BROCK	10/16/2009	6523625.354460	6523625.354460	1806340.478590	246103	1266	sf	79	cf
Infiltration BMP	Existing	7550 BROOKMILL	9/25/2006	6516432.435790	6516432.435790	1801137.496710	246079	1266	sf	79	cf
Infiltration BMP	Existing	10360 BROOKSHIRE	8/2/2005	6524254.056510	6524254.056510	1803200.425100	245119	1266	sf	79	cf
Infiltration BMP	Existing	9336 BUELL	5/4/2007	6527241.052050	6527241.052050	1799190.479610	245126	1266	sf	79	cf
Infiltration BMP	Existing	9408 BUELL	1/1/2007	6527563.840160	6527563.840160	1798993.546660	245126	1266	sf	79	cf
Infiltration BMP	Existing	10210 CASANES	7/20/2005	6529273.829610	6529273.829610	1801143.143100	245125	1266	sf	79	cf
Infiltration BMP	Existing	10308 CASANES	6/9/2005	6528827.020030	6528827.020030	1800415.364480	245126	1266	sf	79	cf
Infiltration BMP	Existing	10845 CASANES	12/4/2007	6527288.943480	6527288.943480	1798213.890680	245119	1266	sf	79	cf
Infiltration BMP	Existing	10922 CASANES	8/3/2005	6527279.490710	6527279.490710	1797849.792160	245119	1266	sf	79	cf
Infiltration BMP	Existing	8715 CAVEL	6/22/2010	6521261.550160	6521261.550160	1795688.489420	245115	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9707 CEDARTREE	5/25/2006	6532283.863380	6532283.863380	1804587.051690	245127	1266	sf	79	cf
Infiltration BMP	Existing	10260 CHANEY	6/21/2010	6527337.911630	6527337.911630	1801874.691650	245119	1266	sf	79	cf
Infiltration BMP	Existing	10362 CHANEY	9/4/2007	6526983.558290	6526983.558290	1801306.071650	245119	1266	sf	79	cf
Infiltration BMP	Existing	9246 CLANCEY	5/1/2007	6528479.118010	6528479.118010	1805448.947460	245125	1266	sf	79	cf
Infiltration BMP	Existing	10546 CLANCEY	5/26/2005	6525904.831900	6525904.831900	1800674.595520	245119	1266	sf	79	cf
Infiltration BMP	Existing	12658 COLDBROOK	6/25/2009	6524501.637760	6524501.637760	1791525.543010	245114	1266	sf	79	cf
Infiltration BMP	Existing	8111 COMOLETTE	12/18/2006	6515465.796840	6515465.796840	1793242.397990	246077	1266	sf	79	cf
Infiltration BMP	Existing	8140 COMOLETTE	12/2/2008	6515640.775000	6515640.775000	1792943.865000	246077	1266	sf	79	cf
Infiltration BMP	Existing	8316 COMOLETTE	5/23/2005	6516475.681440	6516475.681440	1792370.081790	245524	1266	sf	79	cf
Infiltration BMP	Existing	9325 CORD	3/21/2008	6529940.912480	6529940.912480	1803762.584020	245125	1266	sf	79	cf
Infiltration BMP	Existing	7732 COREY	1/8/2009	6515481.796500	6515481.796500	1798137.416600	246079	1266	sf	79	cf
Infiltration BMP	Existing	11810 CORRIGAN	3/4/2009	6523411.287590	6523411.287590	1796210.739300	245114	1266	sf	79	cf
Infiltration BMP	Existing	10925 CROSSDALE	6/9/2005	6532012.125130	6532012.125130	1798163.740010	245122	1266	sf	79	cf
Infiltration BMP	Existing	7757 DACOSTA	6/7/2005	6521506.383470	6521506.383470	1807138.583520	246106	1266	sf	79	cf
Infiltration BMP	Existing	8324 DAVIS	6/15/2005	6520852.481770	6520852.481770	1799213.987880	245114	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8517 DEVENIR	2/19/2008	6517399.640210	6517399.640210	1791811.493450	245115	1266	sf	79	cf
Infiltration BMP	Existing	7345 DINSDALE	9/29/2005	6519203.299320	6519203.299320	1808002.090250	246111	1266	sf	79	cf
Infiltration BMP	Existing	8330 DINSDALE	6/21/2010	6524002.238290	6524002.238290	1804838.107610	246103	1266	sf	79	cf
Infiltration BMP	Existing	10340 DOLAN	8/15/2007	6523856.967630	6523856.967630	1803630.622810	245119	1266	sf	79	cf
Infiltration BMP	Existing	12260 DOLAN	4/5/2006	6518910.565000	6518910.565000	1795264.305000	245115	1266	sf	79	cf
Infiltration BMP	Existing	12521 DOLAN	7/19/2007	6517914.404040	6517914.404040	1794175.419610	245115	1266	sf	79	cf
Infiltration BMP	Existing	12621 DOLAN	8/17/2007	6517501.190610	6517501.190610	1793293.644730	245115	1266	sf	79	cf
Infiltration BMP	Existing	12308 DOWNEY	4/19/2007	6518251.608680	6518251.608680	1795363.261670	245115	1266	sf	79	cf
Infiltration BMP	Existing	12532 DOWNEY	10/11/2005	6517442.718730	6517442.718730	1794104.887260	245115	1266	sf	79	cf
Infiltration BMP	Existing	12820 DOWNEY	5/17/2007	6516486.923440	6516486.923440	1792584.707230	245524	1266	sf	79	cf
Infiltration BMP	Existing	12603 DUNROBIN	6/22/2010	6524864.880980	6524864.880980	1792095.613000	245114	1266	sf	79	cf
Infiltration BMP	Existing	12643 DUNROBIN	11/21/2006	6524865.889210	6524865.889210	1791696.268120	245114	1266	sf	79	cf
Infiltration BMP	Existing	12818 DUNROBIN	12/15/2006	6525044.191110	6525044.191110	1791331.787300	245114	1266	sf	79	cf
Infiltration BMP	Existing	12823 DUNROBIN	2/12/2008	6524866.593650	6524866.593650	1791299.463030	245114	1266	sf	79	cf
Infiltration BMP	Existing	13024 DUNROBIN	5/24/2005	6525048.058670	6525048.058670	1790633.750860	245114	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	13240 DUNROBIN	10/1/2008	6525046.731200	6525046.73 1200	1789833.3483 60	245114	1266	sf	79	cf
Infiltration BMP	Existing	13638 EARNSHAW	9/16/2005	6516330.576340	6516330.57 6340	1788317.0376 30	245524	1266	sf	79	cf
Infiltration BMP	Existing	12155 EASTBROOK	9/16/2005	6525128.882510	6525128.88 2510	1794289.1827 20	245114	2297	sf	144	cf
Infiltration BMP	Existing	9125 EGLISE	1/24/2007	6529928.564580	6529928.56 4580	1804520.9632 70	245125	1266	sf	79	cf
Infiltration BMP	Existing	10213 EGLISE	10/14/2008	6528271.447820	6528271.44 7820	1801803.0931 00	245126	1266	sf	79	cf
Infiltration BMP	Existing	8331 EVEREST	2/21/2007	6517984.856770	6517984.85 6770	1794526.9943 30	245115	1266	sf	79	cf
Infiltration BMP	Existing	9037 FARM	6/18/2010	6525882.141210	6525882.14 1210	1801714.4807 20	245119	1266	sf	79	cf
Infiltration BMP	Existing	9542 FARM	11/15/2005	6529019.221950	6529019.22 1950	1799423.7001 60	245126	1266	sf	79	cf
Infiltration BMP	Existing	8445 FIFTH	6/24/2005	6523180.907390	6523180.90 7390	1801530.1633 40	245114	1266	sf	79	cf
Infiltration BMP	Existing	8529 FIFTH	9/23/2005	6523578.003250	6523578.00 3250	1801288.5437 80	245114	1266	sf	79	cf
Infiltration BMP	Existing	9221 FOSTER	2/16/2008	6519835.324440	6519835.32 4440	1789377.6648 80	245115	1266	sf	79	cf
Infiltration BMP	Existing	9303 FOSTER	8/9/2006	6520280.515660	6520280.51 5660	1789513.9416 70	245115	1266	sf	79	cf
Infiltration BMP	Existing	9536 FOSTORIA	10/13/2005	6527900.524680	6527900.52 4680	1797686.0012 50	245119	1266	sf	79	cf
Infiltration BMP	Existing	7339 GAINFORD	11/5/2007	6519739.997490	6519739.99 7490	1808338.9360 30	246111	1266	sf	79	cf
Infiltration BMP	Existing	8426 GAINFORD	1/7/2008	6524961.213810	6524961.21 3810	1805124.6024 10	246103	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	9315 GAINFORD	7/5/2005	6528715.710300	6528715.710300	1803034.881460	245125	1266	sf	79	cf
Infiltration BMP	Existing	9641 GAINFORD	10/16/2006	6530976.949360	6530976.949360	1801752.372100	245125	1266	sf	79	cf
Infiltration BMP	Existing	9357 GALLATIN	4/17/2006	6529509.957360	6529509.957360	1804133.004270	245125	1266	sf	79	cf
Infiltration BMP	Existing	8411 GALT	7/18/2007	6520931.662600	6520931.662600	1798681.676310	245114	1266	sf	79	cf
Infiltration BMP	Existing	8125 GARDENDALE	10/3/2007	6514840.842010	6514840.842010	1791988.219650	246077	1266	sf	79	cf
Infiltration BMP	Existing	7553 GLENCLIFF	11/5/2008	6521939.189570	6521939.189570	1809565.009220	246111	1266	sf	79	cf
Infiltration BMP	Existing	12615 GURLEY	9/8/2008	6516705.632650	6516705.632650	1793818.816440	246077	1266	sf	79	cf
Infiltration BMP	Existing	10557 HALEDON	3/22/2006	6525946.687500	6525946.687500	1800529.637640	245119	1266	sf	79	cf
Infiltration BMP	Existing	10714 HALEDON	7/11/2008	6525734.412480	6525734.412480	1799854.605530	245119	1266	sf	79	cf
Infiltration BMP	Existing	9101 HALL	7/19/2007	6524088.768660	6524088.768660	1797585.986810	245114	1266	sf	79	cf
Infiltration BMP	Existing	7416 HONDO	11/21/2007	6513414.170490	6513414.170490	1797767.919490	246079	1266	sf	79	cf
Infiltration BMP	Existing	7927 HONDO	1/8/2007	6515926.722240	6515926.722240	1796435.751150	246079	1266	sf	79	cf
Infiltration BMP	Existing	9228 HORLEY	7/20/2005	6522584.029360	6522584.029360	1809343.702000	246111	1266	sf	79	cf
Infiltration BMP	Existing	9929 HORLEY	6/23/2005	6520827.895940	6520827.895940	1807104.698370	246106	1266	sf	79	cf
Infiltration BMP	Existing	12316 HORLEY	1/1/2007	6515085.680000	6515085.680000	1797312.060000	246079	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	11544 HORTON	5/1/2006	6517050.314050	6517050.314050	1801482.158860	246079	1266	sf	79	cf
Infiltration BMP	Existing	12619 IBBETSON	12/26/2007	6525826.717640	6525826.717640	1791950.694670	245114	1266	sf	79	cf
Infiltration BMP	Existing	12816 IBBETSON	11/23/2005	6526008.922590	6526008.922590	1791350.504040	245114	1266	sf	79	cf
Infiltration BMP	Existing	9030 IOWA	8/29/2007	6523719.000250	6523719.000250	1797706.215730	245114	1266	sf	79	cf
Infiltration BMP	Existing	9036 IOWA	1/23/2006	6523761.535660	6523761.535660	1797679.990250	245114	1266	sf	79	cf
Infiltration BMP	Existing	7214 IRWINGROVE	2/7/2008	6517736.835580	6517736.835580	1807424.228480	246104	1266	sf	79	cf
Infiltration BMP	Existing	7425 IRWINGROVE	11/22/2005	6519037.305040	6519037.305040	1806826.286520	246102	1266	sf	79	cf
Infiltration BMP	Existing	7431 IVO	5/23/2005	6520452.019960	6520452.019960	1808862.657860	246106	1266	sf	79	cf
Infiltration BMP	Existing	12258 IZETTA	11/19/2008	6524718.529730	6524718.529730	1793607.751080	245114	1266	sf	79	cf
Infiltration BMP	Existing	11427 JULIUS	10/6/2005	6517068.729490	6517068.729490	1802337.821610	246079	1266	sf	79	cf
Infiltration BMP	Existing	7863 KINGBEE	6/2/2005	6515998.395150	6515998.395150	1797104.463380	246079	1266	sf	79	cf
Infiltration BMP	Existing	10633 LA REINA	6/7/2005	6521844.406030	6521844.406030	1802801.159980	246103	1266	sf	79	cf
Infiltration BMP	Existing	10726 LA REINA	9/20/2005	6521763.725850	6521763.725850	1802369.001800	246103	1266	sf	79	cf
Infiltration BMP	Existing	10717 LAKEWOOD	1/1/2005	6524762.764130	6524762.764130	1800632.321080	245119	1266	sf	79	cf
Infiltration BMP	Existing	13229 LAKEWOOD	8/30/2005	6518145.854860	6518145.854860	1789091.323220	245115	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8248 LANKIN	5/16/2007	6517152.534650	6517152.534650	1794608.293130	246077	1266	sf	79	cf
Infiltration BMP	Existing	13413 LAURELDALE	9/4/2007	6516097.983610	6516097.983610	1789503.029570	245524	1266	sf	79	cf
Infiltration BMP	Existing	9040 LEMORAN	9/16/2005	6529896.207920	6529896.207920	1805874.052840	245125	1266	sf	79	cf
Infiltration BMP	Existing	10225 LESTERFORD	12/22/2005	6530244.844140	6530244.844140	1800567.187010	245126	1266	sf	79	cf
Infiltration BMP	Existing	10415 LESTERFORD	6/22/2010	6529502.521580	6529502.521580	1799500.525910	245126	1266	sf	79	cf
Infiltration BMP	Existing	10730 LESTERFORD	6/8/2005	6528927.837490	6528927.837490	1798058.051080	245126	1266	sf	79	cf
Infiltration BMP	Existing	8020 LUBEC	3/8/2007	6523117.786070	6523117.786070	1806398.918760	246103	1266	sf	79	cf
Infiltration BMP	Existing	9230 LUBEC	9/30/2005	6528205.943320	6528205.943320	1803519.420650	245125	1266	sf	79	cf
Infiltration BMP	Existing	7259 LUXOR	1/1/2007	6514801.884280	6514801.884280	1801808.218080	246079	1266	sf	79	cf
Infiltration BMP	Existing	7315 LUXOR	3/16/2006	6514953.117040	6514953.117040	1801695.155730	246079	1266	sf	79	cf
Infiltration BMP	Existing	8444 LUXOR	11/10/2005	6520775.356850	6520775.356850	1797851.842110	245114	1266	sf	79	cf
Infiltration BMP	Existing	9102 MANZANAR	7/20/2005	6527192.246670	6527192.246670	1807219.965690	246103	1266	sf	79	cf
Infiltration BMP	Existing	10434 MANZANAR	6/7/2005	6523771.930100	6523771.930100	1803007.033470	245119	1266	sf	79	cf
Infiltration BMP	Existing	11109 MARBEL	7/20/2006	6523692.717760	6523692.717760	1799490.635090	245119	1266	sf	79	cf
Infiltration BMP	Existing	12108 MARBEL	1/31/2006	6521445.538760	6521445.538760	1795214.942010	245115	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7830 MELVA	1/1/2006	6515802.415360	6515802.41 5360	1797387.1088 60	246079	1266	sf	79	cf
Infiltration BMP	Existing	7844 MELVA	1/5/2006	6515910.196660	6515910.19 6660	1797321.9834 90	246079	1266	sf	79	cf
Infiltration BMP	Existing	12120 MORNING	8/14/2008	6516533.621320	6516533.62 1320	1797558.6810 60	246079	1266	sf	79	cf
Infiltration BMP	Existing	7339 NADA	7/8/2005	6514489.286480	6514489.28 6480	1800567.4110 80	246079	1266	sf	79	cf
Infiltration BMP	Existing	7351 NADA	6/23/2008	6514590.536380	6514590.53 6380	1800503.7741 90	246079	1266	sf	79	cf
Infiltration BMP	Existing	8202 NADA	1/9/2006	6518631.371590	6518631.37 1590	1797835.5424 30	245115	1266	sf	79	cf
Infiltration BMP	Existing	7415 NOREN	7/26/2005	6520794.671000	6520794.67 1000	1809286.2727 90	246111	1266	sf	79	cf
Infiltration BMP	Existing	9921 NORLAIN	11/3/2008	6519614.140210	6519614.14 0210	1807835.4358 30	246111	1266	sf	79	cf
Infiltration BMP	Existing	8127 ORANGE	6/23/2010	6517401.744430	6517401.74 4430	1796403.8417 80	246077	1266	sf	79	cf
Infiltration BMP	Existing	9554 ORIZABA	8/19/2005	6524235.753500	6524235.75 3500	1806817.6186 50	246103	1266	sf	79	cf
Infiltration BMP	Existing	12333 ORIZABA	1/23/2006	6517077.475660	6517077.47 5660	1795538.4352 60	246077	1266	sf	79	cf
Infiltration BMP	Existing	10834 PANGBORN	9/17/2007	6527760.431910	6527760.43 1910	1798051.7721 60	245119	1266	sf	79	cf
Infiltration BMP	Existing	7156 PELLET	6/22/2010	6515507.126970	6515507.12 6970	1804695.7518 90	246104	1266	sf	79	cf
Infiltration BMP	Existing	9466 PELLET	5/26/2005	6527082.799410	6527082.79 9410	1797550.7829 40	245119	1266	sf	79	cf
Infiltration BMP	Existing	10238 PICO VISTA	7/22/2008	6530559.495000	6530559.49 5000	1800212.2465 20	245126	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	7706 PIVOT	6/18/2010	6517776.543940	6517776.543940	1802077.153370	246079	1266	sf	79	cf
Infiltration BMP	Existing	11951 POMERING	6/18/2010	6515072.562230	6515072.562230	1799936.867790	246079	1266	sf	79	cf
Infiltration BMP	Existing	12010 POMERING	9/20/2005	6514897.027930	6514897.027930	1799318.472210	246079	1266	sf	79	cf
Infiltration BMP	Existing	7803 PURITAN	6/22/2010	6513186.710850	6513186.710850	1793767.422040	246077	1266	sf	79	cf
Infiltration BMP	Existing	8249 QUOIT	5/17/2007	6517406.484080	6517406.484080	1795006.472870	246077	1266	sf	79	cf
Infiltration BMP	Existing	8506 RAVILLER	6/22/2010	6526200.032280	6526200.032280	1805944.598850	246103	1266	sf	79	cf
Infiltration BMP	Existing	9441 RAVILLER	10/7/2005	6529831.524430	6529831.524430	1803323.207760	245125	1266	sf	79	cf
Infiltration BMP	Existing	7110 RIO FLORA	6/1/2010	6515643.202310	6515643.202310	1805187.382260	246104	1266	sf	79	cf
Infiltration BMP	Existing	7371 RIO HONDO PL	7/11/2005	6517283.740950	6517283.740950	1804924.767440	246104	1266	sf	79	cf
Infiltration BMP	Existing	10802 RIVES	3/23/2007	6519422.470020	6519422.470020	1803623.413330	246102	1266	sf	79	cf
Infiltration BMP	Existing	11916 RIVES	2/6/2007	6516737.168290	6516737.168290	1799258.165990	246079	1266	sf	79	cf
Infiltration BMP	Existing	10912 RYERSON	7/14/2005	6515882.754330	6515882.754330	1804962.955590	246104	1266	sf	79	cf
Infiltration BMP	Existing	9505 SAMOLINE	6/21/2010	6523279.038200	6523279.038200	1807936.970620	246106	1266	sf	79	cf
Infiltration BMP	Existing	9631 SAMOLINE	9/4/2007	6522855.010000	6522855.010000	1807250.890000	246103	1266	sf	79	cf
Infiltration BMP	Existing	12030 SAMOLINE	9/23/2005	6517133.868790	6517133.868790	1798177.361600	246079	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	12238 SAMOLINE	9/8/2006	6516738.176240	6516738.176240	1796883.684630	246079	1266	sf	79	cf
Infiltration BMP	Existing	7915 SECOND	3/23/2006	6519374.854020	6519374.854020	1802382.905560	246102	1266	sf	79	cf
Infiltration BMP	Existing	7816 SEVENTH	3/27/2007	6519884.790380	6519884.790380	1804163.292550	246102	1266	sf	79	cf
Infiltration BMP	Existing	8646 SEVENTH	1/3/2006	6524439.566780	6524439.566780	1801605.289810	245119	1266	sf	79	cf
Infiltration BMP	Existing	9225 SIDEVIEW	4/24/2006	6531114.889310	6531114.889310	1804872.365930	245127	1266	sf	79	cf
Infiltration BMP	Existing	8810 SMALLWOOD	6/20/2005	6524153.815510	6524153.815510	1810188.858090	246106	1266	sf	79	cf
Infiltration BMP	Existing	9264 SONGFEST	6/10/2008	6531394.983570	6531394.983570	1804360.661210	245127	1266	sf	79	cf
Infiltration BMP	Existing	7838 SPRINGER	11/21/2006	6515530.871940	6515530.871940	1796818.950680	246079	1266	sf	79	cf
Infiltration BMP	Existing	7844 SPRINGER	3/18/2008	6515582.250000	6515582.250000	1796787.835000	246079	1266	sf	79	cf
Infiltration BMP	Existing	10517 STAMPS	8/18/2005	6522812.240000	6522812.240000	1803043.757460	246103	1266	sf	79	cf
Infiltration BMP	Existing	9520 STEWART & GRAY	2/27/2009	6526628.650930	6526628.650930	1796061.800920	245118	1266	sf	79	cf
Infiltration BMP	Existing	8840 STOAKES	7/15/2005	6527643.045070	6527643.045070	1808263.273840	245125	1266	sf	79	cf
Infiltration BMP	Existing	11831 SUSAN	5/25/2006	6514568.915250	6514568.915250	1801466.560490	246079	1266	sf	79	cf
Infiltration BMP	Existing	8354 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	1266	sf	79	cf
Infiltration BMP	Existing	8356 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	1266	sf	79	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8358 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	1266	sf	79	cf
Infiltration BMP	Existing	8360 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	1266	sf	79	cf
Infiltration BMP	Existing	8362 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	1266	sf	79	cf
Infiltration BMP	Existing	8364 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	1266	sf	79	cf
Infiltration BMP	Existing	8366 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	1266	sf	79	cf
Infiltration BMP	Existing	8368 TELEGRAPH	1/5/2004	6526800.000000	6526800.000000	1809400.000000	246106	1266	sf	79	cf
Infiltration BMP	Existing	7420 THIRD	9/20/2007	6517202.761340	6517202.761340	1803926.714420	246102	1266	sf	79	cf
Infiltration BMP	Existing	7964 THIRD	2/21/2006	6519886.681280	6519886.681280	1802225.378910	246102	1266	sf	79	cf
Infiltration BMP	Existing	9532 TWEEDY	4/20/2007	6523025.939870	6523025.939870	1807743.953100	246106	1266	sf	79	cf
Infiltration BMP	Existing	7347 VIA RIO NIDO	8/1/2007	6518199.953350	6518199.953350	1806523.073370	246104	1266	sf	79	cf
Infiltration BMP	Existing	10419 WILEY BURKE	1/2/2008	6519382.492080	6519382.492080	1805731.311650	246102	1266	sf	79	cf
Infiltration BMP	Existing	10442 WILEY BURKE	1/1/2007	6519428.439440	6519428.439440	1805422.866650	246102	1266	sf	79	cf
Infiltration BMP	Existing	12639 WOODRUFF	12/22/2006	6526127.737740	6526127.737740	1791800.878460	245113	1266	sf	79	cf
Infiltration BMP	Existing	12356 DOWNEY	4/29/2004	6518006.757310	6518006.757310	1794978.083160	245115	5062	sf	316	cf
Infiltration BMP	Existing	10613 NEWVILLE	4/21/2004	6528761.027810	6528761.027810	1798786.621380	245126	2531	sf	158	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	10627 OLD RIVER SCHOOL	7/24/2003	6515233.048270	6515233.048270	1805631.128330	246104	174752	sf	10922	cf
Infiltration BMP	Existing	9215 HALL	12/9/2002	6524758.793890	6524758.793890	1797647.866960	245113	74592	sf	4662	cf
Infiltration BMP	Existing	10933 LAKEWOOD BLVD	10/5/2005	6524600.000000	6524600.000000	1800100.000000	245119	6400	sf	400	cf
Infiltration BMP	Existing	12322 SAMOLINE	7/8/2005	6516301.814120	6516301.814120	1796169.128220	246077	4256	sf	266	cf
Infiltration BMP	Existing	12731 LAKEWOOD	9/17/2003	6519215.285000	6519215.285000	1791371.090000	245115	2128	sf	133	cf
Infiltration BMP	Existing	12739 LAKEWOOD	9/17/2003	6519200.000000	6519200.000000	1791100.000000	245115	2128	sf	133	cf
Infiltration BMP	Existing	8927 BIRCHLEAF	7/11/2006	6527008.160170	6527008.160170	1808327.449830	246103	1056	sf	66	cf
Infiltration BMP	Existing	11929 POMERING	5/1/2006	6515108.241040	6515108.241040	1800149.473170	246079	1056	sf	66	cf
Infiltration BMP	Existing	12240 WOODRUFF	3/19/2010	6526758.991120	6526758.991120	1793878.747920	245118	300224	sf	18764	cf
Infiltration BMP	Existing	12222 WOODRUFF	9/14/2009	6526625.121210	6526625.121210	1794009.479990	245118	70200	sf	4388	cf
Infiltration BMP	Existing	7624 FIRESTONE	1/1/2008	6517500.000000	6517500.000000	1802600.000000	246079	41632	sf	2602	cf
Infiltration BMP	Existing	7714 STEWART & GRAY	4/9/2007	6516397.756580	6516397.756580	1799563.749470	246079	30016	sf	1876	cf
Infiltration BMP	Existing	9637 LAKEWOOD	10/2/2008	6526780.802630	6526780.802630	1805111.536210	245125	15136	sf	946	cf
Infiltration BMP	Existing	12428 BENEDICT	6/14/2007	6525687.022380	6525687.022380	1792528.538110	245114	8080	sf	505	cf
Infiltration BMP	Existing	7774 DINSDALE	2/14/2014	6521332.495780	6521332.495780	1806385.183840	246103	4680	sf	293	cf




Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMP	Existing	8030 IMPERIAL HWY	2/14/2014	6515729.368090	6515729.368090	1794471.493939	246077	41789	sf	2000	cf
Infiltration BMP	Existing	9623 IMPERIAL HWY	2/14/2014	6524482.209740	6524482.209740	1792569.983950	245114	35408	sf	2213	cf
Infiltration BMP	Existing	10531 LAKEWOOD BL	2/14/2014	6525178.634060	6525178.634060	1801497.338680	245119	5840	sf	365	cf
Infiltration BMP	Existing	8121 FOURTH ST	2/14/2014	6521147.926450	6521147.926450	1802216.858440	246103	4680	sf	293	cf
Infiltration BMP	Existing	8123 FOURTH ST	2/14/2014	6521147.926450	6521147.926450	1802216.858440	246103	4680	sf	293	cf
Infiltration BMP	Existing	8555 TENTH ST	2/14/2014	6524962.328390	6524962.328390	1803501.510410	245119	4680	sf	293	cf
Infiltration BMP	Existing	9356 BUELL ST	2/14/2014	6527425.774610	6527425.774610	1799078.145910	245126	3120	sf	195	cf
Infiltration BMP	Existing	8449 COLE ST	2/14/2014	6520362.597670	6520362.597670	1796910.373080	245115	1560	sf	98	cf



### D1.3. City of Lakewood

Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Flow-Through Treatment BMP	Existing	Filtterra Tree Wells (2)		Paramount & Arbor	33.843398	-118.159673	445521				
Infiltration BMP	Existing	Retention Basin at Cherry Cove Park			33.850296	-118.165478	446014				





## D1.4. City of Paramount

Type of BMP	Existing or Planned ?	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Bioswales	Existing	Landscape Swale	2012	Texaco/Alondra	33.889066	-118.171849	606071	37,500	sf	2109	cf
Bioswales	Existing	Landscape Swale	2012	Orange/Windmill	33.891602	-118.177436	606072	0.6	ac	1470	cf

DRAFT



## D1.5. City of Pico Rivera

Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Site-Scale Detention Basin	Existing	French drains at Smith Park	2013	6016 Rosemead Blvd				16	ac		
Site-Scale Detention Basin	Existing	French drains at Rio Vista	2013	Coffman Pico Road				7	ac		
Bioswales	Existing	Beverly Boulevard medians	2012	Beverly Blvd				5280	sf		
Permeable Pavement	Existing	Pico Park permeable pavement	2012	9528 Beverly Blvd				12	ac		
Bioswales	Existing	Telegraph Road medians	2013	Telegraph Rd from Rosemead Blvd to Eastside limit				5280	sf		
Bioswales	Planned	Paramount Blvd medians	2016	Paramount Blvd from Whittier Blvd to Mines Ave				5280	sf		
Infiltration BMPs	Planned	Two (2) Filterra Systems	2016	various				1	ac		
Infiltration BMPs	Existing	City of Pico Rivera City Hall	2011	8615 Passons Blvd				2.75	ac		
Infiltration BMPs	Existing	Rivera Park	2012	9530 Shade Lane				16	ac		



## D1.6. City of Signal Hill

Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Bioretention / Biofiltration		Palm Drive Business Center	2/19/2008	2445 N Palm Drive	33.801973	-118.157962	775510	1	ac		
Bioretention / Biofiltration		Aragon Townhomes & Duplexes (City View)	3/9/2007	1902 (1890) Oribaza Ave	33.790924	-118.156725	776003	93,780	sf		
Bioretention / Biofiltration		EDCO Recycling & Transfer		2755 California Avenue	33.807881	-118.181769	776011	9,583	sf		
Bioretention / Biofiltration		EDCO Recycling & Transfer		2756 California Avenue	33.807881	-118.181769	776011	17,424	sf		
Bioretention / Biofiltration		EDCO Recycling & Transfer		2757 California Avenue	33.807881	-118.181769	776011	33,106	sf		
Bioretention / Biofiltration		EDCO Recycling & Transfer		2758 California Avenue	33.807881	-118.181769	776011	10,454	sf		
Bioretention / Biofiltration		EDCO Recycling & Transfer		2759 California Avenue	33.807881	-118.181769	776011	78,486	sf		
Bioretention / Biofiltration		2-Story Building and Parking Lot	12/28/2010	2653 Walnut Avenue	33.805754	-118.171978	776012	0.51	ac		
Bioretention / Biofiltration		EDCO Administrative Terminal	8/1/2011	950 27th Street	33.806179	-118.1812	776012	9583	sf	0.06	cfs
Bioretention / Biofiltration		EDCO Administrative Terminal	8/2/2011	951 27th Street	33.806179	-118.1812	776012	17424	sf	0.08	cfs
Bioretention / Biofiltration		EDCO Administrative Terminal	8/3/2011	952 27th Street	33.806179	-118.1812	776012	33106	sf	0.14	cfs
Bioretention / Biofiltration		EDCO Administrative Terminal	8/4/2011	953 27th Street	33.806179	-118.1812	776012	10454	sf	0.08	cfs
Bioretention / Biofiltration		Fantasy Castle	6/30/2009	2801 Walnut Ave	33.808289	118.171777		1,584	sf		
Bioswales	Existing	Fresh and Easy Neighborhood Market	11/16/2010	3300 Atlantic Avenue	33.817504	-118.184643	485510	18,000	sf	931	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Bioswales	Existing	Fresh and Easy Neighborhood Market	11/17/2010	3301 Atlantic Avenue	33.817504	-118.184643	485510	120	sf	7	cf
Bioswales	Existing	Fresh and Easy Neighborhood Market	11/18/2010	3302 Atlantic Avenue	33.817504	-118.184643	485510	10,904	sf	542	cf
Bioswales	Existing	Signal Hill Police Station and Emergency Operation	5/26/2011	2745 Walnut Avenue	33.807067	-118.171984	775510	115,870	sf		
Bioswales	Existing	Jack in the Box	10/21/2008	802 Spring Street	33.812049	-118.182595	775510	12,000	sf		
Bioswales		Boiler Tech Warehouse	10/2/2009	2503 Cerritos Avenue	33.802564	-118.177391	776002	6,754	sf		
Bioswales		Aragon Townhomes & Duplexes (City View)	3/11/2007	1904 (1890) Oribaza Ave	33.790924	-118.156725	776003	31,100	sf		
Bioswales		Fantasy Castle	6/29/2009	2800 Walnut Ave	33.808289	118.171777		32,883	sf		
Flow-Through Treatment BMP	Existing	Petco, Party City	3/3/2009	3100 Atlantic Ave	33.813946	-118.184789	485510				
Flow-Through Treatment BMP	Existing	Petco, Party City	3/4/2009	3101 Atlantic Ave	33.813946	-118.184789	485510				
Flow-Through Treatment BMP	Existing	The Home Depot		3100 Atlantic Avenue	33.813946	-118.184789	485510	3.65	ac		
Flow-Through Treatment BMP	Existing	The Home Depot		3101 Atlantic Avenue	33.813946	-118.184789	485510	7.99	ac		
Flow-Through Treatment BMP	Existing	The Home Depot		3102 Atlantic Avenue	33.813946	-118.184789	485510	3.28	ac		



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Flow-Through Treatment BMP	Existing	The Home Depot		3103 Atlantic Avenue	33.813946	-118.184789	485510	4.79	ac		
Flow-Through Treatment BMP		Palm Drive Business Center	2/20/2008	2446 N Palm Drive	33.801973	-118.157962	775510	7,000	sf		
Flow-Through Treatment BMP	Existing	Fresh & Easy	11/17/2009	2475 Cherry Avenue	33.802363	-118.168152	775510	0.68	ac		
Flow-Through Treatment BMP	Existing	Fresh & Easy	11/18/2009	2476 Cherry Avenue	33.802363	-118.168152	775510	0.58	ac		
Flow-Through Treatment BMP	Existing	US Bank	9/17/2008	2615 Cherry Ave	33.804856	-118.167999	775510	18732	sf		
Flow-Through Treatment BMP	Existing	Signal Hill Industrial Center		2665-2745 Temple Ave	33.80648	-118.159782	775510	143,312	sf		
Flow-Through Treatment BMP	Existing	Tanker Interior Washing Facility		1710 E 29th Street	33.80935	-118.170824	775510	10,000	sf		
Flow-Through Treatment BMP	Existing	Delius Restaurant	7/14/2006	2951 Cherry Ave	33.81111	-118.168077	775510	32,000	sf		
Flow-Through Treatment BMP	Existing	Jack in the Box	10/20/2008	801 Spring Street	33.812049	-118.182595	775510	12,000	sf		



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Flow-Through Treatment BMP	Existing	Target (T-2319)	2/13/2007	950 E 33rd Street	33.816767	-118.181488	775510	178,600	sf		
Flow-Through Treatment BMP	Existing	Hawk Industries	5/8/2007	1245 E. 23rd Street	33.799126	-118.17577	776002	27,322	sf		
Flow-Through Treatment BMP	Existing	Hawk Industries	5/9/2007	1246 E. 23rd Street	33.799126	-118.17577	776002	1575	sf		
Flow-Through Treatment BMP		Boiler Tech Warehouse	9/30/2009	2501 Cerritos Avenue	33.802564	-118.177391	776002	6,754	sf		
Flow-Through Treatment BMP	Existing	Las Brisas II Community Housing	1/11/2006	2400-2418 California Ave	33.803504	-118.180639	776002	16,247	sf		
Flow-Through Treatment BMP	Existing	Las Brisas II Community Housing	1/12/2006	2400-2418 California Ave	33.803504	-118.180639	776002	25,047	sf		
Flow-Through Treatment BMP	Existing	Villagio	12/5/2005	2550 Gundry Ave	33.803577	-118.173289	776002	61,000	sf		
Flow-Through Treatment BMP	Existing	Villagio	12/6/2005	2551 Gundry Ave	33.803577	-118.173289	776002	30,492	sf		
Flow-Through Treatment BMP	Existing	Villagio	12/7/2005	2552 Gundry Ave	33.803577	-118.173289	776002	4,356	sf		



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Flow-Through Treatment BMP		Aragon Townhomes & Duplexes (City View)	3/6/2007	1899 (1890) Oribaza Ave	33.790924	-118.156725	776003	31,350	sf		
Flow-Through Treatment BMP		Aragon Townhomes & Duplexes (City View)	3/7/2007	1900 (1890) Oribaza Ave	33.790924	-118.156725	776003	63,400	sf		
Flow-Through Treatment BMP		In-N-Out Burger	5/27/2011	799 E. Spring Street	33.812066	-118.183197	776011	65,220	sf		
Flow-Through Treatment BMP		Shoreline Fabricators	8/1/2007	2652 Gundry Ave	33.805493	-118.173804	776012	16,300	sf		
Flow-Through Treatment BMP		Shoreline Fabricators	8/2/2007	2653 Gundry Ave	33.805493	-118.173804	776012	1,395	sf		
Flow-Through Treatment BMP		2-Story Building and Parking Lot	12/29/2010	2654 Walnut Avenue	33.805754	-118.171978	776012				
Flow-Through Treatment BMP		Islamic Center	5/29/2009	996 27th St	33.806216	-118.180729	776012	5000	sf		
Flow-Through Treatment BMP		Crescent Square Development	8/10/2007	1600-1799 Green House Place				136,955	sf		
Infiltration BMPs	Existing	Fresh & Easy	11/19/2009	2477 Cherry Avenue	33.802363	-118.168152	775510	76,143	sf		
Infiltration BMPs	Existing	US Bank	9/19/2008	2617 Cherry Ave	33.804856	-118.167999	775510	18732	sf		



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMPs	Planned	Applebee's	3/12/2013	899 E. Spring Street	33.812089	-118.181855	775510	23,580	sf		
Infiltration BMPs	Existing	Hawk Industries	5/10/2007	1247 E. 23rd Street	33.799126	-118.17577	776002	27,322	sf		
Infiltration BMPs		Boiler Tech Warehouse	10/1/2009	2502 Cerritos Avenue	33.802564	-118.177391	776002	6,754	sf		
Infiltration BMPs		Pacific Walk	1/4/2011	PCH and Orizaba Avenue	33.789847	-118.156748	776003	100,200	sf		
Infiltration BMPs		Pacific Walk	1/5/2011	PCH and Orizaba Avenue	33.789847	-118.156748	776003	149,015	sf		
Infiltration BMPs		Pacific Walk	1/6/2011	PCH and Orizaba Avenue	33.789847	-118.156748	776003	1,300	sf		
Infiltration BMPs		Aragon Townhomes & Duplexes (City View)	3/8/2007	1901 (1890) Oribaza Ave	33.790924	-118.156725	776003	94,750	sf		
Infiltration BMPs		Aragon Townhomes & Duplexes (City View)	3/10/2007	1903 (1890) Oribaza Ave	33.790924	-118.156725	776003	93,780	sf		
Infiltration BMPs	Planned	Willow Street Medical Office Building	12/9/2013	845 E. Willow Street	33.804664	-118.182279	776009	22,651	sf	1095	cf
Infiltration BMPs	Planned	Willow Street Medical Office Building	12/10/2013	846 E. Willow Street	33.804664	-118.182279	776009	37,304	sf	1890	cf
Infiltration BMPs		In-N-Out Burger	5/28/2011	800 E. Spring Street	33.812066	-118.183197	776011	65,220	sf	3425	cf
Infiltration BMPs		Shoreline Fabricators	8/3/2007	2654 Gundry Ave	33.805493	-118.173804	776012	16,300	sf		
Infiltration BMPs		Islamic Center	5/28/2009	995 27th St	33.806216	-118.180729	776012	5000	sf		
Infiltration BMPs	Existing	A & A Ready Mix Concrete	8/1/2007	900 E. Patterson	33.806664	-118.182206	776012	2	ac		
Permeable Pavement	Existing	US Bank	9/18/2008	2616 Cherry Ave	33.804856	-118.167999	775510	60	sf		



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Permeable Pavement	Existing	Hawk Industries	5/11/2007	1248 E. 23rd Street	33.799126	-118.17577	776002	5,628	sf		

DRAFT



## D1.7. City of South Gate

Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Bioretention / Biofiltration		Self Storage	9/15/2008	2405 Southern Ave	33.953436	-118.229363	796034	0.25	ac		
Bioretention / Biofiltration		Hollydale Plaza	3/30/2010	12222 Garfield Avenue	33.915655	-118.168383	796076	15,278	sf		
Bioretention / Biofiltration		Atlantic Avenue Improvements	4/21/2010	Atlantice from Abbott to Firestone	33.943066	-118.181112	796084	7.44	ac		
Bioretention / Biofiltration	Planned	azalea	11/25/2012	4641 Firestone Blvd.	33.952413	-118.187909	796084	7,328	sf	0.22	cfs
Bioswales		South Gate McDonald's	9/30/2013	3313 Tweedy Boulevard	33.945113	-118.211464	796034	5,119	sf		
Bioswales		South Gate McDonald's	10/1/2013	3314 Tweedy Boulevard	33.945113	-118.211464	796034	5,545	sf		
Bioswales		Commercial Center	10/4/2010	9200 California Avenue	33.950805	-118.206221	796034	12,367	sf		
Bioswales		Commercial Center	10/5/2010	9201 California Avenue	33.950805	-118.206221	796034	4,263	sf		
Bioswales		Hot Mix Asphalt Plant	5/11/2001	5626 Southern Avenue	33.944913	-118.168148	796083	2.7	ac		
Bioswales		Goals Soccer Centers - South Gate	2/9/2010	9599 Pinehurst Avenue	33.945107	-118.182378	796084	53,142	sf		
Flow-Through Treatment BMP	Existing	South Gate McDonald's	9/26/2013	3309 Tweedy Boulevard	33.945113	-118.211464	796034	2,394	sf		
Flow-Through Treatment BMP		South Gate McDonald's	9/28/2013	3311 Tweedy Boulevard	33.945113	-118.211464	796034	2,436	sf		



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Flow-Through Treatment BMP	Existing	Walgreens	7/24/2006	9830 Long Beach	33.946082	-118.215937	796034	48,725	sf		
Flow-Through Treatment BMP	Existing	King's Car Wash	11/29/2006	9801-9807 Long Beach Blvd	33.946452	-118.216775	796034	10,461	sf		
Flow-Through Treatment BMP		King's Car Wash	12/1/2006	9801-9807 Long Beach Blvd	33.946452	-118.216775	796034				
Flow-Through Treatment BMP	Existing	Sarina Townhomes	2/12/2007	9321 State Street	33.950368	-118.21325	796034	14,375	sf		
Flow-Through Treatment BMP		Commercial Center	10/6/2010	9202 California Avenue	33.950805	-118.206221	796034	16,630	sf		
Flow-Through Treatment BMP		Office Bldg	12/20/2007	3830 Firestone Blvd	33.953324	-118.201934	796034	1,000	sf		
Flow-Through Treatment BMP		Office Bldg	12/21/2007	3831 Firestone Blvd	33.953324	-118.201934	796034	112,000	sf		
Flow-Through Treatment BMP		Office Bldg	12/20/2007	3800 Firestone Blvd	33.95348	-118.202386	796034	1,000	sf		
Flow-Through Treatment BMP		Office Bldg	12/21/2007	3801 Firestone Blvd	33.95348	-118.202386	796034	112,000	sf		



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Flow-Through Treatment BMP	Planned	Calden Court Appartments	9/27/2013	8901 Calden Avenue	33.95515	-118.228736	796034	219,543	sf		
Flow-Through Treatment BMP		Hollydale Plaza	3/31/2010	12223 Garfield Avenue	33.915655	-118.168383	796076	27,381	sf		
Flow-Through Treatment BMP	Existing	Sherwin Inc	4/10/2007	5530 Borwick Ave	33.925749	-118.172611	796082	7,892	sf		
Flow-Through Treatment BMP		Hot Mix Asphalt Plant	5/10/2001	5625 Southern Avenue	33.944913	-118.168148	796083	9.5	ac		
Flow-Through Treatment BMP		Atlantic Avenue Improvements	4/22/2010	Atlantice from Abbott to Firestone	33.943066	-118.181112	796084	13.32	ac		
Flow-Through Treatment BMP		Goals Soccer Centers - South Gate	2/11/2010	9601 Pinehurst Avenue	33.945107	-118.182378	796084	70,036	sf		
Flow-Through Treatment BMP		Goals Soccer Centers - South Gate	2/12/2010	9602 Pinehurst Avenue	33.945107	-118.182378	796084	37,897	sf		
Flow-Through Treatment BMP		Goals Soccer Centers - South Gate	2/13/2010	9603 Pinehurst Avenue	33.945107	-118.182378	796084	63,400	sf		
Flow-Through Treatment BMP	Planned	azalea	11/24/2012	4640 Firestone Blvd.	33.952413	-118.187909	796084	1,583,819	sf		



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Flow-Through Treatment BMP	Existing	Interior Removal Specialist Demolition	5/21/2007	9309 Rayo Ave	33.949331	-118.17896	796089				
Flow-Through Treatment BMP		Interior Removal Specialist Demolition	5/22/2007	9310 Rayo Ave	33.949331	-118.17896	796089				
Flow-Through Treatment BMP		Interior Removal Specialist Demolition	5/23/2007	9311 Rayo Ave	33.949331	-118.17896	796089				
Flow-Through Treatment BMP		Interior Removal Specialist Demolition	5/24/2007	9312 Rayo Ave	33.949331	-118.17896	796089				
Flow-Through Treatment BMP		Petrochem Manufacturing	12/18/2006	8401 Quartz	33.957949	-118.191835	796090	162,305	sf		
Flow-Through Treatment BMP		Petrochem Manufacturing	12/19/2006	8402 Quartz	33.957949	-118.191835	796090	51,401	sf		
Infiltration BMPs		South Gate McDonald's	9/27/2013	3310 Tweedy Boulevard	33.945113	-118.211464	796034	2,394	sf		
Infiltration BMPs		South Gate McDonald's	9/29/2013	3312 Tweedy Boulevard	33.945113	-118.211464	796034	2,436	sf		
Infiltration BMPs		South Gate McDonald's	10/4/2013	3317 Tweedy Boulevard	33.945113	-118.211464	796034	3,743	sf		
Infiltration BMPs		King's Car Wash	11/30/2006	9801-9807 Long Beach Blvd	33.946452	-118.216775	796034	3,047	sf		
Infiltration BMPs		Sarina Townhomes	2/13/2007	9322 State Street	33.950368	-118.21325	796034	17,519	sf		



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMPs		Office Bldg	12/22/2007	3832 Firestone Blvd	33.953324	-118.201934	796034	112,000	sf		
Infiltration BMPs		Office Bldg	12/22/2007	3802 Firestone Blvd	33.95348	-118.202386	796034	112,000	sf		
Infiltration BMPs	Existing	Family Dollar	10/8/2012	3610 Firestone	33.95374	-118.204546	796034		sf		
Infiltration BMPs	Planned	Calden Court Appartments	9/28/2013	8902 Calden Avenue	33.95515	-118.228736	796034	219,543	sf		
Infiltration BMPs		South Gate Ward Building New Parking Lot	10/15/2010	2771 Liberty Boulevard	33.961969	-118.220918	796034	14,811	sf		
Infiltration BMPs		Sherwin Inc	4/11/2007	5531 Borwick Ave	33.925749	-118.172611	796082	7,892	sf		
Infiltration BMPs		Atlantic Avenue Improvements	4/23/2010	Atlantice from Abbott to Firestone	33.943066	-118.181112	796084	22,400	sf		
Infiltration BMPs		Batting Cages	11/4/2010	9599 Pinehurst Avenue	33.945107	-118.182378	796084	7,953	sf		
Infiltration BMPs		Goals Soccer Centers - South Gate	2/10/2010	9600 Pinehurst Avenue	33.945107	-118.182378	796084	113	sf		
Infiltration BMPs		Goals Soccer Centers - South Gate	2/14/2010	9604 Pinehurst Avenue	33.945107	-118.182378	796084	171,333	sf		
Infiltration BMPs	Planned	azalea	11/19/2012	4635 Firestone Blvd.	33.952413	-118.187909	796084	444,636	sf	31,365	cf
Infiltration BMPs	Planned	azalea	11/20/2012	4636 Firestone Blvd.	33.952413	-118.187909	796084	110,869	sf	12,946	cf
Infiltration BMPs	Planned	azalea	11/21/2012	4637 Firestone Blvd.	33.952413	-118.187909	796084	582,860	sf	72,234	cf
Infiltration BMPs	Planned	azalea	11/22/2012	4638 Firestone Blvd.	33.952413	-118.187909	796084	222,727	sf	25,348	cf
Infiltration BMPs	Planned	azalea	11/23/2012	4639 Firestone Blvd.	33.952413	-118.187909	796084	222,727	sf	64,314	cf



Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Infiltration BMPs	Existing	New South Central Properties, LLC	5/28/2009	8600 Rheem Ave	33.955566	-118.192042	796084	20,960	sf		
Infiltration BMPs		LA Water	8/4/2010	9415 Burtis	33.947369	-118.176109	796350	154,538	sf		
Permeable Pavement		South Gate McDonald's	10/2/2013	3315 Tweedy Boulevard	33.945113	-118.211464	796034	8,697	sf		
Permeable Pavement		South Gate McDonald's	10/3/2013	3316 Tweedy Boulevard	33.945113	-118.211464	796034	3,550	sf		

### D1.8. City of Whittier

Type of BMP	Existing or Planned	BMP Name	Year Constructed or Planned	Location (Lat/long, or cross streets)	Latitude	Longitude	Sub-watershed	Contributing Area	Unit	Total Capture Volume or Flow Rate	Unit
Bioretention / Biofiltration	Planned	GWT Biolswale	2014	Greenway Trail from to	33.972121	-118.044253	895098				
Bioretention / Biofiltration	Planned	Whittier Blvd Widening and Bioswale	2017	Whittier Blvd from to							
Green Streets (Describe)	Planned	Lower Uptown reverse drains	2014	Milton, Newlin, Comstock from La Cuarta to Walnut	33.970199	-118.039721	895098		TBD		TBD
Site-Scale Detention Basin	Existing	Police Building and City Hall Storm Drainage	2010	13230 Penn St	33.974748	-118.03371	895098				

# Attachment E: SUPPORTING CALIBRATION DATA

---

***Submitted to:***

LLAR WMP Group

LCC WMP Group

LSGR WMP Group

***Submitted by:***



Tetra Tech  
9444 Balboa Ave., Suite 215  
San Diego, CA 92123

**June 6, 2014**



## Contents

1. Lower San Gabriel River.....	6
2. Lower Los Angeles River .....	20
3. Los Cerritos Channel.....	29

DRAFT



## Tables

Table 1. Summary of water quality data evaluated for the Lower San Gabriel River .....8  
 Table 2. Summary of water quality data evaluated for the Lower Los Angeles River.....21  
 Table 3. Summary of water quality data evaluated for Los Cerritos Channel .....29

## Figures

Figure 1. Monthly hydrograph for USGS 11087020 SAN GABRIEL R AB WHITTIER NARROWS DAM CA (10/1/2002 – 9/30/2011). .....6  
 Figure 2. Aggregated monthly hydrograph for USGS 11087020 SAN GABRIEL R AB WHITTIER NARROWS DAM CA (10/1/2002 – 9/30/2011). .....6  
 Figure 3. Monthly hydrograph for USGS 11089200 COYOTE C NR BUENA PARK CA (10/1/2003 – 9/30/2011....7  
 Figure 4. Aggregated monthly hydrograph for USGS 11089200 COYOTE C NR BUENA PARK CA (10/1/2003 – 9/30/2011.....7  
 Figure 5. Simulated vs. observed load duration plots for Total Phosphorous (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.....9  
 Figure 6. Simulated vs. observed time series plots for Total Phosphorous (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.....9  
 Figure 7. Simulated vs. observed load duration plots for Total Copper (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.....10  
 Figure 8. Simulated vs. observed timeseries plots for Total Copper (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14. ....10  
 Figure 9. Simulated vs. observed load duration plots for Total Lead (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14. ....11  
 Figure 10. Simulated vs. observed timeseries plots for Total Lead (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14. ....11  
 Figure 11. Simulated vs. observed load duration plots for Total Zinc (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14. ....12  
 Figure 12. Simulated vs. observed timeseries plots for Total Zinc (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14. ....12  
 Figure 13. Simulated vs. observed load duration plots for Fecal Coliform (10/1/2002 through 9/30/2011).....13  
 Figure 14. Simulated vs. observed timeseries plots for Fecal Coliform (10/1/2002 through 9/30/2011). ....13  
 Figure 15. Simulated vs. observed load duration plots for Total Sediment (10/1/2002 through 9/30/2011).....14  
 Figure 16. Simulated vs. observed time series plots for Total Sediment (10/1/2002 through 9/30/2011). ....14  
 Figure 17. Simulated vs. observed load duration plots for Total Sediment (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.....15  
 Figure 18. Simulated vs. observed timeseries plots for Total Sediment (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13. ....15  
 Figure 19. Simulated vs. observed load duration plots for Total Zinc (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13. ....16  
 Figure 20. Simulated vs. observed timeseries plots for Total Zinc (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.....16



Figure 21. Simulated vs. observed load duration plots for Total Copper (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13. ....17

Figure 22. Simulated vs. observed timeseries plots for Total Copper (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13. ....17

Figure 23. Simulated vs. observed load duration plots for Total Lead (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13. ....18

Figure 24. Simulated vs. observed timeseries plots for Total Lead (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13. ....18

Figure 25. Simulated vs. observed load duration plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13. ....19

Figure 26. Simulated vs. observed timeseries plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13. ....19

Figure 27. Monthly hydrograph for LA DPW Los Angeles River below Wardlow Road (10/1/2002 – 9/30/2011). ...20

Figure 28. Aggregated monthly hydrograph for LA DPW Los Angeles River below Wardlow Road (10/1/2002 – 9/30/2011).....20

Figure 29. Simulated vs. observed time series plots for Total Nitrogen (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....22

Figure 30. Simulated vs. observed time series plots for Total Nitrogen (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....22

Figure 31. Simulated vs. observed load duration plots for Total Phosphorous (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....23

Figure 32. Simulated vs. observed time series plots for Total Phosphorous (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....23

Figure 33. Simulated vs. observed load duration plots for Total Copper (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....24

Figure 34. Simulated vs. observed timeseries plots for Total Copper (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....24

Figure 35. Simulated vs. observed load duration plots for Total Lead (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....25

Figure 36. Simulated vs. observed timeseries plots for Total Lead (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....25

Figure 37. Simulated vs. observed load duration plots for Total Zinc (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....26

Figure 38. Simulated vs. observed timeseries plots for Total Zinc (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....26

Figure 39. Simulated vs. observed load duration plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....27

Figure 40. Simulated vs. observed timeseries plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....27

Figure 41. Simulated vs. observed load duration plots for Total Sediment (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....28

Figure 42. Simulated vs. observed time series plots for Total Sediment (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10. ....28



Figure 43. Simulated vs. observed time series plots for Total Nitrogen (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....30

Figure 44. Simulated vs. observed time series plots for Total Nitrogen (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....30

Figure 45. Simulated vs. observed load duration plots for Total Phosphorous (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....31

Figure 46. Simulated vs. observed time series plots for Total Phosphorous (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....31

Figure 47. Simulated vs. observed load duration plots for Total Copper (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....32

Figure 48. Simulated vs. observed timeseries plots for Total Copper (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....32

Figure 49. Simulated vs. observed load duration plots for Total Lead (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....33

Figure 50. Simulated vs. observed timeseries plots for Total Lead (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....33

Figure 51. Simulated vs. observed load duration plots for Total Zinc (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....34

Figure 52. Simulated vs. observed timeseries plots for Total Zinc (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....34

Figure 53. Simulated vs. observed load duration plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....35

Figure 54. Simulated vs. observed timeseries plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....35

Figure 55. Simulated vs. observed load duration plots for Total Sediment (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....36

Figure 56. Simulated vs. observed time series plots for Total Sediment (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station. ....36



# 1. Lower San Gabriel River




Figure 1. Monthly hydrograph for USGS 11087020 SAN GABRIEL R AB WHITTIER NARROWS DAM CA (10/1/2002 – 9/30/2011).




Figure 2. Aggregated monthly hydrograph for USGS 11087020 SAN GABRIEL R AB WHITTIER NARROWS DAM CA (10/1/2002 – 9/30/2011).




Figure 3. Monthly hydrograph for USGS 11089200 COYOTE C NR BUENA PARK CA (10/1/2003 – 9/30/2011).




Figure 4. Aggregated monthly hydrograph for USGS 11089200 COYOTE C NR BUENA PARK CA (10/1/2003 – 9/30/2011).

Table 1. Summary of water quality data evaluated for the Lower San Gabriel River

Gage	Constituent	Minimum	Q1	Median	Q3	Maximum
S14	Total Copper (ug/l)	5.0	10.5	13.1	23.9	81.4
S13	Total Copper (ug/l)	0.5	11.8	28.1	48.3	351.0
S14	Total Lead (ug/l)	0.7	1.4	2.9	8.2	56.0
S13	Total Lead (ug/l)	0.2	1.1	10.2	19.2	147.0
S14	TSS (mg/L)	5.0	16.8	38.0	169.8	1258.0
S13	TSS (mg/L)	1.0	48.0	97.0	230.5	1556.0
S14	Total Zinc (ug/l)	19.8	36.6	61.0	86.9	440.0
S13	Total Zinc (ug/l)	1.0	62.0	135.0	241.5	2010.0
S14	Fecal Coliform (MPN/100mL)	20	300	1,300	50,000	16,000,000
S13	FC (MPN/100mL)	20	1,300	16,000	90,000	2,200,000
S14	Total Nitrogen (mg/l)	-	-	-	-	-
S13	Total Nitrogen (mg/l)	-	-	-	-	-
S14	Total Phosphorous (mg/l)	0.05	0.11	0.18	0.41	0.86
S13	Total Phosphorous (mg/l)	-	-	-	-	-




Figure 5. Simulated vs. observed load duration plots for Total Phosphorous (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.




Figure 6. Simulated vs. observed time series plots for Total Phosphorous (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.




Figure 7. Simulated vs. observed load duration plots for Total Copper (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.




Figure 8. Simulated vs. observed timeseries plots for Total Copper (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.




Figure 9. Simulated vs. observed load duration plots for Total Lead (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.




Figure 10. Simulated vs. observed timeseries plots for Total Lead (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.




Figure 11. Simulated vs. observed load duration plots for Total Zinc (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.




Figure 12. Simulated vs. observed timeseries plots for Total Zinc (10/1/2002 through 9/30/2011) at San Gabriel River mass emission station S14.




Figure 13. Simulated vs. observed load duration plots for Fecal Coliform (10/1/2002 through 9/30/2011).




Figure 14. Simulated vs. observed timeseries plots for Fecal Coliform (10/1/2002 through 9/30/2011).




Figure 15. Simulated vs. observed load duration plots for Total Sediment (10/1/2002 through 9/30/2011).




Figure 16. Simulated vs. observed time series plots for Total Sediment (10/1/2002 through 9/30/2011).




Figure 17. Simulated vs. observed load duration plots for Total Sediment (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.




Figure 18. Simulated vs. observed timeseries plots for Total Sediment (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.




Figure 19. Simulated vs. observed load duration plots for Total Zinc (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.




Figure 20. Simulated vs. observed timeseries plots for Total Zinc (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.




Figure 21. Simulated vs. observed load duration plots for Total Copper (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.




Figure 22. Simulated vs. observed timeseries plots for Total Copper (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.




Figure 23 Simulated vs. observed load duration plots for Total Lead (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.




Figure 24. Simulated vs. observed timeseries plots for Total Lead (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.




Figure 25. Simulated vs. observed load duration plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.




Figure 26. Simulated vs. observed timeseries plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Coyote Creek mass emission station S13.



## 2. Lower Los Angeles River




Figure 27. Monthly hydrograph for LA DPW Los Angeles River below Wardlow Road (10/1/2002 – 9/30/2011).




Figure 28. Aggregated monthly hydrograph for LA DPW Los Angeles River below Wardlow Road (10/1/2002 – 9/30/2011).

**Table 2. Summary of water quality data evaluated for the Lower Los Angeles River**

Gage	Constituent	Minimum	Q1	Median	Q3	Maximum
S10	Total Copper (ug/l)	0.5	12.975	25.8	49.55	424
S10	Total Lead (ug/l)	0.2	2.45	15.6	35.775	1070
S10	TSS (mg/L)	1	63	142.5	295	2280
S10	Total Zinc (ug/l)	22.3	63.85	124	261.75	2590
S10	Fecal Coliform (MPN/100mL)	20	500	24000	240000	24000000
S10	Total Nitrogen (mg/l)	0.03	0.60245	1.064	1.725	6.75
S10	Total Phosphorous (mg/l)	0.05	0.24	0.3785	0.538	8.24




Figure 29. Simulated vs. observed time series plots for Total Nitrogen (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 30. Simulated vs. observed time series plots for Total Nitrogen (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 31. Simulated vs. observed load duration plots for Total Phosphorous (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 32. Simulated vs. observed time series plots for Total Phosphorous (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 33. Simulated vs. observed load duration plots for Total Copper (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 34. Simulated vs. observed timeseries plots for Total Copper (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 35. Simulated vs. observed load duration plots for Total Lead (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 36. Simulated vs. observed timeseries plots for Total Lead (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 37. Simulated vs. observed load duration plots for Total Zinc (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 38. Simulated vs. observed timeseries plots for Total Zinc (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 39. Simulated vs. observed load duration plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 40. Simulated vs. observed timeseries plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 41. Simulated vs. observed load duration plots for Total Sediment (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.




Figure 42. Simulated vs. observed time series plots for Total Sediment (10/1/2002 through 9/30/2011) at Los Angeles River mass emission station S10.

### 3. Los Cerritos Channel

Table 3. Summary of water quality data evaluated for Los Cerritos Channel

Gage	Constituent	Minimum	Q1	Median	Q3	Maximum
Stearns St.	Total Copper (ug/l)	8.4	17.25	25	43.5	240
Stearns St.	Total Lead (ug/l)	0.78	3.025	17	41.75	370
Stearns St.	TSS (mg/L)	2	52.5	110	210	1700
Stearns St.	Total Zinc (ug/l)	9.5	33	180	390	2600
Stearns St.	Fecal Coliform (MPN/100mL)	18	2275	8000	28500	1600000
Stearns St.	Total Nitrogen (mg/l)	0.9	2.147	3.292	4.532	23.7
Stearns St.	Total Phosphorous (mg/l)	0.083	0.22	0.53	0.91	6.2




Figure 43. Simulated vs. observed time series plots for Total Nitrogen (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 44. Simulated vs. observed time series plots for Total Nitrogen (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 45. Simulated vs. observed load duration plots for Total Phosphorous (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 46. Simulated vs. observed time series plots for Total Phosphorous (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 47. Simulated vs. observed load duration plots for Total Copper (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 48. Simulated vs. observed timeseries plots for Total Copper (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 49. Simulated vs. observed load duration plots for Total Lead (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 50. Simulated vs. observed timeseries plots for Total Lead (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 51. Simulated vs. observed load duration plots for Total Zinc (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 52. Simulated vs. observed timeseries plots for Total Zinc (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 53. Simulated vs. observed load duration plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 54. Simulated vs. observed timeseries plots for Fecal Coliform (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 55. Simulated vs. observed load duration plots for Total Sediment (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.




Figure 56. Simulated vs. observed time series plots for Total Sediment (10/1/2002 through 9/30/2011) at Los Cerritos Channel LA DPW Stearns Street monitoring station.

Watershed Management Program Appendix 7

# A-7-1 Legal Authority Letters

DRAFT



**RICHARDS | WATSON | GERSHON**

ATTORNEYS AT LAW – A PROFESSIONAL CORPORATION

355 South Grand Avenue, 40th Floor, Los Angeles, California 90071-3101  
Telephone 213.626.8484 Facsimile 213.626.0078

RICHARD RICHARDS  
(1916-1988)

GLENN R. WATSON  
(1917-2010)

HARRY L. GERSHON  
(1922-2007)

STEVEN L. DORSEY  
WILLIAM L. STRAUSS  
MITCHELL E. ABBOTT  
GREGORY W. STEPANICICH  
ROCHELLE BROWNE  
QUINN M. BARROW  
CAROL W. LYNCH  
GREGORY M. KUNERT  
THOMAS M. JIMBO  
ROBERT C. CECCON  
STEVEN H. KAUFMANN  
KEVIN G. ENNIS  
ROBIN D. HARRIS  
MICHAEL ESTRADA  
LAURENCE S. WIENER  
STEVEN R. ORR  
B. TILDEN KIM  
SASKIA T. ASAMURA  
KAYSER O. SUME  
PETER M. THORSON  
JAMES L. MARKMAN  
CRAIG A. STEELE  
T. PETER PIERCE  
TERENCE R. BOGA  
LISA BOND  
JANET E. COLESON  
ROXANNE M. DIAZ  
JIM G. GRAYSON  
ROY A. CLARKE  
WILLIAM P. CURLEY III  
MICHAEL F. YOSHIBA  
REGINA N. DANNER  
PAULA GUTIERREZ BAEZA  
BRUCE W. GALLOWAY  
DIANA K. CHUANG  
PATRICK K. BOBKO  
NORMAN A. DUPONT  
DAVID M. SNOW  
LOLLY A. ENRIQUEZ  
KIRSTEN R. BOWMAN  
GINETTA L. GIOVINCO  
TRISHA ORTIZ  
CANDICE K. LEE  
BILLY D. DUNSMORE  
AMY GREYSON  
DEBORAH R. HAKMAN  
D. CRAIG FOX  
G. INDER KHALSA  
MARICELA E. MARROQUIN  
GENA M. STINNETT  
JENNIFER PETRUSIS  
STEVEN L. FLOWER  
CHRISTOPHER J. DIAZ  
ERIN L. POWERS  
TOUSSAINT S. BAILEY  
SERITA R. YOUNG  
SHIRI KLIMA  
DIANA H. VARAT  
JULIE A. HAMILL  
ANDREW J. BRADY  
MOLLY R. MCLUCAS  
AARON C. O'DELL  
BYRON MILLER

OF COUNSEL  
MARK L. LAMKEN  
SAYRE WEAVER  
JIM R. KARPIAK  
TERESA HO-URANO

SAN FRANCISCO OFFICE  
TELEPHONE 415.421.8484

ORANGE COUNTY OFFICE  
TELEPHONE 714.990.0901

TEMECULA OFFICE  
TELEPHONE 951.695.2373

December 9, 2013

**VIA U.S. MAIL AND E-MAIL**

Mr. Samuel Unger  
Executive Officer  
Los Angeles Regional Quality Control Board  
320 W. 4th Street, Suite 200  
Los Angeles, CA 90013  
[sunger@waterboards.ca.gov](mailto:sunger@waterboards.ca.gov)

Re: Legal Authority of the City of Artesia to Implement and Enforce the Requirements of 40 CFR 122.26(d)(2)(i)(A-F) and RWQCB Order R4-2012-0175, NPDES Permit CAS004001

Dear Mr. Unger:

The City of Artesia (the "City"), by and through its City Attorney, hereby submits the following certification ("Statement"), pursuant to Section VI.A.2.b of Order R4-2012-0175 (NPDES Permit CAS004001), issued by the California Regional Water Quality Control Board, Los Angeles Region ("RWQCB") on November 8, 2012 and entitled "Waste Discharge Requirements for Municipal Separate Storm Sewer System ("MS4") Discharges within the Coastal Watersheds of Los Angeles County, Except Those Discharges Originating from the City of Long Beach MS4" (the "Permit").

The City is one of the co-permittees under the Permit. Section VI.A.2.b of the Permit requires the City to provide the RWQCB with a statement by its chief legal counsel, certifying that the City has the legal authority to implement and enforce each of the current requirements set forth in 40 C.F.R. § 122.26(d)(2)(i)(A-F) and the Permit. The purpose of this Statement is to describe the City's compliance with Section VI.A.2.b of the Permit. As discussed in further detail herein, it is our opinion that the City has the necessary legal authority to implement the Permit and to control and prohibit discharges of pollutants into the Municipal Separate Storm Sewer System ("MS4"). However, this Statement is not, nor should it be construed as, a waiver of any rights that the City may have relating to the Permit.

**I. Legal Authority Statement**

In our opinion, the City has the necessary legal authority to comply with the legal requirements imposed upon it under the Permit, consistent with the requirements set forth in the U.S. Environmental Protection Agency's regulations promulgated under the Clean Water Act, and, specifically, 40 C.F.R. § 122.26(d)(2)(i)(A-F), and to the extent permitted by state and federal law and subject to the limitations on municipal action under the California and United States Constitutions, except as noted herein.

Mr. Samuel Unger  
December 9, 2013  
Page 2

The City, as a general law city, has broad general police powers under the California Constitution to enact legislation for health and public welfare of the community to the extent not preempted by federal or state law. In addition, the City adopted ordinances for the purpose of ensuring that it has adequate legal authority to implement and enforce its storm water control program. The City has the authority under the California Constitution and state law to enact and enforce these ordinances, and these ordinances were duly enacted.

## **2. Ordinances**

The City has adopted ordinances related to the regulation of urban runoff to control and prohibit discharges of pollutants into the MS4 and to comply with the requirements of the Permit applicable to it, as well as, to the extent applicable, 40 C.F.R. § 122.26 (d)(2)(i)(A)-(F). The City's Storm Water Ordinance (Title 6, Chapter 7 of the Artesia Municipal Code ("AMC")) is the principal City ordinance addressing the control of urban runoff. Under this ordinance, the City has the necessary legal authority to do the following:

- i. 40 C.F.R. § 122.26(d)(2)(i)(A); Permit Section VI.A.2.a.i: Control the contribution of pollutants to its MS4 from storm water discharges associated with industrial and construction activity and control the quality of storm water discharged from industrial and construction sites. This requirement applies both to industrial and construction sites with coverage under an NPDES permit, as well as to those sites that do not have coverage under an NPDES permit (AMC § 6-7.09--Requirements for industrial/commercial and construction activities);
- ii. 40 C.F.R. § 122.26(d)(2)(i)(C); Permit Section VI.A.2.a.ii: Prohibit all non-storm water discharges through the MS4 to receiving waters not otherwise authorized or conditionally exempt pursuant to Part III.A (AMC § 6-7.06--Prohibited activities; AMC § 6-7.08--Good housekeeping provisions);
- iii. 40 C.F.R. § 122.26(d)(2)(i)(B); Permit Section VI.A.2.a.iii: Prohibit and eliminate illicit discharges and illicit connections to the MS4 (AMC § 6-7.06--Prohibited activities);
- iv. 40 C.F.R. § 122.26(d)(2)(i)(C); Permit Section VI.A.2.a.iv: Control the discharge of spills, dumping, or disposal of materials other than storm water to its MS4 (AMC § 6-7.06--Prohibited activities; AMC § 6-7.08--Good housekeeping provisions; AMC § 6-7.11--Enforcement);
- v. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.v: Require compliance with conditions in Permittee ordinances, permits, contracts or

Mr. Samuel Unger  
December 9, 2013  
Page 3

- orders (*i.e.*, hold dischargers to its MS4 accountable for their contributions of pollutants and flows) (AMC § 6-7.11--Enforcement);
- vi. 40 C.F.R. § 122.26(d)(2)(i)(E)-(F); Permit Section VI.A.2.a.vi: Utilize enforcement mechanisms to require compliance with applicable ordinances, permits, contracts, or orders (AMC § 6-7.11--Enforcement);
  - vii. 40 C.F.R. § 122.26(d)(2)(i)(D); Permit Section VI.A.2.a.vii: Control the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements among Copermitees (AMC § 6-7.06--Prohibited activities; AMC § 6-7.11--Enforcement);
  - viii. 40 C.F.R. § 122.26 (d)(2)(i)(D); Permit Section VI.A.2.a.viii: Control of the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements with other owners of the MS4 such as the State of California Department of Transportation (AMC § 6-7.06--Prohibited activities; AMC § 6-7.11--Enforcement);
  - ix. 40 C.F.R. § 122.26(d)(2)(i)(F); Permit Section VI.A.2.a.ix: Carry out all inspections, surveillance, and monitoring procedures necessary to determine compliance and noncompliance with applicable municipal ordinances, permits, contracts and orders, and with the provisions of this Order, including the prohibition of non-storm water discharges into the MS4 and receiving waters. This means the Permittee must have authority to enter, monitor, inspect, take measurements, review and copy records, and require regular reports from entities discharging into its MS4 (AMC § 6-7.10--Standard urban stormwater mitigation plan (SUSMP) requirements for specified new development and redevelopment projects);
  - x. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.x: Require the use of control measures to prevent or reduce the discharge of pollutants to achieve water quality standards/receiving water limitations (AMC § 6-7.10--Standard urban stormwater mitigation plan (SUSMP) requirements for specified new development and redevelopment projects; AMC § 6-7.08--Good housekeeping provisions);
  - xi. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.xi: Require that structural BMPs are properly operated and maintained (AMC § 6-7.10--Standard urban stormwater mitigation plan (SUSMP) requirements for specified new development and redevelopment projects)); and
  - xii. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.xii: Require documentation on the operation and maintenance of structural BMPs and their effectiveness in reducing the discharge of pollutants to the MS4 (MBMC §

Mr. Samuel Unger  
December 9, 2013  
Page 4

5.84.100--Adoption urban stormwater mitigation plan (SUSMP); AMC § 6-7.08--Good housekeeping provisions; AMC § 6-7.11--Enforcement).

### **3. Implementation**

Some of the City's ordinances are implemented through permit programs and others are implemented as regulatory programs. Under each ordinance, one or more City bodies, departments, or department directors are authorized and directed in each ordinance to take the actions contemplated by the ordinance (*e.g.*, to consider evidence and make findings, to issue or deny permits, to impose conditions on projects, to inspect, to take enforcement action, etc.).

The City's Storm Water Ordinance (MBMC Chapter 5.84) is the principal City ordinance addressing the control of urban runoff. This ordinance is regulatory, and applies to specified new and existing residential and business communities and associated facilities and activities, as well as new development and redevelopment, and all other specified new and existing facilities and activities that threaten to discharge pollutants within the boundaries of the City and within its regulatory jurisdiction, whether or not a City permit or approval is required. The City's Storm Water Ordinance also contains discharge prohibitions and requirements for the implementation of BMPs and other requirements necessary to implement the Permit.

Other City departments require compliance with the City's Storm Water Ordinance as a condition for issuance of relevant City permits. City departments may also impose specific conditions of approval consistent with the City's Storm Water Ordinance. All City environmental ordinances are also implemented, in part, through the application of the CEQA process to proposed projects.

### **4. Administrative and Judicial/Legal Procedures**

In addition to the above authority, the City has in place various legal and administrative procedures to assist in enforcing the various urban runoff related Ordinances, including the following:

#### **A. Administrative Remedies**

- General Penalties (AMC Title 1, Chapter 2—Penalty Provisions and Judicial Challenges).
- Administrative Penalties and Citations (AMC Title 1, Chapter 2—Penalty Provisions and Judicial Challenges; AMC Title 1, Chapter 4—Citations; AMC Title 1, Chapter 7—Administrative Citations).

#### **B. Nuisance Remedies**

- Public nuisance under State law.

Mr. Samuel Unger  
December 9, 2013  
Page 5

- City nuisance abatement procedures (AMC Title 1, Chapter 2—Penalty Provisions and Judicial Challenges; AMC Title 1, Chapter 4—Citations; AMC Title 1, Chapter 7—Administrative Citations).

**C. Criminal Remedies**

- Misdemeanor citations/prosecution (AMC Title 1, Chapter 2—Penalty Provisions and Judicial Challenges; AMC Title 1, Chapter 4—Citations).

**D. Equitable Remedies**

- Injunctive relief under State law and the Municipal Code (AMC Title 1, Chapter 2—Penalty Provisions and Judicial Challenges; AMC Title 1, AMC Title 1, Chapter 7—Administrative Citations).
- Declaratory relief under State law.

**E. Other Civil Remedies**

- Federal law claims (e.g., Clean Water Act and Resource Conservation and Recovery Act Citizen Suits).
- Remedies under the California Government Code.

Violations of the City's Storm Water Ordinance are deemed a "public nuisance," in which case enforcement actions can be completed administratively, or judicially when necessary.

Please contact me if you have any questions or if you need any additional information regarding the City's legal authority to enforce the Permit.

Very truly yours,



Kevin G. Ennis  
City Attorney

cc: Mayor and Members of the City Council  
William Rawlings, City Manager  
Justine Menzel, Deputy Executive Director  
Candice K. Lee, Esq.  
Andrew Brady, Esq.



**ALESHIRE &  
WYNDER LLP**  
ATTORNEYS AT LAW

Respond to Los Angeles  
Joseph W. Pannone  
jpannone@awattorneys.com  
Direct (310) 527-6663

**Orange County**  
18881 Von Karman Ave., Suite 1700  
Irvine, CA 92612  
P 949.223.1170 • F 949.223.1180

**Los Angeles**  
2361 Rosecrans Ave., Suite 475  
El Segundo, CA 90245  
P 310.527.6660 • F 310.532.7395

**Inland Empire**  
3880 Lemon Street, Suite 520  
Riverside, CA 92501  
P 951.241.7338 • F 951.300.0985

**Central Valley**  
2125 Kern Street, Suite 307  
Fresno, CA 93721  
P 559.445.1580 • F 888.519.9160

awattorneys.com

December 6, 2013

Sam Unger, Executive Officer  
California Regional Water Quality Control Board  
Los Angeles Region  
320 W. 4th Street, Suite 200  
Los Angeles, California 90013-1105

Re: Statement of Legal Authority

Dear Mr. Unger:

This letter is provided to serve as the Statement of Legal Authority for the City of Bellflower (the "City") that must be submitted with its Annual Report pursuant to Part VI.A.2.b. of Order No. R4-2012-0175 for NPDES Permit No. CAS004001. As legal counsel for the City, it is my considered legal opinion the City has all the necessary legal authority to implement and enforce the requirements contained in 40 CFR § 122.26(d)(2)(i)(A-F) and this Order during the reporting period of July 1, 2012 through June 30, 2013, to the extent permitted by State and Federal law, subject to the limitations on municipal action under the California and United States Constitutions.

Per the requirement in Part VI.A.2.b.i., here are citations to the Bellflower Municipal Code ("BMC") for each of the following requirements found in Part VI.A.2.a:

- i. *Control the contribution of pollutants to its MS4 from storm water discharges associated with industrial and construction activity and control the quality of storm water discharged from industrial and construction sites. This requirement applies both to industrial and construction sites with coverage under an NPDES permit, as well as to those sites that do not have coverage under an NPDES permit.*

BMC Sections: 13.20.090 Control of Pollutants from Industrial and Commercial Facilities, 13.20.100 Control of Pollutants from Industrial Activities, 13.20.110 Control of Pollutants from Construction Activities Requiring General Construction Activity Stormwater Permit, and 13.20.120 Control of Pollutants from Other Construction Activities

- ii. *Prohibit all non-storm water discharges through the MS4 to receiving waters not otherwise authorized or conditionally exempt pursuant to Part III.A.*

BMC Sections: 13.20.050 Illicit Discharges and Nonstormwater Discharges and 13.20.080 Reduction of Pollutants in Runoff

- iii. *Prohibit and eliminate illicit discharges and illicit connections to the MS4.*

BMC Sections: 13.20.050 Illicit Discharges and Nonstormwater Discharges and 13.20.070 Illicit Connections

- iv. *Control the discharge of spills, dumping, or disposal of materials other than storm water to its MS4.*

BMC Section: 13.20.060 Illegal Disposal/Dumping

- v. *Require compliance with conditions in Permittee ordinances, permits, contracts or orders (i.e., hold dischargers to its MS4 accountable for their contributions of pollutants and flows);*

BMC Section: 13.20.140 Violation, Inspection, Enforcement

- vi. *Utilize enforcement mechanisms to require compliance with applicable ordinances, permits, contracts, or orders.*

BMC Section: 13.20.140 Violation, Inspection, Enforcement

- vii. *Control the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements among Co-permittees;*

BMC Sections: 13.20.050 Illicit Discharges and Nonstormwater Discharges and 13.20.080 Reduction of Pollutants in Runoff

- viii. *Control of the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements with other owners of the MS4 such as the State of California Department of Transportation;*

BMC Sections: 13.20.050 Illicit Discharges and Nonstormwater Discharges and 13.20.080 Reduction of Pollutants in Runoff

- ix. *Carry out all inspections, surveillance, and monitoring procedures necessary to determine compliance and noncompliance with applicable municipal ordinances, permits, contracts and orders, and with the provisions of this Order, including the prohibition of non-storm water discharges into the MS4 and receiving waters.*

*This means the Permittee must have authority to enter, monitor, inspect, take measurements, review and copy records, and require regular reports from entities discharging into its MS4;*

BMC Section: 13.20.140 Violation, Inspection, Enforcement

- x. *Require the use of control measures to prevent or reduce the discharge of pollutants to achieve water quality standards/receiving water limitations;*

BMC Sections: 13.20.090 Control of Pollutants from Industrial and Commercial Facilities and 13.20.130 Control of Pollutants from New Development/Redevelopment Projects

- x. *Require that structural BMPs are properly operated and maintained;*

BMC Section: 13.20.130 Control of Pollutants from New Development/Redevelopment Projects

- xii. *Require documentation on the operation and maintenance of structural BMPs and their effectiveness in reducing the discharge of pollutants to the MS4.*

BMC Section: 13.20.130 Control of Pollutants from New Development/Redevelopment Projects

Per the requirement in Part VI.A.2.b.ii., the City's legal procedures available to mandate compliance with applicable municipal ordinances identified in the above section, and therefore with the conditions of the Order, can be found in BMC Section 13.20.140 Violation, Inspection, Enforcement. Here is the relevant text of that provision:

**13.20.140 Violation, Inspection, Enforcement.**

A. Violation of any provision of this chapter, any stormwater pollution prevention plan or any permit issued pursuant to this chapter shall be a violation per Chapter 1.08.

B. The Director of Community Development, or the Director's designees, may issue notices of violation and administrative orders to achieve compliance with the provisions of this chapter. Failure to comply with the terms and conditions of such a notice of violation or an administrative order shall constitute a violation of this chapter.

C. The violation of any provision of this chapter is hereby declared to be a nuisance, and may be abated by the City in accordance with its authority to abate nuisances.

D. The remedies listed in this chapter are not exclusive of any other remedies available to the City under any applicable Federal, State or local law and it is within the discretion of the City to seek cumulative remedies.

[...]

F. The Director of Community Development, or the Director's designees, may issue notice of violation and administrative orders to any other person who has failed to comply with either a notice of violation or other administrative order an invoice for costs (invoice of cost) for reimbursement of the City's actual costs incurred in issuing and enforcement of any provision of this chapter.

G. The Director of Community Development, or the Director's designees, may require that any person engaged in any activity and/or owning or operating any facility which may cause or contribute to stormwater pollution or contamination, illicit discharges and/or discharge of nonstormwater to the stormwater system, undertake such monitoring activities and/or analysis and furnish such reports as the officer may specify. The burden, including costs, of these activities, analysis and reports shall bear a reasonable relationship to the need for the monitoring, analysis and the benefits to be obtained.

Thus, enforcement actions can be completed administratively or judicially if necessary.

Please contact the undersigned if you have any questions.

Sincerely,

ALESHIRE & WYNDER, LLP

  
Joseph W. Pannone  
City Attorney for the City of Bellflower



December 3, 2013

Mr. Sam Unger, Executive Officer  
California Regional Water Quality Control Board  
Los Angeles Region  
320 W. 4th Street, Suite 200  
Los Angeles, California 90013-1105

Re: Statement of Legal Authority

Dear Mr. Unger:

This letter is provided to serve as the Statement of Legal Authority for the City of Cerritos (the "City") that must be submitted with its Annual Report pursuant to Part VI.A.2.b. of Order No. R4-2012-0175 for NPDES Permit No. CAS004001. As legal counsel for the City, I have determined that it has all the necessary legal authority to implement and enforce the requirements contained in 40 CFR § 122.26(d)(2)(i)(A-F) and this Order during the reporting period of July 1, 2012 through June 30, 2013, to the extent permitted by State and Federal law, subject to the limitations on municipal action under the California and United States Constitutions.

Per the requirement in Part VI.A.2.b.i., here are citations to the City's Municipal Code for each of the following requirements found in Part VI.A.2.a:

- i. *Control the contribution of pollutants to its MS4 from storm water discharges associated with industrial and construction activity and control the quality of storm water discharged from industrial and construction sites. This requirement applies both to industrial and construction sites with coverage under an NPDES permit, as well as to those sites that do not have coverage under an NPDES permit.*

Municipal Code Sections: 6.32.050 Construction sites requiring building permit and/or grading plan and 6.32.060 Industrial activity sites

- ii. *Prohibit all non-storm water discharges through the MS4 to receiving waters not otherwise authorized or conditionally exempt pursuant to Part III.A.*

Municipal Code Section: 6.32.030 Illicit discharges and connections

- iii. *Prohibit and eliminate illicit discharges and illicit connections to the MS4.*

Municipal Code Section: 6.32.030 Illicit discharges and connections

- iv. *Control the discharge of spills, dumping, or disposal of materials other than storm water to its MS4.*

Municipal Code Sections: 6.32.030 Illicit discharges and connections and 6.32.040 Illicit disposal

- v. *Require compliance with conditions in Permittee ordinances, permits, contracts or orders (i.e., hold dischargers to its MS4 accountable for their contributions of pollutants and flows);*

Municipal Code Sections: 6.32.010 Purpose and 6.32.080 Violation—Penalty

- vi. *Utilize enforcement mechanisms to require compliance with applicable ordinances, permits, contracts, or orders.*

Municipal Code Section: 6.32.080 Violation—Penalty

- vii. *Control the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements among Co-permittees;*

Municipal Code Section: 6.32.030 Illicit discharges and connections

- viii. *Control of the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements with other owners of the MS4 such as the State of California Department of Transportation;*

Municipal Code Section: 6.32.030 Illicit discharges and connections

- ix. *Carry out all inspections, surveillance, and monitoring procedures necessary to determine compliance and noncompliance with applicable municipal ordinances, permits, contracts and orders, and with the provisions of this Order, including the prohibition of non-storm water discharges into the MS4 and receiving waters. This means the Permittee must have authority to enter, monitor, inspect, take measurements, review and copy records, and require regular reports from entities discharging into its MS4;*

Municipal Code Section: 6.32.080 Violation—Penalty, subsection (D)

- x. *Require the use of control measures to prevent or reduce the discharge of pollutants to achieve water quality standards/receiving water limitations;*

Municipal Code Section: 6.32.030 Illicit discharges and connections

- xi. Require that structural BMPs are properly operated and maintained;*

Municipal Code Section: 6.32.055 Urban runoff mitigation plan for new development

- xii. Require documentation on the operation and maintenance of structural BMPs and their effectiveness in reducing the discharge of pollutants to the MS4.*

Municipal Code Section: 6.32.055 Urban runoff mitigation plan for new development

Per the requirement in Part VI.A.2.b.ii., the City's legal procedures available to mandate compliance with applicable municipal ordinances identified in the above section, and therefore with the conditions of the Order, can be found in Municipal Code Section 6.32.080 Violation—Penalty. Here is the relevant text of that provision:

**6.32.080 Violation—Penalty.**

(A) The violation of any provision of this chapter, or failure to comply with any of the requirements of this chapter, shall constitute a misdemeanor; except that notwithstanding any other provision of this chapter, any such violation constituting a misdemeanor under this chapter may, at the sole discretion of the authorized enforcement officer, be charged and prosecuted as an infraction.

(B) In addition to the penalties provided, any condition caused or permitted to exist in violation of any of the provisions of this chapter is a threat to the public health, safety and welfare, is declared and deemed a nuisance, may be summarily abated and/or restored by the authorized enforcement officer, and/or civil action to abate, enjoin or otherwise compel the cessation of such nuisance.

(1) The cost of such abatement and restoration shall be borne by the owner of the property and the cost thereof shall be invoiced to the owner of the property. If the invoice is not paid with sixty days, a lien shall be placed upon and against the property. If the lien is not satisfied within three months, the property may be sold in satisfaction thereof in a like manner as other real property is sold under execution.

(2) If any violation of this chapter constitutes a seasonal recurrent nuisance, the authorized enforcement officer shall so declare. Thereafter such seasonal and recurrent nuisance shall be abated every year without the necessity of any further hearing.

(3) In any administrative or civil proceeding under this chapter in which the city prevails, the city shall be awarded all costs of investigation, administrative overhead, out-of-pocket expenses, costs of suit and reasonable attorney fees.

(C) Penalties for Failure to Comply with BMPs. The authorized enforcement officer shall enforce this chapter as follows:

(1) For the first failure to comply with any provision of this chapter, the authorized enforcement officer shall issue to the affected person or business a written notice which includes the following information:

- (a) A statement specifying the violation committed;
- (b) A specified time period within which the affected person or business must correct the failure or file a written notice disputing the notice of failure to comply;
- (c) A statement of the penalty for continued noncompliance.

(2) For each subsequent failure to comply with any provision of this chapter, following written notice issued pursuant to subsection (C)(1) of this section, the authorized enforcement officer may levy a penalty of one hundred dollars each day during which a person or business fails to comply with the provisions of this chapter. Each day following written notice shall constitute a separate offense. Said penalty shall be set by the city council resolution.

[...]

Thus, enforcement actions can be completed administratively or judicially if necessary.

Please contact the undersigned if you have any questions.

Sincerely,

ALESHIRE & WYNDER, LLP



Mark W. Steres

City Attorney for the City of Cerritos



December 4, 2013

**VIA FIRST CLASS MAIL**

Mr. Samuel Unger  
Executive Officer  
Regional Water Quality Control Board  
Los Angeles Region  
320 West Fourth Street, Suite 200  
Los Angeles, CA 90013

Re: Legal Authority Certification for the City of Diamond Bar

Dear Mr. Unger:

The City of Diamond Bar ("City"), through its City Attorney, submits this statement in its capacity as a Permittee pursuant to Part VI.A.2 of RWQCB Order R4-2012-0175 ("Order").

**1. Legal Authority Statement**

The undersigned City Attorney for the City of Diamond Bar does hereby state that in my opinion the City has or will timely obtain adequate legal authority to comply with the legal requirements imposed upon the City set forth in the regulations to the Clean Water Act, 40 CFR [Code of Federal Regulations] 122.26(d)(2)(i)(A-F), and to the extent permitted by State and Federal law and subject to the limitations on municipal action under the California and United States Constitutions. The City has the authority under the Constitution and statutes of the State of California to enact and enforce ordinances. The City has enacted ordinances to implement and enforce a stormwater control program. These ordinances contain specific enforcement provisions such as the suspension and revocation of permits and stop work orders and/or are enforceable under the generally applicable enforcement provisions of the City's Municipal Code (misdemeanors or infractions; suspension or revocation of permits and stop work orders; and nuisance abatement and recovery of abatement expenses).

**2. Status of Implementation**

The City has recently amended its ordinances regulating stormwater discharges to ensure that it has the adequate legal authority to implement and enforce its stormwater control program as directed by the "Waste Discharge Requirements for Municipal Separate Storm Sewer System Discharges within the Coastal Watersheds of Los Angeles County, except those Discharges Originating from the City of Long Beach (MS4)", hereafter the "NPDES Permit". The City

anticipates one additional cleanup amendment will be brought to the City Council this month or in early December of this year.


**3. City Departments**

The City's Public Works Department, Community Development Department and Code Enforcement Officers are all involved with the regulation of stormwater runoff and runoff related activities, including grading, water quality, erosion control, and litter. One or more of these City departments or department directors are authorized and directed to take the actions contemplated by the regulations, *e.g.*, to consider evidence and make findings, to issue or deny permits, to impose conditions on projects, to inspect, to take enforcement action, etc. The City Attorney has authority under the ordinances and state law to bring criminal and civil enforcement actions.

Please do not hesitate to contact the undersigned should you have any questions or need any additional information.

Sincerely,

WOODRUFF, SPRADLIN & SMART  
A Professional Corporation



---

DAVID A. DEBERRY  
City Attorney, City of Diamond Bar

cc: James DeStefano, City Manager  
David Liu, Public Works Director  
Kimberly Young, Associate Engineer



# City of Downey

FUTURE UNLIMITED

**YVETTE M. ABICH GARCIA**  
City Attorney

December 12, 2013

Mr. Sam Unger, Executive Officer  
California Regional Water Quality Control Board  
Los Angeles Region  
320 W. 4th Street, Suite 200  
Los Angeles, CA 90013-1105

RE: Legal Authority Certification for the City of Downey

Dear Mr. Unger:

As the City Attorney for the City of Downey, I have reviewed the City's existing ordinances, applicable statutes, and/or applicable contracts and have determined that as of the date of this letter, the City can operate pursuant to the legal authority required in 40 CFR 122.26(d)(2)(i)(A)-(F) and Part VI.A.2 of Order No. R4-2012-0175, issued by the Regional Water Quality Control Board – Los Angeles Region ("RWQCB"), adopted on December 28, 2012 and entitled "Waste Discharge Requirements for Municipal Separate Storm Sewer System (MS4) Discharges within the Coastal Watersheds of Los Angeles County, except those Discharges Originating from the City of Long Beach (MS4)" [NPDES No. CAS004001] (the "2012 NPDES Permit"). Enforcement of the City's storm water ordinances can be completed administratively or, if necessary, through the judicial system.

This letter is limited to the matters contained herein, and should not be read as expressing any opinion on any other matter except on the matters expressly set forth herein.

Please call the undersigned if you have any questions.

Sincerely,

CITY OF DOWNEY

Yvette M. Abich Garcia  
City Attorney

cc: John L. Hunter & Associates



*"Our Youth - Our Future"*

# CITY OF HAWAIIAN GARDENS

---

December 15, 2013

Mr. Sam Unger, Executive Officer  
California Regional Water Quality Control Board  
Los Angeles Region  
320 W. 4th Street, Suite 200  
Los Angeles, CA 90013-1105

RE: Legal Authority Certification for the City of Hawaiian Gardens

Dear Mr. Unger:

As legal counsel for the City of Hawaiian Gardens, I have reviewed its existing ordinances, applicable statutes, and/or existing contracts and have determined that the City has enacted the legal authority required in 40 CFR 122.26(d)(2)(i)(A)-(F) and Part VI.A.2 of Order No. R4-2012-0175, issued by the Regional Water Quality Control Board – Los Angeles Region ("RWQCB"), adopted on December 28, 2012 and entitled "Waste Discharge Requirements for Municipal Separate Storm Sewer System (MS4) Discharges within the Coastal Watersheds of Los Angeles County, except those Discharges Originating from the City of Long Beach (MS4)" [NPDES No. CAS004001].

Please call the undersigned if you have any questions, or you may contact me by e-mail at [osandoval@wss-law.com](mailto:osandoval@wss-law.com).

Sincerely,

Omar Sandoval, Esq.  
Woodruff, Spradlin & Smart  
555 Anton Boulevard, Suite 1200  
Costa Mesa, California 92626  
Main: (714) 558-7000  
Fax: (714) 835-7787

cc: John L. Hunter & Associates



COUNTY OF LOS ANGELES  
OFFICE OF THE COUNTY COUNSEL

648 KENNETH HAHN HALL OF ADMINISTRATION  
500 WEST TEMPLE STREET  
LOS ANGELES, CALIFORNIA 90012-2713

TELEPHONE  
(213) 974-1923  
FACSIMILE  
(213) 687-7337  
TDD  
(213) 633-0901

JOHN F. KRATTLI  
County Counsel

December 16, 2013

Mr. Samuel Unger, P.E., Executive Officer  
California Regional Water Quality Control Board – Los Angeles Region  
320 West 4th Street, Suite 200  
Los Angeles, CA 90013-2343

Attention: Mr. Ivar Ridgeway

**Re: Certification By Legal Counsel For Los Angeles County Flood  
Control District's Annual Report**

Dear Mr. Unger:

Pursuant to the requirements of Part VI(A)(2)(b) of Order No. R4-2012-0175 (the "Order"), the Office of the County Counsel of the County of Los Angeles makes the following certification in support of the Annual Report of the Los Angeles County Flood Control District ("LACFCD"):

Certification Pursuant To Order Part VI(A)(2)(b)

*"Each Permittee must submit a statement certified by its chief legal counsel that the Permittee has the legal authority within its jurisdiction to implement and enforce the requirements contained in 40 CFR §122.26(d)(2)(i)(A-F) and this Order."*

LACFCD has the legal authority within its jurisdiction to implement and enforce each of the requirements contained in 40 CFR §122.26(d)(2)(i)(A-F) and the Order.

Order Part VI(A)(2)(b)(i)

*"Citation of applicable municipal ordinances or other appropriate legal authorities and their relationship to the requirements of 40 CFR §122.26(d)(2)(i)(A-F) and this Order"*

Citations Of Applicable Ordinances Or Other Legal Authorities

Although many portions of State law, the Charter of the County of Los Angeles, the Los Angeles County Code and LACFCD's Flood Control District Code ("Code") are potentially applicable to the implementation and enforcement of these requirements, the primary applicable laws and ordinances are as follows:

Los Angeles County Code, Title 12, Chapter 12.80 STORMWATER AND RUNOFF POLLUTION CONTROL, including:

§12.80.010 - §12.80.360 Definitions

§12.80.370 Short title.

§12.80.380 Purpose and intent.

§12.80.390 Applicability of this chapter.

§12.80.400 Standards, guidelines and criteria.

§12.80.410 Illicit discharges prohibited.

§12.80.420 Installation or use of illicit connections prohibited.

§12.80.430 Removal of illicit connection from the storm drain system.

§12.80.440 Littering and other discharge of polluting or damaging substances prohibited.

§12.80.450 Stormwater and runoff pollution mitigation for construction activity.

§12.80.460 Prohibited discharges from industrial or commercial activity.

§12.80.470 Industrial/commercial facility sources required to obtain a NPDES permit.

§12.80.480 Public facility sources required to obtain a NPDES permit.

§12.80.490 Notification of uncontrolled discharges required.

§12.80.500 Good housekeeping provisions.

§12.80.510 Best management practices for construction activity.

- §12.80.520 Best management practices for industrial and commercial facilities.
- §12.80.530 Installation of structural BMPs.
- §12.80.540 BMPs to be consistent with environmental goals.
- §12.80.550 Enforcement—Director's powers and duties.
- §12.80.560 Identification for inspectors and maintenance personnel.
- §12.80.570 Obstructing access to facilities prohibited.
- §12.80.580 Inspection to ascertain compliance—Access required.
- §12.80.590 Interference with inspector prohibited.
- §12.80.600 Notice to correct violations—Director may take action.
- §12.80.610 Violation a public nuisance.
- §12.80.620 Nuisance abatement—Director to perform work when—Costs.
- §12.80.630 Violation—Penalty.
- §12.80.635 Administrative fines.
- §12.80.640 Penalties not exclusive.
- §12.80.650 Conflicts with other code sections.
- §12.80.660 Severability.
- §12.80.700 Purpose.
- §12.80.710 Applicability.
- §12.80.720 Registration required.
- §12.80.730 Exempt facilities.
- §12.80.740 Certificate of inspection—Issuance by the director.
- §12.80.750 Certificate of inspection—Suspension or revocation.

§12.80.760 Certificate of inspection—Termination.

§12.80.770 Service fees.

§12.80.780 Fee schedule.

§12.80.790 Credit for overlapping inspection programs.

§12.80.800 Annual review of fees.

Los Angeles County Code, Title 12, Chapter 12.84 LOW IMPACT DEVELOPMENT STANDARDS, including:

§12.84.410 Purpose.

§12.84.420 Definitions.

§12.84.430 Applicability.

§12.84.440 Low Impact Development Standards.

§12.84.445 Hydromodification Control.

§12.84.450 LID Plan Review.

§12.84.460 Additional Requirements.

Los Angeles County Code, Title 22 PLANNING AND ZONING, Part 6 ENFORCEMENT PROCEDURES, including:

§22.60.330 General prohibitions.

§22.60.340 Violations.

§22.60.350 Public nuisance.

§22.60.360 Infractions.

§22.60.370 Injunction.

§22.60.380 Enforcement.

§22.60.390 Zoning enforcement order and noncompliance fee.

Los Angeles County Code, Title 26 BUILDING CODE, including:

§26.103 Violations And Penalties

§26.104 Organization And Enforcement

§26.105 Appeals Boards

§26.106 Permits

§26.107 Fees

§26.108 Inspections

LACFCD Code Chapter 21 - STORMWATER AND RUNOFF  
POLLUTION CONTROL including:

§21.01 Purpose and Intent

§21.03 Definitions

§21.05 Standards, Guidelines, and Criteria

§21.07 Prohibited Discharges

§21.09 Installation or Use of Illicit Connections Prohibited

§21.11 Littering Prohibited

§21.13 Evidence of Compliance With Permit Requirements for Industrial  
or Commercial Activity

§21.15 Notification of Uncontrolled Discharges Required

§21.17 Requirement to Monitor and Analyze

§21.19 Conflicts With Other Code Sections

§21.21 Severability

§21.23 Violation a Public Nuisance

California Government Code §6502

California Government Code §23004

California Water Code §8100 *et. seq.*

Relationship Of Applicable Ordinances Or Other Legal Authorities To  
 The Requirements of 40 CFR §122.26(d)(2)(i)(A-F) And The Order

Although, depending upon the particular issue, there may be multiple ways in which particular sections of the County of Los Angeles' ordinances, LACFCD's ordinances, and statutes relate to the requirements contained in 40 CFR §122.26(d)(2)(i)(A-F) and the Order, the table below indicates the basic relationship with Part VI(A)(2)(a) of the Order:

<b>Order Part VI(A)(2)(a) Items</b>	<b>Primary Applicable Ordinance/Statute</b>
<p>i. Control the contribution of pollutants to its MS4 from storm water discharges associated with industrial and construction activity and control the quality of storm water discharged from industrial and construction sites. This requirement applies both to industrial and construction sites with coverage under an NPDES permit, as well as to those sites that do not have coverage under an NPDES permit.</p>	<p>Los Angeles County Code:                      §12.80.410 [illicit discharge prohibited];                      §12.80.450 [construction]                      §12.80.460 [industrial and commercial]                      §12.80.470 and .480 [industrial and commercial NPDES requirements]                      §12.84.440 [LID standards]                      §12.84.445 [hydromodification control]                      §12.84.450 [LID Plan Review]                      §22.60.330 [general prohibitions]                      §22.60.340 [violations]                      §22.60.350 [public nuisance]                      §22.60.360 [infractions]                      §22.60.370 [injunction]                      §22.60.380 [enforcement.]                      §22.60.390 [zoning enforcement order]                      §26.103 [violations and penalties]</p>

Order Part VI(A)(2)(a) Items	Primary Applicable Ordinance/Statute
	§26.104 [enforcement] §26.106 [permits] §26.108 [inspections] LACFCD Code: §21.05 Standards, Guidelines, and Criteria §21.07 Prohibited Discharges §21.13 Evidence of Compliance With Permit Requirements for Industrial or Commercial Activity §21.15 Notification of Uncontrolled Discharges Required §21.17 Requirement to Monitor and Analyze §21.23 Violation a Public Nuisance
ii. Prohibit all non-storm water discharges through the MS4 to receiving waters not otherwise authorized or conditionally exempt pursuant to Part III.A.	Los Angeles County Code: §12.80.410 [illicit discharge prohibited] LACFCD Code: §21.07 Prohibited Discharges
iii. Prohibit and eliminate illicit discharges and illicit connections to the MS4.	Los Angeles County Code: §12.80.410 [illicit discharge prohibited]; §12.80.420 [illicit connections prohibited] LACFCD Code: §21.05 Standards, Guidelines, and Criteria §21.07 Prohibited Discharges §21.09 Installation or Use of Illicit Connections Prohibited §21.23 Violation a Public Nuisance

Order Part VI(A)(2)(a) Items	Primary Applicable Ordinance/Statute
<p>iv. Control the discharge of spills, dumping, or disposal of materials other than storm water to its MS4.</p>	<p>Los Angeles County Code:                      §12.80.410 [illicit discharge prohibited];                      §12.80.440 [littering and other polluting prohibited]</p> <p>LACFCD Code:                      §19.07 Interference With or Placing Obstructions, Refuse, Contaminating Substances, or Invasive Species in Facilities Prohibited                      §21.05 Standards, Guidelines, and Criteria                      §21.07 Prohibited Discharges                      §21.09 Installation or Use of Illicit Connections Prohibited                      §21.11 Littering Prohibited                      §21.13 Evidence of Compliance With Permit Requirements for Industrial or Commercial Activity                      §21.15 Notification of Uncontrolled Discharges Required                      §21.17 Requirement to Monitor and Analyze                      §21.23 Violation a Public Nuisance</p>
<p>v. Require compliance with conditions in Permittee ordinances, permits, contracts or orders (i.e., hold dischargers to its MS4 accountable for their contributions of pollutants and flows).</p>	<p>Los Angeles County Code:                      §12.80.490 [notification of uncontrolled discharge]                      §12.80.570 [obstructing access to facilities]                      §12.80.580 [compliance inspection]                      §12.80.610 [violation a nuisance]                      §12.620 [nuisance abatement]                      §12.80.635 [violation penalty]</p>

Order Part VI(A)(2)(a) Items	Primary Applicable Ordinance/Statute
	§12.80.640 [penalties not exclusive] §12.84.440 [LID standards] §12.84.445 [hydromodification control] §12.84.450 [LID Plan Review] §22.60.330 [general prohibitions] §22.60.340 [violations] §22.60.350 [public nuisance] §22.60.360 [infractions] §22.60.370 [injunction] §22.60.380 [enforcement.] §22.60.390 [zoning enforcement order] §26.103 [violations and penalties] §26.104 [enforcement] §26.106 [permits] §26.108 [inspections] LACFCD Code: §19.11 Violation a Public Nuisance §21.05 Standards, Guidelines, and Criteria §21.07 Prohibited Discharges §21.09 Installation or Use of Illicit Connections Prohibited §21.11 Littering Prohibited §21.13 Evidence of Compliance With Permit Requirements for Industrial or Commercial Activity §21.15 Notification of Uncontrolled Discharges Required §21.17 Requirement to Monitor and Analyze

Order Part VI(A)(2)(a) Items	Primary Applicable Ordinance/Statute
	§21.19 Conflicts With Other Code Sections §21.23 Violation a Public Nuisance
vi. Utilize enforcement mechanisms to require compliance with applicable ordinances, permits, contracts, or orders.	Same as item v., above
vii. Control the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements among Copermittees.	California Government Code §6502 California Government Code §23004
viii. Control of the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements with other owners of the MS4 such as the State of California Department of Transportation.	California Government Code §6502 California Government Code §23004
ix. Carry out all inspections, surveillance, and monitoring procedures necessary to determine compliance and noncompliance with applicable municipal ordinances, permits, contracts and orders, and with the provisions of this Order, including the prohibition of non-storm water discharges into the MS4 and receiving waters. This means the Permittee must have authority to enter, monitor, inspect, take measurements, review and copy records, and require regular reports from entities discharging into its MS4.	Los Angeles County Code: §12.80.490 [notification of uncontrolled discharge] §12.80.570 [obstructing access to facilities] §12.80.580 [compliance inspection] §12.80.610 [violation a nuisance] §12.80.620 [nuisance abatement] §12.80.635 [violation penalty] §12.80.640 [penalties not exclusive] §22.60.380 [enforcement.] §26.106 [permits] §26.108 [inspections]

Order Part VI(A)(2)(a) Items	Primary Applicable Ordinance/Statute
	LACFCD Code: §21.05 Standards, Guidelines, and Criteria §21.07 Prohibited Discharges §21.09 Installation or Use of Illicit Connections Prohibited §21.11 Littering Prohibited §21.13 Evidence of Compliance With Permit Requirements for Industrial or Commercial Activity §21.15 Notification of Uncontrolled Discharges Required §21.17 Requirement to Monitor and Analyze §21.23 Violation a Public Nuisance
x. Require the use of control measures to prevent or reduce the discharge of pollutants to achieve water quality standards/receiving water limitations.	Los Angeles County Code: §12.80.450 [construction mitigation] §12.80.500 [good housekeeping practices] §12.80.510 [construction BMPs] §12.80.520 [industrial/commercial BMPs] §12.84.440 [LID standards] §12.84.450 [LID Plan Review] §22.60.330 [general prohibitions] §22.60.380 [enforcement.] §22.60.390 [zoning enforcement order] §26.106 [permits] §26.108 [inspections] LACFCD Code: §21.05 Standards, Guidelines, and Criteria

Order Part VI(A)(2)(a) Items	Primary Applicable Ordinance/Statute
	§21.07 Prohibited Discharges §21.09 Installation or Use of Illicit Connections Prohibited §21.11 Littering Prohibited §21.13 Evidence of Compliance With Permit Requirements for Industrial or Commercial Activity §21.15 Notification of Uncontrolled Discharges Required §21.17 Requirement to Monitor and Analyze §21.23 Violation a Public Nuisance
xi. Require that structural BMPs are properly operated and maintained.	Los Angeles County Code: §12.80.530 [installation of structural BMPs] §22.60.380 [enforcement.] §22.60.390 [zoning enforcement order] §26.106 [permits] §26.108 [inspections] LACFCD Code: §21.05 Standards, Guidelines, and Criteria §21.07 Prohibited Discharges §21.09 Installation or Use of Illicit Connections Prohibited §21.11 Littering Prohibited §21.13 Evidence of Compliance With Permit Requirements for Industrial or Commercial Activity §21.15 Notification of Uncontrolled Discharges Required §21.17 Requirement to Monitor and Analyze

Order Part VI(A)(2)(a) Items	Primary Applicable Ordinance/Statute
	§21.23 Violation a Public Nuisance
xii. Require documentation on the operation and maintenance of structural BMPs and their effectiveness in reducing the discharge of pollutants to the MS4.	Los Angeles County Code: §12.80.530 [installation of structural BMPs] §22.60.380 [enforcement.] §22.60.390 [zoning enforcement order] §26.106 [permits] §26.108 [inspections] LACFCD Code: §21.05 Standards, Guidelines, and Criteria §21.07 Prohibited Discharges §21.09 Installation or Use of Illicit Connections Prohibited §21.11 Littering Prohibited §21.13 Evidence of Compliance With Permit Requirements for Industrial or Commercial Activity §21.15 Notification of Uncontrolled Discharges Required §21.17 Requirement to Monitor and Analyze §21.23 Violation a Public Nuisance

Order Part VI(A)(2)(b)(ii)

*"Identification of the local administrative and legal procedures available to mandate compliance with applicable municipal ordinances identified in subsection (i) above and therefore with the conditions of this Order, and a statement as to whether enforcement actions can be completed administratively or whether they must be commenced and completed in the judicial system."*

The local administrative and legal procedures available to mandate compliance with the above ordinances are specified in those ordinances, particularly in:

Los Angeles County Code:

§12.80.550 Enforcement—Director's powers and duties.

§12.80.600 Notice to correct violations—Director may take action.

§12.80.610 Violation a public nuisance.

§12.80.620 Nuisance abatement—Director to perform work when—Costs.

§12.80.630 Violation—Penalty.

§12.80.635 Administrative fines.

§12.80.640 Penalties not exclusive.

§12.84.450 LID Plan Review.

§12.84.460 Additional Requirements.

Title 26, §103 Violations And Penalties

Title 26, §104 Organization And Enforcement

Title 26, §105 Appeals Boards

Title 26, §106 Permits

§22.60.330 General prohibitions.

§22.60.340 Violations.

§22.60.350 Public nuisance.

§22.60.360 Infractions.

§22.60.370 Injunction.

§22.60.380 Enforcement.

§22.60.390 Zoning enforcement order and noncompliance fee.

LACFCD Code:

§21.05 Standards, Guidelines, and Criteria

§21.07 Prohibited Discharges

§21.09 Installation or Use of Illicit Connections Prohibited

§21.11 Littering Prohibited

§21.13 Evidence of Compliance With Permit Requirements for Industrial or Commercial Activity

§21.15 Notification of Uncontrolled Discharges Required

§21.17 Requirement to Monitor and Analyze

§21.23 Violation a Public Nuisance

LACFCD attempts to first resolve each enforcement action administratively. However, the above cited ordinances also provide LACFCD with the authority to pursue such actions in the judicial system as necessary.

Very truly yours,

JOHN F. KRATTLI  
County Counsel

By 

JUDITH A. FRIES  
Principal Deputy County Counsel  
Public Works Division

JAF:jjj

**STEVEN N. SKOLNIK**

Attorney at Law  
15332 Antioch Street, #436  
Pacific Palisades, California 90272  
Telephone: (310) 459-3418 Facsimile: (310) 606-2775  
E-Mail: sskolniklaw@gmail.com

December 9, 2013

Lisa Rapp, Director of Public Works  
City of Lakewood  
5050 Clark Avenue  
Lakewood, CA 90712

Re: Order No. R4-2012-0175  
NPDES No. CAS004001

Dear Ms. Rapp:

In my capacity as City Attorney for the City of Lakewood (the "City"), I hereby confirm that the City has the legal authority within its jurisdiction to implement and enforce each of the requirements contained in 40 CFR @ 122.26(d)(2)(i)(A-F) and the Order referenced above. Such legal authority is derived from Article 11, Section 7 of the California Constitution, Section 13002 of the California Water Code, and Section 5801 of the Lakewood Municipal Code, which incorporates by reference the pertinent provisions of the Los Angeles County Code.

The City is authorized to take enforcement action by administrative proceedings or in the judicial system.

Very truly yours,



Steven N. Skolnik

December 9, 2013

**VIA U.S. MAIL AND E-MAIL**

Mr. Samuel Unger  
Executive Officer  
Los Angeles Regional Quality Control Board  
320 W. 4th Street, Suite 200  
Los Angeles, CA 90013  
[sunger@waterboards.ca.gov](mailto:sunger@waterboards.ca.gov)

Re: Legal Authority of the City of La Mirada to Implement and Enforce the Requirements of 40 CFR 122.26(d)(2)(i)(A-F) and RWQCB Order R4-2012-0175, NPDES Permit CAS004001

Dear Mr. Unger:

The City of La Mirada (the "City"), by and through its City Attorney, hereby submits the following certification ("Statement"), pursuant to Section VI.A.2.b of Order R4-2012-0175 (NPDES Permit CAS004001), issued by the California Regional Water Quality Control Board, Los Angeles Region ("RWQCB") on November 8, 2012 and entitled "Waste Discharge Requirements for Municipal Separate Storm Sewer System ("MS4") Discharges within the Coastal Watersheds of Los Angeles County, Except Those Discharges Originating from the City of Long Beach MS4" (the "Permit").

The City is one of the co-permittees under the Permit. Section VI.A.2.b of the Permit requires the City to provide the RWQCB with a statement by its chief legal counsel, certifying that the City has the legal authority to implement and enforce each of the current requirements set forth in 40 C.F.R. § 122.26(d)(2)(i)(A-F) and the Permit. The purpose of this Statement is to describe the City's compliance with Section VI.A.2.b of the Permit. As discussed in further detail herein, it is our opinion that the City has the necessary legal authority to implement the Permit and to control and prohibit discharges of pollutants into the Municipal Separate Storm Sewer System ("MS4"). However, this Statement is not, nor should it be construed as, a waiver of any rights that the City may have relating to the Permit.

**1. Legal Authority Statement**

In our opinion, the City has the necessary legal authority to comply with the legal requirements imposed upon it under the Permit, consistent with the requirements set forth in the U.S. Environmental Protection Agency's regulations promulgated under the Clean Water Act, and, specifically, 40 C.F.R. § 122.26(d)(2)(i)(A-F), and to the

RICHARD RICHARDS  
(1916-1988)

GLENN R. WATSON  
(1917-2010)

HARRY L. GERSHON  
(1922-2007)

STEVEN L. DORSEY  
WILLIAM L. STRAUSS  
MITCHELL E. ABBOTT  
GREGORY W. STEPANICICH  
ROCHELLE BROWNE  
QUINN M. BARROW  
CAROL W. LYNCH  
GREGORY M. KUNERT  
THOMAS M. JIMBO  
ROBERT C. CECCON  
STEVEN H. KAUFMANN  
KEVIN G. ENNIS  
ROBIN D. HARRIS  
MICHAEL ESTRADA  
LAURENCE S. WIENER  
STEVEN R. ORR  
B. TILDEN KIM  
SASKIA T. ASAMURA  
KAYSER O. SUME  
PETER M. THORSON  
JAMES L. MARKMAN  
CRAIG A. STEELE  
T. PETER PIERCE  
TERENCE R. BOGA  
LISA BOND  
JANET E. COLESON  
ROXANNE M. DIAZ  
JIM G. GRAYSON  
ROY A. CLARKE  
WILLIAM P. CURLLEY III  
MICHAEL F. YOSHIBA  
REGINA N. DANNER  
PAULA GUTIERREZ BAEZA  
BRUCE W. GALLOWAY  
DIANA K. CHUANG  
PATRICK K. BOBKO  
NORMAN A. DUPONT  
DAVID M. SNOW  
LOLLY A. ENRIQUEZ  
KIRSTEN R. BOWMAN  
GINETTA L. GIOVINCO  
TRISHA ORTIZ  
CANDICE K. LEE  
BILLY D. DUNSMORE  
AMY GREYSON  
DEBORAH R. HAKMAN  
D. CRAIG FOX  
G. INDER KHALSA  
MARICELA E. MARROQUIN  
GENA M. STINNETT  
JENNIFER PETRUSIS  
STEVEN L. FLOWER  
CHRISTOPHER J. DIAZ  
ERIN L. POWERS  
TOUSSAINT S. BAILEY  
SERITA R. YOUNG  
SHIRI KLIMA  
DIANA H. VARAT  
JULIE A. HAMILL  
ANDREW J. BRADY  
MOLLY R. MCLUCAS  
AARON C. O'DELL  
BYRON MILLER

OF COUNSEL  
MARK L. LAMKEN  
SAYRE WEAVER  
JIM R. KARPIAK  
TERESA HO-URANO

SAN FRANCISCO OFFICE  
TELEPHONE 415.421.8484

ORANGE COUNTY OFFICE  
TELEPHONE 714.990.0901

TEMECULA OFFICE  
TELEPHONE 951.695.2373

Mr. Samuel Unger  
December 9, 2013  
Page 2

extent permitted by state and federal law and subject to the limitations on municipal action under the California and United States Constitutions, except as noted herein.

The City, as a general law city, has broad general police powers under the California Constitution to enact legislation for health and public welfare of the community to the extent not preempted by federal or state law. In addition, the City adopted ordinances for the purpose of ensuring that it has adequate legal authority to implement and enforce its storm water control program. The City has the authority under the California Constitution and state law to enact and enforce these ordinances, and these ordinances were duly enacted.

## **2. Ordinances**

The City has adopted ordinances related to the regulation of urban runoff to control and prohibit discharges of pollutants into the MS4 and to comply with the requirements of the Permit applicable to it, as well as, to the extent applicable, 40 C.F.R. § 122.26 (d)(2)(i)(A)-(F). The City's Storm Water Ordinance (Chapter 13.12 of the La Mirada Municipal Code ("LMMC")) is the principal City ordinance addressing the control of urban runoff. Under this ordinance, the City has the necessary legal authority to do the following:

- i. 40 C.F.R. § 122.26(d)(2)(i)(A); Permit Section VI.A.2.a.i: Control the contribution of pollutants to its MS4 from storm water discharges associated with industrial and construction activity and control the quality of storm water discharged from industrial and construction sites. This requirement applies both to industrial and construction sites with coverage under an NPDES permit, as well as to those sites that do not have coverage under an NPDES permit (LMMC § 13.12.070—Industrial Site Activity; 13.12.060—Construction sites requiring a building permit and/or grading plan);
- ii. 40 C.F.R. § 122.26(d)(2)(i)(C); Permit Section VI.A.2.a.ii: Prohibit all non-storm water discharges through the MS4 to receiving waters not otherwise authorized or conditionally exempt pursuant to Part III.A (LMMC § 13.12.040 --Illicit discharges and connection.; LMMC § 13.12.050--Illicit disposal);
- iii. 40 C.F.R. § 122.26(d)(2)(i)(B); Permit Section VI.A.2.a.iii: Prohibit and eliminate illicit discharges and illicit connections to the MS4 (LMMC § 13.12.040 --Illicit discharges and connections; LMMC § 13.12.050--Illicit disposal);
- iv. 40 C.F.R. § 122.26(d)(2)(i)(C); Permit Section VI.A.2.a.iv: Control the discharge of spills, dumping, or disposal of materials other than storm water to its MS4 (LMMC § 13.12.040 --Illicit discharges and connections.; LMMC §

Mr. Samuel Unger  
December 9, 2013  
Page 3

- 13.12.050--Illicit disposal; LMMC § 13.12.090--Civil remedies available; LMMC § 13.12.100--Penalty for violation of chapter);
- v. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.v: Require compliance with conditions in Permittee ordinances, permits, contracts or orders (*i.e.*, hold dischargers to its MS4 accountable for their contributions of pollutants and flows) (LMMC § 13.12.090--Civil remedies available; LMMC § 13.12.100--Penalty for violation of chapter);
  - vi. 40 C.F.R. § 122.26(d)(2)(i)(E)-(F); Permit Section VI.A.2.a.vi: Utilize enforcement mechanisms to require compliance with applicable ordinances, permits, contracts, or orders (LMMC § 13.12.090--Civil remedies available; LMMC § 13.12.100--Penalty for violation of chapter);
  - vii. 40 C.F.R. § 122.26(d)(2)(i)(D); Permit Section VI.A.2.a.vii: Control the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements among Copermitees (LMMC § 13.12.090--Civil remedies available; LMMC § 13.12.100--Penalty for violation of chapter);
  - viii. 40 C.F.R. § 122.26 (d)(2)(i)(D); Permit Section VI.A.2.a.viii: Control of the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements with other owners of the MS4 such as the State of California Department of Transportation (LMMC § 13.12.040 --Illicit discharges and connections; LMMC § 13.12.050--Illicit disposal; LMMC § 13.12.090--Civil remedies available; LMMC § 13.12.100--Penalty for violation of chapter);
  - ix. 40 C.F.R. § 122.26(d)(2)(i)(F); Permit Section VI.A.2.a.ix: Carry out all inspections, surveillance, and monitoring procedures necessary to determine compliance and noncompliance with applicable municipal ordinances, permits, contracts and orders, and with the provisions of this Order, including the prohibition of non-storm water discharges into the MS4 and receiving waters. This means the Permittee must have authority to enter, monitor, inspect, take measurements, review and copy records, and require regular reports from entities discharging into its MS4 (LMMC § 13.12.075--Standard urban stormwater mitigation plan (SUSMP) requirements);
  - x. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.x: Require the use of control measures to prevent or reduce the discharge of pollutants to achieve water quality standards/receiving water limitations (LMMC § 13.12.075--Standard urban stormwater mitigation plan (SUSMP) requirements);

Mr. Samuel Unger  
December 9, 2013  
Page 4

- xi. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.xi: Require that structural BMPs are properly operated and maintained (LMMC § 13.12.070—Industrial Site Activity; 13.12.060—Construction sites requiring a building permit and/or grading plan; LMMC § 13.12.075--Standard urban stormwater mitigation plan (SUSMP) requirements); and
- xii. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.xii: Require documentation on the operation and maintenance of structural BMPs and their effectiveness in reducing the discharge of pollutants to the MS4 (LMMC § 13.12.075--Standard urban stormwater mitigation plan (SUSMP) requirements; LMMC § 13.12.090--Civil remedies available; LMMC § 13.12.100--Penalty for violation of chapter).

### **3. Implementation**

Some of the City's ordinances are implemented through permit programs and others are implemented as regulatory programs. Under each ordinance, one or more City bodies, departments, or department directors are authorized and directed in each ordinance to take the actions contemplated by the ordinance (*e.g.*, to consider evidence and make findings, to issue or deny permits, to impose conditions on projects, to inspect, to take enforcement action, etc.).

The City's Storm Water Ordinance (LMMC Chapter 13.12) is the principal City ordinance addressing the control of urban runoff. This ordinance is regulatory, and applies to specified new and existing residential and business communities and associated facilities and activities, as well as new development and redevelopment, and all other specified new and existing facilities and activities that threaten to discharge pollutants within the boundaries of the City and within its regulatory jurisdiction, whether or not a City permit or approval is required. The City's Storm Water Ordinance also contains discharge prohibitions and requirements for the implementation of BMPs and other requirements necessary to implement the Permit.

Other City departments require compliance with the City's Storm Water Ordinance as a condition for issuance of relevant City permits. City departments may also impose specific conditions of approval consistent with the City's Storm Water Ordinance. All City environmental ordinances are also implemented, in part, through the application of the CEQA process to proposed projects.

### **4. Administrative and Judicial/Legal Procedures**

In addition to the above authority, the City has in place various legal and administrative procedures to assist in enforcing the various urban runoff related Ordinances, including the following:

Mr. Samuel Unger  
December 9, 2013  
Page 5

**A. Administrative Remedies**

- General Penalties (LMMC Chapter 1.08—Penalties, Administrative and Civil Remedies, and General Provisions).
- Administrative Penalties and Citations (LMMC Chapter 1.08—Penalties, Administrative and Civil Remedies, and General Provisions).

**B. Nuisance Remedies**

- Public nuisance under State law.
- City nuisance abatement procedures (LMMC Chapter 1.08—Penalties, Administrative and Civil Remedies, and General Provisions).

**C. Criminal Remedies**

- Misdemeanor citations/prosecution (LMMC Chapter 1.08—Penalties, Administrative and Civil Remedies, and General Provisions).

**D. Equitable Remedies**

- Injunctive relief under State law and the Municipal Code (LMMC Chapter 1.08—Penalties, Administrative and Civil Remedies, and General Provisions).
- Declaratory relief under State law.

**E. Other Civil Remedies**

- Federal law claims (*e.g.*, Clean Water Act and Resource Conservation and Recovery Act Citizen Suits).
- Remedies under the California Government Code.

Violations of the City's Storm Water Ordinance are deemed a "public nuisance," in which case enforcement actions can be completed administratively, or judicially when necessary.

Mr. Samuel Unger  
December 9, 2013  
Page 6

Please contact me if you have any questions or if you need any additional information regarding the City's legal authority to enforce the Permit.  
Very truly yours,



James L. Markman  
City Attorney

cc: Mayor and Members of the City Council  
Jeff Boynton, City Manager  
Gary Sanui, Public Works Director  
Marlin Muñoz, Senior Administrative Analyst  
Candice K. Lee, Esq.  
Andrew Brady, Esq.

82001-0004\1669554v1.doc



**RICHARDS | WATSON | GERSHON**

ATTORNEYS AT LAW – A PROFESSIONAL CORPORATION

355 South Grand Avenue, 40th Floor, Los Angeles, California 90071-3101  
Telephone 213.626.8484 Facsimile 213.626.0078

RICHARD RICHARDS  
(1916-1988)

GLENN R. WATSON  
(1917-2010)

HARRY L. GERSHON  
(1922-2007)

STEVEN L. DORSEY  
WILLIAM L. STRAUSS  
MITCHELL E. ABBOTT  
GREGORY W. STEPANICICH  
ROCHELLE BROWNE  
QUINN M. BARROW  
CAROL W. LYNCH  
GREGORY M. KUNERT  
THOMAS M. JIMBO  
ROBERT C. CECCON  
STEVEN H. KAUFMANN  
KEVIN G. ENNIS  
ROBIN D. HARRIS  
MICHAEL ESTRADA  
LAURENCE S. WIENER  
STEVEN R. ORR  
B. TILDEN KIM  
SASKIA T. ASAMURA  
KAYSER O. SUME  
PETER M. THORSON  
JAMES L. MARKMAN  
CRAIG A. STEELE  
T. PETER PIERCE  
TERENCE R. BOGA  
LISA BOND  
JANET E. COLESON  
ROXANNE M. DIAZ  
JIM G. GRAYSON  
ROY A. CLARKE  
WILLIAM P. CURLEY III  
MICHAEL F. YOSHIBA  
REGINA N. DANNER  
PAULA GUTIERREZ BAEZA  
BRUCE W. GALLOWAY  
DIANA K. CHUANG  
PATRICK K. BOBKO  
NORMAN A. DUPONT  
DAVID M. SNOW  
LOLLY A. ENRIQUEZ  
KIRSTEN R. BOWMAN  
GINETTA L. GIOVINCO  
TRISHA ORTIZ  
CANDICE K. LEE  
BILLY D. DUNSMORE  
AMY GREYSON  
DEBORAH R. HAKMAN  
D. CRAIG FOX  
G. INDER KHALSA  
MARICELA E. MARROQUIN  
GENA M. STINNETT  
JENNIFER PETRUSIS  
STEVEN L. FLOWER  
CHRISTOPHER J. DIAZ  
ERIN L. POWERS  
TOUSSAINT S. BAILEY  
SERITA R. YOUNG  
SHIRI KLIMA  
DIANA H. VARAT  
JULIE A. HAMILL  
ANDREW J. BRADY  
MOLLY R. MCLUCAS  
AARON C. O'DELL  
BYRON MILLER

OF COUNSEL  
MARK L. LAMKEN  
SAYRE WEAVER  
JIM R. KARPIAK  
TERESA HO-URANO

SAN FRANCISCO OFFICE  
TELEPHONE 415.421.8484

ORANGE COUNTY OFFICE  
TELEPHONE 714.990.0901

TEMECULA OFFICE  
TELEPHONE 951.695.2373

December 11, 2013

**VIA U.S. MAIL AND E-MAIL**

Mr. Samuel Unger  
Executive Officer  
Los Angeles Regional Quality Control Board  
320 W. 4th Street, Suite 200  
Los Angeles, CA 90013  
[sunger@waterboards.ca.gov](mailto:sunger@waterboards.ca.gov)

Re: Legal Authority of the City of Norwalk to Implement and Enforce the Requirements of 40 CFR 122.26(d)(2)(i)(A-F) and RWQCB Order R4-2012-0175, NPDES Permit CAS004001

Dear Mr. Unger:

The City of Norwalk (the "City"), by and through its City Attorney, hereby submits the following certification ("Statement"), pursuant to Section VI.A.2.b of Order R4-2012-0175 (NPDES Permit CAS004001), issued by the California Regional Water Quality Control Board, Los Angeles Region ("RWQCB") on November 8, 2012 and entitled "Waste Discharge Requirements for Municipal Separate Storm Sewer System ("MS4") Discharges within the Coastal Watersheds of Los Angeles County, Except Those Discharges Originating from the City of Long Beach MS4" (the "Permit").

The City is one of the co-permittees under the Permit. Section VI.A.2.b of the Permit requires the City to provide the RWQCB with a statement by its chief legal counsel, certifying that the City has the legal authority to implement and enforce each of the current requirements set forth in 40 C.F.R. § 122.26(d)(2)(i)(A-F) and the Permit. The purpose of this Statement is to describe the City's compliance with Section VI.A.2.b of the Permit. As discussed in further detail herein, it is our opinion that the City has the necessary legal authority to implement the Permit and to control and prohibit discharges of pollutants into the Municipal Separate Storm Sewer System ("MS4"). However, this Statement is not, nor should it be construed as, a waiver of any rights that the City may have relating to the Permit.

**1. Legal Authority Statement**

In our opinion, the City has the necessary legal authority to comply with the legal requirements imposed upon it under the Permit, consistent with the requirements set forth in the U.S. Environmental Protection Agency's regulations promulgated under the Clean Water Act, and, specifically, 40 C.F.R. § 122.26(d)(2)(i)(A-F), and to the extent permitted by state and federal law and subject to the limitations on municipal action under the California and United States Constitutions, except as noted herein.

Mr. Samuel Unger  
December 11, 2013  
Page 2

The City, as a general law city, has broad general police powers under the California Constitution to enact legislation for health and public welfare of the community to the extent not preempted by federal or state law. In addition, the City adopted ordinances for the purpose of ensuring that it has adequate legal authority to implement and enforce its storm water control program. The City has the authority under the California Constitution and state law to enact and enforce these ordinances, and these ordinances were duly enacted.

## **2. Ordinances**

The City has adopted ordinances related to the regulation of urban runoff to control and prohibit discharges of pollutants into the MS4 and to comply with the requirements of the Permit applicable to it, as well as, to the extent applicable, 40 C.F.R. § 122.26 (d)(2)(i)(A)-(F). The City's Storm Water Ordinance (Chapter 18.04 of the Norwalk Municipal Code ("NMC")) is the principal City ordinance addressing the control of urban runoff. Under this ordinance, the City has the necessary legal authority to do the following:

- i. 40 C.F.R. § 122.26(d)(2)(i)(A); Permit Section VI.A.2.a.i: Control the contribution of pollutants to its MS4 from storm water discharges associated with industrial and construction activity and control the quality of storm water discharged from industrial and construction sites. This requirement applies both to industrial and construction sites with coverage under an NPDES permit, as well as to those sites that do not have coverage under an NPDES permit (NMC § 18.04.100--Requirements for industrial/commercial and construction activities);
- ii. 40 C.F.R. § 122.26(d)(2)(i)(C); Permit Section VI.A.2.a.ii: Prohibit all non-storm water discharges through the MS4 to receiving waters not otherwise authorized or conditionally exempt pursuant to Part III.A (NMC § 18.04.070--Prohibited activities; NMC §18.04.090--Good housekeeping provisions);
- iii. 40 C.F.R. § 122.26(d)(2)(i)(B); Permit Section VI.A.2.a.iii: Prohibit and eliminate illicit discharges and illicit connections to the MS4 (NMC § 18.04.070--Prohibited activities);
- iv. 40 C.F.R. § 122.26(d)(2)(i)(C); Permit Section VI.A.2.a.iv: Control the discharge of spills, dumping, or disposal of materials other than storm water to its MS4 (NMC § 18.04.070--Prohibited activities; NMC §18.04.090--Good housekeeping provisions; NMC §18.04.110--Enforcement);
- v. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.v: Require compliance with conditions in Permittee ordinances, permits, contracts or

Mr. Samuel Unger  
December 11, 2013  
Page 3

- orders (*i.e.*, hold dischargers to its MS4 accountable for their contributions of pollutants and flows) (NMC §18.04.110--Enforcement);
- vi. 40 C.F.R. § 122.26(d)(2)(i)(E)-(F); Permit Section VI.A.2.a.vi: Utilize enforcement mechanisms to require compliance with applicable ordinances, permits, contracts, or orders (NMC §18.04.110--Enforcement);
  - vii. 40 C.F.R. § 122.26(d)(2)(i)(D); Permit Section VI.A.2.a.vii: Control the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements among Copermitees (NMC § 18.04.070--Prohibited activities; NMC §18.04.110--Enforcement);
  - viii. 40 C.F.R. § 122.26 (d)(2)(i)(D); Permit Section VI.A.2.a.viii: Control of the contribution of pollutants from one portion of the shared MS4 to another portion of the MS4 through interagency agreements with other owners of the MS4 such as the State of California Department of Transportation (NMC § 18.04.070--Prohibited activities; NMC §18.04.110--Enforcement);
  - ix. 40 C.F.R. § 122.26(d)(2)(i)(F); Permit Section VI.A.2.a.ix: Carry out all inspections, surveillance, and monitoring procedures necessary to determine compliance and noncompliance with applicable municipal ordinances, permits, contracts and orders, and with the provisions of this Order, including the prohibition of non-storm water discharges into the MS4 and receiving waters. This means the Permittee must have authority to enter, monitor, inspect, take measurements, review and copy records, and require regular reports from entities discharging into its MS4 (NMC § 18.04.105 Standard urban stormwater mitigation plan (SUSMP) requirements for new development and redevelopment projects);
  - x. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.x: Require the use of control measures to prevent or reduce the discharge of pollutants to achieve water quality standards/receiving water limitations (NMC § 18.04.105 Standard urban stormwater mitigation plan (SUSMP) requirements for new development and redevelopment projects; NMC § 18.04.070--Prohibited activities; NMC §18.04.090--Good housekeeping provisions; NMC §18.04.110--Enforcement);
  - xi. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.xi: Require that structural BMPs are properly operated and maintained (NMC § 18.04.105 Standard urban stormwater mitigation plan (SUSMP) requirements for new development and redevelopment projects); and
  - xii. 40 C.F.R. § 122.26(d)(2)(i)(E); Permit Section VI.A.2.a.xii: Require documentation on the operation and maintenance of structural BMPs and their

Mr. Samuel Unger  
December 11, 2013  
Page 4

effectiveness in reducing the discharge of pollutants to the MS4 (NMC § 18.04.105 Standard urban stormwater mitigation plan (SUSMP) requirements for new development and redevelopment projects; NMC §18.04.090--Good housekeeping provisions; NMC §18.04.110--Enforcement).

### **3. Implementation**

Some of the City's ordinances are implemented through permit programs and others are implemented as regulatory programs. Under each ordinance, one or more City bodies, departments, or department directors are authorized and directed in each ordinance to take the actions contemplated by the ordinance (*e.g.*, to consider evidence and make findings, to issue or deny permits, to impose conditions on projects, to inspect, to take enforcement action, etc.).

The City's Storm Water Ordinance (NMC Chapter 18.04) is the principal City ordinance addressing the control of urban runoff. This ordinance is regulatory, and applies to specified new and existing residential and business communities and associated facilities and activities, as well as new development and redevelopment, and all other specified new and existing facilities and activities that threaten to discharge pollutants within the boundaries of the City and within its regulatory jurisdiction, whether or not a City permit or approval is required. The City's Storm Water Ordinance also contains discharge prohibitions and requirements for the implementation of BMPs and other requirements necessary to implement the Permit.

Other City departments require compliance with the City's Storm Water Ordinance as a condition for issuance of relevant City permits. City departments may also impose specific conditions of approval consistent with the City's Storm Water Ordinance. All City environmental ordinances are also implemented, in part, through the application of the CEQA process to proposed projects.

### **4. Administrative and Judicial/Legal Procedures**

In addition to the above authority, the City has in place various legal and administrative procedures to assist in enforcing the various urban runoff related Ordinances, including the following:

#### **A. Administrative Remedies**

- General Penalties (NMC Chapter 1.16--Violations).
- Administrative Penalties and Citations (NMC Chapter 1.13—Administrative Citations; NMC Chapter 1.12—Arrest and Citation Procedure).

#### **B. Nuisance Remedies**

- Public nuisance under State law.

Mr. Samuel Unger  
December 11, 2013  
Page 5

- City nuisance abatement procedures (NMC Chapter 1.16—Violations; NMC Chapter 1.13—Administrative Citations; NMC Chapter 1.12—Arrest and Citation Procedure).

**C. Criminal Remedies**

- Misdemeanor citations/prosecution (NMC Chapter 1.12—Arrest and Citation Procedure).

**D. Equitable Remedies**

- Injunctive relief under State law and the Municipal Code (NMC Chapter 1.16—Violations; NMC Chapter 1.13—Administrative Citations; NMC Chapter 1.12—Arrest and Citation Procedure).
- Declaratory relief under State law.


**E. Other Civil Remedies**

- Federal law claims (*e.g.*, Clean Water Act and Resource Conservation and Recovery Act Citizen Suits).
- Remedies under the California Government Code.

Violations of the City's Storm Water Ordinance are deemed a "public nuisance," in which case enforcement actions can be completed administratively, or judicially when necessary.

Please contact me if you have any questions or if you need any additional information regarding the City's legal authority to enforce the Permit.

Very truly yours,



Steven L. Dorsey  
City Attorney

cc: Mayor and Members of the City Council  
Michael Egan, City Manager  
Adriana Figueroa, Administrative Services Manager  
Candice K. Lee, Esq.  
Andrew Brady, Esq.



December 13, 2013

Sam Unger, P.E., Executive Officer  
California Regional Water Quality  
Control Board -- Los Angeles Region  
320 West 4th Street, Suite 200  
Los Angeles, CA 90013-1105

Subject: Certification of Legal Authority

Dear Mr. Unger:

Alvarez-Glasman & Colvin serves as the City Attorney's Office for the City of Pico Rivera. As the City Attorney for the City of Pico Rivera (the "City"), I am aware of the following legal authority requirements specified in VI.A.2.b, of the MS4 Permit for Los Angeles County, Order No. R4-2012-0175, NPDES Permit No. CAS004001:

Each Permittee must submit a statement certified by its chief legal counsel that the Permittee has the legal authority within its jurisdiction to implement and enforce each of the requirements contained in 40 CFR § 122.26(d)(2)(i)(A-F) and this Order. Each Permittee shall submit this certification annually as part of its Annual Report beginning with the first Annual Report required under this Order. These statements must include:

- i. Citation of applicable municipal ordinances or other appropriate legal authorities and their relationship to the requirements of 40 CFR § 122.26(d)(2)(i)(A)-(F) and of this Order; and
- ii. Identification of the local administrative and legal procedures available to mandate compliance with applicable municipal ordinances identified in subsection (i) above and therefore with the conditions of this Order, and a statement as to whether enforcement actions can be completed administratively or whether they must be commenced and completed in the judicial system.

The City has the legal authority to require compliance with the requirements associated with 40 CFR § 122.26(d)(2)(i)(A-F) and applicable provisions of the Order per Chapter 16.04 Storm Water and Urban Runoff Pollution Prevention of the City of Pico Rivera Municipal Code. The City has had such legal authority since 2002.

The City's Municipal Code provides for both administrative enforcement and legal enforcement of violations, which may result in administrative, civil, or criminal penalties. Section 16.04.140 provides that in the event the City serves a person with a notice of violation, and that person fails to comply within the given time period, the City has multiple remedies which are not listed to be exclusive or exhaustive, including: seeking prosecution of violations as a misdemeanor resulting in fines or imprisonment; seeking restitution of costs incurred by the City in the investigation and enforcement of compliance; and prosecution of violations as nuisance abatement resulting in liens and cost recovery.

Should you have any questions regarding this matter, please feel free to contact Deputy City Attorney Teresa Chen at (562) 699-5500.

Sincerely,

ALVAREZ-GLASMAN & COLVIN



Arnold M. Alvarez-Glasman  
City Attorney

**STEVEN N. SKOLNIK**

Attorney at Law  
15332 Antioch Street, #436  
Pacific Palisades, California 90272  
Telephone: (310) 459-3418 Facsimile: (310) 606-2775  
E-Mail: sskolniklaw@gmail.com

December 9, 2013

Noe Negrete, Director of Public Works  
City of Santa Fe Springs  
11710 Telegraph Road  
Santa Fe Springs, CA 90670

Re: Order No. R4-2012-0175  
NPDES No. CAS004001

Dear Mr. Negrete::

In my capacity as City Attorney for the City of Santa Fe Springs (the "City"), I hereby confirm that the City has the legal authority within its jurisdiction to implement and enforce each of the requirements contained in 40 CFR @ 122.26(d)(2)(i)(A-F) and the Order referenced above. Such legal authority is derived from Article 11, Section 7 of the California Constitution, Section 13002 of the California Water Code, and Chapter 52 of the City Code.

The City is authorized to take enforcement action by administrative proceedings or in the judicial system.

Very truly yours,



Steven N. Skolnik



JONES & MAYER

ATTORNEYS AT LAW

3777 NORTH HARBOR BOULEVARD • FULLERTON, CALIFORNIA 92835  
(714) 446-1400 • (562) 697-1751 • FAX (714) 446-1448

Richard D. Jones\*  
Partners  
Martin J. Mayer  
Kimberly Hall Barlow  
James R. Touchstone

Richard L. Adams II  
Jamaar Boyd-Weatherby  
Baron J. Bettenhausen  
Christian L. Bettenhausen  
Paul R. Coble  
Keith F. Collins

Michael Q. Do  
Thomas P. Duarte  
Elena Q. Gerli  
Katherine M. Hardy  
Krista MacNevin Jee  
Ryan R. Jones

Robert Khuu  
Gary S. Kranker  
Christopher F. Neumeyer  
Kathya M. Oliva  
Gregory P. Palmer

Danny L. Peelman  
Harold W. Potter  
Denise L. Rocawich  
Yolanda M. Summerhill  
Ivy M. Tsai

\*a Professional Law Corporation

Of Counsel  
Michael R. Capizzi  
Dean J. Pucci  
Steven N. Skolnik

Consultant  
Mervin D. Feinstein

December 9, 2013

Mr. Sam Unger, Executive Officer  
California Regional Water Quality Control Board  
320 W. 4<sup>th</sup> Street, Suite 200  
Los Angeles, CA 90013-1105

Re: Legal Authority Certification for the City of Whittier

Dear Mr. Unger:

As legal counsel for the City of Whittier, I have reviewed its existing ordinances including Chapter 8.36 of the Municipal Code, applicable statutes, and/or existing contracts and have determined that the City can operate pursuant to the legal authority required in 40 CFR 122.26(d)(2)(i)(A)-(F) and Part VI. A.2 of Order No. R4-2012-0175, issued by the Regional Water Quality Control Board – Los Angeles Region (“RWQCB”), adopted on December 28, 2012 and entitled “Waste Discharge Requirements for Municipal Separate Storm Sewer System (MS4) Discharges within the Coastal Watersheds of Los Angeles County, except those Discharges Originating from the City of Long Beach (MS4)” [NPDES No. CAS004001] (the \$2012 NPDES Permit”).

Please call the undersigned if you have any questions.

Sincerely,

Richard L. Adams, II  
Assistant City Attorney, City of Whittier

RLA/dm

cc: David Pelsler, Director of Public Works  
John L. Hunter & Associates

Watershed Management Program Appendix 8

# A-8-1 Coordinated Integrated Monitoring Program

**INCLUDED AS A SEPARATE SUBMITTAL**