

Notice of Intent Application Reception

File Number: 302024-04

Project Name: 904141582 Plantenders Anchor Replacement

Received: 2/15/2024

Date Posted: 2/23/2024

End of 21 Day Public Comment Period: 3/15/2024

Project City: Silverado

Project County: Orange

Applicant Organization: Southern California Edison

Applicant Name: Victoria Parsons

Waterboard Staff: CL

Brief Description of Project:

Project Description: SCE is continually repairing, maintaining, upgrading and replacing distribution facilities throughout its service territory. Ongoing operation and maintenance activities are necessary to ensure safe, reliable service as mandated by the California Public Utilities Commission. The proposed Project involves removing one anchor associated with Pole 2044133E and installing a new anchor.

Project Activities: The new anchor hole will be dug by hand using hand-tools or dug using a truck mounted auger. The anchor will be set within a three-foot radius of the old anchor. Standard excavation depths range between 6 and 10 feet with a diameter of 2 to 3 feet, resulting in approximately 1.20 cubic yards of native soil material to be temporarily stored adjacent to the hole. The area of soil disturbance (i.e. excavation, side casting and backfill) would be limited to approximately 10 feet around the anchor. Once the anchor is in place the hole will be backfilled and compacted with native soils. The guy wire will be attached to the anchor rod and pole. The anchor will be accessed by truck from Ridgetop Road and vehicles and equipment will be staged on the side of the road. No vegetation trimming or removal will be required.