

Exhibit 3-9

Delivery of Kern River water to canal and conveyance facilities
located below First Point of Measurement for the 2008 Calendar Year

Delivery Point	Flow (acre-feet)	Percentage of First Point Flow (%)
Kern River at First Point	455,874	100
Beardsley Canal	141,696	31.1
Calloway Canal	27,709	6.1
Kern Island Canal	147,668	32.4
Eastside Canal	15,393	3.4
Stine Canal	15,166	3.3
Arvin-Edison Turnout	7,134	1.6
Buena Vista Canal	20,993	4.6
Rosedale Channel	0	0
Truxtun Lakes	1,002	0.2
The Park at River Walk	633	0.1
Berrenda Mesa Pipeline	0	0
Pioneer Property	0	0
2800 Acre Recharge Facility	0	0
Second Point of Measurement	54,313	11.9
Seepage Loss (River and Carrier)	24,167	5.3

Source: 2008 Hydrologic Annual Report for Kern River (Pearce 2008)