

Any workplan approval must be of sufficient detail to ensure that all current permit terms will be met at all times. If the pond continues in operation into the rainy season, the workplan must also incorporate the technical requirements of option 1 listed in the CDO. The third requirement may be satisfied by a demonstration that the liner system has not leaked. The second and fourth requirement may be satisfied through a third party who is approved by the Executive Officer, determining that the impoundment currently has the capacity to contain, and prevent inundation from, the 1,000 year, 24-hour precipitation event and that the five foot separation from the bottom of the surface impoundment will be maintained. The workplan shall include a timeline for removing all wastes from the surface impoundment at the earliest possible date, but not to exceed 5 years.