

---

## Central Valley Regional Water Quality Control Board

1 September 2016

William Niemi  
Niemi Development Partners, LLC  
4120 Douglas Boulevard, #306-534  
Granite Bay, CA 95746

### **CLEAN WATER ACT §401 TECHNICALLY CONDITIONED WATER QUALITY CERTIFICATION; NIEMI DEVELOPMENT PARTNERS, LLC, MEADOWLANDS SUBDIVISION PROJECT (WDID #5A31CR00439), PLACER COUNTY**

#### **ACTION:**

1.  Order for Standard Certification
2.  Order for Technically-conditioned Certification
3.  Order for Denial of Certification

#### **WATER QUALITY CERTIFICATION STANDARD CONDITIONS:**

1. This Order serves as a Water Quality Certification (Certification) action that is subject to modification or revocation upon administrative or judicial review, including review and amendment pursuant to § 13330 of the California Water Code and § 3867 of the California Code of Regulations (CCR).
2. This certification action is not intended and shall not be construed to apply to any discharge from any activity involving a hydroelectric facility requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent certification application was filed pursuant to 23 CCR § 3855(b) of the California Code of Regulations, and the application specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.
3. The validity of any non-denial certification action shall be conditioned upon total payment of the full fee required § 3833 of the California Code of Regulations.
4. This Certification is no longer valid if the project (as described) is modified, or coverage under § 404 of the Clean Water Act has expired. The Applicant shall notify the Central Valley Water Board within 7 days of the project completion.

5. All reports, notices, or other documents required by this Certification or requested by the Central Valley Water Board shall be signed by a person described below or by a duly authorized representative of that person.
  - a. For a corporation: by a responsible corporate officer such as (1) a president, secretary, treasurer, or vice president of the corporation in charge of a principal business function; (2) any other person who performs similar policy or decision-making functions for the corporation; or (3) the manager of one or more manufacturing, production, or operating facilities if *authority* to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.
  - b. For a partnership or sole proprietorship: by a general partner or the proprietor.
  - c. For a municipality, State, federal, or other public agency: by either a principal executive officer or ranking elected official.

6. Any person signing a document under Standard Condition No. 5 shall make the following certification, whether written or implied:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

#### TECHNICAL CERTIFICATION CONDITIONS:

In addition to the above standard conditions, the Applicant shall satisfy the following:

1. The Applicant shall notify the Central Valley Regional Water Quality Control Board (Central Valley Water Board) in writing at least **seven (7) days** in advance of the start of any work within waters of the United States. The notification shall include the name of the project and the WDID number, and shall be sent to the Central Valley Water Board Contact indicated in this Certification.
2. Except for activities permitted by the U.S. Army Corps under §404 of the Clean Water Act, soil, silt, or other organic materials shall not be placed where such materials could pass into surface water or surface water drainage courses.
3. The Applicant shall maintain a copy of this Certification and supporting documentation (Project Information Sheet) at the Project site during construction for review by site personnel and agencies. All personnel (employees, contractors, and subcontractors) performing work on the proposed Project shall be adequately informed and trained regarding the conditions of this Certification.

4. The Applicant shall perform surface water sampling:
- a) when performing any in-water work;
  - b) in the event that project activities result in any materials reaching surface waters; or
  - c) when any activities result in the creation of a visible plume in surface waters.

The monitoring requirements in Table 1 shall be conducted by taking a sample of the ambient conditions before work begins in the work area, and sampling during work in the work area. The sampling frequency may be modified for certain projects with written approval from Central Valley Water Board staff.

**Table 1:**

Parameter	Unit	Type of Sample	Minimum Sampling Frequency	Required Analytical Test Method
Turbidity	NTU	Grab <sup>(1)</sup>	Every 4 hours during in-water work	(4)
Settleable Material	mL/L	Grab <sup>(1)</sup>	Every 4 hours during in-water work	(2)
Visible construction related pollutants <sup>(3)</sup>	Observations	Visual Inspections	Continuous throughout the construction period	—

<sup>(1)</sup> Grab samples shall be taken at mid-depth and be collected at the same time each day to get a complete representation of variations in the receiving water.

<sup>(2)</sup> Pollutants shall be analyzed using the analytical methods described in 40 Code of Federal Regulations Part 136; where no methods are specified for a given pollutant.

<sup>(3)</sup> Visible construction-related pollutants include oil, grease, foam, fuel, petroleum products, and construction-related, excavated, organic or earthen materials.

<sup>(4)</sup> A hand-held field meter may be used, provided that the meter utilizes a USEPA-approved algorithm/method and is calibrated and maintained in accordance with the manufacturer's instructions. A calibration and maintenance log for each meter used for monitoring required by this Certification shall be maintained at the Project site.

As appropriate, surface water monitoring shall occur at mid-depth. A surface water monitoring report shall be submitted to the Central Valley Water Board Contact indicated in this Certification within two weeks of initiation of sampling and every two weeks thereafter. In reporting the monitoring data, the Applicant shall arrange the data in tabular form so that the sampling locations, date, constituents, and concentrations are readily discernible. The data shall be summarized in such a manner to illustrate clearly whether the Project complies with Certification requirements. The report shall include surface water sampling results, visual observations, and identification of the turbidity increase in the receiving water applicable to the natural turbidity conditions specified in the turbidity criteria below.

If no monitoring is conducted, the Applicant shall submit a written statement to the Central Valley Water Board Contact indicated in the Certification stating, "No monitoring was required." with the Notice of Completion.

5. The Central Valley Water Board adopted a *Water Quality Control Plan for the Sacramento River and San Joaquin River Basins*, Fourth Edition, revised April 2016 (Basin Plan) that designates beneficial uses, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for all waters addressed through the plan. Turbidity and settleable matter limits are based on water quality objectives contained in the Basin Plan and are part of this Certification as follows:

- a) Activities shall not cause turbidity increases in surface water to exceed:
- i. where natural turbidity is less than 1 Nephelometric Turbidity Units (NTUs), controllable factors shall not cause downstream turbidity to exceed 2 NTU;
  - ii. where natural turbidity is between 1 and 5 NTUs, increases shall not exceed 1 NTU;
  - iii. where natural turbidity is between 5 and 50 NTUs, increases shall not exceed 20 percent;
  - iv. where natural turbidity is between 50 and 100 NTUs, increases shall not exceed 10 NTUs;
  - v. where natural turbidity is greater than 100 NTUs, increases shall not exceed 10 percent.

Except that these limits will be eased during in-water working periods to allow a turbidity increase of 15 NTUs over background turbidity. In determining compliance with the above limits, appropriate averaging periods may be applied provided that beneficial uses will be fully protected. Averaging periods may only be used with prior approval of the Central Valley Water Board staff.

- b) Activities shall not cause settleable matter to exceed 0.1 mL/L in surface waters as measured in surface waters within the work area
6. The Applicant shall notify the Central Valley Water Board immediately if the above criteria for turbidity, settleable matter or other water quality objectives are exceeded.
7. Refueling of equipment within the floodplain or within 300 feet of the waterway is prohibited. If critical equipment must be refueled within 300 feet of the waterway, spill prevention and countermeasures must be implemented to avoid spills. Refueling areas shall be provided with secondary containment including drip pans and/or placement of absorbent material. No hazardous materials, pesticides, fuels, lubricants, oils, hydraulic fluids, or other construction-related potentially hazardous substances should be stored within a floodplain or within 300 feet of a waterway. The Applicant must perform frequent inspections of construction equipment prior to utilizing it near surface waters to ensure leaks from the equipment are not occurring and are not a threat to water quality.
8. The Applicant shall develop and maintain onsite a project-specific Spill Prevention, Containment and Cleanup Plan outlining the practices to prevent, minimize, and/or clean up potential spills during construction of the Project. The Plan must detail the Project elements,

construction equipment types and location, access and staging and construction sequence. The Plan must also address the potential of responding to a spill or prevention of spills occurring within the Project site.

9. Asphalt, drilling fluids, lubricants, paints, coating material, oil, petroleum products, or any other substances which could be hazardous to fish and wildlife resulting from or disturbed by project-related activities, shall be prevented from contaminating the soil and/or entering surface waters. Concrete must completely be cured before coming into contact with surface waters. Surface water that contacts wet concrete must be pumped out and disposed of at an appropriate off-site commercial facility, which is authorized to accept concrete wastes.
10. An effective combination of erosion and sediment control Best Management Practices (BMPs) shall be implemented and adequately working during all phases of construction.
11. All areas disturbed by Project activities shall be protected from washout or erosion.
12. All temporarily affected areas shall be restored to pre-construction contours and conditions upon completion of construction activities.
13. This Certification does not allow permanent water diversion of flow from the receiving water. This Certification is invalid if any water is permanently diverted as a part of the Project.
14. If temporary surface water diversions and/or dewatering are anticipated, the Applicant shall develop and maintain on-site a Surface Water Diversion and/or Dewatering Plan(s). The Plan(s) shall include the proposed method and duration of diversion activities. The Surface Water Diversion and/or Dewatering Plan(s) must be consistent with this Certification.
15. When work in a flowing stream is unavoidable and any dam or other artificial obstruction is being constructed, maintained, or placed in operation, sufficient water shall at all times be allowed to pass downstream, to maintain beneficial uses of waters of the State below the dam. Construction, dewatering, and removal of temporary cofferdams shall not violate **Technical Certification Condition 5 of this Certification.**
16. Any temporary dam or other artificial obstruction constructed shall only be built from clean materials such as sandbags, gravel bags, water dams, or clean/washed gravel which will cause little or no siltation. Stream flow shall be temporarily diverted using gravity flow through temporary culverts/pipes or pumped around the work site with the use of hoses.
17. The discharge of petroleum products or other excavated materials to surface water is prohibited. Activities shall not cause visible oil, grease, or foam in the receiving water. The Applicant shall notify the Central Valley Water Board as soon as practicable of any spill of petroleum products or other organic or earthen materials with written follow up within 5 days.
18. The Applicant shall apply for a name change or amendment to this Certification should any of the following occur:

- a) a change in the ownership of all or any portion of the Project;
  - b) any change in the Project description;
  - c) any change involving discharge amounts, temporary impacts, and/or permanent impacts; and/or
  - d) amendments, modifications, revisions, extensions, and/or changes to the United States Army Corps of Engineers' Individual Permit, the United States Fish and Wildlife Service decision document(s), and/or the California Department of Fish and Wildlife Streambed Alteration Agreement.
19. The Applicant shall obtain coverage under an NPDES permit for dewatering activities that result in discharges into surface water and/or shall obtain Waste Discharge Requirements (WDRs) for dewatering activities that result in discharges to land from the Central Valley Water Board.
20. The Conditions in this water quality certification are based on the information contained in the Applicant's application and in the attached "Project Information Sheet." If the Project, as described in the application and the attached Project Information Sheet, is modified or changed, this Certification is no longer valid until amended by the Central Valley Water Board.
21. The Applicant shall implement each of the mitigation measures specified in the certified Environmental Impact Report for the Project, as they pertain to biology, hydrology and water quality impacts as required by § 21081.6 of the Public Resource Code and § 15097 of the California Code of Regulations.
22. In the event of any violation or threatened violation of the conditions of this certification, the violation or threatened violation shall be subject to any remedies, penalties, process, or sanctions as provided for under the applicable state or federal law. For the purposes of section 401(d) of the Clean Water Act, the applicability of any state law authorizing remedies, penalties, process, or sanctions for the violation or threatened violation constitutes a limitation necessary to ensure compliance with water quality standards and other pertinent requirements incorporated into this certification.
- a) If the Applicant or a duly authorized representative of the project fails or refuses to furnish technical or monitoring reports, as required under this Order, or falsifies any information provided in the monitoring reports, the Applicant is subject to civil monetary liabilities, for each day of violation, or criminal liability.
  - b) In response to a suspected violation of any condition of this certification, Central Valley Water Board may require the holder of any federal permit or license subject to this certification to furnish, under penalty of perjury, any technical or monitoring reports the Central Valley Water Board deems appropriate, provided that the burden, including costs, of the reports shall bear a reasonable relationship to the need for the reports and the benefits to be obtained from the reports (Water Code, § 1051, 13165, 13267 and 13383). In response to any violation of the conditions of this certification,

the Central Valley Water Board may add to or modify the conditions of this certification as appropriate to ensure compliance.

- c) The Applicant shall allow the staff of the Central Valley Water Board, or an authorized representative(s), upon the presentation of credentials and other documents, as may be required by law, to enter the Project premises for inspection, including taking photographs and securing copies of Project-related records, for the purpose of assuring compliance with this Certification and determining the ecological success of the Project.

23. The Applicant shall provide evidence of all on-site and off-site compensatory mitigation requirements, including, but not limited to, the purchase of mitigation credits as required by the United States Army Corps of Engineers prior to commencing construction to the Central Valley Water Board.

Compensatory mitigation must comply with the effective policy at the time of Certification, which ensures no overall net loss of wetlands for impacts to waters of the State.

Evidence of compliance with compensatory mitigation requirements includes providing a letter from the approved compensatory mitigation bank. The letter must: (a) be on the compensatory mitigation bank's letterhead; (b) be signed by an authorized representative of the compensatory mitigation bank; (c) indicate the United States Army Corps of Engineers' SPK number; (d) describe the Project name and location; and (e) detail the type of compensatory mitigation credits purchased for the Project's impacts.

24. Staff of the Central Valley Water Board has prepared total maximum daily load (TMDL) allocations that, once approved, would limit methylmercury in storm water discharges to the Sacramento-San Joaquin Delta. The Central Valley Water Board has scheduled these proposed allocations to be considered for adoption. When the Central Valley Water Board adopts the TMDL and once approved by the Environmental Protection Agency, the discharge of methylmercury may be limited from the proposed project. The purpose of this condition is to provide notice to the Applicant that methylmercury discharge limitations and monitoring requirements may apply to this project in the future and also to provide notice of the Central Valley Water Board's TMDL process and that elements of the planned construction may be subject to a TMDL allocation.

25. The Applicant shall provide the Central Valley Water Board Contact indicated in this Certification a Notice of Completion (NOC) no later than 30 days after the Project completion. The NOC shall demonstrate that the project has been carried out in accordance with the project description in the Certification and in any amendments approved. The NOC shall include a map of the project location(s), including final boundaries of any on-site restoration area(s), if appropriate, and representative pre and post construction photographs. Each photograph shall include a descriptive title, date taken, photographic site, and photographic orientation

### **STORM WATER QUALITY CONDITIONS:**

The Applicant shall also satisfy the following additional storm water quality conditions:

1. The Applicant shall obtain coverage under the National Pollutant Discharge Elimination System (NPDES) General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activities Order No. 2009-0009-DWQ, as amended, for discharges to surface waters comprised of storm water associated with construction activity, including, but not limited to, demolition, clearing, grading, excavation, and other land disturbance activities of one or more acres, or where projects disturb less than one acre but are part of a larger common plan of development that in total disturbs one or more acres.
2. During the construction phase, the Applicant must employ strategies to minimize erosion and the introduction of pollutants into storm water runoff. These strategies must include the following:
  - a) the Storm Water Pollution Prevention Plan (SWPPP) must be prepared during the project planning and design phases and before construction;
  - b) an effective combination of erosion and sediment control Best Management Practices (BMPs) must be implemented and adequately working prior to the rainy season and during all phases of construction.
3. The Applicant must minimize the short and long-term impacts on receiving water quality from the Project by implementing the following post-construction storm water management practices:
  - a) minimize the amount of impervious surface;
  - b) reduce peak runoff flows;
  - c) provide treatment BMPs to reduce pollutants in runoff;
  - d) ensure existing waters of the State (e.g., wetlands, vernal pools, or creeks) are not used as pollutant source controls and/or treatment controls;
  - e) preserve and, where possible, create or restore areas that provide important water quality benefits, such as riparian corridors, wetlands, and buffer zones;
  - f) limit disturbances of natural water bodies and natural drainage systems caused by development (including development of roads, highways, and bridges);
  - g) use existing drainage master plans or studies to estimate increases in pollutant loads and flows resulting from projected future development and require incorporation of structural and non-structural BMPs to mitigate the projected pollutant load increases in surface water runoff;
  - h) identify and avoid development in areas that are particularly susceptible to erosion and sediment loss, or establish development guidance that protects areas from erosion/ sediment loss;
  - i) control post-development peak storm water run-off discharge rates and velocities to prevent or reduce downstream erosion, and to protect stream habitat.



4. The Applicant must ensure that all development within the project provides verification of maintenance provisions for post-construction structural and treatment control BMPs. Verification shall include one or more of the following, as applicable:
- a) the developer's signed statement accepting responsibility for maintenance until the maintenance responsibility is legally transferred to another party; or
  - b) written conditions in the sales or lease agreement that require the recipient to assume responsibility for maintenance; or
  - c) written text in project conditions, covenants and restrictions for residential properties assigning maintenance responsibilities to a home owner's association, or other appropriate group, for maintenance of structural and treatment control BMPs; or
  - d) any other legally enforceable agreement that assigns responsibility for storm water BMP maintenance.

**REGIONAL WATER QUALITY CONTROL BOARD CONTACT PERSON:**

Daniel Warner, Senior Water Resource Control Engineer  
Central Valley Regional Water Quality Control Board  
364 Knollcrest Drive, Suite 205, Redding, California 96002  
dwarner@waterboards.ca.gov  
(530) 224-4848


**WATER QUALITY CERTIFICATION:**

I hereby issue an Order certifying that any discharge from the Applicant, Meadowlands Subdivision Project (WDID No. 5A31CR00439) will comply with the applicable provisions of §301 ("Effluent Limitations"), §302 ("Water Quality Related Effluent Limitations"), §303 ("Water Quality Standards and Implementation Plans"), §306 ("National Standards of Performance"), and §307 ("Toxic and Pretreatment Effluent Standards") of the Clean Water Act. This discharge is also regulated under State Water Resources Control Board Water Quality Order No. 2003-0017-DWQ "Statewide General Waste Discharge Requirements For Dredged Or Fill Discharges That Have Received State Water Quality Certification (General WDRs)."

Except insofar as may be modified by any preceding conditions, all Certification actions are contingent on (a) the discharge being limited and all proposed mitigation being completed in compliance with conditions of this Certification, the Applicant's application package, and the attached Project Information Sheet, and (b) compliance with all applicable requirements of the *Water Quality Control Plan for the Sacramento River and San Joaquin River*, Fourth Edition, revised April 2016 (Basin Plan).

Any person aggrieved by this action may petition the State Water Quality Control Board to review the action in accordance with California Water Code § 13320 and California Code of Regulations, Title 23, § 2050 and following. The State Water Quality Control Board must receive the petition by 5:00 p.m., 30 days after the date of this action, except that if the thirtieth day following the date of this action falls on a Saturday, Sunday, or state holiday, the petition must be received by the State Water Quality Control Board by 5:00 p.m. on the next business day. Copies of the law and regulations applicable to filing petitions may be found on the Internet at:

[http://www.waterboards.ca.gov/public\\_notices/petitions/water\\_quality](http://www.waterboards.ca.gov/public_notices/petitions/water_quality) or will be provided upon request.

  
(for) Pamela C. Creedon  
Executive Officer

DLW:reb

Enclosure: Water Quality Order No. 2003-0017-DWQ

cc w/o Ms. Leah Fisher, U.S. Army Corp of Engineers, Sacramento  
enclosures: Department of Fish and Wildlife, Region 2, Rancho Cordova  
U.S. Fish and Wildlife Service, Sacramento  
Mr. Bill Jennings, CALSPA, Stockton  
Dave Claycomb, HELIX Environmental Planning, Inc., Folsom

cc w/o  
Enclosures  
by email: Joe Morgan, U.S. EPA, Region 9, San Francisco  
Mr. Bill Orme, SWRCB, Certification Unit, Sacramento

## PROJECT INFORMATION

**Application Date:** 11 April 2016, Revised – 7 July 2016

**Application Deemed Complete:** 31 August 2016

**Applicant:** William Niemi  
Niemi Development Properties, LLC  
4120 Douglas Bl., #306-534  
Granite Bay, CA 95746

**Project Name:** Meadowland Subdivision Project

**Application Number:** WDID No. 5A31CR00439

**U.S. Army Corps File Number:** SPK-2003-00630

**Type of Project:** Residential Development.

**Project Location:** Sections 10 and 15, Township 12 North, Range 6 East  
Latitude: 38.897° and Longitude: -121.284°

**County:** Placer County

**Receiving Water(s) (hydrologic unit):** Auburn Ravine, tributary to the Sacramento River.  
Valley-American Hydrologic Unit No.519.22 – Pleasant Grove HSA

**Water Body Type:** Streambed

**Designated Beneficial Uses:** The *Water Quality Control Plan for the Sacramento River and San Joaquin River Basins*, Fourth Edition, revised April 2016 (Basin Plan) has designated beneficial uses for surface and ground waters within the region. Beneficial uses that could be impacted by the project include, but are not limited to: Municipal and Domestic Water Supply (MUN); Agricultural Supply (AGR); Industrial Supply (IND); Hydropower Generation (POW); Groundwater Recharge (GWR); Water Contact Recreation (REC-1); Non-Contact Water Recreation (REC-2); Warm Freshwater Habitat (WARM); Cold Freshwater Habitat (COLD); Migration of Aquatic Organisms (MIGR); Spawning, Reproduction, and/or Early Development (SPWN); and Wildlife Habitat (WILD). A comprehensive and specific list of the beneficial uses applicable for the project area can be found at [http://www.waterboards.ca.gov/centralvalley/water\\_issues/basin\\_plans/index.shtml](http://www.waterboards.ca.gov/centralvalley/water_issues/basin_plans/index.shtml).

**Project Description (purpose/goal):** The Meadowlands Subdivision Project is located in the City of Lincoln, northwest of the intersection of Ninth Street and East Avenue. The Meadowlands Subdivision project consists of a mixed density residential development on a 108.9-acre site generally bounded by Gladding Road and the Gladding McBean Clay Plant on the west, 9th Street on the south, East Avenue on the east, and the City of Lincoln corporate boundary on the north.

The Proposed Project would consist of approximately 61.7-acres of residential development providing 190 single-family lots of varying sizes and 5.2 acres of high-density residential

construction (104 units), a 1.4 acre developed park, 4.8 acres of recreational open space, and a 3.1 acre detention basin that would also function as a recreational field.

The remaining 4.2 acres of the site are designated as open space preserve overlain by a conservation easement (the Meadowlands Preserve).

The project will permanently impact 2.76 acre(s)/380 linear feet of waters of the United States.

**Preliminary Water Quality Concerns:** Construction activities including soil disturbance, excavation, cutting/filling, and grading activities could result in increased erosion and sedimentation and may impact surface waters with increased turbidity and settleable matter.

**Proposed Mitigation to Address Concerns:** Niemi Development Partners, LLC will implement Best Management Practices (BMPs) to control sedimentation and erosion. All temporary affected areas will be restored to pre-construction contours and conditions upon completion of construction activities. Niemi Development Partners, LLC will conduct turbidity and settleable matter testing during in-water work, stopping work if Basin Plan criteria are exceeded or are observed.

**Fill/Excavation Area:** Approximately 5,000 cubic yards of clean soil will be placed into 2.76 acres of waters of the United States.

**Dredge Volume:** N/A

**California Integrated Water Quality System Impact Data:** The Project will permanently impact 2.76 acre/380 linear feet of wetland/streambed from fill activities.

**Table 1: Impacts from Fill and/or Excavation Activities**

Fill Type	Permanent			Temporary		
	Acres	Linear Feet	Cubic Yards	Acres	Linear Feet	Cubic Yards
Wetlands						
Vernal Pool	0.31					
Wetland Swale	2.29					
Seasonal Wetland	0.05					
Markham Ravine Complex	0.08					
<b>Wetlands Total</b>	<b>2.73</b>	<b>NA</b>			<b>NA</b>	
Stream Channel						
Stream Total	0.03	380				
<b>Total Impacts</b>	<b>2.76</b>	<b>380</b>				

Notes

NA Not Applicable

**United States Army Corps of Engineers Permit Type:** Individual Permit.

**Department of Fish and Wildlife Lake or Streambed Alteration Agreement:** Niemi Development Partners, LLC did not apply for a Lake or Streambed Alteration Agreement.

**Possible Listed Species:** Federally-threatened Vernal Pool Fairy Shrimp (VPFS; *Branchinecta lynchi*).

**Status of CEQA Compliance:** The City of Lincoln is the Lead Agency responsible for compliance with the California Environmental Quality Act for the Meadowlands Subdivision Project pursuant to § 21000 et seq. of the Public Resources Code. The City of Lincoln certified Environmental Impact Report on 12 June 2012. The City of Lincoln filed a Notice of Determination with the State Clearinghouse on 18 June 2012 (State Clearinghouse Number 2006032003).

**Compensatory Mitigation:** As required by the United States Army Corps of Engineers, Niemi Development Partners, LLC will purchase mitigation credits of 2.57 acres of seasonal wetlands establishment at Toad Hill Ranch Mitigation Bank and 0.35 acres of vernal pool establishment at Toad Hill Ranch Mitigation Bank to mitigate for 2.76 acres of impacts to waters of the United States.

Evidence of this purchase shall be provided to the Central Valley Water Board prior to proceeding with the activity authorized by this Certification.

**Application Fee Provided:** An application fee of \$600.00 was submitted on 11 April 2016 and an additional fee of \$15,049.00 was submitted on 22 August 2016. A total fee of \$15,649.00 has been submitted to the Central Valley Water Board as required by § 3833(b)(3)(A) and § 2200(a)(3) of the California Code of Regulations.