

**Date:**

January 14, 2011

**Applicant:**

Union Pacific Railroad  
Contact: Debra Schafer  
(402) 544-2358

**Applicant's Representative:**

CH2M HILL  
Contact: Christine Roberts  
(916) 798-3137

**Project Name:**

Union Pacific Railroad Bridge 637.44 on the Yuma Subdivision Replacement Project, WDID  
No. 7A333102001

**Receiving Water:**

The receiving water for this project is an unnamed ephemeral drainage that is tributary to the Salton Sea.

**Location:**

City or Area: Salton, County: Riverside, Longitude/Latitude: 33°28'42"N/ 115°53'21W  
Township/Range: T 8 S/ R 10 E/Section 13.

**Project Description:**

Union Pacific Railroad (UPRR) is planning to remove a bridge and install four culverts near the town of Salton in Riverside County, California. Based on review of the 50-year and 100-year flood events, the new culverts have been sized to meet or exceed the capacity of the current structure and will accommodate the existing mainline track and a future second track. UPRR will remove the existing two-span rail top bridge and install four culverts within the unnamed Waters of the U.S. The new culverts will be 36-inches in diameter to accommodate future storm events and uphold the existing mainline and future second mainline tracks. The culverts will be made up of corrugated steel pipes (CSP). Riprap will be placed at the culvert inlets and outlets. A siding adjacent to the track will be retired. Construction will occur between March and December of 2011. Construction duration is approximately 4-6 weeks.

**Action:**

Pending

**Water Board Contact:**

Jay Mirpour, Water Resources Control Engineer  
(760) 776-8981  
jmirpour@waterboards.ca.gov