

STATE WATER RESOURCES CONTROL BOARD

NORTHEAST TULARE COUNTY REGIONAL WATER SUPPLY FEASIBILITY STUDY

**TULARE COUNTY
AUGUST 2025**

PREPARED FOR:

State Water Resources Control Board
Tulare County, CA

PREPARED BY:

PROVOST & PRITCHARD CONSULTING GROUP
455 W. Fir Avenue, Clovis, CALIFORNIA 93611

**PROVOST &
PRITCHARD**

APPENDIX

Appendix A: DFA Summary of Funding Assistance for NE Tulare County Water Systems

Table P-1 Summary of DFA assistance for NE Tulare County water systems

PROGRAMS	TOTAL BUDGET
TA/ Administrator	\$3,017,182
Funding Agreements	\$45,145,077
Interim- Emergency Project Fund	\$7,421,321
Grand Total	\$55,583,580

ABBREVAIATIONS	
AR	Assistance Request
DW	Drinking Water
WW	Wastewater
TAP	Technical Assistance Provider
P&P	Provost & Pritchard
SHE	Self Help Enterprise
TMF	Technical, managerial and Financial
CWSRF	Clean Water State Revolving Funds
DWSRF	Drinking Water State Revolving Funds
EDWG	Expediated Drinking Water Grant
CAA	Cleanup and Abatement Account
Prop 84	Proposition 84
PWSDER	Public Water System Drought Emergency Response
CAS SB 826	California Senate Bill

Table P-2 TA & Administrator Funding

AR# OR PROJECT#	SYSTEM(S) NAME	AR TYPE (WW OR DW)	TAP	TYPE OF ASSISTANCE	START DATE	STATUS (ACTIVE, COMPLETE, ETC)	BUDGET	PROJECT DESCRIPTION/PROGRESS
AR 7142	Cutler PUD	DW	SHE	Feasibility Study	1/26/2024	Active	\$114,008	Work plan developing feasibility to determine feasibility of Cutler PUD consolidating with Orosi PUD. Preliminary Draft Engineering Report sent to Stakeholders for comments
AR 5238	East Orosi CSD	DW	SHE	Full Planning	11/2/2016	Active	\$685,226	Full planning work plan supporting consolidation of East Orosi CSD and Orosi PUD. Resulted in Expedited Drinking Water Grant 5401003-001C.
AR 6013	East Orosi (WW)	WW	SHE	Full Planning	8/23/2019	Transferred	\$112,482	Transferred to SHE's D2118006 Funding Agreement as AR 7029. Final spent to Date amount from 6013 is \$112,482 The goal of this work plan was to submit a CWSRF Construction Application which would aim to eliminate individual septic tanks from the WW system. This work plan completed a draft Engineering Report prior to being transferred.
AR 7029	East Orosi (WW)	WW	SHE	Full Planning	5/1/2023	Active	\$216,243	The goal of this work plan is to submit a CWSRF application which would aim to eliminate individual septic tanks from the WW system; however, the project is currently stalled until a CWSRF applicant is identified, due to EOCSO being without a quorum of directors.

AR# OR PROJECT#	SYSTEM(S) NAME	AR TYPE (WW OR DW)	TAP	TYPE OF ASSISTANCE	START DATE	STATUS (ACTIVE, COMPLETE, ETC)	BUDGET	PROJECT DESCRIPTION/PROGRESS
AR 5008	Seville-Yettem	DW	SHE	Outreach, TMF, Funding Administration	9/9/2016	Transferred	\$116,545	Transferred to SHE's D1917012 Funding Agreement as AR 7147. The final amount from 5008 is \$116,545 . Two-Phase project consolidating Seville with Yettem. Phase 1 involved transferring ownership of the systems from County of Tulare to Yettem-Seville CSD and updating Seville's distribution system. Phase 2 will include an interconnection between Seville and Yettem. Phase 1 was completed in 2020, and Phase 2 currently has an active construction project, 5400550-002C. County of Tulare was the applicant for 5400550-002C, and this work plan had SHE support the County in completing the Construction Application and supporting implementation of the Construction Grant
AR 6797	Seville-Yettem	DW	SHE	TMF (Subvention)	8/22/2022	Complete	\$14,643	Subvention task having SHE support with Drought Reporting. This was completed and continued support of Drought Reporting was included in AR 7147. Final spent to date for 6797 is \$14,642.56

AR# OR PROJECT#	SYSTEM(S) NAME	AR TYPE (WW OR DW)	TAP	TYPE OF ASSISTANCE	START DATE	STATUS (ACTIVE, COMPLETE, ETC)	BUDGET	PROJECT DESCRIPTION/PROGRESS
AR 7147	Seville-Yettem	DW	SHE	Outreach and TMF Support	12/1/2023	Active	\$21,085	Two-Phase project consolidating Seville with Yettem. Phase 1 involved transferring ownership of the systems from County of Tulare to Yettem-Seville CSD and updating Seville's distribution system. Phase 2 will include an interconnection between Seville and Yettem. Phase 1 was completed in 2020, and Phase 2 currently has an active construction project, 5400550-002C. This work plan aims to have SHE support the active construction project by providing outreach to the Yettem-Seville Board and the community of Yettem, as well as providing drought reporting assistance
AR 5311	Seville-Yettem	WW	SHE	Planning Application and Outreach	1/30/2017	Complete	\$91,809	The goal of this work plan was to submit a CWSRF Planning Application aiming to consolidate the Seville and Yettem WW systems. The final spent to date amount is \$91,809 .
AR 5195	Sultana/Monson	DW	SHE	Construction Application Support, TMF, Well Sampling,	7/27/2018	Complete	\$46,676	Work plan assisting with completing DWSRF Construction Application to Consolidate Sultana with Monson. Resulted in Construction Grant 5400824-001C. Work plan included Property Appraisal, ROE Legal Review, Domestic well Sampling, and TMF Capacity building. The final spent to date amount is \$46,676

AR# OR PROJECT#	SYSTEM(S) NAME	AR TYPE (WW OR DW)	TAP	TYPE OF ASSISTANCE	START DATE	STATUS (ACTIVE, COMPLETE, ETC)	BUDGET	PROJECT DESCRIPTION/PROGRESS
AR 6877	Sultana	DW	SHE	Full Planning	2/3/2023	Active (in process of being closed out)	\$312,953	Work Plan was assigned to address Sultana's aging distribution system. A PER was completed, 30% plans and specs were developed, an NOE was developed and filed, and a DWSRF application general package was uploaded to FFAST, but at that point, the project was deemed a Category F Project. Due to this determination, this work plan is being closed out.
D2118203	East Orosi CSD	DW		Administrator (The County)	9/10/2020	Active	\$994,544	An Administrator was assigned to East Orosi CSD to manage the system through consolidation with East Orosi PUD.
AR7197	NE Tulare County	DW	P&P	Feasibility Study		Active	\$290,968	Feasibility Study to explore regional consolidation of local water systems in northeast Tulare County.
						Total	\$3,017,182	

Table P-3 Funding Agreements

PROJECT#	CONTRACT NO.	SYSTEM(S) NAME	TYPE (WW OR DW)	RECIPIENT	TYPE/ SOURCE OF ASSISTANCE	START DATE	STATUS (ACTIVE, COMPLETE, ETC)	BUDGET	PROJECT DESCRIPTION/ PORGRESS
5400550-002C	D21-02058	Seville & Yettem CSD	DW	County of Tulare	DWSRF	8/1/2023	Active	\$11,520,975	Physical consolidation project of Seville Water Company and Yettem CSD. CSD needs to complete their 2021 audited financials prior to DFA disbursing funds under this contract. Test Well P&S should be completed in the next month or two. The County is unsure when they will move forward with Test Well given DFA is unable to disburse funds until the CSD submits their 2021 audited financials.
5400550-001C	D17-02094	Seville Water System	DW	County of Tulare	DWSRF	11/28/2018	Complete	\$4,028,893	Installed a new distribution system and a 211,000-gallon storage tank in Seville.
P84C-5400550-007P	84-11C81	Seville Water Company	DW	Seville Water Company later Tulare County under receivership	Prop 84 - Chemical	11/27/2012	Complete	\$691,000	Planning work for the Seville-Yetterm CSD Consolidation Project Phase 1 and 2
5400550-001P	2013P118	Seville Water Company	DW	County of Tulare	DWSRF	10/11/2013	Complete	\$215,108	To cover a feasibility study for the Surface Water Regional Drinking Water Project
EDWG-5401003-001C	D23-02042	East Orisi CSD	DW	East Orisi CSD (County of Tulare as administrator)	EDWG	6/4/2024	Active	\$13,521,607	consolidation of the East Orisi water system with Orisi PUD project. Pending submission of pre-bid documents but P&S are complete.
P84C-5401003-003P	84-12C99	East Orisi CSD	DW	East Orisi CSD	Prop 84 - Chemical	11/16/2012	Complete	\$337,911	Nitrate exceedance - remediation project. Completed only a PER and test well

PROJECT#	CONTRACT NO.	SYSTEM(S) NAME	TYPE (WW OR DW)	RECIPIENT	TYPE/ SOURCE OF ASSISTANCE	START DATE	STATUS (ACTIVE, COMPLETE, ETC)	BUDGET	PROJECT DESCRIPTION/ PORGRESS
P84C-5410001-001	84-11C54	Culter PUD	DW	Culter PUD	Prop 84 - Chemical	12/2/2011	Active	\$2,605,318	High Nitrate and Source Capacity Construction Project. Pending completion of Phase 3 of 3
5410001-003C	3013C107	Culter PUD	DW	Culter PUD	DWSRF	1/14/2014	Complete	\$1,986,996	Undersized Distribution System Replacement
5400824-001C	D19-02018	Sultana CSD	DW	Sultana CSD	DWSRF	12/3/2019	Active	\$8,590,482	Near completion, with expected completion in summer 2025. The project includes a new well in Sultana and a transmission mainline to connect and consolidate Sultana and Monson.
8506-110	D19-01025	Sultana CSD	WW	Sultana CSD	CWSRF	3/18/2020	Complete	\$83,188	Only a PER was produced for the consolidation of Monson with the Cutler-Orosi Wastewater Treatment Facility, but a consensus on the necessary capacity could not be reached with the Cutler-Orosi group.
	D15-11-904	Monson	DW	County of Tulare	CAA	1/19/2016	Complete	\$1,215,000	The project was co-funded with \$500K from USDA and \$400K from DWR, for a total project cost of \$2,115,000. It includes a new well and distribution system in the community of Monson.
0054002-001L	14-617-550	LEFA Project - North Tulare County Regional Surface Water Treatment Project	DW	County of Tulare	DWSRF	5/4/2015	Complete	\$230,416	Governance Structure

PROJECT#	CONTRACT NO.	SYSTEM(S) NAME	TYPE (WW OR DW)	RECIPIENT	TYPE/ SOURCE OF ASSISTANCE	START DATE	STATUS (ACTIVE, COMPLETE, ETC)	BUDGET	PROJECT DESCRIPTION/ PORGRESS
0054003-001L	D15-02021	Monson	DW	County of Tulare	DWSRF	11/6/2015	Complete	\$23,279	Monson system entity formation, ESA with Sultana CSD
0000541-001P	2013P115	Monson	DW	County of Tulare	DWSRF	10/18/2013	Complete	\$94,905	Produced an engineering report to resolve Monson's drought struck private domestic wells
							Total	\$45,145,077	

Table P-4 Interim Emergency Project Funding benefiting Seville

DATE AWARDED	FUNDING AGENCY	CONTRACT NO.	FUNDING SOURCE	AMOUNT	NOTES
12/23/2011		84-11E22	P84 Emergency	\$40,367	Interim Replacement Drinking Water Program (CAA 358)
8/1/2014		PDE-13015	PWSDE	\$275,000	15,000 gall storage tank, 2 booster pumps, drilling & equipping new well, well destruction. Leaks/breaks
8/21/2015	SWRCB		CAA (AB91 - \$15 Million Allocation)	\$100,000	CAA-emergency bottled water due to depressurization and intermittent water outages
11/4/2016	SWRCB		CAA (2016 \$4 Million Set-Aside)	\$50,000	CAA-emergency bottled water due to depressurization and intermittent water outages. Oral agreement
4/4/2017	SWRCB		CAS SB 826	\$252,000	CAA-emergency bottled water due to depressurization and intermittent water outages Ends March 31, 2019
1/22/2019	SWRCB		CAA Urgent Drinking Water Needs	\$110,000	CAA-emergency bottled Water due to depressurization and intermittent water outages April 1-2019, May 31, 2020
			Total	\$827,367	

Table P-5 Interim Emergency Project Funding benefiting East Orosi

DATE AWARDED	FUNDING AGENCY	CONTRACT NO.	FUNDING SOURCE	AMOUNT (\$)	NOTES
8/28/2013	SWRCB	84-13WE50	P84- Emergency	\$35,071	Bottled Water
2014	SWRCB		Cleanup Abatement Account	\$199,167	Bottled water
2018	SWRCB		Cleanup Abatement Account	\$131,304	Bottled Water
2019	SWRCB		Cleanup Abatement Account	\$398,782	WASTEWATER. replacement of two sewer lift pumps, plus installation cost of a temporary rental pump.
2023	SWRCB	D2217001	O&M	\$199,631	Operation and Maintenance Funding Assistance. In Progress.
			Total	\$963,955	

Table P-6 Interim Emergency Project Funding benefiting Monson

DATE AWARDED	FUNDING AGENCY	CONTRACT NO.	FUNDING SOURCE	AMOUNT	NOTES
2014-2019	SWRCB	Multiple	Cleanup Abatement Account	\$5,630,000	Monson was on individual wells prior to 12/2017 residents were served by Tulare County's County Wide Bottled Water Program

Appendix B: CPUD Permit and 2022 Sanitary Survey

State Water Resources Control Board

Division of Drinking Water

August 24, 2022

Dionicio Rodriguez, Superintendent
Cutler Public Utility District – 5410001
40526 Orosi Drive
Cutler, CA 93615

DOMESTIC WATER SUPPLY PERMIT AMENDMENT NO. 03-24-22PA-019

Dear Mr. Rodriguez:

Please find the Domestic Water Supply Permit Amendment No. 03-24-22PA-019 for the Cutler Public Utility District water system (hereinafter “Water System”). The enclosed permit contains an all-inclusive list of applicable permit provisions.

After evaluation of the Water System and completion of the enclosed Sanitary Survey Report, the State Water Resources Control Board, Division of Drinking Water (Division) finds that in addition to the provisions of the enclosed Domestic Water Supply Permit, the items below are required to be addressed by the Water System.

The following items were required in the 2018 and 2019 Sanitary Survey Report issued by the Division and are still outstanding:

1. By **April 30, 2018**, the Water System must submit a Chlorine Operations Plan to the Division.
2. By **October 31, 2019**, the Water System must submit a Cross Connection Control Program to the Division for review and approval.

The following items were identified in the 2022 Sanitary Survey and require attention:

3. By **September 16, 2022**, the Water System must submit and updated ENP to the Division.
4. By **December 31, 2022**, the Water System must submit an ERP to the Division for review and approval.

Mr. Dionicio Rodriguez
Cutler Public Utility District

- 2 -

August 24, 2022

If you have any questions regarding this letter or the permit, please contact the Tulare District office at (559) 447-3300 or by email at DWPDIST24@waterboards.ca.gov.

Sincerely,

Kristin Willet

Digitally signed by Kristin
Willet
Date: 2022.08.24 13:16:57
-07'00'

Water Boards

Kristin Willet, P.E.
Senior Water Resource Control Engineer, Tulare District
Division of Drinking Water
Southern California Field Operations Branch

cc: Tulare County Environmental Health Department

STATE OF CALIFORNIA

***AMENDMENT TO THE DOMESTIC WATER
SUPPLY PERMIT***

Issued To

Cutler Public Utility District

For the Operation of the

***Cutler Public Utility District Water System
Water System No. 5410001***



By the

State Water Resources Control Board, Division of Drinking Water

PERMIT NUMBER: 03-24-22PA-019

DATE: August 24, 2022

WHEREAS:

1. The public water system known as the *Cutler Public Utility District* water system is located east of the City of Dinuba, whose mailing address is: 40526 Orosi Drive Cutler, CA 93615. The Cutler Public Utility District is the legal owner of the water system. Therefore, the Cutler Public Utility District is responsible for compliance with all statutory and regulatory drinking water requirements and the conditions set forth in this revised permit.
2. This revised permit is being issued to *Cutler Public Utility District* for the purpose of providing an updated permit reflecting the current operations of the *Cutler Public Utility District* water system under the regulations of the State of California Health and Safety Code.
3. The public water system for which the revised permit was written is described briefly below (a more detailed description of the permitted system is described in the attached report):

The Cutler Public Utility District water system's source of supply is groundwater. The Water System is classified as a community water system and serves a population of approximately 6,200 people through 1,218 service connections. The Water System serves one pressure zone and consists of two active groundwater sources: Well 05 and Well 09. The source water receives continuous chlorination treatment.

And WHEREAS:

1. The Division of Drinking Water has evaluated all of the information submitted by *Cutler Public Utility District* and has conducted a physical investigation of the *Cutler Public Utility District* water system.
2. The Division of Drinking Water has the authority to issue domestic water supply permits pursuant to Health and Safety Code Section 116540.

THEREFORE: The Division of Drinking Water has determined the following:

1. The *Cutler Public Utility District* water system meets the criteria for and is hereby classified as a community water system.
2. Provided the following conditions are complied with, the *Cutler Public Utility District* water system should be capable of providing water to consumers that is pure, wholesome, and potable and in compliance with statutory and regulatory drinking water requirements at all times.

THE CUTLER PUBLIC UTILITY DISTRICT IS HEREBY ISSUED THIS REVISED DOMESTIC WATER SUPPLY PERMIT TO OPERATE THE CUTLER PUBLIC UTILITY DISTRICT WATER SYSTEM.

The Cutler Public Utility District water system shall comply with the following permit conditions:

1. The Cutler Public Utility District shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted thereunder.
2. The only approved sources of domestic water supply for use by the Cutler Public Utility District are as follows:

Source Name	Status	Primary Station Code (PS Code)
Well 05 – Raw	Active	CA5410001_003_003
Well 09 – Raw	Active	CA5410001_008_008

3. The only approved treatment for the Cutler Public Utility District is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution.

Source Name	Status	PS Code
-------------	--------	---------

Well 05 – CL2	Active	CA5410001_005_005
Well 09 – CL2	Active	CA5410001_009_009

4. No other sources or treatment (as described in Provisions No. 2 and 3 above) shall be used by the Cutler Public Utility District water system and no changes, additions, or modifications shall be made without prior receipt of an amended domestic water supply permit from the Division.
5. All personnel who operate the distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Cutler Public Utility District water system is classified as a D3 system. The Cutler Public Utility District must have a chief distribution operator who is certified, at a minimum, as a D2 distribution system operator and a shift operator who is certified as a D1 operator or higher. The only treatment provided by the Cutler Public Utility District is continuous chlorination, therefore no treatment operator is required.
6. The Cutler Public Utility District shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The Cutler Public Utility District shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.
7. The Cutler Public Utility District shall submit an Electronic Annual Report each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
8. The Cutler Public Utility District shall record production data from the active sources at least monthly.
9. The Cutler Public Utility District shall collect raw water samples at least monthly from all active wells for analyses of total coliform and fecal coliform or *E. coli* bacteria. The coliform test shall be performed using a density analytical method with results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following month.
10. The Cutler Public Utility District shall monitor for coliform bacteria in the distribution system monthly and in accordance with an approved Bacteriological Sample Siting Plan. The Division shall be notified immediately if either of the following occur
 - a. Any distribution system or source sample shows the presence of *E. coli* bacteria.
 - b. The water system exceeds the maximum contaminant level for total coliform bacteria, in which more than one bacteriological sample shows the presence of coliform bacteria during a single month.

11. The Cutler Public Utility District shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The Cutler Public Utility District shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.
12. The Cutler Public Utility District shall conduct Stage 2 Disinfection Byproduct (DBP) monitoring annually. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Codes:

ST2 DBP Monitoring Sites	PS Codes
ST2S1-12307 Avenue 408	CA5410001_DST_900

13. The Cutler Public Utility District shall operate the water system in accordance with a Division-approved Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval.
14. The Cutler Public Utility District water system shall monitor the chlorine residual in the distribution system weekly and report the residuals to the Division monthly using the Chlorine Operational Log form. The Cutler Public Utility District water system shall submit a monthly treatment report to the Division by the 10th day of the following month.

This permit supersedes all previous domestic water supply permits issued for this public water system and shall remain in effect unless and until it is amended, revised, reissued, or declared to be null and void by the Division of Drinking Water. This revised permit is non-transferable. Should the Cutler Public Utility District water system undergo a change of ownership, the new owner must apply for and receive a new domestic water supply permit.

Any change in the source of water for the water system, any addition or modification of the method of treatment as described in the sanitary survey report, or any addition of distribution system storage reservoirs shall not be made unless an application for such change is submitted to the Division of Drinking Water.

This revised permit shall be effective as of the date shown below.

FOR THE DIVISION OF DRINKING WATER

Kristin Willet  Digitally signed by Kristin Willet
Date: 2022.08.24 13:19:25 -07'00'

Kristin Willet, P.E.
Tulare District Engineer

Date

State Water Resources Control Board

DATE: August 24, 2022

FROM: Kristin Willet, P.E.
District Engineer, Tulare District

SUBJECT: Cutler Public Utility District
Sanitary Survey – 5410001

I. INTRODUCTION

1.1 PURPOSE OF REPORT

On May 19, 2022, the State Water Resource Control Board, Division of Drinking Water (Division), inspected the Cutler Public Utility District (Water System) drinking water supply system. Mr. Dionicio Rodriguez, with the Cutler Public Utility Water District assisted Ms. Willet with the sanitary survey. The purpose of this report is to document the sanitary survey of the Water System and to describe the existing water supply facilities and current operational practices. The last routine sanitary survey was conducted by the Division on August 1, 2019.

Domestic Water Supply Permit

The Water System was issued a Domestic Water Supply Permit No. 03-12-09PA-006 by the California Department of Public Health (CDPH) - Visalia District in June 2009. The Water System is still subject to the following permit provisions; included in Permit No.: 03-12-09PA-006:

1. The Cutler Public Utility District shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted thereunder.
2. The only approved sources of domestic water supply for use by the Cutler Public Utility District are listed in the table below.

Approved Sources

Source Name	Status	Primary Station Number
Well No. 5	Active	CA5410001_003_003
Well No. 6	Active	CA5410001_004_004
Well No. 9	Active	CA5410001_008_008

3. The only approved treatment facilities for the Cutler Public Utility District is disinfection provided at each well head using NSF approved 12.5% sodium hypochlorite solution.
4. No additions, changes or modifications to the sources of water supply or water treatment processes outlined in Provisions Nos. 2 and 3 can be made without prior receipt of an amended domestic water supply permit from this Department.
5. Under the operator certification regulation, the Cutler Public Utility District's water system is classified as a D2 system. The District must have a chief distribution operator who is certified, at a minimum, as a D2 distribution system operator.
6. The Cutler Public Utility District shall conduct monthly source bacteriological monitoring. If a positive total coliform bacteria sample is detected, the sample shall also be analyzed for fecal coliform or E. coliform bacteria. The results of the positive coliform bacteria tests shall be reported as a density (MPN/100 ml), and not solely for the presence of coliform bacteria.
7. The Cutler Public Utility District shall collect remaining initial water quality monitoring requirements for Well No. 9. All results shall be submitted to the Department via EDT.
 - Second quarter VOC and SOC monitoring, to be collected by July 30, 2009.
 - Second quarter of radiological monitoring, to be collected by July 30, 2009. Radiological monitoring shall continue, if required, in the fourth quarter of 2009 and the first quarter of 2010.
 - Second quarter of MTBE monitoring, to be collected by July 30, 2009, and continue in the fourth quarter of 2009 and the first quarter of 2010.
8. The Cutler PUD should implement a water conservation program to reduce water use in the District.
9. The Cutler PUD should monitor water levels of the three active wells monthly (May through September) and quarterly during the rest of the year.

The provisions included in the active permit are not all-inclusive and some do not reflect the current operations of the Water System, including the inactivation of Well 06. As a result, a permit amendment is required. The permit amendment, which accompanies this inspection report, reflects the changes in provisions and describes the current operations of the Water System.

1.2 DESCRIPTION OF SYSTEM

The Water System is classified as a community water system (CWS) which serves an approximate population of 6,200 people through 1,218 service connections. The Water System consists of two active groundwater wells, one elevated 48,000-gallon storage tank, and the associated distribution system composed of different piping sizes and materials. Continuous chlorination treatment is provided at each well site. The Water System's distribution system is operated as one pressure zone. The service area maintains distribution pressure between 25 and 42 pounds per square inch (psi) and is composed of 1,096 unmetered connections and 122 metered connections. The Water System is sewered and maintains a wastewater treatment facility for waste disposal. Appendix A contains photographs of the Water System's well sites and storage tank.

1.3 ENFORCEMENT HISTORY

Enforcement Action:	Compliance Order No. 03-12-06O-002
Issue Date:	February 2007
Description:	The Water System exceeds the maximum contaminant level (MCL) for dibromochloropropane (DBCP) at Well 06.
Status:	Well 06 is inactive due to inadequate water quality.
Enforcement Action:	Compliance Order No. 03-12-12O-006
Issue Date:	September 2012
Description:	The Water System exceeds the MCL for nitrate at Well 06.
Status:	Well 06 is inactive due to inadequate water quality.
Enforcement Action:	Citation No. 03-24-19C-116
Issue Date:	October 2019
Description:	The Water System exceeds the MCL for total coliform in September 2019.
Status:	The Water System returned to compliance in October 2019.
Enforcement Action:	Compliance Order No. 03-24-22R-007
Issue Date:	August 2022
Description:	The Water System exceeds the MCL for 1,2,3-trichloropropane.
Status:	The Water System has issued a Tier 2 1,2,3-trichloropropane notice to customers.

1.4 AREA SERVED

The Water System is in Tulare County and is located east of the City of Dinuba. The service area consists of single and multiple family residences, commercial businesses, retail and agricultural related establishments. The Water System serves an approximate population of 6,200 people through 1,218 service connections. The Water System is operated by Mr. Dionicio (Junior) Rodriguez. The mailing address for the Water System is 40526 Orosi Drive, Cutler CA 93615. The water system is owned and operated by the Cutler PUD. A locational map is included in Appendix A.

1.5 PRODUCTION DATA

Table 1 summarizes the water production information obtained from the Electronic Annual Reports (EARs) from 2011 through 2021.

Table 1 – Production Data

Year	Population	Service Connections	Annual Production (MG)	Max. Month (MG)
2021	6,200	1,218	249	32 (Jul.)
2020	6,200	1,218	253	33 (Jul.)
2019	6,200	1,218	242	32 (Jul.)
2018	6,200	1,218	249	33 (Jul.)
2017	6,200	1,039	246	32 (Jul.)
2016	6,200	1,218	237	30 (Jul.)
2015	6,200	1,218	236	27 (Aug.)
2014	6,200	1,218	273	34 (Jul.)
2013	6,200	1,218	318	41 (Jul.)
2012	6,200	1,218	301	42 (Aug.)
2011	6,200	1,218	292	39 (Jul.)

II. INVESTIGATION AND FINDINGS

2.1 SOURCES OF SUPPLY

The domestic water supply is obtained from two active groundwater sources that are identified as Wells 05 and 09. A description for each source is provided below. Photographs of the well sites are included in Appendix A.

Source Water Assessment

A Possible Contaminating Activity (PCA) checklist and Source Water Assessment Program (SWAP) was completed for Wells 05 and 09 in February 2003 and June 2013 by Tulare County and the Water System. The SWAP indicates the sources are most vulnerable to the following contaminating activities: fertilizer/pesticide/herbicide application and automobile/gas stations.

Active Wells:

Well 05 – RAW, Active – Treated, (CA5410001_003_003)

DWR Well	YES
Completion Report:	
Date of Well	January 1962
Completion:	
Well Depth:	500 feet
Sanitary Seal Depth:	50 feet
Well Casing:	14-inch steel casing to 504 feet; perforations between 180 to 491 feet in regular intervals
Flow Meter:	YES
Pump Type:	Deep well turbine, water-lubricated
Pump Make and Model:	U.S. Motors
Pump Size:	75-hp
Well Capacity:	950 gpm
Source Discharge:	Directly to sand separator then distribution system.
Source Operation:	Radio signal from storage tank.

Well 09 – RAW, Active – Treated, (CA5410001_008_008)

DWR Well	YES
Completion Report:	
Date of Well	July 2007
Completion:	
Well Depth:	515 feet
Sanitary Seal Depth:	270 feet
Well Casing:	14-inch steel casing to 420 feet; perforations between 320 to 420 feet
Flow Meter:	YES
Pump Type:	Deep well turbine, water-lubricated

Pump Make and Model:	U.S. Motors
Pump Size:	40-hp
Well Capacity:	450 gpm
Source Discharge:	Directly to distribution system.
Source Operation:	Radio signal from storage tank.

Inactive Wells:

The Water System has one inactive well; Well 06. Historically, this well produces water that exceeds the MCL for nitrate and DBCP. A DWR Well Driller's Completion Report for Well 06 is on file with the Division. According to the completion report, Well 06 was drilled in 1979 to a depth of 540 feet. The borehole contains a 14-inch steel casing extending to 516 feet. Perforations are located between 315 and 325; 340 and 365; 380 and 395; 408 and 444; and 495 and 510 feet. There is a cement annular seal provided to 72 feet. The well is equipped with a water-lubed 75-hp DWT pump, which is estimated to produce approximately 1,100 gpm. A totalizing flow meter is present and production data is recorded monthly.

The well is secured in a fenced area. The discharge line features a check valve, air relief vent, and a non-threaded raw water sampling tap. The water pumps directly to the distribution system but has isolation valves preventing any flow to the distribution system. The Water System is currently in the process of obtaining funding for a 400,000-gallon blending tank and equipping an existing well to mix with Well 06 water in order to provide more supply for the system in the future. **The Water System must notify the Division in the event of an emergency where Well 06 needs to be used in the distribution system. Additionally, the Water System will need to provide a Tier 1 Public Notice for the chemical exceedances, if Well 06 is used in the distribution system.**

2.2 ADEQUACY OF SUPPLY

Using the data from Table 1, a peaking factor of 1.5 was used to estimate the values found in Table 2. Table 3 displays the estimated total source capacity of the Water System's active sources. It should be noted that the capacities listed in Table 3 are estimates provided by the Water System.

Table 2 - Average Day, Maximum Day & Peak Hour Demand

Year	Average Day (gpm)	Maximum Day (gpm)	Peak Hour (gpm)
2021	474	1,075	1,613
2020	481	1,109	1,663

2019	460	1,075	1,613
2018	473	1,100	1,650
2017	467	1,068	1,602
2016	451	1,008	1,512
2015	449	907	1,361
2014	519	1,142	1,714
2013	605	1,378	2,067
2012	573	1,411	2,117
2011	556	1,310	1,966

Table 3 - Total Active Source Capacity

Source	Capacity (gpm)
Well 05	950
Well 09	450
Total Capacity	1,400

The Water System utilizes Wells 05 and 09 to meet system demand. The estimated capacity of the sources are 950 and 450 gallons per minute (gpm), respectively. The Water System has 48,000 gallons of storage capacity. According to the California Waterworks Standards, the highest water usage during the last ten years is used to estimate the average day demand (ADD), maximum day demand (MDD), and peak hour demand (PHD) for the system. These standards also require a system with greater than 1,000 service connections to have capacity to be able to meet four hours of PHD with source capacity, storage capacity, and/or emergency source connections. Additionally, a community water system using only groundwater shall be capable of meeting MDD with the highest- capacity source offline. The highest water usage during the last ten years for the ADD, MDD, PHD was 605 gpm, 1,378 gpm, and 2,067 gpm, respectively. As such, the Water System is incapable of meeting these requirements with their current combined source capacity and storage capacity at this time.

The Water System is currently in the process of obtaining funding for a 400,000-gallon blending tank and equipping an existing well, Well 10, to mix with Well 06 water in order to provide more supply for the system in the future. Given that the water quality at Well 10 is unknown at this time, it is unclear if the project to equip Well 10 and incorporating the blending tank will provide the Water System with the capacity required by the California Waterworks Standards. The Division highly recommends the addition of extra storage capacity and/or an additional well, or an

emergency connection with an adjacent water system such as Orosi Public Utility District.

2.4 TREATMENT FACILITIES

Continuous Chlorination

The Water System provides continuous chlorination of the water produced by Wells No. 05 and 09. The chlorination equipment is located at each well site and each consists of: NSF-approved clear 15-gallon polyethylene solution tank, LMI chemical metering pumps (Well 05: max output 0.65-gph @ 110 psi; Well 09: max output 1-gph @ 110 psi), and NSF approved 12.5% Sanichlor chlorine solution. The chlorination equipment is enclosed inside a covered, fenced structure.

The chlorine solution is injected into the discharge lines of Well 05 and 09 prior to entering the distribution system. The chlorine residual must be recorded weekly during routine visits. The operator aims to have a chlorine residual of 0.2-0.4 mg/L in the distribution system. The Chlorine Operational Log should be submitted to the Division by the 10th day of the following month.

Chlorination Operations Plans

The Water System does not have an approved Chlorination Operations Plan on file with the Division. A Chlorine Operations Plan template is provided in Appendix F.

The Water System was directed in the 2018 Sanitary Survey to submit a chlorine operations log. The Water System has not addressed this directive and must do so immediately.

2.5 STORAGE

Storage for the Water System is provided by one elevated steel storage tank, which is approximately 48,000 gallons. The tank is a common inlet/outlet configuration and receives chlorinated water from the distribution system. Water from the two well sites flows through the distribution system to the storage tank. The dimensions of the tank are unknown. When the water level in the storage tank is approximately at half of its maximum capacity, a radio signal is sent to the well sites to start the pumps.

According to Mr. Rodriguez, the last cleaning of the storage tank was in 2021. The Division recommends cleaning and inspecting the storage tank every five years.

2.6 OPERATIONS AND MAINTENANCE

The responsible entity of the water system is Cutler Public Utility District. Cutler Public Utility District is operated and maintained by Dionicio (Junior) Rodriguez. Mr. Rodriguez is the chief operator of the Water System and is a certified D3 operator

(Certification Number: 21736). The operator is responsible for the maintenance and operation of the water system. The Water System's distribution system is classified as a D2 distribution facility.

Per Title 22, Section 63770, California Code of Regulations water systems shall utilize only certified distribution operators to make decisions addressing the following operational activities:

1. Install, tap, re-line, disinfect, test and connect water mains and appurtenances.
2. Shutdown, repair, disinfect and test broken water mains.
3. Oversee the flushing, cleaning, and pigging of existing water mains.
4. Pull, reset, rehabilitate, disinfect and test domestic water wells.
5. Stand-by emergency response duties for after-hours distribution system operational emergencies.
6. Drain, clean, disinfect, and maintain distribution reservoirs.

The Water System shall utilize either certified distribution operators or treatment operators that have been trained to make decisions addressing the following operational activities:

1. Operate pumps and related flow and pressure control and storage facilities manually or by using a system control and data acquisition (SCADA) system.
2. Maintain and/or adjust system flow and pressure requirements, control flows to meet consumer demands including fire flow demands and minimum pressure requirements.

The Water System shall utilize either certified distribution operators or treatment operators to make decisions addressing the following operational activities:

1. Determine and control proper chemical dosage rates for wellhead disinfection and distribution residual maintenance.
2. Investigate water quality problems in the distribution system.

Cross Connection Control Program

The Water System is required to maintain a Cross Connection Control Program which shall include the following elements (as applied from Title 17, California Code of Regulations, Section 7584):

1. The conducting of surveys to identify water user premises or locations where cross connections are likely to occur,
2. The provisions of backflow protection by the water user at the user's connection or within the user's premises or both,
3. The provision of at least one person trained in cross connection control to carry out the cross-connection program,
4. The establishment of a procedure or system for annual testing of backflow preventers, and
5. The maintenance of records of locations, tests, and repairs of backflow preventers.

Backflow Prevention Device Testing

Regulation requires all backflow prevention devices to be tested annually. Copies of the testing records must be kept on file with the City for a minimum of three years.

A cross-connection control survey was completed on May 22, 2018. Based on the 2021 EAR, the City has 20 backflow prevention devices in the system. Regulation requires all backflow prevention devices to be tested annually. All backflow assemblies were tested during the 2021 calendar year. Copies of the testing records must be kept on file with the Water System for a minimum of three years. The Water System is required to maintain a Cross Connection Control Program which shall include the following elements (as applied from Title 17, California Code of Regulations, Section 7584):

The Division recommends that a Cross-Connection Control survey be conducted every five years or upon the addition of new service connections or facility changes. The cross-connection control program should contain details on the frequency of surveys, when new surveys will be performed, and the name of the certified cross connection control specialist used.

The Water System indicated that all new service connections are surveyed for backflow and cross-connection hazards and all existing service connections undergo backflow testing each year. **The Water System was directed in the 2019 Sanitary**

Survey to provide a copy of the Cross-Connection Control Program. This directive has not been addressed and the Water System must do so immediately. Instructions are provided in Appendix G.

Complaint Program

The Water System must keep records of all complaints received and actions taken to correct the problems related to the complaints. Records of any complaints must be kept on file by the Water System for a minimum of three years and should be reported to the Division via the Electronic Annual Report (EAR). There were four complaints reported in the 2021 EAR related to taste and odor. All complaints were investigated by the Water System and resolved by explaining to the customers the taste and odor were attributed to chlorine in the system.

Emergency Response Plan (ERP)

On October 23, 2018, America's Water Infrastructure Act (AWIA) was signed into law. AWIA Section 2013 requires community (drinking) water systems serving more than 3,300 people to develop or update risk assessments and emergency response plans (ERPs). By June 30, 2021, the City must certify the completion of its risk and resilience assessment on the U.S. EPA site:

<https://www.epa.gov/waterresilience/how-certify-your-risk-and-resilience-assessment-or-emergency-response-plan>. Additionally, an ERP for the City must be certified by December 31, 2021. Information for completing a risk assessment and ERP is available on the Water Boards' Water Resiliency – Prepare website: https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/water_resiliency/prepare.html

By December 31, 2022, the Water System must submit an ERP to the Division for review and approval. Appendix H provides a guidance document and template that may be used for updating the Water System's ERP.

Consumer Confidence Report (CCR)

The Consumer Confidence Report (CCR) is required to be delivered to all customers within the Water System by July 1st of the following year, and a copy of the CCR and certification of publication is due to the Division by October 1st of each year. The Water System submitted the 2021 CCR and CCR certification on 24, 2022. The Water System must ensure that the CCR and certification of publication are submitted on a timely basis.

Emergency Notification Plan (ENP)

The Water System's Emergency Notification Plan (ENP), submitted in May 2019, lists Mr. Dionicio Rodriguez, Mr. Santiago Venegas, and Mr. Dennis Keller as the primary, secondary, and tertiary contacts, respectively, in the event of a water quality emergency. The Water System has specified the use of local media, posted notification, and handout distribution as the primary modes of notification in the event of a water quality emergency. This would be followed by direct notification via public notices that would be distributed by City personnel.

The Tulare District contacts have changed and required an update to the ENP template. **By September 16, 2022, the Water System must submit an updated ENP to the Division.** The updated ENP template is provided in Appendix I.
Water System Resiliency and Preparedness

The effects of climate change on community water system (CWS) facilities and operations is a concern and priority of the State Water Resources Control Board (SWRCB), which is documented by the SWRCB in its Comprehensive Climate Change Resolution No. 2017-12, adopted in March 2017. DDW is reviewing each water system's preparedness for climate change with the goal to increase awareness and familiarization to the effects of climate change to facilities and operations, encourage the use of EPA's Climate Resilience Evaluation and Awareness Tool (CREAT) or equivalent, and to document and the CWS' efforts in climate change.

As part of the 2021 EAR, CWSs were asked to identify their vulnerabilities, and rank them as either high, medium or low sensitivity, and proposed or implemented projects to prepare for the impacts from climate change. The Cutler PUD Water System *did* provide responses to these questions. The Water System identified the following potential climate change impacts that their facilities are highly vulnerable to: *drought, water quality degradation, and groundwater degradation*. The Water System has implemented, or is considering implementing, the following projects to address current identified needs and which also reduce the impacts to these vulnerabilities: *installing new and deeper drinking water wells or modify existing wells to increase pumping capacity; develop local supplemental water supply, enhanced treatment, or increased storage capacity; relocate facilities, construct or install redundant facilities; conservation measures; alternative or backup energy supply*.

The Water System indicated that they were not aware of the CREAT tool developed by USEPA for identifying climate change vulnerabilities. The Water System has not used CREAT (or similar tool) to identify vulnerabilities to the water system sources and facilities. The SWRCB strongly encourages utilities to evaluate climate change vulnerabilities using tools such as CREAT and engaging in a conversation both

within your water system organization and with customers on how to plan and prepare for being resilient to provide clean and safe water reliably and adequately under all current and future conditions.

Fire ---

A defensible space of 100 feet (*California Public Resources Code, 4291*) **is** maintained around all sources and structures managed by the Water System. Well 05 is immediately adjacent to a convenience store and does not have 100 feet of defensible space. The storage tank and Well 09 both have a defensible space of 100 feet.

Flooding ---

Are any of the drinking water facilities vulnerable to flooding? **No**
The sources are not within a flood zone. The storage tank is elevated.

Backup Power ---

Is backup power available, for example, through portable or permanent power generators? **Yes**
If liquid fuel is used, is it properly contained and stored away from the source? **Yes**

Drought ---

Is the Water System prepared for drought related shortages or outages? (interties, backup supply, increased storage) **No**
If using a groundwater source: Is the Water System monitoring depth to groundwater on a routine basis? **Yes**
The Water System monitors groundwater depth on annual basis. Additionally, the Water System is in the process of obtaining funding to equip an existing well, Well 10, and incorporate a blending tank into the system.

Degrading Source Water Quality –

Has source water quality degraded over time, or specifically during the most recent drought? **No**

The Water System is composed of different types and sizes of distribution piping. The system is primarily composed of C900, ductile iron, galvanized steel, and some asbestos-cement piping. System pressure is maintained between 25 and 42 psi.

2.7 SOURCE WATER QUALITY MONITORING

A summary of the recent source water quality monitoring results and next due dates are included in Appendix B. Additionally, the current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>. Instructions for accessing this information is included in Appendix D.

Bacteriological – Raw Water

The Water System is required to conduct monthly source water bacteriological sampling from all sources with continuous chlorination at a tap located prior to the chlorine injection port. These samples must be analyzed for coliform bacteria density and the results reported as Most Probable Number per 100 mL (MPN/100 mL). The results of these analyses must be reported to the Division monthly using the Monthly Source Bacteriological Monitoring Report. A summary of the source bacteriological results for the last three years is included in Appendix C.

California Ground Water Rule Monitoring

The California Ground Water Rule (GWR) requires public water systems to conduct triggered source monitoring whenever a routine distribution system sample is positive for total coliform bacteria.

General Mineral, General Physical and Inorganic Chemicals

The Water System is required to monitor its active groundwater sources for general mineral (GM), general physical (GP) and inorganic (IO) chemical water quality every three years, except for nitrate which has a different monitoring frequency. The Water System last sampled Wells 05 and 09 for GM, GP, and IO chemicals in July 2022, except for perchlorate which was last sampled for in August 2020 from Well 05 and August 2021 from Well 09. All results were below the respective MCLs. **The next round of GM, GP, and IO chemical water quality monitoring due dates for Wells 05 and 09 are provided in Appendix B.**

Nitrate

The Water System is required to monitor for nitrate (as N) from Well 05 on a monthly basis, and Well 09 quarterly basis. These sources have historically produced water with a nitrate (as N) concentration of greater than or approximately one-half of the MCL for nitrate (as N). The most recent nitrate (as N) results are provided in the table below.

Table 4 – Nitrate Monitoring Results

Source	Last Sample Date	Result (mg/L)	Next Sample Due
Well 05	7/29/2022	9.4	08/2022
Well 09	7/29/2022	4.7	10/2022

Volatile Organic Chemicals (VOC)

The Water System is required to sample Wells 05 and 09 for VOCs once every three years after initial monitoring is complete. The Water System completed the initial VOC analysis for Wells 05 and 09. The Water System last monitored Well 05 for VOCs in July 2022 with non-detect results. The VOC sampling from Well 09 was conducted on July 2021 with all results non-detect. **Well 05 is due to be monitored for VOCs again by July 2025 and Well 09 must be monitored for VOCs again by July 2024.**

Synthetic Organic Chemicals (SOC)

The Water System is required to sample Wells 05 and 09 for select SOC's (alachlor, atrazine, dibromochloropropane (DBCP), ethylene dibromide (EDB), and simazine) for two consecutive quarters every three years after initial monitoring is complete. The Water System last monitored Well 05 for alachlor, atrazine, and simazine in October 2021 with non-detect results. Well 05 was monitored for 1,2,3 – trichloropropane (1,2,3-TCP), DBCP and EDB in July 2021. The only detection was of 1,2,3-TCP at 0.007 ug/L. The Water System last monitored Well 09 for alachlor, atrazine, and simazine in August 2021 and 1,2,3 – trichloropropane (1,2,3-TCP), DBCP and EDB in July 2022, all with non-detect results.

The Water System has been monitoring Well 05 for 1,2,3-TCP on a monthly basis since October 2021 as shown in Table 5 below. As of July 2022, the running annual average (RAA) for 1,2,3-TCP from Well 05 has reached 0.00585 ug/L, exceeding the MCL for 1,2,3-TCP of 0.005 ug/L. The Water System has been issued Compliance Order No. 03-24-22R-007 on August 26, 2022, with a return to compliance date of August 2025.

Table 5: Well 05 1,2,3- TCP Running Annual Average

Well 05	Sample Date	1,2,3-TCP Result (ug/L)
1Q2022	1/14/2022	0.006
	2/9/2022	0.005
	3/9/2022	0.006
2Q2022	4/8/2022	0.006
	5/18/2022	0.005
	6/22/2022	0.006
3Q2022	7/29/2022	0.007
RAA		0.00585

Radiological

Radiological monitoring is based on the collection of four initial consecutive quarterly samples for gross alpha and radium 228. If at any time the gross alpha exceeds 5 pCi/L, analysis for uranium must be performed in that same sample. The Water System has completed initial monitoring requirements for Well 05 and Well 09. The Water System monitored Well 05 for gross alpha in August 2015, with non-detect results. The Water System monitored Well 09 for gross alpha in November 2020 with a result of 5.2 pCi/L. Subsequent radiological monitoring frequency is based on the results of the last sample analyzed. Wells 05 is currently on a nine-year monitoring frequency and Well 09 is now on a six-year monitoring frequency. The Water System must monitor Well 05 for gross alpha by August 2024. The Water System must monitor Well 09 for gross alpha again in November 2026.

3.2 DISTRIBUTION SYSTEM MONITORING

Bacteriological Water Quality

The Water System is required to collect at least seven routine bacteriological samples per month from the distribution system. The Water System submitted a Bacteriological Sample Siting Plan (BSSP) to the Division in July 2013 which indicates the locations where bacteriological routine and repeat samples will be collected.

The Water System must follow their BSSP unless alternative instructions are given by the Division. Any time a routine coliform positive sample occurs, the Water System must collect repeat samples from the locations listed in the BSSP within 24-hours. The analysis must report the results in most probable number (MPN). A summary of the distribution bacteriological sample results is included in Appendix D.

Lead and Copper Monitoring

The Water System has completed initial lead and copper distribution sampling tap monitoring and must now collect twenty samples from the distribution system on a reduced triennial frequency. The Water System last collected lead and copper samples in 2021 with results of non-detect and 0.18 mg/L, respectively. The Water System must monitor twenty sites in the distribution system for lead and copper between June 1 and September 30 in the 2022-2024 monitoring period.

All future lead and copper monitoring results must be submitted to the Division electronically via the Lab-To-State (LTS) Portal. The results may only be submitted through the LTS Portal by an Environmental Laboratory Accreditation Program (ELAP) accredited laboratory. A list of LTS registered laboratories can be found at:

http://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/lts_portal_info.shtml.

The Water System must complete and submit a lead and copper tap sample results reporting form with all subsequent lead and copper monitoring results. A summary of the Water System's lead and copper results and a lead and copper tap sample results reporting form are included in Appendix E.

Disinfection By-Products Monitoring

Due to continuous chlorination of source water, the Water System is required to comply with the Stage 2 Disinfection Byproduct Monitoring Rule (DBPR). To comply with Stage 2 DBPR monitoring requirements, The Water System must collect a total trihalomethane (TTHM) and five haloacetic acid (HAA5) samples from a point in the distribution system w/ the maximum residence time. The Water System currently monitors for TTHM/HAA5 at ST2S1-12307 Avenue 408. The last TTHM/HAA5 sample collected was in August 2021 with results of 1.3 mg/L and non-detect, respectively. **The Water System is due to collect samples for DBPR in August 2022.**

Asbestos

Regulation requires monitoring of systems vulnerable to asbestos contamination within the distribution system at a tap served by asbestos containing pipe. Distribution system monitoring for asbestos is required if asbestos containing pipe is used and the water produced by the sources has an aggressive index of <11.5. The aggressive index is an indicator of the corrosivity, and correlates reasonably well with asbestos fibers leaching from the pipe material. The aggressive index at Wells 05 and 09 are 12, which does not indicate a potential for asbestos contamination in the distribution system.

III. APPRAISAL OF SANITARY HAZARDS & PUBLIC HEALTH SAFEGUARDS

The Cutler Public Utilities District water system relies on two wells to supply the demands of the system. The Water System also maintains one inactive source (Well 06) which is isolated from the distribution system. Storage is provided by one 48,000-gallon elevated storage tank. The Water System's combined source capacity is approximately 1,400 gpm. At this time, the Water System is incapable of meeting California Waterworks Standards requirements to meet demand with their current combined source capacity and storage capacity.

The Water System is currently in the process of obtaining funding for a 400,000-gallon blending tank and equipping an existing well, Well 10, to mix with Well 06 water in order to provide more supply for the system in the future. Given that the

water quality at Well 10 is unknown at this time, it is unclear if the project to equip Well 10 and incorporating the blending tank will provide the Water System with the capacity required by the California Waterworks Standards. **The Division highly recommends the addition of extra storage capacity and/or an additional well, or an emergency connection with an adjacent water system such as Orosi Public Utility District.** The Domestic Water Supply Permit must be amended prior to placing Well 10 and the 400,000-gallon storage tank in service. The Water System must submit a permit amendment application and complete the permit process prior to the Division issuing a permit amendment.

The Water System was issued Compliance Order No. 03-24-22R-007 for exceeding the MCL for 1,2,3-TCP in the third quarter of 2022 at Well 05. The current running annual average for 1,2,3-TCP at Well 05 is 0.00585 ug/L. This well is the primary well for the Water System. The return to compliance date is set for August 2025.

All laboratory chemical analytical results must be submitted to the Division via CLIP with the correct PS Code. The current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>.

IV. CONCLUSIONS AND RECOMMENDATIONS

Issuance of a Domestic Water Supply Permit Amendment by the State Water Resources Control Board, Division of Drinking Water to the Cutler Public Utilities District for the operation of the Cutler Public Utilities District water system is recommended subject to the following provisions:

1. The Cutler Public Utilities District shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted thereunder.
2. The only approved sources of domestic water supply for use by the Cutler Public Utilities District are as follows:

Source Name	Status	Primary Station Code (PS Code)
Well 05 – Raw	Active	CA5410001_003_003
Well 09 – Raw	Active	CA5410001_008_008

3. The only approved treatment for the Cutler Public Utilities District is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution.

Source Name	Status	PS Code
Well 05 – CL2	Active	CA5410001_005_005
Well 09 – CL2	Active	CA5410001_009_009

4. No other sources or treatment (as described in Provisions No. 2 and 3 above) shall be used by the Cutler Public Utilities District water system and no changes, additions, or modifications shall be made without prior receipt of an amended domestic water supply permit from the Division.
5. All personnel who operate the distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Cutler Public Utilities District water system is classified as a D3 system. The Cutler Public Utilities District must have a chief distribution operator who is certified, at a minimum, as a D2 distribution system operator and a shift operator who is certified as a D1 operator or higher. The only treatment provided by the Cutler Public Utilities District is continuous chlorination, therefore no treatment operator is required.
6. The Cutler Public Utilities District shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The Cutler Public Utilities District shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.
7. The Cutler Public Utilities District shall submit an Electronic Annual Report each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
8. The Cutler Public Utilities District shall record production data from the active sources at least monthly.
9. The Cutler Public Utilities District shall collect raw water samples at least monthly from all active wells for analyses of total coliform and fecal coliform or *E. coli* bacteria. The coliform test shall be performed using a density analytical method with results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following month.

10. The Cutler Public Utilities District shall monitor for coliform bacteria in the distribution system monthly and in accordance with an approved Bacteriological Sample Siting Plan. The Division shall be notified immediately if either of the following occur
- a. Any distribution system or source sample shows the presence of *E. coli* bacteria.
 - b. The water system exceeds the maximum contaminant level for total coliform bacteria, in which more than one bacteriological sample shows the presence of coliform bacteria during a single month.
11. The Cutler Public Utilities District shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The Cutler Public Utilities District shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.
12. The Cutler Public Utilities District shall conduct Stage 2 Disinfection Byproduct (DBP) monitoring annually. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Codes:

ST2 DBP Monitoring Sites	PS Codes
ST2S1-12307 Avenue 408	CA5410001_DST_900

13. The Cutler Public Utilities District shall operate the water system in accordance with a Division-approved Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval.
14. The Cutler Public Utilities District water system shall monitor the chlorine residual in the distribution system weekly and report the residuals to the Division monthly using the Chlorine Operational Log form. The Cutler Public Utilities District water system shall submit a monthly treatment report to the Division by the 10th day of the following month.

In addition to the aforementioned permit amendment provision, the following items were required in the 2018 and 2019 Sanitary Survey Report issued by the Division and are still outstanding:

1. By **April 30, 2018**, the Water System must submit a Chlorine Operations Plan to the Division.
2. By **October 31, 2019**, the Water System must submit a copy of the Cross-Connection Control Program to the Division or provide a timeline for completing and submitting a cross-connection control program.

The following items were identified in this sanitary survey and must be addressed by the Water System:


1. By **September 16, 2022**, the Water System must submit an updated ENP to the Division.
2. By **December 31, 2022**, the Water System must submit an ERP to the Division for review and approval.

Appendices:

Appendix A: Location Map and Sanitary Survey Photographs
Appendix B: Last Sample and Next Due Summary Report
Appendix C: Source and Distribution Bacteriological Monitoring Report
Appendix D: Instructions for Accessing Individual Water System's Water Monitoring Schedule and Water Quality Data
Appendix E: Lead and Copper Tap Sample Results Reporting Form
Appendix F: Chlorination Treatment Operations Plan Template
Appendix G: Cross Connection Control Program Guidance
Appendix H: Community Water System Emergency Response Plan – Template and Instructions
Appendix I: Emergency Notification Plan Template

Appendix A:
Location Map and Photographs

Appendix A
Cutler PUD: 5410001
Location Map and Photographs



Appendix A
Cutler PUD: 5410001
Location Map and Photographs

Well 05: The well was drilled to a depth of 500 feet. The borehole contains a 14-inch steel casing to 504 feet. The well is sealed to 50 feet with cement. The well is equipped with a 75-hp deep well turbine (DWT) pump, which produces approximately 1,100 gpm.



Well 09: The well was drilled to a depth of 515 feet. The borehole contains a 14-inch steel casing to 420 feet. The well is sealed to 270 feet with cement. The well is equipped with a 40-hp deep well turbine (DWT) pump, which produces approximately 450 gpm.



Appendix A

Cutler PUD: 5410001

Location Map and Photographs

Continuous Chlorination: The Water System uses LMI chemical metering pumps (Well 04: Max output 0.65-gph @ 110 psi; Well 09: max output 1-gph @ 110 psi). The Water System uses Sanichlor chlorine solution.



48,000 Gallon Elevated Storage Tank: The Water System uses an elevated storage tank to provide distribution system pressure and storage.



Appendix B:
Last Sample & Next Due Date Summary Reports

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY: TULARE

Sample Point: WELL 05 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5410001_003_003		CUTLER PUD					WELL 05 - RAW												
	GP	SECONDARY/GP																	
		1928 ALKALINITY, BICARBONATE	220.000		3.000		MG/L	-----	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 2320 B
		1919 CALCIUM	64.000		0.100		MG/L	-----	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1929 ALKALINITY, CARBONATE		<	3.000		MG/L	-----	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 2320 B
		1017 CHLORIDE	39.000		1.000		MG/L	500	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0
		1905 COLOR	5.000		5.000		UNITS	15	-----	7/29/2022	4	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 2120 B
		1022 COPPER, FREE		<	5.000		UG/L	1000	50	7/29/2022	4	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		2905 FOAMING AGENTS (SURFACTANTS)		<	0.050		MG/L	0.5	-----	7/29/2022	4	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 5540 C-00
		1915 HARDNESS, TOTAL (AS CaCO3)	260.000		0.410		MG/L	-----	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 2340 B
		1021 HYDROXIDE AS CALCIUM CARBONATE		<	3.000		MG/L	-----	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 2320 B
		1028 IRON		<	30.000		UG/L	300	100	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1031 MAGNESIUM	23.000		0.100		MG/L	-----	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1032 MANGANESE	14.000		10.000		UG/L	50	20	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY: TULARE

Sample Point: WELL 05 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORTING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MONTHS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5410001_003_003	GP	SECONDARY/GP																	
		1920	ODOR		<	1.000	TON	3	1	7/29/2022	4	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 2150 B
		1925	PH	7.900		0.000		-----	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 4500-HB
		1050	SILVER		<	10.000	UG/L	100	10	7/29/2022	4	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1052	SODIUM	36.000		1.000	MG/L	-----	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1064	CONDUCTIVITY @ 25 C UMHOS/CM	670.000		1.000	US	1600	-----	7/29/2022	10	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 2510 B
		1055	SULFATE	32.000		1.000	MG/L	500	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0
		1930	TDS	450.000		5.000	MG/L	1000	-----	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 2540 C
		0100	TURBIDITY	0.830		0.100	NTU	5	0.1	7/29/2022	4	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SM 2130 B-01
		1095	ZINC		<	50.000	UG/L	5000	50	7/29/2022	4	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
	IO	INORGANIC																	
		1002	ALUMINUM		<	50.000	UG/L	1000	50	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1074	ANTIMONY, TOTAL		<	2.000	UG/L	6	6	7/29/2022	4	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1005	ARSENIC	2.100		2.000	UG/L	10	2	7/29/2022	4	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY: TULARE

Sample Point: WELL 05 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5410001_003_003	RA	RADIOLOGICAL																		
		4109	GROSS ALPHA PARTICLE ACTIVITY		<	1.500	0.191	PCI/L	15	3	8/11/2015	625	108	Interval	2024/08		59310031 50811124 7R	1180	BSK ANALYTICAL LABORATORIES	
	S1	REGULATED VOC																		
		2981	1,1,1-TRICHLOROETHANE		<	0.500		UG/L	200	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2988	1,1,2,2-TETRACHLOROETHANE		<	0.500		UG/L	1	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2985	1,1,2-TRICHLOROETHANE		<	0.500		UG/L	5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2978	1,1-DICHLOROETHANE		<	0.500		UG/L	5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2977	1,1-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2378	1,2,4-TRICHLOROBENZENE		<	0.500		UG/L	5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2968	O-DICHLOROBENZENE		<	0.500		UG/L	600	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2980	1,2-DICHLOROETHANE		<	0.500		UG/L	0.5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2983	1,2-DICHLOROPROPANE		<	0.500		UG/L	5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY: TULARE

Sample Point: WELL 05 - RAW

CLASS: CLGA

STATUS: Active

PCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5410001_003_003	S1	REGULATED VOC																		
		2413	1,3-DICHLOROPROPENE		<	0.500		UG/L	0.5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2969	P-DICHLOROBENZENE		<	0.500		UG/L	5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2990	BENZENE		<	0.500		UG/L	1	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2982	CARBON TETRACHLORIDE		<	0.500		UG/L	0.5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2380	CIS-1,2-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2964	DICHLOROMETHANE		<	0.500		UG/L	5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2992	ETHYLBENZENE		<	0.500		UG/L	300	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2251	METHYL TERT-BUTYL ETHER		<	0.500		UG/L	13	3	7/29/2022	90	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2989	CHLOROBENZENE		<	0.500		UG/L	70	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2996	STYRENE		<	0.500		UG/L	100	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2987	TETRACHLOROETHYLENE		<	0.500		UG/L	5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2991	TOLUENE		<	0.500		UG/L	150	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD						COUNTY: TULARE														
Sample Point: WELL 05 - RAW						CLASS: CLGA						STATUS: Active								
CA5410001_003_003	S1	2979	TRANS-1,2-DICHLOROE THYLENE		<	0.500		UG/L	10	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2984	TRICHLORO ETHYLENE		<	0.500		UG/L	5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2218	TRICHLORO FLUOROMET HANE		<	5.000		UG/L	150	5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2904	TRICHLORO TRIFLUORO ETHANE		<	10.000		UG/L	1200	10	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2976	VINYL CHLORIDE		<	0.500		UG/L	0.5	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
		2955	XYLENES, TOTAL		<	0.500		UG/L	1750	0.5	7/29/2022	5	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2
	S2	REGULATED SOC																		
		2414	1,2,3-TRICHLORO PROPANE	0.007		0.001		UG/L	0.005	0.005	7/29/2022	28	1	Both	2021/11	DUE NOW	AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	SRL 524M-TCP
		2051	LASSO (ALACHLOR)		<	1.000		UG/L	2	1	10/22/2021	25	36		2024/10		AEJ2543-01	1180	BSK ANALYTICAL LABORATORIES	EPA 505
		2050	ATRAZINE		<	0.500		UG/L	1	0.5	10/22/2021	25	36		2024/10		AEJ2543-01	1180	BSK ANALYTICAL LABORATORIES	EPA 505
		2931	1,2-DIBROMO-3-CHLOROPR OPANE	0.093		0.010		UG/L	0.2	0.01	7/29/2022	120	1	Interval	2022/08	DUE NOW	AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 504.1
		2946	ETHYLENE DIBROMIDE		<	0.020		UG/L	0.05	0.02	7/29/2022	119	36		2025/07		AFG3534-01	1180	BSK ANALYTICAL LABORATORIES	EPA 504.1
		2037	SIMAZINE		<	1.000		UG/L	4	1	10/22/2021	25	36		2024/10		AEJ2543-01	1180	BSK ANALYTICAL LABORATORIES	EPA 505

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY: TULARE

Sample Point: WELL 09 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5410001_008_008	IO	INORGANIC																	
		1010	BARIUM	97.000		50.000	UG/L	1000	100	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1075	BERYLLIUM, TOTAL		<	1.000	UG/L	4	1	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1015	CADMIUM		<	1.000	UG/L	5	1	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1020	CHROMIUM		<	10.000	UG/L	50	10	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1025	FLUORIDE	0.150		0.100	MG/L	2	0.1	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0
		1035	MERCURY		<	0.200	UG/L	2	1	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1036	NICKEL		<	10.000	UG/L	100	10	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1039	PERCHLORATE		<	2.000	UG/L	6	2	8/25/2021	25	36		2024/08		AEH2905-02	1180	BSK ANALYTICAL LABORATORIES	EPA 314.0
		1045	SELENIUM		<	2.000	UG/L	50	5	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1085	THALLIUM, TOTAL		<	1.000	UG/L	2	1	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
	NI	NITRATE/NITRITE																	
		1040	NITRATE	4.700		0.230	mg/L	10	0.4	7/29/2022	25	3	Interval	2022/10		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0
		1041	NITRITE		<	0.050	mg/L	1	0.4	7/29/2022	4	36		2025/07		AFG3534-02	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY: TULARE

Sample Point: WELL 09 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5410001_008_008	RA	RADIOLOGICAL																		
		4109	GROSS ALPHA PARTICLE ACTIVITY	5.210		0.900	0.907	PCI/L	15	3	11/13/2020	64	72	Interval	2026/11		59310082011131025R	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	S1	REGULATED VOC																		
		2981	1,1,1-TRICHLOROETHANE		<	0.500		UG/L	200	0.5	7/23/2021	16	36		2024/07		59310082107231200V	1186	BC LABORATORIES	
		2988	1,1,2,2-TETRACHLOROETHANE		<	0.500		UG/L	1	0.5	7/23/2021	16	36		2024/07		59310082107231200V	1186	BC LABORATORIES	
		2985	1,1,2-TRICHLOROETHANE		<	0.500		UG/L	5	0.5	7/23/2021	16	36		2024/07		59310082107231200V	1186	BC LABORATORIES	
		2978	1,1-DICHLOROETHANE		<	0.500		UG/L	5	0.5	7/23/2021	16	36		2024/07		59310082107231200V	1186	BC LABORATORIES	
		2977	1,1-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	7/23/2021	16	36		2024/07		59310082107231200V	1186	BC LABORATORIES	
		2378	1,2,4-TRICHLOROBENZENE		<	0.500		UG/L	5	0.5	7/23/2021	16	36		2024/07		59310082107231200V	1186	BC LABORATORIES	
		2968	O-DICHLOROBENZENE		<	0.500		UG/L	600	0.5	7/23/2021	16	36		2024/07		59310082107231200V	1186	BC LABORATORIES	
		2980	1,2-DICHLOROETHANE		<	0.500		UG/L	0.5	0.5	7/23/2021	16	36		2024/07		59310082107231200V	1186	BC LABORATORIES	
		2983	1,2-DICHLOROPROPANE		<	0.500		UG/L	5	0.5	7/23/2021	16	36		2024/07		59310082107231200V	1186	BC LABORATORIES	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY: TULARE

Sample Point: WELL 09 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5410001_008_008	S1	REGULATED VOC																	
		2413	1,3-DICHLOROP ROPENE		<	0.500	UG/L	0.5	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2969	P-DICHLOROB ENZENE		<	0.500	UG/L	5	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2990	BENZENE		<	0.500	UG/L	1	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2982	CARBON TETRACHLO RIDE		<	0.500	UG/L	0.5	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2380	CIS-1,2-DICHLOROE THYLENE		<	0.500	UG/L	6	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2964	DICHLOROM ETHANE		<	0.500	UG/L	5	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2992	ETHYLBENZ ENE		<	0.500	UG/L	300	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2251	METHYL TERT-BUTYL ETHER		<	0.500	UG/L	13	3	7/23/2021	100	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2989	CHLOROBEN ZENE		<	0.500	UG/L	70	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2996	STYRENE		<	0.500	UG/L	100	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2987	TETRACHLO ROETHYLEN E		<	0.500	UG/L	5	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2991	TOLUENE		<	0.500	UG/L	150	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY: TULARE

Sample Point: WELL 09 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5410001_008_008	S1	2979	TRANS-1,2-DICHLOROE THYLENE		<	0.500		UG/L	10	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2984	TRICHLORO ETHYLENE		<	0.500		UG/L	5	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2218	TRICHLORO FLUOROMET HANE		<	0.500		UG/L	150	5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2904	TRICHLORO TRIFLUORO ETHANE		<	0.500		UG/L	1200	10	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2976	VINYL CHLORIDE		<	0.500		UG/L	0.5	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
		2955	XYLENES, TOTAL		<	0.500		UG/L	1750	0.5	7/23/2021	16	36		2024/07		59310082 10723120 0V	1186	BC LABORATORIES	
	S2	REGULATED SOC																		
		2414	1,2,3- TRICHLORO PROPANE		<	0.000		UG/L	0.005	0.005	7/23/2021	324	36		2024/07		59310082 10723120 0S	1180	BSK ANALYTICAL LABORATORIES	
		2051	LASSO (ALACHLOR)		<	1.000		UG/L	2	1	8/25/2021	25	36		2024/08		AEH2905- 02	1180	BSK ANALYTICAL LABORATORIES	EPA 505
		2050	ATRAZINE		<	0.500		UG/L	1	0.5	8/25/2021	25	36		2024/08		AEH2905- 02	1180	BSK ANALYTICAL LABORATORIES	EPA 505
		2931	1,2- DIBROMO-3 - CHLOROPR OPANE		<	0.010		UG/L	0.2	0.01	7/29/2022	7	36		2025/07		AFG3534- 02	1180	BSK ANALYTICAL LABORATORIES	EPA 504.1
		2946	ETHYLENE DIBROMIDE		<	0.020		UG/L	0.05	0.02	7/29/2022	7	36		2025/07		AFG3534- 02	1180	BSK ANALYTICAL LABORATORIES	EPA 504.1
		2037	SIMAZINE		<	1.000		UG/L	4	1	8/25/2021	25	36		2024/08		AEH2905- 02	1180	BSK ANALYTICAL LABORATORIES	EPA 505

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY: TULARE

Sample Point: ST2S1-12307 AVE 408

CLASS: DBPA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD				
CA5410001_ DST_900		CUTLER PUD						ST2S1-12307 AVE 408																
	DBP	DISINFECTION BYPRODUCTS																						
		2943	BROMODIC HLOROMET HANE		<	0.500		UG/L	-----	1	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2				
		2942	BROMOFOR M	0.840		0.500		UG/L	-----	1	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2				
		2941	CHLOROFOR M		<	0.500		UG/L	-----	1	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2				
		2454	DIBROMOAC ETIC ACID		<	1.000		UG/L	-----	1	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3				
		2944	DIBROMOC HLOROMET HANE	0.500		0.500		UG/L	-----	1	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2				
		2451	DICHLOROA CETIC ACID		<	1.000		UG/L	-----	1	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3				
		2456	TOTAL HALOACETI C ACIDS (HAA5)		<	2.000		UG/L	60	----	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3				
		2453	MONOBROM OACETIC ACID		<	1.000		UG/L	-----	1	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3				
		2450	MONOCHLO ROACETIC ACID		<	2.000		UG/L	-----	2	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3				
		2950	TTHM	1.300		0.500		UG/L	80	----	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2				

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: CUTLER PUD

COUNTY:

Sample Point:

CLASS: DBPA

STATUS:

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5410001_ DST_900	DBP	2452	TRICHLORO ACETIC ACID		<	1.000		UG/L	-----	1	8/11/2021	81	12		2022/08	DUE NOW	AEH1359 -01	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3

Appendix C:
Source and Distribution Water Bacteriological Monitoring Report

Bacteriological Distribution Monitoring Report

5410001 *Cutler Public Utility District*

Distribution System Freq: 7/M

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>Cl2</i>	<i>Cl2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
8/10/2022	2 samples	A	A			Routine	0.38-0.46				
8/2/2022	2 samples	A	A			Routine	0.48-0.54				
7/26/2022	2 samples	A	A			Routine	0.41-0.45				
7/19/2022	2 samples	A	A			Routine	0.34-0.42				
7/19/2022	Water Tower	A	A			Other	0.46				
7/12/2022	2 samples	A	A			Routine	0.41-0.43				
7/5/2022	2 samples	A	A			Routine	0.46-0.53				
6/28/2022	2 samples	A	A			Routine	0.36-0.50				
6/21/2022	2 samples	A	A			Routine	0.49-0.50				
6/21/2022	Water Tower	A	A			Other	0.56				
6/14/2022	2 samples	A	A			Routine	0.55-0.59				
6/7/2022	2 samples	A	A			Routine	0.49-0.51				
5/31/2022	12663 Amethyst Avenue	A	A			Routine	0.44				
5/31/2022	40474 Cindy Road	A	A			Routine	0.39				
5/24/2022	40612 Road 124	A	A			Routine	0.35				
5/24/2022	13091 Rosalie Avenue	A	A			Routine	0.33				
5/17/2022	2 samples	A	A			Routine	0.41-0.42				
5/17/2022	Water Tower	A	A			Other	0.50				
5/10/2022	40632 Road 124	A	A			Routine	0.3				
5/10/2022	13091 Roasalie Avenue	A	A			Routine	0.59				
5/3/2022	12663 Amethyst Avenue	A	A			Routine	0.35				
5/3/2022	40474 Cindy Road	A	A			Routine	0.35				
4/26/2022	40620 Road 124	A	A			Routine	0.4				
4/26/2022	13091 Roasalie Avenue	A	A			Routine	0.46				
4/19/2022	12663 Amethyst Avenue	A	A			Routine	0.53				
4/19/2022	40474 Cindy Road	A	A			Routine	0.47				
4/19/2022	Water Tower	A	A			Other	0.52				
4/12/2022	40620 Road 124	A	A			Routine	0.53				
4/12/2022	13091 Rosalie Avenue	A	A			Routine	0.51				
4/5/2022	12663 Amethyst Avenue	A	A			Routine	0.42				
4/5/2022	40474 Cindy Road	A	A			Routine	0.36				
3/29/2022	40620 Rd. 124	A	A			Routine	0.47				
3/29/2022	13091 Rosalie Avenue	A	A			Routine	0.4				
3/22/2022	12663 Amethyst Avenue	A	A			Routine	0.31				
3/22/2022	40474 Cindy Road	A	A			Routine	0.33				
3/15/2022	40620 Road 124	A	A			Routine	0.58				
3/15/2022	13091 Rosalie Avenue	A	A			Routine	0.45				
3/15/2022	Water Tower	A	A			Routine	0.62				
3/9/2022	12663 Amethyst avenue	A	A			Routine	0.45				
3/9/2022	40474 Cindy Road	A	A			Routine	0.39				
3/1/2022	13091 Rosalie Avenue	A	A			Routine	0.41				

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>Cl2</i>	<i>Cl2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
3/1/2022	40620 Road 124	A	A			Routine	0.58				
2/22/2022	12663 Amethyst Avenue	A	A			Routine	0.4				
2/22/2022	40474 Cindy Road	A	A			Routine	0.34				
2/16/2022	13091 Rosalie Avenue	A	A			Routine	0.43				
2/16/2022	40620 Road 124	A	A			Routine	0.39				
2/16/2022	Water Tower	A	A			Other	0.47				
2/8/2022	12663 Amethyst Avenue	A	A			Routine	0.43				
2/8/2022	40474 Cindy Road	A	A			Routine	0.35				
2/1/2022	13091 Rosalie Avenue	A	A			Routine	0.4				
2/1/2022	40620 Road 124	A	A			Routine	0.44				
1/25/2022	12663 Amethyst Ave	A	A			Routine	0.41				
1/25/2022	40474 Cindy Road	A	A			Routine	0.3				
1/18/2022	13091 Rosalie Avenue	A	A			Routine	0.39				
1/18/2022	40620 Road 124	A	A			Routine	0.47				
1/18/2022	Water Tower	A	A			Other	0.53				
1/11/2022	12663 Amethyst Ave	A	A			Routine	0.42				
1/11/2022	40474 Cindy Road	A	A			Routine	0.38				
1/4/2022	40620 Road 124	A	A			Routine	0.4				
1/4/2022	13091 Rosalie Avenue	A	A			Routine	0.44				
12/28/2021	12663 Amethyst Ave	A	A			Routine	0.38				
12/28/2021	40474 Cindy Road	A	A			Routine	0.42				
12/21/2021	40620 Road 124	A	A			Routine	0.38				
12/21/2021	13091 Rosalie Avenue	A	A			Routine	0.51				
12/21/2021	Water Tower	A	A			Routine	0.56				
12/14/2021	12663 Amethyst Ave	A	A			Routine	0.39				
12/14/2021	40474 Cindy Road	A	A			Routine	0.41				
12/7/2021	40620 Road 124	A	A			Routine	0.56				
12/7/2021	13091 Rosalie Ave	A	A			Routine	0.38				
11/30/2021	12663 Amethyst Avenue	A	A			Routine	0.37				
11/30/2021	40474 Cindy Road	A	A			Routine	0.33				
11/23/2021	40620 Road 124	A	A			Routine	0.53				
11/23/2021	13091 Rosalie Avenue	A	A			Routine	0.43				
11/16/2021	12663 Amethyst Avenue	A	A			Routine	0.39				
11/16/2021	40474 Cindy Road	A	A			Routine	0.43				
11/16/2021	Water Tower	A	A			Routine	0.67				
11/9/2021	40620 Rd. 124	A	A			Routine	0.43				
11/9/2021	13091 Rosalie Ave	A	A			Routine	0.36				
11/2/2021	12663 Amethyst Avenue	A	A			Routine	0.37				
11/2/2021	40474 Cindy Road	A	A			Routine	0.41				
10/26/2021	40620 Road 124	A	A			Routine	0.34				
10/26/2021	13091 Rosalie Ave	A	A			Routine	0.38				
10/19/2021	12663 Amethyst Avenue	A	A			Routine	0.37				
10/19/2021	40474 Cindy Road	A	A			Routine	0.41				
10/19/2021	Water Tower	A	A			Routine	0.48				
10/12/2021	40620 Rd 124	A	A			Routine	0.4				
10/12/2021	13091 Rosalie Ave	A	A			Routine	0.41				

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>Cl2</i>	<i>Cl2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
10/5/2021	12663 Amethyst Avenue	A	A			Routine	0.38				
10/5/2021	40474 Cindy Road	A	A			Routine	0.34				
9/28/2021	40620 Road 124	A	A			Routine	0.4				
9/28/2021	13091 Rosalie Avenue	A	A			Routine	0.47				
9/21/2021	12663 Amethyst Avenue	A	A				0.43				
9/21/2021	40474 Cindy Road	A	A				0.41				
9/14/2021	40620 Road 124	A	A			Routine	0.4				
9/14/2021	13091 Rosalia Ave	A	A			Routine	0.46				
9/7/2021	12663 Amethyst Ave	A	A			Routine	0.4				
9/7/2021	40474 Cindy Road	A	A			Routine	0.46				
8/31/2021	40620 Road 124	A	A			Routine	0.43				
8/31/2021	13091 Rosalie Ave	A	A			Routine	0.4				
8/25/2021	12663 Amethyst Ave	A	A			Routine	0.45				
8/25/2021	40474 Cindy Road	A	A			Routine	0.56				
8/17/2021	40620 Road 124	A	A			Routine	0.39				
8/17/2021	13091 Rosalie Avenue	A	A			Routine	0.53				
8/17/2021	Water Tower	A	A			Other	0.58				
8/10/2021	12663 Amethyst Avenue	A	A			Routine	0.28				
8/10/2021	40474 Cindy Road	A	A			Routine	0.42				
8/3/2021	2 samples	A	A			Routine	0.32-0.50				
7/27/2021	2 samples	A	A			Routine	0.30-0.36				
7/20/2021	2 samples	A	A			Routine	0.25-0.28				
7/20/2021	Water Tower	A	A			Other	0.28				
7/13/2021	2 samples	A	A			Routine	0.39-0.41				
7/6/2021	2 samples	A	A			Routine	0.32-0.35				
6/29/2021	2 samples	A	A			Routine	0.29-0.36				
6/22/2021	2 samples	A	A			Routine	0.33-0.48				
6/15/2021	2 samples	A	A			Routine	0.43-0.47				
6/15/2021	Water Tower	A	A			Other	0.50				
6/8/2021	2 samples	A	A			Routine					
6/1/2021	2 samples	A	A			Routine					
5/25/2021	2 samples	A	A			Routine					
5/18/2021	2 samples	A	A			Routine					
5/18/2021	Water Tower	A	A			Other	0.58				
5/11/2021	2 samples	A	A			Routine					
5/4/2021	2 samples	A	A			Routine					
4/27/2021	2 samples	A	A			Routine					
4/20/2021	2 samples	A	A			Routine					
4/20/2021	Water Tower	A	A			Other	0.57				
4/13/2021	2 samples	A	A			Routine					
4/6/2021	2 samples	A	A			Routine					
3/30/2021	2 samples	A	A			Routine					
3/24/2021	2 samples	A	A			Routine					
3/16/2021	2 samples	A	A			Routine					
3/16/2021	Water Tower	A	A			Other	0.71				
3/9/2021	2 samples	A	A			Routine					
3/2/2021	2 samples	A	A			Routine	0.39-0.41				
2/23/2021	2 samples	A	A			Routine					
2/16/2021	2 samples	A	A			Routine					
2/16/2021	Water Tower	A	A			Other	0.48				
2/9/2021	2 samples	A	A			Routine					

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>Cl2</i>	<i>Cl2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
2/9/2021	2 samples	A	A			Routine					
2/2/2021	2 samples	A	A			Routine					
1/26/2021	2 samples	A	A			Routine					
1/19/2021	2 samples	A	A			Routine	0.35-0.43				
1/19/2021	Water Tower	A	A			Other	0.65				
1/12/2021	2 samples	A	A			Routine	0.32-0.34				
1/5/2021	2 samples	A	A			Routine					
12/29/2020	2 samples	A	A			Routine					
12/22/2020	2 samples	A	A			Routine					
12/15/2020	2 samples	A	A			Routine					
12/15/2020	Water Tower	A	A			Other	0.59				
12/8/2020	2 samples	A	A			Routine	0.39-0.43				
12/1/2020	2 samples	A	A			Routine	0.49-0.51				
11/24/2020	2 samples	A	A			Routine	0.52-0.59				
11/17/2020	2 samples	A	A			Routine	0.3-0.46				
11/17/2020	Water Tower	A	A			Other	0.58				
11/10/2020	2 samples	A	A			Routine					
11/3/2020	2 samples	A	A			Routine					
10/20/2020	2 samples	A	A			Routine					
10/20/2020	Water Tower	A	A			Routine	0.57				
10/13/2020	2 samples	A	A			Routine	0.39-0.44				
10/6/2020	2 samples	A	A			Routine	0.37-0.49				
9/29/2020	2 samples	A	A			Routine	0.31-0.42				
9/22/2020	2 samples	A	A			Routine	0.32-0.40				
9/15/2020	2 samples	A	A			Routine					
9/15/2020	Water Tower	A	A			Other	0.47				
9/8/2020	2 samples	A	A			Routine					
9/1/2020	2 samples	A	A			Routine					
8/25/2020	2 samples	A	A			Routine					
8/18/2020	2 samples	A	A			Routine	0.49				
8/18/2020	Water Tower	A	A			Other	0.58				
8/11/2020	2 samples	A	A			Routine					
8/4/2020	2 samples	A	A			Routine					
7/28/2020	2 samples	A	A			Routine					
7/21/2020	2 samples	A	A			Routine	0.37-0.54				
7/21/2020	Water Tower	A	A			Other	0.53				
7/14/2020	2 samples	A	A			Routine					
7/7/2020	2 samples	A	A			Routine					
6/30/2020	2 samples	A	A			Routine					
6/23/2020	2 samples	A	A			Routine	0.51-0.56				
6/16/2020	2 samples	A	A			Routine					
6/16/2020	Water Tower	A	A			Other	0.59				
6/9/2020	2 samples	A	A			Routine	0.52-0.56				
6/4/2020	13091 Rosalie Avenue	A	A			Repeat	0.53				
6/4/2020	13103 Rosalie Avenue	A	A			Repeat	0.5				
6/4/2020	13089 Rosalie Avenue	A	A			Repeat	0.55				
6/2/2020	40620 Rd 124	A	A			Routine	0.46				
6/2/2020	13091 Rosalie Avenue	P	A			Routine	0.33				
5/19/2020	Water Tower	A	A			Other	0.55				
5/1/2020	8 samples	A	A			Routine	0.41-0.53				
4/21/2020	Water Tower	A	A			Other	0.61				
4/1/2020	8 samples	A	A			Routine	0.34-0.48				

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>Cl2</i>	<i>Cl2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
3/17/2020	Water Tower	A	A			Other					
3/1/2020	10 samples	A	A			Routine	0.39-0.56				
2/18/2020	Water Tower	A	A			Other	0.44				
2/1/2020	8 samples	A	A			Routine	0.27-0.52				
1/21/2020	Water Tower	A	A			Other	0.63				
1/1/2020	8 samples	A	A			Routine	0.37-0.51				
12/17/2019	Water Tower	A	A			Other					
12/1/2019	10 samples	A	A			Routine	0.4-0.53				
11/20/2019	Water Tower	A	A			Other	0.61				
11/1/2019	8 samples	A	A			Routine	0.43-0.62				
10/15/2019	Water Tower	A	A			Other	0.65				
10/1/2019	10 samples	A	A			Routine	0.39-0.71				
9/20/2019	12663 Amethyst Ave	<1	<1			Repeat	0.60				
9/20/2019	12671 Amethyst	<1	<1			Repeat	0.38				
9/20/2019	12661 Amethyst	<1	<1			Repeat	0.45				
9/20/2019	40466 Cindy	<1	<1			Repeat	0.31				
9/20/2019	40474 Cindy Rd	<1	<1			Repeat	0.33				
9/20/2019	40484 Cindy	<1	<1			Repeat	0.29				
9/19/2019	Wells: 5,9	<1	<1			Source Repeat				Yes	GWR satisfied
9/19/2019	12663 Amethyst Ave	<1	<1			Repeat	0.5				
9/19/2019	12671 Amethyst	<1	<1			Repeat	0.41				
9/19/2019	12661 Amethyst	<1	<1			Repeat	0.45				
9/19/2019	40474 Cindy Road	<1	<1			Repeat	0.58				
9/19/2019	40466 Cindy	<1	<1			Repeat	0.41				
9/19/2019	40484 Cindy	<1	<1			Repeat	0.46				
9/17/2019	12663 Amethyst Ave	P	A			Routine	0.41				
9/17/2019	40474 Cindy Road	P	P			Routine	0.38		MCL		Cit 03-24-19C-116
9/17/2019	Water Tower	A	A			Other	0.55				
9/1/2019	6 samples	A	A			Routine	0.27-0.69				
8/29/2019	Blending Line	A	A			Other	0.14				
8/28/2019	Blending Line	A	A			Other	0.54				
8/20/2019	Water Tower	A	A			Other	0.58				
8/10/2019	System	A	A								
8/8/2019	Blending Tank	A	A			Other	0.25				
8/6/2019	8 samples	A	A			Routine	0.26-0.51				
7/16/2019	Water Tower	A	A			Other	0.41				
7/1/2019	10 samples	A	A			Routine	0.27-0.42				
6/18/2019	Water Tower	A	A			Routine	0.53				
6/1/2019	8 samples	A	A			Routine	0.29-0.47				
5/21/2019	Water Tower	A	A			Other	0.43				
5/1/2019	8 samples	A	A			Routine	0.27-0.33				
4/16/2019	Water Tower	A	A			Other	0.42				
4/1/2019	10 Samples	A	A			Routine	0.29-0.38				
3/29/2019	Topeka & First Dr	A	A			Other	0.33				
3/19/2019	Water Tower	A	A			Other	0.53				
3/1/2019	8 samples	A	A			Routine	0.29-0.49				
2/19/2019	Water Tower	A	A			Other	0.5				
2/1/2019	8 samples	A	A			Routine	0.25-0.46				
1/15/2019	Water Tower	A	A			Other					
1/1/2019	10 Samples	A	A			Routine	0.29-0.41				

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>Cl2</i>	<i>Cl2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
<i>Violation Key</i>											
MCL	Exceeds the maximum contaminant level					MR5	Incorrect number of repeat samples as follow-up to a positive sample				
MR1	No monthly sample for the report month					MR6	No source sample				
MR2	No quarterly sample for the report month					MR7	No summary report submitted				
MR3	Incorrect number of routine samples for the report month					MR8	Other comments and/or info				
MR4	Did not collect 5 routine samples for previous month's positive sample					MR9	Cl2 not reported				

Source Bacteriological Monitoring Report

5410001 Cutler Public Utility District

Sample Date	Time	Source	Sample Type	Test Method	T Coli	E Coli	F Coli	HPC	Violation	Comments
8/10/2022	8:55	Well 9	Well	P/A	A	A				
8/2/2022	8:58	Well 5	Well	P/A	A	A				
7/12/2022	8:15	Well 9	Well	P/A	A	A				
7/5/2022	8:41	Well 5	Well	P/A	A	A				
6/14/2022	8:37	Well 9	Well	P/A	A	A				
6/7/2022	8:55	Well 5	Well	P/A	A	A				
5/10/2022	8:30	Well #9	Well	P/A	A	A				
5/3/2022	9:00	Well #5	Well	P/A	A	A				
4/12/2022	8:47	Well #9	Well	P/A	A	A				
4/12/2022	8:47	Well #9	Well	P/A	A	A				
4/5/2022	8:53	Well #5	Well	P/A	A	A				
3/9/2022	8:50	Well #9	Well	P/A	A	A				
3/1/2022	8:43	Well #5	Well	P/A	A	A				
2/8/2022	8:45	Well #9	Well	P/A	A	A				
2/1/2022	8:36	Well #5	Well	P/A	A	A				
1/11/2022	8:32	Well #9	Well	P/A	A	A				
1/4/2022	9:05	Well #5	Well	P/A	A	A				
12/21/2021	9:23	Well #9	Well	P/A	A	A				
12/14/2021	8:43	Well #9	Well	P/A	P	A				
12/7/2021	9:00	Well #5	Well	P/A	A	A				
11/9/2021	9:08	Well #9	Well	P/A	A	A				
11/2/2021	8:28	Well #5	Well	P/A	A	A				
10/12/2021	8:53	Well #9	Well	P/A	A	A				
10/5/2021	8:47	Well #5	Well	P/A	A	A				
9/21/2021	8:36	Water Tower	Water Tower	P/A	A	A				
9/14/2021	8:50	Well #9	Well	P/A	A	A				
9/7/2021	8:55	Well #5	Well	P/A	A	A				
8/10/2021	8:55	Well #9	Well	P/A	A	A				
8/3/2021	9:05	Well 5	Well	P/A	A	A				
7/13/2021	9:10	Well 9	Well	P/A	A	A				
7/6/2021	8:50	Well 5	Well	P/A	A	A				
6/8/2021	8:45	Well 5	Well	P/A	A	A				
6/1/2021	7:30	Well 9	Well	P/A	A	A				
5/11/2021	7:35	Well 9	Well	P/A	A	A				
5/4/2021	8:44	Well 5	Well	P/A	A	A				
4/13/2021	8:45	Well 9	Well	P/A	A	A				
4/6/2021	8:45	Well 5	Well	P/A	A	A				
3/9/2021	8:13	Well 9	Well	P/A	A	A				
3/2/2021	8:40	Well 5	Well	P/A	A	A				
2/9/2021	8:50	Well 9	Well	P/A	A	A				
2/9/2021	8:50	Well 9	Well	P/A	A	A				

5410001 Cutler Public Utility District

Sample Date	Time	Source	Sample Type	Test Method	T Coli	E Coli	F Coli	HPC	Violation	Comments
2/2/2021	8:45	Well 5	Well	P/A	A	A				
1/12/2021	8:55	Well 9	Well	P/A	A	A				
1/5/2021	8:51	Well #5	Well	P/A	A	A				
12/8/2020	9:09	Well #9	Well	P/A	A	A				
12/1/2020	8:40	Well #5	Well	P/A	A	A				
11/10/2020		Well 9	Well	P/A	A	A				
11/3/2020	8:23	Well 5	Well	P/A	A	A				
10/13/2020	8:50	Well 9	Well	P/A	A	A				
10/6/2020	8:44	Well 5	Well	P/A	A	A				
9/8/2020	8:36	Well 9	Well	P/A	A	A				
9/1/2020	8:53	Well 5	Well	P/A	A	A				
8/11/2020	8:35	Well 9	Well	P/A	A	A				
8/4/2020	8:25	Well 5	Well	P/A	A	A				
7/14/2020	8:40	Well 9	Well	P/A	A	A				
7/7/2020	8:40	Well 5	Well	P/A	A	A				
6/9/2020	8:45	Well 9	Well	P/A	A	A				
6/5/2020	8:50	Well 5	Well	P/A	A	A				
6/2/2020	8:45	Well 5	Well	P/A	A	A				
5/12/2020	8:45	Well 9	Well	P/A	A	A				
5/6/2020	8:42	Well 5	Well	P/A	A	A				
4/14/2020	8:45	Well 9	Well	P/A	A	A				
3/3/2020	8:22	Well 5	Well	P/A	A	A				
2/11/2020	8:03	Well 9	Well	P/A	A	A				
2/4/2020	8:30	Well 5	Well	P/A	A	A				
1/14/2020	8:37	Well 9	Well	P/A	A	A				
1/7/2020	8:38	Well 5	Well	P/A	A	A				
12/10/2019	8:38	Well 9	Well	P/A	A	A				
12/3/2019	8:24	Well #5	Well	P/A	A	A				
11/12/2019	8:10	Well 9	Well	P/A	A	A				
11/5/2019	8:28	Well 5	Well	P/A	A	A				
10/8/2019	8:30	Well #9	Well	P/A	A	A				
10/1/2019	8:55	Well 5	Well	P/A	A	A				
9/20/2019	9:50	Well #5	GWR Well	QTray	<1	<1				Repeat
9/20/2019	10:00	Well #9	GWR Well	Qtray	<1	<1				Repeat
9/19/2019		Wells: 5,9	GWR Well	QTray	<1	<1				
9/10/2019	8:52	Well 9	Well	P/A	A	A				
9/3/2019	9:03	Well 5	Well	P/A	A	A				
8/13/2019	8:45	Well 9	Well	P/A	A	A				
8/6/2019	9:05	Well 5	Well	P/A	A	A				
7/9/2019	8:33	Well 9	Well	P/A	A	A				
7/2/2019	8:42	Well 5	Well	P/A	A	A				
6/11/2019	9:25	Well 9	Well	P/A	A	A				
6/4/2019	8:55	Well 5	Well	P/A	A	A				


5410001 Cutler Public Utility District

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
5/14/2019	8:55	Well 9	Well	P/A	A	A				
5/7/2019	8:48	Well 5	Well	P/A	A	A				
4/9/2019	8:45	Well 9	Well	P/A	A	A				
4/2/2019	8:45	Well 5	Well	P/A	A	A				
3/12/2019	8:42	Well 9	Well	P/A	A	A				
3/5/2019	8:35	Well 5	Well	P/A	A	A				
2/12/2019	8:23	Well 9	Well	P/A	A	A				
2/5/2019	8:13	Well 5	Well	P/A	A	A				
1/8/2019	8:55	Well #9	Well	P/A	A	A				
1/2/2019	8:15	Well #5	Well	P/A	A	A				

Appendix D:
Instructions for Accessing Individual Water System's Water Monitoring
Schedule and Water Quality Data

How To Access Individual System's Drinking Water Monitoring Schedule & Water Quality Data

1. Place the following link in the internet address bar:
<https://sdwis.waterboards.ca.gov/PDWW/>
2. Enter your Water System No. and select "Search For Water Systems"



SDWIS Version 3.21

California Public Water Supply Systems Search Parameters

Water System No. Enter your Water System No. (i.e. 54####)

Water System Name

Principal County Served


Water System Type

Water System Status

Primary Source Water Type

[Click Here for the County Map of CALIFORNIA](#)

3. Click on your Water System No. (Link in blue text).



Drinking Water Division

Water Systems

Hide/show columns: [Water System No.](#) | [Water System Name](#) | [Type](#) | [Status](#) | [Principal County Served](#) | [Primary Source Water Type](#)

Display records Search:

Water System No.	Water System Name	Type	Status	Principal County Served	Primary Source Water Type
CA5403043	YETTEM WATER SYSTEM	C	A	TULARE	GW

Showing 1 to 1 of 1 entries (filtered from 8,332 total entries) Previous Next

- On the left side of the screen, select **Monitoring Schedules** for source monitoring schedule (last sample and next due dates) or **Monitoring Results** for water quality results.

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

Glossary

Contact Info

CA Drinking Water Watch

Water System Details

Water System No. : CA5403043	Federal Type : C
Water System Name : YETTEM WATER SYSTEM	State Type : C
Principal County Served : TULARE	Primary Source : GW
Status : A	Activity Date : 04-28-2014

Water System Contacts

Type	Address	Phone	Email - Web Address
Administrative Contact	5961 S. MOONEY BLVD. VISALIA, CA 93277	Business 559-624-7191	
Physical Location Contact	CA5403043-YETTEM WATER SYSTEM		

Division of Drinking Water District / County Health Dept. Info

Name	Phone	Email	Address
DISTRICT 24 - TULARE	559-447-3300	dwpsdist24@waterboards.ca.gov	265 W. BULLARD AVE., SUITE 101 FRESNO CA 93704

Annual Operating Periods & Population Served

Start Month	Start Day	End Month	End Day	Population Type	Population Served
1	1	12	31	R	350

Service Connections

Type	Count	Meter Type	Meter Size Measure
CB	64	UN	0

Sources of Water

Name	Type Code	Status
WELL 01 - PRE NO3 BLEND	WL	A
WELL 02 - PRE NO3 BLEND	WL	A

Service Areas

Code	Name
R	RESIDENTIAL AREA

Water Purchases

Seller Water System No.	Water System Name	Seller Facility Type	Seller State Asgn ID No.	Buyer Facility Type	Buyer State Asgn ID No.
-------------------------	-------------------	----------------------	--------------------------	---------------------	-------------------------

5. Select Sampling Point corresponding to the source (Link in blue text and is a number).

5A. Monitoring Schedules

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

[Glossary](#)

[Contact Info](#)

CA Drinking Water Watch

Monitoring Schedules

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

The Division of Drinking Water's (DDW's) drinking water quality monitoring schedules identify upcoming required testing of drinking water for water systems in California. These documents should not be used for determining whether water systems are in compliance with monitoring requirements. The purpose for providing these monitoring schedules is to allow water systems to verify that their sampling and analyses have been incorporated into the DDW database and to identify upcoming required monitoring/sampling events.

Notes for Water Systems:

1. The monitoring notification documents should be considered "draft," in that they will change with subsequent updates, and as monitoring data are submitted, or as monitoring schedules are revised.
2. The monitoring notification documents are derived from the DDW Water Quality database and from schedules maintained by DDW districts.
3. If your upcoming monitoring or your data identified as "DUE" are not in agreement with this document, or if you have been advised of any increased monitoring that is not reflected in the report for a particular source, please contact your [District Engineer or LPA representative](#). For a map of the districts, please [click here](#).
4. If your notification report for a source is blank, this does not necessarily indicate compliance with all monitoring requirements.
5. These notification reports may not reflect compliance with initial monitoring for newly regulated constituents, or constituents that require special monitoring frequencies. For example, the DDW database is unable to accurately forecast the vulnerable non-volatile synthetic organic chemical (SOC) frequency for large water systems serving over 3,300 people of 2 quarters every 3 years.
6. Some Nitrate (as N) results under storet code 00618, will have a result of 'N/A' which stands for 'Not Applicable.' This stems from the change in regulation requiring that all nitrate sampling be reported as Nitrate (as N) starting January 1, 2016. Prior nitrate sampling was reported as Nitrate (as NO3). With this change in nitrate reporting requirements, the monitoring schedules have captured the last date of Nitrate (as NO3) sampling and applied it to Nitrate (as N) in determining the next due date [unless there have been Nitrate (as N) samples collected]. The Nitrate (as NO3) result, however, does not carry over to Nitrate (as N) which is why there may be a notation in the 'Constituent Identification' column to reference storet code 71850 for the last nitrate result. In these instances, the 'Constituent Identification' column will say, 'NITRATE (as N) - [see 71850].' Any questions should be referred to your District Engineer.

[Monitoring Schedules for All Sampling Points](#)

Monitoring schedule for all sampling points

Click to view report. Once the report is shown, click on the Export icon on the report header to download.

Monitoring Schedule for Individual Sampling Points

Click on a sampling point number to view the monitoring schedule for the sampling point.
[Click here to bring back the list of sampling points.](#)

Sampling Point	Location	Type
900	ST2S1-14395 AVE 384	
LCR		DS
003	WELL 01 & 02 - NO3 BLEND TANK	
001	WELL 01 - PRE NO3 BLEND	RW
002	WELL 02 - PRE NO3 BLEND	RW

Monitoring schedule for specific sampling points

NOTE: Any *past due* monitoring will have "DUE NOW" in the far-right column. Please schedule this monitoring as soon as possible.

5B. Monitoring Results

Links
[Water System Details](#)
[Water System Facilities](#)
[Monitoring Schedules](#)
[Monitoring Results](#)
[Monitoring Results By Analyte](#)
[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)
[Site Visits](#)
[Consumer Confidence Reports](#)

- [2017](#)
- [2016](#)
- [2015](#)
- [2014](#)

Return Links
[Water System Search](#)
[County Map](#)
Glossary
Contact Info

CA Drinking Water Watch

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

Monitoring Results for Individual Sampling Points

Click on a PS Code to view/download the monitoring results for the sampling point.

Water System Sampling Points					
PS Code	Facility ID	Facility Name	Description	Type Code	Source Class
5403043-001	001	WELL 01 - PRE NO3 BLEND	WELL 01 - PRE NO3 BLEND	RW	DCSGA
5403043-002	002	WELL 02 - PRE NO3 BLEND	WELL 02 - PRE NO3 BLEND	RW	DCSGA
5403043-003	003	WELL 01 & 02 - NO3 BLEND TANK	WELL 01 & 02 - NO3 BLEND TANK		OTHR
5403043-900	DST	DISTRIBUTION SYSTEM	DISTRIBUTION SYSTEM		DBPT
5403043-LCR	DST	DISTRIBUTION SYSTEM		DS	

6. Please contact the Tulare District Office at (559) 447-3300 or DWPDIST24@waterboards.ca.gov if you have any questions.

Appendix E:
Lead and Copper Tap Sample Results Reporting Form



State Water Resources Control Board

Division of Drinking Water

Lead and Copper Tap Sample Results Reporting Form

This form must be submitted by the public water system to the regulating entity (DDW District Office or County Agency) for each round of lead and copper sampling

Report Date: (mm/dd/yyyy)	
Water System Name:	
Water System Number:	
Water System Type:	<input type="radio"/> Community <input type="radio"/> Non-Transient, Non Community
Monitoring Frequency:	<input type="radio"/> 6-month <input type="radio"/> Annual <input type="radio"/> Triennial
# of Samples Required:	
# of Samples Reported:	
	90th Percentile Level (mg/L)
Lead: <i>Action Level = 0.015 mg/L</i>	
Copper: <i>Action Level = 1.3 mg/L</i>	

	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Result	
				Lead (mg/L)	Copper (mg/L)
01					
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Sampling Site Change

Each round of sampling should be conducted at the same sampling sites. If an original sampling site is not available, you should collect a tap sample from another site meeting the same Tier criteria as the original site.

You must complete/submit the ***Lead and Copper Tap Sampling Site Change*** form.

Notification of Results

As required by *40 Code of Federal Regulations Section 141.85(d)*, within 30 days of learning of the tap monitoring results, I notified the participants, by mailing or by another method approved by the State, of the lead sample results from their individual taps, provided an explanation of the health effects of lead, listed steps the consumer could take to reduce exposure to lead, provided contact information for the water utility, the maximum contaminant level goal for lead, action level for lead, and any definitions.

Notification was done on _____ by ☐ Direct Mail
(date) ☐ Posting in public area (NTNC systems only)
☐ Other (please specify below) _____

For general information on lead and copper tap sampling, you can refer to the ***SWRCB Lead and Copper Tap Sample Results Guidance Document***. If you have any questions or comments, please contact your regulating entity (Division of Drinking Water District or County Agency).

SIGNATURE:	DATE:
NAME (Print):	TITLE:

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					

Appendix F:
Chlorination Treatment Operations Plan Template

DISCLAIMER: This document summarizes basic operational, maintenance and monitoring guidelines for chlorination systems serving small public water systems. The guidelines are directed toward chlorination of groundwater sources not subject to significant bacteriological contamination. Nothing in this document supersedes any statutory or regulatory requirements or permit provisions for public water systems. The information below is provided for general information only.

Operation of Continuous Chlorination System

- Operator Certification/Personnel – All persons responsible for the operation of the chlorination system must be reliable, trained and possess a State water operator's certificate of appropriate grade and type (Treatment and/or Distribution Operator). More than one operator should be assigned the responsibility of knowing the routine and emergency chlorination procedures.
- Targeted free chlorine residual – The targeted free chlorine residual range for most systems should be 0.2 mg/L to 1.0 mg/L within the distribution system. At no time should the level be over 4.0 mg/L at the first service connection after the chlorination system.
- Storage of chlorine solution – To minimize the decomposition of chlorine and the formation of chlorate and perchlorate, the following operational practices should be considered:
 - The chlorine solution should be stored in a cool, dry, well-ventilated area, away from direct sunlight and heat.
 - Dilute the stored chlorine solution to eight percent strength or less. Lower chlorine solution strength should be evaluated based on chemical pump performance, feed rate and desired chlorine residual.
 - Minimize storage time for both unopened containers and diluted solutions. Water systems should maintain approximately 30 days of chlorine supply onsite and cycle through diluted solutions at least once per month.
 - Avoid exposure of the chlorine solution to metal materials that might contain iron, copper, nickel and cobalt.
 - All chemicals or products, including chlorine, added directly to the drinking water as part of a treatment process must meet ANSI/NSF Standard 60.
- Inspecting and adjusting the equipment – Equipment should be inspected often enough to ensure prompt detection of problems. Daily inspection of the equipment is recommended. The required frequency of inspecting the equipment is set on a case-by-case basis depending on the system configuration, the consequences of an undetected failure and historical system reliability.

The inspection should consist of a visual inspection of the equipment, checking and filling the chlorine solution level, measuring the free chlorine residual, adjusting the equipment, calculating the dosage rate and writing down the results of the inspection. Any problems noted must be corrected.

- Responding to failures or interruptions – Each system should have a written procedure for responding to chlorination failures or interruptions. This procedure should include prompt repair or correction of the problem and restoration of the chlorine residual. The availability of a replacement or back-up chemical feed system should be addressed.
- Operation and inspection records – Operation and inspection records should be kept each day and should include the following as a minimum. The attached forms may be used to maintain records.
 - Date and time of inspection, name of operator.
 - Chlorine residual and location of residual measurements using the DPD method.
 - Production records.
 - Operational notes.
 - Chlorination failure log.
 - Maintenance performed (both preventative and unscheduled maintenance).

Maintenance of Continuous Chlorination Systems

- Chlorine solution tank – The chlorine solution tank should be emptied and cleaned at least once per year. More frequent cleaning may be necessary depending upon the source water used to prepare the diluted chlorine solution.
- Chlorine feed pump – Preventative maintenance of the chlorine feed pump, such as diaphragm or peristaltic pumps, should be performed in accordance with the manufacturer's specifications. All suction and discharge lines; foot valve and screen; injection valve; pump suction and discharge valves, seats and springs; and pump diaphragm should be replaced annually. Sufficient repair kits, spare parts and equipment for routine maintenance and repair should be kept on hand.
- Descaling – Injectors, diffusers and other components that come into contact with the chlorine solution should be descaled periodically by flushing with a weak acid solution.



Monitoring of Continuous Chlorination Systems

- Monitoring free chlorine residual - Free chlorine residual should be measured using the DPD method and recorded on a regular basis. Prior to sample analyses, the water system should verify that the sample vials are not stained or scratched and reagents are not expired. A pool test kit is **not** acceptable. Free chlorine residual should be measured before and/or after storage (if applicable), prior to the first service connection, and throughout the distribution system at sample sites that are representative of water served to the system. The required frequency of chlorine residual monitoring is set on a case-by-case basis depending on the system configuration. Daily measurement of the residual is recommended.



- Collecting a bacteriological sample – Whenever a bacteriological sample is collected for compliance, a chlorine residual should also be taken at the same time and location. The chlorine residual reading should be recorded on the chain of custody paperwork that comes with the water sample kit.
- Reporting – Operational records and chlorine residual results should be kept onsite for a minimum of three years and may be reviewed and/or submitted to the Division of Drinking Water upon request.

State Water Resources Control Board
Division of Drinking Water

Response to Failures and Interruptions for Chlorination Systems

System Name _____ System Number: _____

In the event the chlorination system is found to be not operating or injecting too little chlorine solution, the following plan of action will be taken to correct the problem or situation. The plan should address the availability of a spare chlorinator, manual feeding of chlorine until the problem is resolved, more frequent chlorine residual monitoring, etc.:

Short-term chlorinator interruption (i.e. less than one day):

Longer-term chlorine interruption (i.e. chlorinator cannot be repaired):

Prepared by: _____ Date: _____

Notes: This plan to be posted at the chlorination station.
This plan to be reviewed and updated annually

State Water Resources Control Board
Division of Drinking Water

Chlorination Operational Log

Month _____ Year _____

System Name _____ Number _____

Were there any malfunctions of the chlorination system this month? Yes _____ No _____

If yes, list the date the malfunction occurred and action taken. Problems that cannot be promptly corrected must be reported to the Division. Bacteriological sampling must be conducted if the safety of the water is in question:

Date	Time	Operator Initials	Free Chlorine Residual	Production Meter Reading	Gallons of Water Produced	Gallons of Chlorine Solution Used	Chlorine Dosage (mg/L)	Operational Notes
1								
2								
3								
4								
5								
6								
7								
8								
9								
10								
11								
12								
13								
14								
15								
16								
17								
18								
19								
20								
21								
22								
23								
24								
25								
26								
27								
28								
29								
30								
31								

This form should be kept on file for review by the Division.

Appendix G:
Connection Control Program Guidance

ELEMENTS OF A CROSS-CONNECTION CONTROL PROGRAM
SWRCB
Division of Drinking Water - Tulare District

When implementing a Cross-Connection Control Program, the water supplier or health agency should follow an organized plan. The following items should be included as a minimum. The items **explain the Division of Drinking Water's policy regarding the regulations.**

7584. Responsibility and Scope of Program

The water supplier shall protect the public water supply from contamination by implementation of a cross-connection control program. The program, or any portion thereof, may be implemented directly by the water supplier or by means of a contract with the local health agency, or with another agency approved by the health agency. The water supplier's cross-connection control program shall for the purpose of addressing the requirements of Sections 7585 through 7605 include, but not limited to, the following elements:

- (a) *The adoption of operating rules or ordinances to implement the cross-connection program.*

Adopting an ordinance or set of rules to implement the cross-connection control program. The ordinance or set of rules is important since it establishes the legal authority to carry out the program.

- (b) *The conducting of surveys to identify places where cross-connections are likely to occur.*

Water utilities do not have any responsibility for controlling or abating cross-connections on a user's premises. All existing facilities where potential cross-connections are suspected, however, shall be listed and inspected or re-inspected on a priority basis, where feasible. All applications for new services or for enlarging existing services or changing of occupant shall be reviewed or screened for cross-connections hazards. Surveys are intended to be conducted by a person certified by AWWA or ABPA as a cross-connection specialist. A list of persons that have this certification may be obtained by contacting AWWA at (909) 481-7200, ABPA at <http://www.abpa.org/>, or by contacting the Tulare District office.

- (c) *The provision of backflow protection at the user's connection or within the user's premises or both.*

Adequate provisions for implementation and enforcement of backflow protection where needed including the shutting off service when necessary.

- (d) *The provision of at least one person trained in cross-connection control to carry out the cross-connection program.*

Specific units of the health agency and/or water supplier should be designated to organize and carry out the cross-connection control program. The personnel in those units should be trained as to the causes and hazards of unprotected cross-connections.

- (e) *The establishment of a procedure or system for testing backflow preventers.*

A list of approved backflow preventers and list of certified testers should be made available to each water user required to provide backflow protection.

The list may include backflow devices approved by University of Southern California, Foundation for Cross-Connection Control and Hydraulic Research which may be found on the Division's website at the following address:

http://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/Publications.shtml

The list of certified cross connection specialist is available on the CA-NV American Water Works Association website:

https://ca-nv-awwa.org/canv/CNS/Professional_Certification/Cross_Connection_Specialist/CNS/Certification/CrossConnectionControlProgramSpecialists.aspx?hkey=5681f413-3a4a-4cc9-86fb-59c2cb1621a0

Backflow preventers should be tested at least yearly or more often as required by the health agency or water supplier.

(f) *The maintenance of records of locations, tests and repairs of backflow preventers*

Adequate records should be kept and filed for reference. These records should include, in addition to the name of the owner of the premises, the:

- a) Date of inspection
- b) Results of inspection
- c) Required protection
- d) List of all backflow preventer devices in the system
- e) Test and maintenance reports
- f) All correspondence between the water supplier, the local health authority, and the consumer
- g) Records must be maintained for a minimum of three years

Records of inspection and testing should be evaluated to determine if:

- a) Devices are frequently or sufficiently reviewed to detect failure.
- b) There are unusual feature of a particular model of device or component.
- c) Cause of failure can be eliminated.

A program should be established to notify the water user when his backflow preventer must be tested. A minimum of once each year is required. After installation or repair, a backflow preventer should be tested and approved before it is accepted.

7605. Testing and Maintenance of Backflow Preventers

Regulations require the following regarding testing and maintenance of backflow prevention devices:

- (a) The water supplier shall assure that adequate maintenance and periodic testing are provided by the water user to ensure their proper operation.
- (b) Backflow preventers shall be tested by persons who have demonstrated their competency in testing of these devices to the water supplier or health agency.
- (c) Backflow preventers shall be tested at least annually or more frequently if determined to be necessary by the health agency or water supplier. When devices are found to be defective, they shall be repaired or replaced in accordance with the provisions of this Chapter.
- (d) Backflow preventers shall be tested immediately after they are installed, relocated or repaired and not placed in service unless they are functioning as required.

- (e) The water supplier shall notify the water user when testing of backflow preventers is needed. The notice shall contain the date when the test must be completed.
- (f) Reports of testing and maintenance shall be maintained by the water supplier for a minimum of three years.

Appendix H:
Community Water System Emergency Response Plan – Template and
Instructions



Guidance for Small Community Water Systems on Risk and Resilience Assessments under America's Water Infrastructure Act

Who Should Use this Guidance?

- This guidance is intended for small community water systems (CWSs) serving greater than 3,300 but less than 50,000 people to comply with the requirements for **risk and resilience assessments** under *America's Water Infrastructure Act of 2018 (AWIA)*.
- For larger CWSs, EPA recommends the [Vulnerability Self-Assessment Tool](#) (VSAT) Web 2.0 or an alternate risk assessment method.
- CWSs serving 3,300 or fewer people are not required to conduct risk and resilience assessments under AWIA. EPA recommends, however, that very small CWSs use this or other guidance to learn how to conduct risk and resilience assessments and address threats from malevolent acts and natural hazards that threaten safe drinking water.

What is the Purpose of this Guidance?

- This guidance will help small CWSs meet the requirements for risk and resilience assessments in AWIA.
- This guidance does not address emergency response plans (ERPs), which are also required under AWIA for CWSs serving more than 3,300 people.
 - EPA has developed an [Emergency Response Plan Template and Instructions](#) for CWSs to comply with AWIA.
- Further, this guidance does not cover all aspects of water system security and resilience, such as asset management, climate change, and emergency preparedness and response. Visit EPA's [Drinking Water and Wastewater Resilience](#) page to find more information.

What are the Risk and Resilience Assessments Requirements in AWIA?

AWIA requires CWSs serving more than 3,300 people to assess the risks to and resilience of the system to malevolent acts and natural hazards. The law specifies water system assets (e.g., infrastructure) that the assessment must address. These assets are listed in Tables 1a – 10b in the *Risk and Resilience Assessment Checklist* (see fillable checklist below on page 4).

Water systems **must certify to EPA** that the system conducted the assessment not later than the following dates:

- March 31, 2020 for systems serving 100,000 or more
- December 31, 2020 for systems serving 50,000 or more but less than 100,000

- June 30, 2021 for systems serving more than 3,300 but less than 50,000

NOTE: Water systems do not submit the actual assessment to EPA. Visit EPA's informational page on [How to Certify Your Risk and Resilience Assessment or ERP](#) for instructions. Every five years, CWSs must review the risk and resilience assessment, revise it as needed, and provide a new certification to EPA.

What are Risk and Resilience in a Water System?

- **Risk** to critical infrastructure, including water systems, is a function of **threat likelihood**, **vulnerability**, and **consequence**.
 - **Threat** can be a malevolent act, like a cyberattack or process sabotage, or a natural hazard, such as a flood or hurricane.
 - **Threat likelihood** is the probability that a malevolent act will be carried out against the water system or that a natural hazard will occur.
 - **Vulnerability** is a weakness that can be exploited by an adversary or impacted by a natural hazard. It is the probability that if a malevolent act or a natural hazard occurred, then the water system would suffer significant adverse impacts.
 - **Consequences** are the magnitude of loss that would ensue if a threat had an adverse impact against a water system. Consequences may include:
 - Economic loss to the water system from damage to utility assets;
 - Economic loss to the utility service area from a service disruption, and
 - Severe illness or deaths that could result from water system contamination, a hazardous gas release, or other hazard involving the water system.
- **Resilience** is the capability of a water system to maintain operations or recover when a malevolent act or a natural hazard occurs.
- **Countermeasures** are steps that a water system implements to reduce risk and increase resilience. They may include plans, equipment, procedures, and other measures.

How does a Community Water System Assess Risk and Resilience Under AWIA?

Tables 1a – 10b in the *Risk and Resilience Assessment Checklist* (see fillable checklist below on page 4) list the categories of water system assets that you must assess under AWIA. In all tables (i.e., for all asset categories), do the following:

1. Select only the **malevolent acts** from those listed in the table that pose a significant risk to the asset category at the CWS. You may write-in malevolent acts not listed in the table.
 - a. Focus the selection of malevolent acts on those that are prevalent in the United States (e.g., cyber-attacks), can exploit vulnerabilities at the CWS (e.g., known security gaps), and have the potential for significant economic or public health consequences (e.g., contamination).

NOTE: EPA's [Baseline Information on Malevolent Acts Relevant to Community Water Systems](#) assists water systems with estimating the likelihood of these malevolent acts and provides resources for additional information.

2. For each malevolent act that you identify as a significant risk, briefly describe how the malevolent act could impact the asset category at the CWS. Include major assets that might be damaged or disabled, water service restrictions or loss, and public health impacts as applicable.
3. Select only the **natural hazards** from those listed in the table that may pose a significant risk to the asset category at the CWS. You may write-in natural hazards not listed in the table.
 - a. Focus the selection of natural hazards on those that are prevalent in the area where the water system is located, may affect vulnerable water system infrastructure, and have the potential for significant economic or public health consequences related to the CWS.
4. For each natural hazard that you identify as a significant risk, briefly describe or provide examples of how the hazard could impact the asset category at the CWS. Include major assets that might be damaged or disabled, water service restrictions or loss, and public health impacts as applicable.
5. **OPTIONAL Table 11 (*Risk and Resilience Assessment Checklist*, see below):** Identify **countermeasures** that the CWS could potentially implement to reduce risk from the malevolent acts and natural hazards that you selected in in this assessment.
 - a. For malevolent acts, countermeasures are intended to deter, delay, detect, and respond to an attack.
 - b. For natural hazards, countermeasures are intended to prepare, respond, and recover from an event.

NOTE: A single countermeasure, such as emergency response planning or power resilience, may reduce risk across multiple malevolent acts, natural hazards and asset categories.

Complete the *Risk and Resilience Assessment Checklist* here

EPA offers the *Risk and Resilience Assessment Checklist* in two formats. A fillable PDF format is provided on the pages that follow. This format has fixed fields and may not be changed by the user. Alternatively, a Word version may be accessed by clicking on the icon below. The Word version may be changed by the user. **The content of the PDF and Word versions is the same.** To access the Word version, the file must be downloaded to your computer.



Risk and Resilience Assessment Checklist

Community Water System Risk and Resilience Assessment

Enter Community Water System Name
Risk and Resilience Assessment

Please fill in the information below.

Facility Name (if applicable):

PWSID:

Analyst Name(s):

Date of Analysis:

Analysis Notes:

Table 1a: Physical Barriers (Malevolent Acts)¹

Asset Category: <i>Physical Barriers</i> Examples of Assets in this Category: Encompasses physical security in place at the CWS. Possible examples include fencing, bollards, and perimeter walls; gates and facility entrances; intrusion detection sensors and alarms; access control systems (e.g., locks, card reader systems); and hardened doors, security grilles, and equipment cages.	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Physical Barriers</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ²	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

¹In a risk assessment, physical barriers are usually treated as countermeasures, which reduce the risk of a threat to an asset, rather than being treated as assets. However, under AWIA, a CWS must assess the risks to and resilience of physical barriers.

²Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: Physical Barriers Examples of Assets in this Category: Encompasses physical security in place at the CWS. Possible examples include fencing, bollards, and perimeter walls; gates and facility entrances; intrusion detection sensors and alarms; access control systems (e.g., locks, card reader systems); and hardened doors, security grilles, and equipment cages.	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Physical Barriers</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ³	
<input type="checkbox"/> Other(s), enter below:	

³ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 1b: Physical Barriers (Natural Hazards)⁴

Asset Category: <i>Physical Barriers</i> Examples of Assets in this Category: Encompasses physical security in place at the CWS. Possible examples include fencing, bollards, and perimeter walls; gates and facility entrances; intrusion detection sensors and alarms; access control systems (e.g., locks, card reader systems); and hardened doors, security grilles, and equipment cages.	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Physical Barriers</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	
<input type="checkbox"/> Fire	

⁴In a risk assessment, physical barriers are usually treated as countermeasures, which reduce the risk of a threat to an asset, rather than analyzed as assets themselves. However, under AWIA, a CWS must assess the risks to and resilience of physical barriers.

Asset Category: *Physical Barriers*

Examples of Assets in this Category: Encompasses physical security in place at the CWS. Possible examples include fencing, bollards, and perimeter walls; gates and facility entrances; intrusion detection sensors and alarms; access control systems (e.g., locks, card reader systems); and hardened doors, security grilles, and equipment cages.

Natural Hazards

Select the natural hazards in the left column that pose a significant risk to this asset category at the CWS.

Brief Description of Impacts

If you select a natural hazard in the left column as a significant risk to the *Physical Barriers* asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.

☐ Other(s), enter below:

Table 2a: Source Water (Malevolent Acts)

Asset Category: Source Water Examples of Assets in this Category: Encompasses all sources that supply water to a water system. Possible examples include rivers, streams, lakes, source water reservoirs, groundwater, and purchased water.	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Source Water</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ⁵	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

⁵Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: Source Water Examples of Assets in this Category: Encompasses all sources that supply water to a water system. Possible examples include rivers, streams, lakes, source water reservoirs, groundwater, and purchased water.	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Source Water</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ⁶	
<input type="checkbox"/> Other(s), enter below:	

⁶ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 2b: Source Water (Natural Hazards)

Asset Category: Source Water Examples of Assets in this Category: Encompasses all sources that supply water to a water system. Possible examples include rivers, streams, lakes, source water reservoirs, groundwater, and purchased water.	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Source Water</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	
<input type="checkbox"/> Fire	

<p>Asset Category: <i>Source Water</i></p> <p>Examples of Assets in this Category: Encompasses all sources that supply water to a water system. Possible examples include rivers, streams, lakes, source water reservoirs, groundwater, and purchased water.</p>	
<p>Natural Hazards</p> <p>Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.</p>	<p>Brief Description of Impacts</p> <p>If you select a natural hazard in the left column as a significant risk to the <i>Source Water</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.</p>
<p><input type="checkbox"/> Other(s), enter below:</p>	

Table 3a: Pipes and Constructed Conveyances, Water Collection, and Intake (Malevolent Acts)

Asset Category: <i>Pipes and Constructed Conveyances, Water Collection, and Intake</i> Examples of Assets in this Category: Encompasses the infrastructure that collects and transports water from a source water to treatment or distribution facilities. Possible examples include holding facilities, intake structures and associated pumps and pipes, aqueducts, and other conveyances.	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Pipes and Constructed Conveyances, Water Collection, and Intake</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ⁷	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

⁷ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: *Pipes and Constructed Conveyances, Water Collection, and Intake*

Examples of Assets in this Category: Encompasses the infrastructure that collects and transports water from a source water to treatment or distribution facilities. Possible examples include holding facilities, intake structures and associated pumps and pipes, aqueducts, and other conveyances.

Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Pipes and Constructed Conveyances, Water Collection, and Intake</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ⁸	
<input type="checkbox"/> Other(s), enter below:	

⁸ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 3b: Pipes and Constructed Conveyances, Water Collection, and Intake (Natural Hazards)

Asset Category: <i>Pipes and Constructed Conveyances, Water Collection, and Intake</i> Examples of Assets in this Category: Encompasses the infrastructure that collects and transports water from a source water to treatment or distribution facilities. Possible examples include holding facilities, intake structures and associated pumps and pipes, aqueducts, and other conveyances.	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Pipes and Constructed Conveyances, Water Collection, and Intake</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	
<input type="checkbox"/> Fire	

Asset Category: *Pipes and Constructed Conveyances, Water Collection, and Intake*

Examples of Assets in this Category: Encompasses the infrastructure that collects and transports water from a source water to treatment or distribution facilities. Possible examples include holding facilities, intake structures and associated pumps and pipes, aqueducts, and other conveyances.

Natural Hazards

Select the natural hazards in the left column that pose a significant risk to this asset category at the CWS.

Brief Description of Impacts

If you select a natural hazard in the left column as a significant risk to the *Pipes and Constructed Conveyances, Water Collection, and Intake* asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.

☐ Other(s), enter below:

Table 4a: Pretreatment and Treatment (Malevolent Acts)

Asset Category: <i>Pretreatment and Treatment</i> Examples of Assets in this Category: Encompasses all unit processes that a water system uses to ensure water meets regulatory public health and aesthetic standards prior to distribution to customers. Possible examples include sedimentation, filtration, disinfection, and chemical treatment. For the risk assessment, individual treatment processes at a facility may be grouped together and analyzed as a single asset if they have a similar risk profile.	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Pretreatment and Treatment</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ⁹	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

⁹ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: Pretreatment and Treatment

Examples of Assets in this Category: Encompasses all unit processes that a water system uses to ensure water meets regulatory public health and aesthetic standards prior to distribution to customers. Possible examples include sedimentation, filtration, disinfection, and chemical treatment. For the risk assessment, individual treatment processes at a facility may be grouped together and analyzed as a single asset if they have a similar risk profile.

Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Pretreatment and Treatment</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ¹⁰	
<input type="checkbox"/> Other(s), enter below:	

¹⁰ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 4b: Pretreatment and Treatment (Natural Hazards)

Asset Category: Pretreatment and Treatment Examples of Assets in this Category: Encompasses all unit processes that a water system uses to ensure water meets regulatory public health and aesthetic standards prior to distribution to customers. Possible examples include sedimentation, filtration, disinfection, and chemical treatment. For the risk assessment, individual treatment processes at a facility may be grouped together and analyzed as a single asset if they have a similar risk profile.	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Pretreatment and Treatment</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	
<input type="checkbox"/> Fire	

Asset Category: *Pretreatment and Treatment*

Examples of Assets in this Category: Encompasses all unit processes that a water system uses to ensure water meets regulatory public health and aesthetic standards prior to distribution to customers. Possible examples include sedimentation, filtration, disinfection, and chemical treatment. For the risk assessment, individual treatment processes at a facility may be grouped together and analyzed as a single asset if they have a similar risk profile.

Natural Hazards

Select the natural hazards in the left column that pose a significant risk to this asset category at the CWS.

Brief Description of Impacts

If you select a natural hazard in the left column as a significant risk to the *Pretreatment and Treatment* asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.

☐ Other(s), enter below:

Table 5a: Storage and Distribution Facilities (Malevolent Acts)

Asset Category: Storage and Distribution Facilities Examples of Assets in this Category: Encompasses all infrastructure used to store water after treatment, maintain water quality, and distribute water to customers. Possible examples include residual disinfection, pumps, tanks, reservoirs, valves, pipes, and meters.	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Storage and Distribution Facilities</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ¹¹	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

¹¹ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: Storage and Distribution Facilities

Examples of Assets in this Category: Encompasses all infrastructure used to store water after treatment, maintain water quality, and distribute water to customers. Possible examples include residual disinfection, pumps, tanks, reservoirs, valves, pipes, and meters.

Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Storage and Distribution Facilities</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ¹²	
<input type="checkbox"/> Other(s), enter below:	

¹² Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 5b: Storage and Distribution Facilities (Natural Hazards)

Asset Category: Storage and Distribution Facilities Examples of Assets in this Category: Encompasses all infrastructure used to store water after treatment, maintain water quality, and distribute water to customers. Possible examples include residual disinfection, pumps, tanks, reservoirs, valves, pipes, and meters.	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Storage and Distribution Facilities</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	
<input type="checkbox"/> Fire	

Asset Category: *Storage and Distribution Facilities*

Examples of Assets in this Category: Encompasses all infrastructure used to store water after treatment, maintain water quality, and distribute water to customers. Possible examples include residual disinfection, pumps, tanks, reservoirs, valves, pipes, and meters.

Natural Hazards

Select the natural hazards in the left column that pose a significant risk to this asset category at the CWS.

Brief Description of Impacts

If you select a natural hazard in the left column as a significant risk to the *Storage and Distribution Facilities* asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.

☐ Other(s), enter below:

Table 6a: Electronic, Computer, or Other Automated Systems (including the security of such systems) (Malevolent Acts)

Asset Category: Electronic, Computer, or Other Automated Systems (including the security of such systems) Examples of Assets in this Category: Encompasses all treatment and distribution process control systems, business enterprise information technology (IT) and communications systems (other than financial), and the processes used to secure such systems. Possible examples include the sensors, controls, monitors and other interfaces, plus related IT hardware and software and communications, used to control water collection, treatment, and distribution. Also includes IT hardware, software, and communications used in business enterprise operations. The assessment must account for the security of these systems (e.g., cybersecurity, information security).	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Electronic, Computer, or Other Automated Systems (including the security of such systems)</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ¹³	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

¹³ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: *Electronic, Computer, or Other Automated Systems (including the security of such systems)*

Examples of Assets in this Category: Encompasses all treatment and distribution process control systems, business enterprise information technology (IT) and communications systems (other than financial), and the processes used to secure such systems. Possible examples include the sensors, controls, monitors and other interfaces, plus related IT hardware and software and communications, used to control water collection, treatment, and distribution. Also includes IT hardware, software, and communications used in business enterprise operations. The assessment must account for the security of these systems (e.g., cybersecurity, information security).

Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Electronic, Computer, or Other Automated Systems (including the security of such systems)</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ¹⁴	
<input type="checkbox"/> Other(s), enter below:	

¹⁴ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 6b: Electronic, Computer, or Other Automated Systems (including the security of such systems) (Natural Hazards)

Asset Category: <i>Electronic, Computer, or Other Automated Systems (including the security of such systems)</i> Examples of Assets in this Category: Encompasses all treatment and distribution process control systems, business enterprise information technology (IT) and communications systems (other than financial), and the processes used to secure such systems. Possible examples include the sensors, controls, monitors and other interfaces, plus related IT hardware and software and communications, used to control water collection, treatment, and distribution. Also includes IT hardware, software, and communications used in business enterprise operations. The assessment must account for the security of these systems (e.g., cybersecurity, information security).	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Electronic, Computer, or Other Automated Systems (including the security of such systems)</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	

Asset Category: *Electronic, Computer, or Other Automated Systems (including the security of such systems)*

Examples of Assets in this Category: Encompasses all treatment and distribution process control systems, business enterprise information technology (IT) and communications systems (other than financial), and the processes used to secure such systems. Possible examples include the sensors, controls, monitors and other interfaces, plus related IT hardware and software and communications, used to control water collection, treatment, and distribution. Also includes IT hardware, software, and communications used in business enterprise operations. The assessment must account for the security of these systems (e.g., cybersecurity, information security).

Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Electronic, Computer, or Other Automated Systems (including the security of such systems)</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Fire	
<input type="checkbox"/> Other(s), enter below:	

Table 7a: Monitoring Practices (Malevolent Acts)¹⁵

Asset Category: Monitoring Practices Examples of Assets in this Category: Encompasses the processes and practices used to monitor source water and finished water quality, along with any monitoring systems not captured in other asset categories. Possible examples include sensors, laboratory resources, sampling capabilities, and data management equipment and systems. Examples are contamination warning systems for the source water or distribution system.	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Monitoring Practices</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ¹⁶	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

¹⁵ Monitoring associated with physical security should be addressed under *Physical Barriers*; monitoring associated with process controls and cybersecurity should be addressed under *Electronic, Computer or Other Automated Systems*; monitoring associated with financial systems should be addressed under *Financial Infrastructure*.

¹⁶ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: Monitoring Practices

Examples of Assets in this Category: Encompasses the processes and practices used to monitor source water and finished water quality, along with any monitoring systems not captured in other asset categories. Possible examples include sensors, laboratory resources, sampling capabilities, and data management equipment and systems. Examples are contamination warning systems for the source water or distribution system.

Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Monitoring Practices</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ¹⁷	
<input type="checkbox"/> Other(s), enter below:	

¹⁷ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 7b: Monitoring Practices (Natural Hazards)¹⁸

Asset Category: Monitoring Practices Examples of Assets in this Category: Encompasses the processes and practices used to monitor source water and finished water quality, along with any monitoring systems not captured in other asset categories. Possible examples include sensors, laboratory resources, sampling capabilities, and data management equipment and systems. Examples are contamination warning systems for the source water or distribution system.	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Monitoring Practices</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	

¹⁸ Monitoring associated with physical security should be addressed under *Physical Barriers*; monitoring associated with process controls and cybersecurity should be addressed under *Electronic, Computer or Other Automated Systems*; monitoring associated with financial systems should be addressed under *Financial Infrastructure*.

Asset Category: Monitoring Practices

Examples of Assets in this Category: Encompasses the processes and practices used to monitor source water and finished water quality, along with any monitoring systems not captured in other asset categories. Possible examples include sensors, laboratory resources, sampling capabilities, and data management equipment and systems. Examples are contamination warning systems for the source water or distribution system.

Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Monitoring Practices</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Fire	
<input type="checkbox"/> Other(s), enter below:	

Table 8a: Financial Infrastructure (Malevolent Acts)

Asset Category: Financial Infrastructure Examples of Assets in this Category: Encompasses equipment and systems used to operate and manage utility finances. Possible examples include billing, payment, and accounting systems, along with third parties used for these services. This asset category is not intended to address the financial “health” of the water utility (e.g., credit rating, debt-to-equity ratios).	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Financial Infrastructure</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ¹⁹	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

¹⁹ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: Financial Infrastructure

Examples of Assets in this Category: Encompasses equipment and systems used to operate and manage utility finances. Possible examples include billing, payment, and accounting systems, along with third parties used for these services. This asset category is not intended to address the financial “health” of the water utility (e.g., credit rating, debt-to-equity ratios).

Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>Financial Infrastructure</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ²⁰	
<input type="checkbox"/> Other(s), enter below:	

²⁰ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 8b: Financial Infrastructure (Natural Hazards)

Asset Category: Financial Infrastructure Examples of Assets in this Category: Encompasses equipment and systems used to operate and manage utility finances. Possible examples include billing, payment, and accounting systems, along with third parties used for these services. This asset category is not intended to address the financial “health” of the water utility (e.g., credit rating, debt-to-equity ratios).	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>Financial Infrastructure</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	
<input type="checkbox"/> Fire	

Asset Category: *Financial Infrastructure*

Examples of Assets in this Category: Encompasses equipment and systems used to operate and manage utility finances. Possible examples include billing, payment, and accounting systems, along with third parties used for these services. This asset category is not intended to address the financial “health” of the water utility (e.g., credit rating, debt-to-equity ratios).

<p>Natural Hazards</p> <p>Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.</p>	<p>Brief Description of Impacts</p> <p>If you select a natural hazard in the left column as a significant risk to the <i>Financial Infrastructure</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.</p>
<p><input type="checkbox"/> Other(s), enter below:</p>	

Table 9a: The Use, Storage, or Handling of Chemicals (Malevolent Acts)

Asset Category: <i>The Use, Storage, or Handling of Chemicals</i> Examples of Assets in this Category: Encompasses the chemicals and associated storage facilities and handling practices used for chemical disinfection and treatment. Assessments under this asset category should focus on the risk of uncontrolled release of a potentially dangerous chemical like chlorine where applicable.	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>The Use, Storage, or Handling of Chemicals</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ²¹	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

²¹ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: *The Use, Storage, or Handling of Chemicals*

Examples of Assets in this Category: Encompasses the chemicals and associated storage facilities and handling practices used for chemical disinfection and treatment. Assessments under this asset category should focus on the risk of uncontrolled release of a potentially dangerous chemical like chlorine where applicable.

Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>The Use, Storage, or Handling of Chemicals</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ²²	
<input type="checkbox"/> Other(s), enter below:	

²² Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 9b: The Use, Storage, or Handling of Chemicals (Natural Hazards)

Asset Category: <i>The Use, Storage, or Handling of Chemicals</i> Examples of Assets in this Category: Encompasses the chemicals and associated storage facilities and handling practices used for chemical disinfection and treatment. Assessments under this asset category should focus on the risk of uncontrolled release of a potentially dangerous chemical like chlorine where applicable.	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>The Use, Storage, or Handling of Chemicals</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	
<input type="checkbox"/> Fire	

Asset Category: *The Use, Storage, or Handling of Chemicals*

Examples of Assets in this Category: Encompasses the chemicals and associated storage facilities and handling practices used for chemical disinfection and treatment. Assessments under this asset category should focus on the risk of uncontrolled release of a potentially dangerous chemical like chlorine where applicable.

Natural Hazards

Select the natural hazards in the left column that pose a significant risk to this asset category at the CWS.

Brief Description of Impacts

If you select a natural hazard in the left column as a significant risk to the *The Use, Storage, or Handling of Chemicals* asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.

☐ Other(s), enter below:

Table 10a: The Operation and Maintenance of the System (Malevolent Acts)

Asset Category: <i>The Operation and Maintenance of the System</i> Examples of Assets in this Category: Encompasses critical processes required for operation and maintenance of the water system that are not captured under other asset categories. Possible examples include equipment, supplies, and key personnel. Assessments may focus on the risk to operations associated with dependency threats like loss of utilities (e.g., power outage), loss of suppliers (e.g., interruption in chemical delivery), and loss of key employees (e.g., disease outbreak or employee displacement).	
Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>The Operation and Maintenance of the System</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Assault on Utility – Physical	
<input type="checkbox"/> Contamination of Finished Water – Intentional	
<input type="checkbox"/> Contamination of Finished Water – Accidental ²³	
<input type="checkbox"/> Theft or Diversion – Physical	
<input type="checkbox"/> Cyberattack on Business Enterprise Systems	

²³ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Asset Category: *The Operation and Maintenance of the System*

Examples of Assets in this Category: Encompasses critical processes required for operation and maintenance of the water system that are not captured under other asset categories. Possible examples include equipment, supplies, and key personnel. Assessments may focus on the risk to operations associated with dependency threats like loss of utilities (e.g., power outage), loss of suppliers (e.g., interruption in chemical delivery), and loss of key employees (e.g., disease outbreak or employee displacement).

Malevolent Acts Select the malevolent acts in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a malevolent act in the left column as a significant risk to the <i>The Operation and Maintenance of the System</i> asset category, briefly describe in the right column how the malevolent act could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Cyberattack on Process Control Systems	
<input type="checkbox"/> Sabotage – Physical	
<input type="checkbox"/> Contamination of Source Water – Intentional	
<input type="checkbox"/> Contamination of Source Water – Accidental ²⁴	
<input type="checkbox"/> Other(s), enter below:	

²⁴ Accidental contamination is not a malevolent act. It is included here due to similar potential consequences and because whether a contamination incident is intentional or accidental may not be known during initial response.

Table 10b: The Operation and Maintenance of the System (Natural Hazards)

Asset Category: <i>The Operation and Maintenance of the System</i> Examples of Assets in this Category: Encompasses critical processes required for operation and maintenance of the water system that are not captured under other asset categories. Possible examples include equipment, supplies, and key personnel. Assessments may focus on the risk to operations associated with dependency threats like loss of utilities (e.g., power outage), loss of suppliers (e.g., interruption in chemical delivery), and loss of key employees (e.g., disease outbreak or employee displacement).	
Natural Hazards Select the natural hazards in the left column that pose a <u>significant risk</u> to this asset category at the CWS.	Brief Description of Impacts If you select a natural hazard in the left column as a significant risk to the <i>The Operation and Maintenance of the System</i> asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.
<input type="checkbox"/> Hurricane	
<input type="checkbox"/> Flood	
<input type="checkbox"/> Earthquake	
<input type="checkbox"/> Tornado	
<input type="checkbox"/> Ice storm	
<input type="checkbox"/> Fire	

Asset Category: *The Operation and Maintenance of the System*

Examples of Assets in this Category: Encompasses critical processes required for operation and maintenance of the water system that are not captured under other asset categories. Possible examples include equipment, supplies, and key personnel. Assessments may focus on the risk to operations associated with dependency threats like loss of utilities (e.g., power outage), loss of suppliers (e.g., interruption in chemical delivery), and loss of key employees (e.g., disease outbreak or employee displacement).

Natural Hazards

Select the natural hazards in the left column that pose a significant risk to this asset category at the CWS.

Brief Description of Impacts

If you select a natural hazard in the left column as a significant risk to the *The Operation and Maintenance of the System* asset category, briefly describe in the right column how the natural hazard could impact this asset category at the CWS. Include effects on major assets, water service, and public health as applicable.

☐ Other(s), enter below:

Table 11: Countermeasures (Optional)²⁵

Countermeasures (optional) List countermeasures in the left column the CWS could potentially implement to reduce risk from the malevolent acts and natural hazards that were selected.	Brief Description of Risk Reduction or Increased Resilience For each countermeasure, in the right column, describe how the countermeasure could reduce risk or increase resilience for CWS assets from malevolent acts or natural hazards that were selected in the analysis. A countermeasure may reduce risk across multiple malevolent acts, natural hazards and asset categories.
1.	
2.	
3.	
4.	
5.	

²⁵ **IMPORTANT NOTE:** The assessment does not require a specific number of countermeasures. You may have fewer than five countermeasures or add more countermeasures and describe them in a separate document.

Change History

Please describe the changes made to this risk and resilience assessment since its original development, who made the changes, and on what date the changes were incorporated.

Name/Title:	Date:	Description of Change:

Appendix I:
Emergency Notification Plan Template

State Water Resources Control Board

System No. _____

DIVISION OF DRINKING WATER – TULARE DISTRICT WATER QUALITY EMERGENCY NOTIFICATION PLAN

Water System Name: _____

Physical Location Address: _____

The following persons have been designated to implement the Plan upon notification by the Division of Drinking Water that an imminent danger to the health of the water users exists:

Contact Name & Title	Email Address	Home/Office	Cell
1. _____			
2. _____			
3. _____			

The implementation of the plan will be carried out with the following Division of Drinking Water and County Health personnel:

Contact Name & Title	Email Address	Office	Cell
1. Kristin Willet, Tulare District Engineer Division of Drinking Water	kristin.willet@waterboards.ca.gov	(559) 447-3300	(559) 280-6363
2. Tricia Wathen, Supervising Sanitary Engineer Division of Drinking Water	tricia.wathen@waterboards.ca.gov	(559) 447-3300	(559) 696-8506
3. Nilsa Gonzalez, Director Tulare County Environmental Health Division Manager	ngonzale@tularehhsa.org	(559) 624-7400	(559) 285-2440
4. If the above personnel cannot be reached, contact:			

Office of Emergency Services (24 Hrs.) (800) 852-7550 or (916) 845-8911
Ask for "Division of Drinking of Drinking Water, Duty Officer"

NOTIFICATION PLAN

Community and Nontransient Noncommunity

(Must identify three methods)

- ☐ Door to Door Delivery ☐ Posted Notification
☐ Social Media ☐ Reverse 911/Telephone
☐ News Media (TV, Radio, Newspaper) ☐ Email
☐ Other: personal phone call _____

Transient Noncommunity

☐ Water system must post notification. Hand delivered notification must be provided to any residential/overnight customers.

***SYSTEMS SERVING MORE THAN 200 SERVICE CONNECTIONS MUST PROVIDE A CUSTOM PLAN.**

APPROXIMATE TIME TO ISSUE NOTICE: _____ HRS

Report prepared by:

Signature and Title

Date

Appendix C: CPUD Compliance Orders

State Water Resources Control Board

Division of Drinking Water

August 26, 2022

System No. 5410001

Dionicio Rodriguez, Superintendent
Cutler Public Utility District
40526 Orosi Drive
Cutler, CA 93615

COMPLIANCE ORDER NO. 03-24-22R-007 **1,2,3-TRICHLOROPROPANE (1,2,3-TCP) MAXIMUM CONTAMINANT LEVEL VIOLATION**

Enclosed is Compliance Order No. 03-24-22R-007 (hereinafter "Order") issued to the Cutler Public Utility District (hereinafter "Water System") public water system. **Please note there are legally enforceable deadlines associated with this Order starting on page 4 of the Order.**

The Water System will be billed at the State Water Resources Control Board's (hereinafter "State Water Board") hourly rate for the time spent on issuing this Order. California Health and Safety Code (hereinafter "CHSC"), Section 116577, provides that a public water system must reimburse the State Water Board for actual costs incurred by the State Water Board for specified enforcement actions, including but not limited to, preparing, issuing and monitoring compliance with an order. At this time, the State Water Board has spent approximately 1.0 hour on enforcement activities associated with this violation.

The Water System will receive a bill sent from the State Water Board in August of the next fiscal year. This bill will contain fees for any enforcement time spent on the Water System for the current fiscal year.

Any person who is aggrieved by a citation, order or decision issued under authority delegated to an officer or employee of the state board under Article 8 (commencing with CHSC, Section 116625) or Article 9 (commencing with CHSC, Section 116650), of the Safe Drinking Water Act (CHSC, Division 104, Part 12, Chapter 4), may file a petition with the State Water Board for reconsideration of the citation, order or decision.

Petitions must be received by the State Water Board within 30 days of the issuance of the citation, order or decision by the officer or employee of the state board. The date of issuance is the date when the Division of Drinking Water mails a copy of the citation, order or decision.

Information regarding filing petitions may be found at:

http://www.waterboards.ca.gov/drinking_water/programs/petitions/index.shtml

If you have any questions regarding this matter, please contact Tulare District staff at (559) 447-3300 or by email at dwpdist24@waterboards.ca.gov.

Sincerely,

Kristin Willet  Digitally signed by Kristin Willet
Date: 2022.08.25 08:27:48 -07'00'

Kristin Willet, P.E.
Senior Water Resources Control Engineer, Tulare District
SOUTHERN CALIFORNIA BRANCH
DRINKING WATER FIELD OPERATIONS

Certified Mail No. 7022 0410 0002 3469 5380

cc: Tulare County Environmental Health Department
Nilsa Gonzalez
NGonzale@tularecounty.ca.gov

03_24_22R_007_5410001

2

3 STATE OF CALIFORNIA

4 STATE WATER RESOURCES CONTROL BOARD

5 DIVISION OF DRINKING WATER

6

7 **Name of Public Water System:** Cutler Public Utility District

8 **Water System No:** 5410001

9

10 **Attention:** Dionicio Rodriguez, Superintendent

11 Cutler Public Utility District

12 40526 Orosi Drive

13 Cutler, CA 93615

14

15 **Issued:** August 26, 2022

16

17 **COMPLIANCE ORDER FOR NONCOMPLIANCE**

18 **1,2,3-TCP MAXIMUM CONTAMINANT LEVEL VIOLATION**

19 **CALIFORNIA CODE OF REGULATIONS, TITLE 22, SECTION 64444**

20 **3rd Quarter 2022**

21

22 The California Health and Safety Code (hereinafter "CHSC"), Section 116655

23 authorizes the State Water Resources Control Board (hereinafter "State Water Board")

24 to issue a compliance order to a public water system when the State Water Board

25 determines that the public water system has violated or is violating the California Safe

26 Drinking Water Act (hereinafter "California SDWA"), (CHSC, Division 104, Part 12,

27 Chapter 4, commencing with Section 116270), or any regulation, standard, permit, or

28 order issued or adopted thereunder.

29

The State Water Board, acting by and through its Division of Drinking Water (hereinafter “Division”) and the Deputy Director for the Division, hereby issues Compliance Order No. 03-24-22R-007 (hereinafter “Order”) pursuant to Section 116655 of the CHSC to the Cutler Public Utility District (hereinafter “Water System”) for violation of CHSC, Section 116555(a)(1) and California Code of Regulations (hereinafter “CCR”), Title 22, Section 64444 Maximum Contaminant Levels (hereinafter “MCL”) – Organic Chemicals.

STATEMENT OF FACTS

The Water System is classified as a community public water system with a population of 6,200 persons served through 1,218 service connections. The Cutler Public Utility District operates under Domestic Water Supply Permit Amendment No. 03-12-09PA-006 issued by the State Water Board on June 30, 2009.

CHSC, Section 116555(a)(1) requires all public water systems to comply with primary drinking water standards as defined in CHSC, Section 116275(c). Primary drinking water standards include maximum levels of contaminants and the monitoring and reporting requirements as specified in regulations adopted by the State Water Board that pertain to maximum contaminant levels.

The State Water Board received 7 laboratory results for 1,2,3-TCP samples from Well 05 collected between January 2022 and July 2022. The running annual average 1,2,3-TCP level of the samples from Well 05 is 0.0000055 mg/L. A summary of the Water System’s 1,2,3-TCP monitoring results from Well 05 is presented in Table 1 below:

Table 1. Well 05 1,2,3-TCP Sample Results (mg/L)

(1,2,3-TCP MCL is 0.000005 mg/L)		
Compliance Period	Sample Date	Result
1st Quarter 2022	1/14/2022	0.000006
1st Quarter 2022	2/9/2022	0.000005
1st Quarter 2022	3/9/2022	0.000006
2nd Quarter 2022	4/8/2022	0.000006
2nd Quarter 2022	5/18/2022	0.000005
2nd Quarter 2022	6/22/2022	0.000006
3rd Quarter 2022	7/29/2022	0.000007
Running Annual Average (RAA)		0.00000585

* If any one sample or average of samples would cause the four quarter average (annual average) to exceed the MCL, the water system is immediately in violation.

DETERMINATION

CCR, Title 22, Section 64444, Maximum Contaminant Levels – Organic Chemicals states that public water systems shall comply with the primary MCLs established in table 64444-A. The MCL for 1,2,3-TCP is 0.000005 mg/L.

CCR, Title 22, Section 64445.1(c)(5)(C) Repeat Monitoring and Compliance – Organic Chemicals states that if any sample would cause the running annual average to exceed the MCL, the water system is immediately in violation. If a system takes more than one sample in a quarter, the average of all the results for that quarter shall be used when calculating the running annual average. If a system fails to complete four consecutive quarters of monitoring, the running annual average shall be based on an average of the available data.

The 1,2,3-TCP RAA from Well 05 is 0.000006 mg/L. Therefore, the State Water Board has determined that the Water System has failed to comply with primary drinking water standards pursuant to CHSC, Section 116555(a)(1) and the 1,2,3-TCP MCL pursuant to CCR, Title 22, Section 64444 during the 3rd Quarter 2022.

DIRECTIVES

To ensure that the water supplied by the Water System is at all times safe, wholesome, healthful, and potable, the Water System is hereby directed to take the following actions:

1. On or before **August 29, 2025**, comply with CCR, Title 22, Section 64444.
2. Quarterly sampling for 1,2,3-TCP from Well 05 shall continue with the **4th Quarter 2022** and shall continue every three months thereafter. The Water System shall ensure that the laboratory, which conducts the analysis, submits the analytical results electronically by State Water Board approved method no later than the 10th day following the month in which the analysis was completed.
3. By **October 10, 2022**, public notification to the customers of the Water System shall be conducted and shall continue every three months until the State Water Board determines that the 1,2,3-TCP contamination is resolved. Public Notification shall be conducted in conformance with CCR, Title 22, Sections 64463.4 and 64465. Appendix 1: Notification Template shall be used to fulfill this directive, unless otherwise approved by the State Water Board.
4. Complete Appendix 2: Certification of Completion of Notification Form. Submit it together with a copy of the public notification conducted in compliance with the

public notification requirement listed above to the State Water Board within 10 days following each notification.

5. Prepare for State Water Board approval, a Corrective Action Plan, identifying improvements to the water system designed to correct the water quality problems identified as an exceedance of the 1,2,3-TCP MCL and ensure that the Water System delivers water to consumers that meets primary drinking water standards. The plan shall include a time schedule for completion of each of the phases of the project such as design, construction, and startup, and a date as of which the Water System will be in compliance with the 1,2,3-TCP MCL, which date shall be no later than **August 29, 2025**.

6. On or before **November 1, 2022**, present in person or via a virtual meeting the Corrective Action Plan required under Directive No. 5 above, to the State Water Board's office located at:

SWRCB – Division of Drinking Water
265 W. Bullard Ave, Suite 101
Fresno, CA 93704

7. Perform the State Water Board approved Corrective Action Plan, and each and every element of said plan, according to the time schedule set forth therein.
8. On or before **January 10, 2023**, and every three months thereafter, submit a report to the State Water Board in the form provided as Appendix 3 showing actions taken during the previous quarter (calendar three months) to comply with the Corrective Action Plan.

9. Not later than ten (10) days following **August 29, 2025**, demonstrate to the State Water Board that the water delivered by the Water System complies with the 1,2,3-TCP MCL.

10. Notify the State Water Board in writing no later than five (5) days prior to the deadline for performance of any Directive set forth herein if the Water System anticipates it will not timely meet such performance deadline.

11. By **September 30, 2022**, complete and return to the State Water Board the "Notification of Receipt" form attached to this Order as Appendix 4. Completion of this form confirms that the Water System has received this Order and understands that it contains legally enforceable directives with due dates.

All submittals, with exception of analytical results, required by this Order shall be electronically submitted to the State Water Board at the following address. The subject line for all electronic submittals corresponding to this Order shall include the following information: Water System name and number, compliance order number and title of the document being submitted.

Kristin Willet, P.E.

dwpdist24@waterboards.ca.gov

The State Water Board reserves the right to make modifications to this Order as it may deem necessary to protect public health and safety. Such modifications may be issued as amendments to this Order and shall be effective upon issuance.

Nothing in this Order relieves the Water System of its obligation to meet the requirements of the California SDWA (CHSC, Division 104, Part 12, Chapter 4,

commencing with Section 116270), or any regulation, standard, permit or order issued or adopted thereunder.

PARTIES BOUND

This Order shall apply to and be binding upon the Water System, its owners, shareholders, officers, directors, agents, employees, contractors, successors, and assignees.

SEVERABILITY

The directives of this Order are severable, and the Water System shall comply with each and every provision thereof notwithstanding the effectiveness of any provision.

FURTHER ENFORCEMENT ACTION

The California SDWA authorizes the State Water Board to: issue a citation or order with assessment of administrative penalties to a public water system for violation or continued violation of the requirements of the California SDWA or any regulation, permit, standard, citation, or order issued or adopted thereunder including, but not limited to, failure to correct a violation identified in a citation or compliance order. The California SDWA also authorizes the State Water Board to take action to suspend or revoke a permit that has been issued to a public water system if the public water system has violated applicable law or regulations or has failed to comply with an order of the State Water Board, and to petition the superior court to take various enforcement measures against a public water system that has failed to comply with an order of the State Water Board. The State Water Board does not waive any further enforcement action by issuance of this Order.

Tricia A. Wathen



Digitally signed by Tricia A. Wathen
Date: 2022.08.24 16:53:52 -07'00'

Tricia Wathen, P.E., Chief
Central California Section
State Water Resources Control Board
Division of Drinking Water

Date

Appendices (4):

1. Notification Template
2. Certification of Completion of Public Notification
3. Quarterly Progress Report
4. Notification of Receipt

Certified Mail No. 7022 0410 0002 3469 5380

APPENDIX 1. NOTIFICATION TEMPLATE

IMPORTANT INFORMATION ABOUT YOUR DRINKING WATER

Este informe contiene información muy importante sobre su agua potable.
Por favor hable con alguien que lo pueda traducir.

Cutler Public Utility District Has levels of 1,2,3-TCP Above Drinking Water Standards

Our water system recently failed a drinking water standard. Although this is not an emergency, as our customers, you have a right to know what you should do, what happened, and what we are doing to correct this situation.

We routinely monitor for the presence of drinking water contaminants. Testing results we received on _____ [Insert date(s) or month, year] show that our system exceeds the standard, or maximum contaminant level (MCL), for 1,2,3-trichloropropane (1,2,3-TCP). The standard for 1,2,3-TCP is 0.005 ug/L (micrograms per liter). The average level of 1,2,3-TCP over the last year was _____ ug/L.

What should I do?

- You **do not** need to use an alternative (e.g. , bottled) water supply.
- This is not an immediate risk. If it had been, you would have been notified immediately. However, *some people who drink water containing 1,2,3-trichloropropane in excess of the MCL over many years may have an increased risk of getting cancer.*
- If you have other health issues concerning the consumption of this water, you may wish to consult your doctor.

What happened? What is being done?

What happened? What is being done?

[Describe corrective action]

We anticipate resolving the problem within [estimated time frame] _____.

For more information, please contact:

[Name of Contact] _____

[Phone Number] or _____

[Mailing Address] _____

Please share this information with all the other people who drink this water, especially those who may not have received this notice directly (for example, people in apartments, nursing homes, schools, and businesses). You can do this by posting this public notice in a public place or distributing copies by hand or mail.

Secondary Notification Requirements

Upon receipt of notification from a person operating a public water system, the following notification must be given within 10 days [Health and Safety Code Section 116450(g)]:

- SCHOOLS: Must notify school employees, students, and parents (if the students are minors).

- RESIDENTIAL RENTAL PROPERTY OWNERS OR MANAGERS (including nursing homes and care facilities): Must notify tenants.
- BUSINESS PROPERTY OWNERS, MANAGERS, OR OPERATORS: Must notify employees of businesses located on the property.

This notice is being sent to you by [Cutler Public Utility District](#) in compliance with the California Domestic Water Quality and Monitoring Regulations as a means of keeping the public informed.

State Water System ID: [5410001](#).

Date distributed: _____

APPENDIX 2.
CERTIFICATION OF COMPLETION OF PUBLIC NOTIFICATION

Compliance Order Number: 03-24-22R-007

Name of Water System: Cutler Public Utility District

System Number: 5410001

Attach a copy of the public notice distributed to the water system's customers.

This form, when completed and sent to dwpdist24@waterboards.ca.gov for the Division of Drinking Water, Tulare District, 265 W. Bullard Avenue, Suite 101, Fresno, CA 93704 serves as certification that public notification to water users was completed as required by Title 22, California Code of Regulations, Sections 64463-64465.

Public notification for failure to comply with the **1,2,3-TCP MCL** was conducted on:

Notification was made on _____ (date).

For the _____ [Insert month or quarter and year].

To summarize report delivery used and good-faith efforts taken, please check all items below that apply and fill-in where appropriate:

For Community and non-transient non-community public water systems

☐ The notice was distributed by mail or direct delivery to each customer on: _____

One or more of the following methods were used to reach persons not likely to be reached by a mailing or direct delivery or persons served by a transient public water system (renters, nursing home patients, prison inmates, etc.):

☐ Posted the notice at the following conspicuous locations served by the water system. (If needed, please attach a list of locations). _____

☐ Publication of the notice in a local newspaper or newsletter of general circulation (attach a copy of the published notice, including name of newspaper and date published).

☐ Posted the notice on the Internet at www._____

☐ Other method used to notify customers. _____

I hereby certify that the above information is factual.

Certified by: Printed Name _____ Title _____

Signature _____

Date _____

Disclosure: Be advised that the California Health and Safety Code, Sections 116725 and 116730 state that any person who knowingly makes any false statement on any report or

document submitted for the purpose of compliance with the Safe Drinking Water Act may be liable for, respectively, a civil penalty not to exceed five thousand dollars (\$5,000) for each separate violation or, for continuing violations, for each day that violation continues, or be punished by a fine of not more than \$25,000 for each day of violation, or by imprisonment in the county jail not to exceed one year, or by both the fine and imprisonment

APPENDIX 3. QUARTERLY PROGRESS REPORT

Water System: Cutler Public Utility District	Water System No: 5410001
Compliance Order No: 03-24-22R-007	Violation: 1,2,3-TCP MCL
Calendar Quarter:	Date:

This form should be prepared and signed by Water System personnel with appropriate authority to implement the directives of the Compliance Order and the Corrective Action Plan. Please attach additional sheets as necessary. The quarterly progress report must be submitted by the 10th day of each subsequent quarter, to the Division of Drinking Water, Tulare District Office to the following email address: dwpdist24@waterboards.ca.gov titled appropriately.

Summary of Compliance Plan:

--

Tasks completed in the reporting quarter:

--

Tasks remaining to complete:

--

Anticipated compliance date:

--

Printed Name

Signature

Title

Date

APPENDIX 4. NOTIFICATION OF RECEIPT

Compliance Order Number: 03-24-22R-007

Name of Water System: Cutler Public Utility District

System Number: 5410001

Certification

I certify that I am an authorized representative of the Cutler Public Utility District and that Compliance Order No. **03-24-22R-007** was received on _____. Further I certify that the Order has been reviewed by the appropriate management staff of the Cutler Public Utility District and it is clearly understood that Compliance Order No. **03-24-22R-007** contains legally enforceable directives with specific due dates.

Signature of Water System Representative

Date

**THIS FORM MUST BE COMPLETED AND RETURNED TO THE STATE WATER BOARD,
DIVISION OF DRINKING WATER, NO LATER THAN SEPTEMBER 30, 2022.**

Disclosure: Be advised that the California Health and Safety Code, Sections 116725 and 116730 state that any person who knowingly makes any false statement on any report or document submitted for the purpose of compliance with the Safe Drinking Water Act may be liable for, respectively, a civil penalty not to exceed five thousand dollars (\$5,000) for each separate violation or, for continuing violations, for each day that violation continues, or be punished by a fine of not more than \$25,000 for each day of violation, or by imprisonment in the county jail not to exceed one year, or by both the fine and imprisonment.



State Water Resources Control Board

Division of Drinking Water

September 21, 2023

System No. CA5410001

Dionicio Rodriguez, Superintendent
Cutler Public Utility District
40526 Orosi Drive
Cutler, CA 93615

COMPLIANCE ORDER NO. 03-24-23R-006 NITRATE MAXIMUM CONTAMINANT LEVEL VIOLATION FOR THIRD QUARTER 2023

Enclosed is Compliance Order No. 03-24-23R-006 (hereinafter "Order"), issued to the Cutler Public Utility District (hereinafter "Water System") public water system. Please note that there are legally enforceable deadlines associated with this Order.

The Water System will be billed at the State Water Resources Control Board's (hereinafter "State Water Board") hourly rate for the time spent on issuing this Order. California Health and Safety Code (hereinafter "CHSC") Section 116577 provides that a public water system must reimburse the State Water Board for actual costs incurred by the State Water Board for specified enforcement actions, including preparing, issuing and monitoring compliance with an order. The Water System will receive a bill sent from the State Water Board in August of the next fiscal year. This bill will contain fees for any enforcement time spent on the Water System for the current fiscal year.

A process exists by which a public water system can petition the State Water Board for reconsideration of this compliance order. Petitions sent to the State Water Board "shall include the name and address of the petitioner, a copy of the order or decision for which the petitioner seeks reconsideration, identification of the reason the petitioner alleges the issuance of the order or decision was inappropriate or improper, the specific action the petitioner requests, and other information as the state board may prescribe. The petition shall be accompanied by a

E. JOAQUIN ESQUIVEL, CHAIR | EILEEN SOBECK, EXECUTIVE DIRECTOR

265 West Bullard Avenue, Suite 101, Fresno, CA 93704 | www.waterboards.ca.gov

statement of points and authorities of the legal issues raised by the petition.” (Health & Saf. Code, § 116701, subd. (b).)

Petitions must be received by the State Water Board within 30 days of the issuance of this compliance order by the State Water Board. If the 30th day falls on a Saturday, Sunday, or state holiday, the petition is due the following business day by 5:00 p.m. Information regarding filing petitions may be found at:

[Drinking Water Petitions for Reconsideration](https://www.waterboards.ca.gov/drinking_water/programs/petitions/instructions.html)

https://www.waterboards.ca.gov/drinking_water/programs/petitions/instructions.html

If you have any questions regarding this matter, please contact Tulare District staff at (559) 447-3300 or by email at dwpdist24@waterboards.ca.gov.

Sincerely,

Kristin Willet  Digitally signed by Kristin Willet
Date: 2023.09.21 11:18:31 -07'00'

Kristin Willet, P.E.
Senior Water Resource Control Engineer, Tulare District
SOUTHERN CALIFORNIA BRANCH
DRINKING WATER FIELD OPERATIONS

Enclosures

Certified Mail No. 7022-0410-0002-3469-6578

cc: [all email only]

Tulare County Environmental Health Division

NGonzale@tularecounty.ca.gov

SCarranz@tularecounty.ca.gov

Dennis Keller

kelweg1@aol.com

03_24_23R_006_5410001_01

Compliance Order No. 03-24-23R-006

STATE OF CALIFORNIA
STATE WATER RESOURCES CONTROL BOARD
DIVISION OF DRINKING WATER

Name of Public Water System: Cutler Public Utility District

Water System No: CA5410001

Attention: Dionicio Rodriguez, Superintendent

40526 Orosi Drive

Cutler, CA 93615

Issued: September 21, 2023

COMPLIANCE ORDER FOR NONCOMPLIANCE
CALIFORNIA HEALTH AND SAFETY CODE, SECTION 116555 AND
CALIFORNIA CODE OF REGULATIONS, TITLE 22, SECTION 64431

NITRATE MAXIMUM CONTAMINANT LEVEL VIOLATION
THIRD QUARTER 2023

The California Health and Safety Code (hereinafter "CHSC"), Section 116655 authorizes the State Water Resources Control Board (hereinafter "State Water Board"), to issue a Compliance Order to a public water system when the State Water Board determines that the public water system has violated or is violating the California Safe

Drinking Water Act (hereinafter “California SDWA”) (CHSC, Division 104, Part 12, Chapter 4, commencing with Section 116270), or any regulation, standard, permit, or order issued or adopted thereunder.

The State Water Board, acting by and through its Division of Drinking Water (hereinafter “Division”), and the Deputy Director for the Division, hereby issues Compliance Order No. 03-24-23R-006 (hereinafter “Order”), pursuant to Section 116655 of the CHSC to the Cutler Public Utility District (hereinafter “Water System”), for violation of CHSC, Section 116555, subdivision (a)(1) and California Code of Regulations (hereinafter “CCR”), Title 22, Section 64431 Maximum Contaminant Levels (hereinafter “MCL”) – Inorganic Chemicals.

STATEMENT OF FACTS

The Water System is classified as a community public water system with a population of 6,200, serving 1,234 connections. The Water System operates under Domestic Water Supply Permit Amendment No. 03-24-22PA-019 issued by the State Water Board on August 24, 2022. The Water System is using groundwater sources to supply potable water to the distribution system.

CHSC, Section 116555, subdivision (a)(1) requires all public water systems to comply with primary drinking water standards as defined in CHSC, Section 116275, subdivision (c). Primary drinking water standards include maximum levels of contaminants, specific treatment standards, and monitoring and reporting requirements as specified in regulations adopted by the State Water Board.

CCR, Title 22, Section 64431 Maximum Contaminant Levels – Inorganic Chemicals states that public water systems shall comply with the primary MCLs established in

table 64431-A. The MCL for Nitrate (as Nitrogen) is 10. milligrams per liter (hereinafter “mg/L”).

The State Water Board received laboratory results for two nitrate samples collected on August 04, 2023, and August 08, 2023, from Well 05. The average nitrate concentration from the two samples was 10.5 mg/L. A summary of the Water System’s nitrate monitoring results are presented in Table 1 below:

Table 1 – Well 05 Nitrate Sample Results

Sample Date	Result (mg/L)	Type of Sample
8/4/2023	11	Initial
8/8/2023	10	Confirmation

Additionally, nitrate results for Well 05 have fluctuated from 8.1 mg/L to 11 mg/L in the last year. Results are summarized in Table 2 below:

Table 2 – Well 05 Nitrate Sample Results

Sample Date	Result (mg/L)
8/09/2023	9.5
7/14/2023	10
6/14/2023	9.5
6/13/2023	8.9
6/09/2023	11
5/22/2023	9.3
4/12/2023	10
3/24/2023	9
2/08/2023	8.6
1/11/2023	8.1

Sample Date	Result (mg/L)
12/09/2022	9.2
11/09/2022	10
10/14/2022	9.4
9/09/2022	9.6
8/26/2022	9.6

DETERMINATION

The State Water Board has determined that the Water System has failed to comply with primary drinking water standards pursuant to CHSC, Section 116555 and the nitrate MCL pursuant to CCR, Title 22, Section 64431.

DIRECTIVES

The Water System is hereby directed to take the following actions:

1. By **September 21, 2026**, comply with CCR, Title 22, Section 64431.
2. Continue monthly sampling for nitrate from Well 05. The analytical results of the samples must be submitted electronically to the State Water Board, by the laboratory, that conducts the analysis, no later than the tenth day of the month following completion of the analyses.
 - Monthly public notification to the customers of the Water System must begin by **October 1, 2023** and continue monthly until the State Water Board determines that the nitrate contamination is resolved. Public Notification shall be conducted in conformance with CCR, Title 22, Sections 64463.1 and

64465. Appendix 1: Notification Template shall be used to fulfill this Directive, unless otherwise approved by the State Water Board.

- By mail or direct delivery of the Public Notification to each customer served by the water system and;
- By one of the following secondary methods to reach persons not likely to be reached by mail or direct delivery;
 - By publication in a local newspaper, by delivery to community organizations or by posting in conspicuous public places served by the water system or on the internet. If the water system opts to issue the notice via internet website, the public notice must remain posted for a minimum of seven (7) consecutive days.
- Public notification for new customers must be conducted in conformance with CCR, Title 22, Section 64463(e) where the Water System shall give new customers a copy of the most recent public notice prior to or at any time service begins.
- Monthly public notification must be provided every month even when a nitrate result shows a concentration below the nitrate MCL. The notice must be updated to include the following wording:

“Although the nitrate level(s) during the most recent monitoring period showed results below the MCL, nitrate levels in the water tend to fluctuate and it is possible that the nitrate level may increase at any time between sampling events. Public notification will continue until the nitrate problem is resolved.”

3. Complete Appendix 2: Certification of Completion of Notification Form. Submit it together with a copy of the public notification required by Directive 3 to the State Water Board within 10 days following each public notification. The first certification of completion of public notification form is due by **November 10, 2023**.
5. Prepare for State Water Board approval, a Corrective Action Plan, identifying improvements to the water system designed to correct the water quality problems identified as an exceedance of the nitrate MCL and ensure that the Water System delivers water to consumers that meets primary drinking water standards. The plan must include a time schedule for completion of each of the phases of the project such as design, construction, and startup, and a date that shows when the Water System will be in compliance with the nitrate MCL. The date must be no later than **September 21, 2026**.
6. On or before **December 11, 2023**, electronically submit and present via a virtual meeting the Corrective Action Plan required under Directive No. 5 above, to the State Water Board's office located at:

Dwpdist24@waterboards.ca.gov

7. Perform the State Water Board approved Corrective Action Plan, and each and every element of said plan, according to the time schedule set forth therein.
8. By **January 10, 2023**, and every three months thereafter, submit a report to the State Water Board in the form provided as Appendix 3 showing actions taken

during the previous quarter (calendar three months) to comply with the Corrective Action Plan.

9. By **September 21, 2026**, demonstrate to the State Water Board that the water delivered by the Waer System complies with the Nitrate MCL.
10. Notify the State Water Board in writing no later than five (5) days prior to the deadline for performance of any directive set forth herein if the Water System anticipates it will not meet the deadline.

All submittals required by this Order, unless otherwise specified in the directives above, must be electronically submitted to the State Water Board at the following address. The subject line for all electronic submittals corresponding to this Order must include the following information: Water System name and number, compliance order number, and title of the document being submitted.

Kristin Willet, P.E.

dwpdist24@waterboards.ca.gov

The State Water Board reserves the right to make modifications to this Order as it may deem necessary to protect public health and safety. Such modifications may be issued as amendments to this Order and shall be effective upon issuance.

Nothing in this Order relieves the Water System of its obligation to meet the requirements of the California SDWA (CHSC, Division 104, Part 12, Chapter 4, commencing with Section 116270), or any regulation, standard, permit, or order issued or adopted thereunder.

PARTIES BOUND

This Order shall apply to and be binding upon the Water System, its owners, shareholders, officers, directors, agents, employees, contractors, successors, and assignees.

SEVERABILITY

The directives of this Order are severable, and the Water System shall comply with each and every provision thereof notwithstanding the effectiveness of any provision.

FURTHER ENFORCEMENT ACTION

The California SDWA authorizes the State Water Board to issue a citation or order with assessment of administrative penalties to a public water system for violation or continued violation of the requirements of the California SDWA or any regulation, permit, standard, citation, or order issued or adopted thereunder including, but not limited to, failure to correct a violation identified in a citation or compliance order. The California SDWA also authorizes the State Water Board to take action to suspend or revoke a permit that has been issued to a public water system if the public water system has violated applicable law or regulations or has failed to comply with an order of the State Water Board, and to petition the superior court to take various enforcement measures against a public water system that has failed to comply with an order of the State Water Board. The State Water Board does not waive any further enforcement action by issuance of this Order.

Tricia A. Wathen  Digitally signed by Tricia A. Wathen
Date: 2023.09.21 11:05:22 -07'00'

Tricia A. Wathen, P.E.
Chief, Central California Section
State Water Resources Control Board

Date

Division of Drinking Water
Southern CA Drinking Water Field Operations Branch

Appendices:

1. Notification Template
2. Certification of Completion of Public Notification
3. Quarterly Progress Report Template

Certified Mail No. 7022-0410-0002-3469-6578

APPENDIX 1. NOTIFICATION TEMPLATE

IMPORTANT INFORMATION ABOUT YOUR DRINKING WATER

Este informe contiene información muy importante sobre su agua potable.

Tradúzcalo o hable con alguien que lo entienda bien.

DRINKING WATER WARNING

Cutler Public Utility District water has high levels of nitrate

DO NOT GIVE THE WATER TO INFANTS UNDER 6 MONTHS OLD OR PREGNANT WOMEN OR USE IT TO MAKE INFANT FORMULA

Water sample results received [date] showed nitrate levels of [level and units]. This is above the nitrate standard, or maximum contaminant level (MCL), of 10 milligrams per liter. Nitrate in drinking water is a serious health concern for infants less than six months old.

What should I do?

- **DO NOT GIVE THE WATER TO INFANTS.** *Infants below the age of six months who drink water containing nitrate in excess of the MCL may quickly become seriously ill and, if untreated, may die because high nitrate levels can interfere with the capacity of the infant's blood to carry oxygen. Symptoms include shortness of breath and blueness of the skin. Symptoms in infants can develop rapidly, with health deteriorating over a period of days. If symptoms occur, seek medical attention immediately.*
- **PREGNANT WOMEN SHOULD NOT CONSUME THE WATER.** *High nitrate levels may also affect the oxygen-carrying ability of the blood of pregnant women.*
- Water, juice, and formula for children under six months of age should not be prepared with tap water. Bottled water or other water low in nitrates should be used for infants until further notice.
- **DO NOT BOIL THE WATER.** Boiling, freezing, filtering, or letting water stand does not reduce the nitrate level. Excessive boiling can make the nitrates more concentrated, because nitrates remain behind when the water evaporates.
- If you have other health issues concerning the consumption of this water, you may wish to consult your doctor.

What happened? What is being done?

Nitrate in drinking water can come from natural, industrial, or agricultural sources (including septic systems, storm water run-off, and fertilizers). Levels of nitrate in drinking

water can vary throughout the year. We will let you know if the amount of nitrate is again below the limit.

[Describe corrective action, seasonal fluctuations, and when system expects to return to compliance.]

For more information, please contact [name of contact] at [phone number] or [mailing address].

Please share this information with all the other people who drink this water, especially those who may not have received this notice directly (for example, people in apartments, nursing homes, schools, and businesses). You can do this by posting this public notice in a public place or distributing copies by hand or mail.

Secondary Notification Requirements

Upon receipt of notification from a person operating a public water system, the following notification must be given within 10 days [Health and Safety Code Section 116450(g)]:

- SCHOOLS: Must notify school employees, students, and parents (if the students are minors).
- RESIDENTIAL RENTAL PROPERTY OWNERS OR MANAGERS (including nursing homes and care facilities): Must notify tenants.
- BUSINESS PROPERTY OWNERS, MANAGERS, OR OPERATORS: Must notify employees of businesses located on the property.

This notice is being sent to you by [Cutler Public Utility District](#)

State Water System ID#: CA5410001

Date distributed: MM/DD/YYYY

INFORMACIÓN IMPORTANTE SOBRE SU AGUA POTABLE

Este aviso contiene información muy importante sobre su agua potable.

Tradúzcalo o hable con alguien que lo entienda bien.

ADVERTENCIA SOBRE EL AGUA POTABLE

El agua de **Cutler Public Utility District** tiene altos niveles de nitratos

NO DE ÉSTA AGUA A BEBÉS MENORES DE 6 MESES O A MUJERES EMBARAZADAS. TAMPOCO USE ÉSTA AGUA PARA PREPARAR FORMULA INFANTIL

Los resultados de las pruebas del agua recibidas el [date] mostraron niveles de nitrato de [level and units]. Estos niveles exceden el estándar o nivel máximo de contaminante (MCL) de 10 miligramos por litro. Los nitratos en el agua potable son una preocupación seria en bebés menores de seis meses.

¿Qué debe hacer?

- **NO DE ÉSTA AGUA A BEBÉS MENORES DE 6 MESES.** *Los bebés menores de 6 meses que toman agua con nitrato en exceso del nivel máximo de contaminante (MCL), se pueden enfermar seriamente y rápidamente. Y si los bebés no reciben atención médica, pueden morir debido a que los altos niveles de nitratos pueden interferir con la capacidad de la sangre de los bebés para transportar oxígeno. Los síntomas incluyen falta de aire y coloración azulada de la piel. Los síntomas en los bebés se pueden desarrollar rápidamente y la salud se deteriora en cuestión de días. Si hay síntomas de intoxicación por altos niveles de nitratos, busque atención médica de inmediato.*
- **LAS MUJERES EMBARAZADAS NO DEBEN CONSUMIR AGUA CON ALTOS NIVELES DE NITRATOS.** *Los altos niveles de nitrato también pueden afectar la capacidad de la sangre de mujeres embarazadas para transportar oxígeno.*
- No use agua de la llave para preparar jugo, agua, y formula para bebés menores de 6 meses. Use agua embotellada u otra agua baja en nitratos para los bebés menores de 6 meses hasta nuevo aviso.
- **NO HIERVA EL AGUA.** Hervir, congelar, filtrar, o dejar reposar el agua, no reduce el nivel de nitratos. Hervir el agua en exceso puede causar que los nitratos se concentren más, porque los nitratos se quedan cuando el agua se evapora.
- Si tiene otros problemas de salud por el consumo de ésta agua, usted debería consultar con su doctor.

¿Qué sucedió? ¿Qué se está haciendo al respecto?

El nitrato en el agua potable puede originar de fuentes naturales, industriales, o agrícolas (incluyendo sistemas sépticos, escorrentía de agua de lluvia, y fertilizantes). Los niveles de nitrato en el agua potable pueden variar a través del año. Le informaremos si el nivel de nitratos vuelve a estar debajo del límite.

[Describe corrective action, seasonal fluctuations, and when system expects to return to compliance.]

Para más información, por favor contacte a [name of contact] al [phone number] o [mailing address]

Por favor comparta esta información con todas las demás personas que tomen de esta agua, especialmente aquellos que no hayan recibido éste aviso directamente (por ejemplo, las personas en apartamentos, asilos, escuelas, y negocios). Puede hacerlo poniendo este aviso en un lugar público o distribuyendo copias en persona o por correo.

Requisitos de Notificación Secundaria

Al recibir la notificación de alguien que opere un sistema de agua público, se debe dar la siguiente notificación dentro de 10 días conforme a la Sección 116450(g) del Código de Salud y Seguridad:

- ESCUELAS: Deben notificar a los empleados de la escuela, estudiantes, y a los padres (si los estudiantes son menores).
- DUEÑOS O GERENTES DE PROPIEDAD PARA ALQUILER RESIDENCIAL (incluyendo asilos e instituciones de cuidado): Deben notificar a sus inquilinos.
- DUEÑOS DE PROPIEDAD DE NEGOCIOS, GERENTES, U OPERADORES: Deben notificar a los empleados de los negocios situados en la propiedad.

Este aviso es enviado por [Cutler Public Utility District](#)

Núm. de Identificación del Sistema Estatal de Agua: CA5410001

Fecha de distribución: MM/DD/YYYY

APPENDIX 2
CERTIFICATION OF COMPLETION OF PUBLIC NOTIFICATION

Compliance Order Number: 03-24-23R-006

Name of Water System: Cutler Public Utility District

System Number: CA5410001

Attach a copy of the public notice distributed to the water system's customers.

This form, when completed and sent to dwpdist24@waterboards.ca.gov for the Division of Drinking Water, Tulare District at 265 W. Bullard Ave., Ste 101, Fresno, CA 93704, serves as certification that public notification to water users was completed as required by Title 22, California Code of Regulations, Sections 64463-64465.

Public notification for failure to comply with the **Nitrate MCL** was conducted on:

Notification was made on _____ (date).

For the month, year of _____, _____.

To summarize report delivery used and good-faith efforts taken, please check all items below that apply and fill-in where appropriate:

For Community and non-transient non-community public water systems

☐ The notice was distributed by mail or direct delivery to each customer on: _____

One or more of the following methods were used to reach persons not likely to be reached by a mailing or direct delivery or persons served by a transient public water system (renters, nursing home patients, prison inmates, etc.):

☐ Posted the notice at the following conspicuous locations served by the water system. (If needed, please attach a list of locations). _____

☐ Publication of the notice in a local newspaper or newsletter of general circulation (attach a copy of the published notice, including name of newspaper and date published).

☐ Posted the notice on the Internet at www. _____

☐ Other method used to notify customers. _____

I hereby certify that the above information is factual.

Certified by: Printed Name _____ Title _____

Signature _____

Date _____

Disclosure: Be advised that the California Health and Safety Code, Sections 116725 and 116730 state that any person who knowingly makes any false statement on any report or document submitted for the purpose of compliance with the Safe Drinking Water Act may be liable for, respectively, a civil penalty not to exceed five thousand dollars (\$5,000) for each separate violation or, for continuing violations, for each day that violation continues, or be punished by a fine of not more than \$25,000 for each day of violation, or by imprisonment in the county jail not to exceed one year, or by both the fine and imprisonment.

APPENDIX 3: QUARTERLY PROGRESS REPORT

Water System: Cutler Public Utility District	Water System No: CA5410001
Compliance Order No: 03-24-23R-006	Violation: Nitrate MCL
Calendar Quarter:	Date:

This form should be prepared and signed by Cutler Public Utility District personnel with appropriate authority to implement the directives of the Compliance Order and the Corrective Action Plan. Please attach additional sheets as necessary. The quarterly progress report must be submitted by the 10th day of each subsequent quarter, to the Division of Drinking Water, Tulare District Office to the following email address: dwpdist24@waterboards.ca.gov, titled appropriately.

Summary of Compliance Plan:

--

Tasks completed in the reporting quarter:

--

Tasks remaining to complete:

--

Anticipated compliance date:

--

Printed Name

Signature

Title

Date _____

Appendix D: CPUD Revised Consolidation Agreement and Extension Letter

State Water Resources Control Board

Division of Drinking Water

June 12, 2024

Martha Lowery
Cutler PUD Officer Manager
40526 Orosi Drive
Cutler, CA 93615

Dear Cutler PUD,

The State Water Resources Control Board's (State Water Board) sent letters, dated May 8, 2023 and January 9, 2024, to both Cutler PUD and Orosi PUD establishing and then extending the voluntary consolidation negotiation period. The most recent letter establishes a negotiation period ending on June 30, 2024.

Based on productive collaboration, the voluntary consolidation negotiation period is now further extended to September 1, 2025. The extension provides the necessary time to complete two efforts critical for project success: 1) A study and report which will detail the needs for consolidation of Cutler PUD and Orosi PUD and 2) A regional level study and report, building on prior efforts, which details the technical, managerial and financial viability of a regional water system and accompanying governance structures.

The additional time should ensure that participants can conduct a thorough and comprehensive assessment, ultimately leading to a successful and sustainable consolidation project.

Should the State Water Board determine that consolidation negotiations have slowed to a point where progress is no longer being made and/or that Cutler PUD or Orosi PUD is no longer responsive in the consolidation effort, the State Water Board may take action pursuant to Health and Safety Code section 116682, subdivision (a) for consolidation of the Cutler PUD and Orosi PUD water systems.

We appreciate your continued support and cooperation as you work together towards consolidation. If you have any questions, please contact Bryan Potter at bryan.potter@waterboards.ca.gov.

Sincerely,

A handwritten signature in black ink, appearing to read "Andrew Altevogt". The signature is fluid and cursive, with the first name "Andrew" and last name "Altevogt" clearly distinguishable.

Andrew Altevogt, P.E.
Assistant Deputy Director
State Water Resources Control Board, Division of Drinking Water

cc:
Maria Elena Vidana
OPUD District Manager
orosipud@sbcglobal.net

J. Patrick Sullivan
Sullivan and Sullivan Law Corporation
505 North West Street
Visalia, Ca 93291

Dennis Keller
District Engineer
kelweg1@aol.com

Eddie Valero
Tulare County Supervisor
evalero@tularecounty.ca.gov

Ben Giuliani
Tulare County LAFCO
bgiuliani@tularecounty.ca.gov

Kristin Willet, P.E., District Engineer
SWRCB, Division of Drinking Water
kristin.willet@waterboards.ca.gov

David Rice, Legal Counsel
SWRCB, Division of Drinking Water
david.rice@waterboards.ca.gov

CUTLER PUBLIC UTILITY DISTRICT

40526 Orosi Drive
Cutler, California 93615
559-528-3859
Cutlerpud@sbcglobal.net

Andrew Altevogt, P.E., Assistant Deputy Director
STATE WATER RESOURCES CONTROL BOARD
1001 I Street
Post Office Box 100
Sacramento, California 95812-0100

March 29, 2024
Via U.S. and fax:
916-341-5199

RE: 2nd Report on Negotiation Period for Voluntary Consolidation; Water System No. 5410008.

Dear Mr. Altevogt:

The Cutler Public Utility District (“CPUD”) and the Orosi Public Utility District (“OPUD”), collectively the “**parties**”, hereby acknowledge receipt of a **January 9, 2024** letter from you and the State Water Resources Control Board (“SWRCB” or “**State Water Board**”), wherein the SWRCB granted an extension for the CPUD to “...**submit a revised draft consolidation agreement by March 31, 2024, and a final consolidation agreement by June 30, 2024.**” Enclosed herewith is a revised draft of the voluntary consolidation agreement which the CPUD and the OPUD boards authorized for submission to the SWRCB for proceeding with a voluntary consolidation.

Since the receipt of your **January 9, 2024** letter, the legislative bodies of both special districts jointly met numerous times to continue to work out the terms of a voluntary consolidation agreement and related issues, including joint meetings on January 23, January 30, February 27 and March 26, 2024. Among others, Mr. Chad Fischer, P.E., and Hon. Laurel Firestone of the SWRCB attended the **January 30, 2024** joint meeting and provided information about the consolidation process and financing options for a consolidated surface water treatment plant project, which the parties desire to pursue.

As previously noted, the parties believe that with approximately 2,800 acre-feet of new surface water guaranteed to them, they have found a consolidation solution, which is laid out in their proposed voluntary consolidation agreement. The comments in your January 9, 2024 letter have been addressed in the attached draft. The Surface Water Plant Authority (the “**Authority**”) was already formed years ago as a perpetual public agency duly registered with the California Secretary of State, and under the attached draft neither the CPUD nor the OPUD would be operating any public water system because the CPUD and the OPUD would be transferring their water systems to the Authority who would be solely responsible to

Andrew Altevogt, P.E., Assistant Deputy Director, State Water Resource Control Board
RE: *2nd Report on Negotiation Period for Voluntary Consolidation; Water System No. 5410008.*
March 29, 2024
Page: 2 of 3

manage and operate them as a single water **system**, under a single water **system permit** issued by the SWRCB. Under the attached draft agreement, the CPUD and the OPUD would not be water systems, and both would not have any water system permit from the SWRCB. Only one water system would exist, the Authority. Please also note that the CPUD and OPUD also manage and operate street lighting and sewer systems for the residents within their territorial boundaries and therefore they cannot cease to exist as special **districts**, because they need to continue those non-water-related functions.

During virtual conferences between representatives of the SWRCB and the parties, various aspects of a consolidation were discussed, including on **March 9, 2024** when it was discussed that **EXHIBIT E** (improvements) of the draft consolidation agreement cannot be finalized until it is known which capital improvements are desired and acceptable by the SWRCB for this consolidation project, and SWRCB representatives indicated that the SWRCB would follow up on that issue to better define the scope of the project. At the follow up virtual conference held on **March 22, 2024**, the parties were informed that such follow up is still in progress. Obviously, a future draft of the consolidation agreement can be updated with this pending information.

The CPUD and the OPUD respectfully request your consideration and feedback on the latest draft of their voluntary consolidation agreement before it is signed and finalized, so that they can qualify for "**Consolidation Incentives**" funding under the SWRCB's programs, including but not limited to those in the SWRCB's FY2023-24 Intended Use Plan. Therefore, in order to assure that the agreement is satisfactory to the SWRCB, the OPUD and the CPUD boards kindly request written comments and feedback from the SWRCB as to any revisions which the SWRCB believes are necessary in order for the proposed agreement to qualify for and be approved for Consolidation Incentives funding.

The SWRCB's comments will enable the CPUD and the OPUD to schedule further and productive joint legislative body meetings under the Ralph M. Brown Act, for the purpose of considering any necessary revisions identified by the SWRCB, or further language which the SWRCB may request for inclusion in the voluntary consolidation agreement. As you may recall, the legislative bodies of both the CPUD and the OPUD are locally elected officials who are **not** full-time members of their respective legislative bodies, and generally carry on full-time employment in most cases. Therefore, scheduling special joint meetings is often a significant task because of differences in each member's schedule and availability. Accordingly, the CPUD and the OPUD thank you in advance for the SWRCB's written feedback which will enable the parties' meetings to be productive and enable the parties to squarely address all language and issues identified by the SWRCB, to meet the June 30, 2024 deadline set by the SWRCB. The CPUD and the OPUD will assume that any aspects of the enclosed draft of the consolidation agreement which do not receive any comments or

Andrew Altevogt, P.E., Assistant Deputy Director, State Water Resource Control Board
RE: *2nd Report on Negotiation Period for Voluntary Consolidation; Water System No. 5410008.*


March 29, 2024

Page: 3 of 3

requested revisions from the SWRCB are acceptable to the SWRCB.

The CPUD and the OPUD thank you for your consideration of the enclosed voluntary consolidation agreement and your comments which will serve to avoid the need for a compulsory consolidation Compliance Order from the SWRCB. We look forward to hearing from you so that the voluntary consolidation agreement can be finalized and signed by the parties. Thank you very much.

Sincerely,


Martha Lowrey, CPUD Office Manager


Maria Elena Vidaña, OPUD District Manager

Enclosures: UPDATED DRAFT of CONSOLIDATION AGREEMENT OF CUTLER PUBLIC UTILITY DISTRICT AND OROSI PUBLIC UTILITY DISTRICT. v5b

CC: CPUD General Counsel, via fax only: 559-741-2864; and
OPUD General Counsel, via fax only: 559-900-3555.

CONSOLIDATION AGREEMENT

OF

CUTLER PUBLIC UTILITY DISTRICT

AND

OROSI PUBLIC UTILITY DISTRICT

DRAFT

TABLE OF CONTENTS

I. INTRODUCTION.....	2
II. RECITALS.....	2
III. TERM AND DEFINITIONS	5
III. CONSOLIDATION AND ADMINISTRATION, OPERATION AND MAINTENANCE.....	6
IV. SERVICE REGULATIONS	9
V. FINANCIAL PROVISIONS.....	9
VI. LIABILITY AND INDEMNIFICATION.....	13
VII. OWNERSHIP INTERESTS.....	15
VIII. TERMINATION AND DISPOSITION OF PROPERTY	16
IX. GENERAL TERMS.....	17
EXHIBIT A	21
EXHIBIT B	22
EXHIBIT C	23
EXHIBIT D	24

I. INTRODUCTION

This consolidation agreement ("**Agreement**") is made by and between OROSI PUBLIC UTILITY DISTRICT ("**OROSI**") a public utility district, CUTLER PUBLIC UTILITY DISTRICT ("**CUTLER**"), a public utility district, and CUTLER-OROSI SURFACE WATER PLANT AUTHORITY ("**Authority**" or "**COSWPA**") a joint powers authority. This Agreement is dated **November 1, 2023** for reference purposes.

II. RECITALS

A. WHEREAS, both OROSI and CUTLER (collectively "**Districts**" or the "**Parties**", singularly a "**Party**" or "**District**") are each public utility districts organized under the Public Utility District Act, Chapter 560 of the Acts of the Regular Session of the 44th Legislature (now codified at Public Utilities Code §§ 15501 *et seq.*).

B. WHEREAS, pursuant to Public Utilities Code §§ 16880, 16881 each district is authorized to contract with any public agency for the joint acquisition or construction or use of any water works or other facilities for supplying water to the public utility district or such other public agency; and a contract may provide for the construction and maintenance of water works or other facilities and for the payment by or for the parties to the contract of such proportionate part of the cost of the acquisition, construction, or maintenance of such water works or other facilities as may be stated in the contract.

C. WHEREAS, pursuant to Public Utilities Code § 16431, each district may lease or dispose of, real and personal property of every kind within or without the district, when in the judgment of its governing board it is in the best interests of the district so to do.

D. WHEREAS, pursuant to Public Utilities Code § 16462, each district may also purchase any water and other commodities or services from any other utility district, municipality, person, or private company, and re-distribute them.

E. WHEREAS, under the provisions of the Joint Exercise of Powers Act (Government Code §§ 6500 *et seq.*), the parties hereto may jointly exercise the powers common to each.

F. WHEREAS, each of the Parties hereto currently own, operate and maintain certain facilities for the collection, treatment, conveyance and distribution of drinking water within their respective jurisdictional boundaries.

G. WHEREAS, the Alta Irrigation District (“Alta”) has developed a source of surface water, which has proven to be reliable for over a decade, as a groundwater water recharge project which offers such surface water at cost to public drinking water systems within Alta’s territorial boundaries, and has contracted with the Authority to guaranty delivery of no less than 2,800 acre-feet (“AF”) of such surface water each year to the Authority.

H. WHEREAS, the contracted supply of 2,800 AF of surface water from the Authority is sufficient to satisfy all of the drinking water capacity demands of both of the Parties, all year around.

I. WHEREAS, the California Legislature has authorized the People to democratically organize and hold an election and form political subdivisions of the State with political boundaries chosen by such People. [Public Utilities Code § 15702.]

J. WHEREAS, the State Water Resources Control Board (SWRCB or SWB) is an executive branch of State government with jurisdiction over water rights and water quality, including the regulation of drinking water systems through a permitting process. [Water Code §§ 13100; 186.]

K. WHEREAS, the California Legislature through the Cortese–Knox–Hertzberg Local Government Reorganization Act of 2000 (“**Reorganization Act**”), created a local agency formation commission (LAFCo) within each California county and such LAFCo has exclusive jurisdiction to consolidate the political boundaries two or more local government entities in a “change of organization” proceeding. [Gov. Code §§ 56000, 56325, 56021(j) and 56100(a).]

L. WHEREAS, representatives from the SWRCB met with representatives of the CUTLER and OROSI and requested that CUTLER and OROSI become a single political subdivision of the State, and as such to operate a single combined drinking water system under a single permit issued by the SWRCB, and to invite other special districts within the same larger region to also combined their political boundaries and water systems under such single political subdivision and water system permit, and to allow for expansion of the governing body of the new single political subdivision for.

M. WHEREAS, the Parties are open to the SWRCB’s request only if the SWRCB awards and fully pays to the receiving water system permit holder the maximum voluntary consolidation incentives authorized in the 2020 version of the SWRCB’s Intended Use Plan (“**Incentive Funds**”) for construction and debt service for a new surface water treatment plant. Each of the Parties would only be obligated to consent to and initiate LAFCo political boundary consolidation after all of the Incentive Funds are deposited into a trust account held solely by receiving water system permit holder for the benefit of the participating residents

of the special districts. If all of the Incentive Funds are not awarded and timely paid, then consolidation of political boundaries shall not be required of any of the Parties.

N. WHEREAS, LAFCo proceedings for consolidation of the political boundaries of the various special districts to form a single combined political subdivision will require, in part, annexation of territory which requires signatures from not less than 25 percent of the registered voters within the affected territory. [Government Code § 56864(a)(1).]

O. WHEREAS, because completion of LAFCo proceedings for a full political boundary consolidation are time-consuming and cannot be completed without satisfaction of certain prerequisites which require substantial time and effort which cannot be avoided, such proceedings would necessarily need to occur as a later stage of the overall consolidation project. In the interim the Parties shall proceed with this project through a joint powers entity which shall be responsible for the Parties' combined water system (including the Parties' combined water supply, treatment, storage and distribution facilities) and shall operate the same under a single water system permit with the SWRCB.

P. WHEREAS, the Parties now desire to promptly proceed to provide for the joint acquisition, construction and/or use of water works and/or other consolidated facilities for treating and supplying drinking water to each of the Parties to distribute to the inhabitants within their jurisdictional boundaries; and furthermore to lease such consolidated facilities to the Cutler-Orosi Surface Water Plant Authority ("**Authority**" or "**COSWPA**"), and to contract with the Authority for the ongoing consolidated operation and maintenance ("**O&M**") of a surface water treatment plant ("**SWTP**") on behalf of the Parties, including procurement from Alta no less than 2,800 AF of surface water which the Authority shall treat, make potable and then deliver to each of the Parties for distribution to their customers.

Q. WHEREAS, by approval of this Agreement, the legislative bodies of the Parties find and determine that is in the best interest and advantage of both of the Parties to authorize and provide for the construction and consolidated operation of a surface water treatment plant, for treatment of surface water and for its delivery to the customers of each of the Parties in an efficient manner, and also to provide for the financing of the same through payments and charges under the terms of this Agreement.

R. WHEREAS, CUTLER and OROSI shall each own a separate fifty percent (50%) interest in the real property and improvements which shall constitute the SWTP and its auxiliary facilities necessary for the consolidated treatment and delivery of surface water.

S. WHEREAS, a purpose of this consolidation Agreement is to jointly finance, acquire, construct, maintain, operate and utilize consolidated water works and facilities under Health and Safety Code § 116275(h)(3) as needed for procurement, treatment, reclamation and/or delivery or disposal of drinking water for the benefit of the inhabitants within the

boundaries of the Parties' respective districts, under a single water system permit to be held by the Authority, thereby eliminating the need for the Parties themselves to hold any SWRCB water system permit.

T. WHEREAS, the Parties by way of this Agreement intend to provide for the consolidated procurement, treatment and delivery of drinking water to the Parties and for the joint ownership and use of capacity rights in a consolidated water system which includes the SWTP to be operated and maintained by the Authority for the benefit of the Parties, and to address proportionate share of its operational costs through payment and compensation from the Parties.

U. WHEREAS, the Parties hereto understand and agree to their obligation to cooperate with one another to the extent necessary to maintain the consolidated SWTP. Therefore, the Parties hereby recognize their obligation to continue communication with one another about the physical matters or events occurring within or to their respective distribution systems which may directly or indirectly effect their receipt of treated surface water from the consolidated SWTP.

ACCORDINGLY, IT IS AGREED:

III. TERM AND DEFINITIONS

1. **Term:** This Agreement shall become effective as of the date of signing by all parties hereto and shall not expire but shall continue in perpetuity unless otherwise provided by law.

2. **Definitions.** Unless the contract otherwise requires, the terms defined in this Section shall, for all purposes of this Agreement and for any agreement supplemental hereto and to any other documents herein mentioned, have the meaning herein specified, to be equally applied to both the singular and the plural forms of any of the terms herein defined.

(a) **"Capacity"** refers to the quantity of surface water which can be successfully treated by the consolidated SWTP and distributed as potable drinking water which satisfies all applicable State and federal drinking water standards.

(b) **"CUTLER"** refers to the Cutler Public Utility District.

(c) **"Cost"** is an amount of money and other equivalent financial resources associated with a specific item or purpose. Costs may be calculated amounts (such as depreciation) or actually incurred or accrued expenses.

- (d) “GPD” and “gpd” is the abbreviation for gallons per day.
- (e) “OROSI” refers to the Orosi Public Utility District.
- (f) “O&M” refers to operation and maintenance.

III. CONSOLIDATION AND ADMINISTRATION, OPERATION AND MAINTENANCE

3. **Consolidation:** The Parties agree to consolidate their water systems into one physically and operationally consolidated water system consisting of a surface water supply collection and treatment plant, all of the Parties’ existing groundwater wells and the Parties’ existing water distribution systems, as a single consolidated public water system as defined in Health and Safety Code § 116275(h), according to and contingent upon all of the terms and conditions, time schedule, and milestones described within this Agreement. Such consolidated water system, which shall be operated and maintained under a single water system permit held by the Authority as the responsible public entity, will source, treat and physically deliver potable drinking water to the customers of each of the Parties.

4. **Timing of Implementation:**

(a) The Parties shall make every reasonable effort to complete the consolidation and related tasks as quickly as possible while ensuring that OROSI’s and CUTLER’s current customers are not negatively impacted and that the consolidated water system is reliable and sustainable.

(b) Subject to provision 4(a) and 4(c), the consolidation and all associated improvements and tasks, shall be completed according to the time schedule and milestones described in **EXHIBIT C**, contingent on the timing and availability of State grant funding to cover the costs of consolidation.

(c) To the extent that any portion of the consolidation project or associated improvements or tasks are delayed despite the diligent and good faith effort of the Parties, the Parties agree to complete the remaining tasks promptly without undue delay.

(d) The physical consolidation is complete when both of the following are complete: (i) the contingency set forth in the following **Section 5** is fully satisfied; and (ii) the construction of the consolidated SWTP and a physical interconnection between the consolidated SWTP and the existing water distribution systems of both CUTLER and OROSI, with all improvements listed in **EXHIBIT D**.

5. Contingent Upon Funding: The obligations of each of the Parties to this Agreement to consolidate the Parties' water systems shall be contingent upon the award of State and/or federal financing package(s) which benefits both OROSI and CUTLER, including receipt of Incentive Funds for each of the Parties and such other for a voluntary consolidation, as provided in the SWB's Drinking Water State Revolving Fund (**DWSRF**) Intended Use Plan (**IUP**) in effect as of the date this Agreement is fully signed. The financing package must, at a minimum, satisfy all of the requirements of California Health and Safety Code § 116682(e) and provide grant funding for the projects, and improvements identified in **EXHIBIT D**, including all associated soft costs (e.g., associated costs for consultants and fees) to complete the projects and improvements, at no cost to OROSI and CUTLER residents and ratepayers, and eliminate and reimburse all financial impact on OROSI resources.
6. Regular Communication: The Parties agree to regularly meet and communicate together and with other involved third parties, including but not limited to the State Water Resources Control Board (**SWRCB** or **SWB**) and any consultants and contractors, at agreeable intervals to ensure that the consolidation project and all related improvements and tasks are completed promptly without undue delay.
7. The consolidated water system shall be overseen and operated by the Authority, which is a separate public entity from the Parties to this Agreement. This Agreement shall not in any way affect or otherwise impair or impinge upon the Parties' authority to continue to provide public street light and sanitary sewer services to their residents.
8. Manner of Exercising Powers. In exercising the powers granted under this Agreement to the Authority, and in the conduct of all business of the Authority, the Authority shall be subject to the restrictions upon the manner of exercising such powers, which applies to public utility districts under California law.
9. Ratepayer Payments. Each of the Parties are entitled to and must charge and collect all rates and capacity, connection and other fees, charges and assessments from each ratepayer within their respective boundaries. Each of the Parties shall be responsible for compliance with all applicable laws pertaining the adjustment of rates, fees, charges and assessments to be collected from the ratepayers within their respective boundaries. The Authority shall not have authority to initiate or otherwise undertake any rate increase, fee or special assessment proceedings or measures within the boundaries of any of the Parties without such Party's express written consent.
10. In order to provide adequate facilities to adequately treat and utilize surface water as drinking water, it is contemplated that new construction within the territory in which the consolidated SWTP is located will be required from time to time. Whenever such new construction is required, the Authority shall make a determination of the following facts:

- (a) Which of the Parties or entity(ies), if any, is the source of the need for additional construction;
- (b) How much capacity shall be added to the consolidated SWTP;
- (c) Whether the financial capability of the Party or entity requiring the increase in capacity of the consolidated SWTP will enable such Party or entity to pay the costs of said expansion of capacity, or whether the state of finances of said Party or entity will require them to stop further growth within their respective boundaries, and refrain from increasing its capacity demand upon the consolidated SWTP.

11. Each of the Parties shall also retain the power to contract for the construction of additional plant and/or treatment capacity.

12. The Authority shall have the power to prevent each or both Parties from permitting additional connections which add capacity demand originating from within the respective boundaries of said Parties into the new consolidated water system, if sufficient capacity does not exist to accommodate said additional water capacity demand. Additional connections with subsequent parties must be approved only by written agreement with the Parties to this Agreement, which may only occur either by amendment to this Agreement or extraterritorial service agreement duly approved by the governing body of the Authority.

13. Water Distribution System. The Authority shall acquire, construct, hold title to, operate and maintain all water distribution works within the Parties' jurisdictional boundaries and such water distribution works as are necessary to convey treated surface water from consolidated SWTP to customers within the Parties' respective territorial boundaries.

14. Connections to District Water Distribution System.

Each of the Parties agrees that each must protect the consolidated water system in entering into any contract and enacting any ordinance pertaining to connections to the water distribution system within such Parties' territorial boundaries, including but not limited to, by authorizing the Authority and each Party to engage in enforcement of relevant connection standards and requirements.

15. Treatment and Storage Facilities. The Authority shall maintain, manage and operate the consolidated treatment and storage facilities consistent with applicable provisions and requirements of this Agreement, if any.

16. Authority Treatment and Transfer of Surface Water.

The Authority shall accept, treat and then transfer the surface water to the Parties so long as said transfers are in compliance with all applicable State and federal laws, rules and regulations.

17. Injunctive Relief. The Authority shall also have the right to take whatever appropriate legal action is necessary in order to compel each of the Parties' compliance with the connection requirements and the use and capacity limits outlined in this Agreement including, but not limited to, enjoining each of the Parties from using the consolidated SWTP.

IV. SERVICE REGULATIONS

18. Limitations on Water Use.

The Parties agree that all water provided by the Authority shall only be used for household purposes and such existing commercial purposes which are currently approved by each of the Parties, but all agricultural use or any use which is deemed wasteful shall not be permitted.

19. The Parties agree to enact specific limitations, prohibitions and actions as follows:

See **EXHIBIT B**.

20. [Reserved].

V. FINANCIAL PROVISIONS

21. Annual Budget.

The Treasurer of the Authority must cause to be prepared and must submit to the Parties, in sufficient time for revision and adoption prior to June 1 of each year, an annual budget of the Authority for the next succeeding fiscal year. All expenditures of funds must be approved by the governing body of the Authority. Amendments to the annual budget cannot be approved through the Authority's governing body consent calendar or consent agenda and must be approved as separate action items.

22. Accountability for Funds. All funds from the Parties which are received by the Authority shall be placed in the custody of the Authority's Treasurer or designee who shall hold such funds in a fiduciary capacity. The Treasurer (or designee) of the Authority must receive, have custody of and disburse Authority funds as nearly as possible in accordance with generally accepted accounting practices applicable to local government agencies within the State of California. These funds must be given object accounts, and the receipt, transfer or disbursement of such funds during the term of this Agreement must be accounted for by the Treasurer or designee in accordance with generally accepted accounting practices applicable to local government agencies within the State of California. There shall be strict accountability of all funds by the Treasurer and designee(s). All revenues and expenditures must be reported by the Treasurer or designee to the Parties at least on a monthly basis, unless more frequent reporting is required by the Parties.

23. Approval of Expenditures. All expenditures must be consistent with the approved budget and must be made upon the review and approval of the General Manager of the Authority in accordance with the rules, policies and procedures adopted by the governing body of the Authority and all such rules, policies and procedures must be consistent with this Agreement and all applicable laws.

24. Unbudgeted But Necessary Expenditures. Notwithstanding any other provision of this Agreement, the Authority must not expend or make any payment which is inconsistent with the Authority's approved budget. Unanticipated and unbudgeted but necessary expenses must be presented to the Parties who may choose to authorize funding them only after amendment of the Authority's annual budget.

25. Annual Audit. Pursuant to the provisions of the Government Code of the State of California, the Authority must cause all accounts, books and other financial records of the Authority to be kept in accordance with generally accepted accounting practices applicable to local government agencies within the State of California. The Authority must cause an annual audit to be performed on its books and records, by an independent Certified Public Accountant, which satisfies the Minimum Audit Requirements and Reporting Guidelines prescribed by State Controller's Office for special districts. A copy of said audit report must be forwarded to each of the Parties. The expense of said audit and report and all bookkeeping and accounting costs must be treated as a required cost of the consolidated SWTP. The annual audit report must be submitted to the Authority's governing body when completed.

26. (a) Records. The Authority shall also cause to be kept accurate and correct books of account, showing in detail the costs and expenses of any new construction, extra construction or reconstruction and the maintenance and operation of the consolidated SWTP and all parts thereof, and all financial transactions of the Authority, which books of account must correctly show each and all receipts and also any costs, expenses or charges to be paid by the Authority, and also metering records of the water delivered to each of the Parties and other entities, together with the daily peak capacity demand of each of the Parties. The books and records must also correctly show each and all receipts and any costs, expenses or charges paid to, or to be paid by, the Parties.

(b) Inspection of Records. All books of account and all financial records and memoranda, whether final or in draft form, must be open to inspection during all normal business hours to: any member of the board of directors of OROSI or CUTLER; any accountant or other person authorized by CUTLER or OROSI's board of directors; and to the general manager or office manager of the Parties. This obligation is separate and independent of the Authority's obligation to comply with the California Public Records Act (Government Code §§ 7920.000 et seq.). The individuals in charge of maintaining books and financial records must be employees of the Authority or qualified independent contractors. Any independent contractor in possession of records of the Authority which are requested by

either of the Parties must comply with the request of any of the Parties within five (5) business days.

(c) Treasurer's Initiation of Annual Audit. The Authority's Treasurer, within one hundred twenty (120) days after the close of each fiscal year, must ensure that all financial activities for such fiscal year have been accurately recorded and must ensure that the annual audit has been commenced and is proceeding without undue delay, unless the governing bodies of both CUTLER and OROSI have expressly authorized otherwise for that particular fiscal year which recently closed.

27. Contributions. The Parties may in the appropriate circumstance when required hereunder: (a) make contributions from their treasuries for the purposes set forth herein; (b) make payments of public funds to defray the cost of such purposes; (c) make advances of public funds for such purposes, such advances to be repaid as provided herein; and/or (d) if specifically authorized by the Parties in writing, and for a particular purpose, use their respective personnel, equipment or property in lieu of other contributions or advances. Under no circumstances will the Parties be obligated to make contributions or payments to the Authority or the Authority's contractors for any expenses for the consolidated SWTP if such expenses are not included in the Authority's approved annual budget.

28. Credit to the Parties. All accounts or funds created and established pursuant to any instrument or agreement to which the Authority is a party, and any interest earned or accrued thereon, shall inure only to the benefit of the Parties to this Agreement in the respective proportions to their ownership interest in all of the real property and improvements of the consolidated water system, insofar as that Party's required payments or contributions to the Authority under this Agreement are not past due.

29. (a) Imposition and Administration of Fees and Costs. The Authority shall have the right to impose upon and collect from each of the Parties, based upon a monthly billing period, the total cost properly determined by the Authority for that Party's actual proportional share of operation and maintenance of the consolidated water system, but only to the extent such operation and maintenance costs are within the Authority's approved budget, as amended from time to time. The Parties shall be charged and must pay the budgeted operation and maintenance charges in direct proportion to the metered amount of water delivered to each such Party receiving treated water from the consolidated water system. The Authority shall also charge and collect the budgeted operation and maintenance charges from the public entities receiving water service from the Authority as identified in **EXHIBIT A** and all other third-party users in direct proportion to their metered use or otherwise as duly allocated to each such person/entity. The foregoing amounts shall be subject to post-fiscal year true-up.

(b) Maintenance and Operation. The term "**maintenance and operation**" as used herein shall mean the repair and upkeep made necessary by ordinary use and operation of the of the consolidated water system, within the Authority's approved budget. Actual annual

operational and maintenance costs shall be defined as including all: labor costs, such as salaries and wages, including overtime and premium pay, health and welfare, and all fringe benefits; all general operating expenses; education and travel allowances; buildings, grounds and equipment maintenance; capital outlay expenses; accounting expenses; collections, enforcement and other legal expenses; and incidental expenses for insurance and special charges. In addition, such costs shall include the pro-rata share of direct and indirect charges for overhead representing actual costs of service.

(c) Under no circumstances will the Parties be obligated to make contributions or payments to the Authority or the Authority's contractors for any expenses for the consolidated water system if such expense(s) is not included in the Authority's approved annual budget, as amended from time to time.

(d) Pro-Rata or Proportionate Share. By default, the Parties' pro-rata and proportionate share shall be determined by the proportion of metered water received by the customers of each Party, after subtracting each and all payments or service charges allocated of all users who are not a Party to this Agreement, if any.

30. Changes in Number of Connections. The Parties hereby agree to advise the Authority and each other by the 25th day of each month of any changes in the number of water accounts for connections to the water distribution system within their boundaries. In addition, by July 1st and January 1st of each year the Parties must provide to the Authority a certified summary of billing units by category of use. This monthly reporting must include changes in the number of water accounts as a result of any extraterritorial service agreement with any customer outside of its normal service area, but invoiced by a Party whose share of capacity is utilized for such account.

31. Surface Water Authority Capital Reserve Fund. The Parties hereby agree to incorporate into their respective rate structure appropriate provisions for depreciation as required by federal and State revenue program guidelines or as required by the Authority should federal and State revenue program guidelines eliminate the requirements for a depreciation set aside fund. Said fund shall include each entity's pro-rata share of the consolidated water system and each entity shall accumulate and utilize such funds in accordance with the aforementioned guidelines. Funds accumulated by each Party in their respective Surface Water Authority Capital Reserve Fund shall be retained by such Party until such times as said funds may be required for major repair and capital improvements expenses as outlined in this Agreement. Each Party must not use said funds for any other purpose other than as outlined in this Agreement and must not borrow against said funds.

32. Major Repairs and Capital Improvement Expenses. Each Party hereby agrees to pay its half (i.e. 50/50 split) and share of major repairs and capital improvement expenses, as specified in the Authority's approved budget, based upon design parameters of the consolidated SWTP, and one hundred percent for each and all groundwater wells and water distribution facilities which are physically located within such Party's territorial boundaries.

In the event that major repair and capital improvement expenses are included in a preliminary budget as prepared by the Authority, then sufficient advance notice by the Authority to the Parties must be provided in order for the Parties to include their pro-rata share in their respective budgets. Where such expenses may be defrayed from accumulated depreciation funds collected in a Party's Surface Water Authority Capital Reserve Fund, then such Party must make payments upon thirty (30) days notice by the Authority of its award of a contract for such work or completion thereof by forced account. In the event that a Party is unable to defray such expenses from accumulated depreciation funds in its Surface Water Authority Capital Reserve Fund, then such Party must make such arrangements for payments of its pro-rata share as are satisfactory to the Authority.

33. Procedure for Collection and Charges Imposed for Facility Use.

Each Party shall, based upon the charges set by the Authority, impose and collect said charges and remit them to the Authority on a monthly basis. The amount set by the Authority must be based upon the total volumetric use of each of the Parties and their users, as determined through metering figures. Payments must be remitted to the Authority within thirty (30) days following the end of the service month for which the charge is billed.

34. Net Contract. It is understood and agreed that this Agreement, including the Parties' obligation to pay all fees, costs and charges described herein, shall be deemed and construed to be a "net contract", except that the Authority may not immediately invoice the Parties for expenses of consultants and contractors that are not yet included in the approved annual budget, but may invoice the Parties after said expenses have been added by amendment to the Authority's annual budget. The Parties agree that such payments shall be an absolute net return to the Authority, free and clear of any expenses, charges or setoffs each of Parties may claim against the Authority or any third party including each of the Parties' customers.

VI. LIABILITY AND INDEMNIFICATION

35. Authority As Tenant of Facility: The Authority shall take full possession of the consolidated waster system, and the improvements and fixtures thereon, and shall be fully responsible for the O&M thereof, and for any contractual and/or tort liability arising from the use or operation thereof and premises upon which the consolidated water system is located.

36. Limitation on Parties' Liability. The Parties shall not be liable at any time for any loss, damage or injury to property or any person whomsoever, arising out of any acts or omissions by the Authority in carrying out its management, operation and maintenance of the consolidated water system. This section shall not limit the Authority's ability to seek an injunction or other equitable or legal remedies against any Party or person so as to prevent the unauthorized use of surface water treated at the consolidated SWTP.

37. Obligations of the Authority; Indemnification from Debt Liabilities. The debts, liabilities and obligations of the Authority shall be the debts, liabilities and obligations of the Authority alone and shall not be binding upon, the Parties. Should any debt, liability or obligation of the Authority not be waived or allowed payable through assets of the Authority, the Parties shall each not be liable therefore. The Authority shall protect, indemnify and hold each of the Parties safe and harmless from any and all debts or liabilities whatsoever arising out of or in connection with the Authority's operation, management and maintenance of the consolidated water system or any of the Authority's day to day activities.

38. Authority's Indemnification of Parties for Tort Liability. Notwithstanding anything to the contrary in this Agreement, and irrespective of any insurance carried by the Authority, the Authority shall protect, defend, indemnify and hold safe and harmless each of the Parties, their respective elected and appointed officials, officers and employees from and against any and all liabilities, damages, loss, cost, claims, expenses, actions or proceedings of any kind or nature caused by officers of or staff employed by the Authority including, without limitation, injury or death of any person, injury or damage to any property, including consequential damages and attorneys' fees and costs, resulting or arising out of or in any way connected with the alleged willful or negligent acts or alleged failure to act in the course and scope of carrying out their responsibilities in the performance of their duties to the Authority.

39. Insurance. The Authority shall obtain liability insurance containing limits of liability no less than such amount as the Parties jointly agree to be necessary to cover the risk of liability incurred by the activities of the Authority. Each Party and its elected and appointed officials, officers and employees shall be named as an additional insured for said liability insurance. Whenever the Authority has employees, the Authority must cover all its employees with workers' compensation insurance.

40. Mutual Indemnification Between the Parties. In lieu of and notwithstanding the pro-rata risk allocation which might otherwise be imposed between the Parties pursuant to Government Code § 895.6, the Parties agree that all losses or liabilities incurred by any of the Parties shall not be shared pro-rata, but instead the Parties agree that pursuant to Government Code § 895.4, each of the Parties hereto shall fully indemnify, hold harmless and defend the other Party, its officers, governing body members, employees and agents, from and against any claim, expense, cost, damage or liability occurring by reason of the negligent acts or omissions or willful misconduct of the indemnifying Party, its officers, governing body members, employees or agents, arising out of or in connection with any work, activity, authority or jurisdiction under the scope of this Agreement. No Party, nor any officer, governing body member, employee or agent thereof shall be responsible for any damage or liability occurring by reason of the negligent acts or omissions or willful misconduct of any other Party hereto, its officers, governing body members, employees or agents.

41. Limitation on Authority's Liability for Parties' Distribution Systems. The Authority shall not be liable at any time for any loss, damage or injury to the property or person whomsoever or to any fines or punitive actions at any time occasioned by or arising out of any acts or omissions by any of the Parties in the distribution of water obtained from the consolidated SWTP, or in the ownership, management, operation and maintenance of the distribution system within the jurisdiction of any of the other Party. Notwithstanding anything to the contrary in this Agreement, and irrespective of any insurance carried by any of the Parties, each of the Parties hereby agree to protect, indemnify and hold the Authority harmless from any and all damages and liabilities whatsoever arising in connection with their receipt of water from the consolidated SWTP or their ownership, maintenance, management and operation of their respective distribution systems within their respective boundaries. Each of the Parties must take all reasonable steps to include the Authority and its officers and employees as additional insureds on all insurance policies held by each of the Parties.

42. Privileges and Immunities from Liability. The provisions of Government Code § 6513 are hereby incorporated into this Agreement by reference.

43. Fines and Penalties Arising From Parties' Breach. In the event that any Party violates any of the terms of this Agreement, and as a result of said violation, the Authority violates its regulatory requirements and is fined or receives any penalties from any State or federal regulatory entity having jurisdiction over the consolidated water system and its operations, then said Party hereby agrees to protect, indemnify and hold the Authority safe and harmless from all such fines and penalties.

44. All indemnification obligations in this Agreement shall continue beyond the term or expiration of this Agreement as to any acts or omissions occurring under this Agreement or any extension of this Agreement.

VII. OWNERSHIP INTERESTS

45. Unless otherwise agreed in a writing signed by each Party, each Party shall separately own a fifty percent (50%) interest in all of the real property and improvements of the consolidated SWTP, including all of the fixtures and equipment used to operate the consolidated SWTP. Such ownership necessarily includes each and all fixtures subsequently added by the Authority. Each Party hereto shall own a one-hundred percent (100%) interest in each groundwater well which it transfers possession of to the Authority. Such ownership necessarily includes each and all fixtures subsequently added by the Authority.

46. All plant capacity in the consolidated SWTP shall be separately vested as follows: fifty percent (50%) in CUTLER; and fifty percent (50%) in OROSI.

47. All personal property, including any valuable byproducts produced, owned or held by the Authority shall be deemed to be held solely in trust by the Authority for the sole benefit of the Parties, in the same proportions specified in this Agreement for the Parties' ownership of fixtures and equipment used to operate the consolidated SWTP.

48. The Authority shall not be authorized to acquire any beneficial fee ownership in the real property or personal and intellectual property held or utilized by the consolidated water system, and the title to each and all portions real property held by the Authority, if any, shall be deemed to be held solely in trust by the Authority for the sole benefit of the CUTLER and OROSI, in the proportions specified in this Agreement for real property and improvements of the consolidated water system. Title to any and all real property acquired by the Authority by means of eminent domain must promptly be conveyed to the Parties who shall hold it as tenants in common (in the same proportions specified in this Agreement for the Parties' ownership of fixtures and equipment used to operate the consolidated SWTP) and until it is conveyed the Authority's holding of title thereto shall be solely in trust for the Parties.

VIII. TERMINATION AND DISPOSITION OF PROPERTY

49. This Agreement shall remain in full force and effect until such earlier time as a court of law or one or more Parties hereof terminate this Agreement according to the terms therefor. Unless otherwise expressly agreed, termination of this Agreement shall not alter the accrued rights, benefits and obligations of the Parties existing at that time. Existing joint operations shall be terminated or amended in an orderly manner as soon as practicable or upon terms mutually agreed upon by the Parties.

50. Distribution of Assets Owned Only By Authority. Upon termination of this Agreement, any assets beneficially owned by the Authority after payment of all liabilities, costs, expenses and charges incurred under this Agreement shall be distributed to whichever public entity or entities shall assume responsibility for collection, treatment, reclamation and/or disposal of sanitary surface water and similar surface waters within the Parties' boundaries, to be used solely for such purposes, or if none, to the Parties hereto in the ownership proportions specified by this Agreement.

51. Disposition of Assets Not Owned by Authority. Upon termination of this Agreement, all property not beneficially owned by the Authority, both real and personal, shall be divided among the Parties hereto in proportion to their ownership interest in the consolidated SWTP.

52. This Agreement shall automatically become void and terminate if either: (a) the SWRCB issues a mandatory consolidation order directed to CUTLER and OROSI under authority codified in the Health and Safety Code; or (b) the Parties are unable to secure adequate funding, either by grant, loan and/or bond, which is sufficient to fully finance the

construction of the SWTP; and notice of the same is confirmed in writing by any Party hereto.

IX. GENERAL TERMS

53. Compliance With Law: The Authority shall provide services in accordance with applicable federal, State, and local laws, regulations and directives. With respect to the Authority's employees, the Authority must comply with all laws and regulations pertaining to wages and hours, State and federal income tax, unemployment insurance, Social Security, disability insurance, workers' compensation insurance, and discrimination in employment.

54. Governing Law: This Agreement shall be interpreted and governed under the laws of the State of California without reference to California conflicts of law principles. The Parties agree that this contract is made in and shall be performed in the County of Tulare, State of California.

55. Notices:

(a) Except as may be otherwise required by law, any notice to be given shall be written and shall be either personally delivered, sent by facsimile transmission or sent by first class mail, postage prepaid and addressed as follows:

OROSI:

Maria Elena Vidaña, District Manager
OROSI PUBLIC UTILITY DISTRICT
12488 Avenue 416
Orosi, California 93647
559-528-4262
559-528-2770 – Fax

With A Copy To:

Moses Diaz, District Counsel
PUBLIC INTEREST LAW FIRM
A Professional Corporation
2924 West Main Street
Visalia, California 93291
559-900-3500
559-900-3555 – Fax

CUTLER:

General Manager
CUTLER PUBLIC UTILITY DISTRICT
40526 Orosi Drive
Cutler, California 93615
559-528-3859
559-528-1919 – Fax

J. Patrick Sullivan, District Counsel
SULLIVAN & SULLIVAN PLC
505 North West Street
Visalia, California 93291
559-741-2860
559-741-2864 – Fax

(b) Notice personally delivered is effective when delivered. Notice sent by facsimile transmission is deemed to be received upon successful transmission, only if accompanied by

a legible fax transmission report. Notice sent by first class mail shall be deemed received on the **fifth** day after the date of mailing. Either party may change the above address by giving written notice pursuant to this paragraph.

56. Dispute Resolution: If a dispute arises out of or relating to this Agreement, or the breach thereof, and if said dispute cannot be settled through negotiation, the Parties agree first to try in good faith to settle the dispute by non-binding mediation before resorting to litigation or some other dispute resolution procedure, unless the Parties mutually agree otherwise. The mediator shall be mutually selected by the Parties, but in case of disagreement, the mediator shall be selected by lot from among two nominations provided by each Party. All costs and fees required by the mediator shall be split equally by the Parties, otherwise each Party shall bear its own costs of mediation. If mediation fails to resolve the dispute within thirty (30) days, either Party may pursue required claims and then litigation to resolve the dispute.

57. Construction: This Agreement reflects the contributions of all undersigned Parties and accordingly the provisions of Civil Code section 1654 shall not apply to address and interpret any alleged uncertainty or ambiguity.

58. Headings: Section headings are provided for organizational purposes only and do not in any manner affect the scope, meaning or intent of the provisions under the headings.

59. No Third-Party Beneficiaries Intended: Unless specifically set forth, the Parties to this Agreement do not intend to provide any other person or entity with any benefit or enforceable legal or equitable right or remedy, except to the extent that the Authority is expressly authorized to pursue an equitable remedy.

60. Waivers: The failure of either Party to insist on strict compliance with any provision of this Agreement shall not be considered a waiver of any right to do so, whether for that breach or any subsequent breach. The acceptance by either Party of either performance or payment shall not be considered to be a waiver of any preceding breach of the Agreement by the other Party.

61. Exhibits And Recitals: The recitals and the exhibits to this Agreement are fully incorporated into and are integral parts of this Agreement.

62. Conflict With Laws or Regulations/Severability: This Agreement is subject to all applicable laws and regulations. If any provision of this Agreement is found by any court or other legal authority, or is agreed by the Parties to be, in conflict with any code or regulation governing its subject matter, only the conflicting provision shall be considered null and void. If the effect of nullifying any conflicting provision is such that a material benefit of the Agreement to either Party is lost, the Agreement may be terminated at the option of the

affected Party. In all other cases the remainder of the Agreement shall continue in full force and effect.

63. Entire Agreement Represented: This Agreement represents the entire agreement between the Parties as to its subject matter and no prior oral or written understanding shall be of any force or effect. No part of this Agreement may be modified without the written consent of both Parties.

64. Amendments: This Agreement may be amended or supplemented by an agreement in writing and executed by the authorized representatives of the parties hereto as authorized by resolution of the legislative bodies of the respective parties hereto.

65. Further Assurances: Each party will execute any additional documents and perform any further acts which may be reasonably required to effect the purposes of this Agreement.

66. Successors. This Agreement shall be binding upon and shall inure to the benefit of the successors of the Parties, respectively. No Party may assign any right or obligation hereunder without the written consent of all of the other Party.

THE PARTIES, having read and considered the above provisions, indicate their agreement by their authorized signatures below.

[SIGNATURES ON NEXT PAGE]

//

CUTLER PUBLIC UTILITY DISTRICT

Bernardino Lopez, Board President (date) Martha Lowery, Secretary (date)

As to form:

J. Patrick Sullivan, Esq. (date)

OROSI PUBLIC UTILITY DISTRICT

Alex Marroquin, Board President (date) Maria Elena Vidana, Board Secretary (date)

As to form:

Moses Diaz, Esq. (date)

CUTLER-OROSI SURFACE WATER PLANT AUTHORITY

_____, Board President (date) _____, Board Secretary (date)

As to form:

James Koontz, Esq. (date)

EXHIBIT A
(Specifications)

TOTAL CAPACITY: _____ gallons per day

CAPACITY ALLOCATIONS (as of January 1, 2024)**

Orosi PUD:

Cutler PUD:

**May change on the 25th of each month, based upon reported AF of each of the Parties or other participating entities.

EXHIBIT B
(minimum requirements of water ordinance)

1. Payment of capacity fees;
2. Inventory and inspection of all installed water fixtures;
3. Backflow prevention device installation and testing;
4. No increase in fixture unit demand without written application and approval;
5. No agricultural use.

EXHIBIT C
(milestones)

1. 2024 – Approval of application for funding to SWRCB for project design;
2. 2024 - 30% plans and specifications;
3. 2024 – 60% plans and specifications;
4. 2025 – 100% plans and specifications; and
5. 2025 - Construction and Notice of Completion.

EXHIBIT D
(improvements)

1. Storage tanks for treatment process;
2. Pumps;
3. Master meters;
4. Distribution lines to Cutler, East Orosi and Orosi;
5. Pneumatic tanks for pressurizing;
6. Office and mechanical shop;
7. Emergency back-up generators for entire plant; and
8. Outdoor lighting system.

Appendix E: OPUD Permit and 2021 Sanitary Survey

State Water Resources Control Board

October 26, 2021

Raul Mariscal
Orosi Public Utility District– 5410008
12488 Avenue 416
Orosi, CA 93647

DOMESTIC WATER SUPPLY PERMIT NO. 03-24-21P-002 (REVISIONS)

Dear Mr. Mariscal:

On February 12, 2021, the State Water Resources Control Board Division of Drinking Water (Division) staff conducted an inspection of the Orosi Public Utility District water system (hereinafter “Water System”) with the assistance of Mr. Raul Mariscal.

After evaluation of the Water System and completion of the enclosed Sanitary Survey Report, the State Water Resources Control Board, Division of Drinking Water (Division) finds that in addition to the provisions of the enclosed Domestic Water Supply Permit, the items below are required to be addressed by the Water System.

The items which require attention are:

1. By **December 31, 2021**, an ERP for the Water System must be certified and submit a copy to the Division.
2. By **December 31, 2021**, the Water System must begin monitoring Wells 04 and 05A for nitrate on a quarterly basis.
3. By **November 30, 2021**, the Water System must submit an updated Bacteriological Sample Siting Plan to the Division.
4. By **November 30, 2021**, the Water System must declare the activity status of Well 07 (standby or inactive) and inform the Division of their decision.

If you have any questions regarding the information contained in the sanitary survey, please contact Kristin Willet at 559-447-3300 or email DWPDIST24@waterboards.ca.gov.

Sincerely,

Bryan Potter



Digitally signed by Bryan Potter
Date: 2021.10.26 13:31:58
-07'00'

Bryan Potter, P.E.
Senior WRCE, Tulare District
SOUTHERN CALIFORNIA BRANCH
DRINKING WATER FIELD OPERATIONS

BP/KW
Enclosures

cc: Tulare County Environmental Health Department

STATE OF CALIFORNIA

DOMESTIC WATER SUPPLY PERMIT

Issued To

Orosi Public Utility District

For the Operation of the

Orosi Public Utility District Water System
Water System No. 5410008

By the

State Water Resources Control Board, Division of Drinking Water

PERMIT NUMBER: 03-24-21P-002

DATE: October 26, 2021



WHEREAS:

1. The public water system known as the *Orosi Public Utility District* water system is located north of the City of Visalia, whose mailing address is: 1288 Avenue 416, Orosi, CA. 93647. The Orosi Public Utility District is the legal owner of the water system. Therefore, the Orosi Public Utility District is responsible for compliance with all statutory and regulatory drinking water requirements and the conditions set forth in this revised permit.
2. This revised permit is being issued to *Orosi Public Utility District* for the purpose of providing an updated permit reflecting the current operations of the *Orosi Public Utility District* water system under the regulations of the State of California Health and Safety Code.
3. The public water system for which the revised permit was written is described briefly below (a more detailed description of the permitted system is described in the attached report):

The Orosi Public Utility District's source of supply is groundwater. The water system is classified as a community water system and serves a population of approximately 8,770 through 1,578 service connections. The water supply system serves one pressure zone and consists of five (5) active groundwater sources: Well Nos. 4, 5A, 7, 8, and 10.

And WHEREAS:

1. The Division of Drinking Water has evaluated all the information submitted by *Orosi Public Utility District* and has conducted a physical investigation of the *Orosi Public Utility District* water system.
2. The Division of Drinking Water has the authority to issue domestic water supply permits pursuant to Health and Safety Code Section 116540.

THEREFORE: The Division of Drinking Water has determined the following:

1. The *Orosi Public Utility District* water system meets the criteria for and is hereby classified as a community water system.
2. Provided the following conditions are complied with, the *Orosi Public Utility District* water system should be capable of providing water to consumers that is pure, wholesome, and potable and in compliance with statutory and regulatory drinking water requirements at all times.

THE OROSI PUBLIC UTILITY DISTRICT IS HEREBY ISSUED THIS REVISED DOMESTIC WATER SUPPLY PERMIT TO OPERATE THE OROSI PUBLIC UTILITY DISTRICT WATER SYSTEM.

The Orosi Public Utility District water system shall comply with the following permit conditions:

1. The Orosi Public Utility District shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted thereunder.
2. The only approved sources of domestic water supply for use by the Orosi Public Utility District are as follows:

Source Name	Status	Primary Station Code (PS Code)
Well No. 4	Active	CA5410008_003_003
Well No. 5A	Active	CA5410008_007_007
Well No. 7	Standby	CA5410008_006_006
Well No. 8	Active	CA5410008_008_008
Well No. 10	Active	CA5410008_014_014

3. The only approved treatment for the Orosi Public Utility District is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution.

Source Name	Status	PS Code
Well No. 4	Active	CA5410008_010_010
Well No. 5A	Active	CA5410008_011_011
Well No. 7	Active	CA5410008_012_012
Well No. 8	Active	CA5410008_013_013
Well No. 10	Active	CA5410008_015_015

4. No other sources or treatment (as described in Provisions No. 2 and 3 above) shall be used by the Orosi Public Utility District water system and no changes, additions, or modifications shall be made without prior receipt of an amended domestic water supply permit from the Division.
5. All personnel who operate the distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Orosi Public Utility District water system is classified as a D3 system. The Orosi Public Utility District must have a chief distribution operator who is certified, at a minimum, as a D2 distribution system operator and a shift operator who is certified as a D1 operator or higher. The only treatment provided by the Orosi Public Utility District is continuous chlorination, therefore no treatment operator is required.
6. The Orosi Public Utility District shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The Orosi Public Utility District shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.
7. The Orosi Public Utility District shall submit an Electronic Annual Report each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
8. The Orosi Public Utility District shall record production data from the active sources at least monthly.
9. The Orosi Public Utility District shall collect raw water samples at least monthly from all active wells for analyses of total coliform and fecal coliform or *E. coli* bacteria. The coliform test shall be performed using a density analytical method with results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following month.

10. The Orosi Public Utility District shall monitor for coliform bacteria in the distribution system monthly and in accordance with an approved Bacteriological Sample Siting Plan. The Division shall be notified immediately if either of the following occur:

- a. Any distribution system or source sample shows the presence of *E. coli* bacteria.
- b. The water system exceeds the maximum contaminant level for total coliform bacteria, in which more than one bacteriological sample shows the presence of coliform bacteria during a single month.

11. The Orosi Public Utility District shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The Orosi Public Utility District shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.

12. The Orosi Public Utility District shall conduct Stage 2 Disinfection Byproduct (DBP) monitoring annually. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Codes:

ST2 DBP Monitoring Sites	PS Codes
ST2S1-12910 Walnut Ave.	5410008-900

13. The Orosi Public Utility District shall operate the water system in accordance with a Division-approved Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval.

14. The Orosi Public Utility District water system shall monitor the chlorine residual in the distribution system weekly and report the residuals to the Division monthly using the Chlorine Operational Log form. The Orosi Public Utility District water system shall submit a monthly treatment report to the Division by the 10th day of the following month.

This permit supersedes all previous domestic water supply permits issued for this public water system and shall remain in effect unless and until it is amended, revised, reissued, or declared to be null and void by the Division of Drinking Water. This revised permit is non-transferable. Should the Orosi Public Utility District water system undergo a change of ownership, the new owner must apply for and receive a new domestic water supply permit.

Any change in the source of water for the water system, any addition or modification of the method of treatment as described in the sanitary survey report, or any addition of distribution system storage reservoirs shall not be made unless an application for such change is submitted to the Division of Drinking Water.

This revised permit shall be effective as of the date shown below.

FOR THE DIVISION OF DRINKING WATER

Bryan Potter



Digitally signed by Bryan Potter
Date: 2021.10.26 13:32:20 -07'00'

Bryan Potter, P.E.
Tulare District Engineer

Date

State Water Resources Control Board

DATE: October 26, 2021

TO: Bryan G. Potter, P.E.
Senior Water Resource Control Engineer, Tulare District

FROM: Kristin Willet, P.E.
Water Resource Control Engineer, Tulare District

SUBJECT: Orosi Public Utility District (PUD)
Sanitary Survey – 5410008

I. INTRODUCTION

1.1 PURPOSE OF REPORT

On February 12, 2021, Ms. Kristin Willet with the State Water Resources Control Board, Division of Drinking Water (Division) inspected the Orosi Public Utility District's water system (Water System) with the assistance of Mr. Raul Mariscal, foreman, who oversees water system operations. The purpose of this report is to document the sanitary survey and to describe the existing water supply facilities and current operational practices. The last sanitary survey was conducted by Mr. Andrew Forbes, with the Division, on November 15, 2018.

Domestic Water Supply Permit

The Water System operates under a Domestic Water Supply Permit No. 03-12-12P-008, issued by the Division's Visalia District in July 2012. The purpose of this Sanitary Survey report is to provide and updated inventory of the Water System's facilities, operations, sampling and compliance. The Water System is still subject to the following permit provisions included in Permit No. 03-12-12P-008, listed below:

1. The District shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted thereunder.
2. The only approved sources of domestic water supply for use by the District are listed in the table below.

Approved Sources

Source Name	Status	Primary Station Number
Well No. 4	Active	5410008-003
Well No. 5A	Active	5410008-007
Well No. 7	Active	5410008-006
Well No. 8	Active	5410008-008
Well No. 10	Active	5410008-014

3. The District must provide continuous chlorination of the distribution system.
4. No additions, changes or modifications to the sources of water supply or water treatment processes outlined in Provision No. 2 and 3 can be made without prior receipt of an amended domestic water supply permit from this Department.
5. Under the operator certification regulation, the Orosi Public Utility District's water system is classified as a D2 system. The Orosi Public Utility District must have a chief distribution operator who is certified, at a minimum, as a D2 distribution system operator.
6. The Orosi Public Utility District shall collect raw water samples at least monthly from each active well for analyses of total coliform, fecal coliform or *E. Coli* bacteria. The coliform tests shall be performed using a density analytical method and the results reported in units of MPN/100ml. The results shall be submitted to the Department by the 10th day of the following month.
7. The City of Farmersville shall collect remaining initial water quality monitoring requirements for Well No. 8A. All results shall be submitted to the Department via EDT.
8. Wells No. 6 and 9 are inactive sources and are not approved sources of supply. They shall be locked out or physically disconnected or otherwise isolated from the system so that they open by an intentional act by an operator, and no automatic response, can place the source in service. Inactive wells can be upgraded to standby status if all monitoring is updated to meet standby requirements and the change in status is approved in writing by the Department. Inactive sources can only be used as a last resort in extreme emergencies after all other active sources of supply have been utilized. Any use of an inactive source is subject to the following restrictions.

- a. Emergency notification to the consumers that the water is unsafe for domestic use must be given immediately preceding, and on a continuing basis, during the emergency use of the source.
- b. Initiation of the use of an inactive source must be the result of an intentional manual action by the system operator.
- c. The use of an inactive source shall not be initiated without the knowledge and approval of the Department.
- d. All monitoring as deemed appropriate by the Department shall be required during or immediately following any emergency use of an inactive source.

The provisions included in the active permit are not all-inclusive and some do not reflect the current operations of the District. As a result, a revised permit is required. The revised permit, which accompanies this inspection report, reflects the changes in provisions and describes the current operations of the District.

1.2 DESCRIPTION OF SYSTEM

The Water System serves the census-designated place of Orosi in Tulare County. The Water System is classified as a community water system and serves a permanent resident population of approximately 8,770 people through 1,578 service connections. The Water System consists of four active wells, one standby well, a 750,000-gallon steel storage tank, four 10,000-gallon hydropneumatics pressure tanks, an 8,000-gallon hydropneumatic tank, two 20-hp booster pumps, and the associated distribution system. The Water System is sewered and sewage disposal is provided by the Cutler/Orosi Wastewater Treatment Plant.

1.3 ENFORCEMENT HISTORY

Notice of Violation No. 03-24-21N-002, issued February 11, 2021

The Water System failed to comply with directives of Compliance Order No. 03-24-20R-002.

Compliance Order No. 03-24-20R-002, issued October 2020

The Water System was directed to mandatory consolidate East Orosi Community Services District.

1.4 AREA SERVED

The Water System serves the community of Orosi located in Tulare County. The mailing address for the Water System is 12488 Avenue 416, Orosi, CA, 93647. The Water System serves 1,578 metered service connections and approximately 8,770 people. A locational map is included in Appendix A.

1.5 PRODUCTION DATA

Table 2 summarizes the water production information obtained from the Electronic Annual Reports (EARs) from 2010 through 2020.

Table 2: Water Production Data for the Water System (2010-2020)

Year	Population	Service Connections	Annual Production (MG)	Maximum Month (MG)
2020	8,770	1,579	333.52	41.6 (July)
2019	8,770	1,578	309.45	38.3 (August)
2018	8,770	1,578	312.4	39.2 (July)
2017	8,770	1,578	305.8	37.2 (July)
2016	8,770	1,578	277.8	33.4 (August)
2015	8,770	1,628	305.5	34.24 (August)
2014	8,770	1,628	341	40.2 (July)
2013	8,770	1,624	362.5	44.6 (July)
2012	8,770	1,624	360.6	45.1 (July)
2011	8,770	1,624	346.8	43.6 (July)

II. INVESTIGATION AND FINDINGS

2.1 SOURCES OF SUPPLY

Source Water Assessments

The Source Water Assessment Program (SWAPs) for Wells No. 4, 5A, 7 and 8 were completed in 2003. A SWAP for Well No. 10 was completed in May 2012. The sources are considered vulnerable to low density septic systems, sewer collection systems, agricultural wells, gas stations, and confirmed leaking underground storage tanks. Copies of the SWAPs are on file at the Tulare District Office.

Active Wells:

Well 04, Active – Treated, (CA5410008_003_003)

A DWR Well Completion Report is on file for Well 04. Well 04 was drilled in 1966 to a depth of 425 feet. The borehole contains a 12-inch diameter steel conductor casing to a depth of 425 feet and perforations between 180 and 425 feet. A cement annular seal is provided to a depth of 70 feet. The well is equipped with a 40-hp oil-lubricated deep well turbine (DWT) pump, which can produce approximately 525 gallons per minute (gpm). The oil used for lubrication is a food grade oil. Well 04 discharges directly to a 10,000-gallon hydropneumatics tank and operates based on system pressure. The well is secured in a fenced area and appurtenances include an air-relief vent, and a non-threaded downturned raw water sampling tap on the discharge line of the well.

Well 05A, Active – Treated, (CA5410008_007_007)

A DWR Well Completion Report is on file for Well 05A. Well 05A was drilled in 1990 to a depth of 433 feet. The borehole contains a 12-inch diameter steel conductor casing to a depth of 433 feet and perforations between 200 and 433 feet. A cement annular seal is provided to a depth of 170 feet. The well is equipped with a 50-hp oil-lubricated deep well turbine (DWT) pump, which can produce approximately 525 gallons per minute (gpm). The oil used for lubrication is a food grade oil. Well 05A discharges directly to a 750,000-gallon welded steel storage tank and operates based on the water level in the tank. From the storage tank, the flow passes through booster pumps to the 10,000-gallon hydropneumatic tank and then to the distribution system. The hydropneumatics tank calls the booster pumps to pull water from the storage tank when the pressure in the hydropneumatics tank drops to 47 psi and turns off at 65 psi. The well is secured in a fenced area and appurtenances include an air-relief vent, and a non-threaded downturned raw water sampling tap on the discharge line of the well.

Well 08, Active – Treated, (5410008_008_008)

A DWR Well Completion Report is on file for Well 08. Well 08 was drilled in 1996 to a depth of 473 feet. The borehole contains a 14-inch diameter steel conductor casing to a depth of 473 feet and perforations between 190 and 473 feet. A cement annular seal is provided to a depth of 138 feet. The well is equipped with a 60-hp water-lubricated deep well turbine (DWT) pump, which can produce approximately 750 gallons per minute (gpm). Well 07 discharges directly to a 10,000-gallon hydropneumatic tank and operates based on system pressure. The well is secured in a fenced area and appurtenances include an air-relief vent, and a non-threaded downturned raw water sampling tap on the

discharge line of the well. The well has an on-site emergency auxiliary power generator to provide power to the well in the event of a power outage. The generator requires diesel to function, and the Water System exercises the generator weekly.

Well 10, Active – Treated, (CA5410008_014_014)

A DWR Well Completion Report is on file for Well 10. Well 10 was drilled in 2006 to a depth of 496 feet. The borehole contains a 14-inch diameter steel casing to a depth of 496 feet. Perforations are present between 251 and 496 feet. A cement annular seal is present to a depth of 95 feet. The well is equipped with a 60-hp water-lubricated deep well turbine (DWT) pump, which can produce approximately 800 gallons per minute (gpm). Well 10 discharges directly to a 8,000-gallon hydropneumatic tank and operates based on system pressure. The well is secured in a fenced area and appurtenances include an air-relief vent, and a non-threaded downturned raw water sampling tap on the discharge line of the well. The well has an on-site emergency auxiliary power generator to provide power to the well in the event of a power outage. The generator requires diesel to function, and the Water System exercises the generator weekly.

Standby Source:

Well 07, Standby – Treated, (CA_5410008_006_006)

A DWR Well Completion Report is on file for Well 07. Well 07 was drilled in 1981 to a depth of 390 feet. The borehole contains a 14-inch diameter steel conductor casing to a depth of 390 feet and perforations between 192 and 390 feet. A cement annular seal is provided to a depth of 50 feet. The well is equipped with a 60-hp water-lubricated deep well turbine (DWT) pump, which can produce approximately 750 gallons per minute (gpm). Well 07 discharges directly to a 10,000-gallon storage tank and operates based on system pressure. The well is physically valved off from the distribution system and has to be manually operated as it produces water with 1,2,3-trichloropropane (TCP) and nitrate over the MCL. The well is secured in a fenced area and appurtenances include an air-relief vent, and a non-threaded downturned raw water sampling tap on the discharge line of the well. The well has an on-site emergency auxiliary power generator to provide power to the well in the event of a power outage. The generator requires gas to function, and the Water System exercises the generator weekly.

2.2 ADEQUACY OF SUPPLY

Production data, as reported by the Water System, and peaking factors established in the California Waterworks Standards were used to determine the Water System's Average Day (ADD), Maximum Day (MDD), and Peak Hour Demands (PHD). The adequacy of supply is determined by comparing the Water System's demands with its total source capacity which includes active and standby sources, storage capacity, and emergency interconnections with other water systems. The Water System's ADD, MDD, and PHD for the most recent ten years are provided in Table 3, below.

Table 4 displays the estimated total source capacity of the Water System's active sources. It should be noted that the capacities listed in Table 4 are estimates provided by the Water System.

Table 3: Average Day, Maximum Day and Peak Hour Demand

Year	Average Day Demand (gpm)	Maximum Day Demand (gpm)	Peak Hour Demand (gpm)
2020	635	1,100	1,650
2019	589	1,287	1,930
2018	594	1,317	1,976
2017	582	1,250	1,875
2016	529	1,122	1,684
2015	581	1,149	1,724
2014	649	1,351	2,026
2013	690	1,499	2,248
2012	686	1,516	2,273
2011	660	1,465	2,198
2010	673	3,182	4,773

Table 4: Total Active Source Capacity

Source	Capacity (gpm)
Well 04	525
Well 05A	525
Well 07*	750
Well 08	750
Well 10	800
Total Capacity	2,600

*Well 07 was omitted from the total source capacity calculation based on it having multiple contaminants.

The total active source capacity of the Water System is approximately 2,600 gpm. The Water System currently relies on Well 04 as the primary source of supply and Well 08 as the backup source.

According to California Waterworks Standards, systems serving 1,000 service connections or more should maintain enough capacity including active and standby sources, storage and any emergency connections to provide at least 4-hours PHD. The total source capacity for the Water System is 2,600 gpm and total storage volume is 750,000 gallons. The Water System has sufficient capacity to meet the Water System's maximum day demand (MDD) and estimated peak hour demand (PHD).

2.3 TREATMENT

Continuous Chlorination

The Water System provides continuous chlorination treatment at each of the Water System's active well sites (Wells No. 04, 05A, 08, 10) prior to entering their respective hydropneumatic pressure tank or storage tank. The operator aims to maintain a distribution system free chlorine residual of approximately 0.3 to 0.7-mg/L. The Water System uses 12.5% solution strength ChemChlor sodium hypochlorite solution, which is fed neat into the distribution system. The Water System utilizes a LMI Roytronic Pump (Model #:751-920HI) on Well No. 04, which operates at a maximum condition of 0.65-gallons per hour (gph) at 110-pounds per square inch (psi) and is set at a speed of 25 and stroke at 55. Wells No. 05A, 08, and 10 utilize a Stenner (Model #: 45MHP10) chemical metering pump which has a maximum operating condition of 10-gallons per day (gpd) at 100-psi; with the speeds at each well site set to 5.

2.4 STORAGE

Storage for the Water System is provided primarily by one storage tank, which is approximately 750,000-gallons. The storage tank was installed and approved by the Division in 1995. The tank is in excellent condition and is composed of welded steel. The tank appears to be coated with paint to prevent erosion of the surfaces. The Water System indicated that the storage tank was cleaned and inspected in 2020. The Division recommends that storage tanks be inspected internally at least once every five years to verify the integrity of the tank coating, check the condition of the inside surface of the tank walls, and to clean the tanks as needed.

In addition to the storage tank, the Water System also has a total of four 10,000-gallon hydropneumatic pressure tanks accompanying each well site. The 750,000-gallon steel storage tank is located at the site of Well No. 5A. The low level in the storage tank is 11 feet, at which point Well 05A is called on to fill the storage tank to the high level at 32 feet. Wells No. 04, 05A, 07, and 08 are accompanied by 10,000-gallon hydropneumatic pressure tanks. Well No. 10 is accompanied by an 8,000-gallon hydropneumatic pressure tank. The

operation of Well 05A is controlled by a float gauge in the tank. The remaining wells (04, 08, 10) are controlled by distribution system pressure in the service areas. Well 07 is physically valved off from the distribution system and is operated manually due to 1,2,3-TCP and nitrate exceedance.

2.5 DISTRIBUTION SYSTEM

Water Mains

The distribution system consists of 6-inch to 12-inch diameter cast iron, asbestos cement, PVC, and ductile iron lines. Previous inspection reports indicate that the Water System has five dead-ends and the operator indicated they are flushed quarterly. The Water System has approximately 440 valves which range from 4 to 12-inch in size.

System Repairs

The Water System must follow American Water Works Association (AWWA) standards when there are any repairs, changes, or additions made to the distribution system.

2.6 OPERATION AND MAINTENANCE

The responsible entity of the water system is Orosi Public Utilities District (PUD). Orosi PUD is operated and maintained by Mr. Raul Mariscal. Mr. Mariscal is a certified D2 distribution and T2 treatment operator (Certification Numbers: 20378 and 28107). The operator is responsible for the maintenance and operation of the water system. The Water System's distribution system is classified as a D2 distribution facility.

Cross Connection Control Program

The Water System is required to maintain a Cross Connection Control Program which shall include the following elements (as applied from Title 17, California Code of Regulations, Section 7584):

1. The conducting of surveys to identify water user premises or locations where cross connections are likely to occur,
2. The provisions of backflow protection by the water user at the user's connection or within the user's premises or both,
3. The provision of at least one person trained in cross connection control to carry out the cross-connection program,
4. The establishment of a procedure or system for annual testing of backflow preventers, and

5. The maintenance of records of locations, tests, and repairs of backflow preventers.

Backflow Prevention Device Testing

Regulation requires all backflow prevention devices to be tested annually. Copies of the testing records must be kept on file with the Water System for a minimum of three years.

The last cross-connection control survey of the Water System's distribution system was performed in May 2020 by Michael McKeever, Cross Connection Specialist (AWWA #02183 and ABPA #S05-00202). The survey noted 11 specific backflow devices that needed repair and 18 that needed to be upgraded. The Water System is in the process of addressing these backflow devices.

According to the 2020 EAR, there are 161 backflow prevention assemblies in the distribution system, of which 1 were repaired or replaced in 2020. The EAR reports that 161 backflow prevention devices were tested in 2020 and 1 of them failed.

Complaint program

The Water System must keep records of all complaints received and actions taken to correct the problems related to the complaints. According to the 2020 EAR, the Water System did not receive any complaints in 2020.

Emergency Response Plan (ERP)

On October 23, 2018, America's Water Infrastructure Act (AWIA) was signed into law. AWIA Section 2013 requires community (drinking) water systems serving more than 3,300 people to develop or update risk assessments and emergency response plans (ERPs). **By June 30, 2021, the Water System was required to certify the completion of its risk and resilience assessment on the U.S. EPA site:** <https://www.epa.gov/waterresilience/how-certify-your-risk-and-resilience-assessment-or-emergency-response-plan>. As of the date of this report, Orosi PUD had not certified the completion of its risk and resilience assessment. **Additionally, an ERP for the Water System must be certified and submit a copy to the Division by December 31, 2021.** According to the 2019 EAR, the ERP was last exercised with a tabletop on June 17, 2020. Information for completing a risk assessment and ERP is available on the Water Boards' Water Resiliency – Prepare website: https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/water_resiliency/prepare.html

Consumer Confidence Report (CCR)

The Consumer Confidence Report (CCR) is required to be delivered to all customers within the water system by July 1st of the following year, and a copy of the CCR and certification of publication is due to the Division by October 1st of each year. The Water System submitted the 2019 CCR and the certification form to the Division on June 12, 2020. The Water System must ensure that the CCR and certification of publication are submitted on a timely basis.

Emergency Notification Plan (ENP)

The Water System's Emergency Notification Plan (ENP), submitted in July 2019, lists Mr. Raul Mariscal, Ms. Elena Vidana, and Mr. Dennis Keller as the primary, secondary, and tertiary contacts, respectively, in the event of a water quality emergency. The Water System has specified the use of local media, door to door delivery, and posted notification as the primary modes of notification in the event of a water quality emergency. This would be followed by direct notification via public notices that would be distributed by Water System personnel.

Water System Resiliency and Preparedness

The effects of climate change on community water system (CWS) facilities and operations is a concern and priority of the State Water Resources Control Board (SWRCB), which is documented by the SWRCB in its Comprehensive Climate Change Resolution No. 2017-12, adopted in March 2017. The Division is reviewing each water system's preparedness for climate change with the goal to increase awareness and familiarization to the effects of climate change to facilities and operations, encourage the use of EPA's Climate Resilience Evaluation and Awareness Tool (CREAT) or equivalent, and to document and the CWS' efforts in climate change.

As part of the 2019 EAR, community water systems were asked to identify their vulnerabilities, and rank them as either high or already experiencing, medium, or low sensitivity, and proposed or implemented projects to prepare for the impacts from climate change. The Water System provided responses to these questions indicating that there were none or low sensitivity for all potential vulnerabilities.

The Water System indicated that they were aware of the CREAT tool developed by USEPA for identifying climate change vulnerabilities. The Water System has not used CREAT (or similar tool) to identify vulnerabilities to the water system sources and facilities. The SWRCB strongly encourages utilities

to evaluate climate change vulnerabilities using tools such as CREAT and engaging in a conversation both within your water system organization and with customers on how to plan and prepare for being resilient to provide clean and safe water reliably and adequately under all current and future conditions.

2.7 SOURCE WATER QUALITY MONITORING

The current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>. Instructions for accessing this information is included in Appendix D.

Bacteriological – Raw Water

Due to the implementation of continuous chlorination, raw water bacteriological samples are required to be collected monthly from each active source. The analysis must report the results as a coliform density in MPN/100mL. The Water System has been conducting the required raw water bacteriological monitoring. A summary of the Water System's raw water source monitoring is provided in Appendix C.

California Ground Water Rule Monitoring

The California Ground Water Rule (GWR) requires public water systems to conduct triggered source monitoring whenever a routine distribution system sample is positive for total coliform bacteria.

General Mineral and General Physical

The Water System is required to sample each active well for general mineral and general physical chemicals once every three years. The Water System last conducted general mineral and general physical monitoring from Wells 04 and 05A in August 2019, and Wells 08 and 10 in August 2021. The results for all active wells were below the respective MCLs. Well 07 is on standby and does not require continuous monitoring of general minerals or physical constituents. The next round of general mineral and general physical monitoring is due from Wells 04 and 05A in August 2022, and Wells 08 and 10 in August 2024.

Inorganic Chemicals

The Water System is required to sample each active well for inorganic chemicals every three years, except for nitrate which has a different monitoring frequency as described below. The Water System last conducted inorganic chemical water quality monitoring from all active sources from Wells

04 and 05A in August 2019, and Wells 08 and 10 in August 2021 and the results were all below the respective MCLs. The Water System last conducted inorganic chemical water quality monitoring from Well 07 in August 2016 and all results were below the respective MCLs. The next round of inorganic chemical water quality monitoring is due from Wells 04 and 05A in August 2022, Wells 08 and 10 in August 2024 and Well 07 in 2025.

Nitrate

The Water System is required to monitor active groundwater sources for nitrate (as N) annually if monitoring data indicate nitrate concentrations less than 5 mg/L as N (one-half the MCL of 10 mg/L) and quarterly if the concentrations are greater or equal to 5 mg/L as N (one-half the MCL). The table below shows the most recent results from wells. The next sample due dates are also provided in the table below. **Wells 04 and 05A produced nitrate levels greater than half of the MCL and must begin monitoring for nitrate at these wells on a quarterly basis. Well 07 produced results that exceeded the MCL and must begin monitoring for nitrate quarterly.**

Well No.	Sample Date	Nitrate Result (mg/L)	Nitrate Monitoring Frequency	Nitrate Due Date
04	8/20/2021	5.6	Quarterly	11/2021
05A	8/20/2021	5.4	Quarterly	11/2021
08	8/20/2021	4.7	Annual	08/2022
10	8/20/2021	2.8	Annual	08/2022
07	8/20/2021	12	Quarterly	11/2021

Volatile Organic Chemicals (VOCs)

The Water System is required to conduct volatile organic chemical (VOC) monitoring once every three years for active sources. The Water System last sampled for VOCs from Wells 04, 05A, and 08 in August 2019, and Well 10 in August 2021 and the results were non-detect. Well 07 was sampled for VOCs last in August 2016 and all results were non-detect. The next round of VOC monitoring is due from Wells 04, 05A, and 08 in August 2022, and Well 10 in August 2024, and Well 07 in August 2028.

Synthetic Organic Chemicals (SOCs)

All large community water systems (>3,300 population) are required to conduct two consecutive quarters of synthetic organic chemical (SOC)

monitoring (1,2,3-trichloropropane (1,2,3-TCP), alachlor, atrazine, dibromochloropropane (DBCP), ethylene dibromide (EDB), and simazine) once every three years.

The Water System's active wells were last sampled for all SOC's, except 1,2,3-trichloropropane, in August 2020 and the results were non-detect, except for Well 08 DBCP with a result of 0.018 µg/L, which is below the MCL of 0.2 µg/L. Well 07 was last sampled for SOC's in August 2017 and all results were non-detect, except for DBCP 0.047 µg/L. The Water System has failed to collect the second consecutive quarterly sample set for SOC's. Well 7 is on a 9-year monitoring frequency for SOC's. **The Water System must conduct two consecutive quarters of SOC's, excluding 1,2,3-TCP, monitoring from the active wells in 2023 and every three years thereafter.**

1,2,3-Trichloropropane (1,2,3-TCP)

The Water System last sampled all active wells for 1,2,3-TCP in February 2021 and the results were non-detect. The Water System has placed Well 07 on standby due to the 1,2,3-TCP contamination. Well 07 is next due for 1,2,3-TCP monitoring in 2030. **The next round of 1,2,3-TCP monitoring for active wells is due in 2024 for two consecutive quarters of 1,2,3-TCP monitoring and every three years thereafter.**

Radiological

The initial radiological monitoring is based on the collection of four consecutive quarterly samples for gross alpha and radium-228. If the results from the first two quarters of initial monitoring are below the DLR, the final two quarters of initial monitoring may be waived. After initial monitoring is complete, no additional monitoring is required for radium-228. Subsequent monitoring frequencies for gross alpha is based on the results of the last sample collected.

The Water System has fulfilled the initial radiological monitoring requirements for all sources. As such, monitoring for radium-228 is no longer required. A gross alpha summary of the last sample result and date, monitoring frequency, and next due dates are outlined in Table 5 below. **By December 31, 2021, the Water System must sample Wells 04, 05A, and 10 for gross alpha. If triggered, analyses for uranium and total radium are required from the same sample as noted below.**

Triggered Monitoring:

Uranium:

If the $GA + (0.84 * CE)$ for any single sample is greater than 5 pCi/L, analysis for U in that same sample, is required.

Total Radium:

If the $GA + (0.84 * CE) - U$ is greater than 5 pCi/L, analysis for total radium in that same sample, is required.

Triggered monitoring needs to be communicated to the laboratory on the chain of custody at the time the sample is submitted.

Table 5 – Gross Alpha Monitoring Data

Source	Last Sample Result (pCi/L)	Last Sample Date	Frequency	Next Due Date
Well 04	ND	08/20/2021	Every 9 years	08/2030
Well 05A	ND	08/20/2021	Every 9 years	08/2030
Well 07	5.06	05/20/2020	Every 9 years	2029
Well 08	2.39	05/20/2020	Every 9 years	05/2029
Well 10	ND	08/20/2021	Every 9 years	08/2030

2.8 DISTRIBUTION SYSTEM MONITORING

Bacteriological Water Quality

The Water System is required to collect three bacteriological samples per week, in accordance with an approved Bacteriological Sample Siting Plan (BSSP). The Water System must follow the approved BSSP unless alternative instructions are given by the Division. The Water System indicated that one of the routine sample sites is no longer available. **By November 30, 2021, the Water System must submit an updated BSSP to the Division.** Any time a routine coliform positive sample occurs, the Water System must collect repeat samples from the locations listed in the BSSP within 24-hours. The Water System must notify the Division of any changes or variances to the BSSP. A summary of the Water System's distribution system monitoring since 2018 is provided in Appendix C.

Lead and Copper Rule Monitoring

The Water System completed the initial monitoring requirements and is now allowed to collect the reduced number of 20 triennial samples. The Water System's 90th percentile lead and copper concentrations in the tap water samples should be below the lead and copper action levels of 0.015 mg/L and 1.3 mg/L, respectively. The Water System last conducted lead and copper tap monitoring from the distribution system on July 15, 2020 and the 90th

percentile lead and copper results were non-detect (ND) and 0.12 mg/L, respectively. **The next set of 20 lead and copper tap samples are due to be collected between June 1 and September 30, 2023.**

All future lead and copper monitoring results must be submitted to the Division electronically via the Lab-To-State (LTS) Portal. The Water System must complete and submit a Lead and Copper Tap Sample Results Reporting Form with all subsequent lead and copper monitoring results. A Lead and Copper Tap Sample Results Reporting Form is included in Appendix E.

Lead Service Line Inventory and Replacement

New lead service line replacement regulations became effective September 2016 that require all public water systems to prepare an inventory of known partial or total lead service lines in use in its distribution system. HSC Section 116885 requires the completion of an inventory of the lead service lines by a July 1, 2018, deadline followed by a proposed schedule for replacement of the identified lead service lines by a July 1, 2020, deadline. The legislation is only applicable to community water systems.

The Water System completed a lead service line inventory in June 2020. The total number of service lines inventoried was 1,447, none of which were lead or unknown material.

Disinfection by-Products Rule (DBPR)

Due to the implementation of continuous chlorination, the Water System is required to comply with the Disinfection Byproduct Monitoring Rule (DBPR). To comply with Stage 2 DBPR monitoring requirements, the Water System is required to collect two DBP samples from the distribution system annually during a month of the warmest water temperature. The samples are required to be analyzed for total trihalomethanes (TTHMs) and haloacetic acids (HAA5s). The Water System last monitored for DBPs in August 2021 and all results were non-detect. **The next set of DBPs samples are due to be collected between June 1 and September 30, 2022.**

The results of Stage 2 DBP monitoring are required to be sent to the Division electronically to the Division's electronic database using the PS Code listed in Table 6 below:

Table 6 – Stage 2 DBPs PS Code

ST2 Monitoring Site	PS Code
ST2S1-12910 Walnut Ave.	5410008-900

Asbestos Monitoring

Regulation requires monitoring of systems vulnerable to asbestos contamination within the distribution system at a tap served by asbestos containing pipe. Distribution system monitoring for asbestos is required if asbestos containing pipe is used and the water produced by the sources has an aggressive index of <11.5. The Water System monitored for asbestos in May 2017 from the asbestos-cement piping and results were non-detect. **The next asbestos sample to be collected from the asbestos-cement piping is due in 2026.**

III. APPRAISAL OF SANITARY HAZARD & PUBLIC HEALTH SAFEGUARDS

The Orosi PUD water system is in good overall condition and is capable of supplying safe and potable water to all customers. The Water System presently has four active wells, Wells 04, 05A, 08 and 10, and one standby well, Well 07. The Water System has approximately 750,000-gallons of storage via a steel storage tank.

Well 07 is a standby source and exceeds the 1,2,3-TCP and nitrate MCLs. Well 07 is valved off from the distribution system and is operated manually for sampling. Sources with nitrate contamination cannot remain a standby source. **By November 30, 2021, the Water System must declare the activity status of Well 07 (standby or inactive) and inform the Division of their decision.** Should the Water System decide to keep Well 07 as a standby source, the Water System will be issued a compliance order for the nitrate MCL violation.

In the case of an emergency that requires the use of Well 07, the Water System must contact the Division immediately. If it is normal business hours, the Water System must follow the Emergency Notification Plan.

The Water System records production information and has enough capacity to meet MDD and PHD requirements. If the Water System experiences a power outage, the water system could rely on the storage tank for approximately 6.3 hours until power is restored under peak hour conditions.

Competent supervision is provided over the operation and maintenance practices of the Water System. System operations and reporting practices are adequate.

All laboratory chemical analytical results must be submitted to the Division via EDT with the correct PS Codes. The current water quality monitoring schedule

and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>.

IV. CONCLUSIONS AND RECOMMENDATIONS

Issuance of a Revised Domestic Water Supply Permit by the State Water Resources Control Board, Division of Drinking Water to Orosi Public Utility District for the operation of the Orosi Public Utility District water system is recommended subject to the following provisions:

1. The Orosi Public Utility District shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted thereunder.
2. The only approved sources of domestic water supply for use by the Orosi Public Utility District are as follows:

Source Name	Status	Primary Station Code (PS Code)
Well No. 4	Active	CA5410008_003_003
Well No. 5A	Active	CA5410008_007_007
Well No. 7	Standby	CA5410008_006_006
Well No. 8	Active	CA5410008_008_008
Well No. 10	Active	CA5410008_014_014

3. The only approved treatment for the Orosi Public Utility District is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution.

Source Name	Status	PS Code
Well No. 4	Active	CA5410008_010_010
Well No. 5A	Active	CA5410008_011_011
Well No. 7	Active	CA5410008_012_012
Well No. 8	Active	CA5410008_013_013
Well No. 10	Active	CA5410008_015_015

4. No other sources or treatment (as described in Provisions No. 2 and 3 above) shall be used by the Orosi Public Utility District water system and no

changes, additions, or modifications shall be made without prior receipt of an amended domestic water supply permit from the Division.

5. All personnel who operate the distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Orosi Public Utility District water system is classified as a D3 system. The Orosi Public Utility District must have a chief distribution operator who is certified, at a minimum, as a D2 distribution system operator and a shift operator who is certified as a D1 operator or higher. The only treatment provided by the Orosi Public Utility District is continuous chlorination, therefore no treatment operator is required.
6. The Orosi Public Utility District shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The Orosi Public Utility District shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.
7. The Orosi Public Utility District shall submit an Electronic Annual Report each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
8. The Orosi Public Utility District shall record production data from the active sources at least monthly.
9. The Orosi Public Utility District shall collect raw water samples at least monthly from all active wells for analyses of total coliform and fecal coliform or *E. coli* bacteria. The coliform test shall be performed using a density analytical method with results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following month.
10. The Orosi Public Utility District shall monitor for coliform bacteria in the distribution system monthly and in accordance with an approved Bacteriological Sample Siting Plan. The Division shall be notified immediately if either of the following occur:
 - a. Any distribution system or source sample shows the presence of *E. coli* bacteria.
 - b. The water system exceeds the maximum contaminant level for total coliform bacteria, in which more than one bacteriological sample shows the presence of coliform bacteria during a single month.

11. The Orosi Public Utility District shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The Orosi Public Utility District shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.
12. The Orosi Public Utility District shall conduct Stage 2 Disinfection Byproduct (DBP) monitoring annually. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Codes:

ST2 DBP Monitoring Sites	PS Codes
ST2S1-12910 Walnut Ave.	5410008-900

13. The Orosi Public Utility District shall operate the water system in accordance with a Division-approved Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval.
14. The Orosi Public Utility District water system shall monitor the chlorine residual in the distribution system weekly and report the residuals to the Division monthly using the Chlorine Operational Log form. The Orosi Public Utility District water system shall submit a monthly treatment report to the Division by the 10th day of the following month.

The Water System needs to address the following issues that were noted during the inspection and a subsequent file review:

1. By **December 31, 2021**, an ERP for the Water System must be certified and submit a copy to the Division.
2. By **December 31, 2021**, the Water System must begin monitoring Wells 04 and 05A for nitrate on a quarterly basis.
3. By **November 30, 2021**, the Water System must submit an updated Bacteriological Sampling Siting Plan to the Division.
4. By **November 30, 2021**, the Water System must declare the activity status of Well 07 (standby or inactive) and inform the Division of their decision.

Appendices:

Appendix A: Location Map and Photo Index

Appendix B: Last Sample Date and Monitoring Schedule


Appendix C: Source and Distribution System Bacteriological Monitoring Report

Appendix D: Instructions for Accessing Individual Water System's Water Monitoring
Schedule and Water Quality Data

Appendix E: Lead and Copper Tap Sample Results Reporting Form

Appendix A:
Location Map & Photo Index

Appendix A
Orosi Public Utility District Water System: 5410008



Appendix A

Orosi Public Utility District Water System: 5410008

Well 04: Well 04 was drilled in 1966 to a depth of 425 feet. The borehole contains a 12-inch casing that is perforated between 180 to 425 feet. The well is equipped with a 40-hp deep well turbine (DWT).



Well 05A: Well No. 05A was drilled in 1990 to a depth of 433 feet. The well is equipped with a 50-hp water lubricated DWT. The borehole contains a 12-inch casing that is perforated between 200 and 433-feet.

Well 7: Well No. 7 was drilled in 1981 to a depth of 390 feet. The well is equipped with a 60-hp water-lubricated DWT. The borehole contains a 14-inch casing that is perforated between 192 and 390 feet. The well is equipped with emergency auxiliary power generator to provide power to the well during the outage. The generator is gas powered and is exercised weekly.



Appendix A

Orosi Public Utility District Water System: 5410008

Well 8: Well No. 8 was drilled in 1996 to a depth of 473 feet. The well is equipped with a 60-hp water-lubricated DWT. The borehole contains a 14-inch diameter casing that is perforated between 190 and 473 feet.



Well 10: Well No. 10 was drilled in 2006 to a depth of 496 feet. The well is equipped with a 60-hp water-lubricated DWT. The borehole contains a 14-inch casing perforated between 251 and 496 feet.

Continuous Chlorination Treatment: Each well site features continuous chlorination equipment which consists of a 30-gallon polyethylene solution tank, either a Stenner peristaltic chemical pump or LMI Roytronic Pump, and NSF certified 12.5% liquid sodium hypochlorite. The solution is injected neat into the system. Chlorine residuals range between 0.3 and 0.7 mg/L.



Appendix A

Orosi Public Utility District Water System: 5410008

Hydropneumatic pressure tanks: The Utility District uses 10,000-gallon hydro-pneumatic pressure tanks at each well site to regulate the operation of the well and regulate system pressure. Pressure settings are 40 psi (on) and 60 psi (off). System pressure is typically about 55 psi.



750,000 Gallon Steel Storage Tank: The Utility District uses a 750,000 gallon steel storage tank that is supplied by Well 5A. The tank calls water from the well.



Appendix B:
Last Sample Date & Monitoring Schedule

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 04-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_003_003		OROSI PUBLIC UTILITY DISTRICT					WELL 04-RAW								
	GP	SECONDARY/GP													
		1928 ALKALINITY, BICARBONATE		0.000	190.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1919 CALCIUM		0.000	46.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1929 ALKALINITY, CARBONATE	<	0.000	0.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1017 CHLORIDE		0.000	18.000	0.000	MG/L	500	-----	8/23/2019	3	36		2022/08	
		1905 COLOR	<	0.000	0.000	0.000	UNITS	15	-----	8/23/2019	3	36		2022/08	
		1022 COPPER, FREE	<	50.000	0.000	0.000	UG/L	1000	50	8/23/2019	3	36		2022/08	
		2905 FOAMING AGENTS (SURFACTANTS)	<	0.000	0.000	0.000	MG/L	0.5	-----	8/23/2019	3	36		2022/08	
		1915 HARDNESS, TOTAL (AS CaCO3)		0.000	190.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1021 HYDROXIDE AS CALCIUM CARBONATE	<	0.000	0.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1028 IRON	<	100.000	0.000	0.000	UG/L	300	100	8/23/2019	3	36		2022/08	
		1031 MAGNESIUM		0.000	17.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1032 MANGANESE	<	20.000	0.000	0.000	UG/L	50	20	8/23/2019	3	36		2022/08	
		1920 ODOR	<	1.000	0.000	0.000	TON	3	1	8/23/2019	3	36		2022/08	
		1925 PH		0.000	8.000	0.000		-----	-----	8/23/2019	3	36		2022/08	
		1050 SILVER	<	10.000	0.000	0.000	UG/L	100	10	8/23/2019	3	36		2022/08	
		1052 SODIUM		0.000	23.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1064 CONDUCTIVITY @ 25 C UMHO/CM		0.000	460.000	0.000	US	1600	-----	8/23/2019	7	36		2022/08	
		1055 SULFATE		0.500	13.000	0.000	MG/L	500	0.5	8/23/2019	3	36		2022/08	
		1930 TDS		0.000	310.000	0.000	MG/L	1000	-----	8/23/2019	3	36		2022/08	
		1095 ZINC	<	50.000	0.000	0.000	UG/L	5000	50	8/23/2019	3	36		2022/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 04-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_003_003	IO	INORGANIC													
		1002	ALUMINUM	<	50.000	0.000	UG/L	1000	50	8/23/2019	3	36		2022/08	
		1074	ANTIMONY, TOTAL	<	6.000	0.000	UG/L	6	6	8/23/2019	3	36		2022/08	
		1005	ARSENIC		2.000	2.200	UG/L	10	2	8/23/2019	3	36		2022/08	
		1010	BARIUM	<	100.000	0.000	UG/L	1000	100	8/23/2019	3	36		2022/08	
		1075	BERYLLIUM, TOTAL	<	1.000	0.000	UG/L	4	1	8/23/2019	3	36		2022/08	
		1015	CADMIUM	<	1.000	0.000	UG/L	5	1	8/23/2019	3	36		2022/08	
		1020	CHROMIUM	<	10.000	0.000	UG/L	50	10	8/23/2019	3	36		2022/08	
		1025	FLUORIDE		0.100	0.130	MG/L	2	0.1	8/23/2019	3	36		2022/08	
		1035	MERCURY	<	1.000	0.000	UG/L	2	1	8/23/2019	3	36		2022/08	
		1036	NICKEL	<	10.000	0.000	UG/L	100	10	8/23/2019	3	36		2022/08	
		1039	PERCHLORATE	<	4.000	0.000	UG/L	6	4	8/24/2018	4	36		2021/08	DUE NOW
		1045	SELENIUM	<	5.000	0.000	UG/L	50	5	8/23/2019	3	36		2022/08	
		1085	THALLIUM, TOTAL	<	1.000	0.000	UG/L	2	1	8/23/2019	3	36		2022/08	
	NI	NITRATE/NITRITE													
		1040	NITRATE		0.230	5.600	mg/L	10	0.4	8/20/2021	23	3	Interval	2021/11	
		1041	NITRITE	<	0.400	0.000	mg/L	1	0.4	8/23/2019	3	36		2022/08	
	RA	RADIOLOGICAL													
		4109	GROSS ALPHA PARTICLE ACTIVITY	<	1.390	0.000	PCI/L	15	3	8/20/2021	18	108	Interval	2030/08	
	S1	REGULATED VOC													
		2981	1,1,1-TRICHLOROETHANE	<	0.500	0.000	UG/L	200	0.5	8/23/2019	3	36		2022/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 04-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_003_003	S1	REGULATED VOC													
		2988 1,1,2,2-TETRACHLOROETHANE	<	0.500	0.000	0.000	UG/L	1	0.5	8/23/2019	3	36		2022/08	
		2985 1,1,2-TRICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2978 1,1-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2977 1,1-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	8/23/2019	3	36		2022/08	
		2378 1,2,4-TRICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2968 O-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	600	0.5	8/23/2019	3	36		2022/08	
		2980 1,2-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2983 1,2-DICHLOROPROPANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2413 1,3-DICHLOROPROPENE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2969 P-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2990 BENZENE	<	0.500	0.000	0.000	UG/L	1	0.5	8/23/2019	3	36		2022/08	
		2982 CARBON TETRACHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2380 CIS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	8/23/2019	3	36		2022/08	
		2964 DICHLOROMETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2992 ETHYLBENZENE	<	0.500	0.000	0.000	UG/L	300	0.5	8/23/2019	3	36		2022/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 04-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_003_003	S1	2251 METHYL TERT-BUTYL ETHER	<	3.000	0.000	0.000	UG/L	13	3	8/23/2019	3	36		2022/08	
		2989 CHLOROBENZENE	<	0.500	0.000	0.000	UG/L	70	0.5	8/23/2019	3	36		2022/08	
		2996 STYRENE	<	0.500	0.000	0.000	UG/L	100	0.5	8/23/2019	3	36		2022/08	
		2987 TETRACHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2991 TOLUENE	<	0.500	0.000	0.000	UG/L	150	0.5	8/23/2019	3	36		2022/08	
		2979 TRANS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	10	0.5	8/23/2019	3	36		2022/08	
		2984 TRICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2218 TRICHLOROFLUOROMETHANE	<	5.000	0.000	0.000	UG/L	150	5	8/23/2019	3	36		2022/08	
		2904 TRICHLOROTRIFLUOROETHANE	<	10.000	0.000	0.000	UG/L	1200	10	8/23/2019	3	36		2022/08	
		2976 VINYL CHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2955 XYLENES, TOTAL	<	0.500	0.000	0.000	UG/L	1750	0.5	8/23/2019	3	36		2022/08	
	S2	REGULATED SOC													
		2414 1,2,3-TRICHLOROPROPANE	<	0.001	0.000	0.000	UG/L	0.005	0.005	9/17/2021	66	36		2024/09	
		2051 LASSO (ALACHLOR)	<	1.000	0.000	0.000	UG/L	2	1	8/21/2020	5	36		2023/08	
		2050 ATRAZINE	<	0.500	0.000	0.000	UG/L	1	0.5	8/21/2020	5	36		2023/08	
		2931 1,2-DIBROMO-3-CHLOROPROPANE	<	0.000	0.000	0.000	UG/L	0.2	0.01	8/21/2020	4	36		2023/08	
		2946 ETHYLENE DIBROMIDE	<	0.000	0.000	0.000	UG/L	0.05	0.02	8/21/2020	4	36		2023/08	
		2037 SIMAZINE	<	1.000	0.000	0.000	UG/L	4	1	8/21/2020	5	36		2023/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 07-STBY

CLASS: STCA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_006_006		OROSI PUBLIC UTILITY DISTRICT					WELL 07-STBY								
	IO	INORGANIC													
		1002 ALUMINUM	<	50.000	0.000	0.000	UG/L	1000	50	8/26/2016	2	108		2025/08	
		1074 ANTIMONY, TOTAL	<	6.000	0.000	0.000	UG/L	6	6	8/26/2016	2	108		2025/08	
		1005 ARSENIC	<	2.000	0.000	0.000	UG/L	10	2	8/26/2016	2	108		2025/08	
		1010 BARIUM		100.000	110.000	0.000	UG/L	1000	100	8/26/2016	2	108		2025/08	
		1075 BERYLLIUM, TOTAL	<	1.000	0.000	0.000	UG/L	4	1	8/26/2016	2	108		2025/08	
		1015 CADMIUM	<	1.000	0.000	0.000	UG/L	5	1	8/26/2016	2	108		2025/08	
		1020 CHROMIUM	<	10.000	0.000	0.000	UG/L	50	10	8/26/2016	2	108		2025/08	
		1025 FLUORIDE		0.100	0.130	0.000	MG/L	2	0.1	8/26/2016	2	108		2025/08	
		1035 MERCURY	<	1.000	0.000	0.000	UG/L	2	1	8/26/2016	2	108		2025/08	
		1036 NICKEL	<	10.000	0.000	0.000	UG/L	100	10	8/26/2016	2	108		2025/08	
		1039 PERCHLORATE	<	4.000	0.000	0.000	UG/L	6	4	8/24/2018	4	108		2027/08	
		1045 SELENIUM	<	5.000	0.000	0.000	UG/L	50	5	8/26/2016	2	108		2025/08	
		1085 THALLIUM, TOTAL	<	1.000	0.000	0.000	UG/L	2	1	8/26/2016	2	108		2025/08	
	NI	NITRATE/NITRITE													
		1040 NITRATE		0.230	12.000	0.000	mg/L	10	0.4	9/17/2021	25	3	Interval	2021/12	
		1041 NITRITE	<	0.400	0.000	0.000	mg/L	1	0.4	8/26/2016	2	108		2025/08	
	RA	RADIOLOGICAL													
		4109 GROSS ALPHA PARTICLE ACTIVITY		3.000	3.130	0.000	PCI/L	15	3	5/20/2020	16	108		2029/05	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 07-STBY

CLASS: STCA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_006_006	S1	REGULATED VOC													
		2981 1,1,1-TRICHLOROETHANE	<	0.500	0.000	0.000	UG/L	200	0.5	8/26/2016	2	108		2025/08	
		2988 1,1,2,2-TETRACHLOROETHANE	<	0.500	0.000	0.000	UG/L	1	0.5	8/26/2016	2	108		2025/08	
		2985 1,1,2-TRICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/26/2016	2	108		2025/08	
		2978 1,1-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/26/2016	2	108		2025/08	
		2977 1,1-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	8/26/2016	2	108		2025/08	
		2378 1,2,4-TRICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/26/2016	2	108		2025/08	
		2968 O-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	600	0.5	8/26/2016	2	108		2025/08	
		2980 1,2-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/26/2016	2	108		2025/08	
		2983 1,2-DICHLOROPROPANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/26/2016	2	108		2025/08	
		2413 1,3-DICHLOROPROPENE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/26/2016	2	108		2025/08	
		2969 P-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/26/2016	2	108		2025/08	
		2990 BENZENE	<	0.500	0.000	0.000	UG/L	1	0.5	8/26/2016	2	108		2025/08	
		2982 CARBON TETRACHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/26/2016	2	108		2025/08	
		2380 CIS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	8/26/2016	2	108		2025/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 07-STBY

CLASS: STCA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_006_006	S1	2964	DICHLOROMETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/26/2016	2	108	2025/08	
		2992	ETHYLBENZENE	<	0.500	0.000	0.000	UG/L	300	0.5	8/26/2016	2	108	2025/08	
		2251	METHYL TERT-BUTYL ETHER	<	3.000	0.000	0.000	UG/L	13	3	8/26/2016	2	108	2025/08	
		2989	CHLOROBENZENE	<	0.500	0.000	0.000	UG/L	70	0.5	8/26/2016	2	108	2025/08	
		2996	STYRENE	<	0.500	0.000	0.000	UG/L	100	0.5	8/26/2016	2	108	2025/08	
		2987	TETRACHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/26/2016	2	108	2025/08	
		2991	TOLUENE	<	0.500	0.000	0.000	UG/L	150	0.5	8/26/2016	2	108	2025/08	
		2979	TRANS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	10	0.5	8/26/2016	2	108	2025/08	
		2984	TRICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/26/2016	2	108	2025/08	
		2218	TRICHLOROFLUOROMETHANE	<	5.000	0.000	0.000	UG/L	150	5	8/26/2016	2	108	2025/08	
		2904	TRICHLOROTRIFLUOROETHANE	<	10.000	0.000	0.000	UG/L	1200	10	8/26/2016	2	108	2025/08	
		2976	VINYL CHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/26/2016	2	108	2025/08	
		2955	XYLENES, TOTAL	<	0.500	0.000	0.000	UG/L	1750	0.5	8/26/2016	2	108	2025/08	
	S2	REGULATED SOC													
		2414	1,2,3-TRICHLOROPROPANE		0.001	0.006	0.000	UG/L	0.005	0.005	9/17/2021	71	108	2030/09	
		2051	LASSO (ALACHLOR)	<	1.000	0.000	0.000	UG/L	2	1	8/23/2017	4	108	2026/08	
		2050	ATRAZINE	<	0.500	0.000	0.000	UG/L	1	0.5	8/23/2017	4	108	2026/08	
		2931	1,2-DIBROMO-3-CHLOROPROPANE		0.000	0.047	0.000	UG/L	0.2	0.01	8/1/2017	3	108	2026/08	
		2946	ETHYLENE DIBROMIDE	<	0.000	0.000	0.000	UG/L	0.05	0.02	8/1/2017	3	108	2026/08	
		2037	SIMAZINE	<	1.000	0.000	0.000	UG/L	4	1	8/23/2017	4	108	2026/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 05A-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_007_007		OROSI PUBLIC UTILITY DISTRICT					WELL 05A-RAW								
	GP	SECONDARY/GP													
		1928 ALKALINITY, BICARBONATE		0.000	180.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1919 CALCIUM		0.000	39.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1929 ALKALINITY, CARBONATE	<	0.000	0.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1017 CHLORIDE		0.000	13.000	0.000	MG/L	500	-----	8/23/2019	3	36		2022/08	
		1905 COLOR	<	0.000	0.000	0.000	UNITS	15	-----	8/23/2019	3	36		2022/08	
		1022 COPPER, FREE	<	50.000	0.000	0.000	UG/L	1000	50	8/23/2019	3	36		2022/08	
		2905 FOAMING AGENTS (SURFACTANTS)	<	0.000	0.000	0.000	MG/L	0.5	-----	8/23/2019	3	36		2022/08	
		1915 HARDNESS, TOTAL (AS CaCO3)		0.000	160.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1021 HYDROXIDE AS CALCIUM CARBONATE	<	0.000	0.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1028 IRON	<	100.000	0.000	0.000	UG/L	300	100	8/23/2019	3	36		2022/08	
		1031 MAGNESIUM		0.000	14.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1032 MANGANESE	<	20.000	0.000	0.000	UG/L	50	20	8/23/2019	3	36		2022/08	
		1920 ODOR	<	1.000	0.000	0.000	TON	3	1	8/23/2019	3	36		2022/08	
		1925 PH		0.000	8.000	0.000		-----	-----	8/23/2019	3	36		2022/08	
		1050 SILVER	<	10.000	0.000	0.000	UG/L	100	10	8/23/2019	3	36		2022/08	
		1052 SODIUM		0.000	20.000	0.000	MG/L	-----	-----	8/23/2019	3	36		2022/08	
		1064 CONDUCTIVITY @ 25 C UMHS/CM		1.000	360.000	0.000	US	1600	-----	8/20/2021	8	36		2024/08	
		1055 SULFATE		0.500	8.100	0.000	MG/L	500	0.5	8/23/2019	3	36		2022/08	
		1930 TDS		0.000	290.000	0.000	MG/L	1000	-----	8/23/2019	3	36		2022/08	
		1095 ZINC	<	50.000	0.000	0.000	UG/L	5000	50	8/23/2019	3	36		2022/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 05A-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_007_007	IO	INORGANIC													
		1002	ALUMINUM	<	50.000	0.000	UG/L	1000	50	8/23/2019	3	36		2022/08	
		1074	ANTIMONY, TOTAL	<	6.000	0.000	UG/L	6	6	8/23/2019	3	36		2022/08	
		1005	ARSENIC		2.000	3.400	UG/L	10	2	8/23/2019	3	36		2022/08	
		1010	BARIUM	<	100.000	0.000	UG/L	1000	100	8/23/2019	3	36		2022/08	
		1075	BERYLLIUM, TOTAL	<	1.000	0.000	UG/L	4	1	8/23/2019	3	36		2022/08	
		1015	CADMIUM	<	1.000	0.000	UG/L	5	1	8/23/2019	3	36		2022/08	
		1020	CHROMIUM	<	10.000	0.000	UG/L	50	10	8/23/2019	3	36		2022/08	
		1025	FLUORIDE		0.100	0.120	MG/L	2	0.1	8/23/2019	3	36		2022/08	
		1035	MERCURY	<	1.000	0.000	UG/L	2	1	8/23/2019	3	36		2022/08	
		1036	NICKEL	<	10.000	0.000	UG/L	100	10	8/23/2019	3	36		2022/08	
		1039	PERCHLORATE	<	2.000	0.000	UG/L	6	2	8/20/2021	5	36		2024/08	
		1045	SELENIUM	<	5.000	0.000	UG/L	50	5	8/23/2019	3	36		2022/08	
		1085	THALLIUM, TOTAL	<	1.000	0.000	UG/L	2	1	8/23/2019	3	36		2022/08	
	NI	NITRATE/NITRITE													
		1040	NITRATE		0.230	5.400	mg/L	10	0.4	8/20/2021	20	3	Interval	2021/11	
		1041	NITRITE	<	0.400	0.000	mg/L	1	0.4	8/23/2019	3	36		2022/08	
	RA	RADIOLOGICAL													
		4109	GROSS ALPHA PARTICLE ACTIVITY	<	1.200	0.000	PCI/L	15	3	8/20/2021	18	108	Interval	2030/08	
	S1	REGULATED VOC													
		2981	1,1,1-TRICHLOROETHANE	<	0.500	0.000	UG/L	200	0.5	8/23/2019	3	36		2022/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 05A-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_007_007	S1	REGULATED VOC													
		2988	1,1,2,2-TETRACHLOROETHANE	<	0.500	0.000	UG/L	1	0.5	8/23/2019	3	36		2022/08	
		2985	1,1,2-TRICHLOROETHANE	<	0.500	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2978	1,1-DICHLOROETHANE	<	0.500	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2977	1,1-DICHLOROETHYLENE	<	0.500	0.000	UG/L	6	0.5	8/23/2019	3	36		2022/08	
		2378	1,2,4-TRICHLOROBENZENE	<	0.500	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2968	O-DICHLOROBENZENE	<	0.500	0.000	UG/L	600	0.5	8/23/2019	3	36		2022/08	
		2980	1,2-DICHLOROETHANE	<	0.500	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2983	1,2-DICHLOROPROPANE	<	0.500	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2413	1,3-DICHLOROPROPENE	<	0.500	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2969	P-DICHLOROBENZENE	<	0.500	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2990	BENZENE	<	0.500	0.000	UG/L	1	0.5	8/23/2019	3	36		2022/08	
		2982	CARBON TETRACHLORIDE	<	0.500	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2380	CIS-1,2-DICHLOROETHYLENE	<	0.500	0.000	UG/L	6	0.5	8/23/2019	3	36		2022/08	
		2964	DICHLOROMETHANE	<	0.500	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2992	ETHYLBENZENE	<	0.500	0.000	UG/L	300	0.5	8/23/2019	3	36		2022/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 05A-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_007_007	S1	2251 METHYL TERT-BUTYL ETHER	<	3.000	0.000	0.000	UG/L	13	3	8/23/2019	3	36		2022/08	
		2989 CHLOROBENZENE	<	0.500	0.000	0.000	UG/L	70	0.5	8/23/2019	3	36		2022/08	
		2996 STYRENE	<	0.500	0.000	0.000	UG/L	100	0.5	8/23/2019	3	36		2022/08	
		2987 TETRACHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2991 TOLUENE	<	0.500	0.000	0.000	UG/L	150	0.5	8/23/2019	3	36		2022/08	
		2979 TRANS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	10	0.5	8/23/2019	3	36		2022/08	
		2984 TRICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2218 TRICHLOROFLUOROMETHANE	<	5.000	0.000	0.000	UG/L	150	5	8/23/2019	3	36		2022/08	
		2904 TRICHLOROTRIFLUOROETHANE	<	10.000	0.000	0.000	UG/L	1200	10	8/23/2019	3	36		2022/08	
		2976 VINYL CHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2955 XYLENES, TOTAL	<	0.500	0.000	0.000	UG/L	1750	0.5	8/23/2019	3	36		2022/08	
	S2	REGULATED SOC													
		2414 1,2,3-TRICHLOROPROPANE	<	0.001	0.000	0.000	UG/L	0.005	0.005	9/17/2021	63	36		2024/09	
		2051 LASSO (ALACHLOR)	<	1.000	0.000	0.000	UG/L	2	1	8/21/2020	4	36		2023/08	
		2050 ATRAZINE	<	0.500	0.000	0.000	UG/L	1	0.5	8/21/2020	4	36		2023/08	
		2931 1,2-DIBROMO-3-CHLOROPROPANE	<	0.000	0.000	0.000	UG/L	0.2	0.01	8/21/2020	4	36		2023/08	
		2946 ETHYLENE DIBROMIDE	<	0.000	0.000	0.000	UG/L	0.05	0.02	8/21/2020	4	36		2023/08	
		2037 SIMAZINE	<	1.000	0.000	0.000	UG/L	4	1	8/21/2020	4	36		2023/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 08-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_008_008		OROSI PUBLIC UTILITY DISTRICT					WELL 08-RAW								
	GP	SECONDARY/GP													
		1928 ALKALINITY, BICARBONATE		3.000	140.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1919 CALCIUM		0.100	38.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1929 ALKALINITY, CARBONATE	<	3.000	0.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1017 CHLORIDE		1.000	19.000	0.000	MG/L	500	-----	8/20/2021	4	36		2024/08	
		1905 COLOR	<	5.000	0.000	0.000	UNITS	15	-----	8/20/2021	4	36		2024/08	
		1022 COPPER, FREE	<	5.000	0.000	0.000	UG/L	1000	50	8/20/2021	4	36		2024/08	
		2905 FOAMING AGENTS (SURFACTANTS)	<	0.050	0.000	0.000	MG/L	0.5	-----	8/20/2021	4	36		2024/08	
		1915 HARDNESS, TOTAL (AS CaCO3)		0.410	150.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1021 HYDROXIDE AS CALCIUM CARBONATE	<	3.000	0.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1028 IRON	<	30.000	0.000	0.000	UG/L	300	100	8/20/2021	4	36		2024/08	
		1031 MAGNESIUM		0.100	13.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1032 MANGANESE	<	10.000	0.000	0.000	UG/L	50	20	8/20/2021	4	36		2024/08	
		1920 ODOR	<	1.000	0.000	0.000	TON	3	1	8/20/2021	4	36		2024/08	
		1925 PH		0.000	8.000	0.000		-----	-----	8/20/2021	4	36		2024/08	
		1050 SILVER	<	10.000	0.000	0.000	UG/L	100	10	8/20/2021	4	36		2024/08	
		1052 SODIUM		1.000	20.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1064 CONDUCTIVITY @ 25 C UMHS/CM		1.000	380.000	0.000	US	1600	-----	8/20/2021	5	36		2024/08	
		1055 SULFATE		1.000	10.000	0.000	MG/L	500	0.5	8/20/2021	4	36		2024/08	
		1930 TDS		5.000	280.000	0.000	MG/L	1000	-----	8/20/2021	4	36		2024/08	
		1095 ZINC	<	50.000	0.000	0.000	UG/L	5000	50	8/20/2021	4	36		2024/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 08-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_008_008	IO	INORGANIC													
		1002	ALUMINUM	<	50.000	0.000	UG/L	1000	50	8/20/2021	4	36		2024/08	
		1074	ANTIMONY, TOTAL	<	2.000	0.000	UG/L	6	6	8/20/2021	4	36		2024/08	
		1005	ARSENIC		2.000	2.800	UG/L	10	2	8/20/2021	4	36		2024/08	
		1010	BARIUM		50.000	66.000	UG/L	1000	100	8/20/2021	4	36		2024/08	
		1075	BERYLLIUM, TOTAL	<	1.000	0.000	UG/L	4	1	8/20/2021	4	36		2024/08	
		1015	CADMIUM	<	1.000	0.000	UG/L	5	1	8/20/2021	4	36		2024/08	
		1020	CHROMIUM	<	10.000	0.000	UG/L	50	10	8/20/2021	4	36		2024/08	
		1025	FLUORIDE		0.100	0.160	MG/L	2	0.1	8/20/2021	4	36		2024/08	
		1035	MERCURY	<	0.200	0.000	UG/L	2	1	8/20/2021	4	36		2024/08	
		1036	NICKEL	<	10.000	0.000	UG/L	100	10	8/20/2021	4	36		2024/08	
		1039	PERCHLORATE	<	2.000	0.000	UG/L	6	2	8/20/2021	5	36		2024/08	
		1045	SELENIUM	<	2.000	0.000	UG/L	50	5	8/20/2021	4	36		2024/08	
		1085	THALLIUM, TOTAL	<	1.000	0.000	UG/L	2	1	8/20/2021	4	36		2024/08	
	NI	NITRATE/NITRITE													
		1040	NITRATE		0.230	4.700	mg/L	10	0.4	8/20/2021	25	12		2022/08	
		1041	NITRITE	<	0.050	0.000	mg/L	1	0.4	8/20/2021	4	36		2024/08	
	RA	RADIOLOGICAL													
		4109	GROSS ALPHA PARTICLE ACTIVITY		3.000	-0.440	PCI/L	15	3	5/20/2020	9	108	Interval	2029/05	
	S1	REGULATED VOC													
		2981	1,1,1-TRICHLOROETHANE	<	0.500	0.000	UG/L	200	0.5	8/23/2019	3	36		2022/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 08-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_008_008	S1	REGULATED VOC													
		2988 1,1,2,2-TETRACHLOROETHANE	<	0.500	0.000	0.000	UG/L	1	0.5	8/23/2019	3	36		2022/08	
		2985 1,1,2-TRICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2978 1,1-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2977 1,1-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	8/23/2019	3	36		2022/08	
		2378 1,2,4-TRICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2968 O-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	600	0.5	8/23/2019	3	36		2022/08	
		2980 1,2-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2983 1,2-DICHLOROPROPANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2413 1,3-DICHLOROPROPENE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2969 P-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2990 BENZENE	<	0.500	0.000	0.000	UG/L	1	0.5	8/23/2019	3	36		2022/08	
		2982 CARBON TETRACHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2380 CIS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	8/23/2019	3	36		2022/08	
		2964 DICHLOROMETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2992 ETHYLBENZENE	<	0.500	0.000	0.000	UG/L	300	0.5	8/23/2019	3	36		2022/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 08-RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_008_008	S1	2251 METHYL TERT-BUTYL ETHER	<	3.000	0.000	0.000	UG/L	13	3	8/23/2019	3	36		2022/08	
		2989 CHLOROBENZENE	<	0.500	0.000	0.000	UG/L	70	0.5	8/23/2019	3	36		2022/08	
		2996 STYRENE	<	0.500	0.000	0.000	UG/L	100	0.5	8/23/2019	3	36		2022/08	
		2987 TETRACHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2991 TOLUENE	<	0.500	0.000	0.000	UG/L	150	0.5	8/23/2019	3	36		2022/08	
		2979 TRANS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	10	0.5	8/23/2019	3	36		2022/08	
		2984 TRICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/23/2019	3	36		2022/08	
		2218 TRICHLOROFLUOROMETHANE	<	5.000	0.000	0.000	UG/L	150	5	8/23/2019	3	36		2022/08	
		2904 TRICHLOROTRIFLUOROETHANE	<	10.000	0.000	0.000	UG/L	1200	10	8/23/2019	3	36		2022/08	
		2976 VINYL CHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/23/2019	3	36		2022/08	
		2955 XYLENES, TOTAL	<	0.500	0.000	0.000	UG/L	1750	0.5	8/23/2019	3	36		2022/08	
	S2	REGULATED SOC													
		2414 1,2,3-TRICHLOROPROPANE	<	0.001	0.000	0.000	UG/L	0.005	0.005	9/17/2021	68	36		2024/09	
		2051 LASSO (ALACHLOR)	<	1.000	0.000	0.000	UG/L	2	1	8/21/2020	5	36		2023/08	
		2050 ATRAZINE	<	0.500	0.000	0.000	UG/L	1	0.5	8/21/2020	5	36		2023/08	
		2931 1,2-DIBROMO-3-CHLOROPROPANE		0.000	0.018	0.000	UG/L	0.2	0.01	8/21/2020	4	36		2023/08	
		2946 ETHYLENE DIBROMIDE	<	0.000	0.000	0.000	UG/L	0.05	0.02	8/21/2020	4	36		2023/08	
		2037 SIMAZINE	<	1.000	0.000	0.000	UG/L	4	1	8/21/2020	5	36		2023/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 10 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_014_014		OROSI PUBLIC UTILITY DISTRICT					WELL 10 - RAW								
	GP	SECONDARY/GP													
		1928 ALKALINITY, BICARBONATE		3.000	120.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1919 CALCIUM		0.100	28.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1929 ALKALINITY, CARBONATE	<	3.000	0.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1017 CHLORIDE		1.000	14.000	0.000	MG/L	500	-----	8/20/2021	4	36		2024/08	
		1905 COLOR	<	5.000	0.000	0.000	UNITS	15	-----	8/20/2021	4	36		2024/08	
		1022 COPPER, FREE	<	5.000	0.000	0.000	UG/L	1000	50	8/20/2021	4	36		2024/08	
		2905 FOAMING AGENTS (SURFACTANTS)	<	0.050	0.000	0.000	MG/L	0.5	-----	8/20/2021	4	36		2024/08	
		1915 HARDNESS, TOTAL (AS CaCO3)		0.410	120.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1021 HYDROXIDE AS CALCIUM CARBONATE	<	3.000	0.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1028 IRON		30.000	42.000	0.000	UG/L	300	100	8/20/2021	4	36		2024/08	
		1031 MAGNESIUM		0.100	12.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1032 MANGANESE	<	10.000	0.000	0.000	UG/L	50	20	8/20/2021	4	36		2024/08	
		1920 ODOR	<	1.000	0.000	0.000	TON	3	1	8/20/2021	4	36		2024/08	
		1925 PH		0.000	7.900	0.000		-----	-----	8/20/2021	4	36		2024/08	
		1050 SILVER	<	10.000	0.000	0.000	UG/L	100	10	8/20/2021	4	36		2024/08	
		1052 SODIUM		1.000	17.000	0.000	MG/L	-----	-----	8/20/2021	4	36		2024/08	
		1064 CONDUCTIVITY @ 25 C UMHS/CM		1.000	310.000	0.000	US	1600	-----	8/20/2021	6	36		2024/08	
		1055 SULFATE		1.000	2.800	0.000	MG/L	500	0.5	8/20/2021	4	36		2024/08	
		1930 TDS		5.000	240.000	0.000	MG/L	1000	-----	8/20/2021	4	36		2024/08	
		1095 ZINC	<	50.000	0.000	0.000	UG/L	5000	50	8/20/2021	4	36		2024/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 10 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_014_014	IO	INORGANIC													
		1002	ALUMINUM	<	50.000	0.000	UG/L	1000	50	8/20/2021	4	36		2024/08	
		1074	ANTIMONY, TOTAL	<	2.000	0.000	UG/L	6	6	8/20/2021	4	36		2024/08	
		1005	ARSENIC		2.000	2.600	UG/L	10	2	8/20/2021	4	36		2024/08	
		1010	BARIUM		50.000	57.000	UG/L	1000	100	8/20/2021	4	36		2024/08	
		1075	BERYLLIUM, TOTAL	<	1.000	0.000	UG/L	4	1	8/20/2021	4	36		2024/08	
		1015	CADMIUM	<	1.000	0.000	UG/L	5	1	8/20/2021	4	36		2024/08	
		1020	CHROMIUM	<	10.000	0.000	UG/L	50	10	8/20/2021	4	36		2024/08	
		1025	FLUORIDE		0.100	0.160	MG/L	2	0.1	8/20/2021	4	36		2024/08	
		1035	MERCURY	<	0.200	0.000	UG/L	2	1	8/20/2021	4	36		2024/08	
		1036	NICKEL	<	10.000	0.000	UG/L	100	10	8/20/2021	4	36		2024/08	
		1039	PERCHLORATE	<	2.000	0.000	UG/L	6	2	8/20/2021	5	36		2024/08	
		1045	SELENIUM	<	2.000	0.000	UG/L	50	5	8/20/2021	4	36		2024/08	
		1085	THALLIUM, TOTAL	<	1.000	0.000	UG/L	2	1	8/20/2021	4	36		2024/08	
	NI	NITRATE/NITRITE													
		1040	NITRATE		0.230	2.800	mg/L	10	0.4	8/20/2021	21	12		2022/08	
		1041	NITRITE	<	0.050	0.000	mg/L	1	0.4	8/20/2021	4	36		2024/08	
	RA	RADIOLOGICAL													
		4109	GROSS ALPHA PARTICLE ACTIVITY	<	1.430	0.000	PCI/L	15	3	8/20/2021	5	108	Interval	2030/08	
	S1	REGULATED VOC													
		2981	1,1,1-TRICHLOROETHANE	<	0.500	0.000	UG/L	200	0.5	8/20/2021	5	36		2024/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 10 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_014_014	S1	REGULATED VOC													
		2988 1,1,2,2-TETRACHLOROETHANE	<	0.500	0.000	0.000	UG/L	1	0.5	8/20/2021	5	36		2024/08	
		2985 1,1,2-TRICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/20/2021	5	36		2024/08	
		2978 1,1-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/20/2021	5	36		2024/08	
		2977 1,1-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	8/20/2021	5	36		2024/08	
		2378 1,2,4-TRICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/20/2021	5	36		2024/08	
		2968 O-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	600	0.5	8/20/2021	5	36		2024/08	
		2980 1,2-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/20/2021	5	36		2024/08	
		2983 1,2-DICHLOROPROPANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/20/2021	5	36		2024/08	
		2413 1,3-DICHLOROPROPENE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/20/2021	5	36		2024/08	
		2969 P-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/20/2021	5	36		2024/08	
		2990 BENZENE	<	0.500	0.000	0.000	UG/L	1	0.5	8/20/2021	5	36		2024/08	
		2982 CARBON TETRACHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/20/2021	5	36		2024/08	
		2380 CIS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	8/20/2021	5	36		2024/08	
		2964 DICHLOROMETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	8/20/2021	5	36		2024/08	
		2992 ETHYLBENZENE	<	0.500	0.000	0.000	UG/L	300	0.5	8/20/2021	5	36		2024/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: WELL 10 - RAW

CLASS: CLGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_014_014	S1	2251 METHYL TERT-BUTYL ETHER	<	0.500	0.000	0.000	UG/L	13	3	8/20/2021	6	36		2024/08	
		2989 CHLOROBENZENE	<	0.500	0.000	0.000	UG/L	70	0.5	8/20/2021	5	36		2024/08	
		2996 STYRENE	<	0.500	0.000	0.000	UG/L	100	0.5	8/20/2021	5	36		2024/08	
		2987 TETRACHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/20/2021	5	36		2024/08	
		2991 TOLUENE	<	0.500	0.000	0.000	UG/L	150	0.5	8/20/2021	5	36		2024/08	
		2979 TRANS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	10	0.5	8/20/2021	5	36		2024/08	
		2984 TRICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	8/20/2021	5	36		2024/08	
		2218 TRICHLOROFLUOROMETHANE	<	5.000	0.000	0.000	UG/L	150	5	8/20/2021	5	36		2024/08	
		2904 TRICHLOROTRIFLUOROETHANE	<	10.000	0.000	0.000	UG/L	1200	10	8/20/2021	5	36		2024/08	
		2976 VINYL CHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	8/20/2021	5	36		2024/08	
		2955 XYLENES, TOTAL	<	0.500	0.000	0.000	UG/L	1750	0.5	8/20/2021	5	36		2024/08	
	S2	REGULATED SOC													
		2414 1,2,3-TRICHLOROPROPANE	<	0.001	0.000	0.000	UG/L	0.005	0.005	9/17/2021	68	36		2024/09	
		2051 LASSO (ALACHLOR)	<	1.000	0.000	0.000	UG/L	2	1	8/21/2020	7	36		2023/08	
		2050 ATRAZINE	<	0.500	0.000	0.000	UG/L	1	0.5	8/21/2020	7	36		2023/08	
		2931 1,2-DIBROMO-3-CHLOROPROPANE	<	0.010	0.000	0.000	UG/L	0.2	0.01	8/20/2021	6	36		2024/08	
		2946 ETHYLENE DIBROMIDE	<	0.020	0.000	0.000	UG/L	0.05	0.02	8/20/2021	6	36		2024/08	
		2037 SIMAZINE	<	1.000	0.000	0.000	UG/L	4	1	8/21/2020	7	36		2023/08	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: OROSI PUBLIC UTILITY DISTRICT

COUNTY: TULARE

Sample Point: ST2S1-12910 WALNUT AVE

CLASS: DBPA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5410008_ DST_900		OROSI PUBLIC UTILITY DISTRICT					ST2S1-12910 WALNUT AVE								
	DBP	DISINFECTION BYPRODUCTS													
		2943 BROMODICHLOROMETHANE	<	0.500	0.000	0.000	UG/L	-----	1	8/11/2021	8	12		2022/08	
		2942 BROMOFORM		0.500	0.780	0.000	UG/L	-----	1	8/11/2021	8	12		2022/08	
		2941 CHLOROFORM	<	0.500	0.000	0.000	UG/L	-----	1	8/11/2021	8	12		2022/08	
		2454 DIBROMOACETIC ACID	<	1.000	0.000	0.000	UG/L	-----	1	8/11/2021	8	12		2022/08	
		2944 DIBROMOCHLOROMETHANE	<	0.500	0.000	0.000	UG/L	-----	1	8/11/2021	8	12		2022/08	
		2451 DICHLOROACETIC ACID	<	1.000	0.000	0.000	UG/L	-----	1	8/11/2021	8	12		2022/08	
		2456 TOTAL HALOACETIC ACIDS (HAA5)	<	2.000	0.000	0.000	UG/L	60	-----	8/11/2021	8	12		2022/08	
		2453 MONOBROMOACETIC ACID	<	1.000	0.000	0.000	UG/L	-----	1	8/11/2021	8	12		2022/08	
		2450 MONOCHLOROACETIC ACID	<	2.000	0.000	0.000	UG/L	-----	2	8/11/2021	8	12		2022/08	
		2950 TTHM		0.500	0.780	0.000	UG/L	80	-----	8/11/2021	8	12		2022/08	
		2452 TRICHLOROACETIC ACID	<	1.000	0.000	0.000	UG/L	-----	1	8/11/2021	8	12		2022/08	

Appendix C:
Source Water and Distribution System Bacteriological Monitoring Reports

Bacteriological Distribution Monitoring Report

5410008 Orosi Public Utility District

Distribution System Freq: 3/W

Sample Date	Location	T Coli	E Coli	F Coli	HPC	Type	Cl2	Cl2 Avg	Viol. Type	GWR Satisfied?	Comments
9/28/2021	12924 Risley Ave	A	A			Routine	0.47				
9/28/2021	12490 Ella Ave	A	A			Routine	0.84				
9/28/2021	12494 Albert Ave	A	A			Routine	0.72				
9/21/2021	12555 Ave 417	A	A			Routine	0.58				
9/21/2021	12461 Barton Ave	A	A			Routine	0.69				
9/21/2021	12910 Walnut Ave	A	A			Routine	0.75				
9/14/2021	12924 Risely Ave	A	A				0.47				
9/14/2021	12490 Ella Ave	A	A				0.51				
9/14/2021	12494 Albert Ave	A	A				0.67				
9/7/2021	12555 Ave 417	A	A				0.76				
9/7/2021	12461 Barton Ave	A	A				0.62				
9/7/2021	12910 Walnut Ave	A	A				0.71				
8/31/2021	12924 Risley Ave	A	A			Routine	0.59				
8/31/2021	12490 Ella Ave	A	A			Routine	0.77				
8/31/2021	12494 Albert Ave	A	A			Routine	0.78				
8/24/2021	12555 Ave 417	A	A			Routine	0.69				
8/24/2021	12461 Barton Ave	A	A			Routine	0.36				
8/24/2021	12910 Walnut Ave	A	A			Routine	0.63				
8/17/2021	12924 Risley Ave	A	A			Routine	0.63				
8/17/2021	Tank Well #5	A	A			Routine	0.85				
8/17/2021	12490 Ella Ave	A	A			Routine	0.91				
8/17/2021	12494 Albert Ave	A	A			Routine	0.97				
8/12/2021	12461 Barton Ave	A	A			Repeat	0.39				
8/12/2021	12438 Barton Ave	A	A			Other	0.4				
8/12/2021	12487 Barton Ave	A	A			Other	0.34				
8/12/2021	Well #5	A	A			Other				Yes	
8/12/2021	Well #8	A	A			Other				Yes	
8/12/2021	Well #10	A	A			Other				Yes	
8/12/2021	Well #4	A	A			Other				Yes	
8/10/2021	12555 Ave 417	A	A			Routine	0.58				
8/10/2021	12461 Barton Ave	A	P			Routine	0.41				
8/10/2021	12910 Walnut Ave	A	A			Routine	0.71				
8/3/2021	12924 Risley Ave.	A	A			Routine	0.72				
8/3/2021	12490 Ella Ave.	A	A			Routine	0.79				
8/3/2021	12494 Albert Ave.	A	A			Routine	0.92				
7/27/2021	12555 Ave 417	A	A			Routine	0.84				
7/27/2021	12461 Barton Ave	A	A			Routine	0.32				
7/27/2021	12910 Walnut Ave	A	A			Routine	0.42				
7/20/2021	3 samples	A	A			Routine	0.48-0.56				
7/13/2021	3 samples	A	A			Routine	0.44-0.61				
7/6/2021	3 samples	A	A			Routine	0.61-0.80				
6/29/2021	3 samples	A	A			Routine	0.21-0.88				
6/22/2021	3 samples	A	A			Routine	0.77-0.87				
6/15/2021	3 samples	A	A			Routine	0.59-0.60				
6/8/2021	3 samples	A	A			Routine	0.62-0.70				
6/1/2021	3 samples	A	A			Routine	0.72-0.76				
5/25/2021	3 samples	A	A			Other					
5/25/2021	3 samples	A	A			Routine					
5/18/2021	3 samples	A	A			Other					
5/18/2021	3 samples	A	A			Routine					

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>CI2</i>	<i>CI2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
5/11/2021	3 samples	A	A			Routine					
5/11/2021	Tank Well 5	A	A			Other	0.69				
5/4/2021	3 samples	A	A			Routine					
4/27/2021	3 samples	A	A			Routine					
4/20/2021	3 samples	A	A			Routine					
4/14/2021	Fire Hydrant Walnut St	A	A			Other	0.54				
4/14/2021	Fire Hydrant Maple St	A	A			Other	0.66				
4/14/2021	Fire Hydrant Ave 413	A	A			Other	0.65				
4/13/2021	3 samples	A	A			Routine					
4/13/2021	Fire Hydrant Walnut St	A	A			Other	0.68				
4/13/2021	Fire Hydrant Maple St	A	A			Other	0.56				
4/13/2021	Fire Hydrant Ave 413	A	A			Other	0.53				
4/6/2021	3 samples	A	A			Routine					
3/30/2021	3 samples	A	A			Routine					
3/23/2021	3 samples	A	A			Routine					
3/16/2021	3 samples	A	A			Routine					
3/9/2021	3 samples	A	A			Routine					
3/2/2021	3 samples	A	A			Routine	0.68-0.79				
2/23/2021	3 samples	A	A			Routine					
2/16/2021	3 samples	A	A			Routine					
2/9/2021	3 samples	A	A			Routine					
2/2/2021	3 samples	A	A			Routine					
2/2/2021	3 samples	A	A			Routine					
1/26/2021	3 samples	A	A			Routine					
1/19/2021	3 samples	A	A			Routine					
1/12/2021	3 samples	A	A			Routine	0.51-0.72				
1/5/2021	3 samples	A	A			Routine	0.72-0.83				
12/29/2020	3 samples	A	A			Routine	0.40-0.94				
12/22/2020	3 samples	A	A			Routine					
12/15/2020	3 samples	A	A			Routine					
12/8/2020	3 samples	A	A			Routine					
12/1/2020	3 samples	A	A			Routine					
11/24/2020	3 Samples	A	A			Routine	0.54-0.91				
11/17/2020	3 samples	A	A			Routine	0.38-0.69				
11/10/2020	3 samples	A	A			Routine					
11/3/2020	3 samples	A	A			Routine					
10/27/2020	2 samples	A	A			Routine					
10/27/2020	3 samples	A	A			Routine					
10/20/2020	3 samples	A	A			Routine					
10/13/2020	3 samples	A	A			Routine	0.56-0.76				
10/13/2020	Tank @ Well 5	A	A			Other	0.73				
10/6/2020	3 samples	A	A			Routine	0.27-0.74				
9/29/2020	3 samples	A	A			Routine	0.67-0.99				
9/22/2020	3 samples	A	A			Routine	0.12-0.50				
9/15/2020	3 samples	A	A			Routine	0.8-0.85				
9/8/2020	3 samples	A	A			Routine	0.52-0.61				
9/1/2020	3 samples	A	A			Routine					
8/25/2020	3 samples	A	A			Routine					
8/18/2020	3 samples	A	A			Routine					
8/11/2020	3 samples	A	A			Routine					

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>CI2</i>	<i>CI2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
8/11/2020	Tank @ Well 5	A	A			Other	0.73				
8/4/2020	3 samples	A	A			Routine					
7/28/2020	3 samples	A	A			Routine					
7/21/2020	3 samples	A	A			Routine					
7/16/2020	Wells: 4,5,8,10	A	A			Source Repeat				Y	GWR satisfied
7/16/2020	12555 Ave 417	A	A			Repeat	0.41				
7/16/2020	12526 Ave 417	A	A			Repeat	0.42				
7/16/2020	12589 Ave 417	A	A			Repeat	0.45				
7/14/2020	2 samples	A	A			Routine	0.42-0.51				
7/14/2020	12555 Ave 417	P	A			Routine	0.48				
7/7/2020	3 samples	A	A			Routine	0.64-0.86				
6/30/2020	3 samples	A	A			Routine					
6/23/2020	3 samples	A	A			Routine					
6/16/2020	3 samples	A	A			Routine	0.66-0.73				
6/9/2020	3 samples	A	A			Routine	0.39-0.51				
6/2/2020	3 samples	A	A			Routine					
5/26/2020	3 samples	A	A			Routine	0.62-0.67				
5/26/2020	3 samples	A	A			Other	0.36-0.73				
5/19/2020	3 samples	A	A			Other	0.47-0.56				
5/19/2020	3 samples	A	A			Routine	0.39-0.59				
5/12/2020	Tank Well 5	A	A			Other	0.48				
5/8/2020	North Bldg HB	A	A			Other					sample collected by Cutler-Orosi School District for Sports Complex
5/1/2020	6 samples	A	A			Routine	0.28-0.65				
4/23/2020	Baseball Concessions HB	A	A			Other					
4/23/2020	East Bldg HB	A	A			Other					
4/23/2020	Noth Bldg HB	P	A			Other					
4/14/2020	Concessions SW Bldg	P	A			Other					samples from Cutler-Orosi School District for new Sports Park.
4/14/2020	Mens Sink	P	A			Other					sample collected by Cutler Orosi Schoold District for new Sports Park.
4/1/2020	12 samples	A	A			Routine	0.36-0.76				
3/18/2020	Tank Well 5	A	A			Other	0.38				
3/18/2020	8" fire line	A	A			Other	0.49				
3/18/2020	4" domestic	A	A			Other	0.64				
3/17/2020	Tank Well 5	A	A			Other	0.45				
3/17/2020	8" fire line	A	A			Other	0.45				
3/17/2020	4" domestic	A	A			Other	0.39				
3/1/2020	15 samples	A	A			Routine	0.10-0.74				
2/1/2020	12 samples	A	A			Routine	0.19-0.6				
1/14/2020	Tank Well 5	A	A			Other	0.10				
1/1/2020	12 samples	A	A			Routine	0.31-0.67				
12/1/2019	15 samples	A	A			Routine	0.37-0.67				
11/1/2019	12 samples	A	A			Routine	0.29-0.70				
10/8/2019	Tank @ Well 5	A	A			Other	0.73				
10/1/2019	15 samples	A	A			Routine	0.24-0.91				
9/3/2019	12 samples	A	A			Routine	0.2-0.89				
8/1/2019	12 samples	A	A			Routine	0.22-0.85				
7/1/2019	15 samples	A	A			Routine	0.46-0.80				
6/1/2019	12 samples	A	A			Routine	0.30-0.85				
5/28/2019	3 samples	A	A			Other	0.58-0.76				

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>CI2</i>	<i>CI2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
5/21/2019	3 samples	A	A			Other	0.5-0.96				
5/14/2019	Tank Well 5	A	A			Other	0.69				
5/1/2019	12 samples	A	A			Routine	0.56-0.86				
4/1/2019	15 Samples	A	A			Routine	0.21-0.89				
3/1/2019	12 samples	A	A			Routine	0.22-0.74				
2/1/2019	12 samples	A	A			Routine	0.4-0.63				
1/1/2019	15 Samples	A	A			Routine	0.3-0.84				
12/1/2018	12 Samples	A	A			Routine	0.22-0.80				
11/1/2018	12 Samples	A	A			Routine	0.17-0.89				
10/9/2018	Tank Well 5	A	A			Other	0.47				
10/1/2018	15 Samples	A	A			Routine	0.15-0.78				
9/1/2018	12 Samples	A	A			Routine	0.11-0.90				
8/14/2018	Tank @ Well 5	A	A			Other	0.45				
8/1/2018	12 Samples	A	A			Routine	0.24-0.88				
7/1/2018	15 Samples	A	A			Routine	0.21-0.72				
6/1/2018	12 Samples	A	A			Routine	0.34-0.98				
5/22/2018	3 Samples	A	A			Other	0.58-0.69				
5/15/2018	3 Samples	A	A			Other	0.48-0.69				
5/1/2018	15 Samples	A	A			Routine	0.31-0.95				
4/1/2018	12 Samples	A	A			Routine	0.32-0.88				
3/1/2018	12 Samples	A	A			Routine	0.11-0.93				
2/1/2018	12 Samples	A	A			Routine	0.66-0.86				
1/1/2018	15 Samples	A	A			Routine	0.33-0.89				

Violation Key

MCL	Exceeds the maximum contaminant level	MR5	Incorrect number of repeat samples as follow-up to a positive sample
MR1	No monthly sample for the report month	MR6	No source sample
MR2	No quarterly sample for the report month	MR7	No summary report submitted
MR3	Incorrect number of routine samples for the report month	MR8	Other comments and/or info
MR4	Did not collect 5 routine samples for previous month's positive sample	MR9	CI2 not reported

Source Bacteriological Monitoring Report

5410008 Orosi Public Utility District

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
9/7/2021	8:52	Well #5	Well	P/A	A	A				
9/7/2021	9:00	Well #8	Well	P/A	A	A				
9/7/2021	9:23	Well #10	Well	P/A	A	A				
9/7/2021	9:35	Well #4	Well	P/A	A	A				
9/7/2021	9:45	Well #7	Well	P/A	A	A				
8/3/2021	8:33	Well #4	Well	P/A	A	A				
8/3/2021	8:44	Well #5	Well	P/A	A	A				
8/3/2021	9:15	Well #10	Well	P/A	A	A				
8/3/2021	9:29	Well #8	Well	P/A	A	A				
8/3/2021	9:40	Well #7	Well	P/A	A	A				
7/6/2021		Wells: 4,5,7,8,10	Well	P/A	A	A				
6/1/2021		Wells: 4,5,7,8,10	Well	P/A	A	A				
5/12/2021	9:11	Well 7	Well	P/A	A	A				
5/11/2021	11:13	Well 7	Well	P/A	A	A				
5/4/2021		Wells: 4,5,8,10	Well	P/A	A	A				
5/4/2021	9:37	Well 7	Well	P/A	P	A				
4/6/2021		Wells: 4,5,7,8,10	Well	P/A	A	A				
3/2/2021		Wells: 4,5,7,8,10	Well	P/A	A	A				
2/2/2021		Wells: 4,5,7,8,10	Well	P/A	A	A				
2/2/2021		Wells: 4,5,7,8,10	Well	P/A	A	A				
1/5/2021		Wells: 4,5,7,8,10	Well	P/A	A	A				
12/1/2020		Wells: 4,5,7,8,10	Well	P/A	A	A				
11/3/2020		Wells: 4,5,7,8,10	Well	P/A	A	A				
10/6/2020		Wells: 4,5,7,8,10	Well	P/A	A	A				
9/1/2020		Wells: 4,5,7,8,10	Well	P/A	A	A				
8/13/2020	8:47	Well 4	Well	P/A	A	A				
8/12/2020	8:38	Well 4	Well	P/A	A	A				
8/4/2020	9:25	Well 4	Well	P/A	P	A				
7/16/2020		Well 7	Well	P/A	A	A				
7/16/2020		Wells: 4,5,8,10	GWR Well	P/A	A	A				
7/15/2020	9:18	Well 7	Well	P/A	A	A				
7/7/2020		Wells: 4,5,8,10	Well	P/A	A	A				
6/10/2020	8:53	Well 7	Well	P/A	A	A				
6/9/2020	8:55	Well 7	Well	P/A	A	A				
6/2/2020		Wells: 4,5,8,10	Well	P/A	A	A				
6/2/2020	9:40	Well 7	Well	P/A	P	A				
5/5/2020		Wells: 4,5,7,8,10	Well	P/A	A	A				
4/7/2020		Wells: 4,5,7,8,10	Well	P/A	A	A				
3/9/2020	9:26	Well 5	Well	P/A	A	A				
3/4/2020	9:00	Well 5	Well	P/A	P	A				
3/3/2020		Wells: 4,5,7,8,10	Well	P/A	A	A				

5410008 Oroshi Public Utility District

Sample Date	Time	Source	Sample Type	Test Method	T Coli	E Coli	F Coli	HPC	Violation	Comments
2/4/2020		Wells: 4,7,8,10	Well	P/A	A	A				
1/7/2020		Wells: 4,7,8,10	Well	P/A	A	A				
12/3/2019	9:30	Well 7, 8, 10	Well	P/A	A	A				
11/15/2019	8:52	Well 7	Well	P/A	A	A				CI2=0.46
11/14/2019	9:01	Well 7	Well	P/A	A	A				CI2=0.57
11/5/2019		Wells: 4,8,10	Well	P/A	A	A				
11/5/2019	9:23	Well 7	Well	P/A	P	A				
10/1/2019		Wells: 4,5,7,8,10	Well	P/A	A	A				
9/3/2019		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
8/6/2019		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
7/30/2019	9:24	Well #4	Well	P/A	A	A				
7/29/2019	10:03	Well 4	Well	P/A	A	A				
7/10/2019	9:02	Well #7	Well	P/A	A	A				CI2 = 0.21
7/9/2019	9:18	Well #7	Well	P/A	A	A				
7/2/2019		Wells: 4,5, 8, 10	Well	P/A	A	A				
7/2/2019	9:38	Well #7	Well	P/A	P	A				
6/4/2019		Wells: 4,5,7,8,10	Well	P/A	A	A				
5/7/2019		Wells: 4,5,7,8,10	Well	P/A	A	A				
4/2/2019		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
3/5/2019		Wells: 4,5,7,8,10	Well	P/A	A	A				
2/5/2019		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
1/8/2019	8:54	Tank Well #5	Well	P/A	A	A				
1/2/2019		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				Repeat
12/4/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
11/6/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
10/2/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
9/4/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
8/7/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
7/12/2018	8:36	Well 4	Well	P/A	A	A				
7/11/2018	8:48	Well 4	Well	P/A	A	A				CI2=0.47
7/3/2018		Wells: 5, 7, 8, 10	Well	P/A	A	A				
6/7/2018		Wells: 5, 7, 8, 10	Well	P/A	A	A				Well 4: No sample due to repairs
5/8/2018	9:05	Tank Well #5	Other	P/A	A	A				
5/1/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
4/3/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
3/13/2018	9:15	Tank Well #5	Well	P/A	A	A				
3/12/2018	8:45	Tank Well #5	Well	P/A	A	A				
3/6/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
2/6/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				
1/9/2018	8:32	Tank Well #5	Other	P/A	A	A				CI2=0.64
1/2/2018		Wells: 4, 5, 7, 8, 10	Well	P/A	A	A				

Appendix D:
Instructions for Accessing Individual Water System's Water Monitoring
Schedule and Water Quality Data

How To Access Individual System's Drinking Water Monitoring Schedule & Water Quality Data

1. Place the following link in the internet address bar:
<https://sdwis.waterboards.ca.gov/PDWW/>
2. Enter your Water System No. and select "Search For Water Systems"

Drinking Water Branch

SDWIS Version 3.21

Drinking Water Watch

California Public Water Supply Systems Search Parameters

Water System No.

Water System Name

Principal County Served

Water System Type

Water System Status

Primary Source Water Type

[Click Here for the County Map of CALIFORNIA](#)

3. Click on your Water System No. (Link in blue text).

Drinking Water Division

Water Systems

Hide/show columns: [Water System No.](#) | [Water System Name](#) | [Type](#) | [Status](#) | [Principal County Served](#) | [Primary Source Water Type](#)

Display records Search:

Water System No.	Water System Name	Type	Status	Principal County Served	Primary Source Water Type
CA5403043	YETTEM WATER SYSTEM	C	A	TULARE	GW

Showing 1 to 1 of 1 entries (filtered from 8,332 total entries) Previous Next

- On the left side of the screen, select **Monitoring Schedules** for source monitoring schedule (last sample and next due dates) or **Monitoring Results** for water quality results.

Links

[Water System Details](#)
[Water System Facilities](#)
[Monitoring Schedules](#)
[Monitoring Results](#)
[Monitoring Results By Analyte](#)
[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)
[Site Visits](#)
[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)
[County Map](#)

Glossary

Contact Info

CA Drinking Water Watch

Water System Details

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

Water System Contacts

Type	Address	Phone	Email - Web Address
Administrative Contact	5961 S. MOONEY BLVD. VISALIA, CA 93277	Business 559-624-7191	
Physical Location Contact	CA5403043-YETTEM WATER SYSTEM		

Division of Drinking Water District / County Health Dept. Info

Name	Phone	Email	Address
DISTRICT 24 - TULARE	559-447-3300	dwpsdist24@waterboards.ca.gov	265 W. BULLARD AVE., SUITE 101 FRESNO CA 93704

Annual Operating Periods & Population Served

Start Month	Start Day	End Month	End Day	Population Type	Population Served
1	1	12	31	R	350

Service Connections

Type	Count	Meter Type	Meter Size Measure
CB	64	UN	0

Sources of Water

Name	Type Code	Status
WELL 01 - PRE NO3 BLEND	WL	A
WELL 02 - PRE NO3 BLEND	WL	A

Service Areas

Code	Name
R	RESIDENTIAL AREA

Water Purchases

Seller Water System No.	Water System Name	Seller Facility Type	Seller State Asgn ID No.	Buyer Facility Type	Buyer State Asgn ID No.
-------------------------	-------------------	----------------------	--------------------------	---------------------	-------------------------

5. Select Sampling Point corresponding to the source (Link in blue text and is a number).

5A. Monitoring Schedules

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

[Glossary](#)

[Contact Info](#)

CA Drinking Water Watch

Monitoring Schedules

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

The Division of Drinking Water's (DDW's) drinking water quality monitoring schedules identify upcoming required testing of drinking water for water systems in California. These documents should not be used for determining whether water systems are in compliance with monitoring requirements. The purpose for providing these monitoring schedules is to allow water systems to verify that their sampling and analyses have been incorporated into the DDW database and to identify upcoming required monitoring/sampling events.

Notes for Water Systems:

- The monitoring notification documents should be considered "draft," in that they will change with subsequent updates, and as monitoring data are submitted, or as monitoring schedules are revised.
- The monitoring notification documents are derived from the DDW Water Quality database and from schedules maintained by DDW districts.
- If your upcoming monitoring or your data identified as "DUE" are not in agreement with this document, or if you have been advised of any increased monitoring that is not reflected in the report for a particular source, please contact your [District Engineer or LPA representative](#). For a map of the districts, please [click here](#).
- If your notification report for a source is blank, this does not necessarily indicate compliance with all monitoring requirements.
- These notification reports may not reflect compliance with initial monitoring for newly regulated constituents, or constituents that require special monitoring frequencies. For example, the DDW database is unable to accurately forecast the vulnerable non-volatile synthetic organic chemical (SOC) frequency for large water systems serving over 3,300 people of 2 quarters every 3 years.
- Some Nitrate (as N) results under storet code 00618, will have a result of 'N/A' which stands for 'Not Applicable.' This stems from the change in regulation requiring that all nitrate sampling be reported as Nitrate (as N) starting January 1, 2016. Prior nitrate sampling was reported as Nitrate (as NO3). With this change in nitrate reporting requirements, the monitoring schedules have captured the last date of Nitrate (as NO3) sampling and applied it to Nitrate (as N) in determining the next due date [unless there have been Nitrate (as N) samples collected]. The Nitrate (as NO3) result, however, does not carry over to Nitrate (as N) which is why there may be a notation in the 'Constituent Identification' column to reference storet code 71850 for the last nitrate result. In these instances, the 'Constituent Identification' column will say, "NITRATE (as N) - [see 71850]." Any questions should be referred to your District Engineer.

Monitoring Schedules for All Sampling Points

Monitoring schedule for all sampling points

Click to view report. Once the report is shown, click on the Export icon on the report header to download.

Monitoring Schedule for Individual Sampling Points

Click on a sampling point number to view the monitoring schedule for the sampling point.
[Click here to bring back the list of sampling points.](#)

Sampling Point	Location	Type
900	ST2S1-14395 AVE 384	
LCR		DS
003	WELL 01 & 02 - NO3 BLEND TANK	
001	WELL 01 - PRE NO3 BLEND	RW
002	WELL 02 - PRE NO3 BLEND	RW

Monitoring schedule for specific sampling points

NOTE: Any *past due* monitoring will have "DUE NOW" in the far-right column. Please schedule this monitoring as soon as possible.

5B. Monitoring Results

Links
[Water System Details](#)
[Water System Facilities](#)
[Monitoring Schedules](#)
[Monitoring Results](#)
[Monitoring Results By Analyte](#)
[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)
[Site Visits](#)
[Consumer Confidence Reports](#)

- 2017
- 2016
- 2015
- 2014

Return Links
[Water System Search](#)
[County Map](#)
Glossary
Contact Info

CA Drinking Water Watch

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

Monitoring Results for Individual Sampling Points

Click on a PS Code to view/download the monitoring results for the sampling point.

Water System Sampling Points					
PS Code	Facility ID	Facility Name	Description	Type Code	Source Class
5403043-001	001	WELL 01 - PRE NO3 BLEND	WELL 01 - PRE NO3 BLEND	RW	DCSGA
5403043-002	002	WELL 02 - PRE NO3 BLEND	WELL 02 - PRE NO3 BLEND	RW	DCSGA
5403043-003	003	WELL 01 & 02 - NO3 BLEND TANK	WELL 01 & 02 - NO3 BLEND TANK		OTHR
5403043-900	DST	DISTRIBUTION SYSTEM	DISTRIBUTION SYSTEM		DBPT
5403043-LCR	DST	DISTRIBUTION SYSTEM		DS	

6. Please contact the Tulare District Office at (559) 447-3300 or DWPDIST24@waterboards.ca.gov if you have any questions.

Appendix E:
Lead and Copper Tap Sample Results Reporting Form



State Water Resources Control Board

Division of Drinking Water

Lead and Copper Tap Sample Results Reporting Form

This form must be submitted to the regulating entity (DDW District Office or County Agency) for each round of lead and copper sampling

Report Date: (mm/dd/yyyy)		Sampling Site Change
Water System Name:		<i>If any sampling sites were changed, please list the old site, new site, and reason for the change in the box below.</i>
Water System Number:		
Sample Schedule:	<input checked="" type="radio"/> 6-month <input type="radio"/> Annual <input type="radio"/> Triennial	
# of Samples Required:		
# of Samples Reported:		
	90th Percentile Level (mg/L)	
Lead:		
Copper:		

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2 or 3	Lead (mg/L)	Copper (mg/L)
01					
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Number of Tap Sample Sites Required

The number of tap sample sites required is based on the number of people served (system size) by your water system and also whether you are performing Standard or Reduced Monitoring (CCR §64675).

System Size	Minimum Number of Sites	
	Standard Tap Sampling	Reduced Tap Sampling
> 100,000	100	50
10,001 to 100,000	60	30
3,301 to 10,000	40	20
501 to 3,300	20	10
101 to 500	10	5
< 101	5	5

Determining the 90th Percentile Lead and Copper Level

Number of Tap Samples Collected	Determination of 90 th Percentile Lead or Copper Level
5	Average the 4 th and 5 th highest sample results to get the 90 th percentile level
More than 5	Place results in ascending order and assign each sample a number, 1 for the lowest concentration. Multiply the total number of samples by 0.9. Round down to the nearest whole number if the decimal is 0.4 or lower and round up if the decimal is 0.5 or higher. The sample result that corresponds with the nearest whole number is the 90 th percentile.

Notification of Results

As required by *40 Code of Federal Regulations Section 141.85(d)*, within 30 days of learning of the tap monitoring results, I notified the participants, by mailing or by another method approved by the State, of the lead sample results from their individual taps, provided an explanation of the health effects of lead, listed steps the consumer could take to reduce exposure to lead, provided contact information for the water utility, the maximum contaminant level goal for lead, action level for lead, and any definitions.

Notification was done on: _____ (date)

SIGNATURE:	DATE:
NAME (Print):	TITLE:

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Additional Samples				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2 or 3	Lead (mg/L)	Copper (mg/L)
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					

Appendix F: East Orosi 2019 Sanitary Survey

State Water Resources Control Board
Division of Drinking Water

September 8, 2022

Ms. Carmen Moreno, Board President
East Oroshi CSD – CA5401003
P.O. Box 213
Oroshi, CA 93647

Dear Ms. Moreno,

On July 20, 2022, the State Water Resource Control Board, Division of Drinking Water (Division) conducted a sanitary survey of the East Oroshi Community Services District Water System (Water System). After evaluation of the East Oroshi CSD water system (Water System) and completion of the enclosed Sanitary Survey Report, the Division finds the following items below are required to be addressed by the Water System.

The following items were not addressed by the Water System and are still OUTSTANDING deadlines requiring completion immediately:

1. By **June 1, 2018**, the Water System must submit a bacteriological sample siting plan to the Division for review and approval.
2. By **June 1, 2018**, the Water System must submit a chlorination operations plan to the Division for review and approval.
3. By **July 1, 2018**, the Water System must provide the Division with a completed cross connection control survey or a plan and time schedule for a cross connection survey to be completed.

The following items need to be addressed by the Water System:

1. By **October 31, 2022**, the Water System must replace the flow meter at Well 01 and begin recording production from both wells at least monthly.
2. By **October 31, 2022**, the Water System must submit an updated ENP to the Division.

If you have any questions regarding this letter or the permit, please contact the Tulare District office at (559) 447-3300 or by email at DWPDIST24@waterboards.ca.gov.

E. JOAQUIN ESQUIVEL, CHAIR | EILEEN SOBECK, EXECUTIVE DIRECTOR

Sincerely,

Kristin Willet  Digitally signed by Kristin Willet
Date: 2022.09.08 09:01:59 -07'00'

Water Boards

Kristin Willet, P.E.

Senior Water Resource Control Engineer, Tulare District
SOUTHERN CALIFORNIA BRANCH
DRINKING WATER FIELD OPERATIONS

Enclosures

cc: [all email only]

Nilsa Gonzalez

Tulare County Environmental Health Division

NGonzale@tularehhsa.org

Ralph Gutierrez, Operator

woodvillerg@yahoo.com

Small Water System Evaluation and Inspection Report
Drinking Water Field Operations Branch: Tulare District

East Orosi CSD
System No. 5401003

Contact:	Carmen Moreno, Board President	System Type:	Community Water System
Inspection Date:	July 20, 2022	Inspected By	Kristin Willet, P.E.

I. INTRODUCTION

On July 20, 2022, the State Water Resources Control Board, Division of Drinking Water (Division) conducted a sanitary survey of the East Orosi CSD water system (Water System). Mr. Roberto Gutierrez, contract operator, assisted the Division with the sanitary survey. The Water System was last inspected by the Division, on September 26, 2019 as a sanitary survey to document the addition of continuous chlorination and amend the domestic water supply permit.

PERMIT STATUS

The Water System currently operates under Domestic Water Supply Permit No. 03-24-19PA-023 issued by the Division on December 31, 2019. The permit provisions are listed below.

1. The East Orosi Community Services District water system shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted there under.
2. The only approved source of domestic water supply for the East Orosi Community Services District water system is as follows:

Source Name	Status	PS Code
Well 01 – East – Raw	Active	CA5401003_001_001
Well 02 – West – Raw	Active	CA5401003_002_002

3. The only approved treatment for the East Orosi Community Services District water system is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution.
4. No other sources or treatment (as described in provisions No. 2 and 3 above) shall be used by the East Orosi Community Services District water system and no changes, additions, or modifications shall be made to the source unless an amended water permit has first been obtained from the Division.

5. All personnel who operate distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The East Orosi Community Services District water system is classified as a D1 water system and shall be operated by a D1 certified distribution operator or higher.
6. The East Orosi Community Services District water system shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The East Orosi Community Services District water system shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.
7. The East Orosi Community Services District water system shall submit an electronic Annual Report (EAR) each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
8. The East Orosi Community Services District water system shall record production data from the active source at least monthly. The monthly water production shall be reported annually to the Division in the EAR.
9. The East Orosi Community Services District water system shall collect monthly raw water samples from the source for analyses of total coliform and fecal coliform or *E. coli* bacteria. The coliform test shall be performed using a density analytical method and the results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following month.
10. The East Orosi Community Services District water system shall monitor for coliform bacteria in the distribution system at least monthly and in accordance with an approved Bacteriological Sample Siting Plan (BSSP). The Division shall be notified immediately if any distribution system or source sample shows the presence of *E. coli* bacteria or if more than one bacteriological sample shows the presence of coliform bacteria during a single month.
11. The East Orosi Community Services District water system shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The East Orosi Community Services District water system shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.

12. The East Orosi Community Services District water system shall conduct Stage 2 Disinfection Byproduct (DBP) Monitoring once every year unless monitoring frequency is reduced by the Division. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Code:

ST2 Monitoring Site	PS Code
ST2S1 - 13920 Ave 418	CA5401003_DST_900

13. The East Orosi Community Services District water system shall submit a monthly chlorination log to the Division by the 10th day of the following month.
14. The East Orosi Community Services District water system shall operate the continuous chlorination treatment facility in accordance with a Division-approved Chlorination Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval prior to implementation.

DESCRIPTION OF SYSTEM

The mailing address for the Water System is P.O. Box 213, Orosi, CA 93647. The Water System is classified as a community water system. The Water System serves a population of 932 permanent residents through 103 unmetered service connections. Service connections consist of primarily residential homes. The domestic water supply is obtained from two active groundwater sources identified as Well 01 – East – Raw and Well 02 – West - Raw. Continuous chlorination is the only treatment provided to the source water. No storage is provided.

ENFORCEMENT HISTORY

The following enforcement actions have been issued since the last sanitary survey report:

Citation No. 03-24-20C-114; issued October 2020

The Water System failed to submit a timeline for replacement of known lead or unknown material user service lines.

Citation No. 03-24-21C-055; issued September 2021

The Water System failed to submit the 2020 EAR.

Citation No. 03-24-21C-089; issued October 2021

The Water System failed to comply with Compliance Order No. 03-24-15R-001 directives for the first and second quarter of 2021.

Citation No. 03-24-22C-047; issued May 2022

The Water System failed to comply with Compliance Order No. 03-24-15R-001 directives for the third and fourth quarter of 2021.

It is expected that the Water System comply with the directives listed in the enforcement actions by their corresponding due dates. **However, the Water System routinely misses compliance deadlines.**

SERVICE AREA

The Water System is located less than one mile east of Orosi, CA. The service area for the Water System is comprised of 103 unmetered service connections consisting of residential homes and approximately four businesses in the East Orosi service area. The Water System has individual septic systems that feed a sewer collection system. The surrounding land use area is largely agricultural. A locational map of the Water System is included in Appendix A.

II. INVESTIGATION AND FINDINGS

SOURCES OF SUPPLY

The Water System's sources of supply are two active groundwater wells identified as Wells 01 and 02. A description of the source is provided below. Photographs of the well sites are included in Appendix A.

Active Sources:

Well 01- East - RAW, Active – Treated, (CA5401003_001_001)

DWR Well Driller's Completion Report is on file at Tulare District Office:	Yes
Date of Well Completion:	August 1983
Well Depth:	365 feet
Sanitary Seal Depth:	200 feet
Well Casing:	10-inch diameter steel casing to 365 feet; perforations between 220 to 360 feet
Flow Meter:	Yes, digital
Pump Type:	Submersible
Pump Make and Model:	Unknown
Pump Size:	7.5-horsepower (hp)
Well Capacity	160 gallons per minute (gpm)

Source Discharge:	Directly to a 7,500-gallon hydropneumatic pressure tank prior to entering the distribution system.
Source Operation:	Based on system pressure.
Comments:	Well 01 is the Water System's primary source of supply.

Well 02- West - RAW, Active – Treated, (CA5401003_002_002)

DWR Well Driller's Completion Report is on file at Tulare District Office:	Yes
Date of Well Completion:	June 1984
Well Depth:	350 feet
Sanitary Seal Depth:	20 feet
Well Casing:	10-inch diameter steel casing to 350 feet; unknown perforations
Flow Meter:	No (inoperable)
Pump Type:	Submersible
Pump Make and Model:	Unknown
Pump Size:	7.5-hp
Well Capacity	150 gpm
Source Discharge:	Directly to a 3,500-gallon hydropneumatic pressure tank prior to entering the distribution system
Source Operation:	Based on system pressure.
Comments:	Well 02 is the Water System's secondary source of supply in times of high demand. The source exceeds the nitrate MCL. Previous inspection reports highlighted that grazing animals were near the source and a 50-foot control zone was not maintained; but these issues were not noted during the most recent inspection. At the time of inspection, the well was disassembled for casing repair and scrubbing.

Source Water Assessments

The Source Water Assessments for Wells 01 and 02 were completed in October 2002 by Tulare County. The sources were identified as being most vulnerable to known contaminant plumes (nitrate) and septic systems. Hard copies of the Source Water Assessments are on file in the Tulare District Office.

WATER PRODUCTION

The Water System primarily uses Well 01 to meet system demands due to nitrate contamination in Well 02. Well 02 is used during times of high demand in the summer months.

Table 1 - Production Data

Year	Population	Service Connections	Annual Production (Gal.)	Max. Month (Gal.)
2021*	932	103	26,805,000	4,920,000 (Jun.)
2020	932	103	18,249,000	2,949,000 (Oct.)

Production records are not available past September 2021. The Water System reported the flow meter at Well 01 is not working and Well 02 has not been producing as it is undergoing repair. **By October 31, 2022, the Water System must replace the flow meter at Well 01 and begin recording production from both wells at least monthly.**

ADEQUACY OF SUPPLY

According to the Waterworks Standard, the highest water usage during the past two years and a peaking factor of 1.5 was used to estimate the maximum day and peak hour demands for the system. Based on Table 1, the values for the aforementioned demands are summarized in Table 2 below.

Table 2 - Average Day, Maximum Day & Peak Hour Demand

Year	Average Day (gpm)	Maximum Day (gpm)	Peak Hour (gpm)
2021	51	171	256
2020	35	99	149

Table 3 – Total Active Source Capacity

Source	Capacity (gpm)
Well 01	160
Well 02	150
Total Capacity	310

Community water systems are required to have capacity equal to or greater than their maximum day demand (MDD). The Division advises the Water System to invest in a storage tank or additional source to improve reliability in the event of a well failure or power outage. The Title 22 drinking water standards requires systems with less than 1,000 service connections have storage capacity equal to or greater than MDD, unless the system can demonstrate that it has an additional source of supply or has an

emergency source connection that can meet the MDD requirement. **The Water System does not meet this requirement.**

The Water System experienced a water outage on July 12, 2022 due to power source issues and pump failure at Well 01, resulting in the Division issuing a Do Not Drink (DND) notice. The outage lasted into the early morning of July 13, 2022. The Water System is working with the Safe and Affordable Funding for Equity and Resilience (SAFER) group within the Division to have Tulare County act as administrator for the Water System to assist with managing the technical, managerial and financial oversight of the water system.

STORAGE & DISTRIBUTION

There are no storage facilities in the system. The well pumps water directly to 7,500 and 3,500-gallon steel hydropneumatic pressure tanks prior to serving the distribution system. The pressure tanks are not equivalent of a storage tank. The purpose of the pressure tanks is to maintain system pressure between the range of 35 and 60 pounds per square inch (psi). The distribution system is classified as a D1 system. The Water System must follow American Water Works Association (AWWA) standards when any repairs or line replacements are made. The material comprising the distribution system was reported as 100% plastic in the 2021 EAR.

TREATMENT FACILITIES

The Water System provides continuous chlorination to the water produced by Wells 01 and 02. A 12.5% solution of sodium hypochlorite is injected directly into the discharge line of Wells 01 and 02 upstream of each pressure tank. The sodium hypochlorite solution is stored at the well site in a 35-gallon polyethylene tank. The chlorination equipment is activated upon startup of the well and consists of a Stenner 45MHP22 at Well 01 and Grundfos DDE 6-10 chemical feed pump at Well 02. The Stenner 45MHP22 chemical feed pump has a capacity of 0.9 gallons per hour (gph) at 100 psi. The Grundfos DDE chemical feed pump has a capacity of 1.5 gph at 150 psi. The chemical storage tank and feed pump appear to be adequately sized. The Water System aims to maintain a chlorine residual between 0.5 to 1.5 mg/L in the distribution system. The Water System must record chlorine residuals from the distribution system weekly and report the monthly chlorination report to the Division by the 10th day of the following month.

The Water System must submit a Chlorination Operations Plan to the Division; this directive is outstanding and due to the Division immediately. Guidance for completing a Chlorination Operations Plan is in Appendix F.

III. WATER QUALITY MONITORING

SOURCE MONITORING

All chemical water quality monitoring from the sources must be submitted to the Division via the California Laboratory Intake Portal (CLIP). To properly upload data to CLIP, the Water System must identify the samples with the correct primary station code (PS Code). The assigned PS Code is listed in Table 4 below. A summary of the recent source water quality monitoring results and next due dates are included in Appendix B. Additionally, the current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>. Instructions for accessing this information is included in Appendix G.

Table 4 – Primary Station Codes

Source Name	Status	PS Code
Well 01 – East – Raw	Active	CA5401003_001_001
Well 02 – West – Raw	Active	CA5401003_002_002

Bacteriological

Due to continuous chlorination, the untreated well water from Wells 01 and 02 are required to be sampled monthly for total coliform bacteria at a sample tap located prior to the chlorine injection port. This is required in order to verify that the well is not producing water that contains coliform bacteria. A summary of the source bacteriological sample results is included in Appendix C.

General Mineral, General Physical and Inorganic Chemicals

The Water System is required to monitor its active groundwater sources for general mineral (GM), general physical (GP) and inorganic (IO) chemicals every three years, except for nitrate which has a different monitoring frequency. The Water System last sampled Well 01 for GM, GP, and IO chemicals in September 2020, except for iron, manganese and turbidity which were monitored for in June 2022, and conductivity and total dissolved solids which were monitored for in June 2021. Well 01 exceeds the secondary MCLs for the following constituents: iron, manganese, and turbidity and monitors for these constituents on a quarterly basis. Well 02 was last sampled for GM, GP, and IO chemicals in March 2022.

Nitrate

The Water System is required to monitor active groundwater sources for nitrate (as N) annually if monitoring data indicates nitrate concentrations of less than one-half the MCL of 10 mg/L and quarterly if the concentrations are greater than or equal to one-half the MCL. Wells 01 and 02 are required to be monitored

quarterly. Well 01 was last sampled in July 2022 with results of 9.8 mg/L and is next due for nitrate monitoring by October 2022. Well 02 was last sampled in April 2022 with a result of 13 mg/L and will be due for nitrate monitoring when the well is back in service.

Volatile Organic Chemicals (VOCs)

The Water System completed initial VOC monitoring for Well 01 and 02. The Water System last sampled Well 01 for VOCs in May 2019 and the results were ND. Well 02 was last sampled for VOCs in February 2020 with non-detect (ND) results. **Well 01 is due for VOC monitoring in the 2020-2022 compliance period, by December 31, 2022. Well 02 is due for VOC monitoring in the 2023-2025 compliance period.**

Synthetic Organic Chemicals (SOCs)

The Water System completed initial SOC monitoring for Well 01 and 02. The Water System sampled Well 01 for SOC in December 2020, except for 1,2,3-trichloropropane (1,2,3-TCP) which was last monitored for in June 2022, all with non-detect results. Well 02 was last monitored for SOC in June 2020, except for 1,2,3-TCP which was last monitored in March 2022, all with non-detect results. The Water System must monitor Well 01 and Well 02 for all SOC in the 2023-2025 compliance period for SOC.

Radiological Monitoring

The initial radiological monitoring is based on the collection of four consecutive quarterly samples for gross alpha and radium-228. If the results from the first two quarters of initial monitoring are below the DLR, the final two quarters of initial monitoring may be waived. After initial monitoring is complete, no additional monitoring is required for radium-228. Subsequent monitoring frequencies for gross alpha is based on the results of the last sample collected. It should be noted that if the gross alpha result for any single sample is greater than 5 pCi/L, analysis for uranium in *that same sample* is required.

The Water System has completed initial monitoring for gross alpha from Wells 01 and 02. The last gross alpha result from Well 01 was 3.38 pCi/L and is on a 72-month frequency. The last gross alpha sample from Well 02 was 5.54 pCi/L and is on a 72-month frequency. The Water System must monitor Well 01 for gross alpha in June 2024 and Well 02 in March 2025.

DISTRIBUTION SYSTEM MONITORING

Bacteriological

Based on the population and number of service connections, the Water System is required to collect at least one routine bacteriological sample each month from the

distribution system. The sample must be analyzed for total coliform bacteria with results sent to the Division by the 10th day of the following month. Additionally, bacteriological samples should be collected in accordance with an approved Bacteriological Sample Siting Plan (BSSP). **The Water System was directed to submit a BSSP in previous sanitary surveys. This directive remains outstanding and must be addressed immediately.** A summary of the distribution bacteriological sample results is included in Appendix C. A BSSP template is provided in Appendix H.

Lead and Copper Monitoring

The Water System is currently on annual monitoring for lead and copper tap monitoring from 10 locations. The 90th percentile for lead and copper should be less than the lead and copper action levels of 0.015 mg/L and 1.3 mg/L, respectively. Lead and Copper Sampling guidance and reporting form is in Appendix D. The Water System last monitored for lead and copper from the distribution system in September 2021 with no samples exceeding the action levels. **The Water System is next due to collect 10 lead and copper samples by September 30, 2022.**

All future lead and copper monitoring results must be submitted to the Division electronically via the Lab-To-State (LTS) Portal. The Water System must complete and submit a Lead and Copper Tap Sample Results Reporting Form with all subsequent lead and copper monitoring results. A Lead and Copper Tap Sample Results Reporting Form is included in Appendix D.

Disinfection Byproduct Monitoring

Due to the implementation of continuous chlorination, the Water System is required to comply with the Stage 2 Disinfection Byproduct Monitoring Rule (DBPR). To comply with Stage 2 DBPR monitoring requirements, the Water System is required to collect one sample every three years during a month of the warmest water temperature. The sample must be analyzed for total trihalomethanes (TTHMs) and haloacetic acids (HAA5s). The results of Stage 2 DBP monitoring must be sent to the Division electronically to the Division's electronic water quality database using the PS Code listed in Table 5 below.

Table 5 – Stage 2 DBP PS Code

ST2 DBP Monitoring Site	PS Code
ST2S1 - 13920 Ave 418	CA5401003_DST_900

The Water System last monitored for TTHM and HAA5s on June 29, 2022, both with results of non-detect. The next TTHM/HAA5 monitoring is due by June 2025.

Asbestos

Regulation requires monitoring of systems vulnerable to asbestos contamination. Monitoring is required if asbestos containing pipe is used and aggressive water is produced by the wells. The aggressive indices from Wells 01 and 02 are 12.0 and 10.4, respectively, however the Water System indicated that the distribution system is comprised of plastic material and is not required to monitor for asbestos.

IV. OPERATIONS AND MAINTENANCE

Operator Certification

The Water System's distribution system is classified as a D1 distribution system and requires a certified distribution system operator with a minimum D1 certification. Mr. Ralph Gutierrez is the certified D3 distribution system operator for the Water System (Cert. #: 18005). Per Title 22, Section 63770, California Code of Regulations, water systems shall utilize only certified distribution operators to make decisions addressing the following operational activities:

- 1) Install, tap, re-line, disinfect, test and connect water mains and appurtenances.
- 2) Shutdown, repair, disinfect and test broken water mains.
- 3) Oversee the flushing, cleaning, and pigging of existing water mains.
- 4) Pull, reset, rehabilitate, disinfect and test domestic water wells.
- 5) Stand-by emergency response duties for after hours distribution system operational emergencies.
- 6) Drain, clean, disinfect, and maintain distribution reservoirs.

The Water System shall utilize either certified distribution operators or treatment operators that have been trained to make decisions addressing the following operational activities:

- 1) Operate pumps and related flow and pressure control and storage facilities manually or by using a system control and data acquisition (SCADA) system.
- 2) Maintain and/or adjust system flow and pressure requirements, control flows to meet consumer demands including fire flow demands and minimum pressure requirements.

The Water System shall utilize either certified distribution operators or treatment operators to make decisions addressing the following operational activities:

- 1) Determine and control proper chemical dosage rates for wellhead disinfection and distribution residual maintenance.
- 2) Investigate water quality problems in the distribution system.

Cross Connection Control

Based on the 2021 EAR, the Water System does not have a Cross Connection Control Program in place and there are no backflow prevention devices in the distribution system. The Water System is required to maintain a Cross Connection Control Program which shall include the following elements (as applied from Title 17, California Code of Regulations, Section 7584):

- 1) The conducting of surveys to identify water user premises or locations where cross connections are likely to occur,
- 2) The provisions of backflow protection by the water user at the user's connection or within the user's premises or both,
- 3) The provision of at least one person trained in cross connection control to carry out the cross-connection program,
- 4) The establishment of a procedure or system for annual testing of backflow preventers, and
- 5) The maintenance of records of locations, tests, and repairs of backflow preventers.

Backflow Prevention Device Testing

Regulation requires all backflow prevention devices to be tested annually. Copies of the testing records must be kept on file with the Water System for a minimum of three years.

The Water System must conduct a cross connection control survey using a certified cross connection control specialist or submit a time and schedule for having one completed; this directive remains outstanding and is due to the Division immediately. A guidance document for implementing a cross-connection control program is included in Appendix E.

Complaints

The Water System must keep records of all complaints received and actions taken to correct the problems related to the complaints. According to the 2021 EAR, the Water System received no complaints.

Emergency Notification Plan (ENP)

The current Emergency Notification Plan (ENP) on file with the Division is dated March 15, 2019. However, it needs to be updated. According to the ENP, the Water System will notify customers of an emergency via door-to-door notification, posted notification, and email. The Division has updated the ENP template for the Tulare District. **By October 31, 2022, the Water System must submit an updated ENP to the Division. An ENP template has been provided in Appendix I.**

Consumer Confidence Report (CCR)

The Water System is required to complete a Consumer Confidence Report (CCR) on an annual basis and provide a copy to all residents and the Division by July 1 of each year. In addition, the Water System is required to provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers. The Water System distributed the 2021 CCR to customers and submitted their CCR certification form to the Division on August 1, 2022.

Electronic Annual Report (EAR)

All public water systems are required to provide updated water system information to the Division annually in the EAR. The 2021 EAR was submitted to the Division on July 15, 2022. No backflow devices were reported, but it is important to note that if backflow devices are present in the water system, they must be tested annually by a certified backflow tester. No cross-connection control survey has been reported in the EAR survey, which is also required.

V. SMALL WATER SYSTEM RESILIENCY AND PREPAREDNESS

The effects of climate change on community water system (CWS) facilities and operations is a concern and priority of the State Water Resources Control Board (SWRCB), which is documented by the SWRCB in its Comprehensive Climate Change Resolution adopted in March 2017. DDW is reviewing each water system preparedness for climate change with the goal to increase awareness and familiarization to the effects of climate change to facilities and operations, encourage the use of EPA's Climate Resilience Evaluation and Awareness Tool (CREAT) or equivalent, and to document the Water System's efforts related to current threats that may also provide mitigation to climate change impacts.

The Water System indicated that they **were not** aware of the CREAT tool developed by USEPA for identifying climate change vulnerabilities. The Water System has not used CREAT (or similar tool) to identify vulnerabilities to the water system sources and facilities. The SWRCB strongly encourages utilities to evaluate climate change vulnerabilities using tools such as CREAT and engaging in a conversation both within your water system organization and with customers on how to plan and prepare for being resilient to provide clean and safe water reliably and adequately under all current and future conditions.

Fire ---

- A defensible space of 100 feet (*California Public Resources Code, 4291*) is maintained around all sources and structures managed by the Water System. **Yes**

Flooding ---

- Are any of the drinking water facilities vulnerable to flooding? **No**

Backup Power ---

- Is backup power available, for example, through portable or permanent power generators? **No**
 - No backup power is provided.
- If liquid fuel is used, is it properly contained and stored away from the source? **N/A**

Drought ---

- Is the Water System prepared for drought related shortages or outages? (interties, backup supply, increased storage) **No**

Degrading Source Water Quality –

- Has source water quality degraded over time, or specifically during the most recent drought? **Yes**

VI. APPRAISAL OF SANITARY HAZARDS & PUBLIC HEALTH SAFEGUARDS

The East Orosi CSD water system relies on Well 01 and Well 02 to supply the demands of the system. Well 01 is the primary well, and Well 02 supplements demand as necessary. According to the operator, the estimated source capacity is approximately 160 and 150 gpm from Wells 01 and 02, respectively. East Orosi CSD has no storage capacity. The water system has no interconnection with any nearby water systems.

The East Orosi CSD lacks managerial capacity to comply with regulatory requirements. The East Orosi CSD is past due on many deadlines related to public notification requirements set forth in Compliance Order No. 03-24-15R-001 and other enforcement actions. East Orosi CSD is working with the SAFER group within the Division to have Tulare County act as administrator for the water system starting in October 2022.

The current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>.

The following items were not addressed by the Water System and are still OUTSTANDING deadlines requiring completion immediately:

1. By **June 1, 2018**, the Water System must submit a bacteriological sample siting plan to the Division for review and approval.

2. By **June 1, 2018**, the Water System must submit a chlorination operations plan to the Division for review and approval.

The following items need to be addressed by the Water System:

1. By **October 31, 2022**, the Water System must replace the flow meter at Well 01 and begin recording production from both wells at least monthly.
2. By **October 31, 2022**, the Water System must submit an updated ENP to the Division.

Appendix:

- Appendix A: Location Map & Photo Index
- Appendix B: Last Sample & Next Due Date Summary Reports
- Appendix C: Source and Distribution System Bacteriological Monitoring Reports
- Appendix D: Lead and Copper Tap Sample Results Reporting Form
- Appendix E: Cross Connection Control Guidance for Community Water Systems
- Appendix F: Chlorination Operations Plan Guidance/Monthly Chlorination Log
- Appendix G: Instructions for Accessing Public Drinking Water Watch
- Appendix H: Bacteriological Sample Siting Plan (BSSP) Template
- Appendix I: Emergency Notification Plan Template

Appendix A:
Location Map & Photo Index

East Orosi CSD

5401003



Florida Ave
East Orosi
Well 01 - East
Illinois Dr
Well 02 - West



Appendix A

East Orosi CSD Water System: 5401003

Sanitary Survey Photographs

Well 01 - East **(CA5401003 001 001):**

- Date Drilled: August 1983
- Depth: 365 feet
- Type: Submersible
- Pump Size: 7.5-hp
- Capacity: 150 gpm



Pressure Tank:

- Location: Well 01—East
- Volume: 7,500 gallons
- Material: Steel



Well 02 - West (CA5401003 002 002):

- Date Drilled: June 1984
- Depth: 350 feet
- Type: Submersible
- Pump Size: 7.5-hp
- Capacity: 150 gpm
- 3,500 gallon steel pressure tank



Appendix B:
Last Sample & Next Due Date Summary Report

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT

COUNTY: TULARE

Sample Point: WELL 01 - EAST - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD			
CA5401003_001_001		EAST OROSI COMMUNITY SERVICES DISTRICT						WELL 01 - EAST - RAW															
	GP	SECONDARY/GP																					
		1928	ALKALINITY, BICARBONA TE	180.000		0.000		MG/L	-----	-----	9/28/2020	9	36			2023/09		65140012 00928101 5G	1180	BSK ANALYTICAL LABORATORIES			
		1919	CALCIUM	44.000		0.000		MG/L	-----	-----	9/28/2020	9	36			2023/09		65140012 00928101 5G	1180	BSK ANALYTICAL LABORATORIES			
		1929	ALKALINITY, CARBONATE		<	0.000		MG/L	-----	-----	9/28/2020	9	36			2023/09		65140012 00928101 5G	1180	BSK ANALYTICAL LABORATORIES			
		1017	CHLORIDE	18.000		0.000		MG/L	500	-----	9/28/2020	9	36			2023/09		65140012 00928101 5G	1180	BSK ANALYTICAL LABORATORIES			
		1905	COLOR		<	0.000		UNITS	15	-----	9/28/2020	16	36			2023/09		65140012 00928101 5G	1180	BSK ANALYTICAL LABORATORIES			
		1022	COPPER, FREE		<	50.000		UG/L	1000	50	9/28/2020	9	36			2023/09		65140012 00928101 5L	1180	BSK ANALYTICAL LABORATORIES			
		2905	FOAMING AGENTS (SURFACTA NTS)		<	0.000		MG/L	0.5	-----	9/28/2020	9	36			2023/09		65140012 00928101 5G	1180	BSK ANALYTICAL LABORATORIES			
		1915	HARDNESS, TOTAL (AS CACO3)	190.000		0.000		MG/L	-----	-----	9/28/2020	9	36			2023/09		65140012 00928101 5G	1180	BSK ANALYTICAL LABORATORIES			
		1021	HYDROXIDE AS CALCIUM CARBONATE		<	0.000		MG/L	-----	-----	9/28/2020	9	36			2023/09		65140012 00928101 5G	1180	BSK ANALYTICAL LABORATORIES			
		1028	IRON	72.000		30.000		UG/L	300	100	6/29/2022	121	3	Interval	2022/09	DUE NOW	AFF3490- 01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7			
		1031	MAGNESIUM	20.000		0.000		MG/L	-----	-----	9/28/2020	9	36			2023/09		65140012 00928101 5G	1180	BSK ANALYTICAL LABORATORIES			

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 01 - EAST - RAW CLASS: DCSGA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_001_001	GP	SECONDARY/GP																	
		1032	MANGANESE		<	10.000	UG/L	50	20	6/29/2022	121	3	Interval	2022/09	DUE NOW	AFF3490-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1920	ODOR		<	1.000	TON	3	1	9/28/2020	16	36		2023/09		65140012009281015G	1180	BSK ANALYTICAL LABORATORIES	
		1925	PH	8.000		0.000		-----	-----	9/28/2020	9	36		2023/09		65140012009281015G	1180	BSK ANALYTICAL LABORATORIES	
		1050	SILVER		<	10.000	UG/L	100	10	9/28/2020	9	36		2023/09		65140012009281015G	1180	BSK ANALYTICAL LABORATORIES	
		1052	SODIUM	20.000		0.000	MG/L	-----	-----	9/28/2020	9	36		2023/09		65140012009281015G	1180	BSK ANALYTICAL LABORATORIES	
		1064	CONDUCTIVITY @ 25 C UMHOS/CM	460.000		0.000	UMHO/CM	1600	-----	6/3/2021	16	36		2024/06		65140012106030950G	1180	BSK ANALYTICAL LABORATORIES	
		1055	SULFATE	19.000		0.500	MG/L	500	0.5	9/28/2020	9	36		2023/09		65140012009281015G	1180	BSK ANALYTICAL LABORATORIES	
		1930	TDS	310.000		0.000	MG/L	1000	-----	6/3/2021	25	36		2024/06		65140012106030950G	1180	BSK ANALYTICAL LABORATORIES	
		0100	TURBIDITY	0.460		0.100	NTU	5	0.1	6/29/2022	100	3	Interval	2022/09	DUE NOW	AFF3490-01	1180	BSK ANALYTICAL LABORATORIES	SM 2130 B-01
		1095	ZINC		<	50.000	UG/L	5000	50	9/28/2020	9	36		2023/09		65140012009281015G	1180	BSK ANALYTICAL LABORATORIES	
	IO	INORGANIC																	
		1002	ALUMINUM		<	50.000	UG/L	1000	50	2/25/2020	9	36		2023/02		65140012002251000I	1180	BSK ANALYTICAL LABORATORIES	
		1074	ANTIMONY, TOTAL		<	6.000	UG/L	6	6	2/25/2020	9	36		2023/02		65140012002251000I	1180	BSK ANALYTICAL LABORATORIES	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 01 - EAST - RAW CLASS: DCSGA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_001_001	IO	INORGANIC																	
		1005	ARSENIC		<	2.000	UG/L	10	2	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
		1010	BARIUM		<	100.000	UG/L	1000	100	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
		1075	BERYLLIUM, TOTAL		<	1.000	UG/L	4	1	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
		1015	CADMIUM		<	1.000	UG/L	5	1	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
		1020	CHROMIUM		<	10.000	UG/L	50	10	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
		1025	FLUORIDE	0.100		0.100	MG/L	2	0.1	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
		1035	MERCURY		<	1.000	UG/L	2	1	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
		1036	NICKEL		<	10.000	UG/L	100	10	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
		1039	PERCHLORATE	4.000		4.000	UG/L	6	4	6/3/2021	16	36		2024/06		6514001210603095OI	1180	BSK ANALYTICAL LABORATORIES	
		1045	SELENIUM		<	5.000	UG/L	50	5	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
		1085	THALLIUM, TOTAL		<	1.000	UG/L	2	1	2/25/2020	9	36		2023/02		6514001200225100OI	1180	BSK ANALYTICAL LABORATORIES	
	NI	NITRATE/NITRITE																	
		1040	NITRATE	9.800		0.230	MG/L	10	0.4	7/28/2022	400	3	Interval	2022/10		AFG3472-01	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT

COUNTY: TULARE

Sample Point: WELL 01 - EAST - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORTING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MONTHS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD	
CA5401003_001_001	NI	NITRATE/NITRITE																			
		1041	NITRITE		<	0.400		MG/L	1	0.4	2/25/2020	9	36			2023/02		65140012002251000N	1180	BSK ANALYTICAL LABORATORIES	
	RA	RADIOLOGICAL																			
		4109	GROSS ALPHA PARTICLE ACTIVITY	3.380		1.300	1.450	PCI/L	15	3	6/22/2018	16	72	Interval	2024/06			65140011806221350R	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	S1	REGULATED VOC																			
		2981	1,1,1-TRICHLOROETHANE		<	0.500		UG/L	200	0.5	5/24/2019	16	36			2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2988	1,1,2,2-TETRACHLOROETHANE		<	0.500		UG/L	1	0.5	5/24/2019	16	36			2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2985	1,1,2-TRICHLOROETHANE		<	0.500		UG/L	5	0.5	5/24/2019	16	36			2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2978	1,1-DICHLOROETHANE		<	0.500		UG/L	5	0.5	5/24/2019	16	36			2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2977	1,1-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	5/24/2019	16	36			2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2378	1,2,4-TRICHLOROBENZENE		<	0.500		UG/L	5	0.5	5/24/2019	9	36			2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2968	O-DICHLOROBENZENE		<	0.500		UG/L	600	0.5	5/24/2019	16	36			2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
2980		1,2-DICHLOROETHANE		<	0.500		UG/L	0.5	0.5	5/24/2019	16	36			2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES		

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 01 - EAST - RAW CLASS: DCSGA STATUS: Active

PCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_001_001	S1	REGULATED VOC																	
		2983	1,2-DICHLOROPROPANE		<	0.500	UG/L	5	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2413	1,3-DICHLOROPROPENE		<	0.500	UG/L	0.5	0.5	5/24/2019	9	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2969	P-DICHLOROBENZENE		<	0.500	UG/L	5	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2990	BENZENE		<	0.500	UG/L	1	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2982	CARBON TETRACHLORIDE		<	0.500	UG/L	0.5	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2380	CIS-1,2-DICHLOROETHYLENE		<	0.500	UG/L	6	0.5	5/24/2019	9	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2964	DICHLOROMETHANE		<	0.500	UG/L	5	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2992	ETHYLBENZENE		<	0.500	UG/L	300	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2251	METHYL TERT-BUTYL ETHER		<	3.000	UG/L	13	3	5/24/2019	49	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2989	CHLOROBENZENE		<	0.500	UG/L	70	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	
		2996	STYRENE		<	0.500	UG/L	100	0.5	5/24/2019	9	36		2022/05	DUE NOW	65140011905241035V	1180	BSK ANALYTICAL LABORATORIES	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 01 - EAST - RAW CLASS: DCSGA STATUS: Active

PCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_001_001	S1	REGULATED VOC																	
		2987	TETRACHLO ROETHYLEN E		<	0.500	UG/L	5	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011 90524103 5V	1180	BSK ANALYTICAL LABORATORIES	
		2991	TOLUENE		<	0.500	UG/L	150	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011 90524103 5V	1180	BSK ANALYTICAL LABORATORIES	
		2979	TRANS-1,2- DICHLOROE THYLENE		<	0.500	UG/L	10	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011 90524103 5V	1180	BSK ANALYTICAL LABORATORIES	
		2984	TRICHLORO ETHYLENE		<	0.500	UG/L	5	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011 90524103 5V	1180	BSK ANALYTICAL LABORATORIES	
		2218	TRICHLORO FLUOROMET HANE		<	5.000	UG/L	150	5	5/24/2019	16	36		2022/05	DUE NOW	65140011 90524103 5V	1180	BSK ANALYTICAL LABORATORIES	
		2904	TRICHLORO TRIFLUORO ETHANE		<	10.000	UG/L	1200	10	5/24/2019	9	36		2022/05	DUE NOW	65140011 90524103 5V	1180	BSK ANALYTICAL LABORATORIES	
		2976	VINYL CHLORIDE		<	0.500	UG/L	0.5	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011 90524103 5V	1180	BSK ANALYTICAL LABORATORIES	
		2955	XYLENES, TOTAL		<	0.500	UG/L	1750	0.5	5/24/2019	16	36		2022/05	DUE NOW	65140011 90524103 5V	1180	BSK ANALYTICAL LABORATORIES	
	S2	REGULATED SOC																	
		2414	1,2,3- TRICHLORO PROPANE		<	0.005	UG/L	0.005	0.005	6/29/2022	64	36		2025/06		AFF3490- 01	1180	BSK ANALYTICAL LABORATORIES	SRL 524M- TCP
		2051	LASSO (ALACHLOR)		<	1.000	UG/L	2	1	12/28/2020	4	36		2023/12		65140012 01228095 5S	1180	BSK ANALYTICAL LABORATORIES	
		2050	ATRAZINE		<	0.500	UG/L	1	0.5	12/28/2020	4	36		2023/12		65140012 01228095 5S	1180	BSK ANALYTICAL LABORATORIES	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT

COUNTY:

Sample Point:

CLASS: DCSGA

STATUS:

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_001_001	S2	2931	1,2-DIBROMO-3-CHLOROPROpane		<	0.000		UG/L	0.2	0.01	12/28/2020	9	36		2023/12		65140012012280955S	1180	BSK ANALYTICAL LABORATORIES	
		2946	ETHYLENE DIBROMIDE		<	0.000		UG/L	0.05	0.02	12/28/2020	9	36		2023/12		65140012012280955S	1180	BSK ANALYTICAL LABORATORIES	
		2037	SIMAZINE		<	1.000		UG/L	4	1	12/28/2020	4	36		2023/12		65140012012280955S	1180	BSK ANALYTICAL LABORATORIES	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 02 - WEST - RAW CLASS: DCSGA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_002_002		EAST OROSI COMMUNITY SERVICES DISTRICT					WELL 02 - WEST - RAW												
	GP	SECONDARY/GP																	
		1928 ALKALINITY, BICARBONATE	230.000		3.000		MG/L	-----	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 2320 B
		1919 CALCIUM	74.000		0.100		MG/L	-----	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1929 ALKALINITY, CARBONATE		<	3.000		MG/L	-----	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 2320 B
		1017 CHLORIDE	29.000		1.000		MG/L	500	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0
		1905 COLOR	5.000		5.000		UNITS	15	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 2120 B
		1022 COPPER, FREE		<	5.000		UG/L	1000	50	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		2905 FOAMING AGENTS (SURFACTANTS)		<	0.050		MG/L	0.5	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 5540 C-00
		1915 HARDNESS, TOTAL (AS CACO3)	320.000		0.410		MG/L	-----	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 2340 B
		1021 HYDROXIDE AS CALCIUM CARBONATE		<	3.000		MG/L	-----	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 2320 B
		1028 IRON		<	30.000		UG/L	300	100	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1031 MAGNESIUM	34.000		0.100		MG/L	-----	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1032 MANGANESE		<	10.000		UG/L	50	20	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 02 - WEST - RAW CLASS: DCSGA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_002_002	GP	SECONDARY/GP																	
		1920	ODOR		<	1.000	TON	3	1	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 2150 B
		1925	PH	7.900		0.000		-----	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 4500-HB
		1050	SILVER		<	10.000	UG/L	100	10	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1052	SODIUM	28.000		1.000	MG/L	-----	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1064	CONDUCTIVITY @ 25 C UMHOS/CM	760.000		1.000	UMHO/CM	1600	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 2510 B
		1055	SULFATE	66.000		1.000	MG/L	500	0.5	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0
		1930	TDS	470.000		5.000	MG/L	1000	-----	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 2540 C
		0100	TURBIDITY	0.170		0.100	NTU	5	0.1	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	SM 2130 B-01
		1095	ZINC		<	50.000	UG/L	5000	50	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
	IO	INORGANIC																	
		1002	ALUMINUM		<	50.000	UG/L	1000	50	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1074	ANTIMONY, TOTAL		<	2.000	UG/L	6	6	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1005	ARSENIC	2.400		2.000	UG/L	10	2	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 02 - WEST - RAW CLASS: DCSGA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_002_002	IO	INORGANIC																	
		1010	BARIUM	130.000		50.000	UG/L	1000	100	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.7
		1075	BERYLLIUM, TOTAL		<	1.000	UG/L	4	1	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1015	CADMIUM		<	1.000	UG/L	5	1	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1020	CHROMIUM		<	10.000	UG/L	50	10	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1025	FLUORIDE	0.120		0.100	MG/L	2	0.1	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0
		1035	MERCURY		<	0.200	UG/L	2	1	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1036	NICKEL		<	10.000	UG/L	100	10	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1039	PERCHLORATE	3.600		2.000	UG/L	6	2	3/23/2022	16	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 314.0
		1045	SELENIUM		<	2.000	UG/L	50	5	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
		1085	THALLIUM, TOTAL		<	1.000	UG/L	2	1	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 200.8
	NI	NITRATE/NITRITE																	
		1040	NITRATE	13.000		0.230	MG/L	10	0.4	4/28/2022	900	3	Interval	2022/07	DUE NOW	AFD3347-01	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0
		1041	NITRITE		<	0.050	MG/L	1	0.4	3/23/2022	9	36		2025/03		AFC2635-01	1180	BSK ANALYTICAL LABORATORIES	EPA 300.0

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 02 - WEST - RAW CLASS: DCSGA STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD	
CA5401003_002_002	RA	RADIOLOGICAL																			
		4109	GROSS ALPHA PARTICLE ACTIVITY	5.540		1.100	0.397	PCI/L	15	3	3/22/2019	16	72	Interval	2025/03		65140021903220905R	1180	BSK ANALYTICAL LABORATORIES		
		4030	RADIUM-228		<	0.642	0.736	PCI/L	-----	1	6/29/2022	100	3	Interval	2022/09	DUE NOW	SP 2210845-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA RA-05	
	S1	REGULATED VOC																			
		2981	1,1,1-TRICHLOROETHANE		<	0.500		UG/L	200	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES		
		2988	1,1,2,2-TETRACHLOROETHANE		<	0.500		UG/L	1	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES		
		2985	1,1,2-TRICHLOROETHANE		<	0.500		UG/L	5	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES		
		2978	1,1-DICHLOROETHANE		<	0.500		UG/L	5	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES		
		2977	1,1-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES		
		2378	1,2,4-TRICHLOROBENZENE		<	0.500		UG/L	5	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES		
		2968	O-DICHLOROBENZENE		<	0.500		UG/L	600	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES		
		2980	1,2-DICHLOROETHANE		<	0.500		UG/L	0.5	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES		

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 02 - WEST - RAW CLASS: DCSGA STATUS: Active

PCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_002_002	S1	REGULATED VOC																	
		2983	1,2-DICHLOROPROPANE		<	0.500	UG/L	5	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2413	1,3-DICHLOROPROPENE		<	0.500	UG/L	0.5	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2969	P-DICHLOROBENZENE		<	0.500	UG/L	5	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2990	BENZENE		<	0.500	UG/L	1	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2982	CARBON TETRACHLORIDE		<	0.500	UG/L	0.5	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2380	CIS-1,2-DICHLOROETHYLENE		<	0.500	UG/L	6	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2964	DICHLOROMETHANE		<	0.500	UG/L	5	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2992	ETHYLBENZENE		<	0.500	UG/L	300	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2251	METHYL TERT-BUTYL ETHER		<	3.000	UG/L	13	3	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2989	CHLOROBENZENE		<	0.500	UG/L	70	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	
		2996	STYRENE		<	0.500	UG/L	100	0.5	2/25/2020	9	36		2023/02		65140022002251010V	1180	BSK ANALYTICAL LABORATORIES	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 02 - WEST - RAW CLASS: DCSGA STATUS: Active

PCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_002_002	S1	REGULATED VOC																	
		2987	TETRACHLO ROETHYLEN E		<	0.500	UG/L	5	0.5	2/25/2020	9	36		2023/02		65140022 00225101 0V	1180	BSK ANALYTICAL LABORATORIES	
		2991	TOLUENE		<	0.500	UG/L	150	0.5	2/25/2020	9	36		2023/02		65140022 00225101 0V	1180	BSK ANALYTICAL LABORATORIES	
		2979	TRANS-1,2- DICHLOROE THYLENE		<	0.500	UG/L	10	0.5	2/25/2020	9	36		2023/02		65140022 00225101 0V	1180	BSK ANALYTICAL LABORATORIES	
		2984	TRICHLORO ETHYLENE		<	0.500	UG/L	5	0.5	2/25/2020	9	36		2023/02		65140022 00225101 0V	1180	BSK ANALYTICAL LABORATORIES	
		2218	TRICHLORO FLUOROMET HANE		<	5.000	UG/L	150	5	2/25/2020	9	36		2023/02		65140022 00225101 0V	1180	BSK ANALYTICAL LABORATORIES	
		2904	TRICHLORO TRIFLUORO ETHANE		<	10.000	UG/L	1200	10	2/25/2020	9	36		2023/02		65140022 00225101 0V	1180	BSK ANALYTICAL LABORATORIES	
		2976	VINYL CHLORIDE		<	0.500	UG/L	0.5	0.5	2/25/2020	9	36		2023/02		65140022 00225101 0V	1180	BSK ANALYTICAL LABORATORIES	
		2955	XYLENES, TOTAL		<	0.500	UG/L	1750	0.5	2/25/2020	9	36		2023/02		65140022 00225101 0V	1180	BSK ANALYTICAL LABORATORIES	
	S2	REGULATED SOC																	
		2414	1,2,3- TRICHLORO PROPANE		<	0.005	UG/L	0.005	0.005	3/30/2022	49	12	Interval	2023/03		AFC3336- 01	1180	BSK ANALYTICAL LABORATORIES	SRL 524M- TCP
		2051	LASSO (ALACHLOR)		<	1.000	UG/L	2	1	6/4/2020	4	36		2023/06		65140022 00604110 0S	1180	BSK ANALYTICAL LABORATORIES	
		2050	ATRAZINE		<	0.500	UG/L	1	0.5	6/4/2020	4	36		2023/06		65140022 00604110 0S	1180	BSK ANALYTICAL LABORATORIES	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT

COUNTY:

Sample Point:

CLASS: DCSGA

STATUS:

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_002_002	S2	2931	1,2-DIBROMO-3-CHLOROPROpane		<	0.000		UG/L	0.2	0.01	6/4/2020	9	36		2023/06		65140022006041100S	1180	BSK ANALYTICAL LABORATORIES	
		2946	ETHYLENE DIBROMIDE		<	0.000		UG/L	0.05	0.02	6/4/2020	9	36		2023/06		65140022006041100S	1180	BSK ANALYTICAL LABORATORIES	
		2037	SIMAZINE		<	1.000		UG/L	4	1	6/4/2020	4	36		2023/06		65140022006041100S	1180	BSK ANALYTICAL LABORATORIES	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: ST2S1 - 13920 AVE 418 CLASS: DBPT STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD		
CA5401003_ DST_900		EAST OROSI COMMUNITY SERVICES DISTRICT						ST2S1 - 13920 AVE 418														
	DBP	DISINFECTION BYPRODUCTS																				
		2943	BROMODIC HLOROMET HANE		<	0.500		UG/L	-----	1	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2		
		2942	BROMOFOR M		<	0.500		UG/L	-----	1	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2		
		2941	CHLOROFOR M		<	0.500		UG/L	-----	1	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2		
		2454	DIBROMOAC ETIC ACID		<	1.000		UG/L	-----	1	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3		
		2944	DIBROMOC HLOROMET HANE		<	0.500		UG/L	-----	1	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2		
		2451	DICHLOROA CETIC ACID		<	1.000		UG/L	-----	1	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3		
		2456	TOTAL HALOACETI C ACIDS (HAA5)		<	2.000		UG/L	60	-----	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3		
		2453	MONOBROM OACETIC ACID		<	1.000		UG/L	-----	1	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3		
		2450	MONOCHLO ROACETIC ACID		<	2.000		UG/L	-----	2	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3		
		2950	TTHM		<	0.500		UG/L	80	-----	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 524.2		

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: EAST OROSI COMMUNITY SERVICES DISTRICT

COUNTY:

Sample Point:

CLASS: DBPT

STATUS:

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5401003_ DST_900	DBP	2452	TRICHLORO ACETIC ACID		<	1.000		UG/L	-----	1	6/29/2022	4	36		2025/06		AFF3490- 03	1180	BSK ANALYTICAL LABORATORIES	EPA 552.3

Appendix C:
Source Water and Distribution System Bacteriological Monitoring Reports

Bacteriological Distribution Monitoring Report

5401003 East Orosi Community Services Distr

Distribution System Freq: 1/M

Sample Date	Location	T Coli	E Coli	F Coli	HPC	Type	Cl2	Cl2 Avg	Viol. Type	GWR Satisfied?	Comments
8/23/2022	See Notes										DND (water outage) rescinded per KW.
8/3/2022	Church	A	A			Routine	1.2				
7/26/2022	Church	A	A			Routine	1.2				
7/13/2022	See Notes										DND issued per KW-TW (water outage)
7/5/2022	See Notes										DND rescinded per TW- KW
6/29/2022	Church	A	A			Routine	1.0				
5/23/2022	Church	A	A			Routine	0.7				
4/28/2022	Church	A	A			Routine	0.7				
3/22/2022	Church	A	A			Routine	0.8				
3/11/2022	See Notes										DND issued per BP (water outage/Well 01 failure)
2/15/2022	Church	A	A			Routine	0.7				
1/28/2022	Church	A	A			Routine	0.7				
12/28/2021	Church	A	A			Routine	1.1				
11/18/2021	Church	A	A			Routine	1				
10/26/2021	Church	A	A			Routine	0.7				
10/26/2021	Church	A	A			Routine	0.7				
9/27/2021	Church	A	A			Routine	0.7				
8/20/2021	Church	A	A			Routine	0.8				
7/20/2021	Church	A	A			Routine	0.8				
6/24/2021	Church	A	A			Routine	1.0				
5/20/2021	Church	A	A			Routine	0.7				
4/21/2021	Church	A	A			Routine	0.8				
3/25/2021	Church	A	A			Routine	0.8				
2/18/2021	Church	A	A			Routine	0.7				
1/14/2021	Church	A	A			Routine	0.8				
12/10/2020	Church	A	A			Routine	0.8				
11/23/2020	Church	A	A			Routine	0.8				
10/13/2020	Church	A	A			Routine	1.00				
9/18/2020	Church	A	A			Routine			MR9		no chlorine residual on report
8/14/2020	Church	A	A			Routine	1				
7/23/2020	Church	A	A			Routine	0.7				
6/19/2020	Church	A	A			Routine			MR9		no chlorine residual on report
5/7/2020	Church	A	A			Routine	0.7				
4/10/2020	Church	A	A			Routine	0.9				
3/20/2020	Church	A	A			Routine	1.0				
2/6/2020	Church	A	A			Routine	0.90				
1/10/2020	Church	A	A			Routine	0.9				
12/5/2019	Church	A	A			Routine	0.9				
11/8/2019	Church	A	A			Routine	1.0				
10/15/2019	Church	A	A			Routine	1.0				
9/18/2019	Church	A	A			Routine	1.0				
8/28/2019	Church	A	A			Routine	1.1				
7/16/2019	Church	A	A			Routine	0.90				
6/6/2019	Church	A	A			Routine	0.80				
5/17/2019	Church HB	<1	<1			Routine	0.7				
4/10/2019	Church	A	A			Routine	0.90				
3/12/2019	Church	A	A			Routine	1.0				

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>Cl2</i>	<i>Cl2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
3/4/2019	5 samples	<1.0	<1.0			Other	0.69-0.95				investigative samples
2/19/2019	Church location	A	A			Routine					
1/1/2019	No sample								MR1		Cit 03-24-19C-010 with fine

Violation Key

MCL	Exceeds the maximum contaminant level	MR5	Incorrect number of repeat samples as follow-up to a positive sample
MR1	No monthly sample for the report month	MR6	No source sample
MR2	No quarterly sample for the report month	MR7	No summary report submitted
MR3	Incorrect number of routine samples for the report month	MR8	Other comments and/or info
MR4	Did not collect 5 routine samples for previous month's positive sample	MR9	Cl2 not reported

Source Bacteriological Monitoring Report

5401003 East Orosi Community Services District

Sample Date	Time	Source	Sample Type	Test Method	T Coli	E Coli	F Coli	HPC	Violation	Comments
8/11/2022	9:58	East Well	Well	QTray	<1	<1				
8/3/2022	10:58	East Well	Well	QTray	<1	<1				
7/22/2022	10:40	East Well	Well	QTray	<1	<1				
7/1/2022	11:10	East Well	Well	QTray	<1	<1				
6/29/2022	10:22	West Well	Well	QTray	>200.5	<1				
6/13/2022	11:10	East Well	Well	QTray	3.1	<1				
6/6/2022	10:45	East Well	Well	QTray	25.4	<1				
5/31/2022	9:11	East Well	Well	Qtray	3.1	<1				
5/27/2022	10:24	East Well	Well	Qtray	200.5	78.2				
5/23/2022	10:23	West Well	Well	Qtray	<1	<1				
4/28/2022	8:54	West Well	Well	Qtray	<1	<1				
3/22/2022	10:46	West Well	Well	Qtray	<1	<1				
2/15/2022	10:30	East Well	Well	Qtray	<1	<1				
2/15/2022	10:38	West Well	Well	Qtray	<1	<1				
1/28/2022	10:20	East Well	Well	Qtray	<1	<1				
1/28/2022	10:38	West Well	Well	Qtray	<1	<1				
12/28/2021	10:26	East Well	Well	Qtray	<1	<1				
12/28/2021	10:40	West Well	Well	Qtray	<1	<1				
11/18/2021	10:10	East Well	Well	Qtray	<1	<1				
11/18/2021	10:24	West Well	Well	Qtray	<1	<1				
10/26/2021		Wells: East, West	Well	QTray	<1	<1				
10/26/2021	9:55	East Well	Well	Qtray	<1	<1				
10/26/2021	10:07	West Well	Well	Qtray	<1	<1				
9/27/2021	10:02	East Well	Well	Qtray	<1	<1				
9/27/2021	10:12	West Well	Well	Qtray	<1	<1				
8/20/2021	10:42	East Well	Well	Qtray	<1	<1				
8/20/2021	10:58	West Well	Well	Qtray	<1	<1				
7/20/2021	10:18	East Well	Well	QTray	<1	<1				
7/20/2021	10:32	West Well	Well	QTray	1	<1				
6/24/2021		Wells: East, West	Well	QTray	<1	<1				
5/20/2021		Wells: East, West	Well	Qtray	<1	<1				
4/21/2021		Wells: East, West	Well	Qtray	<1	<1				
3/25/2021		Wells: East, West	Well	Qtray	<1	<1				
2/18/2021		Wells: East, West	Well	Qtray	<1	<1				
1/14/2021		Wells: East, West	Well	Qtray	<1	<1				
12/10/2020		Wells: East, West	Well	Qtray	<1	<1				
11/23/2020	10:08	Wells: East, West	Well	Qtray	<1.0	<1.0				
10/13/2020		Wells: East, West	Well	Qtray	<1	<1				
9/18/2020		Wells: East, West	Well	Qtray	<1	<1				
8/14/2020		Wells: East, West	Well	Qtray	<1	<1				
7/23/2020		Wells: East, West	Well	Qtray	<1	<1				

5401003 East Orosi Community Services District

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
6/19/2020		Wells: East, West	Well	QTray	<1	<1				
5/7/2020		Wells: East, West	Well	QTray	<1	<1				
4/10/2020		Wells: East, West	Well	QTray	<1	<1				
3/20/2020		Wells: East, West	Well	QTray	<1	<1				
2/6/2020		Wells: East, West	Well	QTray	<1	<1				
1/10/2020		Wells: East, West	Well	QTray	<1	<1				
12/5/2019		Wells: East, West	Well	QTray	<1	<1				
11/8/2019		Wells: East, West	Well	QTray	<1	<1				
10/15/2019		Wells: East West	Well	QTray	<1	<1				
9/18/2019	10:40	East Well	Well	QTray	<1	<1				
9/18/2019	10:55	West Well	Well	QTray	<1	<1				
8/28/2019		Wells: East, West	Well	QTray	<1	<1				
7/16/2019		Wells: East, West	Well	QTray	<1	<1				
6/6/2019		Wells; East, West	Well	QTray	<1	<1				
5/24/2019	11:10	West Well	Well	QTray	<1	<1				
5/17/2019	10:35	East Well	Well	P/A	P	A				
5/17/2019	10:35	West Well	Well	QTray	<1	<1				
4/19/2019	11:00	West Well	Well	QTray	<1	<1				
4/10/2019	10:46	East Well	Well	QTray	<1	<1				
3/14/2019	10:50	West Well	Well	QTray	<1	<1				
3/4/2019	11:23	Well 02 - West	Well	QTray	<1.0	<1.0				investigative sample
2/19/2019		Well 02 - West	Well	QTray	<1	<1				

Appendix D:
Lead and Copper Tap Sample Results Reporting Form



State Water Resources Control Board

Division of Drinking Water

Lead and Copper Tap Sample Results Reporting Form

This form must be submitted to the regulating entity (DDW District Office or County Agency) for each round of lead and copper sampling

Report Date: (mm/dd/yyyy)		Sampling Site Change
Water System Name:		<i>If any sampling sites were changed, please list the old site, new site, and reason for the change in the box below.</i>
Water System Number:		
Sample Schedule:	<input checked="" type="radio"/> 6-month <input type="radio"/> Annual <input type="radio"/> Triennial	
# of Samples Required:		
# of Samples Reported:		
	90th Percentile Level (mg/L)	
Lead:		
Copper:		

	Sample Date	Sample Site Location/Address	Tier 1, 2 or 3	Result	
				Lead (mg/L)	Copper (mg/L)
01					
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Number of Tap Sample Sites Required

The number of tap sample sites required is based on the number of people served (system size) by your water system and also whether you are performing Standard or Reduced Monitoring (CCR §64675).

System Size	Minimum Number of Sites	
	Standard Tap Sampling	Reduced Tap Sampling
> 100,000	100	50
10,001 to 100,000	60	30
3,301 to 10,000	40	20
501 to 3,300	20	10
101 to 500	10	5
< 101	5	5

Determining the 90th Percentile Lead and Copper Level

Number of Tap Samples Collected	Determination of 90 th Percentile Lead or Copper Level
5	Average the 4 th and 5 th highest sample results to get the 90 th percentile level
More than 5	Place results in ascending order and assign each sample a number, 1 for the lowest concentration. Multiply the total number of samples by 0.9. Round down to the nearest whole number if the decimal is 0.4 or lower and round up if the decimal is 0.5 or higher. The sample result that corresponds with the nearest whole number is the 90 th percentile.

Notification of Results

As required by *40 Code of Federal Regulations Section 141.85(d)*, within 30 days of learning of the tap monitoring results, I notified the participants, by mailing or by another method approved by the State, of the lead sample results from their individual taps, provided an explanation of the health effects of lead, listed steps the consumer could take to reduce exposure to lead, provided contact information for the water utility, the maximum contaminant level goal for lead, action level for lead, and any definitions.

Notification was done on: _____ (date)

SIGNATURE:	DATE:
NAME (Print):	TITLE:

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Additional Samples				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2 or 3	Lead (mg/L)	Copper (mg/L)
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					

Appendix E:
Cross Connection Control Survey Guidance

Cross-Connection Control for Small Community Water Systems

Division of Drinking Water – Tulare District

Purpose of Cross-Connection Control Program: Water provided by a public water system may be contaminated via cross-connections within the distribution system. The purpose of the cross-connection control program is to reduce the hazard of contamination of the public water system by identifying actual and potential cross-connections and taking action to protect the system from these hazards. This is accomplished by installing backflow prevention assemblies where hazards are identified; or ensuring that water-using equipment on the premises is installed in accordance with plumbing code requirements and good practice.

What are cross-connections?

Cross-connections are actual and potential unprotected connections between a potable water system and any source or system containing unapproved water or a substance which is not safe. Examples of cross-connections include:

1. Improperly installed irrigation systems that may allow backsiphonage of stagnant, bacteriologically unsafe water into the piping system.
2. Improperly plumbed water-using devices such as hot-tubs, boilers or commercial dishwashers which may allow unsafe water back into the domestic piping system.
3. Irrigation systems served by an auxiliary source, such as a private well or creek. Such systems create a potential for major contamination of the public water system via interties with the domestic piping system.
4. Interconnections between the potable system and a non-potable system.

What the Regulations Require

Section 7584 of the California Code of Regulations requires that each public water system have a cross connection control program that includes these elements:

1. The adoption of operating rules or ordinances to implement the cross-connection program.
2. The conducting of surveys to identify water user premises where cross connections exist or are likely to occur.
3. The provisions of backflow protection by the water user at all connections where a cross connection hazard has been identified.
4. The provision of at least one person trained in cross connection control to carry out the program.
5. The establishment of a procedure or system for testing backflow prevention assemblies.
6. The maintenance of records of locations, tests, and repairs of backflow prevention assemblies within each water supplier's distribution system.

Getting Started

For small community water systems, the initial elements of the program consist of the following:

1. Adopting an ordinance or set of rules to implement the cross-connection control program. The ordinance or set of rules is important since it establishes the legal authority to carry out the program.
2. Conducting a system survey to identify actual and potential cross-connection hazards.
3. Ensuring that hazards are abated by the installation of backflow prevention assemblies at the meter, eliminating the hazard in conjunction with the owner of the property or providing internal cross-connection protection.

System Survey

The system survey consists of a preliminary survey and, if necessary, a more detailed second survey. For most small systems, the initial survey may consist of a questionnaire sent to each customer asking whether the customer has specific potential hazards. Documentation of the system survey is to be submitted to the Division. Attached is a summary form for documentation of the system survey.

Residential areas

Customers should be asked if any of the following are located on-site:

1. Auxiliary water supply (i.e. either a well or a creek pump) - backflow prevention device is mandatory.
2. Irrigation systems - backflow prevention device not required if system is installed in accordance with plumbing codes with appropriate vacuum breakers.
3. Swimming pool, hot tub or spa - backflow prevention device not required if system is installed in accordance with plumbing codes.
4. Solar hot water heating panels - backflow prevention device not required if system is installed in accordance with plumbing codes.
5. Gray water systems - backflow prevention assemblies may not be required if the system is installed in accordance with the Uniform Plumbing Code.

If these or other potential hazards are located on site, the water system is to determine whether the equipment has been installed in accordance with plumbing codes and/or good practice in order to minimize the risk of backflow.

Commercial customers: A more detailed questionnaire and survey is necessary. Small community systems, which also serve commercial customers, should review the Department of Health Service's "Manual of Cross-Connection Control - Procedures and Practices". A system survey of commercial users as specified in the Manual is to be performed. As an alternative, the system may decide to require backflow prevention assemblies' at all commercial service connections where hazards are likely to exist.

Wastewater and Hazardous Wastes: A service connection which handles wastewater or dangerous chemicals requires special evaluation and protection from cross-connection hazards. For additional information on evaluating this type of facility, please contact the appropriate regulatory agency and a cross-connection control specialist.

ELEMENTS OF A CROSS-CONNECTION CONTROL PROGRAM DDW – Tulare District

When implementing a Cross-Connection Control Program, the water supplier or health agency should follow an organized plan. The following items should be included as a minimum. The items **explain the Department of Health Services' policy regarding the regulations.**

7584. Responsibility and Scope of Program

The water supplier shall protect the public water supply from contamination by implementation of a cross-connection control program. The program, or any portion thereof, may be implemented directly by the water supplier or by means of a contract with the local health agency, or with another agency approved by the health agency. The water supplier's cross-connection control program shall for the purpose of addressing the requirements of Sections 7585 through 7605 include, but not limited to, the following elements:

(1) *The adoption of operating rules or ordinances to implement the cross-connection program.*

A public water supplier shall enact an ordinance or rule of service outlining the cross-connection control program and providing enforcement authority.

(2) *The conducting of surveys to identify places where cross-connections are likely to occur.*

Water utilities do not have any responsibility for controlling or abating cross-connections on a user's premises. All existing facilities where potential cross-connections are suspected, however, shall be listed and inspected or reinspected on a priority basis, where feasible. All applications for new services or for enlarging existing services or changing of occupant shall be reviewed or screened for cross-connections hazards

(3) *The provision of backflow protection at the user's connection or within the user's premises or both.*

Adequate provisions for implementation and enforcement of backflow protection where needed including the shutting off service when necessary

4) *The provision of at least one person trained in cross-connection control to carry out the cross-connection program.*

Specific units of the health agency and/or water supplier should be designated to organize and carry out the cross-connection control program. The personnel in those units should be trained as to the causes and hazards of unprotected cross-connections.

(5) *The establishment of a procedure or system for testing backflow preventers.*

A list of approved backflow preventers and list of certified testers should be made available to each water user required to provide backflow protection.

The list may include backflow devices approved by University of Southern California, Foundation for Cross-Connection Control and IAPMO, which may be found on the SWRCB website at the following address:

http://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/Publications.shtml

The List of certified testers may be lists developed by the American Water Works Association and local county health agencies.

Backflow preventers should be tested at least yearly or more often as required by the health agency or water supplier.

(6) *The maintenance of records of locations, tests and repairs of backflow preventers*

Adequate records should be kept and filed for reference. These records should include, in addition to the name of the owner of the premises, the:

- a) Date of inspection
- b) Results of inspection
- c) Required protection
- d) List of all backflow preventer devices in the system
- e) Test and maintenance reports
- f) All correspondence between the water supplier, the local health authority, and the consumer
- g) Records must be maintained for a minimum of three years

Records of inspection and testing should be evaluated to determine if:

- a) Devices are frequently or sufficiently reviewed to detect failure.
- b) There are unusual feature of a particular model of device or component.
- c) Cause of failure can be eliminated.

A program should be established to notify the water user when his backflow preventer must be tested. (A minimum of once each year is required.) After installation or repair, a backflow preventer should be tested and approved before it is accepted.

7605. Testing and Maintenance of Backflow Preventers

Regulations require the following regarding testing and maintenance of backflow prevention devices:

- (a) The water supplier shall assure that adequate maintenance and periodic testing are provided by the water user to ensure their proper operation.
- (b) Backflow preventers shall be tested by persons who have demonstrated their competency in testing of these devices to the water supplier or health agency.
- (c) Backflow preventers shall be tested at least annually or more frequently if determined to be necessary by the health agency or water supplier. When devices are found to be defective, they shall be repaired or replaced in accordance with the provisions of this Chapter.
- (d) Backflow preventers shall be tested immediately after they are installed, relocated or repaired and not placed in service unless they are functioning as required.
- (e) The water supplier shall notify the water user when testing of backflow preventers is needed. The notice shall contain the date when the test must be completed.
- (f) Reports of testing and maintenance shall be maintained by the water supplier for a minimum of three years.

Cross-Connection Survey Summary Form-Small Community Water Systems

Name of System _____ System Number _____

Description of Survey Procedures-How survey was conducted, (include copy of survey form):
Person conducting survey (List name and qualifications):

Procedures for Residential Connections:

Procedures for Commercial Connections:

Total number of service connections _____ Number of service connections surveyed _____
Number of connections with auxiliary sources (i.e. wells or creek pumps) _____
Number of connections with other hazards _____
Total number of backflow prevention devices _____

Type of Hazard Identified(i.e. private well, hot tub, irrigation system, swimming pool, etc)	Number of connections with hazard	Number of devices installed	Number where device not necessary

Describe follow-up for service connections that did not respond to the survey:

Long-term (Describe on-going cross-connection protection & testing of backflow prevention assemblies)

Submitted by (signature) _____ Date _____

Appendix F:
Chlorine Operations Plan Guidance

Guidance Document for the Preparation of an Operations Plan For Small Water Systems With Chlorination

Written Description of Water Sources, Storage Tanks and Distribution System (with as-built maps or schematics) and General Record Keeping

We recommend a brief description of sources, storage, chlorinator unit (treatment) and number of connections and character (seasonal rental, year-round, etc.). Example; 200 foot well drilled in 1972, 1500 gallon welded steel storage tank, chlorinator with a diaphragm type pump (manufacturer and model) and 25 gallon disinfectant reservoir, serving 15 connections (one third seasonal occupancy).

We strongly recommend a multi-tabbed file be set up to keep copies of the laboratory results (10 year retention) and monitoring requirements and an accompanying calendar schedule for all sampling.

Other files that should be kept on file are copies of correspondence from our Division (e.g., water supply permit), all sampling plans (Bacteriological Sample Siting Plan), water main and valve location maps, the well driller's report and County well construction permit that demonstrates conformance to its well ordinance (schematic documenting adequate horizontal protection of well from sanitary hazards), pump and storage tank information, and their accompanying service records, etc.

The Operations Plan elements are as follows:

• **ROUTINE OPERATIONAL PROCEDURES FOR EACH COMPONENT OF THE SYSTEM:**

- A. Visual inspection of **WELL** (daily or minimum of weekly).
Check for the following; water leaks that could contaminate well, unscreened or openings where sealants can be applied, electrical hazards, chemical hazards (proper use of chemicals around well head). Tip: Maintain a log book for each well site that records maintenance and monthly water production and flow rates, water table depths and any maintenance performed.
 - 1. Well has the ability to be pumped to waste and sampling tap (non-threaded down-turned hose bib).
 - 2. Check the pump and controls for proper operation of well and chlorination equipment.
 - 3. General house keeping: remove rodent feces, dirt, vegetation, any standing water, control gophers/squirrel burrowing around well head to eliminate potential contamination hazards.
- B. Visual inspection of the **STORAGE TANKS** (daily or minimum of weekly).
 - 1. Inspect vents and overflow outlets for proper protection (screens, flapper valve, etc.) to keep out rodents and insects.
 - 2. Inspect for any leaks or damage (record observations and repair as needed).
 - 3. Record system pressure. Record the pressure the pump turns on, the pressure the pump turns off and the duration of the run time so storage tank does not overflow.

4. Scheduled inspection and cleaning of storage tank (quarterly, semi-annually or annually). Record kept for the date cleaned and any observations (e.g., remnants of rodents, etc.)
- C. Visual inspection of **CHLORINATOR PUMP** and disinfection reservoir (daily or minimum of weekly).
1. Inspect the pump for proper operation. Hypochlorinator pumps are prone to vapor lock (air bubble in line) and need to be equipped with degassing feature. Installation Tip: The problem can be greatly alleviated by maintaining positive pressure on the intake of the hypochlorinator pump by placing the hypochlorinator pump at the same elevation as the chlorine solution tank.
 2. Inspect the disinfectant in the reservoir for concentration and adequate volume for the operational period (record results).
 3. Determine if there is enough disinfectant on hand for one or more weeks.
- D. Measure the **DISINFECTANT RESIDUAL** in the distribution system (free chlorine test kit required).
1. Monitor and record the results from designated locations which are the same locations as the routine bacteriological sample sites. The residuals must be reported with the bacteriological results at the time the bacteriological sample is collected. This information is also used for reporting the quarterly chlorine residuals under the Disinfection Byproducts Rule). Reporting forms attached.
 2. Determine if an adequate level of disinfectant is maintained.
 - a. If disinfectant level is low (0.2 to 0.3 mg/L is generally the lowest level reportable using colorimetric test kits), determine the reason and correct. If enforcement action taken for repeated Total Coliform Rule violations, there may be more stringent chlorine residual requirements.
 - b. If no measurable disinfectant, notify owner, determine reason, and remedy. If no disinfectant residual for 24 hours, notify Tulare District Office of the California Department of Public Health.
- E. Maintenance of **GAUGES and METERS**.
1. Inspect all gauges and meters for leaks and proper function daily. Repair or replace as needed (keep record of date). Schedule routine calibration checks to ensure accurate readings are being provided.
- F. Inspection and **EXERCISING of the VALVES**.
1. Inspect valves for leaks (record observations, repair or replace if leaking).
 2. Exercise valves on a schedule, as needed (i.e. quarterly, semi-annually, annually, record dates on attached sheet).
- G. Operation and maintenance of **DISTRIBUTION FACILITIES**.
1. Visually inspect the distribution system for leaks on a regular basis. Record date and observations.
 2. Flush dead end mains or lines periodically (quarterly, semi-annually, annually as needed. Record date and observations).

- **MONITORING AND REPORTING:**

- A. **BACTERIOLOGICAL MONITORING FROM DISTRIBUTION SYSTEM;** as per approved Bacteriological Sample Siting Plan, required monthly, report containing results submitted to the Department by the 10th day of the following month (refer to attached guidance). Recommend samples be collected early in the week in case repeat samples must be collected after a positive sample result is received. Repeat samples must be collected within 24 hours of receipt of positive result.
 - 1. If sample positive, lab must notify water system contact person or the Department if you can not be reached. Multiple repeat samples must be collected (three to four repeat samples depending on system classification). Department recommends that water system provides a copy of the Emergency Notification Plan form to analyzing laboratory.
 - 2. Take five routine samples the month following a positive sample.
- B. **BACTERIOLOGICAL MONITORING FROM WELL SOURCES;** should be described in the sample siting plan and is required from raw water at well head PRIOR to chlorination. The samples are required to be analyzed using the density method. If sample positive, notify Department by telephone, e-mail for follow-up investigation. Frequency is dependent on type of water system and report containing the results submitted to the Department by the 10th day of the following month.
- C. **CHEMICAL SOURCE MONITORING;** as required by the Department, forward results to the Department (see attached Water Quality Monitoring Schedule).
- D. **DISINFECTION BYPRODUCT RULE MONITORING;** as required annually for non-transient non-community and community water systems. If less than half the MCL for total trihalomethanes (TTHM) and haloacetic acids (HAA5), the sample can be reduced to once every three years. Routine sample should be collected during the warmest month of the year from a location with the longest detention time in the distribution system. Submit copy of laboratory results to the Visalia District of the CDPH.
- E. **LEAD AND COPPER TAP MONITORING;** as required for nontransient noncommunity and community water systems. Contact Department for when next round of monitoring is due.
- F. **WATER PRODUCTION**
Recommend installation of instantaneous and totalizing flow meter and record daily or at least weekly instantaneous and monthly production volume readings. This is especially valuable and necessary for hard rock wells. This information is reported in the annual report form.
- G. **PUBLIC NOTIFICATION** of violation required.
 - 1. Notification shall be given as per Emergency Notification Plan (copy of form attached). Provide updated plans when personnel change to the Department (attached). Templates of the various for public notices are available at <http://www.cdph.ca.gov/certlic/drinkingwater/Pages/notices.aspx>
 - 2. State the cause of problem, if known, and what steps have been taken to correct it.
 - 3. Send a copy of the notification to the Department with proof of notification.

- **EMERGENCY NOTIFICATION PLAN (ENP), ANNUAL REPORT TO THE DRINKING WATER PROGRAM (ARDWP) AND CONSUMER CONFIDENCE REPORT (CCR):**

- A. ENP: a form that lists the Department's and water system's contact information in the event of **water quality emergency** in which public notification must be performed. It must describe the methods to be followed in order to distribute the public notices to each customer as rapidly as possible. Small system may distribute notices by hand delivery. Attached is a copy of the form.
- B. ARDWP: a form for all water systems that summarizes system operations for the previous calendar year and includes number of service connections and population served and supplemental information relating to consumer complaints, annual water production, sources, and use of NSF approved treatment chemicals, etc. Also provides updated contact and mailing address information. This information is necessary for classification of the system and contact information.
- C. CCR: required for nontransient noncommunity and community water systems that summarizes all monitoring done during the previous calendar year. The CCR must be distributed by July of every year. A template available at <http://www.cdph.ca.gov/certlic/drinkingwater/Pages/CCR.aspx>

- **EMERGENCY OPERATIONAL PRACTICES:**

- A. List of **equipment on hand** for emergency repairs.
 - 1. Miscellaneous wrenches.
 - 2. Leak clamps
- B. List of sources of needed **equipment, not on hand**.
 - 1. Name and address of supplier and type of equipment.
 - 2. If under contract or rental.

Name	Address	Phone #	Equipment	Rental/ Contract
			Steel Tank Welder	
			Electrical repair	
			Digging equipment	
			Generator	
			Chemicals	

- C. List of distributors or suppliers of **replacement parts** for the system.
 - 1. Name and address of supplier and type of equipment.

Name	Address	Phone #	Equipment
			PVC pipe, valves, and fittings
			pumps, pressure tank and gauges
			Chlorinator

D. List of **emergency contact numbers**:

	Name	Phone #
1.	Bryan Potter , SWRCB-DDW Tulare District Office	Office: (559) 447-3300 / Cell: (559) 280-6363
2.	Law Enforcement -	
3.	Electrician	
4.	Laboratory	
5.	Pump repair service	
6.	Chemical disinfectant supplier	
7.	Equipment supplier	
8.	Water System Owner	
9.	Certified Operators (include certification level)	

Attachments (Note: electronic copies of all forms available upon request):

1. Monthly water production and chlorine usage report
2. Coliform monitoring report forms for distribution and raw well sources
3. Quarterly chlorine residual report form for Disinfection Byproducts Rule
4. Bacteriological Sampling Siting Plan guidance
5. Water Quality Monitoring Schedule
6. Emergency Notification Plan form (please include job title and any operator certifications for names listed)
7. Lead and copper tap monitoring guidance

Appendix G:
Instructions for Accessing Individual Water System's Water Monitoring
Schedule and Water Quality Data

How To Access Individual System's Drinking Water Monitoring Schedule & Water Quality Data

1. Place the following link in the internet address bar:
<https://sdwis.waterboards.ca.gov/PDWW/>
2. Enter your Water System No. and select "Search For Water Systems"

SDWIS Version 3.21

California Public Water Supply Systems Search Parameters

Water System No.

Water System Name

Principal County Served

Water System Type

Water System Status

Primary Source Water Type

[Click Here for the County Map of CALIFORNIA](#)

3. Click on your Water System No. (Link in blue text).

Drinking Water Division

Water Systems

Hide/show columns: [Water System No.](#) | [Water System Name](#) | [Type](#) | [Status](#) | [Principal County Served](#) | [Primary Source Water Type](#)

Display records Search:

Water System No.	Water System Name	Type	Status	Principal County Served	Primary Source Water Type
CA5403043	YETTEM WATER SYSTEM	C	A	TULARE	GW

Showing 1 to 1 of 1 entries (filtered from 8,332 total entries) Previous Next

- On the left side of the screen, select **Monitoring Schedules** for source monitoring schedule (last sample and next due dates) or **Monitoring Results** for water quality results.

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

[Glossary](#)

[Contact Info](#)

CA Drinking Water Watch

Water System Details

Water System No. : CA5403043	Federal Type : C
Water System Name : YETTEM WATER SYSTEM	State Type : C
Principal County Served : TULARE	Primary Source : GW
Status : A	Activity Date : 04-28-2014

Water System Contacts

Type	Address	Phone	Email - Web Address
Administrative Contact	5961 S. MOONEY BLVD. VISALIA, CA 93277	Business 559-624-7191	
Physical Location Contact	CA5403043-YETTEM WATER SYSTEM		

Division of Drinking Water District / County Health Dept. Info

Name	Phone	Email	Address
DISTRICT 24 - TULARE	559-447-3300	dwpsdist24@waterboards.ca.gov	265 W. BULLARD AVE., SUITE 101 FRESNO CA 93704

Annual Operating Periods & Population Served

Start Month	Start Day	End Month	End Day	Population Type	Population Served
1	1	12	31	R	350

Service Connections

Type	Count	Meter Type	Meter Size Measure
CB	64	UN	0

Sources of Water

Name	Type Code	Status
WELL 01 - PRE NO3 BLEND	WL	A
WELL 02 - PRE NO3 BLEND	WL	A

Service Areas

Code	Name
R	RESIDENTIAL AREA

Water Purchases

Seller Water System No.	Water System Name	Seller Facility Type	Seller State Asgn ID No.	Buyer Facility Type	Buyer State Asgn ID No.
-------------------------	-------------------	----------------------	--------------------------	---------------------	-------------------------

5. Select Sampling Point corresponding to the source (Link in blue text and is a number).

5A. Monitoring Schedules

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

[Glossary](#)

[Contact Info](#)

CA Drinking Water Watch

Monitoring Schedules

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

The Division of Drinking Water's (DDW's) drinking water quality monitoring schedules identify upcoming required testing of drinking water for water systems in California. These documents should not be used for determining whether water systems are in compliance with monitoring requirements. The purpose for providing these monitoring schedules is to allow water systems to verify that their sampling and analyses have been incorporated into the DDW database and to identify upcoming required monitoring/sampling events.

Notes for Water Systems:

- The monitoring notification documents should be considered "draft," in that they will change with subsequent updates, and as monitoring data are submitted, or as monitoring schedules are revised.
- The monitoring notification documents are derived from the DDW Water Quality database and from schedules maintained by DDW districts.
- If your upcoming monitoring or your data identified as "DUE" are not in agreement with this document, or if you have been advised of any increased monitoring that is not reflected in the report for a particular source, please contact your [District Engineer or LPA representative](#). For a map of the districts, please [click here](#).
- If your notification report for a source is blank, this does not necessarily indicate compliance with all monitoring requirements.
- These notification reports may not reflect compliance with initial monitoring for newly regulated constituents, or constituents that require special monitoring frequencies. For example, the DDW database is unable to accurately forecast the vulnerable non-volatile synthetic organic chemical (SOC) frequency for large water systems serving over 3,300 people of 2 quarters every 3 years.
- Some Nitrate (as N) results under storet code 00618, will have a result of 'N/A' which stands for 'Not Applicable.' This stems from the change in regulation requiring that all nitrate sampling be reported as Nitrate (as N) starting January 1, 2016. Prior nitrate sampling was reported as Nitrate (as NO3). With this change in nitrate reporting requirements, the monitoring schedules have captured the last date of Nitrate (as NO3) sampling and applied it to Nitrate (as N) in determining the next due date [unless there have been Nitrate (as N) samples collected]. The Nitrate (as NO3) result, however, does not carry over to Nitrate (as N) which is why there may be a notation in the 'Constituent Identification' column to reference storet code 71850 for the last nitrate result. In these instances, the 'Constituent Identification' column will say, 'NITRATE (as N) - [see 71850].' Any questions should be referred to your District Engineer.

Monitoring Schedules for All Sampling Points

Monitoring schedule for all sampling points

Click to view report. Once the report is shown, click on the Export icon on the report header to download.

Monitoring Schedule for Individual Sampling Points

Click on a sampling point number to view the monitoring schedule for the sampling point.
[Click here to bring back the list of sampling points.](#)

Sampling Point	Location	Type
900	ST2S1-14395 AVE 384	
LCR		DS
003	WELL 01 & 02 - NO3 BLEND TANK	
001	WELL 01 - PRE NO3 BLEND	RW
002	WELL 02 - PRE NO3 BLEND	RW

Monitoring schedule for specific sampling points

NOTE: Any *past due* monitoring will have "DUE NOW" in the far-right column. Please schedule this monitoring as soon as possible.

5B. Monitoring Results

Links
[Water System Details](#)
[Water System Facilities](#)
[Monitoring Schedules](#)
[Monitoring Results](#)
[Monitoring Results By Analyte](#)
[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)
[Site Visits](#)
[Consumer Confidence Reports](#)

- [2017](#)
- [2016](#)
- [2015](#)
- [2014](#)

Return Links
[Water System Search](#)
[County Map](#)
Glossary
Contact Info

CA Drinking Water Watch

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

Monitoring Results for Individual Sampling Points

Click on a PS Code to view/download the monitoring results for the sampling point.

Water System Sampling Points					
PS Code	Facility ID	Facility Name	Description	Type Code	Source Class
5403043-001	001	WELL 01 - PRE NO3 BLEND	WELL 01 - PRE NO3 BLEND	RW	DCSGA
5403043-002	002	WELL 02 - PRE NO3 BLEND	WELL 02 - PRE NO3 BLEND	RW	DCSGA
5403043-003	003	WELL 01 & 02 - NO3 BLEND TANK	WELL 01 & 02 - NO3 BLEND TANK		OTHR
5403043-900	DST	DISTRIBUTION SYSTEM	DISTRIBUTION SYSTEM		DBPT
5403043-LCR	DST	DISTRIBUTION SYSTEM		DS	

6. Please contact the Tulare District Office at (559) 447-3300 or DWPDIST24@waterboards.ca.gov if you have any questions.

Appendix H:
Bacteriological Sample Siting Plan Template

Division of Drinking Water Tulare District

GUIDELINES FOR COMPLETING THE BACTERIOLOGICAL SAMPLE SITING PLAN FOR SMALL WATER SYSTEMS

The total coliform regulation requires the water supplier to submit a bacteriological sample siting plan to the Division of Drinking Water (Division), District Office for review and approval. The locations where samples are to be collected must be written down and formally approved by the District Office. These guidelines and Attachment 1, "Bacteriological Sample Siting Plan" Form, are to assist you in complying with these requirements.

To comply with the requirements for submitting a Bacteriological Sample Siting Plan, two (2) items must be submitted to the District Office at this time.

1. A system map, street map, or system schematic showing all sampling locations must be submitted. The map can be prepared by any system representative. It does not have to be prepared by an engineer. The following are also to be shown on the map:
 - Water Sources (i.e., well or spring)
 - Treatment Facilities (i.e., chlorination)
 - Storage Tanks
 - Pressure Reducing Stations
 - Booster Stations
 - Pressure Zones
 - Dead Ends
 - Service Area Boundaries
 - Routine Sample Sites
 - Repeat Sample Sites
 - Special Sample Sites
2. Complete Attachment 1, the "Bacteriological Sample Siting Plan" form, and **return the system map and form to the District Office for review and approval.**

Once the Bacteriological Sample Siting Plan has been approved by the Division, copies should be provided to the person responsible for sample collection, the laboratory and the person responsible for reporting coliform-positive samples to the Division.

Selection of Sampling Sites

The routine sampling sites chosen must be representative of the water distribution system including all pressure zones, areas supplied by each water source and distribution reservoir.

Looped Systems: If your entire water distribution system is looped, then one routine sample point may be representative of your system, assuming valves are open.

Pressure Zones: You should only be concerned about sampling in different pressure zones if your water system serves different areas of varying elevations, for example in mountainous areas.

How many routine sampling sites are required?

The minimum number of samples for the water system shall be based on the known population served or the total number of service connections, whichever results in the greater number of samples, as shown in Table 64423-A. For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

Table 64423-A		
Minimum Number of Routine Total Coliform Samples Monthly Population Served¹	Service Connections	Minimum Number of Samples Per Month
25 to 1000	15 to 400	1
1,001 to 2,500	401 to 890	2
2,501 to 3,300	891 to 1,180	3
3,301 to 4,100	1,181 to 1,460	4
4,101 to 4,900	1,461 to 1,750	5
4,901 to 5,800	1,751 to 2,100	6
5,801 to 6,700	2,101 to 2,400	7
6,701 to 7,600	2,401 to 2,700	8
7,601 to 8,500	2,701 to 3,000	9
8,501 to 12,900	3,001 to 4,600	10
12,901 to 17,200	4,601 to 6,100	15
17,201 to 21,500	6,101 to 7,700	20
21,501 to 25,000	7,701 to 8,900	25
25,001 to 33,000	8,901 to 11,800	30
33,001 to 41,000	11,801 to 14,600	40
41,001 to 50,000	14,601 to 17,900	50
50,001 to 59,000	17,901 to 21,100	60
59,001 to 70,000	21,101 to 25,000	70

¹ For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

How many repeat sampling sites are required?

A repeat sample set consists of three samples to be collected from the following locations:

- One repeat sample from the same routine location.
- One repeat sample from an *upstream location* (within 5 connections of the routine site).
- One repeat sample from a *downstream location* (within 5 connections of the routine site).

Each routine sample site must have identified repeat sample sites.

Ground Water Rule Compliance: All active groundwater sources in operation at the time of the coliform-positive sample must also be sampled along with the repeat sample set.

What if the water system does not have enough locations to select the required number of routine and repeat sample sites?

If the water system does not have enough sample locations to identify the required routine and repeat sample sites, contact the District Office for further guidance.

Pointers for Sample Site Selection

- When selecting a routine sample site you should be able to select a site upstream and a site downstream for repeat sampling.
- Select a site where the water is used continuously all year round.
- Pick a site that is easily accessible, i.e., a fenced yard with a locked gate and vicious dog is not a good selection.
- When choosing a sampling tap you should consider these factors:
The sampling tap should be located in as clean an environment as possible. It should be protected from contamination by humans, animals, airborne materials or other sources of contamination.

If you choose an outside private tap, it should be one that is in frequent use, clean, and at least 1½ feet (18 inches) above the ground. The sample tap should discharge downward.

If you choose an inside tap, be sure that you are not sampling from drinking fountains; taps that have aerators or strainers, or swivel faucets; or taps off of individual homeowner treatment units.

Do not choose a fire hydrant as sampling tap.

Avoid taps that are surrounded by excessive foliage or taps that are dirty or corroded.

Avoid taps that leak, have fittings with packing, or have permanent hoses or attachments fastened to the tap (Never collect a sample from a hose).

Avoid the use of dead ends for routine sample collection, and use them for repeat samples only if no other sample sites are available and if there is continuous water use from a service off the dead-end.

Instructions for Completing the Bacteriological Sample Siting Plan Form

This form has been designed to include all the requirements for the Bacteriological Sample Siting Plan.

- **Public Water System Classification**

The public water system (PWS) classification for your water system is either community, nontransient noncommunity or transient noncommunity. If you are uncertain of your classification, contact the District Office.

- **Month/Daily Users**

The monthly population determines the frequency of bacteriological sample collection for community water systems and nontransient noncommunity systems. For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

- **Active Service Connections (Community water systems only)**

This is the number of active hook-ups served by the system. If your system has a hook-up to a vacant lot, do not count this as an active connection. If a vacant lot has a right to a future connection, do not count this as an active connection. If a residence is connected to the system, but the residence is vacant, count this as an active hook-up.

- **Sampling Frequency**

This is the minimum number of routine bacteriological samples required at the frequency specified. If any routine sample is positive for coliform bacteria, additional repeat samples will be required. Repeat samples are in addition to the required routine samples. If you are uncertain of the routine sampling frequency for your water system, contact the District Office.

- **Trained Sampler**

The person collecting samples must be trained.

Sampling Service: Water systems utilizing a certified laboratory or other sampling service for water sample collection will be considered to have trained samplers. Enter the name of the laboratory or sampling service collecting your samples. A copy of the approved Bacteriological Sample Siting Plan should be provided to the laboratory or sampling service, if one is used.

Other Trained Samplers: Any person receiving a certificate from AWWA for attendance of the Water Sampling Training should submit a copy of their certificate along with the completed form. Any other samplers should submit a statement of their experience and training to this office for approval.

- **Analyzing Lab**

Enter the state-certified laboratory, which will be analyzing your water samples.

- **Person Responsible to Report Coliform-Positive Samples to the Division**

This should be the person that the laboratory is required to contact when a sample is total or fecal coliform positive. This person must notify the Division within 24 hours of a violation of the total coliform standard (more than one positive sample in a month) or when any sample is fecal or *E. coli* positive. This person should have the authority to take corrective action as required by regulation and the Division. This should be the same person listed on your Emergency Notification Plan.

- **Day/Evening Phone Number**

The Division requires that the water system provide the phone numbers of the person listed above so that they can be contacted by the laboratory or the Division at any time during the day or evening in the event of a bacteriological emergency.

- **Signature and Date**

The person preparing the Sample Siting Plan should sign and date the plan. If the Division has questions regarding the sampling plan, this is the person to be contacted.

- **Sample ID**

This should be entered on the laboratory slip when the sample is turned into the laboratory. This is the unique identifier for the water sample location, or the location address may also be used. For systems, which have no more than five (5) routine locations, these routine sites will be 1-ROU, 2-ROU, 3-ROU, 4-ROU, and 5-ROU.

Each routine sample site must have two repeat sampling sites. Repeat sample sites are to be located within five (5) service connections upstream and downstream of the routine sample site.

All sample locations should be marked in some way with the Sample ID or location address, i.e., the code painted on the sampling location or tagged with a water proof tag so the person collecting the water sample is sure to collect the water from the correct sample locations.

- **Sample Type**

This describes what type of sample (routine or repeat) is to be collected at this location.

- **Sample Point**

This is the type of the sample location. Use the following abbreviations, when appropriate: HB - Hose Bib (exterior), SF - Sink Faucet, PC - Goose Neck Type Copper Tube with Pet Cock

- **Location of Sample Point**

This is the description of the area in the distribution that the sample site is located. Routine sample sites shall not be located at dead ends. Use the following abbreviations, when appropriate: DE - Dead End (Not Recommended), PZ - Pressure Zone, RD - Representative Distribution

- **Location Address**

This is the actual physical location where the water sample is to be collected. If possible use a street address, i.e., 103 Good Street. If the location does not have a street address, use the nearest crossroads or use the last name of the resident, i.e., "Brown Residence." If the location is a business, please list the business name and address.

When describing the location, keep in mind that the person collecting water samples must be able to locate the sample site from your description.

- **Months Sample Collected at This Location**

This is the schedule for routine samples to be collected. For example, suppose two (2) sites are representative of your systems. Site No. 1 will be sampled in January, March, May, July, September, and November. Site No. 2 will be sampled in February, April, June, August, October, and December. All routine sites identified should be rotated to allow sampling at least every 3 months.

BACTERIOLOGICAL SAMPLE SITING PLAN (BSSP) FOR SMALL WATER SYSTEMS

System No.:		System Name:			PWS Classification:	
No. of Monthly Users:		No. of Daily Users:		No. Active Service Connections:		Cl2 Treatment:
Sampling Frequency: __ per month		Seasonal System:		Period of Operation:		
Name of Trained Sampler:			Analyzing Lab:		Analyzing Lab:	
Person Responsible to Report Positive Samples to the Division:					Day/Evening Phone No:	
Signature of Water System Representative:					Date:	

Sample ID	Sample Type	Sample Point	Location of Sample Point	Address of Sample Point	Months Sample Collection at this Location
1-ROU	Routine				
1-REP1	<i>Repeat</i>				<i>Repeat Sample Only</i>
1-REP2	<i>Repeat</i>				<i>Repeat Sample Only</i>

In the event of a routine positive sample, a sample(s) will be collected from the well(s) in use for Ground Water Rule compliance.

If continuous chlorination is provided, raw water samples are taken **monthly**.

The SWRCB-Division of Drinking Water or Local Primacy Agency has reviewed and approved this BSSP. Any plans on file dated prior to approval date below are void. The water system must sample their distribution system and raw water special purpose source samples for bacteriological quality in accordance with the approved BSSP beginning _____. Per the California Code of Regulations-Title 22 §64422, a water system is required to submit an updated plan to the State Board at least once every ten years and at any time the plan no longer ensures representative monitoring of the system.

District Office Representative Name: _____ Title: _____ District Name: Tulare District

Signature: _____ Date: _____

Appendix I:
Emergency Notification Plan Template

State Water Resources Control Board

System No. _____

DIVISION OF DRINKING WATER – TULARE DISTRICT WATER QUALITY EMERGENCY NOTIFICATION PLAN

Water System Name: _____

Physical Location Address: _____

The following persons have been designated to implement the Plan upon notification by the Division of Drinking Water that an imminent danger to the health of the water users exists:

Contact Name & Title	Email Address	Home/Office	Cell
1. _____			
2. _____			
3. _____			

The implementation of the plan will be carried out with the following Division of Drinking Water and County Health personnel:

Contact Name & Title	Email Address	Office	Cell
1. Kristin Willet, Tulare District Engineer Division of Drinking Water	kristin.willet@waterboards.ca.gov	(559) 447-3300	(559) 280-6363
2. Tricia Wathen, Supervising Sanitary Engineer Division of Drinking Water	tricia.wathen@waterboards.ca.gov	(559) 447-3300	(559) 696-8506
3. Nilsa Gonzalez, Director Tulare County Environmental Health Division Manager	ngonzale@tularehhsa.org	(559) 624-7400	(559) 285-2440
4. If the above personnel cannot be reached, contact:			

Office of Emergency Services (24 Hrs.) (800) 852-7550 or (916) 845-8911
Ask for "Division of Drinking of Drinking Water, Duty Officer"

NOTIFICATION PLAN

Community and Nontransient Noncommunity

(Must identify three methods)

- ☐ Door to Door Delivery ☐ Posted Notification
☐ Social Media ☐ Reverse 911/Telephone
☐ News Media (TV, Radio, Newspaper) ☐ Email
☐ Other: personal phone call _____

Transient Noncommunity

☐ Water system must post notification. Hand delivered notification must be provided to any residential/overnight customers.

***SYSTEMS SERVING MORE THAN 200 SERVICE CONNECTIONS MUST PROVIDE A CUSTOM PLAN.**

APPROXIMATE TIME TO ISSUE NOTICE: _____ HRS

Report prepared by:

Signature and Title

Date

Appendix G: Sultana 2024 Sanitary Survey

State Water Resources Control Board

Division of Drinking Water

August 12, 2024

Ms. Celeste Perez, Board Secretary
Sultana Community Services District – CA5400824
P.O. Box 158
Sultana, CA 93666

2024 Sanitary Survey

Dear Ms. Perez:

On October 30, 2023, Tulare District staff member Michelle Palencia, with the Division of Drinking Water (Division) conducted an inspection of the Sultana Community Services District's water system (Water System).

The findings of this inspection are detailed in the enclosed sanitary survey report. Upon completion of the inspection, the items listed below are required to be addressed by the Water System.

1. **DUE IMMEDIATELY**, a plan for the continuous chlorination of the water delivered from Well 03 shall be submitted for the Division's review.
2. By **September 30, 2024**, the Water System must sample Well 02 and Well 03 quarterly for Nitrate.
3. **DUE IMMEDIATELY**, the Water System must sample Well 03 for 1,2,3-TCP and Alachlor.
4. By **September 1, 2024**, a map and updated BSSP must be submitted to the Division for review and approval.

If you have any questions regarding the information contained in the report, please contact the Tulare District at (559) 447-3132 or email dwpsdist24@waterboards.ca.gov.

E. JOAQUIN ESQUIVEL, CHAIR | ERIC OPPENHEIMER, EXECUTIVE DIRECTOR

Sincerely,

A handwritten signature in black ink, appearing to read 'Jeff Densmore', with a stylized, cursive flourish at the end.

Jeff Densmore, P.E.
South Central Section Chief
Central Branch Division of Drinking Water
State Water Resources Control Board

JD/MP
Enclosures

Cc: Jose A Padilla, Contract Operator, D1/T2
Jose_padilla2010@yahoo.com

Cruz Perez, Contract Operator, D1
Cruzperez0323@gmail.com

Small Water System Evaluation and Technical Report

Division of Drinking Water: Tulare District

Sultana Community Services District System No. CA5400824

Contact:	Celeste Perez, Board Secretary
Report Date:	August 12, 2024
System Type:	Community Water System
Prepared by:	Michelle Palencia

I. INTRODUCTION

Date of Sanitary Survey Inspection: October 30, 2023

Water System Name: Sultana Community Services District water system (Water System)

Inspected by: Michelle Palencia, Division of Drinking Water (DDW) Staff

Regulatory Entity: State Water Resources Control Board, Division of Drinking Water (Division)

Other Attendees: Jose A. Padilla, Contract Operator

Previous Inspection Date: January 17, 2020 by Andrew Forbes

PERMIT STATUS

Current Permit: Issued by Tulare District- DDW on August 29, 2014.

Purpose of this Report: The Water System is currently in compliance with all permit provisions. The purpose of this engineering report is to document the inspection of the water system, describe the facilities and operational practices as they exist today, and to describe any deficiencies needing corrective action.

SERVICE AREA

Mailing Address: P.O. Box 158, Sultana, CA 93666

Physical Location: Located across from 41645 Road 105, Sultana, CA 93618

Average Daily Population: 779

Service Connections: Total 249; 239 residential, 10 commercial. Unmetered.

Description of water system: The legal owner of the Sultana Community Services District is Sultana Community Services District and the headquarters is located near the intersection of El Monte Way and Road 105, Sultana, CA 93666. The Water System is classified as a community water system and serves a population of 779 permanent residents through 249 service connections. The service connection types are

residential and businesses. The domestic water supply is obtained from one active groundwater source, Well 03 – MAIN RAW, and one standby source, Well 02 – SOUTH STBY. Continuous chlorination is the only treatment provided to the source water produced by Well 03. The water system has one pressure zone and uses 2,500 and 5,300-gallon hydropneumatic pressure tanks to main system pressure. There is no storage provided. The service connections are unmetered.

Treatment: Continuous Chlorination

A simple configuration of the water system schematic including all treatment is shown below.




Figure 1. Flow Schematic for the Water System

II. INVESTIGATION AND FINDINGS

ENFORCEMENT

The Water System has not been issued any enforcement actions from the Division since the last inspection in 2019.

SOURCE OF SUPPLY

Source Water:	Groundwater
Source of Supply:	Well 03 and Well 02
Source Capacity:	Well 03: 540 gallons per minute (gpm) and Well 02: 525 gpm

Source Water Assessment
on File at Tulare District
Office:

Yes; Well 03 has a completed PCA checklist on file with the Division. Documents for the Source Water Assessment Program (DSWAP) for Well 03 are on file with the Division. Based on the DSWAP documents, Well 03 is most vulnerable to automobile-gas stations, underground storage tanks (confirmed leaking tanks), fertilizer/pesticide/herbicide application, chemical/petroleum processing/storage, historic gas stations, and known contaminant plumes.

This information is required to be reported each year in the Consumer Confidence Report (CCR) to each of the Water System's customers.

Well 03 – MAIN RAW, CA5400824_003_003: Status – Active, Treated

DWR Well Completion Report:	A DWR Well Completion Report for Well 03 is on file at the Tulare District office.
Location of Well/Source:	
Date of Well Completion:	September 1996
Well Depth:	430 feet
Sanitary Seal Depth:	250 feet; cement
Perforation Depths:	260 to 420 feet
Well Casing:	26-inch steel casing to 430 feet
Flow Meter:	Yes, digital
Pump Type:	Deep-well turbine (DWT); oil-lubed
Pump Make and Model:	Unknown
Pump Size:	60-horsepower (hp)
Well Capacity:	540 gpm
Well Equipment:	Raw water sample tap, check valve, air release valve
Casing Vents:	No
Air Vacuum Release Valves:	No
Check Valves:	Yes; One (1)
Sampling Tap:	Yes; Threaded, down-turned
Pump Pedestal:	18 inches in height
Source Discharge:	Directly to 2,500-gallon hydropneumatic pressure tank
Source Operation:	Operation based on system pressure
Discharge to waste:	Yes
Back-up Power Supply:	No
Type of access control:	Fencing
Site Security:	Yes; Locked gate

Distance to closest sanitary condition:	Well 03 is most vulnerable to historic leaking underground petroleum tanks, known contamination plumes, agricultural activity and drainage and sewer lines. The contamination plumes are for nitrate and DBCP.
Status of Deficiencies from last inspection:	Not applicable

Well 02 – SOUTH STBY, CA5400824_002_002: Status - Standby

DWR Well Completion Report:	A DWR Well Completion Report for Well 02 is on file at the Tulare District office.
Location of Well/Source:	
Date of Well Completion:	March 1978
Well Depth:	358 feet
Sanitary Seal Depth:	60 feet; cement
Perforation Depths:	162 to 322 feet
Well Casing:	14-inch steel casing to 332 feet
Flow Meter:	Yes, digital
Pump Type:	Submersible
Pump Make and Model:	Unknown
Pump Size:	60-horsepower (hp)
Well Capacity:	525 gpm
Well Equipment:	Raw water sample tap, check valve
Casing Vents:	Yes
Air Vacuum Release Valves:	No
Check Valves:	Yes; One (1)
Sampling Tap:	Yes; Threaded, down-turned
Pump Pedestal:	4 inches in height
Other Equipment:	
Source Discharge:	Directly to 5,500-gallon hydropneumatic pressure tank
Source Operation:	Manual operation
Discharge to waste:	Yes
Back-up Power Supply:	Yes
Type of access control:	Fencing
Site Security:	Yes; Locked gate
Distance to closest sanitary condition:	Well 02 is most vulnerable to historic leaking underground petroleum tanks, known contamination plumes, agricultural activity and drainage and sewer lines.
Status of Deficiencies from last inspection:	Not applicable

WATER PRODUCTION AND ADEQUACY OF SUPPLY

Flow Meter on all Sources: Yes.
Production Records: Yes.
Total Source Capacity: Well 02: 525 gpm
Well 03: 540

Year	Annual Production (MG)	Max Month (MG)	Max Month
2014	45.6	5.3	July
2015	45	5.53	July
2016	39.9	5.24	August
2017	43.5	5.33	June
2018	38.9	4.95	August
2019	46.63	6.22	July
2020	53.27	6.57	July
2021	57.31	7.5	August
2022	54.9	6.8	July

Year	Average Day Demand (gpm)	Max Day Demand (gpm)	Peak Hour Demand (gpm)
2014	86.8	178	267
2015	85.6	185	277
2016	75.9	176	264
2017	82.7	185	278
2018	74.0	166	249
2019	88.7	209	314
2020	101.3	221	331
2021	109.0	252	378
2022	104.5	229	343

The 2023 Production Data was not reported by the Water System.

Sufficient Capacity: Yes

The Waterworks Standard outlines that the highest water usage during the most recent ten years and a peaking factor of 1.5 be used to estimate the average day (ADD), maximum day (MDD) and peak hour demand (PHD) for the Water System. The ADD, MDD, and PHD for the Water System are 109.0 gpm, 252 gpm, and 378 gpm,

respectively. The Water System is able to meet the peak hour demand with the active source offline and using only the standby source. The Water System does not have any storage. Although the Water System does have the standby source that can meet the MDD and is not required to have storage the Division still recommends that storage be implemented in the future.

TREATMENT FACILITIES

Disinfection Treatment – CA5400824_004_004

Type:	Continuous chlorination using liquid sodium hypochlorite
Source Treated:	Well 03
Purpose and Description:	The Water System injects a 12.5% solution of sodium hypochlorite for disinfection directly into the discharge line of Well 03 upstream of the pressure tank.
Treatment Site Location:	Discharge line of Well 03, upstream of pressure tank
Chemical Storage:	120-gallon polyethylene tank
Equipment:	Iwaki Model EHE36E1-VC chemical feed pump (max output 8.5 gallons per hour (gph) @ 105 pounds per square inch (psi))
Housing Facilities:	Yes.
NSF Approved:	Yes. NSF/ANSI 60 certified.
Operations Plan on File:	No. The Water System was previously directed to submit a Chlorination Operations Plan to the Division and is still outstanding. DUE IMMEDIATELY, a plan for the continuous chlorination of the water delivered from Well 03 shall be submitted for the Division's review. Guidance for completing a Chlorination Operations Plan is in Appendix G.

STORAGE AND DISTRIBUTION

Distribution System:	¾-inch high density polyethylene to 8-inch ductile iron mains
Storage:	None
Pressure Tanks:	2,500 and 5,500-gallon steel hydropneumatic pressure tanks
Typical System Pressure:	39 to 62 pounds per square inch (psi)
Isolation Valves:	YES

NOTE: The pressure tanks are not considered the equivalent of a storage tank.

III. WATER QUALITY MONITORING

SOURCE MONITORING

A summary report of the last source sample results and next due dates are included in Appendix B. Additionally, the current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>.

All chemical water quality monitoring from the sources must be submitted to the Division via the California Laboratory Intake Portal (CLIP). For CLIP to work properly, the Water System must identify the samples with the correct primary station code (PS Code). The correct assigned PS Code is listed in the table below.

Primary Station Code		
Source Name	PS Code	Status
Well 02	CA5400824_002_002	Standby
Well 03	CA5400824_003_003	Active Raw

General Mineral (GM), General Physical (GP) Constituent Monitoring

Monitoring Requirements: Every 3 years
Date of Last Analysis: Well 02: February 18, 2021
Well 03: April 29, 2019
Last Sample Results: All results were below the respective MCLs.
Past Due Monitoring: None
GM and GP Results: Appendix B

Inorganic Chemical Monitoring

Monitoring Requirements: Every 3 years
Date of Last Analysis: Well 02: February 18, 2021
Well 03: March 29, 2019
Last Sample Results: All results were below the respective MCLs.
Past Due Monitoring: None or List Constituents
Nitrate (as N) Monitoring: Well 02; Due annually. Sampled on February 12, 2024, result was 4.5 mg/L.
Well 03; Due annually. Sampled on March 7, 2024, result was 5.7 mg/L.




Figure 2. Well 02 Nitrate Results from 2011-2024




Figure 3. Well 03 Nitrate Results from 2011-2024

The Water System is required to monitor groundwater for nitrate (as N) annually if monitoring data indicates concentrations of less than one half the MCL of 10.0 mg/L, and

quarterly if the concentrations are greater than or equal to one-half the MCL. After four consecutive quarterly samples are less than the MCL, a system may request reduced monitoring to annual. Wells 02 and 03 have been consistently over half the MCL and even exceeding the MCL at times as shown by Figures 2 and 3. **By September 30, 2024, the Water System must sample Well 03 quarterly for Nitrate. Since Well 02 is a standby source it will remain on annual monitoring.**

Volatile Organic Chemicals (VOCs) Monitoring period 2023-2025

Monitoring Requirements: Every 6 years. Initial monitoring requirements have been completed.

Date of Last Analysis: Well 02: February 18, 2021
Well 03: March 29, 2019

Last Sample Results: All results were non-detect.

Past Due Monitoring: None

VOC waiver: Submitted on February 15, 2023. Approved.

The waiver reduces the VOC monitoring frequency from every 3 years to every 6 years. The approved waiver is for the monitoring period of January 1, 2023, through December 31, 2025. With this waiver, the Water System is required to sample all active wells for VOC's once every six years. For the Water System to renew the waiver, the waiver request must be submitted to the Division prior to December 31, 2025. It must be renewed every 3 years.

Synthetic Organic Chemicals (SOCs) Monitoring

Monitoring Requirements: Every 3 years. Initial monitoring requirements have been completed.

Date of Last Analysis: Well 02: February 18, 2021
Well 03: March 21, 2022

Last Sample Results: Well 03: All results below the respective MCLs.
Well 02: DBCP detected at levels above MCL

Past Due Monitoring: Well 03: 1,2,3-Trichloropropane (1,2,3-TCP) and Alachlor monitoring are overdue.

DUE IMMEDIATELY, the Water System must sample Well 03 for 1,2,3-TCP and Alachlor.

By September 30, 2024, the Water System needs to sample Well 03 for Dibromochloropropane (DBCP) on a quarterly basis.

Radiological Monitoring

Initial Monitoring Requirements:	Complete
Monitoring Frequency:	Available online
Date of Last Analysis:	02/2023
Last Sample Results:	Non-detect (Wells 01 and 02)
Past Due Monitoring:	None
Next Sample Due Date:	02/2032

Initial Monitoring:

Initial radiological monitoring is based on the collection of four consecutive quarterly samples for gross alpha activity (GA) and total radium. If the results from the first two quarters of initial monitoring are below the detection limit for the purposes of reporting (DLR), the final two quarters of initial monitoring may be waived. **The Water System has completed the initial monitoring requirements for GA and total radium. The next GA sample is due in 2032.**

Source Bacteriological Monitoring

Routine Frequency:	Monthly
Analytes:	Total coliform and <i>E. coli</i> bacteria
Sample Site Location:	Raw water sample tap prior to chlorine injection port.
Analytical Method:	Density analytical method with the results reported in units of MPN/100mL. Submit results to the Division by the 10 th day of the following month.
Source Bacteriological Results:	Appendix C

Groundwater Rule

In the event that a routine distribution sample is positive for total coliform bacteria, the Water System must collect a raw water bacteriological sample from each source in operation at the time of the positive result. The bacteriological sample shall be analyzed for total coliform and *E.coli* bacteria using a density analytical method with the analytical results reported in MPN/100 mL (Most Probable Number per 100 milliliters).

DISTRIBUTION SYSTEM MONITORING

Bacteriological

Bacteriological Sample Siting Plan (BSSP) on file:	Yes, however it is outdated. By September 1, 2024, a map and updated BSSP must be submitted to the Division for review and approval. Guidelines for completing a BSSP are included in Appendix D.
Date of BSSP:	March 19, 2020

Routine Frequency: One routine sample per month. Bacteriological sampling must be conducted in accordance with the State Board-approved BSSP.

Groundwater Rule: Source repeat upon any routine distribution positive from all active sources.

Distribution Bacteriological Sampling Results: Appendix C

Lead and Copper Tap Sampling

The Water System is required to comply with the Lead and Copper Rule (LCR) and conduct lead and copper tap monitoring during each monitoring period. Compliance with the lead and copper action levels is based on the 90th percentile lead and copper results. The 90th percentile for lead and copper should be less than the lead and copper action levels of 0.015 mg/L and 1.3 mg/L, respectively. A summary of all lead and copper tap monitoring results is outlined in the tables below.

Results:

Monitoring Period	Sample Date(s)	No. of Samples	Lead 90 th Percentile Result (mg/L)	Copper 90 th Percentile Result (mg/L)	No. of Samples Exceeding Action Level
3Y2020-2022	8/4/2022	6	0	0.119	--
3Y2017-2019	7/21/2019	6	0	0.31	--
3Y2014-2016	6/20/2016	5	ND	0.211	--
3Y2011-2013	7/8/2013	5	ND	0.46	--
3Y2008-2010	7/14/2010	5	0.0034	0.114	--
3Y2005-2007	7/26/2007	5	ND	0.256	--
3Y2002-2004	8/3/2004	5	0.0027	0.2085	--
YR2001	8/1/2001	5	0.005	0.361	--
YR1999	8/1/1999	5	0.005	0.26	--
6M2ND-1998	11/1/1998	10	0.005	0.05	--
6M2ND-1997	7/1/1997	10	0.005	0.235	--

Future Monitoring Period:

Frequency	No. of Samples Required	Monitoring Period	Next Monitoring Period Begin	Next Monitoring Period End	Next Sample Due Date
3 years	5	3YR2023-2025	6/1/2023	9/30/2025	9/30/2025

It should be noted that all future lead and copper monitoring results must be submitted to the Division electronically via the California Laboratory Intake Portal (CLIP). The results may only be submitted through the CLIP by an Environmental Laboratory Accreditation Program (ELAP) accredited laboratory. More information regarding the new drinking water quality data intake portal can be found at:

https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/clip.html

The Water System must complete and submit a Lead and Copper Tap Sample Results Reporting Form with all subsequent lead and copper monitoring results. A Lead and Copper Tap Sample Results Reporting Form is included in Appendix E.

Lead Service Line Inventory Requirement

On January 15, 2021, the US EPA issued revisions to the federal Lead and Copper Rule (LCR). US EPA's new Lead and Copper Rule Revisions (LCRR) aim to strengthen the LCR to better protect communities and children in elementary schools and childcare facilities from the impacts of lead exposure. All community and nontransient noncommunity water systems must complete and submit their inventory by **October 16, 2024**. Each water system must maintain the required inventory information described in the FAQ and inventory instructions are found on the Lead and Copper Rule for Drinking Water website:

https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/leadandcopperrule.html.

Asbestos

Asbestos monitoring from the distribution system is not required.

Disinfection Byproduct (DBP) Monitoring

Analytes:	Total trihalomethanes (TTHMs) and Haloacetic acids (HAA5s)
MCLs:	TTHM MCL is 80 ug/L; HAA5 MCL is 60 ug/L
DBP Monitoring Site:	ST2S1 – 10427 AVE 416 (POST OFC) (CA5400824_DST_900)
Current Frequency:	Annually
Date of Last Analysis:	August 14, 2023
Last Sample Results:	TTHM – non-detect ; HAA5 – non-detect
Next Due Date:	August 2024

The results of TTHMs and HAA5s for Stage 2 DBP monitoring are to be submitted electronically to the Division's electronic water quality database using the PS Code listed above by the site name.

IV. OPERATIONS AND MAINTENANCE

Operator Certification

Distribution System Classification:	D1
Distribution Operator Requirement:	D1
Certified Operator:	Jose Padilla, D1, Certification No. 27640

Complaint Records

The Water System must keep records of all complaints received and actions taken to correct the problems related to the complaints. This information should then be reported in the electronic annual report (EAR) to the Division each year. There were no complaints reported in the 2023 EAR.

Consumer Confidence Report (CCR)

Current CCR Year:	2023
Current CCR submitted to Division:	2023 CCR
CCR Certification Form Submittal to the Division:	Yes; April 23, 2024
CCR Evaluation:	The 2023 CCR was filled out appropriately and submitted in a timely manner.

The Water System is required to complete a CCR on an annual basis and provide a copy to all residents in their service area by July 1 of each year.

Cross Connection Control Program

Cross Connection Control Program:	No
Cross Connection Control Program Coordinator:	None
Cross Connection Control Survey:	No
Backflow Prevention Devices in System:	4

Cross Connection Control Appendix F
Program Guidance:

Backflow Prevention Device Testing

Regulation requires all backflow prevention devices to be tested annually and certified by a licensed Backflow Prevention Device Tester. Copies of the testing records must be kept on file with the Water System for a minimum of three years.

The 2017 Sanitary Survey had a directive that the Water System must conduct a cross connection control survey using a certified cross connection control specialist or submit a time and schedule for having one completed. This directive remains outstanding and is due immediately.

Emergency Notification Plan (ENP)

Approved ENP on File at Yes.
the Tulare District Office:
Date of approved ENP: March 13, 2019
Notification Method(s): The ENP identifies using door-to-door delivery, posted notification and telephone as their notification methods in the event of an emergency.

Electronic Annual Report (EAR)

Current EAR Year, 2023 EAR. Submitted on March 29, 2024
Submittal Date:
Deficiencies: No.

All public water systems are required to provide updated water system information to the Division annually. The technical information included in the report is required per Section 116530 of the California Health and Safety Code.

Small Water System Resiliency And Preparedness

Current EAR Year: 2023
Climate Related Impacts None
Identified by Water System:

The effects of extreme weather on community water system (CWS) facilities and operations is a concern and priority of the State Water Resources Control Board (SWRCB), which is documented by the SWRCB in its Comprehensive Climate Change Resolution adopted in March 2017. The Division is reviewing each water system's level of resiliency and preparedness for changing climate conditions and extreme weather events, increasing awareness and familiarization to the effects of climate change to facilities and operations, encouraging the use of EPA's Climate Resilience Evaluation

and Awareness Tool (CREAT), and documenting the Water System's efforts related to current threats that may also provide mitigation to climate change impacts.

The SWRCB strongly encourages utilities to evaluate infrastructure and operational vulnerabilities to extreme weather and other emergency conditions using tools such as CREAT and engaging in a conversation both within your water system organization and with customers on how to plan and prepare for being resilient to provide clean and safe water reliably and adequately under all current and future conditions.

V. APPRAISAL OF SANITARY HAZARDS & PUBLIC HEALTH SAFEGUARDS

The Water System relies on Well 03 to supply the demands of the system. The system has a backup emergency source, Well 02, on standby. The total source capacity of the water system appears to meet demand requirements. The system has no storage capacity and there are no interconnections with any nearby water systems.

Overall, the Water System's water supply facilities are in good sanitary condition and appear to be operating satisfactorily. The Water System supplies water that currently meets all primary and secondary drinking water standards. The water system is capable of providing adequate water quality and resiliency.

The Water System has items that need to be addressed that are identified below. The Water System needs to ensure that all directives in this report are complied with in a timely manner.

The Water System may access the public Drinking Water Watch website (<https://sdwis.waterboards.ca.gov/PDWW/>) where the Water System can access system information including the current water quality sampling status and schedules.

VI. CONCLUSIONS AND RECOMMENDATIONS

The following items need to be addressed by the Water System:

1. **DUE IMMEDIATELY**, a plan for the continuous chlorination of the water delivered from Well 03 shall be submitted for the Division's review.
2. By **September 30, 2024**, the Water System must sample Well 03 quarterly for Nitrate.
3. **DUE IMMEDIATELY**, the Water System must sample Well 03 for 1,2,3-TCP and Alachlor.
4. By **September 30, 2024**, the Water System needs to sample Well 03 for Dibromochloropropane (DBCP) on a quarterly basis.

5. By **September 1, 2024**, a map and updated BSSP must be submitted to the Division for review and approval.

Appendices

- Appendix A: Photo Index
- Appendix B: Last Sample & Next Due Date Summary Report
- Appendix C: Source Water & Distribution Bacteriological Monitoring Report
- Appendix D: Guidance for Bacteriological Sample Site Plan
- Appendix E: Lead and Copper Tap Sample Results Reporting Form
- Appendix F: Cross Connection Control Guidance for Community Water Systems
- Appendix G: Guidance for Chlorination Operations Plan

Appendix A: Photo Index



Well 02 – SOUTH STBY
(CA5400824 003 003):

- No deficiencies found at well site





Well 03 – MAIN RAW
(CA5400824 003 003):

- No deficiencies found at well site
- Chlorination operations plan needs to be submitted

Appendix B: Last Sample & Next Due Date Summary Report

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT

COUNTY: TULARE

Sample Point: WELL 03 - MAIN RAW

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORTING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MONTHS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_003_003		SULTANA COMMUNITY SERVICES DISTRICT						WELL 03 - MAIN RAW												
	GP	SECONDARY/GP																		
		1928	ALKALINITY, BICARBONATE	200.000		10.000		MG/L	-----	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 2320 B
		1919	CALCIUM	55.000		1.000		MG/L	-----	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.7
		1929	ALKALINITY, CARBONATE		<	10.000		MG/L	-----	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 2320 B
		1017	CHLORIDE	35.000		1.000		MG/L	500	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 300.0
		1905	COLOR		<	5.000		UNITS	15	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 2120 B
		1022	COPPER, FREE		<	50.000		UG/L	1000	50	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.7
		2905	FOAMING AGENTS (SURFACTANTS)		<	0.050		MG/L	0.5	-----	3/7/2022	3	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 5540 C-00
		1915	HARDNESS, TOTAL (AS CaCO3)	199.000		1.000		MG/L	-----	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.7
		1021	HYDROXIDE AS CALCIUM CARBONATE		<	10.000		MG/L	-----	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 2320 B
		1028	IRON		<	100.000		UG/L	300	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.7
		1031	MAGNESIUM	15.000		1.000		MG/L	-----	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.7

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 03 - MAIN RAW CLASS: CTGA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORTING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MONTHS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_003_003	GP	SECONDARY/GP																	
		1032	MANGANESE		<	20.000	UG/L	50	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.7
		1920	ODOR	2.000		1.000	TON	3	1	3/7/2022	4	36		2025/03		VI 2241498-001 ADD2	2810	FGL ENVIRONMENTAL (VISALIA, CA)	SM 2150 B
		1925	PH	6.900		0.000	pH	-----	-----	4/29/2019	3	36		2022/04	DUE NOW	64870031 90429151 5G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1050	SILVER		<	10.000	UG/L	100	10	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
		1052	SODIUM	38.000		1.000	MG/L	-----	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.7
		1064	CONDUCTIVITY @ 25 C UMHOS/CM	530.000		0.000	UMHO/CM	1600	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 2510 B
		1055	SULFATE	24.000		0.500	MG/L	500	0.5	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 300.0
		1930	TDS	330.000		40.000	MG/L	1000	-----	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 2540 C
		0100	TURBIDITY		<	0.100	NTU	5	0.1	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 2130 B-01
		1095	ZINC		<	50.000	UG/L	5000	50	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.7
	IO	INORGANIC																	
		1002	ALUMINUM		<	50.000	UG/L	1000	50	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
		1074	ANTIMONY, TOTAL		<	6.000	UG/L	6	6	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 03 - MAIN RAW CLASS: CTGA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_003_003	IO	INORGANIC																	
		1005	ARSENIC	2.000		2.000	UG/L	10	2	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
		1010	BARIUM		<	100.000	UG/L	1000	100	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
		1075	BERYLLIUM, TOTAL		<	1.000	UG/L	4	1	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
		1015	CADMIUM		<	1.000	UG/L	5	1	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
		1020	CHROMIUM		<	10.000	UG/L	50	10	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
		1025	FLUORIDE	0.100		0.100	MG/L	2	0.1	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 300.0
		1035	MERCURY		<	1.000	UG/L	2	1	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 245.1
		1036	NICKEL		<	10.000	UG/L	100	10	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
		1039	PERCHLORATE		<	2.000	UG/L	6	1	2/12/2024	6	36		2027/02		VI 2441075-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 331.0
		1045	SELENIUM		<	5.000	UG/L	50	5	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
		1085	THALLIUM, TOTAL		<	1.000	UG/L	2	1	3/7/2022	4	36		2025/03		VI 2241498-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.8
	NI	NITRATE/NITRITE																	
		1040	NITRATE	4.800		0.400	MG/L	10	0.4	3/7/2024	10	3	Interval	2024/06	DUE NOW	VI 2441776-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 4500-VO3-F-00

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 03 - MAIN RAW CLASS: CTGA STATUS: Active

PCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_003_003	S1	REGULATED VOC																	
		2983	1,2-DICHLOROPROPANE		<	0.500	UG/L	5	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2413	1,3-DICHLOROPROPENE		<	0.500	UG/L	0.5	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2969	P-DICHLOROBENZENE		<	0.500	UG/L	5	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2990	BENZENE		<	0.500	UG/L	1	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2982	CARBON TETRACHLORIDE		<	0.500	UG/L	0.5	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2380	CIS-1,2-DICHLOROETHYLENE		<	0.500	UG/L	6	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2964	DICHLOROMETHANE		<	0.500	UG/L	5	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2992	ETHYLBENZENE		<	0.500	UG/L	300	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2251	METHYL TERT-BUTYL ETHER		<	3.000	UG/L	13	3	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2989	CHLOROBENZENE		<	0.500	UG/L	70	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2996	STYRENE		<	0.500	UG/L	100	0.5	3/29/2019	3	72		2025/03		64870031903291000V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 03 - MAIN RAW CLASS: CTGA STATUS: Active

PCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_003_003	S1	REGULATED VOC																	
		2987	TETRACHLO ROETHYLEN E	<	0.500		UG/L	5	0.5	3/29/2019	3	72		2025/03		64870031 90329100 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2991	TOLUENE	<	0.500		UG/L	150	0.5	3/29/2019	3	72		2025/03		64870031 90329100 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2979	TRANS-1,2- DICHLOROE THYLENE	<	0.500		UG/L	10	0.5	3/29/2019	3	72		2025/03		64870031 90329100 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2984	TRICHLORO ETHYLENE	<	0.500		UG/L	5	0.5	3/29/2019	3	72		2025/03		64870031 90329100 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2218	TRICHLORO FLUOROMET HANE	<	5.000		UG/L	150	5	3/29/2019	3	72		2025/03		64870031 90329100 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2904	TRICHLORO TRIFLUORO ETHANE	<	10.000		UG/L	1200	10	3/29/2019	3	72		2025/03		64870031 90329100 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2976	VINYL CHLORIDE	<	0.500		UG/L	0.5	0.5	3/29/2019	3	72		2025/03		64870031 90329100 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2955	XYLENES, TOTAL	<	0.500		UG/L	1750	0.5	3/29/2019	3	72		2025/03		64870031 90329100 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	S2	REGULATED SOC																	
		2414	1,2,3- TRICHLORO PROPANE	<	0.000		UG/L	0.005	0.005	11/5/2018	6	36		2021/11	DUE NOW	64870031 81105144 5S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2051	LASSO (ALACHLOR)	<	1.000		UG/L	2	1	3/29/2019	3	36		2022/03	DUE NOW	64870031 90329100 0S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2050	ATRAZINE	<	0.500		UG/L	1	0.5	3/21/2022	4	36		2025/03		C2C3168- 01	2698	E.S. BABCOCK & SONS	EPA 525.2

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT

COUNTY:

Sample Point:

CLASS: CTGA

STATUS:

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_003_003	S2	2931	1,2-DIBROMO-3-CHLOROPROpane	0.065		0.010		UG/L	0.2	0.01	3/7/2022	5	3	Interval	2022/06	DUE NOW	C2C0965-01	2698	E.S. BABCOCK & SONS	EPA 504.1
		2946	ETHYLENE DIBROMIDE		<	0.020		UG/L	0.05	0.02	3/7/2022	5	36		2025/03		C2C0965-01	2698	E.S. BABCOCK & SONS	EPA 504.1
		2037	SIMAZINE		<	1.000		UG/L	4	1	3/21/2022	4	36		2025/03		C2C3168-01	2698	E.S. BABCOCK & SONS	EPA 525.2

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT

COUNTY: TULARE

Sample Point: WELL 02 - SOUTH STBY

CLASS: STCA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_002_002		SULTANA COMMUNITY SERVICES DISTRICT						WELL 02 - SOUTH STBY												
	IO	INORGANIC																		
		1002	ALUMINUM		<	50.000		UG/L	1000	50	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1074	ANTIMONY, TOTAL		<	6.000		UG/L	6	6	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1005	ARSENIC		<	2.000		UG/L	10	2	2/18/2021	3	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1010	BARIUM		<	100.000		UG/L	1000	100	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1075	BERYLLIUM, TOTAL		<	1.000		UG/L	4	1	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1015	CADMIUM		<	1.000		UG/L	5	1	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1020	CHROMIUM		<	10.000		UG/L	50	10	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1025	FLUORIDE	0.100		0.100		MG/L	2	0.1	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1035	MERCURY		<	1.000		UG/L	2	1	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1036	NICKEL		<	10.000		UG/L	100	10	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1039	PERCHLORA TE		<	4.000		UG/L	6	4	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1045	SELENIUM		<	5.000		UG/L	50	5	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 02 - SOUTH STBY CLASS: STCA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_002_002	IO	INORGANIC																	
		1085 THALLIUM, TOTAL		<	1.000		UG/L	2	1	2/18/2021	2	108		2030/02		64870022 10218145 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	NI	NITRATE/NITRITE																	
		1040 NITRATE	4.500		0.400		MG/L	10	0.4	2/12/2024	9	12	Interval	2025/02		VI 2441076- 001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 4500- VO3-F-00
		1041 NITRITE		<	0.400		MG/L	1	0.4	2/18/2021	2	108		2030/02		64870022 10218145 ON	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	RA	RADIOLOGICAL																	
		4109 GROSS ALPHA PARTICLE ACTIVITY		<	1.900	1.410	PCI/L	15	3	2/17/2023	2	108		2032/02		VI 2341038- 001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 900.0
	S1	REGULATED VOC																	
		2981 1,1,1-TRICHLOROETHANE		<	0.500		UG/L	200	0.5	2/18/2021	2	108		2030/02		64870022 10218145 OV	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2988 1,1,2,2-TETRACHLOROETHANE		<	0.500		UG/L	1	0.5	2/18/2021	2	108		2030/02		64870022 10218145 OV	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2985 1,1,2-TRICHLOROETHANE		<	0.500		UG/L	5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 OV	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2978 1,1-DICHLOROETHANE		<	0.500		UG/L	5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 OV	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2977 1,1-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	2/18/2021	2	108		2030/02		64870022 10218145 OV	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2378 1,2,4-TRICHLOROBENZENE		<	0.500		UG/L	5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 OV	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 02 - SOUTH STBY CLASS: STCA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_002_002	S1	REGULATED VOC																	
		2968	O-DICHLOROB ENZENE		<	0.500	UG/L	600	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2980	1,2-DICHLOROE THANE		<	0.500	UG/L	0.5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2983	1,2-DICHLOROP ROPANE		<	0.500	UG/L	5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2413	1,3-DICHLOROP ROPENE		<	0.500	UG/L	0.5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2969	P-DICHLOROB ENZENE		<	0.500	UG/L	5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2990	BENZENE		<	0.500	UG/L	1	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2982	CARBON TETRACHLO RIDE		<	0.500	UG/L	0.5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2380	CIS-1,2-DICHLOROE THYLENE		<	0.500	UG/L	6	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2964	DICHLOROM ETHANE		<	0.500	UG/L	5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2992	ETHYLBENZ ENE		<	0.500	UG/L	300	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2251	METHYL TERT-BUTYL ETHER		<	3.000	UG/L	13	3	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT COUNTY: TULARE
Sample Point: WELL 02 - SOUTH STBY CLASS: STCA STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_002_002	S1	REGULATED VOC																	
		2989	CHLOROBEN ZENE	<	0.500		UG/L	70	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2996	STYRENE	<	0.500		UG/L	100	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2987	TETRACHLO ROETHYLEN E	<	0.500		UG/L	5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2991	TOLUENE	<	0.500		UG/L	150	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2979	TRANS-1,2- DICHLOROE THYLENE	<	0.500		UG/L	10	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2984	TRICHLORO ETHYLENE	<	0.500		UG/L	5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2218	TRICHLORO FLUOROMET HANE	<	5.000		UG/L	150	5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2904	TRICHLORO TRIFLUORO ETHANE	<	10.000		UG/L	1200	10	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2976	VINYL CHLORIDE	<	0.500		UG/L	0.5	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2955	XYLENES, TOTAL	<	0.500		UG/L	1750	0.5	2/18/2021	2	108		2030/02		64870022 10218145 0V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	S2	REGULATED SOC																	
		2414	1,2,3- TRICHLORO PROPANE	<	0.000		UG/L	0.005	0.005	11/5/2018	6	108		2027/11		64870021 81105143 0S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SULTANA COMMUNITY SERVICES DISTRICT

COUNTY:

Sample Point:

CLASS: STCA

STATUS:

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400824_002_002	S2	2051	LASO (ALACHLOR)		<	0.200		UG/L	2	1	2/2/2012	1	108		2021/02	DUE NOW	64870021202021430S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2050	ATRAZINE		<	0.500		UG/L	1	0.5	2/18/2021	2	108		2030/02		64870022102181450S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2931	1,2-DIBROMO-3-CHLOROPROPANE	0.710		0.050		UG/L	0.2	0.01	2/28/2022	7	12	Interval	2023/02	DUE NOW	C2C0065-01	2698	E.S. BABCOCK & SONS	EPA 504.1
		2946	ETHYLENE DIBROMIDE		<	0.020		UG/L	0.05	0.02	2/28/2022	6	108		2031/02		C2C0065-01	2698	E.S. BABCOCK & SONS	EPA 504.1
		2037	SIMAZINE		<	1.000		UG/L	4	1	2/18/2021	2	108		2030/02		64870022102181450S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

Appendix C: Source Water & Distribution Bacteriological Monitoring Report

Source Bacteriological Monitoring Report

5400824 *Sultana Community Services District*

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
7/11/2024	10:15	Well 03 Main	Well	QTray	<1.0	<1.0				
6/20/2024	12:15	Well 03 Main	Well	QTray	<1.0	<1.0				
5/6/2024	13:55	Well 03 - Main	Well	QTray	<1.0	<1.0				
4/16/2024	13:35	Well 03 Main	Well	QTray	<1.0	<1.0				
3/7/2024	14:55	Well 03 - Main	Well	QTray	<1.0	<1.0				
2/12/2024	12:45	Well 03 Main	Well	QTray	<1.0	<1.0				
1/4/2024	13:25	Well 03 Main	Well	QTray	1	<1.0				

Bacteriological Distribution Monitoring Report

5400824 Sultana Community Services District

Distribution System Freq: 1/M

Sample Date	Location	T Coli	E Coli	F Coli	HPC	Type	Cl2	Cl2 Avg	Viol. Type	GWR Satisfied?	Comments
7/11/2024	410427 Ave 416	A	A			Routine	0.56				
6/20/2024	10427 Ave 416	A	A			Routine	0.51				
5/6/2024	10427 Ave 416	A	A			Routine	0.88				
4/16/2024	10427 Ave 416	A	A			Routine	0.57				
3/7/2024	10427 Ave 416	A	A			Routine	0.67				
2/12/2024	10427 Ave 416	A	A			Routine	0.80				
1/4/2024	10427 Ave 416	A	A			Routine	0.89				

Violation Key

MCL	Exceeds the maximum contaminant level	MR5	Incorrect number of repeat samples as follow-up to a positive sample
MR1	No monthly sample for the report month	MR6	No source sample
MR2	No quarterly sample for the report month	MR7	No summary report submitted
MR3	Incorrect number of routine samples for the report month	MR8	Other comments and/or info
MR4	Did not collect 5 routine samples for previous month's positive sample	MR9	Cl2 not reported

Appendix D: Guidance for Bacteriological Sample Site Plan

Division of Drinking Water Tulare District

GUIDELINES FOR COMPLETING THE BACTERIOLOGICAL SAMPLE SITING PLAN FOR SMALL WATER SYSTEMS

The total coliform regulation requires the water supplier to submit a bacteriological sample siting plan to the Division of Drinking Water (Division), District Office for review and approval. The locations where samples are to be collected must be written down and formally approved by the District Office. These guidelines and Attachment 1, "Bacteriological Sample Siting Plan" Form, are to assist you in complying with these requirements.

To comply with the requirements for submitting a Bacteriological Sample Siting Plan, two (2) items must be submitted to the District Office at this time.

1. A system map, street map, or system schematic showing all sampling locations must be submitted. The map can be prepared by any system representative. It does not have to be prepared by an engineer. The following are also to be shown on the map:
 - Water Sources (i.e., well or spring)
 - Treatment Facilities (i.e., chlorination)
 - Storage Tanks
 - Pressure Reducing Stations
 - Booster Stations
 - Pressure Zones
 - Dead Ends
 - Service Area Boundaries
 - Routine Sample Sites
 - Repeat Sample Sites
 - Special Sample Sites
2. Complete Attachment 1, the "Bacteriological Sample Siting Plan" form, and **return the system map and form to the District Office for review and approval.**

Once the Bacteriological Sample Siting Plan has been approved by the Division, copies should be provided to the person responsible for sample collection, the laboratory and the person responsible for reporting coliform-positive samples to the Division.

Selection of Sampling Sites

The routine sampling sites chosen must be representative of the water distribution system including all pressure zones, areas supplied by each water source and distribution reservoir.

Looped Systems: If your entire water distribution system is looped, then one routine sample point may be representative of your system, assuming valves are open.

Pressure Zones: You should only be concerned about sampling in different pressure zones if your water system serves different areas of varying elevations, for example in mountainous areas.

How many routine sampling sites are required?

The minimum number of samples for the water system shall be based on the known population served or the total number of service connections, whichever results in the greater number of samples, as shown in Table 64423-A. For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

Table 64423-A		
Minimum Number of Routine Total Coliform Samples Monthly Population Served¹	Service Connections	Minimum Number of Samples Per Month
25 to 1000	15 to 400	1
1,001 to 2,500	401 to 890	2
2,501 to 3,300	891 to 1,180	3
3,301 to 4,100	1,181 to 1,460	4
4,101 to 4,900	1,461 to 1,750	5
4,901 to 5,800	1,751 to 2,100	6
5,801 to 6,700	2,101 to 2,400	7
6,701 to 7,600	2,401 to 2,700	8
7,601 to 8,500	2,701 to 3,000	9
8,501 to 12,900	3,001 to 4,600	10
12,901 to 17,200	4,601 to 6,100	15
17,201 to 21,500	6,101 to 7,700	20
21,501 to 25,000	7,701 to 8,900	25
25,001 to 33,000	8,901 to 11,800	30
33,001 to 41,000	11,801 to 14,600	40
41,001 to 50,000	14,601 to 17,900	50
50,001 to 59,000	17,901 to 21,100	60
59,001 to 70,000	21,101 to 25,000	70

¹ For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

How many repeat sampling sites are required?

A repeat sample set consists of three samples to be collected from the following locations:

- One repeat sample from the same routine location.
- One repeat sample from an *upstream location* (within 5 connections of the routine site).
- One repeat sample from a *downstream location* (within 5 connections of the routine site).

Each routine sample site must have identified repeat sample sites.

Ground Water Rule Compliance: All active groundwater sources in operation at the time of the coliform-positive sample must also be sampled along with the repeat sample set.

What if the water system does not have enough locations to select the required number of routine and repeat sample sites?

If the water system does not have enough sample locations to identify the required routine and repeat sample sites, contact the District Office for further guidance.

Pointers for Sample Site Selection

- When selecting a routine sample site you should be able to select a site upstream and a site downstream for repeat sampling.
- Select a site where the water is used continuously all year round.
- Pick a site that is easily accessible, i.e., a fenced yard with a locked gate and vicious dog is not a good selection.
- When choosing a sampling tap you should consider these factors:
The sampling tap should be located in as clean an environment as possible. It should be protected from contamination by humans, animals, airborne materials or other sources of contamination.

If you choose an outside private tap, it should be one that is in frequent use, clean, and at least 1½ feet (18 inches) above the ground. The sample tap should discharge downward.

If you choose an inside tap, be sure that you are not sampling from drinking fountains; taps that have aerators or strainers, or swivel faucets; or taps off of individual homeowner treatment units.

Do not choose a fire hydrant as sampling tap.

Avoid taps that are surrounded by excessive foliage or taps that are dirty or corroded.

Avoid taps that leak, have fittings with packing, or have permanent hoses or attachments fastened to the tap (Never collect a sample from a hose).

Avoid the use of dead ends for routine sample collection, and use them for repeat samples only if no other sample sites are available and if there is continuous water use from a service off the dead-end.

Instructions for Completing the Bacteriological Sample Siting Plan Form

This form has been designed to include all the requirements for the Bacteriological Sample Siting Plan.

- **Public Water System Classification**

The public water system (PWS) classification for your water system is either community, nontransient noncommunity or transient noncommunity. If you are uncertain of your classification, contact the District Office.

- **Month/Daily Users**

The monthly population determines the frequency of bacteriological sample collection for community water systems and nontransient noncommunity systems. For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

- **Active Service Connections (Community water systems only)**

This is the number of active hook-ups served by the system. If your system has a hook-up to a vacant lot, do not count this as an active connection. If a vacant lot has a right to a future connection, do not count this as an active connection. If a residence is connected to the system, but the residence is vacant, count this as an active hook-up.

- **Sampling Frequency**

This is the minimum number of routine bacteriological samples required at the frequency specified. If any routine sample is positive for coliform bacteria, additional repeat samples will be required. Repeat samples are in addition to the required routine samples. If you are uncertain of the routine sampling frequency for your water system, contact the District Office.

- **Trained Sampler**

The person collecting samples must be trained.

Sampling Service: Water systems utilizing a certified laboratory or other sampling service for water sample collection will be considered to have trained samplers. Enter the name of the laboratory or sampling service collecting your samples. A copy of the approved Bacteriological Sample Siting Plan should be provided to the laboratory or sampling service, if one is used.

Other Trained Samplers: Any person receiving a certificate from AWWA for attendance of the Water Sampling Training should submit a copy of their certificate along with the completed form. Any other samplers should submit a statement of their experience and training to this office for approval.

- **Analyzing Lab**

Enter the state-certified laboratory, which will be analyzing your water samples.

- **Person Responsible to Report Coliform-Positive Samples to the Division**

This should be the person that the laboratory is required to contact when a sample is total or fecal coliform positive. This person must notify the Division within 24 hours of a violation of the total coliform standard (more than one positive sample in a month) or when any sample is fecal or *E. coli* positive. This person should have the authority to take corrective action as required by regulation and the Division. This should be the same person listed on your Emergency Notification Plan.

- **Day/Evening Phone Number**

The Division requires that the water system provide the phone numbers of the person listed above so that they can be contacted by the laboratory or the Division at any time during the day or evening in the event of a bacteriological emergency.

- **Signature and Date**

The person preparing the Sample Siting Plan should sign and date the plan. If the Division has questions regarding the sampling plan, this is the person to be contacted.

- **Sample ID**

This should be entered on the laboratory slip when the sample is turned into the laboratory. This is the unique identifier for the water sample location, or the location address may also be used. For systems, which have no more than five (5) routine locations, these routine sites will be 1-ROU, 2-ROU, 3-ROU, 4-ROU, and 5-ROU.

Each routine sample site must have two repeat sampling sites. Repeat sample sites are to be located within five (5) service connections upstream and downstream of the routine sample site.

All sample locations should be marked in some way with the Sample ID or location address, i.e., the code painted on the sampling location or tagged with a water proof tag so the person collecting the water sample is sure to collect the water from the correct sample locations.

- **Sample Type**

This describes what type of sample (routine or repeat) is to be collected at this location.

- **Sample Point**

This is the type of the sample location. Use the following abbreviations, when appropriate: HB - Hose Bib (exterior), SF - Sink Faucet, PC - Goose Neck Type Copper Tube with Pet Cock

- **Location of Sample Point**

This is the description of the area in the distribution that the sample site is located. Routine sample sites shall not be located at dead ends. Use the following abbreviations, when appropriate: DE - Dead End (Not Recommended), PZ - Pressure Zone, RD - Representative Distribution

- **Location Address**

This is the actual physical location where the water sample is to be collected. If possible use a street address, i.e., 103 Good Street. If the location does not have a street address, use the nearest crossroads or use the last name of the resident, i.e., "Brown Residence." If the location is a business, please list the business name and address.

When describing the location, keep in mind that the person collecting water samples must be able to locate the sample site from your description.

- **Months Sample Collected at This Location**

This is the schedule for routine samples to be collected. For example, suppose two (2) sites are representative of your systems. Site No. 1 will be sampled in January, March, May, July, September, and November. Site No. 2 will be sampled in February, April, June, August, October, and December. All routine sites identified should be rotated to allow sampling at least every 3 months.

BACTERIOLOGICAL SAMPLE SITING PLAN (BSSP) FOR SMALL WATER SYSTEMS

System No.:		System Name:			PWS Classification:	
No. of Monthly Users:		No. of Daily Users:		No. Active Service Connections:		Cl2 Treatment:
Sampling Frequency: __ per month		Seasonal System:		Period of Operation:		
Name of Trained Sampler:			Analyzing Lab:		Analyzing Lab:	
Person Responsible to Report Positive Samples to the Division:					Day/Evening Phone No:	
Signature of Water System Representative:					Date:	

Sample ID	Sample Type	Sample Point	Location of Sample Point	Address of Sample Point	Months Sample Collection at this Location
1-ROU	Routine				
1-REP1	<i>Repeat</i>				<i>Repeat Sample Only</i>
1-REP2	<i>Repeat</i>				<i>Repeat Sample Only</i>

In the event of a routine positive sample, a sample(s) will be collected from the well(s) in use for Ground Water Rule compliance.

If continuous chlorination is provided, raw water samples are taken **monthly**.

The SWRCB-Division of Drinking Water or Local Primacy Agency has reviewed and approved this BSSP. Any plans on file dated prior to approval date below are void. The water system must sample their distribution system and raw water special purpose source samples for bacteriological quality in accordance with the approved BSSP beginning _____. Per the California Code of Regulations-Title 22 §64422, a water system is required to submit an updated plan to the State Board at least once every ten years and at any time the plan no longer ensures representative monitoring of the system.

District Office Representative Name: _____ Title: _____ District Name: Tulare District

Signature: _____ Date: _____

Appendix E: Lead and Copper Tap Sample Results Reporting Form



State Water Resources Control Board

Division of Drinking Water

Lead and Copper Tap Sample Results Reporting Form

This form must be submitted by the public water system to the regulating entity (DDW District Office or County Agency) for each round of lead and copper sampling

Report Date: (mm/dd/yyyy)	
Water System Name:	
Water System Number:	
Water System Type:	<input type="radio"/> Community <input type="radio"/> Non-Transient, Non Community
Monitoring Frequency:	<input type="radio"/> 6-month <input type="radio"/> Annual <input type="radio"/> Triennial
# of Samples Required:	
# of Samples Reported:	
	90th Percentile Level (mg/L)
Lead: <i>Action Level = 0.015 mg/L</i>	
Copper: <i>Action Level = 1.3 mg/L</i>	

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
01					
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Sampling Site Change

Each round of sampling should be conducted at the same sampling sites. If an original sampling site is not available, you should collect a tap sample from another site meeting the same Tier criteria as the original site.

You must complete/submit the ***Lead and Copper Tap Sampling Site Change*** form.

Notification of Results

As required by *40 Code of Federal Regulations Section 141.85(d)*, within 30 days of learning of the tap monitoring results, I notified the participants, by mailing or by another method approved by the State, of the lead sample results from their individual taps, provided an explanation of the health effects of lead, listed steps the consumer could take to reduce exposure to lead, provided contact information for the water utility, the maximum contaminant level goal for lead, action level for lead, and any definitions.

Notification was done on _____ by _____
(date)

- ☐ Direct Mail
☐ Posting in public area (NTNC systems only)
☐ Other (please specify below) _____
-

For general information on lead and copper tap sampling, you can refer to the ***SWRCB Lead and Copper Tap Sample Results Guidance Document***. If you have any questions or comments, please contact your regulating entity (Division of Drinking Water District or County Agency).

SIGNATURE:	DATE:
NAME (Print):	TITLE:

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					

Appendix F: Cross Connection Control Guidance

Cross-Connection Control for Small Community Water Systems

Division of Drinking Water – Tulare District

Purpose of Cross-Connection Control Program: Water provided by a public water system may be contaminated via cross-connections within the distribution system. The purpose of the cross-connection control program is to reduce the hazard of contamination of the public water system by identifying actual and potential cross-connections and taking action to protect the system from these hazards. This is accomplished by installing backflow prevention assemblies where hazards are identified; or ensuring that water-using equipment on the premises is installed in accordance with plumbing code requirements and good practice.

What are cross-connections?

Cross-connections are actual and potential unprotected connections between a potable water system and any source or system containing unapproved water or a substance which is not safe. Examples of cross-connections include:

1. Improperly installed irrigation systems that may allow backsiphonage of stagnant, bacteriologically unsafe water into the piping system.
2. Improperly plumbed water-using devices such as hot-tubs, boilers or commercial dishwashers which may allow unsafe water back into the domestic piping system.
3. Irrigation systems served by an auxiliary source, such as a private well or creek. Such systems create a potential for major contamination of the public water system via interties with the domestic piping system.
4. Interconnections between the potable system and a non-potable system.

What the Regulations Require

Section 7584 of the California Code of Regulations requires that each public water system have a cross connection control program that includes these elements:

1. The adoption of operating rules or ordinances to implement the cross-connection program.
2. The conducting of surveys to identify water user premises where cross connections exist or are likely to occur.
3. The provisions of backflow protection by the water user at all connections where a cross connection hazard has been identified.
4. The provision of at least one person trained in cross connection control to carry out the program.
5. The establishment of a procedure or system for testing backflow prevention assemblies.
6. The maintenance of records of locations, tests, and repairs of backflow prevention assemblies within each water supplier's distribution system.

Getting Started

For small community water systems, the initial elements of the program consist of the following:

1. Adopting an ordinance or set of rules to implement the cross-connection control program. The ordinance or set of rules is important since it establishes the legal authority to carry out the program.
2. Conducting a system survey to identify actual and potential cross-connection hazards.
3. Ensuring that hazards are abated by the installation of backflow prevention assemblies at the meter, eliminating the hazard in conjunction with the owner of the property or providing internal cross-connection protection.

System Survey

The system survey consists of a preliminary survey and, if necessary, a more detailed second survey. For most small systems, the initial survey may consist of a questionnaire sent to each customer asking whether the customer has specific potential hazards. Documentation of the system survey is to be submitted to the Division. Attached is a summary form for documentation of the system survey.

Residential areas

Customers should be asked if any of the following are located on-site:

1. Auxiliary water supply (i.e. either a well or a creek pump) - backflow prevention device is mandatory.
2. Irrigation systems - backflow prevention device not required if system is installed in accordance with plumbing codes with appropriate vacuum breakers.
3. Swimming pool, hot tub or spa - backflow prevention device not required if system is installed in accordance with plumbing codes.
4. Solar hot water heating panels - backflow prevention device not required if system is installed in accordance with plumbing codes.
5. Gray water systems - backflow prevention assemblies may not be required if the system is installed in accordance with the Uniform Plumbing Code.

If these or other potential hazards are located on site, the water system is to determine whether the equipment has been installed in accordance with plumbing codes and/or good practice in order to minimize the risk of backflow.

Commercial customers: A more detailed questionnaire and survey is necessary. Small community systems, which also serve commercial customers, should review the Department of Health Service's "Manual of Cross-Connection Control - Procedures and Practices". A system survey of commercial users as specified in the Manual is to be performed. As an alternative, the system may decide to require backflow prevention assemblies' at all commercial service connections where hazards are likely to exist.

Wastewater and Hazardous Wastes: A service connection which handles wastewater or dangerous chemicals requires special evaluation and protection from cross-connection hazards. For additional information on evaluating this type of facility, please contact the appropriate regulatory agency and a cross-connection control specialist.

ELEMENTS OF A CROSS-CONNECTION CONTROL PROGRAM

DDW – Tulare District

When implementing a Cross-Connection Control Program, the water supplier or health agency should follow an organized plan. The following items should be included as a minimum. The items **explain the Department of Health Services' policy regarding the regulations.**

7584. Responsibility and Scope of Program

The water supplier shall protect the public water supply from contamination by implementation of a cross-connection control program. The program, or any portion thereof, may be implemented directly by the water supplier or by means of a contract with the local health agency, or with another agency approved by the health agency. The water supplier's cross-connection control program shall for the purpose of addressing the requirements of Sections 7585 through 7605 include, but not limited to, the following elements:

(1) *The adoption of operating rules or ordinances to implement the cross-connection program.*

A public water supplier shall enact an ordinance or rule of service outlining the cross-connection control program and providing enforcement authority.

(2) *The conducting of surveys to identify places where cross-connections are likely to occur.*

Water utilities do not have any responsibility for controlling or abating cross-connections on a user's premises. All existing facilities where potential cross-connections are suspected, however, shall be listed and inspected or reinspected on a priority basis, where feasible. All applications for new services or for enlarging existing services or changing of occupant shall be reviewed or screened for cross-connections hazards

(3) *The provision of backflow protection at the user's connection or within the user's premises or both.*

Adequate provisions for implementation and enforcement of backflow protection where needed including the shutting off service when necessary

4) *The provision of at least one person trained in cross-connection control to carry out the cross-connection program.*

Specific units of the health agency and/or water supplier should be designated to organize and carry out the cross-connection control program. The personnel in those units should be trained as to the causes and hazards of unprotected cross-connections.

(5) *The establishment of a procedure or system for testing backflow preventers.*

A list of approved backflow preventers and list of certified testers should be made available to each water user required to provide backflow protection.

The list may include backflow devices approved by University of Southern California, Foundation for Cross-Connection Control and IAPMO, which may be found on the SWRCB website at the following address:

http://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/Publications.shtml

The List of certified testers may be lists developed by the American Water Works Association and local county health agencies.

Backflow preventers should be tested at least yearly or more often as required by the health agency or water supplier.

(6) *The maintenance of records of locations, tests and repairs of backflow preventers*

Adequate records should be kept and filed for reference. These records should include, in addition to the name of the owner of the premises, the:

- a) Date of inspection
- b) Results of inspection
- c) Required protection
- d) List of all backflow preventer devices in the system
- e) Test and maintenance reports
- f) All correspondence between the water supplier, the local health authority, and the consumer
- g) Records must be maintained for a minimum of three years

Records of inspection and testing should be evaluated to determine if:

- a) Devices are frequently or sufficiently reviewed to detect failure.
- b) There are unusual feature of a particular model of device or component.
- c) Cause of failure can be eliminated.

A program should be established to notify the water user when his backflow preventer must be tested. (A minimum of once each year is required.) After installation or repair, a backflow preventer should be tested and approved before it is accepted.

7605. Testing and Maintenance of Backflow Preventers

Regulations require the following regarding testing and maintenance of backflow prevention devices:

- (a) The water supplier shall assure that adequate maintenance and periodic testing are provided by the water user to ensure their proper operation.
- (b) Backflow preventers shall be tested by persons who have demonstrated their competency in testing of these devices to the water supplier or health agency.
- (c) Backflow preventers shall be tested at least annually or more frequently if determined to be necessary by the health agency or water supplier. When devices are found to be defective, they shall be repaired or replaced in accordance with the provisions of this Chapter.
- (d) Backflow preventers shall be tested immediately after they are installed, relocated or repaired and not placed in service unless they are functioning as required.
- (e) The water supplier shall notify the water user when testing of backflow preventers is needed. The notice shall contain the date when the test must be completed.
- (f) Reports of testing and maintenance shall be maintained by the water supplier for a minimum of three years.

Cross-Connection Survey Summary Form-Small Community Water Systems

Name of System _____ System Number _____

Description of Survey Procedures-How survey was conducted, (include copy of survey form):
Person conducting survey (List name and qualifications):

Procedures for Residential Connections:

Procedures for Commercial Connections:

Total number of service connections _____ Number of service connections surveyed _____
Number of connections with auxiliary sources (i.e. wells or creek pumps) _____
Number of connections with other hazards _____
Total number of backflow prevention devices _____

Type of Hazard Identified(i.e. private well, hot tub, irrigation system, swimming pool, etc)	Number of connections with hazard	Number of devices installed	Number where device not necessary

Describe follow-up for service connections that did not respond to the survey:

Long-term (Describe on-going cross-connection protection & testing of backflow prevention assemblies)

Submitted by (signature) _____ Date _____

Appendix G: Guidance for Chlorination Operations Plan

Guidance Document for the Preparation of an Operations Plan for Small Water Systems with Chlorination

Written Description of Water Sources, Storage Tanks and Distribution System (with as-built maps or schematics) and General Record Keeping

We recommend a brief description of sources, storage, chlorinator unit (treatment) and number of connections and character (seasonal rental, year-round, etc.). Example; 200 foot well drilled in 1972, 1500 gallon welded steel storage tank, chlorinator with a diaphragm type pump (manufacturer and model) and 25 gallon disinfectant reservoir, serving 15 connections (one third seasonal occupancy).

We strongly recommend a multi-tabbed file be set up to keep copies of the laboratory results (10 year retention) and monitoring requirements and an accompanying calendar schedule for all sampling.

Other files that should be kept on file are copies of correspondence from our Division (e.g., water supply permit), all sampling plans (Bacteriological Sample Siting Plan), water main and valve location maps, the well driller's report and County well construction permit that demonstrates conformance to its well ordinance (schematic documenting adequate horizontal protection of well from sanitary hazards), pump and storage tank information, and their accompanying service records, etc.

The Operations Plan elements are as follows:

• **ROUTINE OPERATIONAL PROCEDURES FOR EACH COMPONENT OF THE SYSTEM:**

- A. Visual inspection of **WELL** (daily or minimum of weekly).
Check for the following; water leaks that could contaminate well, unscreened or openings where sealants can be applied, electrical hazards, chemical hazards (proper use of chemicals around well head). Tip: Maintain a log book for each well site that records maintenance and monthly water production and flow rates, water table depths and any maintenance performed.
 - 1. Well has the ability to be pumped to waste and sampling tap (non-threaded down-turned hose bib).
 - 2. Check the pump and controls for proper operation of well and chlorination equipment.
 - 3. General house keeping: remove rodent feces, dirt, vegetation, any standing water, control gophers/squirrel burrowing around well head to eliminate potential contamination hazards.
- B. Visual inspection of the **STORAGE TANKS** (daily or minimum of weekly).
 - 1. Inspect vents and overflow outlets for proper protection (screens, flapper valve, etc.) to keep out rodents and insects.
 - 2. Inspect for any leaks or damage (record observations and repair as needed).
 - 3. Record system pressure. Record the pressure the pump turns on, the pressure the pump turns off and the duration of the run time so storage tank does not overflow.

4. Scheduled inspection and cleaning of storage tank (quarterly, semi-annually or annually). Record kept for the date cleaned and any observations (e.g., remnants of rodents, etc.)
- C. Visual inspection of **CHLORINATOR PUMP** and disinfection reservoir (daily or minimum of weekly).
1. Inspect the pump for proper operation. Hypochlorinator pumps are prone to vapor lock (air bubble in line) and need to be equipped with degassing feature. Installation Tip: The problem can be greatly alleviated by maintaining positive pressure on the intake of the hypochlorinator pump by placing the hypochlorinator pump at the same elevation as the chlorine solution tank.
 2. Inspect the disinfectant in the reservoir for concentration and adequate volume for the operational period (record results).
 3. Determine if there is enough disinfectant on hand for one or more weeks.
- D. Measure the **DISINFECTANT RESIDUAL** in the distribution system (free chlorine test kit required).
1. Monitor and record the results from designated locations which are the same locations as the routine bacteriological sample sites. The residuals must be reported with the bacteriological results at the time the bacteriological sample is collected. This information is also used for reporting the quarterly chlorine residuals under the Disinfection Byproducts Rule). Reporting forms attached.
 2. Determine if an adequate level of disinfectant is maintained.
 - a. If disinfectant level is low (0.2 to 0.3 mg/L is generally the lowest level reportable using colorimetric test kits), determine the reason and correct. If enforcement action taken for repeated Total Coliform Rule violations, there may be more stringent chlorine residual requirements.
 - b. If no measurable disinfectant, notify owner, determine reason, and remedy. If no disinfectant residual for 24 hours, notify Tulare District Office of the California Department of Public Health.
- E. Maintenance of **GAUGES and METERS**.
1. Inspect all gauges and meters for leaks and proper function daily. Repair or replace as needed (keep record of date). Schedule routine calibration checks to ensure accurate readings are being provided.
- F. Inspection and **EXERCISING of the VALVES**.
1. Inspect valves for leaks (record observations, repair or replace if leaking).
 2. Exercise valves on a schedule, as needed (i.e. quarterly, semi-annually, annually, record dates on attached sheet).
- G. Operation and maintenance of **DISTRIBUTION FACILITIES**.
1. Visually inspect the distribution system for leaks on a regular basis. Record date and observations.
 2. Flush dead end mains or lines periodically (quarterly, semi-annually, annually as needed. Record date and observations).

- **MONITORING AND REPORTING:**

- A. **BACTERIOLOGICAL MONITORING FROM DISTRIBUTION SYSTEM;** as per approved Bacteriological Sample Siting Plan, required monthly, report containing results submitted to the Department by the 10th day of the following month (refer to attached guidance). Recommend samples be collected early in the week in case repeat samples must be collected after a positive sample result is received. Repeat samples must be collected within 24 hours of receipt of positive result.
 - 1. If sample positive, lab must notify water system contact person or the Department if you can not be reached. Multiple repeat samples must be collected (three to four repeat samples depending on system classification). Department recommends that water system provides a copy of the Emergency Notification Plan form to analyzing laboratory.
 - 2. Take five routine samples the month following a positive sample.
- B. **BACTERIOLOGICAL MONITORING FROM WELL SOURCES;** should be described in the sample siting plan and is required from raw water at well head PRIOR to chlorination. The samples are required to be analyzed using the density method. If sample positive, notify Department by telephone, e-mail for follow-up investigation. Frequency is dependent on type of water system and report containing the results submitted to the Department by the 10th day of the following month.
- C. **CHEMICAL SOURCE MONITORING;** as required by the Department, forward results to the Department (see attached Water Quality Monitoring Schedule).
- D. **DISINFECTION BYPRODUCT RULE MONITORING;** as required annually for non-transient non-community and community water systems. If less than half the MCL for total trihalomethanes (TTHM) and haloacetic acids (HAA5), the sample can be reduced to once every three years. Routine sample should be collected during the warmest month of the year from a location with the longest detention time in the distribution system. Submit copy of laboratory results to the Visalia District of the CDPH.
- E. **LEAD AND COPPER TAP MONITORING;** as required for nontransient noncommunity and community water systems. Contact Department for when next round of monitoring is due.
- F. **WATER PRODUCTION**
Recommend installation of instantaneous and totalizing flow meter and record daily or at least weekly instantaneous and monthly production volume readings. This is especially valuable and necessary for hard rock wells. This information is reported in the annual report form.
- G. **PUBLIC NOTIFICATION** of violation required.
 - 1. Notification shall be given as per Emergency Notification Plan (copy of form attached). Provide updated plans when personnel change to the Department (attached). Templates of the various for public notices are available at [Templates for Public Notification | California State Water Resources Control Board](#)
 - 2. State the cause of problem, if known, and what steps have been taken to correct it.
 - 3. Send a copy of the notification to the Department with proof of notification.

- **EMERGENCY NOTIFICATION PLAN (ENP), ELECTRONIC ANNUAL REPORT TO THE DIVISION OF DRINKING WATER AND CONSUMER CONFIDENCE REPORT (CCR):**

- ENP: a form that lists the Department's and water system's contact information in the event of **water quality emergency** in which public notification must be performed. It must describe the methods to be followed in order to distribute the public notices to each customer as rapidly as possible. Small system may distribute notices by hand delivery. Attached is a copy of the form.
- Electronic Annual Report to the Division of Drinking Water: Outline the process for completing the Electronic Annual Report (EAR) to the Division of Drinking Water. The EAR is located at: <http://drinc.ca.gov/ear/home.aspx>
- CCR: required for nontransient noncommunity and community water systems that summarizes all monitoring done during the previous calendar year. The CCR must be distributed by July of every year. A template available at [Consumer Confidence Reports \(CCRs\) | California State Water Resources Control Board](#)

- **EMERGENCY OPERATIONAL PRACTICES:**

- List of **equipment on hand** for emergency repairs.
 - Miscellaneous wrenches.
 - Leak clamps
- List of sources of needed **equipment, not on hand**.
 - Name and address of supplier and type of equipment.
 - If under contract or rental.

Name	Address	Phone #	Equipment	Rental/ Contract
			Steel Tank Welder	
			Electrical repair	
			Digging equipment	
			Generator	
			Chemicals	

- List of distributors or suppliers of **replacement parts** for the system.
 - Name and address of supplier and type of equipment.

Name	Address	Phone #	Equipment
			PVC pipe, valves, and fittings
			pumps, pressure tank and gauges
			Chlorinator

D. List of **emergency contact numbers**:

	Name	Phone #
1.	Kristin Willet , SWRCB-DDW Tulare District Office	Office: (559) 447-3310 / Cell: (559) 280-6363
2.	Law Enforcement -	
3.	Electrician	
4.	Laboratory	
5.	Pump repair service	
6.	Chemical disinfectant supplier	
7.	Equipment supplier	
8.	Water System Owner	
9.	Certified Operators (include certification level)	

Attachments (Note: electronic copies of all forms available upon request):

1. Monthly water production and chlorine usage report
2. Coliform monitoring report forms for distribution and raw well sources
3. Quarterly chlorine residual report form for Disinfection Byproducts Rule
4. Bacteriological Sampling Siting Plan guidance
5. Water Quality Monitoring Schedule
6. Emergency Notification Plan form (please include job title and any operator certifications for names listed)
7. Lead and copper tap monitoring guidance

Appendix H: Monson Permit and 2022 Sanitary Survey

State Water Resources Control Board

Division of Drinking Water

May 12, 2022

Mrs. Celeste Perez
Monson Water System – 5403212
P.O. Box 158
Sultana, CA 93666

2022 DOMESTIC WATER SUPPLY PERMIT AMENDMENT NO. 03-24-22P-012 (REVISED PERMIT)

Dear Mrs. Perez:

On April 21, 2022, the State Water Resources Control Board, Division of Drinking Water (Division) staff conducted an inspection of the Monson Water System water system (Water System). The findings of this inspection are detailed in the enclosed sanitary survey report. Attached to this letter is Permit Amendment No. 03-24-22P-012. After evaluation of the Water System and completion of the enclosed sanitary survey report, the Division finds that the items below are required to be addressed by the Water System.

The items below were included in the 2017 and 2018 Sanitary Survey Report and are not considered past due.

1. By **January 31, 2018**, the Water System must complete a Possible Contaminating Activity (PCA) checklist for Well 01 and submit it to the Division.
2. By **May 31, 2020**, The Water System must submit an Operations Plan to the Division for review and approval.
3. By **December 31, 2017**, the Water System must submit a Bacteriological Sample Siting Plan to the Division for review and approval.
4. By **May 31, 2020**, the Water System must conduct a cross connection control survey using a certified cross connection control specialist or submit a time and schedule for having one completed.

E. JOAQUIN ESQUIVEL, CHAIR | EILEEN SOBECK, EXECUTIVE DIRECTOR

Mrs. Celeste Perez
Monson Water System

- 2 -

May 12, 2022

If you have any questions regarding the information contained in the sanitary survey report, please contact the Tulare District office at (559) 447-3300 or by email at DWPDIST24@waterboards.ca.gov.

Sincerely,

Kurt
Souza
Digitally signed by
Kurt Souza
Date: 2022.05.12
16:51:18 -07'00'

Kurt Souza, P.E.
Principle Engineer
DIVISION OF DRINKING WATER
SOUTHERN CALIFORNIA FIELD OPERATIONS BRANCH

KS/JA

cc: [all email only]
Tulare County Environmental Health Department
NGonzale@tularehhsa.org

Jose Padilla, Operator
jose_Padilla2010@yahoo.com

STATE OF CALIFORNIA

DOMESTIC WATER SUPPLY PERMIT

Issued To

Sultana Community Services District

For the Operation of the

Monson Water System
Water System No. 5403212

By the

State Water Resources Control Board, Division of Drinking Water



PERMIT NUMBER: 03-24-22P-012

DATE: May 11, 2022

WHEREAS:

1. The public water system known as *Monson Water System* is located approximately two miles southeast of Dinuba, California.
2. The legal owner of the *Monson Water System* is *Sultana Community Services District*. *Sultana Community Services District*, therefore, is responsible for compliance with all statutory and regulatory drinking water requirements and the conditions set forth in this permit.
3. This permit is being issued to *Sultana Community Services District* for the purpose of providing an updated permit reflecting the current operations of the *Monson Water System* under the regulations of the State of California Health and Safety Code.
4. The public water system for which the permit was written is described briefly below (a more detailed description of the permitted system is described in the attached report):

The Monson Water System's source of supply is groundwater. The Water System is classified as a community water system and serves a population of approximately 140 people through 32 service connections. The Water System serves one pressure zone and consists of one active groundwater source, Well 01. The water produced by Well 01 is treated using continuous chlorination prior to entering the distribution system.

And WHEREAS:

1. The Division of Drinking Water has evaluated all of the information submitted by *Sultana Community Services District* and has conducted a physical investigation of the *Monson Water System*.
2. The Division of Drinking Water has the authority to issue domestic water supply permits pursuant to Health and Safety Code Section 116540.

THEREFORE: The Division of Drinking Water has determined the following:

1. The *Monson Water System* meets the criteria for and is hereby classified as a community water system.
2. Provided the following conditions are complied with, the *Monson Water System* should be capable of providing water to consumers that is pure, wholesome, and potable and in compliance with statutory and regulatory drinking water requirements at all times.

SULTANA COMMUNITY SERVICES DISTRICT IS HEREBY ISSUED THIS DOMESTIC WATER SUPPLY PERMIT TO OPERATE SULTANA COMMUNITY SERVICES DISTRICT WATER SYSTEM.

The Monson Water System shall comply with the following permit conditions:

1. The Monson Water System shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted there under.
2. The only approved sources of domestic water supply for the Monson Water System are as follows:

Source	PS Code	Status
Well 01	CA5403212_001_001	Active

3. The only approved treatment for Monson Water System is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution.
4. No other sources or treatment (as described in provisions No. 2 and 3 above) shall be used by Monson Water System and no changes, additions, or modifications shall be made to the source unless an amended water permit has first been obtained from the Division.

5. All personnel who operate distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Monson Water System is classified as a D1 distribution system and shall be operated by, at minimum, a D1 certified distribution operator.
6. The Monson Water System shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The Water System shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.
7. The Monson Water System shall submit an Electronic Annual Report (EAR) each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
8. The Monson Water System shall record production data from each active source at least monthly.
9. The Monson Water System shall collect monthly raw water samples from the source for analyses of total coliform and fecal coliform or *E. coli* bacteria. The coliform test shall be performed using a density analytical method and the results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following
10. The Monson Water System shall monitor for coliform bacteria in the distribution system at least monthly and in accordance with an approved Bacteriological Sample Siting Plan (BSSP). The Division shall be notified immediately if any distribution system or source sample shows the presence of *E. coli* bacteria or if more than one bacteriological sample shows the presence of coliform bacteria during a single month.
11. The Monson Water System shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The Monson Water System shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.
12. The Monson Water System shall conduct Stage 2 Disinfection Byproduct (DBP) monitoring from the sample site listed below. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Code:

ST2 Monitoring Site	PS Code
ST2S1 - 13920 Ave 418	CA5403212_DST_900

13. The Monson Water System shall submit a monthly chlorination log to the Division by the 10th day of the following month.
14. The Monson Water System shall operate the continuous chlorination treatment facility in accordance with a Division-approved Chlorination Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval prior to implementation.

This permit supersedes all previous domestic water supply permits issued for this public water system and shall remain in effect unless and until it is amended, revised, reissued, or declared to be null and void by the Division of Drinking Water. This revised permit is non-transferable. Should Monson Water System water system undergo a change of ownership, the new owner must apply for and receive a new domestic water supply permit.

Any change in the source of water for the water system, any modification of the method of treatment as described in the Sanitary Survey Report, or any addition of distribution system storage reservoirs shall not be made unless an application for such change is submitted to the Division of Drinking Water.

This permit shall be effective as of the date shown below.

FOR THE DIVISION OF DRINKING WATER

Kurt
Souza

Digitally signed by
Kurt Souza
Date: 2022.05.12
16:58:49 -07'00'

Kurt Souza, P.E.
Principle Engineer

Date

Small Water System Evaluation and Technical Report
Division of Drinking Water: Tulare District

Monson Water System
System No. 5403212

Contact:	Celeste Perez, Board Secretary	System Type:	Community Water System
Inspection Date:	April 21, 2022	Inspected by:	Mr. Jason Autry, E.I.T.

I. INTRODUCTION

On April 21, 2022, the State Water Resources Control Board, Division of Drinking Water (Division) conducted a sanitary survey of the Monson Water System (Water System). The purpose of this report is to document the findings of the sanitary survey, to describe the existing water supply facilities and current operational practices, and to describe any deficiencies needing corrective action. The Water System was last inspected by the Division on January 17, 2019, as a routine sanitary survey.

PERMIT STATUS

The Water System currently operates under Domestic Water Supply Permit No. 03-24-20PA-010 issued by the Division on April 10, 2020. The permit provisions are listed below.

1. The Monson Water System water system shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted there under.
2. The only approved source of domestic water supply for the Monson Water System water system is as follows:

Source Name	Status	PS Code
Well 01 – Raw	Active	5403212-001

3. The only approved treatment for the Monson Water System water system is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution.
4. No other sources or treatment (as described in provisions No. 2 and 3 above) shall be used by the Monson Water System water system and no changes, additions, or modifications shall be made to the source unless an amended water permit has first been obtained from the Division.

5. All personnel who operate distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Monson Water System water system is classified as a D1 water system and shall be operated by a D1 certified distribution operator or higher.
6. The Monson Water System water system shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The Monson Water System water system shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.
7. The Monson Water System water system shall submit an electronic Annual Report (EAR) each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
8. The Monson Water System water system shall record production data from the active source at least monthly. The monthly water production shall be reported annually to the Division in the EAR.
9. The Monson Water System water system shall collect monthly raw water samples from the source for analyses of total coliform and fecal coliform or *E. coli* bacteria. The coliform test shall be performed using a density analytical method and the results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following month.
10. The Monson Water System water system shall monitor for coliform bacteria in the distribution system at least monthly and in accordance with an approved Bacteriological Sample Siting Plan (BSSP). The Division shall be notified immediately if any distribution system or source sample shows the presence of *E. coli* bacteria or if more than one bacteriological sample shows the presence of coliform bacteria during a single month.
11. The Monson Water System water system shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The Monson Water System shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.
12. The Monson Water System water system shall conduct Stage 2 Disinfection Byproduct (DBP) Monitoring once every year unless monitoring frequency is

reduced by the Division. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Code:

ST2 Monitoring Site	PS Code
ST2S1 - 13920 Ave 418	5403212-900

13. The Monson Water System water system shall submit a monthly chlorination log to the Division by the 10th day of the following month.

14. The Monson Water System water system shall operate the continuous chlorination treatment facility in accordance with a Division-approved Chlorination Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval prior to implementation.

The provisions included in the active permit are not all-inclusive and some do not reflect the current operations of the Water System. As a result, a revised permit is required. The revised permit, which accompanies this inspection report, reflects the changes in provisions and describes the current operations of the Water System.

DESCRIPTION OF WATER SYSTEM

Sultana Community Services District is the legal owner of the Water System. The mailing address for the Water System is P.O. Box 158 Sultana, California 93666. The Water System is located north of the City of Visalia, California. The Water System is classified as a community water system and supplies water to a population of approximately 140 through 32 service connections.

The Water System consists of a single pressure zone, one well, a storage tank and a distribution system. The Water System does not provide treatment to the source water. A locational map is provided in Appendix A.

ENFORCEMENT HISTORY

Citation No. 03-24-22C-024, issued February 18, 2022

The Water System failed to monitor Well 01 for nitrate in 2021.

II. INVESTIGATION AND FINDINGS

SOURCES OF SUPPLY

Well 01, Active – Treated, (CA5403212_001_001)

DWR Well Driller's Yes
Completion Report is on

file at Tulare District

Office:

Date of Well Completion: May 2017

Well Depth: 920 feet

Sanitary Seal Depth: 315 feet; cement

Well Casing: 22-inch diameter steel casing to 910 feet; perforations between 350 to 510, 550 to 730, and 780 to 900 feet

Flow Meter: Yes, digital

Pump Type: Submersible

Pump Make and Model: Unknown

Pump Size: 50-horsepower (hp)

Well Capacity 550 gallons per minute (gpm)

Source Discharge: Directly to a 65,000-gallon steel storage prior to entering the distribution system.

Source Operation: Based on tank level.

Comments: Well 01 is the Water System's only source of supply.

Source Water Assessments

In the 2018 Sanitary Survey Report, the Water System was directed to submit a Possible Contaminating Activity (PCA) Checklist. This directive remains outstanding and must be addressed by the Water System immediately. Please note, the Division does not establish new deadlines for past due items.

By January 31, 2018, the Water System must complete a Possible Contaminating Activity (PCA) checklist for Well 01 and submit it to the Division. A PCA Inventory form is included in Attachment F.

WATER PRODUCTION

The Water System uses Well 01 to meet system demands. Flow meters was installed at the wells in 2018. Based on the information reported in the Electronic Annual Reports, the production data from the active sources is outlined in Table 1 below. According to Water System staff flow data is recorded daily.

Table 1 – Water Production Data

Year	Annual Production (Gal.)	Max. Month (Gal.)
2020	4,959,000	618,000 (Aug.)
2019	4,401,000	723,000 (Sept.)
2018	3,946,100	481,400 (Jul.)

ADEQUACY OF SUPPLY

Production data, as reported by the Water System, and peaking factors established in the California Waterworks Standards were used to determine the Water System's Average Day (ADD), Maximum Day (MDD), and Peak Hour Demands (PHD). The adequacy of supply is determined by comparing the Water System's demands with its total source capacity which includes active and standby sources, storage capacity, and emergency interconnections with other water systems. The Water System's ADD, MDD, and PHD for the most recent four years are provided in Table 2. The total source capacity is provided by Well 01, which is 550 gpm

Table 2 – Average Day, Maximum Day, and Peak Hour Demands

Year	Average Day Demand (gpm)	Maximum Day Demand (gpm)	Peak Hour Demand (gpm)
2020	9.4	20.8	31.1
2019	8.4	25.1	37.7
2018	7.5	16.2	24.3

Table 3 – Total Active Source Capacity

Source	Capacity (gpm)
Well 01	550
Total Source Capacity	290

The total source capacity of the Water System is estimated to be 550 gpm. The Water System has adequate source capacity to supply the average day, maximum day, and peak hour demands of 8.4 gpm, 25.1 gpm, and 37.7 gpm, respectively.

Water systems with fewer than 1,000 service connections shall have storage capacity equal to or greater than the maximum day demand (MDD). The Water System currently meets this requirement. The 65,000 gallon storage tank is equivalent to 43 hours of MDD.

According to California Waterworks Standards, community water systems using only groundwater shall have a minimum of two approved sources. Additionally, the system shall be capable of meeting MDD with the highest-capacity source offline. The Division recommends the Water System explore options for adding a source or consolidating with a nearby public drinking water system.

STORAGE & DISTRIBUTION

The Water System uses a 65,000 gallon bolted steel storage tank. The well pumps water directly to a 65,000 gallon steel storage tank. Water is called at 5.3 feet (low) and stops at 12.5 feet (high). The water from the storage tank is then sent to four 119-gallon

bladder tanks and three alternating 20-hp Grundfos booster pumps to pressurize the effluent of the tank. The purpose of the pressure tank and booster pumps is to maintain distribution system pressure between the range of 50 and 60 pounds per square inch (psi) after the storage tank. The distribution system is classified as a D1 system. The Water System must follow American Water Works Association (AWWA) standards when any repairs or line replacements are made. The distribution system is new (as of 2017) and primarily composed of 8-inch-high density polyethylene (HDPE) piping. The 2018 Lead Service Line Inventory in the Division's records showed 28 service connections with high density polyethylene (HDPE).

In the 2020 Sanitary Survey Report, the Water System was directed to submit an Operations Plan to the Division for review and approval. This directive remains outstanding and must be addressed by the Water System immediately. Please note, the Division does not establish new deadlines for past due items.

By May 31, 2020, The Water System must submit an Operations Plan to the Division for review and approval. Guidance for completing a Chlorination Operations Plan is in Attachment F.

TREATMENT FACILITIES

The Water System provides continuous chlorination to the water produced by Well 01. A 12.5% solution of sodium hypochlorite is injected directly into the discharge line of Well prior to entering the storage tank. The sodium hypochlorite solution is stored at the well site in a 120-gallon polyethylene tank. The chlorination equipment is activated upon startup of the well and consists of an Iwaki Model: EHE36E1-VC at Well 01. The Iwaki EHE36E1-VC chemical feed pump has a capacity of 8.5 gallons per hour (gph) at 105 psi. The chemical feed pump appears to be adequately sized and is not operating at the upper or lower dial limits. The Water System aims to maintain a chlorine residual of approximately 1.0 mg/L in the distribution system. The Water System must record chlorine residuals from the distribution system weekly and report the monthly chlorination report to the Division by the 10th day of the following month.

III. WATER QUALITY MONITORING

SOURCE MONITORING

For purposes of water quality monitoring, the Water System's source has been assigned a water quality monitoring schedule. The current water quality monitoring schedule and water quality monitoring results can also be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>. A summary report of the last source sample results and next due dates is included in Appendix B. Directions to access the monitoring schedules and monitoring results are included in Appendix D.

Bacteriological

Due to continuous chlorination, the untreated well water from Well 01 is required to be sampled monthly for total coliform bacteria at a sample tap located prior to the chlorine injection port. This is required in order to verify that the well is not producing water that contains coliform bacteria. A summary of the source bacteriological sample results is included in Attachment C.

General Mineral (GM), General Physical (GP) and Inorganic (IO) Chemicals

The Water System is required to monitor its active groundwater sources for general mineral, general physical, and inorganic chemical water quality every three years, except for nitrate which has an annual monitoring frequency.

The Water System last sampled Well 01 for GM, GP, and IO chemicals in March 2020. All GM, GP, and IO chemical monitoring results for Well 01 was below the respective MCLs. The next round of GM, GP, and IO chemical monitoring for Well 01 is due in 2023.

Nitrate

The Water System is required to monitor active groundwater sources for nitrate (as N) annually if monitoring data indicates nitrate concentrations of less than one-half the MCL of 10 mg/L and quarterly if the concentrations are greater than or equal to one-half the MCL. The nitrate result on February 10, 2022 from Well 01 was 3.1 mg/L. Nitrate is next due to be monitored in March 2023.

Volatile Organic Chemicals (VOCs)

The Water System monitors VOCs from Well 01 once during every three-year monitoring period. Well 01 was last sampled for VOCs in September 2021, during the 2020-2022 monitoring period, and the results were non-detect. The next round of VOC monitoring is due to be collected in the 2023-2025 monitoring period.

Synthetic Organic Chemicals (SOCs)

The Water System is required to sample for 1,2,3-trichloropropane (1,2,3-TCP), alachlor, atrazine, dibromochloropropane (DBCP), ethylene dibromide (EDB), and simazine once during every three-year monitoring period. Well 01 was last sampled for alachlor, atrazine, DBCP and EDB in June 2020, and for 1,2,3-TCP in August 2020. The sample results were all non-detect. The next round of SOC monitoring is due to be collected in the 2023-2025 monitoring period.

Radiological Monitoring

The initial radiological monitoring is based on the collection of four consecutive quarterly samples for gross alpha and radium-228. If the results from the first two quarters of initial monitoring are below the DLR, the final two quarters of initial monitoring may be waived. After initial monitoring is complete, no additional monitoring is required for radium-228. Subsequent monitoring frequencies for gross alpha are based on the results of the last sample collected. It should be noted that if the gross alpha result for any single sample is greater than 5 pCi/L, analysis for uranium in *that same sample* is required.

The Water System completed the initial radium-228 monitoring requirements from Well 01 in September 2019; all results were below the DLR. No further monitoring is required for radium 228.

The Water System has completed initial monitoring requirements for gross alpha from Well 01; the result was below the DLR. Wells 01 was last sampled for gross alpha in February 2022. The sample result was non-detect. Wells 01 is currently on a nine-year monitoring frequency for gross alpha. Therefore, the next gross alpha sample is scheduled to be collected from Well 01 in September 2031.

It is noted that monitoring for uranium, radium-226 and radium-228 may be triggered from *the same sample* as noted below. Triggered monitoring needs to be communicated to the laboratory on the chain of custody at the time the sample is submitted.

Triggered Monitoring:

Uranium (U):

If the gross alpha (GA) + $(0.84 * \text{Counting Error, CE})$ for any single sample is greater than 5 pCi/L, analysis for U in that same sample, is required.

Radium-226 and Radium-228:

If the $GA + (0.84 * CE) - U$ is greater than 5 pCi/L, analysis for radium-226 and radium-228 in that same sample, is required.

DISTRIBUTION SYSTEM MONITORING

Bacteriological Monitoring

Based on the population served and number of service connections, the Water System is required to collect at least one routine bacteriological sample each month from the distribution system. The sample must be analyzed for total coliform bacteria with results sent to the Division by the 10th day of the following month. Additionally, bacteriological samples should be collected in accordance with an approved Bacteriological Sample

Siting Plan (BSSP). Anytime the BSSP is updated, the Water System must submit the updated copy to the Division for review and approval.

In the 2017 Sanitary Survey Report, the Water System was directed to submit a Bacteriological Sample Siting Plan (BSSP) to the Division for review and approval. This directive remains outstanding and must be addressed by the Water System immediately. Please note, the Division does not establish new deadlines for past due items.

By December 31, 2017, the Water System must submit a Bacteriological Sample Siting Plan to the Division for review and approval. Appendix E contains guidelines for completing the BSSP in compliance with the RTCR and a template that should be used.

The Federal Groundwater Rule states that when a Water System receives a total coliform positive sample, all sources that were running at the time when the positive sample was collected must be sampled for *E.coli*. A summary of the distribution bacteriological sample results is included in Appendix C.

Lead and Copper Tap Sampling

The Water System is currently on reduced monitoring schedule for lead and copper tap monitoring, which consists of collecting five samples from the distribution system every three years. The 90th percentile for lead and copper should be less than the lead and copper action levels of 0.015 mg/L and 1.3 mg/L, respectively. Table 4 summarizes the lead and copper sample tap results.

Table 4 – Lead and Copper Sample Tap Results

Monitoring Period	Sample Date	No. of Samples	Lead 90 th Percentile Result (mg/L)	Copper 90 th Percentile Result (mg/L)
6M1ST-2018	6/8/2018	10	0	0
6M2ND-2018	11/2/2018	10	0	0
YR2019	7/5/2019	10	0	0
YR2020	8/14/2020	5	0	0.0035
YR2021	8/6/2021	5	0	0

The Water System last collected five tap samples in August 2021, as presented in Table 4 and submitted the corresponding Lead and Copper Tap Sample Results Reporting Form. Samples for the current 3Y2022-2024 monitoring period must be collected no later than September 30, 2024.

It should be noted that all future lead and copper monitoring results must be submitted to the Division electronically via the Lab-To-State (LTS) Portal. The results may only be submitted through the LTS Portal by an Environmental Laboratory Accreditation Program (ELAP) accredited laboratory. A list of LTS registered laboratories can be found at:

http://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/lts_portal_info.shtml

The Water System must complete and submit a Lead and Copper Tap Sample Results Reporting Form with all subsequent lead and copper monitoring results. A Lead and Copper Tap Sample Results Reporting Form is included in Appendix F. It is noted that lead and copper tap sampling must be conducted between June 1st and September 30th.

Lead Service Line Inventory and Replacement

The Water System submitted a lead service line inventory on August 1, 2018 showing 28 high density polyethylene (HDPE) service lines and no lead service lines or lead fittings.

Asbestos Pipe Distribution System Monitoring

Regulation requires monitoring of systems vulnerable to asbestos contamination. The Water System indicated in the Lead Service Line Inventory that the distribution system is composed primarily of high-density polyethylene (HDPE) and that no asbestos-containing cement piping is in the distribution system.

IV. OPERATIONS AND MAINTENANCE

Operator Certification

The Water System's distribution system is classified as a D1 distribution system and requires a certified distribution system operator with a minimum D1 certification. The Water System meets the Division's requirement. Mr. Jose Padilla maintains a D1 certification (Certification No. 27640). Per Title 22, Section 63770, California Code of Regulations water systems shall utilize only certified distribution operators to make decisions addressing the following operational activities:

- 1) Install, tap, re-line, disinfect, test and connect water mains and appurtenances.
- 2) Shutdown, repair, disinfect and test broken water mains.
- 3) Oversee the flushing, cleaning, and pigging of existing water mains.
- 4) Pull, reset, rehabilitate, disinfect and test domestic water wells.
- 5) Stand-by emergency response duties for after-hours distribution system operational emergencies.
- 6) Drain, clean, disinfect, and maintain distribution reservoirs.

The Water System shall utilize either certified distribution operators or treatment operators that have been trained to make decisions addressing the following operational activities:

- 1) Operate pumps and related flow and pressure control and storage facilities manually or by using a system control and data acquisition (SCADA) system.
- 2) Maintain and/or adjust system flow and pressure requirements, control flows to meet consumer demands including fire flow demands and minimum pressure requirements.

The Water System shall utilize either certified distribution operators or treatment operators to make decisions addressing the following operational activities:

- 1) Determine and control proper chemical dosage rates for wellhead disinfection and distribution residual maintenance.
- 2) Investigate water quality problems in the distribution system.

Cross Connection Control

The Water System is required to maintain a Cross Connection Control Program which shall include the following elements (as applied from Title 17, California Code of Regulations, Section 7584):

- 1) The conducting of surveys to identify water user premises or locations where cross connections are likely to occur,
- 2) The provisions of backflow protection by the water user at the user's connection or within the user's premises or both,
- 3) The provision of at least one person trained in cross connection control to carry out the cross-connection program,
- 4) The establishment of a procedure or system for annual testing of backflow preventers, and
- 5) The maintenance of records of locations, tests, and repairs of backflow preventers.

Backflow Prevention Device Testing

Regulations require all backflow prevention devices to be tested annually. Copies of the testing records must be kept on file with the Water System for a minimum of three years.

In the 2020 Sanitary Survey Report, the Water System was directed to conduct a cross connection control survey using a certified cross connection control specialist or submit a time and schedule for having one completed. This directive remains outstanding and

must be addressed by the Water System immediately. Please note, the Division does not establish new deadlines for past due items.

By May 31, 2020, the Water System must conduct a cross connection control survey using a certified cross connection control specialist or submit a time and schedule for having one completed.

Complaint Records

The Water System must keep records of all complaints received and actions taken to correct the problems related to complaints. Records of any complaints must be kept on file by the water system for a minimum of three years. In the 2020 Electronic Annual Report (EAR), the Water System reported zero (0) complaints from customers.

Emergency Notification Plan (ENP)

The Water System submitted an Emergency Notification Plan (ENP) to the Tulare District on March 2019. Included in the ENP is a plan that outlines the notification methods that will be used in case of an emergency. These methods include door-to-door contact, posted notifications, and telephone calls.

Consumer Confidence Report (CCR)

The Water System is required to complete a CCR annually and provide a copy to all residents by July 1st of each year. In addition, a signed certification form is required to be submitted to the Division by October 1 of each year that certifies the report has been distributed to customers. A copy of the 2020 CCR was submitted to the Division on June 25, 2021.

Electronic Annual Report (EAR)

All public water systems are required to provide updated water system information to the Division annually. The technical information included in the report is required per Section 116530 of the California Health and Safety Code. The 2020 Electronic Annual Report was submitted to the Division on June 23, 2021.

V. SMALL WATER SYSTEM RESILIENCY AND PREPAREDNESS

The effects of climate change on community water system (CWS) facilities and operations is a concern and priority of the State Water Resources Control Board (SWRCB), which is documented by the SWRCB in its Comprehensive Climate Change Resolution adopted in March 2017. DDW is reviewing each water system preparedness for climate change with the goal to increase awareness and familiarization to the effects of climate change to facilities and operations, encourage the use of EPA's Climate Resilience Evaluation and Awareness Tool (CREAT) or equivalent, and to document the

Water System's efforts related to current threats that may also provide mitigation to climate change impacts.

The Water System indicated that they **were not** aware of the CREAT tool developed by USEPA for identifying climate change vulnerabilities. The Water System has not used CREAT (or similar tool) to identify vulnerabilities to the water system sources and facilities. The SWRCB strongly encourages utilities to evaluate climate change vulnerabilities using tools such as CREAT and engaging in a conversation both within your water system organization and with customers on how to plan and prepare for being resilient to provide clean and safe water reliably and adequately under all current and future conditions.

Fire ---

- A defensible space of 100 feet (*California Public Resources Code, 4291*) is maintained around all sources and structures managed by the Water System. **Yes.**

Flooding ---

- Are any of the drinking water facilities vulnerable to flooding? **No**

Backup Power ---

- Is backup power available, for example, through portable or permanent power generators? **Yes**
 - Backup power connection point is provided at Well 01.
- If liquid fuel is used, is it properly contained and stored away from the source? **N/A. No generator on site at the moment.**

Drought ---

- Is the Water System prepared for drought related shortages or outages? (interties, backup supply, increased storage) **Yes**

Degrading Source Water Quality –

- Has source water quality degraded over time, or specifically during the most recent drought? **No**

VI. APPRAISAL OF SANITARY HAZARDS & PUBLIC HEALTH SAFEGUARDS

The Monson Water System water system relies on Well 01 to supply the demands of the system. The system has storage that meets MDD requirements in the event of an emergency. Monson Water System has no interconnection with any nearby water systems. However, arrangements are being made to connect Sultana CSD to Monson Water System nearby to increase reliability. The Water System has not implemented a cross-connection control program. The Water System must prioritize implementing the cross-connection control program and testing the backflow prevention devices annually.

All laboratory chemical analytical results must be submitted to the Division via electronic data transfer (EDT) with the correct primary station code (PS Code). The current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>.

Competent supervision is provided over the operational and maintenance practices of the Water System.

VI. CONCLUSIONS AND RECOMMENDATIONS

Issuance of a Domestic Water Supply Permit Amendment by the State Water Resources Control Board, Division of Drinking Water to Monson Water System for the operation of the Monson Water System water system is recommended subject to the following provisions:

1. The Monson Water System shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted there under.
2. The only approved sources of domestic water supply for the Monson Water System are as follows:

Source	PS Code	Status
Well 01	CA5403212_001_001	Active

3. The only approved treatment for Monson Water System is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution.
4. No other sources or treatment (as described in provisions No. 2 and 3 above) shall be used by Monson Water System and no changes, additions, or modifications shall be made to the source unless an amended water permit has first been obtained from the Division.
5. All personnel who operate distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Monson Water System is classified as a D1 distribution system and shall be operated by, at minimum, a D1 certified distribution operator.
6. The Monson Water System shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The Water System shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.

7. The Monson Water System shall submit an Electronic Annual Report (EAR) each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
8. The Monson Water System shall record production data from each active source at least monthly.
9. The Monson Water System shall collect monthly raw water samples from the source for analyses of total coliform and fecal coliform or *E. coli* bacteria. The coliform test shall be performed using a density analytical method and the results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following
10. The Monson Water System shall monitor for coliform bacteria in the distribution system at least monthly and in accordance with an approved Bacteriological Sample Siting Plan (BSSP). The Division shall be notified immediately if any distribution system or source sample shows the presence of *E. coli* bacteria or if more than one bacteriological sample shows the presence of coliform bacteria during a single month.
11. The Monson Water System shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The Monson Water System shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.
12. The Monson Water System shall conduct Stage 2 Disinfection Byproduct (DBP) monitoring from the sample site listed below. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Code:

ST2 Monitoring Site	PS Code
ST2S1 - 13920 Ave 418	CA5403212_DST_900

13. The Monson Water System shall submit a monthly chlorination log to the Division by the 10th day of the following month.
14. The Monson Water System shall operate the continuous chlorination treatment facility in accordance with a Division-approved Chlorination Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval prior to implementation.

In addition to the aforementioned permit provisions, and after evaluation of the existing water supply facilities and completion of a subsequent file review, the Division finds that the items below need to be addressed by the Water System:

The Water System has two directives that were included in the 2017 Sanitary Survey Report, and two directives that were included in the 2020 Sanitary Survey, that are past due. The Division does not establish new deadlines for the directives and the Water System is required to address the directives as soon as possible:

1. By **January 31, 2018**, the Water System must complete a Possible Contaminating Activity (PCA) checklist for Well 01 and submit it to the Division.
2. By **May 31, 2020**, The Water System must submit an Operations Plan to the Division for review and approval.
3. By **December 31, 2017**, the Water System must submit a Bacteriological Sample Siting Plan to the Division for review and approval.
4. By **May 31, 2020**, the Water System must conduct a cross connection control survey using a certified cross connection control specialist or submit a time and schedule for having one completed.

Appendices

Appendix A: System Map & Photographs

Appendix B: Last Sample Next Due Summary Report

Appendix C: Distribution System Bacteriological Sample Results Summary

Appendix D: Instructions for Accessing Individual Water System's Water Monitoring Schedule and Water Quality Data


Appendix E: Guidelines for Completing BSSP for Small Water Systems and Template

Appendix F: Lead and Copper Tap Sample Results Reporting Form

Appendix A:
Location Map & Photo Index

Monson Water System

5403212



Appendix A Monson Water System Photographs

Well 01

Pump Type: Submersible

Pump Make and Model: Unknown

Pump Size: 50 hp

Capacity: 550 gpm



65,000 Gallon Storage Tank

Steel storage tank, bottom in/out configuration. Located at the Well 01 site.



Appendix A Monson Water System Photographs

Continuous Chlorination

120-gallon 12.5% sodium hypochlorite solution. Iwaki EHE36E1-VC chemical feed pump. Injected into discharge of Well 01 prior to storage tank.



Booster Station

Three Grundfos 20-hp booster pumps and four 119 gallon pressure tanks



Appendix B:
Last Sample & Next Due Date Summary Reports

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: MONSON WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: NCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MONTHS	MOD	NEXT SAMPLE DUE	NOTES
CA5403212_001_001		MONSON WATER SYSTEM					WELL 01 - RAW								
	GP	SECONDARY/GP													
		1928 ALKALINITY, BICARBONATE		0.000	140.000	0.000	MG/L	-----	----	3/6/2020	2	36		2023/03	
		1919 CALCIUM		0.000	24.000	0.000	MG/L	-----	----	3/6/2020	3	36		2023/03	
		1929 ALKALINITY, CARBONATE	<	10.000	0.000	0.000	MG/L	-----	----	3/6/2020	2	36		2023/03	
		1017 CHLORIDE		0.000	21.000	0.000	MG/L	500	----	3/6/2020	2	36		2023/03	
		1905 COLOR		0.000	5.000	0.000	UNITS	15	----	3/6/2020	2	36		2023/03	
		1022 COPPER, FREE	<	50.000	0.000	0.000	UG/L	1000	50	3/6/2020	2	36		2023/03	
		2905 FOAMING AGENTS (SURFACTANTS)	<	0.100	0.000	0.000	MG/L	0.5	----	3/6/2020	2	36		2023/03	
		1915 HARDNESS, TOTAL (AS CaCO3)		0.000	88.700	0.000	MG/L	-----	----	3/6/2020	2	36		2023/03	
		1021 HYDROXIDE AS CALCIUM CARBONATE	<	10.000	0.000	0.000	MG/L	-----	----	3/6/2020	2	36		2023/03	
		1028 IRON	<	100.000	0.000	0.000	UG/L	300	100	3/6/2020	2	36		2023/03	
		1031 MAGNESIUM		0.000	7.000	0.000	MG/L	-----	----	3/6/2020	3	36		2023/03	
		1032 MANGANESE	<	20.000	0.000	0.000	UG/L	50	20	3/6/2020	2	36		2023/03	
		1920 ODOR	<	1.000	0.000	0.000	TON	3	1	3/6/2020	2	36		2023/03	
		1925 PH		0.000	8.100	0.000		-----	----	3/6/2020	2	36		2023/03	
		1050 SILVER	<	10.000	0.000	0.000	UG/L	100	10	3/6/2020	2	36		2023/03	
		1052 SODIUM		0.000	32.000	0.000	MG/L	-----	----	3/6/2020	2	36		2023/03	
		1064 CONDUCTIVITY @ 25 C UMHO/CM		0.000	350.000	0.000	US	1600	----	3/6/2020	2	36		2023/03	
		1055 SULFATE		0.500	4.500	0.000	MG/L	500	0.5	3/6/2020	2	36		2023/03	
		1930 TDS		0.000	230.000	0.000	MG/L	1000	----	3/6/2020	2	36		2023/03	
		0100 TURBIDITY		0.100	1.300	0.000	NTU	5	0.1	3/6/2020	2	36		2023/03	
		1095 ZINC	<	50.000	0.000	0.000	UG/L	5000	50	3/6/2020	2	36		2023/03	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: MONSON WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: NCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5403212_001_001	IO	INORGANIC													
		1002	ALUMINUM	<	50.000	0.000	UG/L	1000	50	3/6/2020	2	36		2023/03	
		1074	ANTIMONY, TOTAL	<	6.000	0.000	UG/L	6	6	3/6/2020	2	36		2023/03	
		1005	ARSENIC		2.000	3.000	UG/L	10	2	3/6/2020	2	36		2023/03	
		1010	BARIUM	<	100.000	0.000	UG/L	1000	100	3/6/2020	2	36		2023/03	
		1075	BERYLLIUM, TOTAL	<	1.000	0.000	UG/L	4	1	3/6/2020	2	36		2023/03	
		1015	CADMIUM	<	1.000	0.000	UG/L	5	1	3/6/2020	2	36		2023/03	
		1020	CHROMIUM	<	10.000	0.000	UG/L	50	10	3/6/2020	2	36		2023/03	
		1025	FLUORIDE		0.100	0.200	MG/L	2	0.1	3/6/2020	2	36		2023/03	
		1035	MERCURY	<	1.000	0.000	UG/L	2	1	3/6/2020	2	36		2023/03	
		1036	NICKEL	<	10.000	0.000	UG/L	100	10	3/6/2020	2	36		2023/03	
		1039	PERCHLORATE	<	2.000	0.000	UG/L	6	2	3/7/2022	7	36		2025/03	
		1045	SELENIUM	<	5.000	0.000	UG/L	50	5	3/6/2020	2	36		2023/03	
		1085	THALLIUM, TOTAL	<	1.000	0.000	UG/L	2	1	3/6/2020	2	36		2023/03	
	NI	NITRATE/NITRITE													
		1040	NITRATE		0.400	3.100	mg/L	10	0.4	2/10/2022	4	12		2023/02	
		1041	NITRITE	<	0.400	0.000	mg/L	1	0.4	9/10/2020	2	36		2023/09	
	RA	RADIOLOGICAL													
		4109	GROSS ALPHA PARTICLE ACTIVITY	<	1.230	0.000	PCI/L	15	3	2/10/2022	9	72	Interval	2028/02	
	S1	REGULATED VOC													
		2981	1,1,1-TRICHLOROETHANE	<	0.500	0.000	UG/L	200	0.5	9/28/2021	8	12	Interval	2022/09	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: MONSON WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: NCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5403212_001_001	S1	REGULATED VOC													
		2988 1,1,2,2-TETRACHLOROETHANE	<	0.500	0.000	0.000	UG/L	1	0.5	9/28/2021	8	12	Interval	2022/09	
		2985 1,1,2-TRICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	9/28/2021	8	12	Interval	2022/09	
		2978 1,1-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	9/28/2021	8	12	Interval	2022/09	
		2977 1,1-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	9/28/2021	8	12	Interval	2022/09	
		2378 1,2,4-TRICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	9/28/2021	8	12	Interval	2022/09	
		2968 O-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	600	0.5	9/28/2021	8	12	Interval	2022/09	
		2980 1,2-DICHLOROETHANE	<	0.500	0.000	0.000	UG/L	0.5	0.5	9/28/2021	8	12	Interval	2022/09	
		2983 1,2-DICHLOROPROPANE	<	0.500	0.000	0.000	UG/L	5	0.5	9/28/2021	8	12	Interval	2022/09	
		2413 1,3-DICHLOROPROPENE	<	0.500	0.000	0.000	UG/L	0.5	0.5	9/28/2021	8	12	Interval	2022/09	
		2969 P-DICHLOROBENZENE	<	0.500	0.000	0.000	UG/L	5	0.5	9/28/2021	8	12	Interval	2022/09	
		2990 BENZENE	<	0.500	0.000	0.000	UG/L	1	0.5	9/28/2021	8	12	Interval	2022/09	
		2982 CARBON TETRACHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	9/28/2021	8	12	Interval	2022/09	
		2380 CIS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	6	0.5	9/28/2021	8	12	Interval	2022/09	
		2964 DICHLOROMETHANE	<	0.500	0.000	0.000	UG/L	5	0.5	9/28/2021	8	12	Interval	2022/09	
		2992 ETHYLBENZENE	<	0.500	0.000	0.000	UG/L	300	0.5	9/28/2021	8	12	Interval	2022/09	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: MONSON WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: NCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
CA5403212_001_001	S1	2251 METHYL TERT-BUTYL ETHER	<	3.000	0.000	0.000	UG/L	13	3	9/28/2021	8	12	Interval	2022/09	
		2989 CHLOROBENZENE	<	0.500	0.000	0.000	UG/L	70	0.5	9/28/2021	8	12	Interval	2022/09	
		2996 STYRENE	<	0.500	0.000	0.000	UG/L	100	0.5	9/28/2021	8	12	Interval	2022/09	
		2987 TETRACHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	9/28/2021	8	12	Interval	2022/09	
		2991 TOLUENE	<	0.500	0.000	0.000	UG/L	150	0.5	9/28/2021	8	12	Interval	2022/09	
		2979 TRANS-1,2-DICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	10	0.5	9/28/2021	8	12	Interval	2022/09	
		2984 TRICHLOROETHYLENE	<	0.500	0.000	0.000	UG/L	5	0.5	9/28/2021	8	12	Interval	2022/09	
		2218 TRICHLOROFLUOROMETHANE	<	5.000	0.000	0.000	UG/L	150	5	9/28/2021	8	12	Interval	2022/09	
		2904 TRICHLOROTRIFLUOROETHANE	<	10.000	0.000	0.000	UG/L	1200	10	9/28/2021	8	12	Interval	2022/09	
		2976 VINYL CHLORIDE	<	0.500	0.000	0.000	UG/L	0.5	0.5	9/28/2021	8	12	Interval	2022/09	
		2955 XYLENES, TOTAL	<	0.500	0.000	0.000	UG/L	1750	0.5	9/28/2021	8	12	Interval	2022/09	
	S2	REGULATED SOC													
		2414 1,2,3-TRICHLOROPROPANE	<	0.000	0.000	0.000	UG/L	0.005	0.005	8/13/2020	11	36	Interval	2023/08	
		2051 LASSO (ALACHLOR)	<	1.000	0.000	0.000	UG/L	2	1	6/16/2020	7	36	Interval	2023/06	
		2050 ATRAZINE	<	0.500	0.000	0.000	UG/L	1	0.5	6/16/2020	7	36	Interval	2023/06	
		2931 1,2-DIBROMO-3-CHLOROPROPANE	<	0.000	0.000	0.000	UG/L	0.2	0.01	6/16/2020	7	36	Interval	2023/06	
		2946 ETHYLENE DIBROMIDE	<	0.000	0.000	0.000	UG/L	0.05	0.02	6/16/2020	7	36	Interval	2023/06	
		2037 SIMAZINE	<	1.000	0.000	0.000	UG/L	4	1	6/16/2020	7	36	Interval	2023/06	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: MONSON WATER SYSTEM

COUNTY: TULARE

Sample Point: ST2S1 - 10678 SIMPSON DR

CLASS: DBPT

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LESS THAN	REPORTING LEVEL	LAST RESULT	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MONTHS	MOD	NEXT SAMPLE DUE	NOTES
CA5403212_ DST_900		MONSON WATER SYSTEM					ST2S1 - 10678 SIMPSON DR								
	DBP	DISINFECTION BYPRODUCTS													
		2943 BROMODICHLOROMETHANE	<	1.000	0.000	0.000	UG/L	-----	1	7/26/2019	1	36		2022/07	
		2942 BROMOFORM	<	1.000	0.000	0.000	UG/L	-----	1	7/26/2019	1	36		2022/07	
		2941 CHLOROFORM	<	1.000	0.000	0.000	UG/L	-----	1	7/26/2019	1	36		2022/07	
		2454 DIBROMOACETIC ACID	<	1.000	0.000	0.000	UG/L	-----	1	7/26/2019	1	36		2022/07	
		2944 DIBROMOCHLOROMETHANE	<	1.000	0.000	0.000	UG/L	-----	1	7/26/2019	1	36		2022/07	
		2451 DICHLOROACETIC ACID	<	1.000	0.000	0.000	UG/L	-----	1	7/26/2019	1	36		2022/07	
		2456 TOTAL HALOACETIC ACIDS (HAA5)	<	0.000	0.000	0.000	UG/L	60	-----	7/26/2019	1	36		2022/07	
		2453 MONOBROMOACETIC ACID	<	1.000	0.000	0.000	UG/L	-----	1	7/26/2019	1	36		2022/07	
		2450 MONOCHLOROACETIC ACID	<	2.000	0.000	0.000	UG/L	-----	2	7/26/2019	1	36		2022/07	
		2950 TTHM	<	0.000	0.000	0.000	UG/L	80	-----	7/26/2019	1	36		2022/07	
		2452 TRICHLOROACETIC ACID	<	1.000	0.000	0.000	UG/L	-----	1	7/26/2019	1	36		2022/07	

Appendix C:
Distribution System Bacteriological Sample Results Summary

Bacteriological Distribution Monitoring Report

5403212 Monson Water System

Distribution System Freq: 1/M

Sample Date	Location	T Coli	E Coli	F Coli	HPC	Type	Cl2	Cl2 Avg	Viol. Type	GWR Satisfied?	Comments
4/25/2022	Hyd #3	A	A			Routine	0.29				
3/7/2022	Hyd #3	A	A			Routine	0.83				
2/8/2022	Hyd #3	A	A			Routine	0.37				
1/7/2022	Monson Hyd #3	A	A			Routine	0.19				
12/27/2021	Monson Hyd #3	A	A			Routine	1.17				
11/19/2021	Monson Hyd #3	A	A			Routine	0.72				
10/18/2021	Monson Hyd #3	A	A			Routine	0.55				
9/28/2021	Monson Hyd #3	A	A			Routine	0.19				
8/23/2021	Monson Hyd #3	A	A			Routine	0.35				
7/26/2021	Monson Hyd #3	A	A			Routine	0.39				
6/21/2021	Hyd #3	A	A			Routine	0.23				
5/24/2021	Hyd #3	A	A			Routine	0.19				
4/15/2021	Hyd#3	A	A			Routine	0.13				
3/15/2021	Hyd #3	A	A			Routine	0.56				
2/18/2021	Hyd #3	A	A			Routine	0.41				
1/19/2021	Hyd #3	A	A			Routine	0.69				
12/21/2020	Monson Hyd #3	A	A			Routine	0.7				
11/3/2020	Monson Hyd #3	A	A			Routine	0.74				
10/26/2020	Hyd #3	A	A			Routine	0.39				
9/10/2020	Hyd #3	A	A			Routine	0.25				
8/13/2020	Hyd #3	A	A			Routine	0.19				
7/15/2020	Hyd #3	A	A			Routine	0.19				
6/16/2020	Hyd #3	A	A			Routine	0.41				
5/14/2020	Hyd #3	A	A			Routine	0.31				
4/22/2020	Hyd #3	A	A			Routine	0.21				
3/6/2020	Hyd #3	A	A			Routine	0.64				
2/14/2020	Hyd #3	A	A			Routine	0.37				
1/13/2020	Hyd #3	A	A			Routine	0.35				

Violation Key

MCL	Exceeds the maximum contaminant level	MR5	Incorrect number of repeat samples as follow-up to a positive sample
MR1	No monthly sample for the report month	MR6	No source sample
MR2	No quarterly sample for the report month	MR7	No summary report submitted
MR3	Incorrect number of routine samples for the report month	MR8	Other comments and/or info
MR4	Did not collect 5 routine samples for previous month's positive sample	MR9	Cl2 not reported

Source Bacteriological Monitoring Report

5403212 Monson Water System

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
4/25/2022	12:15	Well 01	Well	QTray	<1.0	<1.0				
3/7/2022	12:45	Well 01	Well	QTray	<1.0	<1.0				
2/8/2022	10:50	Well 01	Well	QTray	<1.0	<1.0				
1/7/2022	11:35	Well 01	Well	Qtray	<1.0	<1.0				
12/27/2021	13:00	Well 01	Well	Qtray	<1.0	<1.0				
11/19/2021	13:45	Well 01	Well	Qtray	<1.0	<1.0				
10/18/2021	10:15	Well 01 - Raw	Well	Qtray	<1.0	<1.0				
9/28/2021	11:15	Well 01	Well	Qtray	<1.0	<1.0				
8/23/2021	14:00	Well 01	Well	Qtray	<1.0	<1.0				
7/26/2021	12:50	Well 01	Well	Qtray	<1.0	<1.0				
6/21/2021	14:05	Well 01	Well	QTray	<1.0	<1.0				
5/24/2021	12:50	Well 01	Well	Qtray	<1.0	<1.0				
4/15/2021	12:40	Well 01	Well	Qtray	<1.0	<1.0				
3/15/2021	13:20	Well 01	Well	Qtray	<1.0	<1.0				
2/18/2021	14:00	Well 01	Well	Qtray	<1.0	<1.0				
1/19/2021	12:55	Well 01	Well	QTray	<1.0	<1.0				
12/21/2020	12:15	Well 01	Well	Qtray	<1	<1				
11/3/2020	15:25	Well 01	Well	Qtray	<1.0	<1.0				
10/26/2020	13:30	Well 01	Well	Qtray	<1.0	<1.0				
9/10/2020	15:40	Well 01	Well	Qtray	<1.0	<1.0				
8/13/2020	14:35	Well 01	Well	Qtray	<1.0	<1.0				
7/15/2020	14:35	Well 01	Well	Qtray	<1.0	<1.0				
6/16/2020	13:30	Well 01	Well	Qtray	2	<1.0				
5/14/2020	14:00	Well 01	Well	QTray	28.8	<1.0				
4/22/2020	13:00	Well 01	Well	QTray	<1.0	<1.0				
3/6/2020	13:20	Well 01	Well	QTray	<1.0	<1.0				
2/14/2020	11:05	Well 01	Well	QTray	<1.0	<1.0				
1/13/2020	14:20	Well 01	Well	QTray	<1.0	<1.0				

Appendix D:
Instructions for Accessing Individual Water System's Water Monitoring
Schedule and Water Quality Data

How To Access Individual System's Drinking Water Monitoring Schedule & Water Quality Data

1. Place the following link in the internet address bar:
<https://sdwis.waterboards.ca.gov/PDWW/>
2. Enter your Water System No. and select "Search For Water Systems"

SDWIS Version 3.21

California Public Water Supply Systems Search Parameters

Water System No.

Water System Name

Principal County Served

Water System Type

Water System Status

Primary Source Water Type

[Click Here for the County Map of CALIFORNIA](#)

3. Click on your Water System No. (Link in blue text).

Drinking Water Division

Water Systems

Hide/show columns: [Water System No.](#) | [Water System Name](#) | [Type](#) | [Status](#) | [Principal County Served](#) | [Primary Source Water Type](#)

Display records Search:

Water System No.	Water System Name	Type	Status	Principal County Served	Primary Source Water Type
CA5403043	YETTEM WATER SYSTEM	C	A	TULARE	GW

Showing 1 to 1 of 1 entries (filtered from 8,332 total entries) Previous Next

4. On the left side of the screen, select **Monitoring Schedules** for source monitoring schedule (last sample and next due dates) or **Monitoring Results** for water quality results.

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

Glossary

Contact Info

CA Drinking Water Watch

Water System Details

Water System No. : CA5403043	Federal Type : C
Water System Name : YETTEM WATER SYSTEM	State Type : C
Principal County Served : TULARE	Primary Source : GW
Status : A	Activity Date : 04-28-2014

Water System Contacts

Type	Address	Phone	Email - Web Address
Administrative Contact	5961 S. MOONEY BLVD. VISALIA, CA 93277	Business 559-624-7191	
Physical Location Contact	CA5403043-YETTEM WATER SYSTEM		

Division of Drinking Water District / County Health Dept. Info

Name	Phone	Email	Address
DISTRICT 24 - TULARE	559-447-3300	dwpsdist24@waterboards.ca.gov	265 W. BULLARD AVE., SUITE 101 FRESNO CA 93704

Annual Operating Periods & Population Served

Start Month	Start Day	End Month	End Day	Population Type	Population Served
1	1	12	31	R	350

Service Connections

Type	Count	Meter Type	Meter Size Measure
CB	64	UN	0

Sources of Water

Name	Type Code	Status
WELL 01 - PRE NO3 BLEND	WL	A
WELL 02 - PRE NO3 BLEND	WL	A

Service Areas

Code	Name
R	RESIDENTIAL AREA

Water Purchases

Seller Water System No.	Water System Name	Seller Facility Type	Seller State Asgn ID No.	Buyer Facility Type	Buyer State Asgn ID No.
-------------------------	-------------------	----------------------	--------------------------	---------------------	-------------------------

5. Select Sampling Point corresponding to the source (Link in blue text and is a number).

5A. Monitoring Schedules

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

[Glossary](#)

[Contact Info](#)

CA Drinking Water Watch

Monitoring Schedules

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

The Division of Drinking Water's (DDW's) drinking water quality monitoring schedules identify upcoming required testing of drinking water for water systems in California. These documents should not be used for determining whether water systems are in compliance with monitoring requirements. The purpose for providing these monitoring schedules is to allow water systems to verify that their sampling and analyses have been incorporated into the DDW database and to identify upcoming required monitoring/sampling events.

Notes for Water Systems:

1. The monitoring notification documents should be considered "draft," in that they will change with subsequent updates, and as monitoring data are submitted, or as monitoring schedules are revised.
2. The monitoring notification documents are derived from the DDW Water Quality database and from schedules maintained by DDW districts.
3. If your upcoming monitoring or your data identified as "DUE" are not in agreement with this document, or if you have been advised of any increased monitoring that is not reflected in the report for a particular source, please contact your [District Engineer or LPA representative](#). For a map of the districts, please [click here](#).
4. If your notification report for a source is blank, this does not necessarily indicate compliance with all monitoring requirements.
5. These notification reports may not reflect compliance with initial monitoring for newly regulated constituents, or constituents that require special monitoring frequencies. For example, the DDW database is unable to accurately forecast the vulnerable non-volatile synthetic organic chemical (SOC) frequency for large water systems serving over 3,300 people of 2 quarters every 3 years.
6. Some Nitrate (as N) results under storet code 00618, will have a result of 'N/A' which stands for 'Not Applicable.' This stems from the change in regulation requiring that all nitrate sampling be reported as Nitrate (as N) starting January 1, 2016. Prior nitrate sampling was reported as Nitrate (as NO3). With this change in nitrate reporting requirements, the monitoring schedules have captured the last date of Nitrate (as NO3) sampling and applied it to Nitrate (as N) in determining the next due date [unless there have been Nitrate (as N) samples collected]. The Nitrate (as NO3) result, however, does not carry over to Nitrate (as N) which is why there may be a notation in the 'Constituent Identification' column to reference storet code 71850 for the last nitrate result. In these instances, the 'Constituent Identification' column will say, 'NITRATE (as N) - [see 71850].' Any questions should be referred to your District Engineer.

[Monitoring Schedules for All Sampling Points](#)

Monitoring schedule for all sampling points

Click to view report. Once the report is shown, click on the Export icon on the report header to download.

Monitoring Schedule for Individual Sampling Points

Click on a sampling point number to view the monitoring schedule for the sampling point.
[Click here to bring back the list of sampling points.](#)

Sampling Point	Location	Type
900	ST2S1-14395 AVE 384	
LCR		DS
003	WELL 01 & 02 - NO3 BLEND TANK	
001	WELL 01 - PRE NO3 BLEND	RW
002	WELL 02 - PRE NO3 BLEND	RW

Monitoring schedule for specific sampling points

NOTE: Any *past due* monitoring will have "DUE NOW" in the far-right column. Please schedule this monitoring as soon as possible.

5B. Monitoring Results

Links
[Water System Details](#)
[Water System Facilities](#)
[Monitoring Schedules](#)
[Monitoring Results](#)
[Monitoring Results By Analyte](#)
[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)
[Site Visits](#)
[Consumer Confidence Reports](#)

- 2017
- 2016
- 2015
- 2014

Return Links
[Water System Search](#)
[County Map](#)
Glossary
Contact Info

CA Drinking Water Watch

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

Monitoring Results for Individual Sampling Points

Click on a PS Code to view/download the monitoring results for the sampling point.

Water System Sampling Points					
PS Code	Facility ID	Facility Name	Description	Type Code	Source Class
5403043-001	001	WELL 01 - PRE NO3 BLEND	WELL 01 - PRE NO3 BLEND	RW	DCSGA
5403043-002	002	WELL 02 - PRE NO3 BLEND	WELL 02 - PRE NO3 BLEND	RW	DCSGA
5403043-003	003	WELL 01 & 02 - NO3 BLEND TANK	WELL 01 & 02 - NO3 BLEND TANK		OTHR
5403043-900	DST	DISTRIBUTION SYSTEM	DISTRIBUTION SYSTEM		DBPT
5403043-LCR	DST	DISTRIBUTION SYSTEM		DS	

6. Please contact the Tulare District Office at (559) 447-3300 or DWPDIST24@waterboards.ca.gov if you have any questions.

Appendix E:
Guidelines for Completing BSSP for Small Water Systems and Template

Division of Drinking Water Tulare District

GUIDELINES FOR COMPLETING THE BACTERIOLOGICAL SAMPLE SITING PLAN FOR SMALL WATER SYSTEMS

The total coliform regulation requires the water supplier to submit a bacteriological sample siting plan to the Division of Drinking Water (Division), District Office for review and approval. The locations where samples are to be collected must be written down and formally approved by the District Office. These guidelines and Attachment 1, "Bacteriological Sample Siting Plan" Form, are to assist you in complying with these requirements.

To comply with the requirements for submitting a Bacteriological Sample Siting Plan, two (2) items must be submitted to the District Office at this time.

1. A system map, street map, or system schematic showing all sampling locations must be submitted. The map can be prepared by any system representative. It does not have to be prepared by an engineer. The following are also to be shown on the map:
 - Water Sources (i.e., well or spring)
 - Treatment Facilities (i.e., chlorination)
 - Storage Tanks
 - Pressure Reducing Stations
 - Booster Stations
 - Pressure Zones
 - Dead Ends
 - Service Area Boundaries
 - Routine Sample Sites
 - Repeat Sample Sites
 - Special Sample Sites
2. Complete Attachment 1, the "Bacteriological Sample Siting Plan" form, and **return the system map and form to the District Office for review and approval.**

Once the Bacteriological Sample Siting Plan has been approved by the Division, copies should be provided to the person responsible for sample collection, the laboratory and the person responsible for reporting coliform-positive samples to the Division.

Selection of Sampling Sites

The routine sampling sites chosen must be representative of the water distribution system including all pressure zones, areas supplied by each water source and distribution reservoir.

Looped Systems: If your entire water distribution system is looped, then one routine sample point may be representative of your system, assuming valves are open.

Pressure Zones: You should only be concerned about sampling in different pressure zones if your water system serves different areas of varying elevations, for example in mountainous areas.

How many routine sampling sites are required?

The minimum number of samples for the water system shall be based on the known population served or the total number of service connections, whichever results in the greater number of samples, as shown in Table 64423-A. For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

Table 64423-A		
Minimum Number of Routine Total Coliform Samples Monthly Population Served¹	Service Connections	Minimum Number of Samples Per Month
25 to 1000	15 to 400	1
1,001 to 2,500	401 to 890	2
2,501 to 3,300	891 to 1,180	3
3,301 to 4,100	1,181 to 1,460	4
4,101 to 4,900	1,461 to 1,750	5
4,901 to 5,800	1,751 to 2,100	6
5,801 to 6,700	2,101 to 2,400	7
6,701 to 7,600	2,401 to 2,700	8
7,601 to 8,500	2,701 to 3,000	9
8,501 to 12,900	3,001 to 4,600	10
12,901 to 17,200	4,601 to 6,100	15
17,201 to 21,500	6,101 to 7,700	20
21,501 to 25,000	7,701 to 8,900	25
25,001 to 33,000	8,901 to 11,800	30
33,001 to 41,000	11,801 to 14,600	40
41,001 to 50,000	14,601 to 17,900	50
50,001 to 59,000	17,901 to 21,100	60
59,001 to 70,000	21,101 to 25,000	70

¹ For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

How many repeat sampling sites are required?

A repeat sample set consists of three samples to be collected from the following locations:

- One repeat sample from the same routine location.
- One repeat sample from an *upstream location* (within 5 connections of the routine site).
- One repeat sample from a *downstream location* (within 5 connections of the routine site).

Each routine sample site must have identified repeat sample sites.

Ground Water Rule Compliance: All active groundwater sources in operation at the time of the coliform-positive sample must also be sampled along with the repeat sample set.

What if the water system does not have enough locations to select the required number of routine and repeat sample sites?

If the water system does not have enough sample locations to identify the required routine and repeat sample sites, contact the District Office for further guidance.

Pointers for Sample Site Selection

- When selecting a routine sample site you should be able to select a site upstream and a site downstream for repeat sampling.
- Select a site where the water is used continuously all year round.
- Pick a site that is easily accessible, i.e., a fenced yard with a locked gate and vicious dog is not a good selection.
- When choosing a sampling tap you should consider these factors:
The sampling tap should be located in as clean an environment as possible. It should be protected from contamination by humans, animals, airborne materials or other sources of contamination.

If you choose an outside private tap, it should be one that is in frequent use, clean, and at least 1½ feet (18 inches) above the ground. The sample tap should discharge downward.

If you choose an inside tap, be sure that you are not sampling from drinking fountains; taps that have aerators or strainers, or swivel faucets; or taps off of individual homeowner treatment units.

Do not choose a fire hydrant as sampling tap.

Avoid taps that are surrounded by excessive foliage or taps that are dirty or corroded.

Avoid taps that leak, have fittings with packing, or have permanent hoses or attachments fastened to the tap (Never collect a sample from a hose).

Avoid the use of dead ends for routine sample collection, and use them for repeat samples only if no other sample sites are available and if there is continuous water use from a service off the dead-end.

Instructions for Completing the Bacteriological Sample Siting Plan Form

This form has been designed to include all the requirements for the Bacteriological Sample Siting Plan.

- **Public Water System Classification**

The public water system (PWS) classification for your water system is either community, nontransient noncommunity or transient noncommunity. If you are uncertain of your classification, contact the District Office.

- **Month/Daily Users**

The monthly population determines the frequency of bacteriological sample collection for community water systems and nontransient noncommunity systems. For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

- **Active Service Connections (Community water systems only)**

This is the number of active hook-ups served by the system. If your system has a hook-up to a vacant lot, do not count this as an active connection. If a vacant lot has a right to a future connection, do not count this as an active connection. If a residence is connected to the system, but the residence is vacant, count this as an active hook-up.

- **Sampling Frequency**

This is the minimum number of routine bacteriological samples required at the frequency specified. If any routine sample is positive for coliform bacteria, additional repeat samples will be required. Repeat samples are in addition to the required routine samples. If you are uncertain of the routine sampling frequency for your water system, contact the District Office.

- **Trained Sampler**

The person collecting samples must be trained.

Sampling Service: Water systems utilizing a certified laboratory or other sampling service for water sample collection will be considered to have trained samplers. Enter the name of the laboratory or sampling service collecting your samples. A copy of the approved Bacteriological Sample Siting Plan should be provided to the laboratory or sampling service, if one is used.

Other Trained Samplers: Any person receiving a certificate from AWWA for attendance of the Water Sampling Training should submit a copy of their certificate along with the completed form. Any other samplers should submit a statement of their experience and training to this office for approval.

- **Analyzing Lab**

Enter the state-certified laboratory, which will be analyzing your water samples.

- **Person Responsible to Report Coliform-Positive Samples to the Division**

This should be the person that the laboratory is required to contact when a sample is total or fecal coliform positive. This person must notify the Division within 24 hours of a violation of the total coliform standard (more than one positive sample in a month) or when any sample is fecal or *E. coli* positive. This person should have the authority to take corrective action as required by regulation and the Division. This should be the same person listed on your Emergency Notification Plan.

- **Day/Evening Phone Number**

The Division requires that the water system provide the phone numbers of the person listed above so that they can be contacted by the laboratory or the Division at any time during the day or evening in the event of a bacteriological emergency.

- **Signature and Date**

The person preparing the Sample Siting Plan should sign and date the plan. If the Division has questions regarding the sampling plan, this is the person to be contacted.

- **Sample ID**

This should be entered on the laboratory slip when the sample is turned into the laboratory. This is the unique identifier for the water sample location, or the location address may also be used. For systems, which have no more than five (5) routine locations, these routine sites will be 1-ROU, 2-ROU, 3-ROU, 4-ROU, and 5-ROU.

Each routine sample site must have two repeat sampling sites. Repeat sample sites are to be located within five (5) service connections upstream and downstream of the routine sample site.

All sample locations should be marked in some way with the Sample ID or location address, i.e., the code painted on the sampling location or tagged with a water proof tag so the person collecting the water sample is sure to collect the water from the correct sample locations.

- **Sample Type**

This describes what type of sample (routine or repeat) is to be collected at this location.

- **Sample Point**

This is the type of the sample location. Use the following abbreviations, when appropriate: HB - Hose Bib (exterior), SF - Sink Faucet, PC - Goose Neck Type Copper Tube with Pet Cock

- **Location of Sample Point**

This is the description of the area in the distribution that the sample site is located. Routine sample sites shall not be located at dead ends. Use the following abbreviations, when appropriate: DE - Dead End (Not Recommended), PZ - Pressure Zone, RD - Representative Distribution

- **Location Address**

This is the actual physical location where the water sample is to be collected. If possible use a street address, i.e., 103 Good Street. If the location does not have a street address, use the nearest crossroads or use the last name of the resident, i.e., "Brown Residence." If the location is a business, please list the business name and address.

When describing the location, keep in mind that the person collecting water samples must be able to locate the sample site from your description.

- **Months Sample Collected at This Location**

This is the schedule for routine samples to be collected. For example, suppose two (2) sites are representative of your systems. Site No. 1 will be sampled in January, March, May, July, September, and November. Site No. 2 will be sampled in February, April, June, August, October, and December. All routine sites identified should be rotated to allow sampling at least every 3 months.

BACTERIOLOGICAL SAMPLE SITING PLAN (BSSP) FOR SMALL WATER SYSTEMS

System No.:		System Name:			PWS Classification:	
No. of Monthly Users:		No. of Daily Users:		No. Active Service Connections:		Cl2 Treatment:
Sampling Frequency: __ per month			Seasonal System:		Period of Operation:	
Name of Trained Sampler:			Analyzing Lab:		Analyzing Lab:	
Person Responsible to Report Positive Samples to the Division:					Day/Evening Phone No:	
Signature of Water System Representative:					Date:	

Sample ID	Sample Type	Sample Point	Location of Sample Point	Address of Sample Point	Months Sample Collection at this Location
1-ROU	Routine				
1-REP1	<i>Repeat</i>				<i>Repeat Sample Only</i>
1-REP2	<i>Repeat</i>				<i>Repeat Sample Only</i>

In the event of a routine positive sample, a sample(s) will be collected from the well(s) in use for Ground Water Rule compliance.

If continuous chlorination is provided, raw water samples are taken **monthly**.

The SWRCB-Division of Drinking Water or Local Primacy Agency has reviewed and approved this BSSP. Any plans on file dated prior to approval date below are void. The water system must sample their distribution system and raw water special purpose source samples for bacteriological quality in accordance with the approved BSSP beginning _____. Per the California Code of Regulations-Title 22 §64422, a water system is required to submit an updated plan to the State Board at least once every ten years and at any time the plan no longer ensures representative monitoring of the system.

District Office Representative Name: _____ Title: _____ District Name: Tulare District

Signature: _____ Date: _____

Appendix F:
Lead and Copper Tap Sample Results Reporting Form



State Water Resources Control Board

Division of Drinking Water

Lead and Copper Tap Sample Results Reporting Form

This form must be submitted by the public water system to the regulating entity (DDW District Office or County Agency) for each round of lead and copper sampling

Report Date: (mm/dd/yyyy)	
Water System Name:	
Water System Number:	
Water System Type:	<input type="radio"/> Community <input type="radio"/> Non-Transient, Non Community
Monitoring Frequency:	<input type="radio"/> 6-month <input type="radio"/> Annual <input type="radio"/> Triennial
# of Samples Required:	
# of Samples Reported:	
	90th Percentile Level (mg/L)
Lead: <i>Action Level = 0.015 mg/L</i>	
Copper: <i>Action Level = 1.3 mg/L</i>	

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
01					
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Sampling Site Change

Each round of sampling should be conducted at the same sampling sites. If an original sampling site is not available, you should collect a tap sample from another site meeting the same Tier criteria as the original site.

You must complete/submit the ***Lead and Copper Tap Sampling Site Change*** form.

Notification of Results

As required by *40 Code of Federal Regulations Section 141.85(d)*, within 30 days of learning of the tap monitoring results, I notified the participants, by mailing or by another method approved by the State, of the lead sample results from their individual taps, provided an explanation of the health effects of lead, listed steps the consumer could take to reduce exposure to lead, provided contact information for the water utility, the maximum contaminant level goal for lead, action level for lead, and any definitions.

Notification was done on _____ by _____
(date)

- ☐ Direct Mail
☐ Posting in public area (NTNC systems only)
☐ Other (please specify below) _____
-

For general information on lead and copper tap sampling, you can refer to the ***SWRCB Lead and Copper Tap Sample Results Guidance Document***. If you have any questions or comments, please contact your regulating entity (Division of Drinking Water District or County Agency).

SIGNATURE:	DATE:
NAME (Print):	TITLE:

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					

Appendix I: Yettem 2023 Sanitary Survey

State Water Resources Control Board Division of Drinking Water

June 01, 2023

Ms. Celeste V. Perez
Yettem Water System - CA5403043
5961 S. Mooney Blvd.
Visalia, CA 93277

2023 SANITARY SURVEY

Dear Ms. Perez,

On April 10, 2023, the State Water Resources Control Board, Division of Drinking Water (Division) staff conducted an inspection of the Yettem Water System (Water System) with the assistance of Mr. Jose Padilla, Contract Operator for the Water System. After evaluation of the Water System and completion of the enclosed sanitary survey report, the Division finds that the items below are required to be addressed by the Water System.

After evaluation of the existing water supply facilities and completion of a subsequent file review, the Division finds that the items below must addressed by the Water System:

1. By **July 30, 2023**, the Water System must install a non-corrodible fine mesh screen on the storage tank vent.
2. **Due immediately**, the Water System must begin to sample Well 01 for iron quarterly.
3. **Due immediately**, the Water System must begin testing the backflow devices annually or provide an explanation of why is not necessary. In addition, the Water System must provide information regarding how the remainder of the action items were addressed.

The following items were required by Water Supply Permit Amendment No. 03-24-20PA-025 and the 2020 Sanitary Survey and have not been addressed by the Water System. These items are DUE IMMEDIATELY:

During the inspection the Division identified holes in the storage tank and an active leak. This is a Significant Deficiency and must be addressed by the Water System.

4. By **October 19, 2020**, the Water System must submit a timeline with a course of action for having the storage tank repaired.

E. JOAQUIN ESQUIVEL, CHAIR | EILEEN SOBECK, EXECUTIVE DIRECTOR

In addition, the following items also require attention.

5. By **December 31, 2020**, the Water System must designate a shift treatment operator with a minimum T1 treatment operator certification.
6. By **December 31, 2020**, the Water System must submit a revised Operations Plan to the Division for review and approval.

If you have any questions regarding the information contained in the sanitary survey report, please contact the Tulare District office at (559) 447-3300 or by email at DWPDIST24@waterboards.ca.gov.

Sincerely,

Kristin Willet  Digitally signed by Kristin Willet
Date: 2023.06.01 15:42:10 -07'00'

Kristin Willet, P.E.
Senior Water Resource Control Engineer, Tulare District
Division of Drinking Water
Southern California Field Operations Branch

ER/KW

cc: Tulare County Environmental Health Division
ngonzale@tularecounty.ca.gov

Brenda Pauli, Division of Financial Assistance-Project Manager
Brenda.Pauli@waterboards.ca.gov

Caitlyn Juarez, Division of Drinking Water, SAFER
Caitlin.Juarez@Waterboards.ca.gov

Jose A. Padilla, Contract Operator
jose_padilla2010@yahoo.com

Small Water System Evaluation and Inspection Report
Drinking Water Field Operations Branch: Tulare District

Yettem Water System
System No. CA5403043

Contact:	Ms. Celeste Perez, General Manager	System Type:	Community Water System
Inspection Date:	April 10, 2023	Inspected by:	Elvira Reyes

I. INTRODUCTION

On April 10, 2023, Elvira Reyes, with the State Water Resources Control Board, Division of Drinking Water (Division) conducted a sanitary survey of the Yettem Water System (Water System). Mr. Jose Padilla, water system contract operator, assisted with the sanitary survey. Ms. Reyes is responsible for the investigation, analysis, and preparation of this report as well as the directives regarding the deficiencies noted during the sanitary survey and subsequent file review. The Water System was last inspected by the Division on September 11, 2020 as a routine sanitary survey.

PERMIT STATUS

The Water System currently operates under Domestic Water Supply Permit No. 03-24-20PA-025 issued by the Division on September 18, 2020. The permit provisions are listed below.

The Yettem Water System shall comply with the following permit conditions:

1. The Yettem Water System shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted there under.
2. The only approved sources of domestic water supply for the Yettem Water System are as follows:

Source	PS Code	Status
Well 01 – Pre NO3 Blend	CA5403043_001_001	Active
Well 02 – Pre NO3 Blend	CA5403043_002_002	Active

3. The only approved treatment for the Yettem Water System is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution and nitrate blending.

Treatment Facility	PS Code
Well 01 & 02 – NO3 Blend Tank	CA5403043_003_003

4. No other sources or treatment (as described in provision Nos. 2 and 3 above) shall be used by the Yettem Water System and no changes, additions, or modifications shall be made to the sources or treatment unless an amended domestic water supply permit has first been obtained from the Division.
5. All personnel who operate the distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Yettem Water System is classified as a D1 distribution system and shall be operated by a certified D1 distribution operator or higher.
6. All personnel who operate the treatment facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Yettem Water System's nitrate blending treatment facility is classified as a T2 treatment facility. The Yettem Water System must have a chief treatment operator who is certified, at a minimum, as a T2 treatment operator and a shift operator who is certified as a T1 treatment operator or higher.
7. The Yettem Water System shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The Yettem Water System shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.
8. The Yettem Water System shall submit an electronic Annual Report (EAR) each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
9. The Yettem Water System shall record water production data from the active sources at least monthly. The monthly water production data shall be reported annually to the Division in the EAR.
10. The Yettem Water System shall collect monthly raw water samples from each source for analyses of total coliform and fecal coliform or E. coli bacteria. The coliform test shall be performed using a density analytical method and the results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following month.
11. The Yettem Water System shall monitor for coliform bacteria in the distribution system at least monthly and in accordance with an approved Bacteriological Sample Siting Plan (BSSP). The Division shall be notified immediately if any distribution system or source sample shows the presence of E. coli bacteria or if

more than one bacteriological sample shows the presence of coliform bacteria during a single month.

12. The Yettem Water System shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The Yettem Water System shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.
13. The Yettem Water System shall conduct Stage 2 Disinfection Byproduct (DBP) monitoring from the sample site below. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Code:

ST2 Monitoring Site	PS Code
ST2S1 – 14395 Ave 384	CA5403043_DST_900

14. The Yettem Water System shall submit a monthly chlorination log to the Division by the 10th day of the following month.
15. The Yettem Water System shall operate the continuous chlorination and nitrate blending treatment facilities in accordance with a Division-approved Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval prior to implementation.

SERVICE AREA & DESCRIPTION OF SYSTEM

The mailing address for the Yettem Water System is 5961 S. Mooney Blvd. Visalia, CA 93277. The legal owner of the Water System is the Yettem-Seville Community Services District. The Water System is classified as a community water system (CWS), which serves an approximate population of 350 people through 66 service connections. The domestic water supply is obtained from two active groundwater sources, identified as Wells No. 01 and 02. Continuous chlorination and nitrate blending treatments are provided to the source water. Storage is provided by a 150,000-gallon bolted steel storage tank. Figure 1 illustrates the components of the Water System. The surrounding land use area is largely agricultural. The Seville Water Company is located two miles east of the Water System. Appendix A provides a map of the Water System and photos of Water System components.

The Water System is involved in a two-phase water system improvement project with the Seville Water Company (System No. CA5400550). The first phase was completed in 2020. This phase included replacing the distribution system, adding a 211,000-gallon storage tank with booster station in the Seville Water Company water system. The second phase is in progress. It includes the addition of a new well, an interconnection of it with the existing system and to the Seville Water Company; installation of new water meters for existing connections; storage tank site improvements; integration of the

Yettem and Seville pump station sites using a Supervisory Control and Data Acquisition (SCADA) system; and the installation of an emergency standby generator. New water services and meters (approximately 26 connections) will be included along the interconnection pipeline (including on-site private lateral pipes to connect to existing homes). The project is being funded by the State Water Resources Control Board, Division of Financial Assistance (DFA).




Figure 1 – Current Flow Schematic for the Water System

ENFORCEMENT HISTORY

The Water System has received the following enforcement action from the Division since the last sanitary survey in September 2020:

Enforcement Action:	Citation No.03-24-21C-011
Issue Date:	January 29, 2021
Description:	The Water System failed to collect the required bacteriological samples for November 2021.
Status	The Water System returned to compliance in February 2021. The directives on the citation were completed.

II. INVESTIGATION AND FINDINGS

SOURCES OF SUPPLY

The Water System's source of supply is from two active groundwater sources identified as Wells No. 01 and 02.

Well 01, Active - Treated, Groundwater, (CA5403043_001_001)

DWR Well Completion Report:	Yes
Date of Well Completion:	December 1994
Well Depth:	330 feet
Sanitary Seal Depth:	89 feet, cement
Well Casing:	10-inch diameter steel casing to 330 feet; perforations between 130 to 260 feet and 270 to 330 feet.
Flow Meter:	Yes
Pump Type:	Deep well turbine, oil-lubricated
Pump Make and Model:	U.S. Motors
Pump Size:	10-horsepower (hp)
Well Capacity:	130-gallons per minute (gpm)
Source Discharge:	Directly to a 150,000-gallon bolted steel storage tank
Source Operation:	Water level in the storage tank
Well Equipment:	Well 01 is equipped with a sounding tube, air relief valve, sampling port, check valve, and source meter. Well 01, the storage tank, booster pumps and pressure tanks are located at the same site. The site is fenced and locked.
Discharge-to-waste:	No

Well 02, Active - Treated, Groundwater, (CA5403043_002_002)

DWR Well Completion Report:	Yes
Date of Well Completion:	December 1994
Well Depth:	320 feet
Sanitary Seal Depth:	90 feet, cement
Well Casing:	10-inch diameter steel casing to 316 feet; perforations between 120 and 316 feet.
Flow Meter:	Yes
Pump Type:	Submersible
Pump Make and Model:	Hitachi

Pump Size: 7.5-hp
Well Capacity: 130-gpm
Source Discharge: Directly to a 150,000-gallon bolted steel storage tank
Source Operation: Water level in the storage tank
Well Equipment: Well 02 is equipped with a sounding tube, screened and inverted casing vent, sampling port, check valve, and source meter. The well is in a fenced and locked site.

Discharge-to-waste: No

Source Water Assessments

Source water assessments were completed for Wells No. 01 and 02 by Tulare County in September 2002. According to the source water assessments, Wells No. 01 and 02 are considered most vulnerable to known contaminant plumes, agricultural drainage, sewer collection systems, and agricultural/irrigation wells. This information should be included in the annual Consumer Confidence Report.

WATER PRODUCTION

Based on the information reported to the Division in the 2014 through 2021 electronic Annual Reports, the population, number of service connections, annual production, and maximum month of production is outlined in Table 1 below. Production data 2022 was obtained from the monthly production report submittals.

Table 1 - Production Data

Year	Population	Service Connections	Annual Production (Gal.)	Max. Month (Gal.)
2014	350	66	13,456,100	2,005,700 (JUL.)
2015	350	66	13,455,600	1,764,300 (JUN.)
2016	350	64	18,131,300	2,404,300 (SEP.)
2017	350	64	8,209,708	1,820,600 (JUN.)
2018	350	64	13,857,100	1,785,500 (JUL.)
2019	350	66	12,872,700	2,044,900 (JUL.)
2020	350	66	5,038,934	627,100 (OCT.)
2021	350	66	14,290,000	2,325,000 (MAY.)
2022	350	66	16,817,000	2,116,000 (SEP..)

Annual production reported for 2017 and 2020 appear to be lower than typical values reported. The reason for the low production values is unknown.

ADEQUACY OF SUPPLY

Production data, as reported by the Water System, and peaking factors established in the California Waterworks Standards were used to determine the Water System's Average Day Demand (ADD), Maximum Day Demand (MDD), and Peak Hour Demand (PHD). The Water System's ADD, MDD, and PHD and the total source capacities are provided in Tables 2 and 3, respectively, below. The 2017 values were not considered in the water usage evaluation due to the discrepancy in reported values. According to Water System staff, monthly production is based on water meter reads.

Table 2 - Average Day, Maximum Day & Peak Hour Demands

Year	ADD (gpm)	MDD (gpm)	PHD (gpm)
2014	26	67	101
2015	26	61	92
2016	34	83	125
2017	16	63	95
2018	26	60	90
2019	25	68	103
2020	9.6	22	33
2021	27	78	117
2022	32	73	110

Table 3 - Total Active Source Capacity

Source	Capacity (gpm)
Well 01	130
Well 02	130
Total System Capacity	260

The total combined source capacity of the Water System is estimated to be 260 gpm. Based on the highest reported water usage for 2016, the Water System appears to have adequate source capacity to supply the ADD, MDD, and PHD of 34 gpm, 83 gpm, and 125 gpm, respectively.

California Waterworks standards require water systems serving less than 1,000 service connections to have storage capacity equal to or greater than MDD, unless the water system can demonstrate that it has an additional source of supply or has an emergency source connection that can meet the MDD requirement. The Water System has a total storage capacity of 150,000 gallons, which is equivalent to approximately 20 hours of MDD. The Water System appears to meet storage capacity requirements. It should be noted that the storage tank has a leak deficiency (discussed in more detail below) which may affect storage capacity volume.

STORAGE TANK & BOOSTER STATION

Storage is provided by a 150,000-gallon bolted steel storage tank. The tank is configured with a top inlet and a bottom outlet and is equipped with a locked ladder with safety cage. The vent was noted to be unscreened. An overflow vent features a flapper to keep any insects or small animals from accessing the tank. An external water level indicator is installed on the exterior of the tank but does not work. **By July 30, 2023, the Water System must install a non-corrodible fine-mesh screen on the storage tank vent.**

The deficiencies noted in the last inspection remained unaddressed, there are still several rust spots and the visible leak at the bottom outer surface of the storage tank are present. A new leak was observed near the same vicinity and subsection of the existing leak. The date of the last internal inspection and/or cleaning is still unknown. The leaks and rusting of the outer surface of the storage tank is a Significant Deficiency. Photos of the Significant Deficiency are provided in Appendix A. **In the 2020 Sanitary Survey, the Water System was directed to immediately investigate and repair the storage tank as needed or submit a timeline with a course of action for having the tank repaired by October 19, 2020. This directive remains outstanding and must be addressed by the Water System immediately.**

A programmable logic control (PLC) water level control system controls how the tank is filled. A float switch inside the tank communicates with the PLC to signal Wells No. 01 and 02 to fill the storage tank based on predetermined water level settings. At the time of the inspection, the high and low level alarm settings remained at 22 feet and 16 feet, respectively. Water from the storage tank is boosted to a 10,000-gallon steel hydropneumatic pressure tank using a 10-hp vertical centrifugal pump (lead) and a 25-hp water-lubricated turbine pump (lag). Operation of the booster pumps is based on system pressure and controlled with the PLC.

DISTRIBUTION SYSTEM

The distribution system is classified as a D1 system and consists of 6-inch diameter galvanized steel and polyvinyl chloride (PVC) mains with 1-inch diameter service laterals. The distribution system was installed in the 1980s. Distribution system pressure is maintained between 40 and 60 psi. AWWA standards are followed when any repairs are made. If a main is taken out of service, special bacteriological samples are required to be collected and must be coliform free prior to placing the main back in service.

TREATMENT FACILITIES

Nitrate Blending, Well 01 & 02 NO3 Blend Tank, Active, (CA5403043_003_003)

The Water System provides nitrate blending treatment to the water produced by Wells No. 01 and 02 to reduce the nitrate concentration in Well 01. The nitrate blending

treatment occurs in the 150,000-gallon storage tank. The PLC signals Wells No. 01 and 02 to fill the tank simultaneously when the water level in the tank reaches 19 feet. Well 01 is signaled to turn off when the water level reaches 19 $\frac{3}{4}$ feet, but Well 02 continues to fill the tank until the water level in the tank reaches 21 feet.

The Water System has been sampling Wells No. 01 and 02 and the blended effluent monthly for nitrate. The nitrate effluent sample is collected at the tank. The average blended nitrate effluent result is 7.2 mg/L and the range is 6.3 mg/L to 10 mg/L. Per data available, February 7, 2020 has been the only date where the nitrate level was at 10 mg/L. A follow up sample was collected on February 11, 2020 and the result was 7.5 mg/L. The blending tank is not equipped with an online nitrate analyzer to instantaneously verify that the water served to customers meets the nitrate standard. From February 2020 to August 2020, the Water system monitored treated effluent at least every two weeks for nitrate, as directed from the Division. There is no data available from September 2020 through September 2021 for nitrate blended effluent. A graphical representation of all raw and blended effluent nitrate (as N) results available are illustrated in Figure 2 below. Under the Operations Plan section, the Division has requested an updated plan from the Water System that must include actions on how it will address potential nitrate exceedances.




Figure 2 –Raw and Blend Nitrate Results

Continuous Chlorination

The Water System provides continuous chlorination to the water produced by Wells No. 01 and 02. A 12.5% solution of sodium hypochlorite is injected directly into the effluent line of the storage tank, upstream of the 10,000-gallon hydropneumatic pressure tank. The sodium hypochlorite solution is stored at the site of the storage tank in a 35-gallon polyethylene tank inside a fiberglass shelter. The chlorination equipment consists of an Iwaki (Walchem) E-Class chemical feed pump. The chemical feed pump has a capacity of 0.6 gallons per hour (gph) at 150 psi. The chemical storage tank and feed pump appear to be adequately sized. A sample tap located downstream of the injection point is used to measure the chlorine residual entering the distribution system. The typical chlorine residual range maintained within the distribution system is 0.28-1.9 mg/L.

SOURCE MONITORING

A summary of the recent source water quality monitoring results and next due dates is included in Appendix B. Additionally, the current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>. Instructions for accessing this information is included in Appendix C.

Bacteriological

Due to continuous chlorination, the untreated well water from Wells No. 01 and 02 must be sampled monthly for total coliform bacteria at a sample tap located prior to the chlorine injection port. This is required in order to verify that the wells are not producing water that contains coliform bacteria. A summary of source water bacteriological sample results is included in Appendix D.

General Mineral and General Physical

The Water System is required to monitor its active groundwater sources for general mineral (GM) and general physical (GP) chemical water quality every three years. The Water System last sampled Well 01 for GM and GP in 2021. All chemical monitoring results for Well 01 were below the MCL, except for iron. The result for iron is 480 mg/L which exceeds secondary MCL of 300 mg/L. Monitoring frequency was increased to quarterly for iron and compliance will be determined on an average of the initial sample and the next three consecutive quarterly samples collected. **Due immediately, the Water System must begin to sample Well 01 for iron quarterly.** The monitoring schedule was modified to reflect the new due dates and is available online. Well 02 sampled for GM and GP in 2021 and all chemical monitoring results were below the MCL. The next round of GM and GP monitoring for Well 01 and Well 02 is due in 2024, except for iron from Well 01.

Inorganic Chemicals

The Water System is required to sample each active well for inorganic chemicals every three years, except for nitrate which has a different monitoring frequency as described below. Well 01 and Well 02 chemical monitoring results were below the respective MCLs. The next round of inorganic chemical water quality monitoring from Well 01 and Well 02 is due in 2024.

Nitrate

Wells No. 01 and 02 are on a monthly nitrate (as N) monitoring frequency and were last sampled in April 2023. The results for Wells No. 01 and 02 were 10.8 mg/L and 4.8 mg/L, respectively. The next round of nitrate monitoring for Wells No. 01 and 02 is due in May 2023.

Volatile Organic Chemicals (VOCs)

The monitoring waiver application for volatile organic chemicals (VOCs) for the 2023-2025 monitoring period was approved for all VOCs for both wells. Both wells are on a six-year sampling frequency for VOCs. The monitoring schedule was modified to reflect the new due dates and is available online. Wells No. 01 and 02 were last sampled for VOCs in 2021 and 2018, respectively. The results were all non-detect. The next round of VOC monitoring for Well 01 is due in 2024 and Well 02 is due in 2027.

Synthetic Organic Chemicals (SOCs)

The Water System is required to sample Wells No. 01 and 02 on a three-year frequency for synthetic organic chemicals (SOCs). Wells No. 01 and 02 were last sampled for 1,2,3-trichloropropane (1,2,3-TCP), alachlor, atrazine, and simazine in 2021 and dibromochloropropane (DBCP) and ethylene dibromide (EDB) in 2020. The SOC results were all non-detect. The next round of SOC monitoring for both sources is scheduled for 2024, except for DBCP and EDB which are due in 2023.

The Water System must sample for DBCP and EDB by December 31, 2023.

Radiological Monitoring

Initial radiological monitoring is based on the collection of four consecutive quarterly samples of gross alpha and radium-228. If the results from the first two quarters of initial monitoring are below the detection limit for the purposes of reporting (DLR), the final two quarters of initial monitoring may be waived. After initial monitoring is complete, no additional monitoring is required for radium-228. Subsequent monitoring frequencies for gross alpha is based on the results of the last sample collected. It should be noted that

if the gross alpha result for any single sample is greater than 5 pCi/L, analysis for uranium in *that same sample* is required.

Triggered Monitoring:

Uranium:

If the $GA + (0.84 * CE)$ for any single sample is greater than 5 pCi/L, analysis for U in that same sample, is required.

Total Radium:

If the $GA + (0.84 * CE) - U$ is greater than 5 pCi/L, analysis for total radium in that same sample, is required.

Triggered monitoring needs to be communicated to the laboratory on the chain of custody at the time the sample is submitted.

The Water System has completed the initial gross alpha and radium-228 monitoring requirements for Wells No. 01 and 02. As such, the Water System is no longer required to monitor for radium-228. Wells No. 01 and 02 were last sampled for gross alpha in 2017 and 2015, respectively, and the result for both sources was non-detect. Wells No. 01 and 02 are currently on a nine-year monitoring frequency for gross alpha. Therefore, the next gross alpha sample from Wells No. 01 and 02 are scheduled for 2026 and 2024, respectively.

DISTRIBUTION SYSTEM MONITORING

Bacteriological

Based on the population and number of service connections, the Water System is required to collect at least one routine bacteriological sample each month from the distribution system. The sample must be analyzed for total coliform bacteria with results sent to the Division by the 10th day of the following month. A summary of the distribution bacteriological sample results is included in Appendix D.

Bacteriological samples should be collected in accordance with an approved Bacteriological Sample Siting Plan (BSSP). The last approved BSSP is dated April 30, 2015. The Water System Operator submitted an updated BSSP during the inspection. The review and approval of the new BSSP will be issued in a separate cover letter.

Lead and Copper Monitoring

The Water System is required to comply with the Lead and Copper Rule (LCR) and conduct lead and copper tap monitoring during each monitoring period. Compliance with the lead and copper action levels is based on the 90th percentile lead and copper results. The 90th percentile for lead and copper should be less than the lead and copper

action levels of 0.015 mg/L and 1.3 mg/L, respectively. A summary of all lead and copper tap monitoring results is outlined in Table 4 below. **The next round of lead and copper tap monitoring from the distribution system must be collected between June 1 and September 30, 2023, see Table 5 below.**

Table 4 – Lead and Copper Tap Monitoring Results

Monitoring Period	Sample Date(s)	No. of Samples	Lead 90 th Percentile Result (mg/L)	Copper 90 th Percentile Result (mg/L)	No. of Samples Exceeding Action Level
3Y2018-2020	10/02/2020	5	ND	ND	--
3Y2016-2018	7/25/2017-8/15/2017	10	0.012	ND	1 (Lead)
6M2ND-2017	12/22/2017	10	ND	ND	--
3Y2013-2015	6/24/2015	5	ND	ND	--
3Y2010-2012	8/10/2012	5	0.006	0.172	--
3Y2009-2011	6/30/2011	5	ND	0.099	--
3Y2006-2008	9/25/2008	5	0.003	0.034	--
3Y2003-2005	5/12/2005	10	0.002	0.025	--
3Y2000-2002	5/1/2002	5	0.002	0.025	--
YR2001	2/1/2001	5	0.007	0.006	--
YR1999	6/1/1999	5	0.013	0.025	--
6M1ST-1997	6/1/1997	10	0.002	0.025	--
6M2ND-1996	12/1/1996	10	0.013	0.025	--

Table 5 – Future Lead and Copper Tap Monitoring Period

Frequency	No. of Samples Required	Monitoring Period	Next Monitoring Period Begin	Next Monitoring Period End	Next Sample Due Date
3 years	5	3Y2021-2023	6/1/2023	9/30/2023	9/30/2023

All future lead and copper monitoring results must be submitted to the Division electronically via California Laboratory Intake Portal (CLIP) using PS Code CA5403043_DST_LCR.

The Water System must complete and submit a Lead and Copper Tap Sample Results Reporting Form with all subsequent lead and copper monitoring results. A Lead and Copper Tap Sample Results Reporting Form is included in Appendix E.

Lead Service Line Inventory Requirement

The Water System submitted a service line inventory dated September 5, 2018. The Water System identified 104 polyethylene service lines and did not indicate any lead or unknown material service lines.

On January 15, 2021, the US EPA issued revisions to the federal Lead and Copper Rule (LCR). US EPA's new Lead and Copper Rule Revisions (LCRR) aim to strengthen the LCR to better protect communities and children in elementary schools and childcare facilities from the impacts of lead exposure. All community and nontransient noncommunity water systems must complete and submit their inventory by **October 16, 2024**. Each water system must maintain the required inventory information described in the FAQ and inventory instructions are found on the Lead and Copper Rule for Drinking Water website: https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/leadandcopperrule.html.

Disinfection Byproduct Monitoring

Due to the implementation of continuous chlorination, the Water System is required to comply with the Stage 2 Disinfection Byproduct Monitoring Rule (DBPR). To comply with Stage 2 DBPR monitoring requirements, the Water System is required to collect one DBP sample from the distribution system every three years during a month of the warmest water temperature. The sample must be analyzed for total trihalomethanes (TTHMs) and haloacetic acids (HAA5s). The results of the Stage 2 DBP monitoring must be sent to the Division electronically using the PS Code listed in Table 6 below.

Table 6 – Stage 2 DBP Monitoring Site

ST2 DBP Monitoring Site	PS Code
ST2S1-14395 Ave 384	CA5403043_DST_900

The last Stage 2 DBP sample was collected on July 8, 2020. The results for TTHMs and HAA5s were non-detect and 0.0055 mg/L, respectively. The next round of DBP monitoring in the distribution system is scheduled for 2023. **Between June 1 and September 30, 2023, the Water System must sample for DBPs.**

Asbestos

Asbestos monitoring from the distribution system is not required since the system does not have any asbestos cement distribution piping.

IV. OPERATIONS AND MAINTENANCE

Operator Certification

The Water System's distribution system is classified as a D1 system and requires a certified distribution system operator with a minimum D1 certification or higher. In addition, the Water System's nitrate blending treatment facility is classified as a T2 treatment facility and requires a certified chief treatment operator with a minimum T2 certification or higher and a shift treatment operator with a minimum T1 treatment operator certification. Mr. Jose Padilla is the Water System's chief treatment operator and is a certified D1 distribution operator (Certification No. 27640, Exp. 6/1/2025) and T2 treatment operator (Certification No. 25926, Exp. 4/1/2025). Mr. Cruz Perez is the Water System's Chief distribution operator and is a certified D1 distribution operator (Certification No. 39737, Exp. 7/1/2023). The Water System does not meet the minimum shift treatment operator requirements of a T1 certification or higher. **In the 2020 Sanitary Survey the Water System was directed to designate a shift operator with a minimum T1 treatment operator certification by December 31, 2020. This directive remains outstanding and must be completed immediately to avoid enforcement action.**

Per Title 22, Section 63770, California Code of Regulations, water systems shall utilize only certified distribution operators to make decisions addressing the following operational activities:

- 1) Install, tap, re-line, disinfect, test and connect water mains and appurtenances.
- 2) Shutdown, repair, disinfect and test broken water mains.
- 3) Oversee the flushing, cleaning, and pigging of existing water mains.
- 4) Pull, reset, rehabilitate, disinfect and test domestic water wells.
- 5) Stand-by emergency response duties for after hours distribution system operational emergencies.
- 6) Drain, clean, disinfect, and maintain distribution reservoirs.

The Water System shall utilize either certified distribution operators or treatment operators that have been trained to make decisions addressing the following operational activities:

- 1) Operate pumps and related flow and pressure control and storage facilities manually or by using a system control and data acquisition (SCADA) system.
- 2) Maintain and/or adjust system flow and pressure requirements, control flows to meet consumer demands including fire flow demands and minimum pressure requirements.

The Water System shall utilize either certified distribution operators or treatment operators to make decisions addressing the following operational activities:

- 1) Determine and control proper chemical dosage rates for wellhead disinfection and distribution residual maintenance.
- 2) Investigate water quality problems in the distribution system.

Cross Connection Control

The Water System is required to maintain a Cross Connection Control Program, which shall include the following elements (as applied from Title 17, California Code of Regulations, Section 7584):

- 1) The conducting of surveys to identify water user premises or locations where cross connections are likely to occur,
- 2) The provisions of backflow protection by the water user at the user's connection or within the user's premises or both,
- 3) The provision of at least one person trained in cross connection control to carry out the cross-connection program,
- 4) The establishment of a procedure or system for annual testing of backflow preventers, and
- 5) The maintenance of records of locations, tests, and repairs of backflow preventers.

Backflow Prevention Device Testing

Regulation requires all backflow prevention devices to be tested annually. Copies of the testing records must be kept on file with the Water System for a minimum of three years.

Mr. Michael McKeever, Cross Connection Specialist (AWWA#02183 and ABPA3S05-00202), completed the last cross connection control survey of the water system on November 6, 2015. The survey highlighted eight items of which four required follow-up action items. Per the site visit, one of the action items has been resolved, it is unknown if the three remainder items were addressed. The survey stated that there were two backflow assemblies that must be tested annually. The Water System indicated in the 2021 EAR that it does not have any backflow prevention assemblies in the distribution system. **Due immediately, the Water System must begin testing the backflow devices annually or provide an explanation of why is not necessary. In addition, the Water System must provide information regarding how the remainder of the action items were addressed.** The Water System adopted a Cross Connection Control Program on July 16, 2019.

Cross-Connection Control Policy Handbook (CCCPH)

The State Water Board is developing a CCCPH with anticipated adoption in late 2023. Standards described in the CCCPH will be applicable to all California

Public Water Systems, as defined in California's Health and Safety Code (CHSC, Section 116275(h)). Compliance with the CCCPH will be mandatory for all California Public Water Systems. More information is available at this link: https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/cccp.html.

Complaints

The Water System must keep records of all complaints received and actions taken to correct the problems related to the complaints. According to the 2019 through 2021 electronic Annual Reports, the Water System did not receive any complaints during those calendar years.

Operations Plan

The current Operations Plan on file with the Division for the Water System is dated September 24, 2015. The plan reflects the implementation of the continuous chlorination and nitrate blending treatment. The Operations Plan is outdated and does not include the most current information. In addition, the Water System must include a plan of action on how to address potential nitrate exceedances. **In the 2020 Sanitary Survey, the Water System was directed to revised and submit an Operations Plan to the Division for review and approval by December 31, 2020. This directive remains outstanding and must be completed immediately to avoid enforcement action.** Guidance for completing an Operations Plan is included in Appendix F.

Emergency Notification Plan (ENP)

The current Emergency Notification Plan (ENP) on file with the Division is dated April 10, 2023. The Water System will provide notifications via door-to-door delivery, posted notification and automated phone notifications.

Consumer Confidence Report (CCR)

The Water System is required to complete a Consumer Confidence Report (CCR) on an annual basis and provide a copy to all residents and the Division by July 1 of each year. In addition, the Water System is required to provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers. The Water System submitted the CCR in April 2022 and the 2021 CCR Certification Form on June 7, 2022.

Electronic Annual Report (EAR)

All public water systems are required to provide updated water system information to the Division annually in the EAR. The Water System submitted the 2022 EAR to the Division via the Division's DRINC Portal on May 17, 2023. The Division noted that the

Water System does not meet the shift treatment operator requirements and that the backflow assemblies reported differentiate from the Cross Connection survey.

Water System Resiliency and Preparedness

The effects of climate change on community water system (CWS) facilities and operations is a concern and priority of the State Water Resources Control Board (SWRCB), which is documented by the SWRCB in its Comprehensive Climate Change Resolution adopted in March 2017. DDW is reviewing each water system preparedness for climate change with the goal to increase awareness and familiarization to the effects of climate change to facilities and operations, encourage the use of EPA's Climate Resilience Evaluation and Awareness Tool (CREAT) or equivalent, and to document the Water System's efforts related to current threats that may also provide mitigation to climate change impacts.

As part of the 2021 EAR, community water systems were asked to identify their vulnerabilities, and rank them as either high or already experiencing, medium, or low sensitivity, and proposed or implemented projects to prepare for the impacts from climate change. The Water System indicated none to low sensitivity to the list of questions regarding drought, water quality degradation, flooding/sea level rise, extreme heat, fire and other climate threats, sensitivity, and magnitude of impacts. There are no adaptation measures implemented.

The Water System operator indicated that he is not aware of the CREAT tool developed by USEPA for identifying climate change vulnerabilities. It is unclear if the Water System representative has used the CREAT (or similar tool) to identify vulnerabilities to the water system sources and facilities. The SWRCB strongly encourages utilities to evaluate climate change vulnerabilities using tools such as CREAT and engaging in a conversation both within your water system organization and with customers on how to plan and prepare for being resilient to provide clean and safe water reliably and adequately under all current and future conditions.

V. APPRAISAL OF SANITARY HAZARDS & PUBLIC HEALTH SAFEGUARDS

The Yettem Water System is composed of Wells 01, Well 02, two booster pumps, 150,000 gallon bolted steel storage tank, 10,000 gallon steel hydropneumatic pressure tank, and chlorination system. The total source capacity of the system is approximately 260 gpm. The Water System provides nitrate blending treatment and continuous chlorination. The nitrate blending occurs in the 150,000 gallon storage tank and is controlled with the PLC.

The Water System maintains the same physical deficiencies as noted in the last inspection, several rust spots and one active leak were still noted to be at the bottom outer surface of the storage tank. To date the significant deficiency has not been investigated nor a timeline has been submitted to the Division of when it will be

addressed. At this inspection, it was noted that the storage tank vent was missing a non-corrodible screen and an additional leak was present. In addition, the directive to conduct more frequent nitrate effluent sampling is not performed. The Water System also began experiencing elevated iron levels for Well 01, surpassing MCL secondary levels.

The Water System has several directives that remain outstanding that were established in the 2020 Sanitary Survey, including providing a timeline with a course of action for having the storage tank repaired, designating a shift treatment operator with a minimum T1 treatment certification, and submitting a revised operations plan. The Division established directives for the Water System in Permits, Sanitary Surveys and Enforcement Actions. The Water System is expected to address any Division issued directives by the deadline cited in this report. Fulfilling directives beyond the specified deadline is unacceptable. Please note that the Division does not grant deadline extensions. Failure to comply with Drinking Water Regulations demonstrates the Water System's lack of technical, managerial, and financial capacity.

The Water System is involved in a two-phase water system improvement project with the Seville Water Company (System No. CA5400550) that is being funded by the State Water Resources Control Board, Division of Financial Assistance. The first phase was completed in 2020, which replaced the distribution system and added a 211,000 gallon storage tank and booster station at the Seville Water Company. The second phase is in progress and will provide a new well, interconnection of that well with the existing system and to the Seville Water Company, installation of new water meters for existing connections, storage tank site improvements, integration of the Yettem and Seville pump station sites using a Supervisory Control and Data Acquisition and installation of an emergency standby generator. It will also add new water services and meters (approximately 26 connections) along the interconnection pipeline (including on-site private lateral pipes to connect to existing homes). The Division understands the Water System expects to resolve physical deficiencies via future projects, but it must still complete the directives stipulated in the Sanitary Surveys because they do not depend on the project completion.

The current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>. All laboratory chemical analytical results must be submitted to the Division via the California Laboratory Intake Portal (CLIP) using the correct primary station code (PS Code).

After evaluation of the existing water supply facilities and completion of a subsequent file review, the Division finds that the items below must be addressed by the Water System:

1. By **July 30, 2023**, the Water System must install a non-corrodible fine mesh screen on the storage tank vent.

2. **Due immediately**, the Water System must begin to sample Well 01 for iron quarterly.
3. **Due immediately**, the Water System must begin testing the backflow devices annually or provide an explanation of why is not necessary. In addition, the Water System must provide information regarding how the remainder of the action items were addressed.

The following items were required by Water Supply Permit Amendment No. 03-24-20PA-025 and the 2020 Sanitary Survey and have not been addressed by the Water System. These items are DUE IMMEDIATELY:

During the inspection the Division identified holes in the storage tank and an active leak. This is a Significant Deficiency and must be addressed by the Water System.

4. By **October 19, 2020**, the Water System must submit a timeline with a course of action for having the storage tank repaired.

In addition, the following items also require attention.

5. By **December 31, 2020**, the Water System must designate a shift treatment operator with a minimum T1 treatment operator certification.
6. By **December 31, 2020**, the Water System must submit a revised Operations Plan to the Division for review and approval.

Appendices:

Appendix A: Location Map & Photo Index

Appendix B: Last Sample & Next Due Date Summary Reports

Appendix C: Instructions for Accessing Public Drinking Water Watch


Appendix D: Source and Distribution System Bacteriological Monitoring Reports

Appendix E: Lead and Copper Tap Sample Results Reporting Form

Appendix F: Guidance Document for the Preparation of an Operations Plan

Appendix A:
Location Map & Photo Index

Appendix A
Yettem Water System: CA5403043
Location Map



Appendix A

Yettem Water System: CA5403043

Sanitary Survey Photographs

Well 01-Pre NO3 Blend (CA5403043_001_001)

- Date Drilled:
December 1994
- Depth: 330 feet
- Type: Deep well turbine, oil-lube.
- Pump Size: 10-hp
- Capacity: 130 gpm



Well 02-Pre NO3 Blend (CA5403043_002_002)

- Date Drilled:
December 1994
- Depth: 320 feet
- Type: Submersible
- Pump Size: 7.5-hp
- Capacity: 130 gpm



Appendix A

Yettem Water System: CA5403043

Sanitary Survey Photographs

Chlorination Equipment:

- Location: Chlorine solution is injected to the effluent line of the storage tank, upstream of the pressure tank
- Storage: 35 gallon poly. tank
- Chemical Pump:
 - Make: Walchem E-Class
 - Capacity: 0.6 gph/150 psi



Injection Point



Booster Station:

- Type: Centrifugal (lead) and turbine (lag)
- Size: 10-hp (lead) and 25-hp (lag)



Appendix A

Yettem Water System: CA5403043

Sanitary Survey Photographs

Pressure Tank:

- Location:
Downstream of
booster pumps
- Volume: 10,000
gallons
- Material: Steel



Programmable Logic Controller (PLC):

- Location: Site of Well
01



Appendix A
Yettem Water System: CA5403043
Sanitary Survey Photographs

**Storage/Blending
Tank:**

- Location:
Downstream of Wells
01 and 02
- Volume: 150,000
gallons
- Material: Bolted steel




Appendix A
Yettem Water System: CA5403043
Sanitary Survey Photographs

Tank Deficiencies



Leak 1: First observed in 2020 Sanitary Survey. Still present



Leak 2: New Leak observed in 2023 Sanitary Survey

Appendix A
Yettem Water System: CA5403043
Sanitary Survey Photographs



Storage Vent does not have a non-corrodible screen.

Appendix B:
Last Sample & Next Due Date Summary Report

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 01 - PRE NO3 BLEND

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5403043_001_001		YETTEM WATER SYSTEM					WELL 01 - PRE NO3 BLEND												
	GP	SECONDARY/GP																	
		1928 ALKALINITY, BICARBONATE	170.000		0.000		MG/L	-----	-----	7/14/2021	5	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1919 CALCIUM	20.000		0.000		MG/L	-----	-----	7/14/2021	7	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1929 ALKALINITY, CARBONATE		<	10.000		MG/L	-----	-----	7/14/2021	5	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1017 CHLORIDE	22.000		0.000		MG/L	500	-----	7/14/2021	5	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1905 COLOR		<	5.000		UNITS	15	-----	7/14/2021	5	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1022 COPPER, FREE		<	50.000		UG/L	1000	50	7/14/2021	6	36		2024/07		69520012107141400L	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2905 FOAMING AGENTS (SURFACTANTS)		<	0.100		MG/L	0.5	-----	7/14/2021	6	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1915 HARDNESS, TOTAL (AS CaCO3)	112.000		0.000		MG/L	-----	-----	7/14/2021	4	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1021 HYDROXIDE AS CALCIUM CARBONATE		<	10.000		MG/L	-----	-----	7/14/2021	5	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1028 IRON	480.000		100.000		UG/L	300	100	7/14/2021	6	3	Interval	2021/10	DUE NOW	69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1031 MAGNESIUM	15.000		0.000		MG/L	-----	-----	7/14/2021	7	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1032 MANGANESE	40.000		20.000		UG/L	50	20	7/14/2021	6	36		2024/07		69520012107141400G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 01 - PRE NO3 BLEND

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5403043_001_001	GP	SECONDARY/GP																	
		1920	ODOR		<	1.000	TON	3	1	7/14/2021	5	36		2024/07		69520012 10714140 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1925	PH	7.610		0.000	pH	-----	-----	7/14/2021	5	36		2024/07		69520012 10714140 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1050	SILVER		<	10.000	UG/L	100	10	7/14/2021	5	36		2024/07		69520012 10714140 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1052	SODIUM	44.000		0.000	MG/L	-----	-----	7/14/2021	5	36		2024/07		69520012 10714140 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1064	CONDUCTIV ITY @ 25 C UMHOS/CM	456.000		0.000	UMHO/CM	1600	-----	7/14/2021	6	36		2024/07		69520012 10714140 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1055	SULFATE	17.400		0.500	MG/L	500	0.5	7/14/2021	6	36		2024/07		69520012 10714140 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1930	TDS	280.000		0.000	MG/L	1000	-----	7/14/2021	6	36		2024/07		69520012 10714140 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		0100	TURBIDITY	1.900		0.100	NTU	5	0.1	7/14/2021	5	36		2024/07		69520012 10714140 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1095	ZINC		<	50.000	UG/L	5000	50	7/14/2021	6	36		2024/07		69520012 10714140 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	IO	INORGANIC																	
		1002	ALUMINUM	120.000		50.000	UG/L	1000	50	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1074	ANTIMONY, TOTAL		<	6.000	UG/L	6	6	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1005	ARSENIC	3.000		2.000	UG/L	10	2	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 01 - PRE NO3 BLEND

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5403043_001_001	IO	INORGANIC																	
		1010	BARIUM		<	100.000	UG/L	1000	100	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1075	BERYLLIUM, TOTAL		<	1.000	UG/L	4	1	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1015	CADMIUM		<	1.000	UG/L	5	1	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1020	CHROMIUM		<	10.000	UG/L	50	10	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1025	FLUORIDE	0.100		0.100	MG/L	2	0.1	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1035	MERCURY		<	1.000	UG/L	2	1	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1036	NICKEL		<	10.000	UG/L	100	10	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1039	PERCHLORA TE		<	2.000	UG/L	6	2	7/14/2021	8	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1045	SELENIUM		<	5.000	UG/L	50	5	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1085	THALLIUM, TOTAL		<	1.000	UG/L	2	1	7/14/2021	4	36		2024/07		69520012 10714140 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	NI	NITRATE/NITRITE																	
		1040	NITRATE	10.800		0.400	MG/L	10	0.4	4/18/2023	127	1	Interval	2023/05	DUE NOW	VI 2342312- 001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 4500- NO3-F-00
		1041	NITRITE		<	0.400	MG/L	1	0.4	7/14/2021	6	36		2024/07		69520012 10714140 ON	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 01 - PRE NO3 BLEND

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD	
CA5403043_001_001	S1	REGULATED VOC																		
		2413	1,3-DICHLOROPROPENE		<	0.500		UG/L	0.5	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2969	P-DICHLOROBENZENE		<	0.500		UG/L	5	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2990	BENZENE		<	0.500		UG/L	1	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2982	CARBON TETRACHLORIDE		<	0.500		UG/L	0.5	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2380	CIS-1,2-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2964	DICHLOROMETHANE		<	0.500		UG/L	5	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2992	ETHYLBENZENE		<	0.500		UG/L	300	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2251	METHYL TERT-BUTYL ETHER		<	3.000		UG/L	13	3	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2989	CHLOROBENZENE		<	0.500		UG/L	70	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2996	STYRENE		<	0.500		UG/L	100	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2987	TETRACHLOROETHYLENE		<	0.500		UG/L	5	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2991	TOLUENE		<	0.500		UG/L	150	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 01 - PRE NO3 BLEND

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MONTHS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5403043_001_001	S1	2979	TRANS-1,2-DICHLOROE THYLENE		<	0.500		UG/L	10	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2984	TRICHLORO ETHYLENE		<	0.500		UG/L	5	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2218	TRICHLORO FLUOROMET HANE		<	5.000		UG/L	150	5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2904	TRICHLORO TRIFLUORO ETHANE		<	10.000		UG/L	1200	10	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2976	VINYL CHLORIDE		<	0.500		UG/L	0.5	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2955	XYLENES, TOTAL		<	0.500		UG/L	1750	0.5	7/14/2021	4	72		2027/07		69520012107141400V	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	S2	REGULATED SOC																		
		2414	1,2,3-TRICHLORO PROPANE		<	0.000		UG/L	0.005	0.005	7/14/2021	7	36		2024/07		69520012107141400S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2051	LASSO (ALACHLOR)		<	1.000		UG/L	2	1	7/14/2021	5	36		2024/07		69520012107141400S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2050	ATRAZINE		<	0.500		UG/L	1	0.5	7/14/2021	5	36		2024/07		69520012107141400S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2931	1,2-DIBROMO-3 - CHLOROPR OPANE		<	0.000		UG/L	0.2	0.01	7/8/2020	5	36		2023/07		69520012007081340S	1371	MOORE TWINING ASSOCIATES, INC.	
		2946	ETHYLENE DIBROMIDE		<	0.000		UG/L	0.05	0.02	7/8/2020	5	36		2023/07		69520012007081340S	1371	MOORE TWINING ASSOCIATES, INC.	
		2037	SIMAZINE		<	1.000		UG/L	4	1	7/14/2021	5	36		2024/07		69520012107141400S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 02 - PRE NO3 BLEND

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5403043_002_002		YETTEM WATER SYSTEM						WELL 02 - PRE NO3 BLEND												
	GP	SECONDARY/GP																		
		1928	ALKALINITY, BICARBONATE	170.000		0.000		MG/L	-----	-----	7/14/2021	7	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1919	CALCIUM	16.000		0.000		MG/L	-----	-----	7/14/2021	8	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1929	ALKALINITY, CARBONATE		<	10.000		MG/L	-----	-----	7/14/2021	7	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1017	CHLORIDE	17.000		0.000		MG/L	500	-----	7/14/2021	7	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1905	COLOR		<	5.000		UNITS	15	-----	7/14/2021	7	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1022	COPPER, FREE		<	50.000		UG/L	1000	50	7/14/2021	7	36		2024/07		69520022107141420L	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2905	FOAMING AGENTS (SURFACTANTS)		<	0.100		MG/L	0.5	-----	7/14/2021	7	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1915	HARDNESS, TOTAL (AS CaCO3)	93.400		0.000		MG/L	-----	-----	7/14/2021	7	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1021	HYDROXIDE AS CALCIUM CARBONATE		<	10.000		MG/L	-----	-----	7/14/2021	7	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1028	IRON		<	100.000		UG/L	300	100	7/15/2022	12	36		2025/07		VI 2245358-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 200.7
		1031	MAGNESIUM	13.000		0.000		MG/L	-----	-----	7/14/2021	8	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1032	MANGANESE		<	20.000		UG/L	50	20	7/14/2021	7	36		2024/07		69520022107141420G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 02 - PRE NO3 BLEND

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5403043_002_002	GP	SECONDARY/GP																	
		1920	ODOR		<	1.000	TON	3	1	7/14/2021	7	36		2024/07		69520022 10714142 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1925	PH	7.760		0.000	pH	-----	-----	7/14/2021	7	36		2024/07		69520022 10714142 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1050	SILVER		<	10.000	UG/L	100	10	7/14/2021	7	36		2024/07		69520022 10714142 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1052	SODIUM	41.000		0.000	MG/L	-----	-----	7/14/2021	7	36		2024/07		69520022 10714142 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1064	CONDUCTIV ITY @ 25 C UMHOS/CM	400.000		0.000	UMHO/CM	1600	-----	7/14/2021	7	36		2024/07		69520022 10714142 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1055	SULFATE	15.100		0.500	MG/L	500	0.5	7/14/2021	7	36		2024/07		69520022 10714142 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1930	TDS	250.000		0.000	MG/L	1000	-----	7/14/2021	7	36		2024/07		69520022 10714142 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		0100	TURBIDITY		<	0.100	NTU	5	0.1	7/14/2021	7	36		2024/07		69520022 10714142 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1095	ZINC		<	50.000	UG/L	5000	50	7/14/2021	7	36		2024/07		69520022 10714142 OG	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
	IO	INORGANIC																	
		1002	ALUMINUM		<	50.000	UG/L	1000	50	7/14/2021	6	36		2024/07		69520022 10714142 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1074	ANTIMONY, TOTAL		<	6.000	UG/L	6	6	7/14/2021	6	36		2024/07		69520022 10714142 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1005	ARSENIC	3.000		2.000	UG/L	10	2	7/14/2021	6	36		2024/07		69520022 10714142 OI	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 02 - PRE NO3 BLEND

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5403043_002_002	RA	RADIOLOGICAL																		
		4109	GROSS ALPHA PARTICLE ACTIVITY		<	1.900	1.900	PCI/L	15	3	12/21/2015	9	108	Interval	2024/12		69520021 51221132 4R	2920	EUROFINS EATON ANALYTICAL (SOUTH BEND)	
	S1	REGULATED VOC																		
		2981	1,1,1- TRICHLORO ETHANE		<	0.500		UG/L	200	0.5	4/27/2018	3	72		2024/04		69520021 80427135 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2988	1,1,2,2- TETRACHLO ROETHANE		<	0.500		UG/L	1	0.5	4/27/2018	3	72		2024/04		69520021 80427135 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2985	1,1,2- TRICHLORO ETHANE		<	0.500		UG/L	5	0.5	4/27/2018	3	72		2024/04		69520021 80427135 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2978	1,1- DICHLOROE THANE		<	0.500		UG/L	5	0.5	4/27/2018	3	72		2024/04		69520021 80427135 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2977	1,1- DICHLOROE THYLENE		<	0.500		UG/L	6	0.5	4/27/2018	3	72		2024/04		69520021 80427135 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2378	1,2,4- TRICHLORO BENZENE		<	0.500		UG/L	5	0.5	4/27/2018	3	72		2024/04		69520021 80427135 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2968	O- DICHLOROB ENZENE		<	0.500		UG/L	600	0.5	4/27/2018	3	72		2024/04		69520021 80427135 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2980	1,2- DICHLOROE THANE		<	0.500		UG/L	0.5	0.5	4/27/2018	3	72		2024/04		69520021 80427135 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2983	1,2- DICHLOROP ROPANE		<	0.500		UG/L	5	0.5	4/27/2018	3	72		2024/04		69520021 80427135 5V	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: WELL 02 - PRE NO3 BLEND

CLASS: CTGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5403043_002_002	S1	REGULATED VOC																		
		2413	1,3-DICHLOROPROPENE		<	0.500		UG/L	0.5	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2969	P-DICHLOROBENZENE		<	0.500		UG/L	5	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2990	BENZENE		<	0.500		UG/L	1	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2982	CARBON TETRACHLORIDE		<	0.500		UG/L	0.5	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2380	CIS-1,2-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2964	DICHLOROMETHANE		<	0.500		UG/L	5	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2992	ETHYLBENZENE		<	0.500		UG/L	300	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2251	METHYL TERT-BUTYL ETHER		<	3.000		UG/L	13	3	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2989	CHLOROBENZENE		<	0.500		UG/L	70	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2996	STYRENE		<	0.500		UG/L	100	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2987	TETRACHLOROETHYLENE		<	0.500		UG/L	5	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	
		2991	TOLUENE		<	0.500		UG/L	150	0.5	4/27/2018	3	72		2024/04		69520021804271355V	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY: TULARE

Sample Point: ST2S1-14395 AVE 384

CLASS: DBPT

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD			
CA5403043_ DST_900		YETTEM WATER SYSTEM						ST2S1-14395 AVE 384															
	DBP	DISINFECTION BYPRODUCTS																					
		2943	BROMODIC HLOROMET HANE		<	1.000		UG/L	-----	1	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				
		2942	BROMOFOR M		<	1.000		UG/L	-----	1	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				
		2941	CHLOROFOR M		<	1.000		UG/L	-----	1	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				
		2454	DIBROMOAC ETIC ACID	1.100		1.000		UG/L	-----	1	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				
		2944	DIBROMOC HLOROMET HANE		<	1.000		UG/L	-----	1	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				
		2451	DICHLOROA CETIC ACID	1.900		1.000		UG/L	-----	1	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				
		2456	TOTAL HALOACETI C ACIDS (HAA5)	5.500		0.000		UG/L	60	-----	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				
		2453	MONOBROM OACETIC ACID		<	1.000		UG/L	-----	1	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				
		2450	MONOCHLO ROACETIC ACID		<	2.000		UG/L	-----	2	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				
		2950	TTHM		<	0.000		UG/L	80	-----	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.				

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: YETTEM WATER SYSTEM

COUNTY:

Sample Point:

CLASS: DBPT

STATUS:

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5403043_ DST_900	DBP	2452	TRICHLORO ACETIC ACID	1.600		1.000		UG/L	-----	1	7/8/2020	4	36		2023/07		69529002 00708141 0D	1371	MOORE TWINING ASSOCIATES, INC.	

Appendix C:
Instructions for Accessing Public Drinking Water Watch

How To Access Individual System's Drinking Water Monitoring Schedule & Water Quality Data

1. Place the following link in the internet address bar:
<https://sdwis.waterboards.ca.gov/PDWW/>
2. Enter your Water System No. and select "Search For Water Systems"

SDWIS Version 3.21

California Public Water Supply Systems Search Parameters

Water System No.

Water System Name

Principal County Served

Water System Type

Water System Status

Primary Source Water Type

[Click Here for the County Map of CALIFORNIA](#)

3. Click on your Water System No. (Link in blue text).

Drinking Water Division

Water Systems

Hide/show columns: [Water System No.](#) | [Water System Name](#) | [Type](#) | [Status](#) | [Principal County Served](#) | [Primary Source Water Type](#)

Display records Search:

Water System No.	Water System Name	Type	Status	Principal County Served	Primary Source Water Type
CA5403043	YETTEM WATER SYSTEM	C	A	TULARE	GW

Showing 1 to 1 of 1 entries (filtered from 8,332 total entries) Previous Next

4. On the left side of the screen, select **Monitoring Schedules** for source monitoring schedule (last sample and next due dates) or **Monitoring Results** for water quality results.

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

Glossary

Contact Info

CA Drinking Water Watch

Water System Details

Water System No. : CA5403043	Federal Type : C
Water System Name : YETTEM WATER SYSTEM	State Type : C
Principal County Served : TULARE	Primary Source : GW
Status : A	Activity Date : 04-28-2014

Water System Contacts

Type	Address	Phone	Email - Web Address
Administrative Contact	5961 S. MOONEY BLVD. VISALIA, CA 93277	Business 559-624-7191	
Physical Location Contact	CA5403043-YETTEM WATER SYSTEM		

Division of Drinking Water District / County Health Dept. Info

Name	Phone	Email	Address
DISTRICT 24 - TULARE	559-447-3300	dwpsdist24@waterboards.ca.gov	265 W. BULLARD AVE., SUITE 101 FRESNO CA 93704

Annual Operating Periods & Population Served

Start Month	Start Day	End Month	End Day	Population Type	Population Served
1	1	12	31	R	350

Service Connections

Type	Count	Meter Type	Meter Size Measure
CB	64	UN	0

Sources of Water

Name	Type Code	Status
WELL 01 - PRE NO3 BLEND	WL	A
WELL 02 - PRE NO3 BLEND	WL	A

Service Areas

Code	Name
R	RESIDENTIAL AREA

Water Purchases

Seller Water System No.	Water System Name	Seller Facility Type	Seller State Asgn ID No.	Buyer Facility Type	Buyer State Asgn ID No.
-------------------------	-------------------	----------------------	--------------------------	---------------------	-------------------------

5. Select Sampling Point corresponding to the source (Link in blue text and is a number).

5A. Monitoring Schedules

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

[Glossary](#)

[Contact Info](#)

CA Drinking Water Watch

Monitoring Schedules

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

The Division of Drinking Water's (DDW's) drinking water quality monitoring schedules identify upcoming required testing of drinking water for water systems in California. These documents should not be used for determining whether water systems are in compliance with monitoring requirements. The purpose for providing these monitoring schedules is to allow water systems to verify that their sampling and analyses have been incorporated into the DDW database and to identify upcoming required monitoring/sampling events.

Notes for Water Systems:

- The monitoring notification documents should be considered "draft," in that they will change with subsequent updates, and as monitoring data are submitted, or as monitoring schedules are revised.
- The monitoring notification documents are derived from the DDW Water Quality database and from schedules maintained by DDW districts.
- If your upcoming monitoring or your data identified as "DUE" are not in agreement with this document, or if you have been advised of any increased monitoring that is not reflected in the report for a particular source, please contact your [District Engineer or LPA representative](#). For a map of the districts, please [click here](#).
- If your notification report for a source is blank, this does not necessarily indicate compliance with all monitoring requirements.
- These notification reports may not reflect compliance with initial monitoring for newly regulated constituents, or constituents that require special monitoring frequencies. For example, the DDW database is unable to accurately forecast the vulnerable non-volatile synthetic organic chemical (SOC) frequency for large water systems serving over 3,300 people of 2 quarters every 3 years.
- Some Nitrate (as N) results under storet code 00618, will have a result of 'N/A' which stands for 'Not Applicable.' This stems from the change in regulation requiring that all nitrate sampling be reported as Nitrate (as N) starting January 1, 2016. Prior nitrate sampling was reported as Nitrate (as NO3). With this change in nitrate reporting requirements, the monitoring schedules have captured the last date of Nitrate (as NO3) sampling and applied it to Nitrate (as N) in determining the next due date [unless there have been Nitrate (as N) samples collected]. The Nitrate (as NO3) result, however, does not carry over to Nitrate (as N) which is why there may be a notation in the 'Constituent Identification' column to reference storet code 71850 for the last nitrate result. In these instances, the 'Constituent Identification' column will say, 'NITRATE (as N) - [see 71850].' Any questions should be referred to your District Engineer.

[Monitoring Schedules for All Sampling Points](#)

Monitoring schedule for all sampling points

Click to view report. Once the report is shown, click on the Export icon on the report header to download.

Monitoring Schedule for Individual Sampling Points

Click on a sampling point number to view the monitoring schedule for the sampling point.
[Click here to bring back the list of sampling points.](#)

Sampling Point	Location	Type
900	ST2S1-14395 AVE 384	
LCR		DS
003	WELL 01 & 02 - NO3 BLEND TANK	
001	WELL 01 - PRE NO3 BLEND	RW
002	WELL 02 - PRE NO3 BLEND	RW

Monitoring schedule for specific sampling points

NOTE: Any *past due* monitoring will have "DUE NOW" in the far-right column. Please schedule this monitoring as soon as possible.

5B. Monitoring Results

Links
[Water System Details](#)
[Water System Facilities](#)
[Monitoring Schedules](#)
[Monitoring Results](#)
[Monitoring Results By Analyte](#)
[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)
[Site Visits](#)
[Consumer Confidence Reports](#)

- 2017
- 2016
- 2015
- 2014

Return Links
[Water System Search](#)
[County Map](#)
Glossary
Contact Info

CA Drinking Water Watch

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

Monitoring Results for Individual Sampling Points

Click on a PS Code to view/download the monitoring results for the sampling point.

Water System Sampling Points					
PS Code	Facility ID	Facility Name	Description	Type Code	Source Class
5403043-001	001	WELL 01 - PRE NO3 BLEND	WELL 01 - PRE NO3 BLEND	RW	DCSGA
5403043-002	002	WELL 02 - PRE NO3 BLEND	WELL 02 - PRE NO3 BLEND	RW	DCSGA
5403043-003	003	WELL 01 & 02 - NO3 BLEND TANK	WELL 01 & 02 - NO3 BLEND TANK		OTHR
5403043-900	DST	DISTRIBUTION SYSTEM	DISTRIBUTION SYSTEM		DBPT
5403043-LCR	DST	DISTRIBUTION SYSTEM		DS	

6. Please contact the Tulare District Office at (559) 447-3300 or DWPDIST24@waterboards.ca.gov if you have any questions.

Appendix D:
Source and Distribution System Bacteriological Monitoring Reports

Bacteriological Distribution Monitoring Report

5403043 Yettem Water System

Distribution System Freq: 1/M

Sample Date	Location	T Coli	E Coli	F Coli	HPC	Type	Cl2	Cl2 Avg	Viol. Type	GWR Satisfied?	Comments
3/6/2023	14246 Ave 384	A	A			Routine	0.79				
2/13/2023	14246 Ave 384	A	A			Routine	0.71				
1/9/2023	14246 Ave 384	A	A			Routine	0.67				
12/12/2022	14246 Ave 384	A	A			Routine	0.50				
11/7/2022	14246 Ave 384	A	A			Routine	0.69				
10/24/2022	14246 Ave 384	A	A			Routine	0.50				
9/22/2022	14246 Ave 384	A	A			Routine	0.66				
8/9/2022	14246 ave 384	A	A			Routine	0.49				
7/15/2022	14246 Ave 384	A	A			Routine	0.93				
6/9/2022	14246 Ave 384	A	A			Routine	0.84				
5/16/2022	14246 Ave 384	A	A			Routine	0.98				
4/25/2022	14246 Ave 384	A	A			Routine	0.97				
3/21/2022	14246 Ave 384	A	A			Routine	0.77				
2/10/2022	14246 Ave 384	A	A			Routine	0.87				
2/10/2022	14246 Ave 384	A	A			Routine	0.87				
1/24/2022	14246 Ave 384	A	A			Routine	0.28				
12/28/2021	14246 Ave 384	A	A			Routine	0.55				
11/19/2021	14246 Ave 384	A	A			Routine	0.60				
10/19/2021	14246 Ave 384	A	A			Routine	0.32				
9/28/2021	14246 Ave 384	A	A			Routine	0.51				
8/23/2021	14246 Ave 384	A	A			Routine	0.39				
7/14/2021	14246 Ave 384	A	A			Routine	0.65				
6/21/2021	14246 Ave 384	A	A			Routine	0.09				
5/24/2021	14246 Ave 384	A	A			Routine	0.52				
4/20/2021	14246 Ave 384	A	A			Routine	0.35				
3/12/2021	14246 Ave 384	A	A			Routine	0.69				
2/18/2021	14246 Ave 384	A	A			Routine	0.4				
1/25/2021	14246 Ave 384	A	A			Routine	0.45				
12/21/2020	4246 Ave 384	A	A			Routine	0.73				
11/1/2020	No sample								MR1		Cit 03-24-21C-011
10/26/2020	14246 Ave 384	A	A			Routine	1.07				
9/28/2020	14246 Ave 384	A	A			Routine	0.32				
8/10/2020	Learning Center	A	A			Routine	0.65				
7/8/2020	Cafeteria (high school)	A	A			Routine	1.2				
6/3/2020	14050 Ave 384	A	A			Routine	0.68				
5/13/2020	US Post Office	A	A			Routine			MR9		no chlorine residual on report
4/3/2020	Learning Center	A	A			Routine	1.1				
3/4/2020	Cafeteria - Yettem High	A	A			Routine	0.55				
2/7/2020	14050 Ave 384	A	A			Routine	1.2				
1/7/2020	US Post Office	A	A			Routine			MR9		no chlorine residual on report or coc
12/9/2019	Learning Center	A	A			Routine			MR9		no chlorine residual on report
11/6/2019	Cafeteria (Yettem High)	A	A			Routine			MR9		no chlorine residual on report
10/4/2019	14050 Ave 384	A	A			Routine	1.2				
9/4/2019	US Post Office HB	A	A			Routine	1.0				
8/5/2019	Learning Center	A	A			Routine	1.2				

<i>Sample Date</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Type</i>	<i>CI2</i>	<i>CI2 Avg</i>	<i>Viol. Type</i>	<i>GWR Satisfied?</i>	<i>Comments</i>
7/10/2019	High School Cafeteria	A	A			Routine	1.9				
6/10/2019	14050 Ave 384	A	A			Routine	0.80				
5/9/2019	US Post Office HB	A	A			Routine	0.95				
4/10/2019	Learning Center	A	A			Routine	0.87				
3/13/2019	Café Yettem High	A	A			Routine	1.8				
2/6/2019	14050 Ave 384	A	A			Routine	1.8				
1/7/2019	Post Office	A	A			Routine	1.5				
12/3/2018	Learning Center	A	A			Routine	1.6				
11/5/2018	Café Yettem High School	A	A			Routine	1.1				
10/1/2018	14050 Ave. 384	A	A			Routine	0.92				
9/4/2018	14026 Ave 384	A	A			Routine	0.72				
8/2/2018	14246 Ave 384	A	A			Routine	0.88				
7/6/2018	14395 Ave 384	A	A			Routine	1.2				
6/5/2018	14050 Ave 389	A	A			Routine	0.40				
5/3/2018	US Post Office	A	A			Routine	0.50				
4/3/2018	Learning Center	A	A			Routine	0.76				
3/22/2018	Learning Center	A	A			Routine	0.88				
2/9/2018	14050 Ave 384	A	A			Routine	0.62				
1/3/2018	Post Office	A	A			Routine	1.9				

Violation Key

MCL	Exceeds the maximum contaminant level	MR5	Incorrect number of repeat samples as follow-up to a positive sample
MR1	No monthly sample for the report month	MR6	No source sample
MR2	No quarterly sample for the report month	MR7	No summary report submitted
MR3	Incorrect number of routine samples for the report month	MR8	Other comments and/or info
MR4	Did not collect 5 routine samples for previous month's positive sample	MR9	CI2 not reported

Source Bacteriological Monitoring Report

5403043 Yettem Water System

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
3/6/2023		Wells: 01,02	Well	QTray	<1.0	<1.0				
2/13/2023		Wells: 01,02	Well	QTray	<1.0	<1.0				
1/9/2023		Wells: 01,02	Well	QTray	<1.0	<1.0				
12/12/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
11/7/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
10/24/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
9/22/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
8/9/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
7/15/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
6/9/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
5/16/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
4/25/2022	13:40	Well 01 - Pre NO3 Blend	Well	Qtray	<1.0	<1.0				
4/25/2022	13:55	Well 02 - Pre NO3 Blend	Well	Qtray	<1.0	<1.0				
3/21/2022	12:15	Well 01 - Pre NO3 Blend	Well	Qtray	<1.0	<1.0				
3/21/2022	12:30	Well 02 - Pre NO3 Blend	Well	Qtray	<1.0	<1.0				
2/10/2022	11:40	Well 01 - Pre NO3 Blend	Well	Qtray	<1.0	<1.0				
2/10/2022	11:40	Well 01 - Pre NO3 Blend	Well	Qtray	<1.0	<1.0				
2/10/2022	11:55	Well 02 - Pre NO3 Blend	Well	Qtray	<1.0	<1.0				
2/10/2022	11:55	Well 02 - Pre NO3 Blend	Well	Qtray	<1.0	<1.0				
1/24/2022	12:40	Well 01	Well	Qtray	<1.0	<1.0				
1/24/2022	13:00	Well 02	Well	Qtray	<1.0	<1.0				
12/28/2021		Wells: 01,02	Well	QTray	<1.0	<1.0				
11/19/2021		Wells: 01,02	Well	QTray	<1.0	<1.0				
10/19/2021		Wells: 01,02	Well	QTray	<1.0	<1.0				
9/28/2021		Wells: 01,02	Well	QTray	<1.0	<1.0				
8/23/2021		Wells: 01,02	Well	QTray	<1.0	<1.0				
7/14/2021		Wells: 1,2	Well	QTray	<1.0	<1.0				
6/21/2021		Wells: 01,02	Well	QTray	<1.0	<1.0				
5/24/2021		Wells: 01,02	Well	QTray	<1.0	<1.0				
4/20/2021		Wells: 01,02	Well	Qtray	<1.0	<1.0				
3/12/2021		Wells: 01, 02	Well	MPN	<1.0	<1.0				
2/18/2021		Wells: 1,2	Well	Qtray	<1.0	<1.0				
1/25/2021		Wells: 1,2	Well	Qtray	<1.0	<1.0				
12/21/2020		Wells: 1,2	Well	Qtray	<1	<1				
10/26/2020		Wells: 01,02	Well	Qtray	<1.0	<1.0				
9/28/2020		Wells: 01, 02	Well	Qtray	<1.0	<1.0				

5403043 Yettem Water System

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
8/10/2020		Wells: 01,02	Well	Qtray	<1.0	<1.0				
7/8/2020	13:40	Well 01	Well	Qtray	1	<1.0				
7/8/2020	13:45	Well 02	Well	Qtray	<1.0	<1.0				
6/3/2020		Wells: 01, 02	Well	Qtray	<1.0	<1.0				
5/13/2020		Wells: 01, 02	Well	QTray	<1.0	<1.0				
4/3/2020		Wells; 01,02	Well	QTray	<1.0	<1.0				
3/4/2020		Wells: 01, 02	Well	QTray	<1.0	<1.0				
2/7/2020		Wells: 01, 02	Well	QTray	<1.0	<1.0				
1/7/2020		Wells: 01,02	Well	QTray	<1.0	<1.0				
12/9/2019		Wells: 1,2	Well	QTray	<1.0	<1.0				
11/6/2019		Wells: 1,2	Well	QTray	<1.0	<1.0				
10/4/2019		Wells: 01, 02	Well	QTray	<1.0	<1.0				
9/4/2019		Wells: 01, 02	Well	QTray	<1.0	<1.0				
8/5/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
7/15/2019	12:45	Well 1	Well	QTray	<1.0	<1.0				
7/10/2019	12:15	Well 01	Well	QTray	11	<1.0				
7/10/2019	12:20	Well 02	Well	QTray	<1.0	<1.0				
6/10/2019		Wells: 01, 02	Well	QTray	<1.0	<1.0				
5/9/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
4/10/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
3/13/2019		Wells: 1,2	Well	QTray	<1.0	<1.0				
2/6/2019		Wells: 1,2	Well	QTray	<1.0	<1.0				
1/7/2019		Wells: 1,2	Well	QTray	<1.0	<1.0				
12/3/2018		Wells: 1,2	Well	MPN	<1.1					
11/5/2018		Wells: 1, 2	Well	QTray	<1.0	<1.0				
10/1/2018		Wells: 1, 2	Well	QTray	<1.0	<1.0				
9/4/2018		Wells: 01, 02	Well	QTray	<1.0	<1.0				
8/2/2018		Wells: 01,02	Well	QTray	<1.0	<1.0				
7/6/2018		Wells: 02, 01	Well	QTray	<1.0	<1.0				
6/5/2018		Wells: 1, 2	Well	QTray	<1.0	<1.0				
5/3/2018		Wells; 1, 2	Well	QTray	<1.0	<1.0				
4/3/2018		Wells: 1, 2	Well	QTray	<1.0	<1.0				
3/22/2018		Wells: 1, 2	Well	QTray	<1.0	<1.0				
2/9/2018		Wells: 1, 2	Well	QTray	<1.0	<1.0				
1/3/2018		Wells: 1, 2	Well	MPN	<1.1					

Appendix E:
Lead and Copper Tap Sample Results Reporting Form



State Water Resources Control Board

Division of Drinking Water

Lead and Copper Tap Sample Results Reporting Form

This form must be submitted by the public water system to the regulating entity (DDW District Office or County Agency) for each round of lead and copper sampling

Report Date: (mm/dd/yyyy)	
Water System Name:	
Water System Number:	
Water System Type:	<input type="radio"/> Community <input type="radio"/> Non-Transient, Non Community
Monitoring Frequency:	<input type="radio"/> 6-month <input type="radio"/> Annual <input type="radio"/> Triennial
# of Samples Required:	
# of Samples Reported:	
	90th Percentile Level (mg/L)
Lead: <i>Action Level = 0.015 mg/L</i>	
Copper: <i>Action Level = 1.3 mg/L</i>	

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
01					
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Sampling Site Change

Each round of sampling should be conducted at the same sampling sites. If an original sampling site is not available, you should collect a tap sample from another site meeting the same Tier criteria as the original site.

You must complete/submit the ***Lead and Copper Tap Sampling Site Change*** form.

Notification of Results

As required by *40 Code of Federal Regulations Section 141.85(d)*, within 30 days of learning of the tap monitoring results, I notified the participants, by mailing or by another method approved by the State, of the lead sample results from their individual taps, provided an explanation of the health effects of lead, listed steps the consumer could take to reduce exposure to lead, provided contact information for the water utility, the maximum contaminant level goal for lead, action level for lead, and any definitions.

Notification was done on _____ by _____
(date)

- ☐ Direct Mail
☐ Posting in public area (NTNC systems only)
☐ Other (please specify below) _____
-

For general information on lead and copper tap sampling, you can refer to the ***SWRCB Lead and Copper Tap Sample Results Guidance Document***. If you have any questions or comments, please contact your regulating entity (Division of Drinking Water District or County Agency).

SIGNATURE:	DATE:
NAME (Print):	TITLE:

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2, 3, or R	Lead (mg/L)	Copper (mg/L)
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					

Appendix F:
Guidance Document for the Preparation of an Operations Plan

Water System Operations Plan Guidance

Overview:

The purpose of this document is to provide guidance for a water system when completing a Water System Operations Plan. However, this guidance is not considered an all-inclusive list of items required in an operations plan. A water system's operations plan should be specific and tailored to the water system and must adequately address the physical operation, maintenance, repair, and troubleshooting of water system facilities; routine monitoring, reporting and record keeping; and emergency response. All Operations Plans must be submitted and are subject to District Office comment and approval. The Operations Plan is a living document that should be updated as necessary to provide overview of the current operation of the water system. All updates should be submitted to the Division for review and approval.

I. Title and System Information

The Operation Plan must include title, date, system name, system number, system address, mailing address, contact name, phone number and email.

II. Brief Description of Water System

The Operations Plan should include a description of the following: Water System Type (Community-CWS, Non-transient Noncommunity-NTNC, and Transient Noncommunity-TNC), number of service connections, population served, operating period (seasonal, year-round, etc.), sources, treatment facilities, and distribution facilities (storage, booster pumps, pressure tanks, etc.).

Include maps, as-built drawings, or other schematics as attachments to the Operations Plan.

Example; System Type: Community-CWS; Service Connections: 100; Population: 300; Operational Period: Year-round; System Description: XYZ water system has one groundwater well (Well No. 1) equipped with a submersible pump capable of producing 300 gallons per minute (gpm). Chlorination is provided using a LMI chemical metering pump. Well No. 1 is pumped directly into a 30,000 gallon storage tank. The booster pump and pressure tanks are used to maintain pressure in the distribution system (40-60 psi). The distribution system consists of 6-inch C900 PVC mains and 1-inch C900 PVC laterals.

III. Record Keeping and Organization Chart

The Operations Plan should include a water system organization chart detailing the management structure and responsibilities of each staff member as it relates to the operation and oversight of the water system.

The Operations Plan should describe the methods of record keeping (digital and hardcopy) and the retention policy. A multi-tabbed water system file is strongly recommended. The file should include all bacteriological and chemical laboratory results (10 year retention), monitoring requirements and an accompanying calendar schedule for all sampling, correspondence from our Division (e.g., water supply permit), all sampling plans (Bacteriological Sample Siting Plan), water main and valve location maps, the well driller's report and County well construction permit that demonstrates conformance to its well

ordinance (schematic documenting adequate horizontal protection of well from sanitary hazards), pump and storage tank information, and their accompanying service records, etc.

IV. Sources

A. Detailed Description

The Operations Plan should include detailed descriptions of source facilities. Not all information needs to be included in the written description; however, attachments should be included that provide pertinent information about the water system facilities (e.g. DWR well completion report, pump information/manufacturer documentations, maps, As-Built drawings, etc.).

B. Routine Operational Procedures (daily or minimum of weekly)

The Water System conducts source site visits for the following: water leaks that could contaminate well, unscreened or openings where sealants can be applied, electrical hazards, chemical hazards (proper use of chemicals around well head). Verify proper operation of pump and controls. Remove rodent feces, dirt, insects, vegetation, any standing water, control gophers/squirrel burrowing around well head to eliminate potential contamination hazards. Take necessary actions to repair all deficiencies at the source site.

Tip: Maintain a log book for each well site that records maintenance and monthly water production and flow rates, water table depths and any maintenance performed.

C. Monitoring and Reporting

1. Bacteriological Monitoring From Sources

Source bacteriological sampling should be described in the sample siting plan and must be collected from all active raw water sources PRIOR to chlorination. The samples are required to be analyzed using the density method (Most Probable Number-MPN). If any sample is positive, notify Division by telephone, for follow-up investigation. Source sampling frequency is dependent on the water system's classification. A report containing the results must be submitted to the Division by the 10th day of the following month.

2. Chemical Source Monitoring

The Operations Plan should specify all chemical source monitoring required by Drinking Water Regulations, which is based on system and source classification. All results must be submitted to the Division's Water Quality Database electronically (electronic data transfer-EDT) by an ELAP Certified Laboratory. The Operations Plan should indicate each source and their corresponding Primary Station Code (PSCode) so that water quality data can be EDT'd. The Operations Plan should include a copy of the appropriate chemical monitoring schedule for the water system's sources.

System monitoring information available at: <https://sdwis.waterboards.ca.gov/PDWW/>

3. Water Production

Drinking Water Regulations require each water source to be equipped with a flow meter. Source water production must be monitored and recorded at least monthly. Water production is required to be reported annually to the Division in the Electronic Annual Report.

V. Treatment Facilities

A. Detailed Description

The Operations Plan should include detailed descriptions of treatment facilities (chlorination, surface water treatment, nitrate, arsenic, etc.). Not all information needs to be included in the written description; however, attachments should be included to provide pertinent information about the treatment facilities (e.g. process flow diagram, manufacturer documentation including operational specifications, As-Built drawings, etc.).

B. Routine Operational Procedures (daily or minimum of weekly)

Check treatment facilities for the following; water leaks, electrical hazards, chemical hazards (proper use of chemicals). Verify proper operation of treatment facility (pumps, filters, chemical pumps, etc.), monitoring instruments, and controls. Inspect the chemical reservoirs for concentration and adequate volume for the operational period (record results). Take necessary actions to repair all deficiencies at the treatment facility.

Tip: Maintain a log book for each treatment facility that records maintenance, monthly water production and flow rates, chemical use and dosages, media condition, and any maintenance performed.

C. Monitoring and Reporting

1. Treatment Plant Monitoring

The Operations Plan must specify all treatment plant monitoring required by Drinking Water Regulations, Domestic Water Supply Permit, and Division. The Operations Plan must outline all required routine monitoring of the treatment plant (turbidity, contact time, chlorine residual, chemical concentrations, dosages etc.), all treatment goals and measures to prevent treatment failure, and response plan in the event that the treated effluent exceeds the treatment goal. The Operations Plan must include reporting forms and templates.

All monthly treatment reports must be submitted to the Division by the 10th day of the following month. The Operations Plan must include the appropriate templates of the monthly reporting forms. For treatment plants removing chemical constituents, all results must be submitted to the Division's Water Quality Database electronically, EDT, by an ELAP Certified Laboratory to the treatment facility's PScore.

VI. Distribution Facilities

A. Detailed Description

The Operations Plan should include detailed descriptions of distribution system facilities (storage tanks, distribution lines, pressure tanks, booster pumps, etc.). Not all information needs to be included in the written description; however, attachments should be included to provide pertinent information about the distribution system facilities (e.g. distribution maps and flow diagrams, manufacturer documentation including operational specifications, As-Built drawings, etc.). The water system's cross-connection control program should also be included in this section.

B. Routine Operational Procedures (daily or minimum of weekly)

The following items and their operational procedures should be addressed in the Operations Plan. Corrective action should be taken to remedy any deficiencies found during inspections.

1. Storage Tanks

Check storage tanks for the following; water leaks, structural damage, proper vent and overflow outlet protection (screens, flapper valve, etc.), volume, float operation, etc. Scheduled inspection and cleaning of storage tank (quarterly, semi-annually, annually, etc.). Record the date of the inspection and cleaning and any observations (e.g., remnants of rodents, sediment, corrosion, etc.).

2. Pressure Tanks

Check pressure tanks for the following; water leaks, structural damage, compressor operation, pressure gauge operation, etc.

3. Gauges and Meters

Inspect all gauges and meters for leaks and proper function daily. Repair or replace as needed (keep record of date). Schedule routine calibration checks to ensure accurate readings are being provided.

4. Valves

Inspect valves for leaks (record observations, repair or replace if leaking). Exercise valves on a schedule, as needed (i.e. quarterly, semi-annually, annually, etc.).

5. Cross-Connections

Inspect water system for potential cross connections on a regular basis (i.e. semi-annually, annually, etc.).

6. Backflow Devices/Assemblies

Backflow devices/assemblies are required to be tested at least annually by a certified Backflow Tester.

7. Booster Pumps/Stations

Visually inspect the starter panel, electric motor, pump and related pump system components. Perform necessary running tests (Amp/Voltage readings and system pressure checks) to monitor operational efficiency.

8. Distribution Lines

Visually inspect the distribution system for leaks on a regular basis. Flush dead end mains or lines periodically (quarterly, semi-annually, annually as needed. Record date and observations made during inspection.

Tip: Maintain a log book for the distribution facilities that records the date of the inspection, observations made during the inspection and any maintenance performed.

C. Monitoring and Reporting

1. Bacteriological monitoring from distribution system

The Operations Plan should include the routine bacteriological sampling procedures and sample in accordance with the most recently District approved Bacteriological Sample Siting Plan. Bacteriological sampling results are required to be submitted to the Division by the 10th day of the following month.

2. Disinfectant Residual Monitoring

For water systems that chlorinate, monitor and record the results from designated locations which are the same locations as the routine bacteriological sample sites. The residuals must be reported with the bacteriological results at the time the bacteriological sample is collected. These results will also be used by distribution and treatment operators when adjusting chemical dosages at the treatment facility.

3. Disinfection Byproduct Rule Monitoring

For community and non-transient noncommunity water systems, the Operations Plan should include the most recently approved Disinfection Byproduct Rule (DBP) Monitoring Plan. The DBP Monitoring Plan should include, at minimum, the frequency of sampling, the required number of samples, and the sampling locations and corresponding PScodes for EDT submittal by an ELAP certified laboratory.

4. Lead and Copper Monitoring

For community and non-transient noncommunity water systems, the Operations Plan should include the most recently approved Lead and Copper Rule (LCR) Monitoring Plan. The LCR Monitoring Plan should include, at minimum, the frequency of sampling, the required number of samples, and sampling locations.

VII. Emergency Response

The Operations Plan should include emergency response procedures to be implemented in the event of a contamination event, a natural disaster, treatment failure, etc.

A. Emergency Notification Plan

The Operations Plan must include a copy of the most current Emergency Notification Plan (ENP). **The Division must be notified immediately in the event of an emergency.**

B. List of equipment for emergency repairs

List all equipment, tools and spare parts on hand that would be used for emergency repairs.

C. List of contractors and operators available for emergency repairs

Contractor Name	Address	Phone #	Equipment	Rental/ Contract
			Steel Tank Welder	
			Electrician	
			General Contractor	
			Plumber	
			Chemicals	
			Operator	

D. List of Sources of needed equipment/supplies not on hand

Supplier Name	Address	Phone #	Equipment	Rental/ Contract
			Tool Company	
			Digging equipment	
			Generator	
			Chemicals	

E. List of distributors or suppliers of replacement parts.

Supplier Name	Address	Phone #	Parts
			PVC pipe, valves, and fittings
			pumps, pressure tank and gauges
			Chlorinator

VIII. Miscellaneous Reporting**A. Electronic Annual Report to the Division of Drinking Water**

Outline the process for completing the Electronic Annual Report (EAR) to the Division of Drinking Water. The EAR is located at: <http://drinc.ca.gov/ear/home.aspx>

B. Consumer Confidence Report

For community and non transient non community water systems, outline the process for completing the Consumer Confidence Report (CCR), the submittal dates (July 1 for customers and October 1 to the Division of Drinking water), and the methods of distribution. Reporting forms should be attached to the Operations Plan. A template is available at:

http://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/CCR.shtml.

IX. Contact Information

The Operation Plan should include contact information.

A. Water System Staff

Name	Address	Phone #	Position	Rental/ Contract

B. Contract Operators

Name	Address	Phone #	Operator Certifications	Certification Nos.

X. Attachments

The Operations Plan should include all necessary attachments referenced in the Operations Plan. Electronic copies of all forms are available upon request. The following is a list of examples of possible attachments.

- A. Monthly water production reports**
- B. Coliform monitoring report forms**
- C. Treatment Reports**
- D. Bacteriological Sampling Siting Plan Guidance**
- E. Water Quality Monitoring Schedule**
- F. Emergency Notification Plan**
- G. DBP Plan**

Appendix J: Seville 2022 Sanitary Survey

State Water Resources Control Board

Division of Drinking Water

October 17, 2022

Celeste Perez, General Manager
Seville Water Company – CA5400550
5961 S. Mooney Blvd.
Visalia, CA 93277

2022 Sanitary Survey

Dear Ms. Perez:

On July 20, 2022, the State Water Resources Control Board, Division of Drinking Water (Division) conducted a sanitary survey of the Seville Water Company water system (Water System). After evaluation of the Water System and completion of the enclosed Sanitary Survey Report, the Division has identified several outstanding deadlines from previous Sanitary Survey Reports from 2018 and 2020. **The Division does not extend directive deadlines. The following directives are past due and require immediate attention:**

1. The Water System must have a cross connection control survey completed by a certified cross connection control specialist.
2. The Water System must submit an Operations Plan to the Division for review and approval.
3. The Water System must submit a revised Bacteriological Sample Siting Plan (BSSP) to the Division for review and approval.

In addition to the directives above, the following was identified in this Sanitary Survey:

1. By **November 1, 2022**, the Water System must submit an updated emergency notification plan to the Division.

If you have any questions regarding this letter or the Sanitary Survey Report, please contact the Tulare District office at (559) 447-3300 or by email at DWPDIST24@waterboards.ca.gov.

Sincerely,

Kristin Willet Digitally signed by Kristin Willet
Date: 2022.10.17 10:28:30 -07'00'
Water Boards

Kristin Willet, P.E.
Senior Water Resource Control Engineer, Tulare District
SOUTHERN CALIFORNIA BRANCH
DRINKING WATER FIELD OPERATIONS

cc: [all email only]
Nilsa Gonzalez
Tulare County Environmental Health Division
NGonzale@tularehhsa.org

Jose Padilla
Contract Operator
Jose_padilla2010@yahoo.com

Cruz Perez
Contract Operator
Cruzperez0323@gmail.com

Small Water System Evaluation and Inspection Report
Drinking Water Field Operations Branch: Tulare District

Seville Water Company
System No. 5400550

Contact:	Ms. Celeste Perez	System Type:	Community Water System
Inspection Date:	July 20, 2022	Inspected by:	Kristin Willet, P.E.

I. INTRODUCTION

On July 20, 2022, the State Water Resources Control Board, Division of Drinking Water (Division) conducted a sanitary survey of the Seville Water Company water system (Water System). Mr. Cruz Perez, contract operator for Seville, assisted the Division with the sanitary survey. The Water System was last inspected by the Division on December 16, 2019, as a routine sanitary survey.

PERMIT STATUS

The Water System currently operates under Domestic Water Supply Permit No. 03-24-20PA-023 issued by the Division on August 26, 2020. A comprehensive list of the permit provisions within the permit amendment are provided below:

1. The Seville Water Company water system shall comply with all the requirements set forth in the California Safe Drinking Water Act, California Health and Safety Code and any regulations, standards or orders adopted there under.
2. The only approved sources of domestic water supply for the Seville Water Company water system are as follows:

Source	PS Code	Status
Well 01 – Raw	CA5400550_001_001	Active
Well 02 – Raw	CA5400550_003_003	Active

3. The only approved treatment for the Seville Water Company water system is continuous chlorination using NSF/ANSI 60 certified sodium hypochlorite solution.
4. No other sources or treatment (as described in provisions No. 2 and 3 above) shall be used by the Seville Water Company water system and no changes, additions, or modifications shall be made to the sources or treatment unless an amended water permit has first been obtained from the Division.
5. All personnel who operate distribution facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The

Seville Water Company water system is classified as a D1 water system and shall be operated by a D1 certified distribution operator or higher.

6. The Seville Water Company water system shall comply with Title 17 of the California Code of Regulations, to prevent the water system from being contaminated from possible cross-connections. The Seville Water Company water system shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.
7. The Seville Water Company water system shall submit an electronic Annual Report (EAR) each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
8. The Seville Water Company water system shall record production data from the active sources at least monthly. The monthly water production shall be reported annually to the Division in the EAR.
9. The Seville Water Company water system shall collect monthly raw water samples from each source for analyses of total coliform and fecal coliform or *E. coli* bacteria. The coliform test shall be performed using a density analytical method and the results reported in units of MPN/100mL. The results shall be submitted to the Division by the 10th day of the following month.
10. The Seville Water Company water system shall monitor for coliform bacteria in the distribution system at least monthly and in accordance with an approved Bacteriological Sample Siting Plan (BSSP). The Division shall be notified immediately if any distribution system or source sample shows the presence of *E. coli* bacteria or if more than one bacteriological sample shows the presence of coliform bacteria during a single month.
11. The Seville Water Company water system shall prepare a Consumer Confidence Report (CCR) annually, which must be distributed to customers and a copy provided to the Division by July 1 of each year. The Seville Water Company water system shall also provide the Division with a certification form by October 1 of each year that certifies the report has been distributed to customers.
12. The Seville Water Company water system shall conduct Stage 2 Disinfection Byproduct (DBP) monitoring. The monitoring results must be submitted via electronic data transfer (EDT) to the following PS Code:

ST2 Monitoring Site	PS Code
ST2S1 – 15348 Ave 381	CA5400550_DST_900

13. The Seville Water Company water system shall submit a monthly chlorination log to the Division by the 10th day of the following month.
14. The Seville Water Company water system shall operate the continuous chlorination treatment facility in accordance with a Division-approved Operations Plan. Any changes to the Operations Plan shall be submitted to the Division for review and approval prior to implementation.

It should be noted that phase two of the improvement project will include the addition of a third groundwater source of supply for the Yettem water system and an interconnection between the Yettem and Seville water systems. The interconnection will result in a consolidation of the two water systems to form the Yettem-Seville Community Services District water system.

DESCRIPTION OF SYSTEM

The Water System is owned by the Yettem-Seville Community Services District (CSD). The CSD was formed in June 2020 and ownership of the Water System was transferred to the CSD from Tulare County in July 2022. The Water System is classified as a community water system (CWS), which serves an approximate population of 691 people through 90 service connections. The domestic water supply is obtained from two active groundwater wells identified as Wells 01 and 02. Continuous chlorination is the only treatment provided to the source water. Storage is provided by one 15,000-gallon welded steel storage tank and one 211,000-gallon bolted steel storage tank.

ENFORCEMENT HISTORY

The following enforcement actions have been issued since the last sanitary survey report:

Citation No. 03-24-21C-010; issued January 2021

The Water System failed to collect and report one bacteriological sample during November 2020.

It should be noted that at the time of inspection the Water System had a standing boil water notice since July 11, 2022. The notice was issued after the Water System experienced a water outage due to Wells 01 and 02 failing to meet the demands of the system. Emergency hauled water was provided after the Division and Tulare County Office of Emergency Services were informed of the outage. Hauled water is still being delivered to the Water System on a weekly basis. Nearly all residents, as well as the school that is served by the Water System, are on emergency conservation orders and have been enrolled in the Tulare County bottled water program, funded through the State Water Resources Control Board, Division of Financial Assistance.

SERVICE AREA

The Water System is located approximately 15 miles north of the City of Visalia, CA. The service area for the Water System is comprised of 90 metered service connections consisting primarily of residential housing. The surrounding land use area is largely agricultural. The Yettem Water System is located two miles west of the Water System. A locational map of the Water System is included in Appendix A.

II. INVESTIGATION AND FINDINGS

SOURCES OF SUPPLY

The Water System's source of supply is from two active groundwater sources identified as Well 01 and Well 02. A description of each source is provided below. Photographs of the well sites are included in Appendix A.

Active Sources:

Well 01, Active - Treated, Groundwater, (CA5400550_001_001)

DWR Well Completion Report:	Yes
Date of Well Completion:	January 1960
Well Depth:	125 feet
Sanitary Seal Depth:	Unknown
Well Casing:	16-inch diameter conductor casing to 52 feet and 12-inch diameter steel casing to 118 feet; perforations between 60 and 80 feet.
Flow Meter:	Yes
Pump Type:	Submersible
Pump Make and Model:	Unknown
Pump Size:	7.5-horsepower (hp)
Well Capacity:	10 gallons per minute (gpm)
Source Discharge:	Directly to the 15,000-gallon welded steel storage tank
Source Operation:	Water level in the 15,000-gallon storage tank
Comments:	Well 01 is the Water System's secondary source of supply and is seldomly used due to low production and excessive sanding.

Well 02, Active - Treated, Groundwater, (CA5400550_003_003)

DWR Well Completion Report:	Yes
Date of Well Completion:	August 2014

Well Depth: 300 feet
Sanitary Seal Depth: 85 feet
Well Casing: 8 5/8-inch diameter steel casing to 300 feet; perforations between 80 to 160 feet and 180 to 300 feet.
Flow Meter: Yes
Pump Type: Submersible
Pump Make and Model: Unknown
Pump Size: 10-hp
Well Capacity: 100 gpm
Source Discharge: Directly to the 15,000-gallon welded steel storage tank
Source Operation: Water level in the 15,000-gallon storage tank
Comments: Well 02 is the Water System primary source of supply.

Source Water Assessments

A source water assessment was completed for Well 01 by Tulare County in September 2002. A Possible Contaminating Activities (PCA) Inventory Form was completed for Well 02 by the contract operator, Mr. James Derby, in September 2018. Wells 01 and 02 are considered most vulnerable to known contaminant plumes, agricultural drainage, sewer collection systems, agricultural/irrigation wells, and confirmed leaking underground storage tanks.

WATER PRODUCTION

Based on the information reported to the Division in the 2014 through 2021 electronic Annual Reports, the population, number of service connections, annual production, and maximum month of production is outlined in Table 1 below.

Table 1 - Production Data

Year	Population	Service Connections	Annual Production (Gallons)	Max. Month (Gallons)
2014	400	77	15,469,200 ¹	2,596,000 (Jul.)
2015	400	77	25,325,700	4,248,700 (Jul.)
2016	400	77	19,495,030	2,600,500 (Jun.)
2017	400	77	22,132,100	3,108,600 (Jul.)
2018	400	77	21,332,930	2,888,400 (Jul.)
2019	480	90	25,033,000	3,150,000 (Jun.)
2020 ²	691	90	2,491,572	269,700 (Oct.)
2021	691	90	19,077,000	2,660,000 (Jun.)

1. The 2014 annual production value does not include data for the months of January, February, and March.

2. The 2020 EAR reported production data appears to be inaccurate. Demand calculations are not provided below for this year.

ADEQUACY OF SUPPLY

Production data, as reported by the Water System, and peaking factors established in the California Waterworks Standards were used to determine the Water System's Average Day Demand (ADD), Maximum Day Demand (MDD), and Peak Hour Demand (PHD). The adequacy of supply is determined by comparing the Water System's demands with its total source capacity which includes active and standby sources, storage capacity, and emergency interconnections with other water systems. The Water System's ADD, MDD, and PHD for the most recent seven years, except for 2020, and the total source capacity are provided in Tables 2 and 3, respectively below. It should be noted that the capacities listed in Table 3 are estimates provided by the Water System.

Table 2 - Average Day, Maximum Day & Peak Hour Demands

Year	ADD (gpm)	MDD (gpm)	PHD (gpm)
2014	39	87	131
2015	48	143	214
2016	37	90	135
2017	42	104	157
2018	41	97	146
2019	48	109	164
2021	36	92	139

Table 3 - Total Active Source Capacity

Source	Capacity (gpm)
Well 01	10
Well 02	100
Total Capacity	110

The total combined source capacity of the Water System is approximately 110 gpm. Based on the highest reported water usage for 2015, the Water System has adequate source capacity to supply the ADD of 48 gpm. However, the Water System does not have the source capacity to meet the MDD and PHD of 143 gpm and 214 gpm, respectively.

California Waterworks standards require water systems serving less than 1,000 service connections to have storage capacity equal to or greater than MDD, unless the water system can demonstrate that it has an additional source of supply or has an emergency source connection that can meet the MDD requirement. The Water System has a total

of 226,000 gallons of storage, which is equivalent to approximately 26 hours of MDD. Again, the Water System is in the process of a water system improvement project that will ultimately consolidate the Seville and Yettem water systems. The Water System is also in the process of applying for funding with the Department of Water Resources to drill a new well for the Seville system while the Phase 2 of the Yettem-Seville consolidation project.

STORAGE

Storage is provided by one 15,000-gallon welded steel storage tank and one 211,000-gallon bolted steel storage tank.

The 15,000-gallon tank was installed in 2014 and is located at the site of Wells 01 and 02. The tank is configured with a top inlet and bottom outlet and is equipped with a screened top vent and overflow pipe. Both Wells 01 and 02 discharge separately to the 15,000-gallon tank and are controlled by the water level in the tank. Well 02 may bypass the tank if needed. Water from the 15,000-gallon tank is boosted through two 900-gallon hydropneumatic pressure tanks using two 7.5-hp vertical centrifugal pumps.

The 211,000-gallon bolted steel storage tank was installed in 2019 and is located in the northwest region of the community. The tank is configured with a bottom inlet and outlet and is equipped with a screened roof vent, overflow pipe, caged ladder, and exterior water level indicator. The tank is filled from the distribution system during off-peak hours. Stored water is discharged out to the distribution system through a 5,000-gallon hydropneumatic pressure tank using two 15-hp centrifugal pumps. A high-flow 40-hp centrifugal pump is also available to keep up with demand and fire flow purposes. The two 15-hp booster pumps are activated at 45 pounds per square inch (psi) and the high-flow booster pump is activated at 35 psi. The 211,000-gallon tank is also equipped with a recirculation line that allows the Water System to exercise the high-flow 40-hp booster pump.

The wells, booster stations, and tanks are controlled with a programmable logic controller (PLC). The PLC has been programmed with several modes and set points that allow the Water System to operate and pressurize the system for various scenarios. The Water System must submit an Operations Plan to the Division that includes details on the tank-fill modes, set points, low/high-level alarms, and any other programmed operational parameters.

The Division recommends that storage tanks be inspected internally at least once every five years to verify the integrity of the tank coating, check the condition of the inside surface of the tank walls, and to clean the tanks as needed. It is unclear when the Water System last cleaned and inspected the interior of the 15,000-gallon storage tank. The 211,000-gallon tank was installed in 2019. As such, the Water System should plan on inspecting and cleaning the tank in 2024.

DISTRIBUTION SYSTEM

The Water System recently installed a new distribution system and sanitary sewer system as part of phase one of the two-phase water system improvement project for the Seville and Yettem water systems. The old distribution system was in poor and failing condition which required the Water System to remain on a long-term Boil Water Notice due to intermittent outages. The new distribution system consists of 8-inch to 6-inch diameter C900 polyvinyl chloride (PVC) mains with 2-inch to 1-inch diameter service laterals. Distribution system pressure is maintained between 40 and 60 psi.

TREATMENT FACILITIES

The Water System provides continuous chlorination treatment to the water produced by Wells 01 and 02. A 12.5% solution of sodium hypochlorite is injected directly into the discharge line of Well 02 upstream of the 15,000-gallon storage tank. Well 01 discharges directly to the storage tank to blend with the chlorinated water from Well 02. The sodium hypochlorite solution is stored at the well site in a 35-gallon polyethylene tank inside a fiberglass enclosure. The chlorination equipment is activated upon startup of Well 02 and consists of an Iwaki (Walchem) E-Class chemical feed pump. The chemical feed pump has a capacity of 0.6 gallons per hour (gph) at 110 psi.

The Water System also provides continuous chlorination treatment at the site of the new 211,000-gallon storage tank. A 12.5% solution of sodium hypochlorite is injected directly to the booster pump manifold line upstream of the 5,000-gallon hydropneumatic pressure tank. The sodium hypochlorite solution is stored at the tank site in a 50-gallon polyethylene drum inside a fiberglass enclosure. The chlorination equipment consists of a Grundfos DDA chemical feed pump. The chemical feed pump has a capacity of 15.8 gph at 145 psi. An emergency eye-wash station is installed adjacent to the chlorination equipment at the new tank site.

The chemical solution tanks and feed pumps appear to be adequately sized. A free chlorine residual of at least 1.0 mg/L is maintained in the distribution system.

III. WATER QUALITY MONITORING

SOURCE MONITORING

A summary of the recent source water quality monitoring results and next due dates is included in Appendix B. Additionally, the current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>. Instructions for accessing this information is included in Appendix C.

Bacteriological

Due to continuous chlorination, the untreated well water from Wells 01 and 02 must be sampled monthly for total coliform bacteria at a sample tap located prior to the chlorine injection port. This is required in order to verify that the wells are not producing water that contains coliform bacteria. A summary of source water bacteriological sample results is included in Appendix D.

General Mineral, General Physical, and Inorganic Chemicals

The Water System is required to monitor its active groundwater sources for general mineral (GM), general physical (GP), and inorganic (IO) chemical water quality every three years, except for nitrate which has a different monitoring frequency.

The Water System last sampled Wells 01 and 02 for GM, GP, and IO chemicals in August 2020, except for calcium, hardness, and magnesium which were sampled in July 2021. All GM, GP, and IO chemical monitoring results for both wells were below the respective maximum contaminant levels (MCLs). The Water System is next due to monitor Wells 01 and 02 for GM, GP, IO by the end of 2023.

Nitrate

The Water System is required to monitor active groundwater sources for nitrate (as N) annually if monitoring data indicates nitrate concentrations of less than one-half the MCL of 10 mg/L and quarterly if the concentrations are greater than or equal to one-half the MCL. Both sources produce water with nitrate concentrations greater than 5 mg/L and are on a quarterly monitoring frequency. The nitrate MCL has never been exceeded. Wells 01 and 02 were last sampled in May 2022 and the nitrate result was 8.4 mg/L and 5.9 mg/L, respectively. The next round of nitrate monitoring is scheduled for the third quarter of 2022.

Volatile Organic Chemicals (VOCs)

The Water System submitted a monitoring waiver application for volatile organic chemicals (VOCs) for the 2017-2019 monitoring period. The monitoring waiver was approved for select VOCs. The monitoring schedule was modified to reflect the new due dates and is available online. Well 01 was last sampled for VOCs in 2020. Well 02 was last sampled for VOCs in 2021. The results were all non-detect. The next round of VOC monitoring for both sources is due in the 2023-2025 monitoring period.

Synthetic Organic Chemicals (SOCs)

The Water System is required to sample Wells 01 and 02 at a three-year frequency for synthetic organic chemicals (SOCs). Wells 01 and 02 were last sampled for SOCs in August 2020, except for 1,2,3-trichloropropane (1,2,3-TCP) which was sampled in

October 2021 and dibromochloropropane (DBCP) and ethylene dibromide (EDB) in July 2021. The SOC results were all non-detect. The next round of SOC monitoring for both sources is due in the 2023-2025 monitoring period.

Radiological Monitoring

Initial radiological monitoring is based on the collection of four consecutive quarterly samples of gross alpha and radium-228. If the results from the first two quarters of initial monitoring are below the detection limit for the purposes of reporting (DLR), the final two quarters of initial monitoring may be waived. After initial monitoring is complete, no additional monitoring is required for radium-228. Subsequent monitoring frequencies for gross alpha is based on the results of the last sample collected. It should be noted that if the gross alpha result for any single sample is greater than 5 pCi/L, analysis for uranium in *that same sample* is required.

Triggered Monitoring:

Uranium:

If the $GA + (0.84 * CE)$ for any single sample is greater than 5 pCi/L, analysis for U in that same sample, is required.

Total Radium:

If the $GA + (0.84 * CE) - U$ is greater than 5 pCi/L, analysis for total radium in that same sample, is required.

Triggered monitoring needs to be communicated to the laboratory on the chain of custody at the time the sample is submitted.

The Water System has completed the initial gross alpha and radium-228 monitoring requirements for Wells 01 and 02. As such, the Water System is no longer required to monitor for radium-228. Well 01 was last sampled for gross alpha in August 2014 and the result was 2 pCi/L. Well 02 was last sampled for gross alpha in January 2018 and the result was non-detect. Wells 01 and 02 are currently on a nine-year monitoring frequency for gross alpha. Therefore, the next gross alpha sample from Wells 01 and 02 is scheduled for 2023 and 2027, respectively.

DISTRIBUTION SYSTEM MONITORING

Bacteriological

Based on the population and number of service connections, the Water System is required to collect at least one routine bacteriological sample each month from the distribution system. The sample must be analyzed for total coliform bacteria with results sent to the Division by the 10th day of the following month. A summary of the distribution bacteriological sample results is included in Appendix D.

Bacteriological samples should also be collected in accordance with an approved Bacteriological Sample Siting Plan (BSSP). The current BSSP on file with the Division is dated March 21, 2018. However, the BSSP should be revised to reflect the new designated sample site stations that were installed as part of the Seville and Yettem water system improvement project. Additionally, the revised total coliform rule (rTCR) was adopted in July 2021, requiring all water systems to update their BSSP. **The Water System was directed to provide an updated BSSP in the 2020 sanitary survey. This directive remains outstanding and must be addressed by the Water System immediately. By August 31, 2020, the Water System must submit a revised BSSP to the Division for review and approval.** Guidelines for completing a BSSP are included in Appendix F and an instructional video is also available at <https://youtu.be/fc7MFjpEcvU>.

Lead and Copper Monitoring

The Water System is required to comply with the Lead and Copper Rule (LCR) and conduct lead and copper tap monitoring during each monitoring period. Compliance with the lead and copper action levels is based on the 90th percentile lead and copper results. The 90th percentile for lead and copper should be less than the lead and copper action levels of 0.015 mg/L and 1.3 mg/L, respectively. A summary of all lead and copper tap monitoring results is outlined in Table 4 below. The next round of lead and copper tap monitoring from the distribution system is due between June 1 and September 30, 2024, see Table 5 below.

Table 4 – Lead and Copper Tap Monitoring Results

Monitoring Period	Sample Date(s)	No. of Samples	Lead 90 th Percentile Result (mg/L)	Copper 90 th Percentile Result (mg/L)	No. of Samples Exceeding Action Level
3YR2019-2021	7/30/2021	5	0.0	0.0	--
3YR2016-2018	7/27/2018	5	0.0	0.056	--
3YR2013-2015	6/26/2015	5	0.0	0.06	--
3YR2012-2014	6/15/2012	10	0.0	0.037	--
3YR2009-2011	7/29/2009	10	0.005	0.014	1 (Lead)
6M2ND-2000	9/21/2000	10	0.011	0.0	--
6M1ST-2000	4/18/2000	11	0.0	0.0	--

Table 5 – Future Lead and Copper Tap Monitoring Period

Frequency	No. of Samples Required	Monitoring Period	Next Monitoring Period Begin	Next Monitoring Period End	Next Sample Due Date
3 years	5	3YR2022-2024	6/1/2024	9/30/2024	9/30/2024

The Division has established electronic reporting of the lead and copper data via CLIP using the PS Code **CA5400550_DST_LCR**. The Water System must complete and submit a Lead and Copper Tap Sample Results Reporting Form with all subsequent lead and copper monitoring results. A Lead and Copper Tap Sample Results Reporting Form is included in Appendix E.

Disinfection Byproduct (DBP) Monitoring

Due to the implementation of continuous chlorination, the Water System is required to comply with the Stage 2 Disinfection Byproduct Monitoring Rule (DBPR). To comply with Stage 2 DBPR monitoring requirements, the Water System is required to collect one DBP sample from the distribution system every three years during a month of the warmest water temperature. The sample must be analyzed for total trihalomethanes (TTHMs) and haloacetic acids (HAA5s). The results of the Stage 2 DBP monitoring must be sent to the Division electronically using the PS Code listed in Table 6 below.

Table 6 – Stage 2 DBP Monitoring Site

ST2 DBP Monitoring Site	PS Code
ST2S1-15348 Ave 381	CA5400550_DST_900

The last Stage 2 DBP sample was collected in July 2020. The results for TTHMs and HAA5s were 0.011 mg/L and non-detect, respectively. The Water System must monitor again for Stage 2 DBP in July 2023.

Asbestos

Asbestos monitoring from the distribution system is not required since the system does not have any asbestos cement distribution piping.

IV. OPERATIONS AND MAINTENANCE

Operator Certification

The Water System's distribution system is classified as a D1 distribution system and requires a certified distribution system operator with a minimum D1 certification. Mr. Jose Padilla is the Water System's designated operator. Mr. Jose Padilla is a certified D1 distribution operator (Certification No. 27640) and T2 treatment operator (Certification No. 25926). Per Title 22, Section 63770, California Code of Regulations, water systems shall utilize only certified distribution operators to make decisions addressing the following operational activities:

- 1) Install, tap, re-line, disinfect, test and connect water mains and appurtenances.
- 2) Shutdown, repair, disinfect and test broken water mains.
- 3) Oversee the flushing, cleaning, and pigging of existing water mains.
- 4) Pull, reset, rehabilitate, disinfect and test domestic water wells.
- 5) Stand-by emergency response duties for after hours distribution system operational emergencies.
- 6) Drain, clean, disinfect, and maintain distribution reservoirs.

The Water System shall utilize either certified distribution operators or treatment operators that have been trained to make decisions addressing the following operational activities:

- 1) Operate pumps and related flow and pressure control and storage facilities manually or by using a system control and data acquisition (SCADA) system.
- 2) Maintain and/or adjust system flow and pressure requirements, control flows to meet consumer demands including fire flow demands and minimum pressure requirements.

The Water System shall utilize either certified distribution operators or treatment operators to make decisions addressing the following operational activities:

- 1) Determine and control proper chemical dosage rates for wellhead disinfection and distribution residual maintenance.
- 2) Investigate water quality problems in the distribution system.

Cross Connection Control

Based on the 2021 electronic Annual Report, the Water System does not have a cross connection control program coordinator. The Water System is required to maintain a Cross Connection Control Program which shall include the following elements (as applied from Title 17, California Code of Regulations, Section 7584):

- 1) The conducting of surveys to identify water user premises or locations where cross connections are likely to occur,
- 2) The provisions of backflow protection by the water user at the user's connection or within the user's premises or both,
- 3) The provision of at least one person trained in cross connection control to carry out the cross-connection program,
- 4) The establishment of a procedure or system for annual testing of backflow preventers, and
- 5) The maintenance of records of locations, tests, and repairs of backflow preventers.

Backflow Prevention Device Testing

Regulation requires all backflow prevention devices to be tested annually. Copies of the testing records must be kept on file with the Water System for a minimum of three years.

The Water System was directed to complete a cross connection control survey or submit a timeline to the Division for having one completed in the 2018 Sanitary Survey Report. **This directive remains outstanding and the water system is still required to have a cross connection control survey completed by a certified cross connection control specialist.** A cross-connection control guidance document for CWSs is included in Appendix G.

Complaints

The Water System must keep records of all complaints received and actions taken to correct the problems related to the complaints. According to the 2021 electronic Annual Report, the Water System received no customer complaints.

Operations Plan

The Division does not have an approved Operations Plan on file for the Water System. The Water System was directed to complete and submit an Operations Plan to the Division in the 2018 Sanitary Survey Report. **This directive remains outstanding, and the Water System is still required to submit an Operations Plan to the Division for review and approval.** Again, the Operations Plan should include details on the tank-fill modes, set points, low/high-level alarms, and any other programmed operational parameters.

Emergency Notification Plan (ENP)

The current Emergency Notification Plan (ENP) on file with the Division is dated August 23, 2019. The ENP specifies that customers will be notified of an emergency via door-to-door delivery, posted notification, and an emergency notification message system.

The Division has updated contacts for the Tulare District and requires an updated ENP from the Water System. The updated ENP template is provided in Appendix H. **By November 1, 2022, the Water System must submit an updated ENP to the Division.**

Consumer Confidence Report (CCR)

The Water System is required to complete a Consumer Confidence Report (CCR) on an annual basis and provide a copy to all residents and the Division by July 1 of each year. In addition, the Water System is required to provide the Division with a CCR Certification Form by October 1 of each year certifying that the CCR has been distributed to customers. The Water System submitted the 2021 CCR and certification form in June 2022.

Electronic Annual Report (EAR)

All public water systems are required to provide updated water system information to the Division annually in the electronic Annual Report (EAR). Several portions of the 2021 EAR were lacking pertinent information. In the future, the Water System must ensure that all required fields are completed, and information submitted is accurate.

Water System Resiliency and Preparedness

The effects of climate change on CWS facilities and operations is a concern and priority of the Division, which is documented in its Comprehensive Climate Change Resolution No. 2017-12, adopted in March 2017. The Division is reviewing each water system's preparedness for climate change with the goal to increase awareness and familiarization to the effects of climate change to facilities and operations, encourage the use of EPA's Climate Resilience Evaluation and Awareness Tool (CREAT) or equivalent, and to document and the CWS' efforts in climate change.

As part of the 2021 EAR, CWSs were asked to identify their vulnerabilities, and rank them as either high, medium or low sensitivity, and proposed or implemented projects to prepare for the impacts from climate change. The Water System provided responses to these questions and has no sensitivity to low sensitivity to the potential climate-related impacts. The Water System indicated that they were aware of the CREAT tool developed by USEPA for identifying climate change vulnerabilities. It is unclear if the Water System has had an opportunity to use the CREAT (or similar tool) to identify vulnerabilities to the water system sources and facilities. The Division strongly encourages utilities to evaluate climate change vulnerabilities using tools such as CREAT and engaging in a conversation both within your water system organization and with customers on how to plan and prepare for being resilient to provide clean and safe water reliably and adequately under all current and future conditions.

As previously described, the Water System is in the process of consolidating with Yettem, as well as pursuing funding for a new well that will serve Seville in the meantime. In July 2022, the Water System experienced water outages due to lack of source capacity to meet demand. The Water System implemented emergency conservation measures including no outdoor watering. Additionally, the Water System began billing customers based on meter readings in September 2022.

V. APPRAISAL OF SANITARY HAZARDS & PUBLIC HEALTH SAFEGUARDS

The Seville Water Company water system relies primarily on Well 02 to supply the demands of the system and has Well 01 as a backup source for redundancy. The total source capacity of the system is approximately 110 gpm. The total storage capacity of the system is 226,000 gallons.

The Water System recently replaced the distribution system piping and added a 211,000-gallon bolted steel storage tank and booster station as part of a two-phase water system improvement project for the Seville and Yettem water systems. An interconnection between the two water systems and eventual consolidation is forthcoming (Phase two). The Water System was under a long-term Boil Water Notice due to intermittent outages from failing mains (issued June 2015). The Boil Water Notice was rescinded in May 2020. A Boil Water Notice was issued again in July 2022 due to water outages. Wells 01 and 02 were unable to meet demands of the system. The Water System received emergency services to provide bottled water for potable use and hauled water for the distribution system for sanitary purposes.

Wells 01 and 02 produce water with nitrate concentrations greater than one-half the nitrate MCL. The Water System must continue to monitor both sources quarterly for nitrate. The current water quality monitoring schedule and water quality monitoring results can be accessed through the public version of Drinking Water Watch at <https://sdwis.waterboards.ca.gov/PDWW/>. Overall, the water supply facilities are in good condition and appear to be operating satisfactorily under competent supervision.

The following items need to be addressed by the Water System:

1. By **November 1, 2022**, the Water System must submit an updated emergency notification plan to the Division.

Outstanding directives from the 2018 and 2020 Sanitary Survey Report:

1. The Water System must have a cross connection control survey completed by a certified cross connection control specialist.
2. The Water System must submit an Operations Plan to the Division for review and approval.


3. The Water System must submit a revised Bacteriological Sample Siting Plan (BSSP) to the Division for review and approval.

Appendices

- Appendix A: Location Map & Photo Index
- Appendix B: Last Sample & Next Due Date Summary Reports
- Appendix C: Instructions for Accessing Individual Water System's Water Monitoring Schedule and Water Quality Data
- Appendix D: Source Water and Distribution System Bacteriological Monitoring Reports
- Appendix E: Lead and Copper Tap Sample Results Reporting Form
- Appendix F: Guidelines for Completing a Bacteriological Sample Siting Plan (BSSP)
- Appendix G: Cross Connection Control Guidance for Community Water Systems
- Appendix H: Emergency Notification Plan Template (ENP)
- Appendix I: Water System Operations Plan Guidance

Appendix A:
Location Map & Photo Index

Appendix A
Seville Water Company - CA5400550
Location Map



Appendix A

Seville Water Company - CA5400550

Sanitary Survey Photographs

Well 01 (CA5400550_001_001):

- Date Drilled: January 1960
- Depth: 125 feet
- Type: Submersible
- Pump Size: 7.5-hp
- Capacity: 10 gpm



Well 02 (CA5400550_003_003):

- Date Drilled: August 2014
- Depth: 300 feet
- Type: Submersible
- Pump Size: 10-hp
- Capacity: 100 gpm



Chlorination Equipment (1):

- Location: Chlorine solution is injected to the discharge line of Well 02 and blended in the 15,000 gallon storage tank with water from Well 01.
- Storage: 35 gallon poly. tank
- Chemical Pump:
 - ◇ Make: Walchem E-Class
 - ◇ Capacity: 0.6 gph/150 psi



Appendix A

Seville Water Company - CA5400550

Sanitary Survey Photographs

Storage Tank (1):

- Location: Downstream of Wells 01 and 02
- Volume: 15,000 gallons
- Material: Welded steel



Booster Station (1):

Downstream of 15,000 gallon storage tank

Pumps:

- Type: Centrifugal
- Size: 2 x 7.5-hp

Pressure Tanks:

- Volume: 2 x 900 gallons
- Material: Steel



Storage Tank (2):

- Location: Northwestern service area of the distribution system.
- Volume: 211,000 gallons
- Material: Bolted steel



Appendix A

Seville Water Company - CA5400550

Sanitary Survey Photographs

Booster Station (2) — Pumps:

- Location: Downstream of 211,000 gallon storage tank
- Type: Centrifugal
- Size:
 - ◇ Regular Duty: 2 x 15-hp
 - ◇ High-Flow: 1 x 40-hp

Booster Station (2) — Pressure Tank:

- Location: Downstream of booster pumps
- Volume: 5,000 gallons
- Material: Steel



Chlorination Equipment (2):

- Location: Chlorine solution is injected to the discharge line of the booster pumps, upstream of the 5,000 gallon pressure tank.
- Storage: 50 gallon poly. tank
- Chemical Pump:
 - ◇ Make: Grundfos DDA
 - ◇ Capacity: 15.8 gph/145 psi



Appendix B:
Last Sample & Next Due Date Summary Report

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_001_001		SEVILLE WATER COMPANY					WELL 01 - RAW												
	GP	SECONDARY/GP																	
		1928 ALKALINITY, BICARBONATE	170.000		0.000		MG/L	-----	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1919 CALCIUM	35.000		0.000		MG/L	-----	-----	7/14/2021	49	36		2024/07		75310012107141300G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1929 ALKALINITY, CARBONATE		<	0.000		MG/L	-----	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1017 CHLORIDE	27.000		0.000		MG/L	500	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1905 COLOR		<	0.000		UNITS	15	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1022 COPPER, FREE		<	50.000		UG/L	1000	50	8/19/2020	16	36		2023/08		75310012008191245L	1371	MOORE TWINING ASSOCIATES, INC.	
		2905 FOAMING AGENTS (SURFACTANTS)		<	0.000		MG/L	0.5	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1915 HARDNESS, TOTAL (AS CaCO3)	157.000		0.000		MG/L	-----	-----	7/14/2021	16	36		2024/07		75310012107141300G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1021 HYDROXIDE AS CALCIUM CARBONATE		<	0.000		MG/L	-----	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1028 IRON		<	100.000		UG/L	300	100	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1031 MAGNESIUM	17.000		0.000		MG/L	-----	-----	7/14/2021	49	36		2024/07		75310012107141300G	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		1032 MANGANESE		<	20.000		UG/L	50	20	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_001_001	GP	SECONDARY/GP																	
		1920	ODOR	1.000	1.000		TON	3	1	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1925	PH	8.100	0.000			-----	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1050	SILVER		<	10.000	UG/L	100	10	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1052	SODIUM	31.000		0.000	MG/L	-----	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1064	CONDUCTIVITY @ 25 C UMHOS/CM	450.000		0.000	UMHO/CM	1600	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1055	SULFATE	24.000		0.500	MG/L	500	0.5	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1930	TDS	300.000		0.000	MG/L	1000	-----	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		0100	TURBIDITY	0.180		0.100	NTU	5	0.1	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
		1095	ZINC		<	50.000	UG/L	5000	50	8/19/2020	16	36		2023/08		75310012008191245G	1371	MOORE TWINING ASSOCIATES, INC.	
	IO	INORGANIC																	
		1002	ALUMINUM	9.100		50.000	UG/L	1000	50	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1074	ANTIMONY, TOTAL		<	6.000	UG/L	6	6	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1005	ARSENIC	1.500		2.000	UG/L	10	2	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_001_001	IO	INORGANIC																	
		1010 BARIUM	62.000		100.000		UG/L	1000	100	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1075 BERYLLIUM, TOTAL		<	1.000		UG/L	4	1	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1015 CADMIUM		<	1.000		UG/L	5	1	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1020 CHROMIUM		<	10.000		UG/L	50	10	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1025 FLUORIDE	0.170		0.100		MG/L	2	0.1	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1035 MERCURY		<	1.000		UG/L	2	1	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1036 NICKEL		<	10.000		UG/L	100	10	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1039 PERCHLORATE		<	4.000		UG/L	6	4	8/19/2020	100	36		2023/08		75310012008191245I	1186	BC LABORATORIES	
		1045 SELENIUM	1.000		5.000		UG/L	50	5	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
		1085 THALLIUM, TOTAL		<	1.000		UG/L	2	1	8/19/2020	16	36		2023/08		75310012008191245I	1371	MOORE TWINING ASSOCIATES, INC.	
	NI	NITRATE/NITRITE																	
		1040 NITRATE	6.700		0.400		MG/L	10	0.4	8/9/2022	25	3	Interval	2022/11		VI 2246083-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 4500-NO3-F-00
		1041 NITRITE		<	0.400		MG/L	1	0.4	8/19/2020	16	36		2023/08		75310012008191245N	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_001_001	RA	RADIOLOGICAL																		
		4109	GROSS ALPHA PARTICLE ACTIVITY	2.000		2.000	0.600	PCI/L	15	3	8/18/2014	49	108	Interval	2023/08		75310011408181440R	2920	EUROFINS EATON ANALYTICAL (SOUTH BEND)	
	S1	REGULATED VOC																		
		2981	1,1,1-TRICHLOROETHANE		<	0.500		UG/L	200	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2988	1,1,2,2-TETRACHLOROETHANE		<	0.500		UG/L	1	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2985	1,1,2-TRICHLOROETHANE		<	0.500		UG/L	5	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2978	1,1-DICHLOROETHANE		<	0.500		UG/L	5	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2977	1,1-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2378	1,2,4-TRICHLOROBENZENE		<	0.500		UG/L	5	0.5	8/19/2020	9	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2968	O-DICHLOROBENZENE		<	0.500		UG/L	600	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2980	1,2-DICHLOROETHANE		<	0.500		UG/L	0.5	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2983	1,2-DICHLOROPROPANE		<	0.500		UG/L	5	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_001_001	S1	REGULATED VOC																	
		2413	1,3-DICHLOROP ROPENE	<	0.500		UG/L	0.5	0.5	8/19/2020	9	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2969	P-DICHLOROB ENZENE	<	0.500		UG/L	5	0.5	8/19/2020	16	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2990	BENZENE	<	0.500		UG/L	1	0.5	8/19/2020	9	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2982	CARBON TETRACHLO RIDE	<	0.500		UG/L	0.5	0.5	8/19/2020	16	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2380	CIS-1,2-DICHLOROE THYLENE	<	0.500		UG/L	6	0.5	8/19/2020	9	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2964	DICHLOROM ETHANE	<	0.500		UG/L	5	0.5	8/19/2020	16	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2992	ETHYLBENZ ENE	<	0.500		UG/L	300	0.5	8/19/2020	9	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2251	METHYL TERT-BUTYL ETHER	<	3.000		UG/L	13	3	8/19/2020	36	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2989	CHLOROBEN ZENE	<	0.500		UG/L	70	0.5	8/19/2020	16	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2996	STYRENE	<	0.500		UG/L	100	0.5	8/19/2020	9	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2987	TETRACHLO ROETHYLEN E	<	0.500		UG/L	5	0.5	8/19/2020	16	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	
		2991	TOLUENE	<	0.500		UG/L	150	0.5	8/19/2020	25	36		2023/08		75310012 00819124 5V	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 01 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORTING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MONTHS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_001_001	S1	2979	TRANS-1,2-DICHLOROETHYLENE		<	0.500		UG/L	10	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2984	TRICHLOROETHYLENE		<	0.500		UG/L	5	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2218	TRICHLOROFLUOROMETHANE		<	5.000		UG/L	150	5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2904	TRICHLOROTRIFLUOROETHANE		<	10.000		UG/L	1200	10	8/19/2020	9	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2976	VINYL CHLORIDE		<	0.500		UG/L	0.5	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
		2955	XYLENES, TOTAL		<	0.500		UG/L	1750	0.5	8/19/2020	16	36		2023/08		75310012008191245V	1371	MOORE TWINING ASSOCIATES, INC.	
	S2	REGULATED SOC																		
		2414	1,2,3-TRICHLOROPROPANE		<	0.005		UG/L	0.005	0.005	10/19/2021	36	36		2024/10		VI 2148263-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SRL 524M-TCP
		2051	LASSO (ALACHLOR)		<	1.000		UG/L	2	1	8/19/2020	25	36		2023/08		75310012008191245S	1371	MOORE TWINING ASSOCIATES, INC.	
		2050	ATRAZINE		<	0.500		UG/L	1	0.5	8/19/2020	25	36		2023/08		75310012008191245S	1371	MOORE TWINING ASSOCIATES, INC.	
		2931	1,2-DIBROMO-3-CHLOROPROPANE		<	0.000		UG/L	0.2	0.01	7/14/2021	16	36		2024/07		75310012107141300S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2946	ETHYLENE DIBROMIDE		<	0.000		UG/L	0.05	0.02	7/14/2021	16	36		2024/07		75310012107141300S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	
		2037	SIMAZINE		<	1.000		UG/L	4	1	8/19/2020	25	36		2023/08		75310012008191245S	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 02 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD	
CA5400550_003_003	GP	SECONDARY/GP																		
		1920	ODOR	1.000		1.000		TON	3	1	8/19/2020	9	36		2023/08		7531003200819125OG	1371	MOORE TWINING ASSOCIATES, INC.	
		1925	PH	8.000		0.000			-----	-----	8/19/2020	9	36		2023/08		7531003200819125OG	1371	MOORE TWINING ASSOCIATES, INC.	
		1050	SILVER		<	10.000		UG/L	100	10	8/19/2020	9	36		2023/08		7531003200819125OG	1371	MOORE TWINING ASSOCIATES, INC.	
		1052	SODIUM	42.000		0.000		MG/L	-----	-----	8/19/2020	9	36		2023/08		7531003200819125OG	1371	MOORE TWINING ASSOCIATES, INC.	
		1064	CONDUCTIVITY @ 25 C UMHOS/CM	540.000		0.000		UMHO/CM	1600	-----	8/19/2020	9	36		2023/08		7531003200819125OG	1371	MOORE TWINING ASSOCIATES, INC.	
		1055	SULFATE	22.000		0.500		MG/L	500	0.5	8/19/2020	9	36		2023/08		7531003200819125OG	1371	MOORE TWINING ASSOCIATES, INC.	
		1930	TDS	330.000		0.000		MG/L	1000	-----	8/19/2020	9	36		2023/08		7531003200819125OG	1371	MOORE TWINING ASSOCIATES, INC.	
		0100	TURBIDITY	0.140		0.100		NTU	5	0.1	8/19/2020	9	36		2023/08		7531003200819125OG	1371	MOORE TWINING ASSOCIATES, INC.	
		1095	ZINC		<	50.000		UG/L	5000	50	8/19/2020	9	36		2023/08		7531003200819125OG	1371	MOORE TWINING ASSOCIATES, INC.	
	IO	INORGANIC																		
		1002	ALUMINUM	4.900		50.000		UG/L	1000	50	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1074	ANTIMONY, TOTAL		<	6.000		UG/L	6	6	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1005	ARSENIC	1.800		2.000		UG/L	10	2	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 02 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_003_003	IO	INORGANIC																		
		1010	BARIUM	76.000		100.000		UG/L	1000	100	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1075	BERYLLIUM, TOTAL		<	1.000		UG/L	4	1	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1015	CADMIUM		<	1.000		UG/L	5	1	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1020	CHROMIUM	3.900		10.000		UG/L	50	10	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1025	FLUORIDE		<	0.100		MG/L	2	0.1	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1035	MERCURY		<	1.000		UG/L	2	1	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1036	NICKEL	3.000		10.000		UG/L	100	10	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1039	PERCHLORATE		<	4.000		UG/L	6	4	8/19/2020	16	36		2023/08		7531003200819125OI	1186	BC LABORATORIES	
		1045	SELENIUM	1.600		5.000		UG/L	50	5	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
		1085	THALLIUM, TOTAL		<	1.000		UG/L	2	1	8/19/2020	9	36		2023/08		7531003200819125OI	1371	MOORE TWINING ASSOCIATES, INC.	
	NI	NITRATE/NITRITE																		
		1040	NITRATE	6.000		0.400		MG/L	10	0.4	8/9/2022	29	3	Interval	2022/11		VI 2246083-002	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SM 4500-NO3-F-00
		1041	NITRITE		<	0.400		MG/L	1	0.4	8/19/2020	9	36		2023/08		7531003200819125ON	1371	MOORE TWINING ASSOCIATES, INC.	

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 02 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_003_003	RA	RADIOLOGICAL																		
		4109	GROSS ALPHA PARTICLE ACTIVITY		<	2.100	2.000	PCI/L	15	3	1/15/2018	64	108	Interval	2027/01		75310031 80115123 OR	2920	EUROFINS EATON ANALYTICAL (SOUTH BEND)	
	S1	REGULATED VOC																		
		2981	1,1,1-TRICHLOROETHANE		<	0.500		UG/L	200	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2988	1,1,2,2-TETRACHLOROETHANE		<	0.500		UG/L	1	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2985	1,1,2-TRICHLOROETHANE		<	0.500		UG/L	5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2978	1,1-DICHLOROETHANE		<	0.500		UG/L	5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2977	1,1-DICHLOROETHYLENE		<	0.500		UG/L	6	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2378	1,2,4-TRICHLOROBENZENE		<	0.500		UG/L	5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2968	O-DICHLOROBENZENE		<	0.500		UG/L	600	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2980	1,2-DICHLOROETHANE		<	0.500		UG/L	0.5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2983	1,2-DICHLOROPROPANE		<	0.500		UG/L	5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 02 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_003_003	S1	REGULATED VOC																	
		2413	1,3-DICHLOROPROPENE		<	0.500	UG/L	0.5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2969	P-DICHLOROBENZENE		<	0.500	UG/L	5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2990	BENZENE		<	0.500	UG/L	1	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2982	CARBON TETRACHLORIDE		<	0.500	UG/L	0.5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2380	CIS-1,2-DICHLOROETHYLENE		<	0.500	UG/L	6	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2964	DICHLOROMETHANE		<	0.500	UG/L	5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2992	ETHYLBENZENE		<	0.500	UG/L	300	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2251	METHYL TERT-BUTYL ETHER		<	3.000	UG/L	13	3	8/9/2022	11	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2989	CHLOROBENZENE		<	0.500	UG/L	70	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2996	STYRENE		<	0.500	UG/L	100	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2987	TETRACHLOROETHYLENE		<	0.500	UG/L	5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2
		2991	TOLUENE		<	0.500	UG/L	150	0.5	8/9/2022	7	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: WELL 02 - RAW

CLASS: DCSGA

STATUS: Active

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORTING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULTS	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD	
CA5400550_003_003	S1	2979	TRANS-1,2-DICHLOROE THYLENE		<	0.500		UG/L	10	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2	
		2984	TRICHLORO ETHYLENE		<	0.500		UG/L	5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2	
		2218	TRICHLORO FLUOROMET HANE		<	5.000		UG/L	150	5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2	
		2904	TRICHLORO TRIFLUORO ETHANE		<	10.000		UG/L	1200	10	8/9/2022	4	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2	
		2976	VINYL CHLORIDE		<	0.500		UG/L	0.5	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2	
		2955	XYLENES, TOTAL		<	0.500		UG/L	1750	0.5	8/9/2022	5	36		2025/08		VI 2246084-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	EPA 524.2	
	S2	REGULATED SOC																			
		2414	1,2,3-TRICHLORO PROPANE		<	0.005		UG/L	0.005	0.005	10/19/2021	36	36		2024/10		VI 2148264-001	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)	SRL 524M-TCP	
		2051	LISSO (ALACHLOR)		<	1.000		UG/L	2	1	8/19/2020	9	36		2023/08		75310032 00819125 0S	1371	MOORE TWINING ASSOCIATES, INC.		
		2050	ATRAZINE		<	0.500		UG/L	1	0.5	8/19/2020	9	36		2023/08		75310032 00819125 0S	1371	MOORE TWINING ASSOCIATES, INC.		
		2931	1,2-DIBROMO-3-CHLOROPR OPANE		<	0.000		UG/L	0.2	0.01	7/14/2021	9	36		2024/07		75310032 10714131 0S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)		
		2946	ETHYLENE DIBROMIDE		<	0.000		UG/L	0.05	0.02	7/14/2021	9	36		2024/07		75310032 10714131 0S	1573	FGL ENVIRONMENTAL (SANTA PAULA, CA)		
		2037	SIMAZINE		<	1.000		UG/L	4	1	8/19/2020	9	36		2023/08		75310032 00819125 0S	1371	MOORE TWINING ASSOCIATES, INC.		

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY: TULARE

Sample Point: ST2S1-15348 AVE 381

CLASS: DBPT

STATUS: Active

PSCODE	GC	GROUP/ANALYTE	LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD	
CA5400550_ DST_900		SEVILLE WATER COMPANY				ST2S1-15348 AVE 381														
	DBP	DISINFECTION BYPRODUCTS																		
	2943	BROMODIC HLOROMET HANE	2.200		1.000		UG/L	-----	1	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		
	2942	BROMOFOR M	4.000		1.000		UG/L	-----	1	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		
	2941	CHLOROFOR M	1.500		1.000		UG/L	-----	1	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		
	2454	DIBROMOAC ETIC ACID		<	1.000		UG/L	-----	1	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		
	2944	DIBROMOC HLOROMET HANE	3.700		1.000		UG/L	-----	1	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		
	2451	DICHLOROA CETIC ACID		<	1.000		UG/L	-----	1	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		
	2456	TOTAL HALOACETI C ACIDS (HAA5)		<	0.000		UG/L	60	-----	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		
	2453	MONOBROM OACETIC ACID		<	1.000		UG/L	-----	1	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		
	2450	MONOCHLO ROACETIC ACID		<	2.000		UG/L	-----	2	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		
	2950	TTHM	11.000		0.000		UG/L	80	-----	7/10/2020	16	36		2023/07		75319002 00710113 OD	1371	MOORE TWINING ASSOCIATES, INC.		

"Mod" field: "Interval", formerly seen as "M", means the sample Frequency was modified. "Date", formerly seen as "I", means the Next Required sample date was modified.

System: SEVILLE WATER COMPANY

COUNTY:

Sample Point:

CLASS: DBPT


STATUS:

PSCODE	GC	GROUP/ANALYTE		LAST RESULT	LESS THAN	REPORT ING LEVEL	COUNTING ERROR (±)	UOM	MCL	DLR	LAST SAMPLE	COUNT OF RESULT S	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES	SAMPLE ID	LAB ID	LAB NAME	METHOD
CA5400550_ DST_900	DBP	2452	TRICHLORO ACETIC ACID		<	1.000		UG/L	-----	1	7/10/2020	16	36		2023/07		75319002 00710113 0D	1371	MOORE TWINING ASSOCIATES, INC.	

Appendix C:
Instructions for Accessing Individual Water System's Water Monitoring
Schedule and Water Quality Data

How To Access Individual System's Drinking Water Monitoring Schedule & Water Quality Data

1. Place the following link in the internet address bar:
<https://sdwis.waterboards.ca.gov/PDWW/>
2. Enter your Water System No. and select "Search For Water Systems"



SDWIS Version 3.21

California Public Water Supply Systems Search Parameters

Water System No. Enter your Water System No. (i.e. 54####)

Water System Name

Principal County Served


Water System Type

Water System Status

Primary Source Water Type

[Click Here for the County Map of CALIFORNIA](#)

3. Click on your Water System No. (Link in blue text).



Drinking Water Division

Water Systems

Hide/show columns: [Water System No.](#) | [Water System Name](#) | [Type](#) | [Status](#) | [Principal County Served](#) | [Primary Source Water Type](#)

Display records Search:

Water System No.	Water System Name	Type	Status	Principal County Served	Primary Source Water Type
CA5403043	YETTEM WATER SYSTEM	C	A	TULARE	GW

Showing 1 to 1 of 1 entries (filtered from 8,332 total entries) Previous Next

4. On the left side of the screen, select **Monitoring Schedules** for source monitoring schedule (last sample and next due dates) or **Monitoring Results** for water quality results.

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

Glossary

Contact Info

CA Drinking Water Watch

Water System Details

Water System No. : CA5403043	Federal Type : C
Water System Name : YETTEM WATER SYSTEM	State Type : C
Principal County Served : TULARE	Primary Source : GW
Status : A	Activity Date : 04-28-2014

Water System Contacts

Type	Address	Phone	Email - Web Address
Administrative Contact	5961 S. MOONEY BLVD. VISALIA, CA 93277	Business 559-624-7191	
Physical Location Contact	CA5403043-YETTEM WATER SYSTEM		

Division of Drinking Water District / County Health Dept. Info

Name	Phone	Email	Address
DISTRICT 24 - TULARE	559-447-3300	dwpsdist24@waterboards.ca.gov	265 W. BULLARD AVE., SUITE 101 FRESNO CA 93704

Annual Operating Periods & Population Served

Start Month	Start Day	End Month	End Day	Population Type	Population Served
1	1	12	31	R	350

Service Connections

Type	Count	Meter Type	Meter Size Measure
CB	64	UN	0

Sources of Water

Name	Type Code	Status
WELL 01 - PRE NO3 BLEND	WL	A
WELL 02 - PRE NO3 BLEND	WL	A

Service Areas

Code	Name
R	RESIDENTIAL AREA

Water Purchases

Seller Water System No.	Water System Name	Seller Facility Type	Seller State Asgn ID No.	Buyer Facility Type	Buyer State Asgn ID No.
-------------------------	-------------------	----------------------	--------------------------	---------------------	-------------------------

5. Select Sampling Point corresponding to the source (Link in blue text and is a number).

5A. Monitoring Schedules

Links

[Water System Details](#)

[Water System Facilities](#)

[Monitoring Schedules](#)

[Monitoring Results](#)

[Monitoring Results By Analyte](#)

[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)

[Site Visits](#)

[Consumer Confidence Reports](#)

Return Links

[Water System Search](#)

[County Map](#)

[Glossary](#)

[Contact Info](#)

CA Drinking Water Watch

Monitoring Schedules

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

The Division of Drinking Water's (DDW's) drinking water quality monitoring schedules identify upcoming required testing of drinking water for water systems in California. These documents should not be used for determining whether water systems are in compliance with monitoring requirements. The purpose for providing these monitoring schedules is to allow water systems to verify that their sampling and analyses have been incorporated into the DDW database and to identify upcoming required monitoring/sampling events.

Notes for Water Systems:

1. The monitoring notification documents should be considered "draft," in that they will change with subsequent updates, and as monitoring data are submitted, or as monitoring schedules are revised.
2. The monitoring notification documents are derived from the DDW Water Quality database and from schedules maintained by DDW districts.
3. If your upcoming monitoring or your data identified as "DUE" are not in agreement with this document, or if you have been advised of any increased monitoring that is not reflected in the report for a particular source, please contact your [District Engineer or LPA representative](#). For a map of the districts, please [click here](#).
4. If your notification report for a source is blank, this does not necessarily indicate compliance with all monitoring requirements.
5. These notification reports may not reflect compliance with initial monitoring for newly regulated constituents, or constituents that require special monitoring frequencies. For example, the DDW database is unable to accurately forecast the vulnerable non-volatile synthetic organic chemical (SOC) frequency for large water systems serving over 3,300 people of 2 quarters every 3 years.
6. Some Nitrate (as N) results under storet code 00618, will have a result of 'N/A' which stands for 'Not Applicable.' This stems from the change in regulation requiring that all nitrate sampling be reported as Nitrate (as N) starting January 1, 2016. Prior nitrate sampling was reported as Nitrate (as NO3). With this change in nitrate reporting requirements, the monitoring schedules have captured the last date of Nitrate (as NO3) sampling and applied it to Nitrate (as N) in determining the next due date [unless there have been Nitrate (as N) samples collected]. The Nitrate (as NO3) result, however, does not carry over to Nitrate (as N) which is why there may be a notation in the 'Constituent Identification' column to reference storet code 71850 for the last nitrate result. In these instances, the 'Constituent Identification' column will say, 'NITRATE (as N) - [see 71850].' Any questions should be referred to your District Engineer.

[Monitoring Schedules for All Sampling Points](#)

Monitoring schedule for all sampling points

Click to view report. Once the report is shown, click on the Export icon on the report header to download.

Monitoring Schedule for Individual Sampling Points

Click on a sampling point number to view the monitoring schedule for the sampling point.
[Click here to bring back the list of sampling points.](#)

Sampling Point	Location	Type
900	ST2S1-14395 AVE 384	
LCR		DS
003	WELL 01 & 02 - NO3 BLEND TANK	
001	WELL 01 - PRE NO3 BLEND	RW
002	WELL 02 - PRE NO3 BLEND	RW

Monitoring schedule for specific sampling points

NOTE: Any *past due* monitoring will have "DUE NOW" in the far-right column. Please schedule this monitoring as soon as possible.

5B. Monitoring Results

Links
[Water System Details](#)
[Water System Facilities](#)
[Monitoring Schedules](#)
[Monitoring Results](#)
[Monitoring Results By Analyte](#)
[Lead And Copper Sampling](#)

- [Summaries](#)
- [Next Sampling Due Dates](#)
- [All Lead Sampling Results](#)
- [All Copper Sampling Results](#)

[Violations/Enforcement Actions](#)
[Site Visits](#)
[Consumer Confidence Reports](#)

- 2017
- 2016
- 2015
- 2014

Return Links
[Water System Search](#)
[County Map](#)
Glossary
Contact Info

CA Drinking Water Watch

Water System No. :	CA5403043	Federal Type :	C
Water System Name :	YETTEM WATER SYSTEM	State Type :	C
Principal County Served :	TULARE	Primary Source :	GW
Status :	A	Activity Date :	04-28-2014

Monitoring Results for Individual Sampling Points

Click on a PS Code to view/download the monitoring results for the sampling point.

Water System Sampling Points					
PS Code	Facility ID	Facility Name	Description	Type Code	Source Class
5403043-001	001	WELL 01 - PRE NO3 BLEND	WELL 01 - PRE NO3 BLEND	RW	DCSGA
5403043-002	002	WELL 02 - PRE NO3 BLEND	WELL 02 - PRE NO3 BLEND	RW	DCSGA
5403043-003	003	WELL 01 & 02 - NO3 BLEND TANK	WELL 01 & 02 - NO3 BLEND TANK		OTHR
5403043-900	DST	DISTRIBUTION SYSTEM	DISTRIBUTION SYSTEM		DBPT
5403043-LCR	DST	DISTRIBUTION SYSTEM		DS	

6. Please contact the Tulare District Office at (559) 447-3300 or DWPDIST24@waterboards.ca.gov if you have any questions.

Appendix D:
Source Water and Distribution System Bacteriological Monitoring Reports

Bacteriological Distribution Monitoring Report

5400550 Seville Water Company

Distribution System Freq: 1/M

Sample Date	Location	T Coli	E Coli	F Coli	HPC	Type	Cl2	Cl2 Avg	Viol. Type	GWR Satisfied?	Comments
9/22/2022	Stone Corral SP	A	A			Routine	1.31				
8/9/2022	Stone Corral SP	A	A			Routine	0.83				
7/15/2022	Stone Corral SP	A	A			Routine	0.75				
7/11/2022	See Notes										BWN issued per KW-TW (water outage).
6/13/2022	Stone Corral SP	A	A			Routine	0.96				
5/16/2022	Stone Corral SP	A	A			Routine	1.03				
4/25/2022	Stone Corral Sample Point	A	A			Routine	1.13				
3/28/2022	Stone Corral Sample Point	A	A			Routine	0.45				
2/10/2022	Stone Corral SP	A	A			Routine	0.40				
1/24/2022	Stone Corral SP	A	A			Routine	1.16				
12/28/2021	Sample Point	A	A			Routine	1.09				
11/19/2021	Stone Corral Sample Point	A	A			Routine	0.29				
10/19/2021	Stone Corral Sample Point	A	A			Routine	0.6				
9/28/2021	Stone Corral Sample Point	A	A			Routine	0.33				
9/28/2021	Stone Corral Sample Point	A	A			Routine	0.33				
8/23/2021	Stone Corral Sampling Point	A	A			Routine	1.09				
7/14/2021	Stone Corral SP	A	A			Routine	0.85				
6/21/2021	Stone Corral SP	A	A			Routine	0.29				
5/26/2021	Wells: 01,02	<1.0	<1.0			Source Repeat				Yes	GWR satisfied
5/26/2021	Tank	<1.0	<1.0			Repeat	0.84				
5/26/2021	Stone Corral SP	<1.0	<1.0			Repeat	1.32				
5/26/2021	15455 Ave 381	<1.0	<1.0			Repeat	1.41				
5/26/2021	38111 Rd 155	<1.0	<1.0			Repeat	1.27				
5/24/2021	Stone Corral SP	A	A			Routine	1.32				
4/20/2021	Stone Corral Sample Point	A	A			Routine	0.45				
3/12/2021	Stone Corral SP	A	A			Routine	0.44				
2/18/2021	Stone Corral SP	A	A			Routine	0.57				
1/18/2021	Stone Corral SP	A	A			Routine	0.58				
12/21/2020	Stone Corral Sample Point	A	A			Routine	0.41				
11/1/2020	No sample								MR1		Cit 03-24-21C-010
10/26/2020	Stone Corral SP	A	A			Routine	0.42				
9/28/2020	Stone corral sample point	A	A			Routine	1.52				
8/14/2020	38256 Rd 156 HB	A	A			Routine	0.74				
7/16/2020	4 samples	<1.0	<1.0			Other	1.4-1.7				
7/10/2020	15361 Ave 383	A	A			Routine	0.64				
7/8/2020	5 samples	<1.0	<1.0			Other					
7/8/2020	5 samples	<1.0	<1.0			Other	0.46-0.96				
7/1/2020	See Notes										BWN issued per BP (intermittent outages)
6/5/2020	15491 Visalia HB	A	A			Routine	1.1				
5/27/2020	5 samples	<1.0	<1.0			Other	0.42-0.61				special samples/Stone Corral Elementary Schoc

Sample Date	Location	T Coli	E Coli	F Coli	HPC	Type	CI2	CI2 Avg	Viol. Type	GWR Satisfied?	Comments
5/15/2020	See Comments										BWN (2015-6) Cancelled, per BGP
5/13/2020	15316 Ave 383	<1.0	<1.0			Other	0.63				
5/13/2020	Seville/Rd 153	<1.0	<1.0			Other	0.81				
5/13/2020	Inyo Ave/Rd154	<1.0	<1.0			Other	0.74				
5/13/2020	Visalia/Rd 155	<1.0	<1.0			Other	0.61				
5/13/2020	Ave 384/Rd156	<1.0	<1.0			Other	0.61				
5/11/2020	15361 Ave 383	<1.0	<1.0			Other	0.83				
5/11/2020	Seville Ave Rd 153	<1.0	<1.0			Other	0.79				
5/11/2020	Inya Ave Rd 154	<1.0	<1.0			Other	0.84				
5/11/2020	Visalia Ave Rd 155	<1.0	<1.0			Other	0.87				
5/11/2020	Ave 383/Rd 156	<1.0	<1.0			Other	0.88				
5/5/2020	Stone Corral Rm 5	A	A			Routine	0.75				
4/3/2020	15491 Visalia Ave	A	A			Routine	0.77				
3/4/2020	15361 Front HB	A	A			Routine	0.63				
2/7/2020	15491 Visalia Ave	A	A			Routine	0.51				
1/10/2020	New Storage Tank	<1.0	<1.0			Other	1.6				
1/3/2020	Stone Corral Elem Rm 5	A	A			Routine					
12/6/2019	38256 Rd 156	A	A			Routine			MR9		
11/25/2019	5 samples	<1.0	<1.0			Other	0.89-1.46				
10/17/2019	13 samples	A	A			Other	2.00-2.06				Special distribution system samples during construction.
10/16/2019	13 samples	A	A			Other	2.00-2.06				Special distribution system samples during construction.
10/4/2019	15491 Visalia Ave	A	A			Routine	1.5				
9/4/2019	Stone Corral Elem Room 5	A	A			Routine	0.40				
8/9/2019	38256 Rd 156 HB	A	A			Routine					
7/15/2019	15361 Ave 383	A	A			Routine	0.97				
6/20/2019	15515 Ave 381	A	A			Other	0.91				Line repair sample
6/20/2019	38256 Rd 156	A	A			Other	0.87				Line repair sample
6/20/2019	Stone Corral Rm 5	A	A			Other	0.96				Line repair sample
6/7/2019	15491 Visalia Ave	A	A			Routine	0.41				
5/9/2019	Stone Corral Elem Room #5	A	A			Routine	0.84				
4/12/2019	38256 Rd 156	A	A			Routine			MR9		Chlorine residual not on report
3/13/2019	15362 Ave 383	A	A			Routine	0.68				
2/4/2019	15491 Visalia Ave	A	A			Routine	0.35				
1/23/2019	Stone Corral Room #5	A	A			Routine	0.78				

Violation Key

MCL	Exceeds the maximum contaminant level	MR5	Incorrect number of repeat samples as follow-up to a positive sample
MR1	No monthly sample for the report month	MR6	No source sample
MR2	No quarterly sample for the report month	MR7	No summary report submitted
MR3	Incorrect number of routine samples for the report month	MR8	Other comments and/or info
MR4	Did not collect 5 routine samples for previous month's positive sample	MR9	CI2 not reported

Source Bacteriological Monitoring Report

5400550 Seville Water Company

Sample Date	Time	Source	Sample Type	Test Method	T Coli	E Coli	F Coli	HPC	Violation	Comments
9/22/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
8/9/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
7/15/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
6/13/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
5/16/2022		Wells: 01,02	Well	QTray	<1.0	<1.0				
4/25/2022	14:40	Well 02 - Raw	Well	Qtray	<1.0	<1.0				
4/25/2022	14:50	Well 01 - Raw	Well	Qtray	<1.0	<1.0				
3/21/2022	13:15	Well 01 Raw	Well	Qtray	<1.0	<1.0				
3/21/2022	13:20	Well 02 Raw	Well	Qtray	<1.0	<1.0				
2/10/2022	13:00	Well 01	Well	Qtray	<1.0	<1.0				
2/10/2022	13:10	Well 02	Well	Qtray	<1.0	<1.0				
1/24/2022		Wells: 1,2	Well	QTray	<1.0	<1.0				
12/28/2021	11:20	Well 01	Well	Qtray	<1.0	<1.0				
12/28/2021	11:30	Well 02	Well	Qtray	<1.0	<1.0				
11/19/2021	12:45	Well 01	Well	Qtray	<1.0	<1.0				
11/19/2021	12:55	Well 02	Well	Qtray	<1.0	<1.0				
10/19/2021	12:50	Well 01 RAW	Well	Qtray	2	<1				
10/19/2021	13:00	Well 02 RAW	Well	Qtray	<1	<1				
9/28/2021	12:50	Well 01	Well	Qtray	<1.0	<1.0				
9/28/2021	12:50	Well 01	Well	Qtray	<1.0	<1.0				
9/28/2021	12:55	Well 02	Well	Qtray	<1.0	<1.0				
9/28/2021	12:55	Well 02	Well	Qtray	<1.0	<1.0				
8/23/2021	13:25	Well 02- Raw	Well	Qtray	<1.0	<1.0				
8/23/2021	13:30	Well 01- Raw	Well	Qtray	<1.0	<1.0				
7/14/2021		Wells: 01,02	Well	QTray	<1.0	<1.0				
6/21/2021		Wells: 01, 02	Well	QTray	<1.0	<1.0				
5/26/2021		Wells: 01,02	GWR Well	QTray	<1.0	<1.0				
5/24/2021	14:15	Well 01	Well	QTray	9.9	<1.0				
5/24/2021	14:25	Well 02	Well	QTray	>200.5	<1.0				
4/20/2021		Wells: 01,02	Well	Qtray	<1.0	<1.0				
3/12/2021		Wells: 1,2	Well	Qtray	<1.0	<1.0				
2/18/2021		Wells: 01,02	Well	Qtray	<1.0	<1.0				
1/18/2021		Wells: 1,2	Well	QTray	<1.0	<1.0				
12/21/2020	10:00	Wells: 1,2	Well	Qtray	<1	<1				
10/26/2020		Wells: 1,2	Well	Qtray	<1.0	<1.0				
9/28/2020		Wells: 01, 02	Well	Qtray	<1.0	<1.0				
8/14/2020		Wells: 1,2	Well	Qtray	<1.0	<1.0				
7/10/2020		Wells: 1,2	Well	Qtray	<1.0	<1.0				
6/5/2020		Wells: 01, 02	Well	Qtray	<1.0	<1.0				
5/5/2020		Wells: 01, 02	Well	QTray	<1.0	<1.0				
4/3/2020		Wells: 01, 02	Well	QTray	<1.0	<1.0				

5400550 Seville Water Company

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
3/4/2020		Wells: 1,2	Well	QTray	<1.0	<1.0				
2/7/2020		Wells: 01, 02	Well	QTray	<1.0	<1.0				
1/3/2020	10:40	Wells: 01, 02	Well	QTray	<1.0	<1.0				
12/6/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
10/4/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
9/4/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
8/9/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
7/15/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
6/7/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
5/9/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
4/12/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
3/13/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
2/4/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				
1/23/2019		Wells: 01,02	Well	QTray	<1.0	<1.0				

Appendix E:
Lead and Copper Tap Sample Results Reporting Form



State Water Resources Control Board

Division of Drinking Water

Lead and Copper Tap Sample Results Reporting Form

This form must be submitted to the regulating entity (DDW District Office or County Agency) for each round of lead and copper sampling

Report Date: (mm/dd/yyyy)		Sampling Site Change
Water System Name:		<i>If any sampling sites were changed, please list the old site, new site, and reason for the change in the box below.</i>
Water System Number:		
Sample Schedule:	<input checked="" type="radio"/> 6-month <input type="radio"/> Annual <input type="radio"/> Triennial	
# of Samples Required:		
# of Samples Reported:		
	90th Percentile Level (mg/L)	
Lead:		
Copper:		

				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2 or 3	Lead (mg/L)	Copper (mg/L)
01					
02					
03					
04					
05					
06					
07					
08					
09					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Number of Tap Sample Sites Required

The number of tap sample sites required is based on the number of people served (system size) by your water system and also whether you are performing Standard or Reduced Monitoring (CCR §64675).

System Size	Minimum Number of Sites	
	Standard Tap Sampling	Reduced Tap Sampling
> 100,000	100	50
10,001 to 100,000	60	30
3,301 to 10,000	40	20
501 to 3,300	20	10
101 to 500	10	5
< 101	5	5

Determining the 90th Percentile Lead and Copper Level

Number of Tap Samples Collected	Determination of 90 th Percentile Lead or Copper Level
5	Average the 4 th and 5 th highest sample results to get the 90 th percentile level
More than 5	Place results in ascending order and assign each sample a number, 1 for the lowest concentration. Multiply the total number of samples by 0.9. Round down to the nearest whole number if the decimal is 0.4 or lower and round up if the decimal is 0.5 or higher. The sample result that corresponds with the nearest whole number is the 90 th percentile.

Notification of Results

As required by *40 Code of Federal Regulations Section 141.85(d)*, within 30 days of learning of the tap monitoring results, I notified the participants, by mailing or by another method approved by the State, of the lead sample results from their individual taps, provided an explanation of the health effects of lead, listed steps the consumer could take to reduce exposure to lead, provided contact information for the water utility, the maximum contaminant level goal for lead, action level for lead, and any definitions.

Notification was done on: _____ (date)

SIGNATURE:	DATE:
NAME (Print):	TITLE:

Division of Drinking Water
Lead and Copper Tap Sample Results Reporting Form

Additional Samples				Result	
	Sample Date	Sample Site Location/Address	Tier 1, 2 or 3	Lead (mg/L)	Copper (mg/L)
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					

Appendix F:
Bacteriological Sample Siting Plan Template

Division of Drinking Water Tulare District

GUIDELINES FOR COMPLETING THE BACTERIOLOGICAL SAMPLE SITING PLAN FOR SMALL WATER SYSTEMS

The total coliform regulation requires the water supplier to submit a bacteriological sample siting plan to the Division of Drinking Water (Division), District Office for review and approval. The locations where samples are to be collected must be written down and formally approved by the District Office. These guidelines and Attachment 1, "Bacteriological Sample Siting Plan" Form, are to assist you in complying with these requirements.

To comply with the requirements for submitting a Bacteriological Sample Siting Plan, two (2) items must be submitted to the District Office at this time.

1. A system map, street map, or system schematic showing all sampling locations must be submitted. The map can be prepared by any system representative. It does not have to be prepared by an engineer. The following are also to be shown on the map:
 - Water Sources (i.e., well or spring)
 - Treatment Facilities (i.e., chlorination)
 - Storage Tanks
 - Pressure Reducing Stations
 - Booster Stations
 - Pressure Zones
 - Dead Ends
 - Service Area Boundaries
 - Routine Sample Sites
 - Repeat Sample Sites
 - Special Sample Sites
2. Complete Attachment 1, the "Bacteriological Sample Siting Plan" form, and **return the system map and form to the District Office for review and approval.**

Once the Bacteriological Sample Siting Plan has been approved by the Division, copies should be provided to the person responsible for sample collection, the laboratory and the person responsible for reporting coliform-positive samples to the Division.

Selection of Sampling Sites

The routine sampling sites chosen must be representative of the water distribution system including all pressure zones, areas supplied by each water source and distribution reservoir.

Looped Systems: If your entire water distribution system is looped, then one routine sample point may be representative of your system, assuming valves are open.

Pressure Zones: You should only be concerned about sampling in different pressure zones if your water system serves different areas of varying elevations, for example in mountainous areas.

How many routine sampling sites are required?

The minimum number of samples for the water system shall be based on the known population served or the total number of service connections, whichever results in the greater number of samples, as shown in Table 64423-A. For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

Table 64423-A		
Minimum Number of Routine Total Coliform Samples Monthly Population Served¹	Service Connections	Minimum Number of Samples Per Month
25 to 1000	15 to 400	1
1,001 to 2,500	401 to 890	2
2,501 to 3,300	891 to 1,180	3
3,301 to 4,100	1,181 to 1,460	4
4,101 to 4,900	1,461 to 1,750	5
4,901 to 5,800	1,751 to 2,100	6
5,801 to 6,700	2,101 to 2,400	7
6,701 to 7,600	2,401 to 2,700	8
7,601 to 8,500	2,701 to 3,000	9
8,501 to 12,900	3,001 to 4,600	10
12,901 to 17,200	4,601 to 6,100	15
17,201 to 21,500	6,101 to 7,700	20
21,501 to 25,000	7,701 to 8,900	25
25,001 to 33,000	8,901 to 11,800	30
33,001 to 41,000	11,801 to 14,600	40
41,001 to 50,000	14,601 to 17,900	50
50,001 to 59,000	17,901 to 21,100	60
59,001 to 70,000	21,101 to 25,000	70

¹ For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

How many repeat sampling sites are required?

A repeat sample set consists of three samples to be collected from the following locations:

- One repeat sample from the same routine location.
- One repeat sample from an *upstream location* (within 5 connections of the routine site).
- One repeat sample from a *downstream location* (within 5 connections of the routine site).

Each routine sample site must have identified repeat sample sites.

Ground Water Rule Compliance: All active groundwater sources in operation at the time of the coliform-positive sample must also be sampled along with the repeat sample set.

What if the water system does not have enough locations to select the required number of routine and repeat sample sites?

If the water system does not have enough sample locations to identify the required routine and repeat sample sites, contact the District Office for further guidance.

Pointers for Sample Site Selection

- When selecting a routine sample site you should be able to select a site upstream and a site downstream for repeat sampling.
- Select a site where the water is used continuously all year round.
- Pick a site that is easily accessible, i.e., a fenced yard with a locked gate and vicious dog is not a good selection.
- When choosing a sampling tap you should consider these factors:
The sampling tap should be located in as clean an environment as possible. It should be protected from contamination by humans, animals, airborne materials or other sources of contamination.

If you choose an outside private tap, it should be one that is in frequent use, clean, and at least 1½ feet (18 inches) above the ground. The sample tap should discharge downward.

If you choose an inside tap, be sure that you are not sampling from drinking fountains; taps that have aerators or strainers, or swivel faucets; or taps off of individual homeowner treatment units.

Do not choose a fire hydrant as sampling tap.

Avoid taps that are surrounded by excessive foliage or taps that are dirty or corroded.

Avoid taps that leak, have fittings with packing, or have permanent hoses or attachments fastened to the tap (Never collect a sample from a hose).

Avoid the use of dead ends for routine sample collection, and use them for repeat samples only if no other sample sites are available and if there is continuous water use from a service off the dead-end.

Instructions for Completing the Bacteriological Sample Siting Plan Form

This form has been designed to include all the requirements for the Bacteriological Sample Siting Plan.

- **Public Water System Classification**

The public water system (PWS) classification for your water system is either community, nontransient noncommunity or transient noncommunity. If you are uncertain of your classification, contact the District Office.

- **Month/Daily Users**

The monthly population determines the frequency of bacteriological sample collection for community water systems and nontransient noncommunity systems. For a transient-noncommunity water system, monthly population served shall be based on the average number of persons served per day in a month.

- **Active Service Connections (Community water systems only)**

This is the number of active hook-ups served by the system. If your system has a hook-up to a vacant lot, do not count this as an active connection. If a vacant lot has a right to a future connection, do not count this as an active connection. If a residence is connected to the system, but the residence is vacant, count this as an active hook-up.

- **Sampling Frequency**

This is the minimum number of routine bacteriological samples required at the frequency specified. If any routine sample is positive for coliform bacteria, additional repeat samples will be required. Repeat samples are in addition to the required routine samples. If you are uncertain of the routine sampling frequency for your water system, contact the District Office.

- **Trained Sampler**

The person collecting samples must be trained.

Sampling Service: Water systems utilizing a certified laboratory or other sampling service for water sample collection will be considered to have trained samplers. Enter the name of the laboratory or sampling service collecting your samples. A copy of the approved Bacteriological Sample Siting Plan should be provided to the laboratory or sampling service, if one is used.

Other Trained Samplers: Any person receiving a certificate from AWWA for attendance of the Water Sampling Training should submit a copy of their certificate along with the completed form. Any other samplers should submit a statement of their experience and training to this office for approval.

- **Analyzing Lab**

Enter the state-certified laboratory, which will be analyzing your water samples.

- **Person Responsible to Report Coliform-Positive Samples to the Division**

This should be the person that the laboratory is required to contact when a sample is total or fecal coliform positive. This person must notify the Division within 24 hours of a violation of the total coliform standard (more than one positive sample in a month) or when any sample is fecal or *E. coli* positive. This person should have the authority to take corrective action as required by regulation and the Division. This should be the same person listed on your Emergency Notification Plan.

- **Day/Evening Phone Number**

The Division requires that the water system provide the phone numbers of the person listed above so that they can be contacted by the laboratory or the Division at any time during the day or evening in the event of a bacteriological emergency.

- **Signature and Date**

The person preparing the Sample Siting Plan should sign and date the plan. If the Division has questions regarding the sampling plan, this is the person to be contacted.

- **Sample ID**

This should be entered on the laboratory slip when the sample is turned into the laboratory. This is the unique identifier for the water sample location, or the location address may also be used. For systems, which have no more than five (5) routine locations, these routine sites will be 1-ROU, 2-ROU, 3-ROU, 4-ROU, and 5-ROU.

Each routine sample site must have two repeat sampling sites. Repeat sample sites are to be located within five (5) service connections upstream and downstream of the routine sample site.

All sample locations should be marked in some way with the Sample ID or location address, i.e., the code painted on the sampling location or tagged with a water proof tag so the person collecting the water sample is sure to collect the water from the correct sample locations.

- **Sample Type**

This describes what type of sample (routine or repeat) is to be collected at this location.

- **Sample Point**

This is the type of the sample location. Use the following abbreviations, when appropriate: HB - Hose Bib (exterior), SF - Sink Faucet, PC - Goose Neck Type Copper Tube with Pet Cock

- **Location of Sample Point**

This is the description of the area in the distribution that the sample site is located. Routine sample sites shall not be located at dead ends. Use the following abbreviations, when appropriate: DE - Dead End (Not Recommended), PZ - Pressure Zone, RD - Representative Distribution

- **Location Address**

This is the actual physical location where the water sample is to be collected. If possible use a street address, i.e., 103 Good Street. If the location does not have a street address, use the nearest crossroads or use the last name of the resident, i.e., "Brown Residence." If the location is a business, please list the business name and address.

When describing the location, keep in mind that the person collecting water samples must be able to locate the sample site from your description.

- **Months Sample Collected at This Location**

This is the schedule for routine samples to be collected. For example, suppose two (2) sites are representative of your systems. Site No. 1 will be sampled in January, March, May, July, September, and November. Site No. 2 will be sampled in February, April, June, August, October, and December. All routine sites identified should be rotated to allow sampling at least every 3 months.

BACTERIOLOGICAL SAMPLE SITING PLAN (BSSP) FOR SMALL WATER SYSTEMS

System No.:		System Name:		PWS Classification:	
No. of Monthly Users:		No. of Daily Users:		No. Active Service Connections:	
CI2 Treatment:					
Sampling Frequency: __ per month		Seasonal System:		Period of Operation:	
Name of Trained Sampler:		Analyzing Lab:		Analyzing Lab:	
Person Responsible to Report Positive Samples to the Division:				Day/Evening Phone No:	
Signature of Water System Representative:					Date:

Sample ID	Sample Type	Sample Point	Location of Sample Point	Address of Sample Point	Months Sample Collection at this Location
1-ROU	Routine				
1-REP1	Repeat				Repeat Sample Only
1-REP2	Repeat				Repeat Sample Only

In the event of a routine positive sample, a sample(s) will be collected from the well(s) in use for Ground Water Rule compliance.

If continuous chlorination is provided, raw water samples are taken **monthly**.

The SWRCB-Division of Drinking Water or Local Primacy Agency has reviewed and approved this BSSP. Any plans on file dated prior to approval date below are void. The water system must sample their distribution system and raw water special purpose source samples for bacteriological quality in accordance with the approved BSSP beginning _____. Per the California Code of Regulations-Title 22 §64422, a water system is required to submit an updated plan to the State Board at least once every ten years and at any time the plan no longer ensures representative monitoring of the system.

District Office Representative Name: _____ Title: _____ District Name: Tulare District

Signature: _____ Date: _____

Appendix G:
Cross Connection Control Survey Guidance for Community Water Systems

Cross-Connection Control for Small Community Water Systems

Division of Drinking Water – Tulare District

Purpose of Cross-Connection Control Program: Water provided by a public water system may be contaminated via cross-connections within the distribution system. The purpose of the cross-connection control program is to reduce the hazard of contamination of the public water system by identifying actual and potential cross-connections and taking action to protect the system from these hazards. This is accomplished by installing backflow prevention assemblies where hazards are identified; or ensuring that water-using equipment on the premises is installed in accordance with plumbing code requirements and good practice.

What are cross-connections?

Cross-connections are actual and potential unprotected connections between a potable water system and any source or system containing unapproved water or a substance which is not safe. Examples of cross-connections include:

1. Improperly installed irrigation systems that may allow backsiphonage of stagnant, bacteriologically unsafe water into the piping system.
2. Improperly plumbed water-using devices such as hot-tubs, boilers or commercial dishwashers which may allow unsafe water back into the domestic piping system.
3. Irrigation systems served by an auxiliary source, such as a private well or creek. Such systems create a potential for major contamination of the public water system via interties with the domestic piping system.
4. Interconnections between the potable system and a non-potable system.

What the Regulations Require

Section 7584 of the California Code of Regulations requires that each public water system have a cross connection control program that includes these elements:

1. The adoption of operating rules or ordinances to implement the cross-connection program.
2. The conducting of surveys to identify water user premises where cross connections exist or are likely to occur.
3. The provisions of backflow protection by the water user at all connections where a cross connection hazard has been identified.
4. The provision of at least one person trained in cross connection control to carry out the program.
5. The establishment of a procedure or system for testing backflow prevention assemblies.
6. The maintenance of records of locations, tests, and repairs of backflow prevention assemblies within each water supplier's distribution system.

Getting Started

For small community water systems, the initial elements of the program consist of the following:

1. Adopting an ordinance or set of rules to implement the cross-connection control program. The ordinance or set of rules is important since it establishes the legal authority to carry out the program.
2. Conducting a system survey to identify actual and potential cross-connection hazards.
3. Ensuring that hazards are abated by the installation of backflow prevention assemblies at the meter, eliminating the hazard in conjunction with the owner of the property or providing internal cross-connection protection.

System Survey

The system survey consists of a preliminary survey and, if necessary, a more detailed second survey. For most small systems, the initial survey may consist of a questionnaire sent to each customer asking whether the customer has specific potential hazards. Documentation of the system survey is to be submitted to the Division. Attached is a summary form for documentation of the system survey.

Residential areas

Customers should be asked if any of the following are located on-site:

1. Auxiliary water supply (i.e. either a well or a creek pump) - backflow prevention device is mandatory.
2. Irrigation systems - backflow prevention device not required if system is installed in accordance with plumbing codes with appropriate vacuum breakers.
3. Swimming pool, hot tub or spa - backflow prevention device not required if system is installed in accordance with plumbing codes.
4. Solar hot water heating panels - backflow prevention device not required if system is installed in accordance with plumbing codes.
5. Gray water systems - backflow prevention assemblies may not be required if the system is installed in accordance with the Uniform Plumbing Code.

If these or other potential hazards are located on site, the water system is to determine whether the equipment has been installed in accordance with plumbing codes and/or good practice in order to minimize the risk of backflow.

Commercial customers: A more detailed questionnaire and survey is necessary. Small community systems, which also serve commercial customers, should review the Department of Health Service's "Manual of Cross-Connection Control - Procedures and Practices". A system survey of commercial users as specified in the Manual is to be performed. As an alternative, the system may decide to require backflow prevention assemblies' at all commercial service connections where hazards are likely to exist.

Wastewater and Hazardous Wastes: A service connection which handles wastewater or dangerous chemicals requires special evaluation and protection from cross-connection hazards. For additional information on evaluating this type of facility, please contact the appropriate regulatory agency and a cross-connection control specialist.

ELEMENTS OF A CROSS-CONNECTION CONTROL PROGRAM

DDW – Tulare District

When implementing a Cross-Connection Control Program, the water supplier or health agency should follow an organized plan. The following items should be included as a minimum. The items **explain the Department of Health Services' policy regarding the regulations.**

7584. Responsibility and Scope of Program

The water supplier shall protect the public water supply from contamination by implementation of a cross-connection control program. The program, or any portion thereof, may be implemented directly by the water supplier or by means of a contract with the local health agency, or with another agency approved by the health agency. The water supplier's cross-connection control program shall for the purpose of addressing the requirements of Sections 7585 through 7605 include, but not limited to, the following elements:

(1) *The adoption of operating rules or ordinances to implement the cross-connection program.*

A public water supplier shall enact an ordinance or rule of service outlining the cross-connection control program and providing enforcement authority.

(2) *The conducting of surveys to identify places where cross-connections are likely to occur.*

Water utilities do not have any responsibility for controlling or abating cross-connections on a user's premises. All existing facilities where potential cross-connections are suspected, however, shall be listed and inspected or reinspected on a priority basis, where feasible. All applications for new services or for enlarging existing services or changing of occupant shall be reviewed or screened for cross-connections hazards

(3) *The provision of backflow protection at the user's connection or within the user's premises or both.*

Adequate provisions for implementation and enforcement of backflow protection where needed including the shutting off service when necessary

4) *The provision of at least one person trained in cross-connection control to carry out the cross-connection program.*

Specific units of the health agency and/or water supplier should be designated to organize and carry out the cross-connection control program. The personnel in those units should be trained as to the causes and hazards of unprotected cross-connections.

(5) *The establishment of a procedure or system for testing backflow preventers.*

A list of approved backflow preventers and list of certified testers should be made available to each water user required to provide backflow protection.

The list may include backflow devices approved by University of Southern California, Foundation for Cross-Connection Control and IAPMO, which may be found on the SWRCB website at the following address:

http://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/Publications.shtml

The List of certified testers may be lists developed by the American Water Works Association and local county health agencies.

Backflow preventers should be tested at least yearly or more often as required by the health agency or water supplier.

(6) *The maintenance of records of locations, tests and repairs of backflow preventers*

Adequate records should be kept and filed for reference. These records should include, in addition to the name of the owner of the premises, the:

- a) Date of inspection
- b) Results of inspection
- c) Required protection
- d) List of all backflow preventer devices in the system
- e) Test and maintenance reports
- f) All correspondence between the water supplier, the local health authority, and the consumer
- g) Records must be maintained for a minimum of three years

Records of inspection and testing should be evaluated to determine if:

- a) Devices are frequently or sufficiently reviewed to detect failure.
- b) There are unusual feature of a particular model of device or component.
- c) Cause of failure can be eliminated.

A program should be established to notify the water user when his backflow preventer must be tested. (A minimum of once each year is required.) After installation or repair, a backflow preventer should be tested and approved before it is accepted.

7605. Testing and Maintenance of Backflow Preventers

Regulations require the following regarding testing and maintenance of backflow prevention devices:

- (a) The water supplier shall assure that adequate maintenance and periodic testing are provided by the water user to ensure their proper operation.
- (b) Backflow preventers shall be tested by persons who have demonstrated their competency in testing of these devices to the water supplier or health agency.
- (c) Backflow preventers shall be tested at least annually or more frequently if determined to be necessary by the health agency or water supplier. When devices are found to be defective, they shall be repaired or replaced in accordance with the provisions of this Chapter.
- (d) Backflow preventers shall be tested immediately after they are installed, relocated or repaired and not placed in service unless they are functioning as required.
- (e) The water supplier shall notify the water user when testing of backflow preventers is needed. The notice shall contain the date when the test must be completed.
- (f) Reports of testing and maintenance shall be maintained by the water supplier for a minimum of three years.

Cross-Connection Survey Summary Form-Small Community Water Systems

Name of System _____ System Number _____

Description of Survey Procedures-How survey was conducted, (include copy of survey form):
Person conducting survey (List name and qualifications):

Procedures for Residential Connections:

Procedures for Commercial Connections:

Total number of service connections _____ Number of service connections surveyed _____
Number of connections with auxiliary sources (i.e. wells or creek pumps) _____
Number of connections with other hazards _____
Total number of backflow prevention devices _____

Type of Hazard Identified(i.e. private well, hot tub, irrigation system, swimming pool, etc)	Number of connections with hazard	Number of devices installed	Number where device not necessary

Describe follow-up for service connections that did not respond to the survey:

Long-term (Describe on-going cross-connection protection & testing of backflow prevention assemblies)

Submitted by (signature) _____ Date _____

Appendix H:
Emergency Notification Plan Template

State Water Resources Control Board

System No. _____

DIVISION OF DRINKING WATER – TULARE DISTRICT WATER QUALITY EMERGENCY NOTIFICATION PLAN

Water System Name: _____

Physical Location Address: _____

The following persons have been designated to implement the Plan upon notification by the Division of Drinking Water that an imminent danger to the health of the water users exists:

Contact Name & Title	Email Address	Home/Office	Cell
1. _____			
2. _____			
3. _____			

The implementation of the plan will be carried out with the following Division of Drinking Water and County Health personnel:

Contact Name & Title	Email Address	Office	Cell
1. Kristin Willet, Tulare District Engineer Division of Drinking Water	kristin.willet@waterboards.ca.gov	(559) 447-3300	(559) 280-6363
2. Tricia Wathen, Supervising Sanitary Engineer Division of Drinking Water	tricia.wathen@waterboards.ca.gov	(559) 447-3300	(559) 696-8506
3. Nilsa Gonzalez, Director Tulare County Environmental Health Division Manager	ngonzale@tularehhsa.org	(559) 624-7400	(559) 285-2440
4. If the above personnel cannot be reached, contact:			

Office of Emergency Services (24 Hrs.) (800) 852-7550 or (916) 845-8911
Ask for "Division of Drinking of Drinking Water, Duty Officer"

NOTIFICATION PLAN

Community and Nontransient Noncommunity

(Must identify three methods)

- ☐ Door to Door Delivery ☐ Posted Notification
☐ Social Media ☐ Reverse 911/Telephone
☐ News Media (TV, Radio, Newspaper) ☐ Email
☐ Other: personal phone call _____

Transient Noncommunity

☐ Water system must post notification. Hand delivered notification must be provided to any residential/overnight customers.

***SYSTEMS SERVING MORE THAN 200 SERVICE CONNECTIONS MUST PROVIDE A CUSTOM PLAN.**

APPROXIMATE TIME TO ISSUE NOTICE: _____ HRS

Report prepared by:

Signature and Title

Date

Appendix K: Groundwater Quality Data Summary

YETTEM WELL 01 WATER QUALITY SUMMARY

ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	2	11.4	11.5	11.5
ALKALINITY, BICARBONATE AS CaCO ₃	MG/L	6	170	180	210
ALKALINITY, CARBONATE	MG/L	6	0	0	0
ALKALINITY, TOTAL AS CaCO ₃	MG/L	6	140	147	170
ALUMINUM	UG/L	5	0	33.4	120
ANTIMONY, TOTAL	UG/L	5	0	0	0
ARSENIC	UG/L	5	2.8	2.92	3
BARIUM	UG/L	5	0	52.4	98
BERYLLIUM, TOTAL	UG/L	5	0	0	0
BORON	UG/L	2	0	0	0
CADMIUM	UG/L	5	0	0	0
CALCIUM	MG/L	8	20	23.3	28
CHLORIDE	MG/L	6	16	22.2	29
CHROMIUM, HEX	UG/L	1	0	0	0
CHROMIUM, TOTAL	UG/L	5	0	0.26	1.3
COLOR	UNITS	6	0	0.833	5
COPPER, FREE	UG/L	7	0	1.36	5.9
FLUORIDE	MG/L	5	0	0.104	0.18
FOAMING AGENTS (SURFACTANTS)	MG/L	7	0	0	0
HARDNESS, TOTAL AS CaCO ₃	MG/L	5	110	123	150
HYDROXIDE AS CALCIUM CARBONATE	MG/L	6	0	0	0
IRON	UG/L	12	0	82.7	480
LANGELIER INDEX @ SOURCE TEMP	LANG	3	-0.4	-0.0133	0.22
LEAD	UG/L	5	0	0	0
MAGNESIUM	MG/L	8	14	17.3	21
MANGANESE	UG/L	7	0	8.29	40
MERCURY	UG/L	5	0	0	0
NICKEL	UG/L	5	0	0	0
NITRATE (AS N)	MG/L	200	4.2	8.87	12.2
NITRATE + NITRITE (AS N)	MG/L	5	10	10.6	12
NITRITE (AS N)	MG/L	7	0	0	0
ODOR THRESHOLD	TON	6	0	0.667	2
PERCHLORATE	UG/L	9	0	0	0
PH, LAB	pH	5	7.4	7.86	8.2
POTASSIUM	MG/L	4	0	0.875	1.3
SELENIUM	UG/L	5	0	0	0
SILVER	UG/L	6	0	0	0
SODIUM	MG/L	6	40	42.2	44
SPECIFIC CONDUCTANCE	UMHO/CM	7	400	459	530
SULFATE	MG/L	7	11	14.7	18
TDS	MG/L	7	250	277	300
THALLIUM, TOTAL	UG/L	5	0	0	0
TURBIDITY, LAB	NTU	6	0.1	0.657	1.9
ZINC	UG/L	7	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	9	0	1.32	3.07
RADIUM-228	PCI/L	4	0	0.30	1.2
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	8	0	0	0
DIBROMOCHLOROPROPANE	UG/L	5	0	0	0

EAST OROSI WELL 01 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	4	10.6	11.7	12.4
ALKALINITY, BICARBONATE AS CaCO3	MG/L	4	110	173	240
ALKALINITY, CARBONATE	MG/L	4	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	4	90	150	200
ALUMINUM	UG/L	4	0	0	0
ANTIMONY, TOTAL	UG/L	4	0	0	0
ARSENIC	UG/L	4	0	0.5	2
BARIUM	UG/L	4	0	46.3	130
BERYLLIUM, TOTAL	UG/L	4	0	0	0
BORON	UG/L	2	0	0	0
CADMIUM	UG/L	4	0	0	0
CALCIUM	MG/L	4	31	46.5	69
CHLORIDE	MG/L	4	16	21.5	30
CHROMIUM, HEX	UG/L	2	0	0.235	0.47
CHROMIUM, TOTAL	UG/L	4	0	0	0
COLOR	UNITS	5	0	1	5
COPPER, FREE	UG/L	4	0	0	0
FLUORIDE	MG/L	4	0.1	0.155	0.3
FOAMING AGENTS (SURFACTANTS)	MG/L	4	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	4	139	201	296
HYDROXIDE AS CALCIUM CARBONATE	MG/L	4	0	0	0
IRON	UG/L	17	0	153	1300
LANGELIER INDEX @ SOURCE TEMP	LANG	2	-1.2	-0.3	0.6
LEAD	UG/L	4	0	0.275	1.1
MAGNESIUM	MG/L	5	15	20.8	30
MANGANESE	UG/L	17	0	15.7	210
MERCURY	UG/L	4	0	0	0
NICKEL	UG/L	4	0	0	0
NITRATE (AS N)	MG/L	44	0.43	10.0000	14.4
NITRATE + NITRITE (AS N)	MG/L	4	8.8	10.2	12.8
NITRITE (AS N)	MG/L	4	0	0	0
ODOR THRESHOLD	TON	5	0	0	0
PERCHLORATE	UG/L	5	0	1.36	4
PH, LAB	pH	4	6.8	7.58	8
POTASSIUM	MG/L	4	3	3.58	4
SELENIUM	UG/L	4	0	0	0
SILVER	UG/L	4	0	0	0
SODIUM	MG/L	4	19	20.5	24
SPECIFIC CONDUCTANCE	UMHO/CM	6	397	500	713
SULFATE	MG/L	4	19	30.2	58
TDS	MG/L	6	240	330	450
THALLIUM, TOTAL	UG/L	4	0	0	0
TURBIDITY, LAB	NTU	18	0	0.673	6.9
ZINC	UG/L	4	0	7.5	30
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	5	0.283	1.83	3.38
RADIUM-228	PCI/L	5	0	0.01	0.07
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	8	0	0.00075	0.006
DIBROMOCHLOROPROPANE	UG/L	4	0	0	0

MONSON WELL 01 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	2	11.9	12	12
ALKALINITY, BICARBONATE AS CaCO3	MG/L	3	140	150	160
ALKALINITY, CARBONATE	MG/L	3	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	3	120	123	130
ALUMINUM	UG/L	2	0	0	0
ANTIMONY, TOTAL	UG/L	2	0	0	0
ARSENIC	UG/L	2	3	3.6	4.2
BARIUM	UG/L	2	0	17.5	35
BERYLLIUM, TOTAL	UG/L	2	0	0	0
BORON	UG/L	2	0	0	0
CADMIUM	UG/L	2	0	0	0
CALCIUM	MG/L	4	19	27	43
CHLORIDE	MG/L	3	21	22	23
CHROMIUM, HEX		0	0	0	0
CHROMIUM, TOTAL	UG/L	2	0	0	0
COLOR	UNITS	2	0	2.5	5
COPPER, FREE	UG/L	3	0	0	0
FLUORIDE	MG/L	3	0.1	0.143	0.2
FOAMING AGENTS (SURFACTANTS)	MG/L	3	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	3	83.7	112	165
HYDROXIDE AS CALCIUM CARBONATE	MG/L	3	0	0	0
IRON	UG/L	3	0	0	0
LANGELIER INDEX @ SOURCE TEMP	LANG	1	0.1	0.1	0.1
LEAD	UG/L	2	0	0	0
MAGNESIUM	MG/L	4	5.9	8.48	14
MANGANESE	UG/L	3	0	0	0
MERCURY	UG/L	2	0	0	0
NICKEL	UG/L	2	0	0	0
NITRATE (AS N)	MG/L	7	0	1.44	3.1
NITRATE + NITRITE (AS N)	MG/L	4	2.6	2.83	3.1
NITRITE (AS N)	MG/L	3	0	0	0
ODOR THRESHOLD	TON	2	0	0.5	1
PERCHLORATE	UG/L	10	0	0	0
PH, LAB	pH	2	7.9	8	8.1
POTASSIUM	MG/L	3	1.9	2.97	4
SELENIUM	UG/L	2	0	0	0
SILVER	UG/L	2	0	0	0
SODIUM	MG/L	3	32	37.7	43
SPECIFIC CONDUCTANCE	UMHO/CM	3	340	347	350
SULFATE	MG/L	3	4.2	4.57	5
TDS	MG/L	3	200	220	230
THALLIUM, TOTAL	UG/L	2	0	0	0
TURBIDITY, LAB	NTU	2	0.58	0.94	1.3
ZINC	UG/L	3	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	18	0	0.79	3.64
RADIUM-228	PCI/L	7	0	0.38	1.97
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	12	0	0	0
DIBROMOCHLOROPROPANE	UG/L	8	0	0	0

SEVILLE WELL 01 WATER QUALITY SUMMARY

ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	1	10.9	10.9	10.9
ALKALINITY, BICARBONATE AS CaCO ₃	MG/L	5	160	180	200
ALKALINITY, CARBONATE	MG/L	5	0	0	0
ALKALINITY, TOTAL AS CaCO ₃	MG/L	5	130	146	160
ALUMINUM	UG/L	5	0	409	2000
ANTIMONY, TOTAL	UG/L	5	0	0	0
ARSENIC	UG/L	5	0	1.08	1.5
BARIUM	UG/L	5	0	54.4	77
BERYLLIUM, TOTAL	UG/L	5	0	0	0
BORON	UG/L	1	0	0	0
CADMIUM	UG/L	5	0	0	0
CALCIUM	MG/L	9	22	34.9	44
CHLORIDE	MG/L	5	15	32	66
CHROMIUM, HEX	UG/L	2	0	1	2
CHROMIUM, TOTAL	UG/L	5	0	0.4	2
COLOR	UNITS	5	0	1.4	5
COPPER, FREE	UG/L	5	0	0	0
FLUORIDE	MG/L	5	0	0.108	0.17
FOAMING AGENTS (SURFACTANTS)	MG/L	5	0	0.024	0.12
HARDNESS, TOTAL AS CaCO ₃	MG/L	6	120	154	200
HYDROXIDE AS CALCIUM CARBONATE	MG/L	5	0	0	0
IRON	UG/L	5	0	400	2000
LANGELIER INDEX @ SOURCE TEMP	LANG	2	0.17	0.235	0.3
LEAD	UG/L	4	0	0	0
MAGNESIUM	MG/L	9	15	17	22
MANGANESE	UG/L	5	0	19.4	72
MERCURY	UG/L	5	0	0.04	0.2
NICKEL	UG/L	5	0	13.5	66
NITRATE (AS N)	MG/L	72	2.2	7.80	9.71
NITRATE + NITRITE (AS N)	MG/L	3	5.7	7.4	8.6
NITRITE (AS N)	MG/L	5	0	0	0
ODOR THRESHOLD	TON	5	0	1	2
PERCHLORATE	UG/L	11	0	0	0
PH, LAB	pH	4	7.8	7.95	8.1
POTASSIUM	MG/L	3	1	1.53	2
SELENIUM	UG/L	5	0	0.2	1
SILVER	UG/L	5	0	0	0
SODIUM	MG/L	5	31	35.4	47
SPECIFIC CONDUCTANCE	UMHO/CM	5	440	487	580
SULFATE	MG/L	5	20	22.7	26
TDS	MG/L	5	270	324	370
THALLIUM, TOTAL	UG/L	5	0	0	0
TURBIDITY, LAB	NTU	5	0	3.56	16
ZINC	UG/L	5	0	13	40
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	8	-0.33	0.67	2
RADIUM-228	PCI/L	3	-0.14	0.05	0.28
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	6	0	0	0
DIBROMOCHLOROPROPANE	UG/L	5	0	0	0

YETTEM WELL 02 WATER QUALITY SUMMARY

ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	1	11.5	11.5	11.5
ALKALINITY, BICARBONATE AS CaCO3	MG/L	7	170	177	190
ALKALINITY, CARBONATE	MG/L	7	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	7	140	141	150
ALUMINUM	UG/L	6	0	6	17
ANTIMONY, TOTAL	UG/L	6	0	0	0
ARSENIC	UG/L	6	2.3	2.68	3
BARIUM	UG/L	6	0	70.5	92
BERYLLIUM, TOTAL	UG/L	6	0	0	0
BORON	UG/L	1	0	0	0
CADMIUM	UG/L	6	0	0	0
CALCIUM	MG/L	8	16	18.3	22
CHLORIDE	MG/L	7	15	17	18
CHROMIUM, HEX	UG/L	1	0	0	0
CHROMIUM, TOTAL	UG/L	6	0	0.383	1.2
COLOR	UNITS	7	0	0.714	5
COPPER, FREE	UG/L	7	0	0	0
FLUORIDE	MG/L	6	0	0.117	0.19
FOAMING AGENTS (SURFACTANTS)	MG/L	7	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	7	93.4	105	120
HYDROXIDE AS CALCIUM CARBONATE	MG/L	7	0	0	0
IRON	UG/L	12	0	81.5	430
LANGELIER INDEX @ SOURCE TEMP	LANG	4	-0.3	0.0125	0.35
LEAD	UG/L	6	0	0	0
MAGNESIUM	MG/L	8	13	14.6	16
MANGANESE	UG/L	7	0	0.971	6.8
MERCURY	UG/L	6	0	0	0
NICKEL	UG/L	6	0	0.483	1.6
NITRATE (AS N)	MG/L	175	3.8	5.72	9.8
NITRATE + NITRITE (AS N)	MG/L	5	5.5	5.68	5.8
NITRITE (AS N)	MG/L	8	0	0	0
ODOR THRESHOLD	TON	7	0	0.714	2
PERCHLORATE	UG/L	8	0	0	0
PH, LAB	pH	7	7.5	7.97	8.3
POTASSIUM	MG/L	3	0	0.733	1.1
SELENIUM	UG/L	6	0	0	0
SILVER	UG/L	7	0	0	0
SODIUM	MG/L	7	39	42.7	46
SPECIFIC CONDUCTANCE	UMHO/CM	7	380	414	430
SULFATE	MG/L	7	13	14	15.1
TDS	MG/L	7	230	243	260
THALLIUM, TOTAL	UG/L	6	0	0	0
TURBIDITY, LAB	NTU	7	0	0.706	3.1
ZINC	UG/L	7	0	0.971	6.8
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	9	0	1.04	1.98
RADIUM-228	PCI/L	4	0	0.28	1.1
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	7	0	0	0
DIBROMOCHLOROPROPANE	UG/L	6	0	0	0

EAST OROSI WELL 02 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	3	12	12.4	13
ALKALINITY, BICARBONATE AS CaCO3	MG/L	3	170	210	230
ALKALINITY, CARBONATE	MG/L	3	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	3	140	187	230
ALUMINUM	UG/L	3	0	0	0
ANTIMONY, TOTAL	UG/L	3	0	0	0
ARSENIC	UG/L	3	0	1.47	2.4
BARIUM	UG/L	3	0	60.6	130
BERYLLIUM, TOTAL	UG/L	3	0	0	0
BORON	UG/L	1	0	0	0
CADMIUM	UG/L	3	0	0	0
CALCIUM	MG/L	3	41	58.3	74
CHLORIDE	MG/L	3	16	23.7	29
CHROMIUM, HEX	UG/L	2	0	0.225	0.45
CHROMIUM, TOTAL	UG/L	3	0	0	0
COLOR	UNITS	3	0	1.67	5
COPPER, FREE	UG/L	3	0	0	0
FLUORIDE	MG/L	3	0.12	0.15	0.2
FOAMING AGENTS (SURFACTANTS)	MG/L	3	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	3	176	252	320
HYDROXIDE AS CALCIUM CARBONATE	MG/L	3	0	0	0
IRON	UG/L	3	0	0	0
LANGELIER INDEX @ SOURCE TEMP	LANG	1	0.2	0.2	0.2
LEAD	UG/L	3	0	0	0
MAGNESIUM	MG/L	3	18	26.3	34
MANGANESE	UG/L	3	0	0	0
MERCURY	UG/L	3	0	0	0
NICKEL	UG/L	3	0	0	0
NITRATE (AS N)	MG/L	59	0	10.80	14.3
NITRATE + NITRITE (AS N)	MG/L	3	9.1	11	12
NITRITE (AS N)	MG/L	3	0	0	0
ODOR THRESHOLD	TON	3	0	0	0
PERCHLORATE	UG/L	4	0	0.9	3.6
PH, LAB	pH	3	7.9	7.9	7.9
POTASSIUM	MG/L	3	3	4.27	5.4
SELENIUM	UG/L	3	0	0	0
SILVER	UG/L	3	0	0	0
SODIUM	MG/L	3	17	23.3	28
SPECIFIC CONDUCTANCE	UMHO/CM	3	456	609	760
SULFATE	MG/L	3	16	41.7	66
TDS	MG/L	3	310	393	470
THALLIUM, TOTAL	UG/L	3	0	0	0
TURBIDITY, LAB	NTU	3	0	0.143	0.26
ZINC	UG/L	3	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	4	0.823	2.35	5.54
RADIUM-228	PCI/L	16	0	0.19	1.05
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	9	0	0.000889	0.008
DIBROMOCHLOROPROPANE	UG/L	4	0	0.0163	0.065

SEVILLE WELL 02 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	1	11	11	11
ALKALINITY, BICARBONATE AS CaCO3	MG/L	4	150	168	200
ALKALINITY, CARBONATE	MG/L	4	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	4	130	138	160
ALUMINUM	UG/L	4	0	505	2000
ANTIMONY, TOTAL	UG/L	4	0	0	0
ARSENIC	UG/L	4	1.2	1.73	2
BARIUM	UG/L	4	0	59.5	97
BERYLLIUM, TOTAL	UG/L	4	0	0	0
BORON	UG/L	1	0	0	0
CADMIUM	UG/L	4	0	0	0
CALCIUM	MG/L	8	35	43.3	58
CHLORIDE	MG/L	4	15	68.8	100
CHROMIUM, HEX	UG/L	1	0.38	0.38	0.38
CHROMIUM, TOTAL	UG/L	4	0	1.28	3.9
COLOR	UNITS	4	0	1.25	5
COPPER, FREE	UG/L	4	0	0	0
FLUORIDE	MG/L	4	0	0.0575	0.13
FOAMING AGENTS (SURFACTANTS)	MG/L	4	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	5	160	177	211
HYDROXIDE AS CALCIUM CARBONATE	MG/L	4	0	0	0
IRON	UG/L	4	0	500	2000
LANGELIER INDEX @ SOURCE TEMP	LANG	1	0.3	0.3	0.3
LEAD	UG/L	3	0	0	0
MAGNESIUM	MG/L	8	14	16.3	19
MANGANESE	UG/L	4	17	38.5	72
MERCURY	UG/L	4	0	0.05	0.2
NICKEL	UG/L	4	0	17.6	66
NITRATE (AS N)	MG/L	88	0	6.26	8.1
NITRATE + NITRITE (AS N)	MG/L	3	5.5	5.63	5.8
NITRITE (AS N)	MG/L	4	0	0	0
ODOR THRESHOLD	TON	4	0	1	2
PERCHLORATE	UG/L	5	0	0	0
PH, LAB	pH	3	7.8	7.93	8
POTASSIUM	MG/L	2	2	2	2
SELENIUM	UG/L	4	0	0.4	1.6
SILVER	UG/L	4	0	0	0
SODIUM	MG/L	4	31	43	50
SPECIFIC CONDUCTANCE	UMHO/CM	4	440	559	635
SULFATE	MG/L	4	14.3	19.3	23
TDS	MG/L	4	330	360	390
THALLIUM, TOTAL	UG/L	4	0	0	0
TURBIDITY, LAB	NTU	4	0	4.1	16
ZINC	UG/L	4	0	12	40
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	8	0	1.36	3.6
RADIUM-228	PCI/L	7	0	0.52	1.2
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	6	0	0	0
DIBROMOCHLOROPROPANE	UG/L	4	0	0	0

SULTANA WELL 02 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	2	11.6	11.8	12
ALKALINITY, BICARBONATE AS CaCO3	MG/L	2	230	230	230
ALKALINITY, CARBONATE	MG/L	2	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	2	190	190	190
ALUMINUM	UG/L	2	0	0	0
ANTIMONY, TOTAL	UG/L	2	0	0	0
ARSENIC	UG/L	3	0	0	0
BARIUM	UG/L	2	0	35.4	70.8
BERYLLIUM, TOTAL	UG/L	2	0	0	0
BORON	UG/L	2	0	0	0
CADMIUM	UG/L	2	0	0	0
CALCIUM	MG/L	2	53	54.5	56
CHLORIDE	MG/L	2	16	17.5	19
CHROMIUM, HEX	UG/L	1	0.8	0.8	0.8
CHROMIUM, TOTAL	UG/L	2	0	0.5	1
COLOR	UNITS	2	0	3	6
COPPER, FREE	UG/L	2	0	0	0
FLUORIDE	MG/L	2	0	0.05	0.1
FOAMING AGENTS (SURFACTANTS)	MG/L	2	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	2	206	212	218
HYDROXIDE AS CALCIUM CARBONATE	MG/L	2	0	0	0
IRON	UG/L	2	0	130	260
LANGELIER INDEX @ SOURCE TEMP	LANG	2	-0.3	-0.05	0.2
LEAD	UG/L	2	0	0	0
MAGNESIUM	MG/L	2	18	18.5	19
MANGANESE	UG/L	2	0	5	10
MERCURY	UG/L	2	0	0	0
NICKEL	UG/L	2	0	0	0
NITRATE (AS N)	MG/L	14	4.5	8.48	11.7
NITRATE + NITRITE (AS N)	MG/L	2	9.8	9.85	9.9
NITRITE (AS N)	MG/L	2	0	0	0
ODOR THRESHOLD	TON	2	0	0	0
PERCHLORATE	UG/L	2	0	0	0
PH, LAB	pH	2	7.2	7.4	7.6
POTASSIUM	MG/L	2	2	2.5	3
SELENIUM	UG/L	2	0	0	0
SILVER	UG/L	2	0	0	0
SODIUM	MG/L	2	27	28	29
SPECIFIC CONDUCTANCE	UMHO/CM	2	545	550	554
SULFATE	MG/L	2	30	30.6	31.2
TDS	MG/L	2	360	370	380
THALLIUM, TOTAL	UG/L	2	0	0	0
TURBIDITY, LAB	NTU	2	0.3	1.85	3.4
ZINC	UG/L	2	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	2	0	0.28	0.561
RADIUM-228	PCI/L	4	0	0.0000	0
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	6	0	0	0
DIBROMOCHLOROPROPANE	UG/L	7	0.45	0.536	0.71

SULTANA WELL 03 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	4	11.2	11.7	12.1
ALKALINITY, BICARBONATE AS CaCO3	MG/L	4	160	178	200
ALKALINITY, CARBONATE	MG/L	4	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	4	130	145	160
ALUMINUM	UG/L	4	0	0	0
ANTIMONY, TOTAL	UG/L	4	0	0	0
ARSENIC	UG/L	4	2	2	2
BARIUM	UG/L	4	0	27.4	55.9
BERYLLIUM, TOTAL	UG/L	4	0	0	0
BORON	UG/L	4	0	0	0
CADMIUM	UG/L	4	0	0	0
CALCIUM	MG/L	4	37	44	55
CHLORIDE	MG/L	4	35	41.5	46
CHROMIUM, HEX	UG/L	1	0.8	0.8	0.8
CHROMIUM, TOTAL	UG/L	4	0	0.25	1
COLOR	UNITS	4	0	0	0
COPPER, FREE	UG/L	4	0	0	0
FLUORIDE	MG/L	4	0.1	0.15	0.2
FOAMING AGENTS (SURFACTANTS)	MG/L	3	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	4	133	159	199
HYDROXIDE AS CALCIUM CARBONATE	MG/L	4	0	0	0
IRON	UG/L	4	0	7.5	30
LANGELIER INDEX @ SOURCE TEMP	LANG	3	-0.7	-0.2	0.2
LEAD	UG/L	4	0	0	0
MAGNESIUM	MG/L	4	10	12	15
MANGANESE	UG/L	4	0	0	0
MERCURY	UG/L	4	0	0	0
NICKEL	UG/L	4	0	0	0
NITRATE (AS N)	MG/L	17	2.03	3.46	6.4
NITRATE + NITRITE (AS N)	MG/L	4	2.3	4.05	6.4
NITRITE (AS N)	MG/L	4	0	0	0
ODOR THRESHOLD	TON	4	0	2.5	8
PERCHLORATE	UG/L	6	0	0	0
PH, LAB	pH	3	6.9	7.5	8
POTASSIUM	MG/L	4	2	2.25	3
SELENIUM	UG/L	4	0	0.5	1
SILVER	UG/L	4	0	0	0
SODIUM	MG/L	4	33	35.3	38
SPECIFIC CONDUCTANCE	UMHO/CM	4	442	479	530
SULFATE	MG/L	4	6	13.8	24
TDS	MG/L	4	290	313	330
THALLIUM, TOTAL	UG/L	4	0	0	0
TURBIDITY, LAB	NTU	4	0	0.125	0.3
ZINC	UG/L	4	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	11	0	0.50	1.41
RADIUM-228	PCI/L	9	0	0.23	1.15
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	6	0	0	0
DIBROMOCHLOROPROPANE	UG/L	5	0.02	0.043	0.065

OROSI WELL 04 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	4	12	12	12
ALKALINITY, BICARBONATE AS CaCO3	MG/L	4	170	195	210
ALKALINITY, CARBONATE	MG/L	4	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	4	160	170	180
ALUMINUM	UG/L	4	0	0	0
ANTIMONY, TOTAL	UG/L	4	0	0	0
ARSENIC	UG/L	4	0	1.73	2.6
BARIUM	UG/L	4	0	48.5	100
BERYLLIUM, TOTAL	UG/L	4	0	0	0
BORON	UG/L	2	0	0	0
CADMIUM	UG/L	4	0	0	0
CALCIUM	MG/L	4	44	45.8	47
CHLORIDE	MG/L	4	18	18.5	19
CHROMIUM, HEX	UG/L	1	0	0	0
CHROMIUM, TOTAL	UG/L	4	0	0	0
COLOR	UNITS	4	0	2.5	10
COPPER, FREE	UG/L	4	0	0	0
FLUORIDE	MG/L	4	0.1	0.123	0.14
FOAMING AGENTS (SURFACTANTS)	MG/L	4	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	4	190	190	190
HYDROXIDE AS CALCIUM CARBONATE	MG/L	4	0	0	0
IRON	UG/L	4	0	0	0
LANGELIER INDEX @ SOURCE TEMP	LANG	4	0.29	0.475	0.56
LEAD	UG/L	4	0	0	0
MAGNESIUM	MG/L	4	17	17.8	18
MANGANESE	UG/L	4	0	0	0
MERCURY	UG/L	4	0	0	0
NICKEL	UG/L	4	0	0	0
NITRATE (AS N)	MG/L	55	4.2	5.73	6.5
NITRATE + NITRITE (AS N)	MG/L	3	5.5	5.7	5.9
NITRITE (AS N)	MG/L	4	0	0	0
ODOR THRESHOLD	TON	4	0	0	0
PERCHLORATE	UG/L	6	0	0.267	1.6
PH, LAB	pH	4	8	8.13	8.2
POTASSIUM	MG/L	4	3.3	3.38	3.4
SELENIUM	UG/L	4	0	0	0
SILVER	UG/L	4	0	0	0
SODIUM	MG/L	4	22	22.8	24
SPECIFIC CONDUCTANCE	UMHO/CM	9	430	456	510
SULFATE	MG/L	4	13	13.8	14
TDS	MG/L	4	300	315	330
THALLIUM, TOTAL	UG/L	4	0	0	0
TURBIDITY, LAB	NTU	4	0	0.025	0.1
ZINC	UG/L	4	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	18	0	0.85	3.35
RADIUM-228	PCI/L	2	0.08	0.27	0.46
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	98	0	0.0000148	0.00074
DIBROMOCHLOROPROPANE	UG/L	5	0	0	0

CUTLER WELL 05 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	4	12	12.3	13
ALKALINITY, BICARBONATE AS CaCO3	MG/L	5	220	254	270
ALKALINITY, CARBONATE	MG/L	5	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	5	210	216	220
ALUMINUM	UG/L	5	0	0	0
ANTIMONY, TOTAL	UG/L	4	0	0	0
ARSENIC	UG/L	4	0	0.525	2.1
BARIUM	UG/L	4	150	163	180
BERYLLIUM, TOTAL	UG/L	4	0	0	0
BORON	UG/L	1	0	0	0
CADMIUM	UG/L	4	0	0	0
CALCIUM	MG/L	5	62	63.8	66
CHLORIDE	MG/L	5	30	37	42
CHROMIUM, HEX	UG/L	2	0	0	0
CHROMIUM, TOTAL	UG/L	4	0	0	0
COLOR	UNITS	4	0	1.25	5
COPPER, FREE	UG/L	4	0	0	0
FLUORIDE	MG/L	4	0.14	0.15	0.16
FOAMING AGENTS (SURFACTANTS)	MG/L	4	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	5	250	254	260
HYDROXIDE AS CALCIUM CARBONATE	MG/L	5	0	0	0
IRON	UG/L	5	0	0	0
LANGELIER INDEX @ SOURCE TEMP	LANG	4	0.4	0.52	0.68
LEAD	UG/L	4	0	0	0
MAGNESIUM	MG/L	5	23	23	23
MANGANESE	UG/L	5	0	18	33
MERCURY	UG/L	4	0	0	0
NICKEL	UG/L	4	0	0	0
NITRATE (AS N)	MG/L	173	7.91	9.17	11
NITRATE + NITRITE (AS N)	MG/L	3	8.8	9	9.4
NITRITE (AS N)	MG/L	4	0	0	0
ODOR THRESHOLD	TON	4	0	0	0
PERCHLORATE	UG/L	6	0	0.467	2.8
PH, LAB	pH	5	7.8	7.94	8.1
POTASSIUM	MG/L	5	3.4	3.7	3.9
SELENIUM	UG/L	4	0	0	0
SILVER	UG/L	4	0	0	0
SODIUM	MG/L	5	33	36.4	39
SPECIFIC CONDUCTANCE	UMHO/CM	11	580	637	680
SULFATE	MG/L	5	27	29.6	32
TDS	MG/L	5	410	434	460
THALLIUM, TOTAL	UG/L	4	0	0	0
TURBIDITY, LAB	NTU	4	0.1	0.313	0.83
ZINC	UG/L	4	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	25	0	1.28	2.94
RADIUM-228	PCI/L	4	-0.11	-0.03	0
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	50	0	0.00392	0.0087
DIBROMOCHLOROPROPANE	UG/L	146	0.019	0.0793	0.13

OROSI WELL 05A WATER QUALITY SUMMARY

ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	4	12	12	12
ALKALINITY, BICARBONATE AS CaCO ₃	MG/L	4	150	168	180
ALKALINITY, CARBONATE	MG/L	4	0	0	0
ALKALINITY, TOTAL AS CaCO ₃	MG/L	4	130	143	150
ALUMINUM	UG/L	4	0	0	0
ANTIMONY, TOTAL	UG/L	4	0	0	0
ARSENIC	UG/L	4	0	1.58	3.4
BARIUM	UG/L	4	0	17.5	70
BERYLLIUM, TOTAL	UG/L	4	0	0	0
BORON	UG/L	2	0	0	0
CADMIUM	UG/L	4	0	0	0
CALCIUM	MG/L	4	32	36.5	39
CHLORIDE	MG/L	4	12	13	14
CHROMIUM, HEX	UG/L	1	0	0	0
CHROMIUM, TOTAL	UG/L	4	0	0	0
COLOR	UNITS	4	0	1.25	5
COPPER, FREE	UG/L	4	0	0	0
FLUORIDE	MG/L	4	0.1	0.118	0.14
FOAMING AGENTS (SURFACTANTS)	MG/L	4	0	0	0
HARDNESS, TOTAL AS CaCO ₃	MG/L	4	140	153	160
HYDROXIDE AS CALCIUM CARBONATE	MG/L	4	0	0	0
IRON	UG/L	4	0	0	0
LANGELIER INDEX @ SOURCE TEMP	LANG	4	0.17	0.283	0.4
LEAD	UG/L	4	0	0	0
MAGNESIUM	MG/L	4	13	14	15
MANGANESE	UG/L	4	0	0	0
MERCURY	UG/L	4	0	0	0
NICKEL	UG/L	4	0	0	0
NITRATE (AS N)	MG/L	38	3.84	5.23	9
NITRATE + NITRITE (AS N)	MG/L	3	4.4	4.93	5.2
NITRITE (AS N)	MG/L	4	0	0	0
ODOR THRESHOLD	TON	4	0	0.25	1
PERCHLORATE	UG/L	6	0	0.3	1.8
PH, LAB	pH	4	8	8.13	8.2
POTASSIUM	MG/L	4	2.8	2.9	3
SELENIUM	UG/L	4	0	0	0
SILVER	UG/L	4	0	0	0
SODIUM	MG/L	4	19	19.8	20
SPECIFIC CONDUCTANCE	UMHO/CM	9	320	363	410
SULFATE	MG/L	4	5.7	7.3	8.6
TDS	MG/L	4	250	270	290
THALLIUM, TOTAL	UG/L	4	0	0	0
TURBIDITY, LAB	NTU	4	0	0.09	0.18
ZINC	UG/L	4	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	18	-1.06	0.35	2
RADIUM-228	PCI/L	2	0.29	0.38	0.47
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	100	0	0.00056	0.005
DIBROMOCHLOROPROPANE	UG/L	5	0	0	0

CUTLER WELL 06 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX		0	0	0	0
ALKALINITY, BICARBONATE AS CaCO3	MG/L	10	170	209	270
ALKALINITY, CARBONATE		0	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	10	150	174	220
ALUMINUM	UG/L	7	0	2.86	20
ANTIMONY, TOTAL	UG/L	6	0	0	0
ARSENIC	UG/L	10	2.3	3.61	5
BARIIUM	MG/L	10	0	0.055	0.2
BERYLLIUM, TOTAL	UG/L	7	0	0.143	1
BORON	MG/L	2	0.024	0.062	0.1
CADMIUM	UG/L	11	0	0.409	1
CALCIUM	MG/L	10	29	43	60
CHLORIDE	MG/L	10	12	18.8	29
CHROMIUM, HEX	UG/L	2	0	0.5	1
CHROMIUM, TOTAL	UG/L	13	0	3.23	10
COLOR		0	0	0	0
COPPER, FREE	MG/L	11	0	0.0227	0.05
FLUORIDE	MG/L	10	0	0.159	0.21
FOAMING AGENTS (SURFACTANTS)	MG/L	10	0	0.025	0.05
HARDNESS, TOTAL AS CaCO3	MG/L	10	120	181	250
HYDROXIDE AS CALCIUM CARBONATE		0	0	0	0
IRON	UG/L	11	0	66.4	220
LANGELIER INDEX @ SOURCE TEMP		0	0	0	0
LEAD	UG/L	10	0	2	5
MAGNESIUM	MG/L	10	12	17.7	25
MANGANESE	UG/L	11	0	22.7	110
MERCURY	UG/L	11	0	0.336	1
NICKEL	UG/L	7	0	1.43	10
NITRATE (AS N)	MG/L	170	0	4.13	13
NITRATE + NITRITE (AS N)		0	0	0	0
NITRITE (AS N)	MG/L	8	0	0.05	0.4
ODOR THRESHOLD		0	0	0	0
PERCHLORATE	UG/L	9	0	1.44	4
PH, LAB	PH UNITS	9	7	7.73	8.2
POTASSIUM	MG/L	8	3	6.1	25
SELENIUM	UG/L	11	0	1.18	5
SILVER	UG/L	11	0	3.36	20
SODIUM	MG/L	10	3	25.4	31
SPECIFIC CONDUCTANCE	UMHOS/CM	13	330	460	540
SULFATE	MG/L	10	5	13.3	26
TDS	MG/L	10	260	306	370
THALLIUM, TOTAL	UG/L	7	0	0.143	1
TURBIDITY, LAB		0	0	0	0
ZINC	MG/L	11	0	0.0782	0.66
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	pCi/L	23	-0.59	0.928	3.39
RADIUM-228	pCi/L	4	-0.22	0.445	1
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	23	0	0	0
DIBROMOCHLOROPROPANE	UG/L	141	0	0.179	0.36

OROSI WELL 07 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	2	13	13	13
ALKALINITY, BICARBONATE AS CaCO3	MG/L	2	240	250	260
ALKALINITY, CARBONATE	MG/L	2	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	2	200	205	210
ALUMINUM	UG/L	2	0	0	0
ANTIMONY, TOTAL	UG/L	2	0	0	0
ARSENIC	UG/L	2	0	0	0
BARIUM	UG/L	2	100	105	110
BERYLLIUM, TOTAL	UG/L	2	0	0	0
BORON	UG/L	2	0	0	0
CADMIUM	UG/L	2	0	0	0
CALCIUM	MG/L	2	52	53.5	55
CHLORIDE	MG/L	2	23	23	23
CHROMIUM, HEX	UG/L	1	0	0	0
CHROMIUM, TOTAL	UG/L	2	0	0	0
COLOR	UNITS	2	0	0	0
COPPER, FREE	UG/L	2	0	0	0
FLUORIDE	MG/L	2	0	0.065	0.13
FOAMING AGENTS (SURFACTANTS)	MG/L	2	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	2	220	225	230
HYDROXIDE AS CALCIUM CARBONATE	MG/L	2	0	0	0
IRON	UG/L	2	0	0	0
LANGELIER INDEX @ SOURCE TEMP	LANG	2	0.57	0.64	0.71
LEAD	UG/L	2	0	0	0
MAGNESIUM	MG/L	2	22	22	22
MANGANESE	UG/L	2	0	0	0
MERCURY	UG/L	2	0	0	0
NICKEL	UG/L	2	0	0	0
NITRATE (AS N)	MG/L	50	5.3	8.66	13
NITRATE + NITRITE (AS N)	MG/L	5	0	5.34	8.3
NITRITE (AS N)	MG/L	2	0	0	0
ODOR THRESHOLD	TON	2	0	0	0
PERCHLORATE	UG/L	4	0	0	0
PH, LAB	pH	2	8.1	8.15	8.2
POTASSIUM	MG/L	2	3.3	3.45	3.6
SELENIUM	UG/L	2	0	0	0
SILVER	UG/L	2	0	0	0
SODIUM	MG/L	2	26	26	26
SPECIFIC CONDUCTANCE	UMHO/CM	6	540	573	640
SULFATE	MG/L	2	21	23	25
TDS	MG/L	2	370	375	380
THALLIUM, TOTAL	UG/L	2	0	0	0
TURBIDITY, LAB	NTU	2	0	0.05	0.1
ZINC	UG/L	2	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	16	0	2.73	6.18
RADIUM-228	PCI/L	2	0.06	0.38	0.7
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	92	0	0.0067	0.01
DIBROMOCHLOROPROPANE	UG/L	4	0.021	0.0428	0.059

OROSI WELL 08 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	5	12	12	12.1
ALKALINITY, BICARBONATE AS CaCO3	MG/L	5	140	164	190
ALKALINITY, CARBONATE	MG/L	5	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	5	140	146	160
ALUMINUM	UG/L	5	0	0	0
ANTIMONY, TOTAL	UG/L	5	0	0	0
ARSENIC	UG/L	5	0	2.04	2.8
BARIUM	UG/L	5	0	26.2	66
BERYLLIUM, TOTAL	UG/L	5	0	0	0
BORON	UG/L	2	0	0	0
CADMIUM	UG/L	5	0	0	0
CALCIUM	MG/L	5	36	37.4	40
CHLORIDE	MG/L	5	15	16.4	19
CHROMIUM, HEX	UG/L	2	0	0.315	0.63
CHROMIUM, TOTAL	UG/L	5	0	0	0
COLOR	UNITS	5	0	0	0
COPPER, FREE	UG/L	5	0	0	0
FLUORIDE	MG/L	5	0.14	0.152	0.17
FOAMING AGENTS (SURFACTANTS)	MG/L	5	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	5	140	148	160
HYDROXIDE AS CALCIUM CARBONATE	MG/L	5	0	0	0
IRON	UG/L	5	0	0	0
LANGELIER INDEX @ SOURCE TEMP	LANG	5	0.11	0.214	0.37
LEAD	UG/L	5	0	0	0
MAGNESIUM	MG/L	5	13	13.2	14
MANGANESE	UG/L	5	0	0	0
MERCURY	UG/L	5	0	0	0
NICKEL	UG/L	5	0	0	0
NITRATE (AS N)	MG/L	55	3.84	4.99	7
NITRATE + NITRITE (AS N)	MG/L	4	4.3	4.65	5
NITRITE (AS N)	MG/L	5	0	0	0
ODOR THRESHOLD	TON	5	0	0	0
PERCHLORATE	UG/L	6	0	0.267	1.6
PH, LAB	pH	5	8	8.04	8.2
POTASSIUM	MG/L	5	2.8	2.86	2.9
SELENIUM	UG/L	5	0	0	0
SILVER	UG/L	5	0	0	0
SODIUM	MG/L	5	20	20.8	22
SPECIFIC CONDUCTANCE	UMHO/CM	6	360	398	490
SULFATE	MG/L	5	8.8	10.4	13
TDS	MG/L	5	260	270	280
THALLIUM, TOTAL	UG/L	5	0	0	0
TURBIDITY, LAB	NTU	5	0	0.092	0.18
ZINC	UG/L	5	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	10	-0.44	1.20	2.39
RADIUM-228	PCI/L	2	0.06	0.24	0.41
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	101	0	0	0
DIBROMOCHLOROPROPANE	UG/L	5	0	0.0142	0.024

CUTLER WELL 09 WATER QUALITY SUMMARY					
ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	4	12	12	12
ALKALINITY, BICARBONATE AS CaCO3	MG/L	5	150	180	190
ALKALINITY, CARBONATE	MG/L	5	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	5	150	156	160
ALUMINUM	UG/L	7	0	0	0
ANTIMONY, TOTAL	UG/L	4	0	0	0
ARSENIC	UG/L	4	0	1.58	2.3
BARIUM	UG/L	4	0	49.3	100
BERYLLIUM, TOTAL	UG/L	4	0	0	0
BORON	UG/L	1	0	0	0
CADMIUM	UG/L	4	0	0	0
CALCIUM	MG/L	5	36	39.4	42
CHLORIDE	MG/L	5	20	21.8	23
CHROMIUM, HEX	UG/L	1	0	0	0
CHROMIUM, TOTAL	UG/L	4	0	0	0
COLOR	UNITS	4	0	1.25	5
COPPER, FREE	UG/L	4	0	0	0
FLUORIDE	MG/L	4	0.14	0.153	0.16
FOAMING AGENTS (SURFACTANTS)	MG/L	4	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	5	150	160	170
HYDROXIDE AS CALCIUM CARBONATE	MG/L	5	0	0	0
IRON	UG/L	5	0	0	0
LANGELIER INDEX @ SOURCE TEMP	LANG	4	0.097	0.247	0.42
LEAD	UG/L	4	0	0	0
MAGNESIUM	MG/L	5	14	15	16
MANGANESE	UG/L	5	0	0	0
MERCURY	UG/L	4	0	0	0
NICKEL	UG/L	4	0	0	0
NITRATE (AS N)	MG/L	53	4.2	4.74	5.3
NITRATE + NITRITE (AS N)	MG/L	3	4.5	4.73	5
NITRITE (AS N)	MG/L	4	0	0	0
ODOR THRESHOLD	TON	4	0	0	0
PERCHLORATE	UG/L	5	0	0	0
PH, LAB	pH	5	7.9	8.02	8.2
POTASSIUM	MG/L	5	2.7	2.88	3.1
SELENIUM	UG/L	4	0	0	0
SILVER	UG/L	4	0	0	0
SODIUM	MG/L	5	25	26.2	27
SPECIFIC CONDUCTANCE	UMHO/CM	10	400	430	450
SULFATE	MG/L	5	9.2	11	12
TDS	MG/L	5	290	298	310
THALLIUM, TOTAL	UG/L	4	0	0	0
TURBIDITY, LAB	NTU	4	0	0.09	0.23
ZINC	UG/L	4	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	8	0	0.88	5.21
RADIUM-228	PCI/L	5	0	0.22	1.1
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	40	0	0	0
DIBROMOCHLOROPROPANE	UG/L	30	0	0	0

OROSI WELL 010 WATER QUALITY SUMMARY

ANALYTE	UNITS	DATA POINTS AVAILABLE	MIN	AVERAGE	MAX
GENERAL					
AGGRESSIVE INDEX	AGGR	5	11.9	12	12
ALKALINITY, BICARBONATE AS CaCO3	MG/L	5	120	138	150
ALKALINITY, CARBONATE	MG/L	5	0	0	0
ALKALINITY, TOTAL AS CaCO3	MG/L	5	120	124	130
ALUMINUM	UG/L	5	0	0	0
ANTIMONY, TOTAL	UG/L	5	0	0	0
ARSENIC	UG/L	5	0	2.22	3.3
BARIUM	UG/L	5	0	23.2	59
BERYLLIUM, TOTAL	UG/L	5	0	0	0
BORON		0	0	0	0
CADMIUM	UG/L	5	0	0	0
CALCIUM	MG/L	5	28	28.8	30
CHLORIDE	MG/L	5	11	11.8	14
CHROMIUM, HEX	UG/L	2	0	0.395	0.79
CHROMIUM, TOTAL	UG/L	5	0	0	0
COLOR	UNITS	5	0	0	0
COPPER, FREE	UG/L	5	0	0	0
FLUORIDE	MG/L	5	0.13	0.144	0.16
FOAMING AGENTS (SURFACTANTS)	MG/L	5	0	0	0
HARDNESS, TOTAL AS CaCO3	MG/L	5	110	120	130
HYDROXIDE AS CALCIUM CARBONATE	MG/L	5	0	0	0
IRON	UG/L	5	0	8.4	42
LANGELIER INDEX @ SOURCE TEMP	LANG	5	-0.14	-0.0142	0.13
LEAD	UG/L	5	0	0	0
MAGNESIUM	MG/L	5	11	11.6	12
MANGANESE	UG/L	5	0	0	0
MERCURY	UG/L	5	0	0	0
NICKEL	UG/L	5	0	0	0
NITRATE (AS N)	MG/L	39	2.5	3.06	3.7
NITRATE + NITRITE (AS N)	MG/L	4	2.8	3.03	3.4
NITRITE (AS N)	MG/L	5	0	0	0
ODOR THRESHOLD	TON	5	0	0	0
PERCHLORATE	UG/L	6	0	0.267	1.6
PH, LAB	pH	5	7.9	7.98	8.1
POTASSIUM	MG/L	5	2.6	2.72	2.8
SELENIUM	UG/L	5	0	0	0
SILVER	UG/L	5	0	0	0
SODIUM	MG/L	5	17	17.4	18
SPECIFIC CONDUCTANCE	UMHO/CM	7	280	300	320
SULFATE	MG/L	5	2.8	3.26	4.2
TDS	MG/L	5	220	230	250
THALLIUM, TOTAL	UG/L	5	0	0	0
TURBIDITY, LAB	NTU	5	0	0.126	0.38
ZINC	UG/L	5	0	0	0
RADIOACTIVE					
GROSS ALPHA PARTICLE ACTIVITY	PCI/L	6	0	0.29	1.51
RADIUM-228	PCI/L	4	0	0.0000	0
ORGANIC					
1,2,3-TRICHLOROPROPANE	UG/L	102	0	0	0
DIBROMOCHLOROPROPANE	UG/L	7	0	0	0


Appendix L: COSWPA MOU Agreement No 29795

BEFORE THE BOARD OF SUPERVISORS COUNTY OF TULARE, STATE OF CALIFORNIA

IN THE MATTER OF CUTLER OROSI)
SURFACE WATER PROJECT) Resolution No. 2020-0496
AUTHORITY MEMORANDUM OF) Agreement No. 29795
UNDERSTANDING)

UPON MOTION OF SUPERVISOR TOWNSEND, SECONDED BY
SUPERVISOR SHUKLIAN, THE FOLLOWING WAS ADOPTED BY THE BOARD OF
SUPERVISORS, AT AN OFFICIAL MEETING HELD AUGUST 18, 2020, BY THE
FOLLOWING VOTE:

AYES: SUPERVISORS CROCKER, VANDER POEL, SHUKLIAN, VALERO AND
TOWNSEND
NOES: NONE
ABSTAIN: NONE
ABSENT: NONE



ATTEST: JASON T. BRITT
COUNTY ADMINISTRATIVE OFFICER/
CLERK, BOARD OF SUPERVISORS

BY: *Mercedes Lemos*
Deputy Clerk

* * * * *

Approved a Memorandum of Understanding with the Cutler Orosi Surface Water
Project Joint Powers Authority for participation in the Cutler Orosi Surface Water
Project for water supply for communities and residents in the north County.

CAO

08/18/2020

ML

Memorandum of Understanding Water Supply Feasibility

This Memorandum of Understanding ("MOU") is made and entered into effective August 18, 2025 (the "Effective Date") by and among the Cutler-Orosi Surface Water Plant Authority ("COSWPA"), a joint powers agency, and the County of Tulare, ("Tulare County") collectively referred to herein as the "Parties."

Recitals

- A. The Parties have concerns over water quality and water supply. The Parties are interested in developing a surface water supply to be used solely or in conjunction with existing groundwater wells to create a stable and potable water supply.
- B. The COSWPA was formed between the Cutler Public Utility District "CPUD" and the Orosi Public Utility District "OPUD" to seek grant funding to construct and operate a surface water treatment plant.
- C. By this MOU, the COSWPA and Tulare County are stating their joint interest and intent to participate in the planning for the construction and operation of such a plant.

NOW THEREFORE, the Parties agree as follows:

1. Funding. The Parties agree that they will share the preliminary costs as specified in this MOU based on the following proposed division:

COSWPA – 93.41%

Tulare County – 6.59% - Representing estimated capacity for the unincorporated communities of Yettem, Seville (4.39%), and potential users along the planned pipeline routes (2.2%) that would be able to receive treated surface water.

This cost allocation may be modified by separate amendment signed by both parties. The cost allocation is based on the approximate estimate of water each represented community would receive from the surface water treatment plant and the amount of water that would be reserved for use by Tulare County residents in areas adjacent to supply lines that could receive treated surface water.

All costs spent under this MOU shall be tracked by the Parties. Costs may be advanced by one Party on behalf of another Party by separate agreement. However, Parties will be responsible for reimbursing their respective share of all costs incurred.

Parties agree that interest will not be charged on the amounts owed but that they will make best efforts to reimburse the amounts owed as soon as possible.

Prior to adding additional parties, the Parties shall be required to agree in writing to the revised amount of costs owed. Cost responsibilities include amounts that will be incurred

moving forward and allocations of amounts previously spent that shall be considered an advanced cost and that will be subject to reimbursement from the additional parties.

2. Grant Funding and Reimbursement. Parties hereby state that it is the intention of the Parties to apply for and obtain grant funding for the construction of the surface water treatment plant, and to apply for and obtain grant funding to reimburse preliminary project costs incurred under this MOU. Parties agree that any eligible grant funding received shall be used to reduce the total amount incurred prior to dividing the applicable share of costs according to the cost share percentages stated in this MOU.

3. Term and Termination of MOU

a. The term of this MOU shall commence on the Effective Date and continue until terminated by a party or for thirty years as allowed under Public Utilities Code section 16885.

b. Each Party reserves the right to terminate this MOU upon sixty (60) days written notice to other party. The obligation to pay or reimburse for agreed-upon costs incurred under this MOU will survive the termination of this MOU and Parties agree to complete such reimbursement within five (5) years from the date of termination.

c. The agree that this MOU does not include the costs of construction, operation, or maintenance of a surface water treatment plant. Parties acknowledge that this MOU is intended to terminate prior to the commitment to fund construction of a surface water treatment plant, so that the Parties will have the opportunity to review the preliminary cost estimates of operating and maintaining the surface water treatment plant before being committed to additional costs. Should any or all Parties agree to jointly move forward with the construction, operation, and maintenance of a surface water treatment then that would be memorialized in a separate agreement, such as a Joint Powers Agreement, between the Parties and any other participating agencies. If no agreement can be reached involving all Parties, then COSWPA or any other Party may move forward with the surface water plant independently or with other participating agencies.

d. Parties agree that if a scheduling conflict occurs concerning the time to finalize any grant application that the COSWPA may decide whether to pursue the grant application, and such application would not be binding on another Participating Agency without that agency's separate approval.

4. Meetings. Any joint meetings of Parties shall be subject to the requirements of the Ralph M. Brown Act and all other California laws regarding open meetings and public records.

5. Costs Subject to Division. Under this MOU the Parties agree to divide the following types of costs based on the applicable cost share percentages listed above:

- a. Environmental review of potential site locations.
- b. Engineering review, including preparation of a preliminary engineering study of the proposed surface water treatment plant, this also includes geotechnical review of potential site locations.
- c. Preliminary discussions with property owner(s) – costs of right of way consultant, including costs to review title, appraisal costs, negotiations over a right of entry and site locations for the plant with the owner of land where site is currently being considered, may also include costs to negotiate an option to purchase the land.
- d. Costs to prepare and submit grant or loan applications for the surface water treatment plant.

This would include costs incurred prior to the Effective Date of this MOU.

Parties agree that prior to paying a negotiated amount for an option to purchase land that they would meet to discuss potential ownership and cost responsibility of purchase option if the grant application for construction has not been submitted and the membership of the JPA has not been modified to specifically address the ownership and operation of the plant by the additional communities participating in the grant application.

The costs to form and operate the COSWPA would not be included under this MOU.

6. Data, Studies, and Related Information. Parties agree to provide all data, studies, and related information for the construction of the surface water treatment and to provide such documents upon request between the Parties. All documents prepared or data gathered during the project shall belong equally and shall be shared between the Parties.

7. Notices. All notices relative to this MOU shall be given in writing and shall be personally served or sent by first class mail and be effective upon personal service or by depositing such notice in the United States mail. The Parties shall be addressed as follows, or at any other address as later designated by a Party:

COSWPA: Cutler-Orosi Surface Water Plant Authority
 Attn: Dennis Keller, Board Secretary
 P.O. Box 911
 Visalia, CA 93279

Tulare County: County of Tulare
 Attn: Denise England
 2800 W. Burrel Avenue
 Visalia, CA 93291

Any party may change its address for the purpose of this Paragraph by giving written notice of such change to the other Participating Agencies in the manner provided for in this Paragraph.

9. Entire MOU. This MOU sets forth the entire agreement among the Participating Agencies and supersedes all other oral or written representations. This MOU may be modified only in a writing approved by all Parties. All exhibits and recitals to this MOU are herein incorporated by this reference

10. No Joint Powers Agreement. No Party or employee of any Party is an agent or employee of any other Participating Agency for any purpose and is not entitled to any of the benefits provided by a Party to its employees. This MOU shall not be construed as forming a partnership or any of other association or separate joint powers agency among the Parties or a separate special district.

11. Dispute Resolution. If a dispute arises between the Parties, then they agree to meet and confer in an attempt to resolve the matter. If no resolution is reached, then parties agree to seek non-binding mediation of the dispute. If resolution is still not reached, then parties may seek formal arbitration or have the matter heard by a court of appropriate jurisdiction.


IN WITNESS WHEREOF, the Parties hereto have executed this agreement to be effective as of the date all parties have executed this agreement.

Cutler-Orosi Surface Water Plant Authority


Board President

Dated 8-10-20

County of Tulare


Chairman, Board of Supervisors

Dated 8/18/2020

APPROVED

By Marit C. Erickson at 12:43 pm, Aug 11, 2020

Tulare County Counsel

Dated _____

Appendix M: Orange Cove Permit 03-23-20P-001

State Water Resources Control Board

Division of Drinking Water

January 29, 2020

Mr. Rudy Hernandez, Interim City Manager
City of Orange Cove - 1010023
633 Sixth Street
Orange Cove, CA 93646

REVISED PERMIT NO. 03_23_20P_001

Dear Mr. Hernandez:

On January 11, 2018, Ms. Cristina Knudsen with the State Water Resources Control Board, Division of Drinking Water (Division) conducted an inspection of the City of Orange Cove water system (Water System). The findings of this inspection are detailed in the enclosed engineering report and include a list of deficiencies the City must address by specified timelines. Also enclosed is a Revised Domestic Water Supply Permit approving the use of the new backwash recycling facilities.

A public water system may file with the State Water Resources Control Board (State Water Board) a petition for reconsideration of a decision by the Deputy Director to issue, deny or amend a permit. Petitions must be received by the State Water Board within 30 calendar days of the issuance of the permit, permit amendment or decision. The date of issuance is the date when the Division of Drinking Water mails or serves a copy of the permit, permit amendment, or decision, whichever occurs first. If the 30th day falls on a Saturday, Sunday, or state holiday, the petition is due the following business day. Petitions must be received by 5:00 p.m. Information regarding filing petitions may be found at:

http://www.waterboards.ca.gov/drinking_water/programs/petitions/index.shtml

Please acknowledge in writing by **February 15, 2020**, receipt of this permit. If you have any questions regarding this letter, please contact the Fresno District office at (559) 447-3300.

E. JOAQUIN ESQUIVEL, CHAIR | EILEEN SOBECK, EXECUTIVE DIRECTOR

Sincerely,



José A. Robledo, P.E.

Senior Water Resource Control Engineer, Fresno District
SOUTHERN CALIFORNIA BRANCH
DRINKING WATER FIELD OPERATIONS

JAR/CK

Enclosures

cc: Fresno County Division of Environmental Health
Mr. Andy Valencia, Chief Operator, 602 2nd Street, Orange Cove, CA 93646

STATE WATER RESOURCES CONTROL BOARD
DIVISION OF DRINKING WATER

Certificate of Issuance
OF A
WATER SUPPLY PERMIT
ISSUED TO

City of Orange Cove
For The Operation of The
City of Orange Cove Water System
System No. 1010023

This is to certify that a water supply permit **03-23-20P-001** has been issued to, City of Orange Cove for the Operation of the City of Orange Cove Water System, on **January 29, 2020**, to supply water for domestic purposes to the City of Orange Cove Water System. The permit was issued by the State Water Resources Control Board, pursuant to the provisions of Division 104, Part 12, Chapter 4, Article 7, of the California Health and Safety Code. The permit is subject to the requirements of Title 22, California Code of Regulations, and to the conditions provided in the water supply permit.



A copy of the water supply permit is on file with the City of Orange Cove Water System or may be obtained by contacting the State Water Resources Control Board, Division of Drinking Water, Fresno District at 265 W. Bullard Ave., Ste. 101, Fresno, CA 93704.


José A. Robledo, P.E. – Fresno District Senior Sanitary Engineer

STATE OF CALIFORNIA

REVISED

DOMESTIC WATER SUPPLY PERMIT

Issued To
City of Orange Cove

Public Water System No. 1010023

By The

State Water Resources Control Board
Division of Drinking Water



PERMIT NUMBER: 03-23-20P-001 DATE: January 29, 2020

WHEREAS:

1. The City of Orange Cove submitted an application to the State Water Resources Control Board, Division of Drinking Water (Division) on November 29, 2016 for a permit amendment to the Domestic Water Supply Permit issued to the City of Orange Cove on February 25, 1999. The application was submitted for the addition of a backwash reclaim system, in accordance with California Health and Safety Code, Section 116525. The existing domestic water supply permit is greater than 10 years old and is no longer representative of the system. Therefore, the State Water Resources Control Board, Division of Drinking Water (Division) is issuing a revised water supply permit.
2. This public water system is known as the City of Orange Cove Water System (City) whose headquarters is located at 633 Sixth Street, Orange Cove, CA 93646.
3. The legal owner of the water system is the City of Orange Cove. The City, therefore, is responsible for compliance with all statutory and regulatory drinking water requirements and the conditions set forth in this permit.

4. The public water system for which the permit application has been submitted is as described briefly below (a more detailed description of the permitted system is described in the attached Engineering Report):

The City owns and operates a community water system. It treats surface water obtained from the Friant-Kern Canal at its Surface Water Treatment Facility comprised of two treatment plants; Plant A and Plant B. Treatment Plant A utilizes conventional treatment and has a design capacity of 1.5 million gallons per day (MGD). Treatment Plant B utilizes an alternative filtration and has a design capacity of 1.5 MGD. Following treatment, the water is chlorinated and is also treated with zinc orthophosphate for corrosion control. Treated water is sent to a 2.0-MG clearwell tank and is then sent to distribution.

And WHEREAS:

1. The City has submitted all of the required information relating to the proposed operation of the City's Water System.
2. The Division has evaluated all of the information submitted by the City and has conducted a physical investigation of the existing Water System.
3. The Division has the authority to issue domestic water supply permits pursuant to Health and Safety Code Section 116540.

THEREFORE: The Division has determined the following:

1. The City's Water System meets the criteria for and is hereby classified as a *community* water system.
2. The design of the proposed water system complies with the Water Works Standards and all applicable regulations.
4. The applicant has demonstrated adequate technical, managerial, and financial capacity to operate reliably the proposed water system.
5. Provided the following conditions are complied with, the City's Water System should be capable of providing water to consumers that is pure, wholesome, and potable and in compliance with statutory and regulatory drinking water requirements at all times.

THE CITY OF ORANGE COVE IS HEREBY ISSUED THIS DOMESTIC WATER SUPPLY PERMIT TO OPERATE THE CITY'S WATER SYSTEM.

The City's Water System shall comply with the following permit conditions:

1. The only sources approved for potable water supply are as follows:

Approved Sources

Source	PSCode	Status
FRIANT KERN CANAL - RAW	1010023 – 002	ACTIVE

2. The only approved treatment for the City includes the following processes:

Approved Treatment

Source	PSCode	Treatment
ORANGE COVE WTP - TREATED	1010023 – 007	SURFACE WATER TREATMENT & DISINFECTION
TRT PLNT – CORROSION CONTROL	1010023 – 011	CORROSION CONTROL

3. No changes, additions, or modifications shall be made to the sources or treatment mentioned in Conditions No. 1 and 2 unless an amended water permit has first been obtained from the Division.
4. The City shall not allow water intended for drinking water purposes to bypass any required treatment process, at any time.
5. All water supplied by the City for domestic purposes shall meet all applicable Maximum Contaminant Levels (MCLs) established by the California Division of Drinking Water. If the water quality does not comply with the California Drinking Water Standards, treatment shall be provided to meet standards, subject to permit approval.
6. All personnel who operate the distribution and treatment facilities shall be certified in accordance with Title 22, Sections 63765 and 63770, California Code of Regulations. The Water System shall be operated by a D2 certified distribution operator or higher and T3 certified treatment operator or higher.
7. The City shall comply with Title 17 of the California Code of Regulations, to prevent the water system and treatment facilities from being contaminated from possible cross-connections. The City shall maintain a program for the protection of the domestic water system against backflow from premises having dual or unsafe water systems in accordance with Title 17. All backflow prevention devices shall be tested annually.

8. The Water System shall submit an electronic Annual Report (eAR) to the Division of Drinking Water each year, documenting specific water system information for the prior year. The report shall be in the format specified by the Division.
9. The Water System shall maintain an up-to-date Emergency Notification Plan (ENP) identifying how customers will be notified in the event of a water quality emergency. The Water System shall refer to the ENP for phone numbers to contact the Division after normal business hours in the event of a water quality emergency.
10. The Water System shall prepare a Consumer Confidence Report on an annual basis, which must be distributed to customers and a copy provided to the Division by July 1 of each year.
11. All chemicals used in the water system, including chlorine, shall be certified under NSF/ANSI Standard 60. All water system equipment and materials that come into contact with the drinking water shall be certified under NSF/ANSI Standard 61 to demonstrate the material does not leach any contaminants into the drinking water.
12. The City's surface water treatment facility shall be operated in accordance with an approved Operations Plan and permit provisions cited in this permit. Any proposed changes to the Operations Plan shall be submitted to the Division for review and approval prior to implementation.
13. The water system shall continuously provide a minimum of 2-logs (99%) of *Cryptosporidium* reduction, 3-logs (99.9%) of *Giardia lamblia* reduction and 4-logs (99.99%) of virus reduction through filtration and disinfection at the City's surface water treatment plant (SWTPs), Plant A and Plant B. Compliance with this requirement is defined by California Code of Regulations (CCR) Title 22 Sections 64652, 64653, 64654, 64655, 64656, 64660 and 64664.

CONVENTIONAL TREATMENT

14. The City is permitted to operate Plant A, the original conventional treatment plant, provided that compliance is maintained with the turbidity performance standards outlined in the Surface Water Treatment Rule of the California Code of Regulations (CCR), Title 22, Chapter 17. In addition, the City shall monitor the clarified and filtered water turbidity daily from Plant A. The water turbidity data shall be reported to the Division in the monthly SWTP report.
15. Plant A is approved for a maximum operating capacity of 1.5 MGD. This SWTP shall not be operated at a maximum flow in excess of the total permitted capacity without first applying for and obtaining an amended permit from the Division.
16. The conventional SWTP, operated in compliance with the Title 22 sections listed in Provision 13 above and a Division approved Operations Plan, shall be credited with 2-logs of *Cryptosporidium* reduction, 2.5-logs of *Giardia lamblia* cyst reduction and 2-

logs of virus reduction through filtration. The remaining reduction of *Giardia lamblia* and virus shall be achieved through disinfection.

17. The water system shall monitor the turbidity of the raw water and settled water pursuant to CCR Title 22 Section 64654.8(b)(1)(2). The water system shall continuously monitor the turbidity of each Individual Filter Effluent (IFE), and Combined Filter Effluent (CFE) pursuant to CCR Title 22 Section 64655. The results of the IFE and CFE monitoring shall be recorded at least once every 15 minutes while the plant is in operation. If there is a failure of the IFE and CFE continuous monitoring equipment, the water system shall collect grab samples for turbidity every four hours, but continuous monitoring shall be reinitiated within 48 hours of system failure or maintenance interruption for the CFE turbidimeters and within five (5) working days for the IFE turbidimeters.
18. The Plant A shall be operated in accordance with the following CFE turbidity criteria while the plant is in operation:
 - a. Be less than or equal to 0.3 NTU in at least 95 percent of the measurements taken each month;
 - b. Not exceed 1 NTU for more than one continuous hour;
 - c. Not exceed 1 NTU at four-hour intervals; and
 - d. Not exceed 1.0 NTU for more than eight consecutive hours.

ALTERNATIVE FILTRATION

19. Plant B is approved for a maximum operating capacity of 1.5 MGD. This SWTP shall not be operated at a maximum flow in excess of the total permitted capacity without first applying for and obtaining an amended permit from the Division.
20. The City is permitted to operate Plant B, the package water treatment plant, provided that the filtered water turbidity remains below 0.2 NTU in 95 percent of monthly samples collected in 15-minute intervals. Plant B is credited with 2.0 logs of *Giardia* cysts removal and 1.0 log of virus removal when the effluent turbidity ranges from 0.2 to 0.3 NTU. For effluent turbidity levels less than 0.2 NTU, Plant B will be credited with 2.5 logs of *Giardia* cysts removal and 2.0 logs of virus removal. The City is required to monitor the effluent turbidity in accordance with the Surface Water Treatment Rule of the CCR, Title 22, Chapter 17. In addition, the City shall monitor daily the clarified water turbidity from Plant B. The clarified water turbidity data shall be reported to the Division in the Monthly SWTP report.
21. The IFE turbidimeters at Plants A and B and CFE used for compliance reporting shall be calibrated using the procedure specified by the turbidimeter manufacturer. The procedure and frequency for verifying and calibrating turbidimeters shall be included in the water system's Division approved Operations Plan. Turbidimeter calibration

records, including date, model, location of turbidimeter, and procedures used shall be maintained.

RECYCLED FLOW

22. Return all recycled flows to the headworks of the treatment facility. The recycled water flows shall not exceed 10 percent of the raw water flow into either Plant A or Plant B.
23. The City shall handle water treatment plant recycled flows per a Division approved Operations Plan.

CORROSION CONTROL

24. The City is approved to use Zinc Orthophosphate for corrosion control.
25. The City must submit a revised Operations Plan for Division review and approval which describes the corrosion control treatment utilized by the City. The Operations Plan is due by **March 31, 2020** specifying an operational pH level range and optimal pH level.

MONITORING, RECORDKEEPING, AND REPORTING

26. In accordance with the California Waterworks Standards (Section 64561, California Code of Regulations), monthly water production records shall be maintained for each active source and shall be reported to the Division annually on the Annual Report to the drinking Water Program.
27. All source chemical water quality monitoring shall be reported to the Division electronically by the analyzing laboratory using the assigned primary station codes as shown in Provision 2 above.
28. The City shall monitor the raw surface water source, before chlorination, monthly for total coliform and *E. coli* bacteria. The coliform tests shall be performed using a density analytical method and results reported in units of MPN/100 mL. The results from the source monitoring shall be submitted monthly to the Division by the 10th day of the following month.
29. The Water System shall monitor for coliform bacteria in the distribution system in accordance with the approved Bacteriological Sample Siting Plan. The Water System shall follow the Bacteriological Monitoring Requirements whenever any distribution system sample shows the presence of total coliform bacteria. The Division shall be notified immediately if either of the following occur:
 - Any distribution system or source sample shows the presence of *E. coli* bacteria


- The water system exceeds the maximum contaminant level for total coliform bacteria, in which more than one sample shows the presence of coliform bacteria during a month.
30. The disinfectant residual concentration of the water delivered to the distribution system shall be measured and recorded continuously pursuant to CCR Title 22 Sections 64656 (c)(e). The water entering the distribution system shall not contain a disinfectant residual less than 0.2 mg/L for more than four hours in any 24-hour period.
 31. The City shall submit a monthly surface water treatment plant report, signed by a person directly responsible for plant operation, on the operation of the SWTPs, Plants A and B, by the 10th day of the following month that includes, but not limited to, daily amount of water treated, average raw water turbidity results, daily combined filter effluent turbidity levels collected in 15 minute intervals, daily disinfection contact time calculations.
 32. Following the corrosion control treatment process, the City is required to monitor each treated water entry point at least once every two weeks for pH and orthophosphate levels (dosage rate and concentration). In addition, the City is required to monitor at least two taps for pH, alkalinity and orthophosphate levels every six months.
 33. As part of the monthly SWTP Report, the City must submit the following:
 - a. Daily recycled flows and the frequency with which recycled flows are returned
 - b. The average and maximum flow rates through the filters;
 - c. The average durations of the filter backwash process in minutes;
 - d. Daily maximum turbidity readings.
 34. The City shall include in the monthly report to the Division the following information;
 - a. Total volume treated with zinc orthophosphate during the month;
 - b. pH field results summarized in a table;
 - c. Orthophosphate results summarized in a table;
 - d. Results of any special investigations related to the treatment system and emergency and scheduled interruptions.

This permit supersedes all previous domestic water supply permits and permit amendments issued for this public water system, except for Permit Amendment 2017PA-SCHOOLS issued on January 17, 2017, which is expressly incorporated by reference herein and which continues to be in full force and effect from the date of issuance. This permit shall remain in effect unless and until it is amended, revised, reissued, or declared to be null and void by the Division. This permit is non-transferable. Should the City undergo a change of ownership, the new owner must apply for and receive a new domestic water supply permit.

Any change in the source of water for the water system, any modification of the method of treatment as described in the Engineering Report, or any addition of distribution system storage reservoirs shall not be made unless an application for such change is submitted to the Division.

This permit shall be effective as of the date shown below.

FOR THE STATE WATER RESOURCES CONTROL BOARD

A handwritten signature in blue ink, consisting of a stylized 'J' followed by several loops, is written over a horizontal line.

José A. Robledo, P.E.
Fresno District Engineer

Dated: 1/29/2020

**Engineering Report
For the Consideration of a Permit Amendment for
City of Orange Cove
System No. 1010032
Fresno County
January 2020**

**State Water Resources Control Board
Division of Drinking Water
Cristina Knudsen, P.E., Water Resource Control Engineer**

A. INTRODUCTION

In November 2016, the City of Orange Cove (City) submitted a permit amendment application to the State Water Resources Control Board, Division of Drinking Water (Division) to install and operate a backwash reclaim system at the City's existing surface water treatment facility. The purpose of the following engineering report is to describe the facilities and operational practices, as they exist today and to make a recommendation for the issuance of a revised domestic water supply permit to the Water System that will include the approval of the newly installed backwash reclaim system.

The City currently operates a domestic water system under the existing Water Supply Permit No. 03-11-99P-001 issued by the State Water Resources Control Board, Division of Drinking Water (formerly the California Department of Health Services) on February 25, 1999. The existing permit allows for the operation of two surface water treatment plants: Plant A (conventional) and Plant B (alternative filtration technology). Some of the permit provisions are no longer applicable, since the groundwater sources are no longer active.

On January 11, 2018, State Water Resources Control Board, Division of Drinking Water (Division) staff conducted an inspection of City of Orange Cove's (City) drinking water supply system. Mr. Andy Valencia, Chief Operator, Mr. David Lopez, Water Operator with the City were in attendance. Also, in attendance was Mr. Alfonso Manrique, the City's contract engineer, with AM Consulting Engineers. The last inspection was conducted by Arnold Hatai on December 18, 2013.

The findings listed in the 2013 inspection are provided below and are followed by the status for each item:

1. The Friant Water Authority (FWA) is planning a full flow treatment of the Friant-Kern Canal in Spring 2014. On December 18, 2013, we sent an email to Eric Quinley with the FWA regarding this issue. The City will need to take all necessary measures to maintain adequate source capacity and water quality during any herbicide treatment.

Status: Source capacity is an ongoing concern, particularly during times of drought or when the canal is chemically treated, sometimes making the surface water unusable for an extended period of time. The City has been awarded a funding agreement through the SWRCB Drinking Water State Revolving Fund for a basin lining project to help assure the existing basins can hold water during planned water outages. Currently, the existing basins cannot hold water for more than 30 days. Ultimately, the City will need to construct an additional fourth basin to meet source water capacity during times when

the Friant-Kern Canal is shut down for extended periods of time for maintenance and repair.

2. The City has been directed to provide quarterly updates on its progress to increase source capacity for any new developments before they can be approved. In the next update, please include a list of plant improvements that should be in the next major capital improvement project. The City's water meter project is proceeding and requires the City perform a water rate review. As a result of our inspection, it is recommended that the following items be addressed in any project to increase capacity:

- a. Add a raw water turbidity alarm due to the turbidity spikes that originate from storm water discharges that can adversely affect Plant B, which is an alternative technology and is required to meet a lower turbidity performance standard of 0.2 NTU in 95 percent of monthly samples collected at 15-minute intervals.

Status: The City has been awarded a funding agreement that will include some improvements to Plant B to address some operational needs.

- b. Upgrade the backwash solids settling capacity and drying bed capacity to accommodate the higher plant demands. During the last upgrade, the capacity was not increased. Recycling of the backwash water should be evaluated and our office contacted regarding the requirements of the Filter Backwash Rule requirements (flow and turbidity monitoring requirements).

Status: A new backwash reclaim system has been installed and is now in operation and recycles clarified backwash water back to the headworks of the two treatment plants.

- c. Evaluation and rehabilitation of the Plant A upflow contact clarifier. It continues to provide little, if any, turbidity reduction.

Status: The City has been awarded funding to add a new surface water treatment plant to replace Plant A. The City has submitted both design plans and specifications to the Division for review and approval.

- d. Capability to adjust chlorination dosages entering and leaving the clearwell based on any changes in chlorine demand.

Status: Currently, the City is having to manually adjust the chemical metering pump for chlorination.

- e. Upgrade the SCADA system to accommodate the needs for above items.

Status: An upgraded SCADA system is still needed.

3. The City schedules regular contract inspections of the filters. The filter media was replaced in 2011 in Plant B and 2012 in Plant A. The City operators have conducted inspections in-house annually, but it is recommended that a full inspection by a qualified contractor be conducted at least every 5 years or earlier if there is reduction in filter

performance or any evidence of problems during operator examinations (excessive media loss, reduced filter runs, etc.). The inspections should be based on the time period the media was replaced.

Status: On-going

4. As a drought mitigation measure, we understand the City plans to recirculate its backwash water, but this requires capital improvements to the pond system. The existing backwash ponds do not provide adequate settling to comply with the operational requirements. Please contact our office when the design of the system is under development for our review and comments.

Status: Completed. A new backwash handling facility has been installed.

5. The City is encouraged to make efforts to enforce its water service ordinance and connect private homes within its service area given the known water quality problems in the areal groundwater. Also, to make efforts to serve existing private residences when new water mains are installed.


Status: Due to inadequate source capacity, the Division does not approve any additional development within the City where additional water service is needed.

B. BRIEF DESCRIPTION OF SYSTEM

The City's water system is classified as a community water system, serving a permanent population of about 9,780 people through 1,694 service connections. It is located approximately 35 miles southeast of the City of Fresno within Fresno County. See Figure 1 for a vicinity map of the City.

Raw surface water from the Friant-Kern Canal serves as the City's single source of supply. Raw water is treated at the City's surface water treatment facility comprised of two treatment plants (Plants A and B) owned and operated by the City. Plant A is a conventional treatment plant and Plant B is considered an alternative filtration technology. Filtered water is disinfected prior to entering the two million-gallon clearwell. The clearwell is used to achieve the required chlorine contact time prior to entry into the distribution system. A backwash return system has recently been added to the treatment facility. The return system recycles less than 10 percent of the spent backwash water to the headworks, only when the filtration plants are operating.

Figure 1 – Vicinity Map



During times when the Friant-Kern Canal is taken down for maintenance (i.e. herbicide application by the Friant Water Authority), the City relies on three existing basins to temporarily store raw water for treatment. The basins are not sufficiently lined and allow water to slowly percolate into the subsurface. It is estimated that these basins hold less than a 30 day of supply. This poses an issue for the City during times when the Friant Water Authority plans routine maintenance on the canal for extended periods of time.

Water service rates are currently billed using a flat base-rate. Water meters have been installed however a tiered water rate structure has not been implemented to date. The City owns and operates a wastewater treatment facility that services water users within the City's service boundaries.

C. ENFORCEMENT HISTORY

The City has been issued four (4) enforcement actions since the last sanitary survey was completed in 2013. More recently, the City was issued a revised Compliance Order 03_23_17R_001 in February 27, 2017 for noncompliance with the source capacity requirement. This compliance order remains in effect today. Table 1 summarizes the enforcement actions since year 2013 and provides a brief discussion for each action.

Table 1: Summary of Recent Enforcement Actions

Enforcement Action	ID	Date	Violation
Enforcement Letter	03-23-15E-034	02/04/15	LCR Monitoring & Reporting
Compliance Order	03_23_17R_001	02/27/17	Source Capacity
Citation	03-23-18C-056	04/20/18	LCR Monitoring & Reporting
Notice of Violation	03-23-19N-025	03/13/19	1,2,3-TCP Monitoring & Reporting

Enforcement Letter No. 03-23-15E-034, Issued on February 4, 2015

This enforcement letter was issued to the City for failing to conduct the triennial lead and copper tap sampling that was due to the Division by September 30, 2014. The City was required to conduct tap sampling at 20 monitoring sites.

Status: Sample tap monitoring was conducted in August 2014 and the results were submitted to the Division. The City was returned to compliance with the lead and copper rule.

Compliance Order No. 03 23 17R 001 (Revised), Issued on February 27, 2017

This revised compliance order was issued to the City for failure to ensure that sufficient water is available from the water source and distribution reservoirs to adequately, dependably, and safely supply all users under maximum day demand conditions. The revision was issued to correct the compliance deadline of March 31, 2020.

Status: The Compliance Order remains in effect.

Citation No. 03-23-18C-056, Issued on April 20, 2018

This citation was issued to the City for failing to conduct the triennial lead and copper tap sampling that was due to the Division by September 30, 2017. The City was required to conduct tap sampling at 20 monitoring sites.

Status: Sample tap monitoring was conducted in September 2018 and results were submitted to the Division. The City was returned to compliance with the lead and copper rule.

Notice of Violation No. 03-23-19N-025, Issued on March 13, 2019

1,2,3-trichloropropane (1,2,3-TCP) is a newly regulated contaminant, falling under the synthetic organic chemical (SOC) group of constituents. As with all newly regulated SOC's, Water Systems must satisfy the initial monitoring requirements comprised of four consecutive quarters of monitoring for 1,2,3-TCP to determine compliance with the maximum contaminant level of 0.000005 mg/L. A Notice of Violation was issued to the City for failure to conduct 1,2,3-TCP monitoring of the raw water source during the fourth quarter of the 2018 calendar year.

Status: The City monitored for 1,2,3-TCP on March 13, 2019, thereby satisfying the initial monitoring requirements. The violation has been returned to compliance.

D. SOURCE OF SUPPLY

Surface water from the Friant-Kern Canal is the City's only source of supply. Raw water enters the City's surface water treatment facility through an intake structure where water is pumped from a concrete vault into two surface water treatment plants; Plant A and Plant B. These plants are standalone plants that typically operate in a parallel configuration. The combined filtered effluent is disinfected and sent to a clearwell prior to delivery to customers. For more discussion about the treatment plants, see Section F – Treatment. Table 2 provides the Primary Station Codes (PSCode) assigned to the approved raw water source and associated treated water source.

Table 2: Approved Raw and Treated Sources

Source Name	PSCode	Status
FRIANT KERN CANAL - RAW	1010023-002	Active
ORANGE COVE WTP - TREATED	1010023-007	Active

ACTIVE SOURCE

The Friant-Kern Canal (Canal) is an element of the Central Valley Project managed by the U.S. Bureau of Reclamation (USBR). The Friant Water Authority, through contract with the USBR, is responsible for the operation and maintenance of the Canal. The Canal runs approximately 152 miles from the town of Friant to the Kern River in Bakersfield. It receives water from Millerton Lake, an impoundment of the San Joaquin River, that ultimately collects drainage from the western slopes of the Sierra Nevada Mountain Range. The Friant Water Authority manages delivery of the San Joaquin River water supply via the Friant-Kern Canal, on behalf of the Friant Division Contractors of the Federal Central Valley Project.

The City has a water contract with the USBR allocating 1,400 acre-feet (ac-ft) per year or roughly 456 million gallons (MG) per year. To provide for future growth, the City entered a long-term Friant-Kern Canal water transfer agreement with the Lower Tule Irrigation District for an additional 2,000 ac-ft of water. It provides for a series of 500 ac-ft options that require a one-time payment of \$250,000 per increment. The City has exercised its first 500 ac-ft option and now has an annual allotment of 1,900 ac-ft as a long-term right. However, this right is dependent on drought conditions and can be reduced during years with low snowpack. The City anticipates increasing its surface water allotment, as recommended by the City's engineering consultant for the planned surface water treatment plant expansion.

Watershed Sanitary Survey – A sanitary survey was prepared for the watershed but was divided into two segments; the upper watershed that feeds the Friant-Kern Canal and the areas along the canal. The 2008 Updates to the watershed sanitary surveys are on file at the Fresno District office. The reports were prepared and implemented by a joint Memorandum of Understanding (MOU) between ten water suppliers: Bass Lake Water Company, County of Madera, Fresno County Waterworks No. 18, City of Orange Cove, City of Lindsay, Lindsay-Strathmore Irrigation District, Strathmore Public Utilities District, Terra Bella Irrigation District,

Kern County Water Agency and City of Fresno. Watershed sanitary surveys are to be conducted every five years with completed reports submitted to the Division for review and approval. The same water suppliers, with the addition of County of Fresno, coordinated another joint effort for the preparation and implementation of the 2019 Update. A draft copy of the 2019 Update, prepared by Keller/Wegley Engineering, is on file with the Fresno District office and is under review.

Source Water Assessment – A source water assessment was completed in 2003 and is on file with the Fresno District office. According to the assessment, the Friant-Kern Canal is considered most vulnerable to the following activities not associated with any detected contaminants including; agricultural drainage, sewer collection systems, utility stations-maintenance areas, metal plating/finishing/fabricating and plastics/synthetics producers.

INACTIVE SOURCES

The City inactivated all groundwater sources of supply (Wells 03, 05, 06 and 08) during 2003 and 2004, due to low production capacity and elevated nitrate levels. The groundwater wells were connected to a transmission line that blended at the intake of the surface water treatment plant to comply with the nitrate maximum contaminant level. At present, the City's sole source of supply is surface water. According to records, the wells have been inactivated and abandoned; but have not been destroyed.

E. WATER PRODUCTION AND ADEQUACY OF SUPPLY

According to the City's 2018 electronic Annual Report (eAR), submitted to the Drinking Water Program, the City provides water service to 1,575 residential and 119 commercial/industrial connections. According to the California Drinking Water Regulations, all public water systems are required to record the water production from their sources on a monthly basis and report them to the Division in the eAR.

Table 3 provides the City's historical water production summary that includes the number of service connections, maximum month demand, maximum day demand and peak hour demand. The table includes annual production values provided by the City for each year shown below. Equations obtained from the California Waterworks Standards were used to estimate maximum day and peak hour demands when data was not provided in the eAR. These values are identified with an asterisk.

Table 3: Historical Water Production

Year	Total Annual Production (MG)	Service Connections	Maximum Month Demand (MG)	Maximum Day Demand (GPM)	Peak Hourly Demand* (GPM)
2018	435.2	1,694	50.40 (Mar)	1,200	1,800
2017	416.0	1,666	52.73 (Jul)	1,772*	2,658
2016	471.9	1,610	53.26 (Jul)	1,790*	2,685
2015	412.9	1,531	40.90 (Jul)	1,000	1,500
2014	507.3	1,508	61.04 (Jul)	1,600	2,400
2013	580.2	1,485	66.38 (Jul)	2,000	3,000
2012	564.4	1,479	65.95 (Jul)	1,800	2,700
2011	549.1	1,483	73.01 (Jul)	2,000	3,000
2010	614.6	1,465	76.36 (Jul)	1,900	2,850
2009	677.9	1,455	76.56 (Jul)	2,000	3,000

Based on the historical water production summary provided in Table 3, the City's year with the greatest annual water production occurred in 2009, where 677.9 million gallons of water was produced. The most recent water production values have significantly decreased with the promotion of water conservation (year 2015) and the installation of water meters. Currently, all service connections are metered, however a tiered water rate structure has not been implemented. The year with the highest maximum day demand (MDD) and peak hourly demand (PHD) was 2009 at 2,000 gpm and 3,000 gpm, respectively. The MDD yielded approximately 2.88 million gallons per day (MGD).

In accordance with the California Waterworks Standard, all public water systems are required to have source capacity to meet the City's MDD. In addition, systems with more than 1,000 service connections shall also be able to meet the four hours of PHD utilizing source, storage and/or emergency source connections. The City has a two-million-gallon storage tank that in tandem with the two surface water treatment plants, can meet the City's MDD of 2.88 MGD. The surface water treatment plants are estimated to have a combined treatment capacity of 2,100 gpm or about 3 MGD. The four-hour peak demand at 3,000 gpm equates to approximately 720,000 gallons which can be easily met by the storage tank alone. However, the existing clearwell is considered an integral part of the disinfection process, used to achieve the required chlorine contact time. The City needs to plan for the installation of a designated storage water tank to meet the required four hours of PHD and maximum day demands.

The City's water system can meet both maximum day demand and peak hour demand. However, the poor condition of Plant A, does not ensure reliable treatment capacity. It is recommended that the City move forward with planned improvements to the surface water treatment facility to ensure uninterrupted service to customers. Planned improvements should include the addition of an appropriately sized water storage tank.

F. TREATMENT

The following section will provide descriptions of each component of the City's overall surface water treatment facility. Photographs of the various processes can be found in Appendix A.

Emergency Raw Water Storage

The City owns three raw water storage ponds which are typically bypassed during normal operations. On occasion, the Friant Water Authority will shut down sections of the Friant-Kern Canal for maintenance and/or repair. Maintenance activities can include chemical application for treatment of weeds and aquatic vegetation. Longer shutdowns occur about every three to five years and can last for a period of weeks to several months, depending on the level of structural maintenance and repairs needed within the canal.

Upon notification of a pre-scheduled canal outage from the Friant Water Users Authority, the City will store raw surface water in the three storage basins that lie east of the treatment facility, located approximately 900 feet east of the canal. The shutdowns lower the canal water level below the City's raw water intake. The City's turnout currently has a bar rack installed.

Together, the three basins have a total storage capacity of 140 ac-ft (two 49 ac-ft and one 45.4 ac-ft capacity earthen reservoirs). They are utilized to help maintain uninterrupted water service during canal shutdowns and provide flexibility when the canal water yields high turbidities. Two of the three storage basins have high percolation rates, limiting the holding capacity during long canal shutdown periods. Attempts have been made to artificially seal the ponds to improve water retention, however, these projects were unsuccessful. The City is currently planning a basin lining project as part of the upgrades to the surface water treatment facility.

As previously mentioned, the City was issued Compliance Order No. 03_23_17R_001 due to the City's inability to provide a source of supply that can adequately, dependably, and safely service all users under maximum day demand conditions. In addition to lining the basins, the City will need to add a fourth basin to help meet the source capacity demand during normal canal shutdowns.

Surface Water Treatment Plant (SWTP)

To meet the requirements of the Surface Water Treatment Rule (SWTR), the City's water system must meet a minimum 2-log reduction for *Cryptosporidium* and 3-log reduction/inactivation for *Giardia lamblia* cysts, and 4-log reduction/inactivation for viruses. The City's surface water treatment facility utilizes two types of treatment plants: conventional filtration (Plant A) and alternative filtration (Plant B) technologies. Each plant has a treatment capacity of about 1.5 MGD or 1,050 gpm.

As required by the SWTR, each surface water treatment plant must provide multi-barrier treatment. Table 4 provides a breakdown of the filtration credits for physical microbial removal along with the needed disinfection/inactivation credits for each specific filtration technology.

Table 4 – Filtration Credits for Microbial Removal

Filtration Treatment Technology	Combined Filter Effluent Turbidity (95% Monthly/Max) NTU	Maximum Logs of Credit for Physical Removal			Minimum Log inactivation Credit for Disinfection	
		Cryptosporidium	Giardia	Viruses	Giardia	Viruses
Conventional	0.3/1	2	2.5	2.0	0.5	2.0
Alternative*	0.2/1	2	2.5	2.0	0.5	2.0

*Removal credits are dependent upon treated effluent turbidity levels. This table provides the minimum logs of credit for physical removal based on the current permit provisions.

As stated in the City's current Water Supply Permit No. 03-11-99P-001, Plant B, which utilizes an alternative filtration technology treatment process, can receive a 2.5-log removal credit for *Giardia cysts* and a 2.0-log removal credit for viruses so long as treated water turbidities of 0.2 NTU or lower are produced using the 95 percentile readings. However, if turbidities between 0.2 NTU to 0.5 NTU are produced, the plant is only credited with 2.0-logs of *Giardia cysts* removal and 1.0-log of virus removal therefore requiring higher inactivation requirements. Consequently, with California's adoption of the Federal Long Term 1 Enhanced Surface Water Treatment Rule, the permitted upper limit of 0.5 NTU was later reduced to 0.3 NTU in accordance with the new performance standard requirements. Table 4 provides the more stringent permit condition to show the minimum logs of credit given for physical removal.

The startup and shutdown of the water treatment plants are controlled by the water level at the clearwell. Prior to entering the treatment plants, raw surface water from the Friant-Kern Canal first passes through the City's intake structure equipped with a bar screen. The screened raw water flows through an existing USBR flow meter, into a concrete vault and wetwell. The wetwell holds three 20-horsepower (hp) vertical turbine pumps. Each of these transfer pumps is capable of pumping at the design flow of 1,050 gpm into the discharge manifold that splits into two flow streams feeding treatment Plants A and B. During normal operation, only two raw water transfer pumps are in service. The third raw water transfer pump has been installed for redundancy.

The intake facilities include a separate above ground manifold equipped with a flow meter. The flow meter was originally installed to capture flows from the active groundwater sources that were used to blend with surface water. The groundwater sources were inactivated in 2003 and 2004. The pipeline connecting the groundwater sources has since been severed and capped. The inactive wells, however, are still present and have not yet been destroyed.

Pretreatment for Plants A & B – Chemical pretreatment consists of an alum-based polymer blend and a low-dose injection of chlorine. The polymer is injected first followed by chlorine. The chemically treated water then passes through an in-line static mixer. The injected polymer blend promotes coagulation of the suspended particles found in the raw surface water. Currently, the City manually adjusts the chemical feed pumps based on the turbidity levels of the incoming raw water.

Polymer – The City uses Pro Pac 926 for its polymer blend. It's manufactured by NTU Technologies, Inc and is certified as meeting NSF/ANSI Standard 60. According to the

NSF website, Pro Pac 926 is listed as having a maximum use dosage of 83 mg/L. At the time of the inspection, the City was dosing polymer (Pro Pac 926) at 3 mg/L through use of two ProMinent chemical metering pumps, one for each plant. Each pump has a rated capacity of 1.1 gallons per hour (gph) at a maximum pressure of 145 pounds per square inch (psi). During times of high raw water turbidity, the operator has reported dosages as high as 16 mg/L. A chemical tank with double containment is used to store the polymer which is fed neat.

Pre-chlorination – Following the polyblend injection, the City then prechlorinates the incoming water with a 12.5-percent strength solution of sodium hypochlorite, (Chem Chlor) manufactured by Chem Quip Inc. Chem Chlor is NSF/ANSI Standard 60 certified and has a maximum use dosage of 84 mg/L. Sodium hypochlorite is injected using a Blue-White Flexflo® peristaltic chemical metering pump. It has a maximum feed capacity of 3.96 gph at a maximum pressure of 100 psi. Dosages range between 0.3 mg/L to 0.1 mg/L.

Following chemical injection, the water passes through an inline static mixer. The water line then splits into two feedlines to feed the individual surface water treatment plants, Plants A and B.

Plant A – Plant A was originally constructed in 1974 and is comprised of a concrete circular upflow flocculator-clarifier followed by four modular sand filters. At the time of the inspection, Plant A was in use however was taken offline on January 25, 2018 for yearly maintenance and inspection.

Upflow Clarifier – Water first enters the mixing zone (center hood) of the clarifier from the bottom, where mechanical mixing and flocculation occur. Flocculated solids settle to the bottom of the basin, forming a sludge blanket. According to the operator, the clarifier was last drained and cleaned in the summer of 2017. The condition of the clarifier is overall poor, as there are signs of concrete deterioration on the interior clarifier walls and signs of corrosion of the submerged steel components.

The clarifier measures 37 feet in diameter and has a volume of 84,000 gallons. The top of the flocculation hood has a diameter of 13 feet. There are eight radial launders measuring 11 feet in length placed in a wagon wheel arrangement. The weir loading rate is approximately 6 gpm per foot of weir length. At the maximum flow rate of 1,050 gpm, the surface overflow rate and detention time are approximately 1.1 gpm/ft² and 80 minutes, respectively. Clarified water flows into the launders which divert the flow to a collection vault where the water then flows to four rapid sand filters for gravity filtration.

The settled solids found at the bottom of the clarifier are routinely pumped to the sludge handling facilities.

Rapid Sand Filtration – Filtration is provided by two declining rate gravity filters that each contain two cells. Each cell measures 12 feet by eight feet, yielding a total surface area of 384 square feet (ft²). The filter media is comprised of 18 inches of anthracite coal that sits on top of nine inches of sand. The filters are contained in open-top modular steel tanks. Flow into each filter is controlled through use of a float-controlled throttling butterfly valve on each discharge header. The filtration rate is about 2.7 gpm/ft² at the design flow rate of 1,050 gpm. Filtered water is then disinfected and sent to a buried concrete tank prior to entering the two million-gallon clearwell.

At the time of the inspection, Filters No. 3 and 4 were the only filters in use at Plant A. Filters No. 1 and 2 were out of service due to faulty actuators. The actuators were replaced in March 2018. During the inspection, it was noted that the tank walls were showing signs of corrosion.

Each filter cell is backwashed using treated water from the clearwell. The backwash sequence is comprised of a surface wash, backwash/surface wash combination, and then backwash that is followed by filter-to waste cycle. The filter is left idle for a specified time to stabilize the media before the filter is placed back into service. If the turbidity of the filtered water exceeds 0.3 NTU, the filter is automatically placed into filter-to-waste mode until the turbidity level drops below 0.3 NTU. Currently, an individual cell can be backwashed while the other three filters remain in service.

Plant B – Plant B is a Roberts Filter Group Pacer II® adsorption clarifier-filtration system that was originally constructed in 1996. It is comprised of two identical treatment trains, each measuring eight feet by 20 feet with an operating depth of eight feet. Together, the trains can treat a total flow of 1,050 gpm or 525 gpm each. Each train consists of the proprietary ContaClarifier® and conventional gravity tri-media filter. The trains can operate independently of each or in tandem.

Contact Clarifier – Following chemical pretreatment, water flows into the clarifier through the bottom. Water flows upwards through a bed of coarse non-buoyant media, combining flocculation and clarification into one process. Clarified water is then channeled into the adjacent filtration process.

According to the previous sanitary survey report, the clarifier has a surface area of 52.78 ft², a bed volume of 211.1 ft³ and a hydraulic loading rate (overflow rate) of 9.95 gpm/ft². The detention time is calculated at 6 minutes, based on the surface area and operational depth of eight feet using the design flowrate of 525 gpm. Based on this detention time, the process is considered a high-rate process.

Every four hours and prior to filter backwashes, the adsorption media in the clarifiers is flushed by increasing the influent raw water flow (media expansion) followed by an air scour cycle. A containment screen is suspended above the non-buoyant media to prevent the loss of media during the cleaning process (media expansion and air scouring).

Filtration – Clarified water enters the tri-media filter, allowing for gravitational filtration through the filter bed. According to the previous sanitary survey report, the tri-media filter has a surface area of 105.56 ft² with a filtration rate of 4.97 gpm/ft², assuming the design flow rate of 525 gpm. The water level at each filter is modulated at the filter effluent to maintain a constant water level above the media bed. The tri-media bed is comprised of the following media types shown in Table 5:

Table 5: Dual Pacer II Tri-Media

Media Type	Depth	Specifications
Anthracite (top)	18 inches	Effective Size 1.0 – 1.1 mm Uniformity Coefficient of 1.65
Silica Sand	9 inches	Effective Size 0.45 – 0.55 mm Uniformity Coefficient of 1.5
Garnet Sand	3 inches	Effective Size 0.25 – 0.35 mm Uniformity Coefficient of 1.8
Garnet Gravel (bottom)	3 inches	Effective Size 1.0 – 3.0 mm

A perforated polyvinyl chloride (PVC) underdrain system lies under a gravel layer at the bottom. Filtered water is then disinfected and sent to a buried concrete tank prior to entering the two million-gallon clearwell.

Initiation of the filter surface wash and backwash sequences are automated and occur once a day. The sequence consists of a surface wash followed by a backwash/surface wash combination and a backwash followed by three to five minutes of a filter-to-waste cycle. The train is then placed into service. However, if the turbidity of the filtered water exceeds 0.2 NTU, the filter is automatically placed back into rinse-to-waste mode until the turbidity level drops below 0.2 NTU.

Disinfection – Filtered water from Plants A and B combines and receives post-chlorination. The water is then conveyed to a buried concrete tank before being pumped into the clearwell.

Post-chlorination – Filtered water from both treatment plants is injected with a 12.5-percent strength solution of sodium hypochlorite, (Chem Chlor) manufactured by Chem Quip Inc. Chem Chlor is NSF/ANSI Standard 60 certified and has a maximum use dosage of 84 mg/L. The sodium hypochlorite is stored in a large storage container used to supply chemical to both the raw water and treated water flows. The sodium hypochlorite solution is injected using a Blue-White Flexflo® peristaltic chemical metering pump.

Operation of all chemical feed equipment is prompted via SCADA when a signal is triggered, indicating the treatment plant(s) are in use. Chemical feed rates are adjusted manually. Disinfection is paced to maintain a chlorine residual in the finished water clearwell of at least 1 mg/L.

Corrosion Control – Beginning in 2006, the City began implementing zinc orthophosphate for corrosion control in lieu of the previously used chemical, caustic soda. The City conducts weekly sampling at the designated sample point at the water treatment plant and also monitors once every two weeks from within the distribution system. There are two sites located at the furthest points in the distribution system that are monitored on a rotational basis (1426 South Ave. and 1205 Adams Ave.). These sites also serve as routine bacteriological sampling sites and are found in the northwest and southwest corners of the distribution system. According to monthly monitoring reports, the City is maintaining a zinc orthophosphate concentration of about 0.5 mg/L, monitored as phosphorous (P), at both locations. The City currently utilizes a test kit with a color wheel for concentration measurements.

Zinc Orthophosphate – Zinc orthophosphate is used a corrosion inhibitor and is NSF/ANSI Standard 60 certified. It is stored in 250-gallon to 350-gallon totes in the

chemical storage area inside the Control Building at the Treatment facility. The zinc orthophosphate solution is injected into the filtered water prior to entering the 34,000-gallon underground storage tank. The City uses two Prominent metering pumps for chemical injection. Each metering pump has a rated capacity of 1.1 gph.

By March 31, 2020, the City needs to provide the Division with a revised Operations Plan to describe the current operations at the plant and include the corrosion control treatment system. The Operations Plan shall consist of a description of all treatment facilities; operating personnel, including number of staff, certifications levels and responsibilities; procedures used to determine chemical doses rates; monitoring locations and sampling frequency for water quality parameters; records; response to plant emergencies and chemicals used. The plan should include a range of pH levels allowed within the distribution system and the optimal pH level.

Backwash Reclaim Facility

The Backwash reclaim facility is comprised of the following: a backwash receiving basin, sedimentation basin, polymer injection and sludge dewatering. According to the Operator, the backwash reclaim facility returns clarified spent backwash flow from the sedimentation tank to the head of the SWTPs. The PLC allows a backwash return flow of exactly nine percent of the overall daily treated flow. The following subsections provide a detailed description for each individual handling process.

Backwash Receiving Basin – The SWTP has a backwash receiving basin that collects spent filter backwash water from the Plant B contact clarifiers and receives the spent rinse water used in between backwash cycles. At times, the basin is also designed to receive overflow water from the 2-MG clearwell, in addition to water drained from the bottom of the backwash sedimentation tank. In event of an emergency, an 18-inch overflow pipe connecting the receiving basin to the storm drain can be used to prevent an overflow event at the basin.

The receiving basin measures 40 feet by 25 feet. The basin floor slopes toward the center, having a maximum depth of 11 feet. The basin is equipped with a submersible 1400-gpm pump furnished with a 30-hp electric motor. The pump transfers spent backwash water into the adjacent sedimentation tank or alternatively can transfer water to the raw water storage ponds. An ultrasonic level sensor at the receiving basin triggers the operation of the submersible pump. According to the Operator, the pump is called into operation at a 6.5-foot water level and will shut-off at a two-foot water level in the receiving basin or when the high-water level at the sedimentation tank is reached. A low-low level switch will also shut-off the pump, in the event the ultrasonic level sensor fails. The transfer pump is triggered when the water level in the sedimentation tank is at a low-water level of 12 feet. The receiving basin transfer pump will shut-off once the high-water level of 20 feet is reached.

Sedimentation Tank – Backwash water from the receiving basin is pumped into a 230,000-gallon bolted-steel sedimentation tank. Prior to entry into the tank, the water is dosed with a polymer to facilitate coagulation of suspended solids for gravitational settling and aids in the sludge dewatering process.

Polymer Injection – The backwash handling facility includes a polymer feed building that houses the polymer feed system. The feed system is comprised of a 50-gallon polymer drum and a skid-mounted chemical metering pump, manufactured by Velodyne, used for polymer injection. The metering pump has a maximum rated pressure of 100 psi and a polymer flow range of 0.25 to 5.0 gph. Polymer dosage is flow paced.

The City has the capability of injecting polymer at two locations using this polymer metering system. The first injection site is located upstream of the sedimentation tank. The second injection site is located upstream of the sludge dewatering box. The operator must manually control where polymer injection will occur. Operation of the polymer metering pump is triggered when flow is detected through installed flowmeters found upstream of each of these two processes. Following polymer injection, the chemically treated flow passes through a static mixer to encourage conglomeration.

The polymer used is AE212P (a polyacrylamide polymer) manufactured by NTU Technologies. It is NSF/ANSI Standard 60 certified and has a maximum use dosage of 3 mg/L, according to the NSF Product listing website. The chemical comes as a 40 percent stock and is diluted down to 0.5 percent.

Following polymer injection, the water is top fed into a 25-foot high, 39-foot diameter sedimentation tank. The chemically treated backwash water is then allowed to settle for three hours before decanting occurs, according to the operator. The settling time is adjusted based on the incoming backwash water quality. The sedimentation tank is equipped with an ultrasonic level sensor and a floating decanter that is connected to the Backwash Reclaim Pump. The Reclaim Pump will decant clarified water to the head of the surface water treatment process until a low-level setpoint is reached. The sedimentation tank also has an 18-inch diameter overflow line that directs water back into the backwash receiving basin, in the event the tank is overfilled.

Backwash Reclaim Pump – The sedimentation tank is equipped with a floating decanter connected to a backwash reclaim pump. The reclaim pump has a 3-hp electric motor with a variable frequency drive (VFD). The reclaim pump conveys clarified water from the sedimentation tank back to the raw water wet well located at the head of both surface water treatment plants (Plants A and B). The reclaim pump is automated. A modulating-valve on the discharge line of the decanter restricts the reclaim flow to nine percent of the surface water treatment flow. **According to the Operator, the returned nine percent flow is not based on the instantaneous flow entering the SWTP process. The return flow is currently based on the total daily treated flow.** According to the Operations Plan dated March 2017, the reclaim pump is set to shut-off at a low-water level of 10-feet.

Once the allotted settling time in the sedimentation tank has been reached (3 hours), an actuating valve opens triggering the operation of the reclaim pump. The floating decanter includes a strainer and it draws water from below the surface preventing any unsettled solids from being pumped and discharged at the raw well. The reclaim pump will shut-off once the low-water level setpoint is reached.

A turbidimeter is located on the reclaim discharge pipeline. Turbidity setpoints of 20 NTU and 50 NTU trigger the high reclaim turbidity warning and alarm, respectively.

Sludge Mixing System – The sludge mixing system is comprised of a mixing pump with a 50-hp electric motor, and mixing eductors that are mounted on the sedimentation tank floor. The sludge mixing system serves to maintain a uniform sludge blanket within the tank and prevents sludge buildup along the tank circumference. The mixing pump draws water from the center of the tank and discharges it through the mixing eductors.

Following each decant cycle, the sludge mixing pump is called into operation for a specified duration. The sludge mixing pump can also be used to drain the sedimentation tank and will return flow back to the backwash receiving basin by adjusting the valving on the discharge piping manifold.

Sludge Pump – The sludge pump is located adjacent to the sludge mixing pump. The sludge pump is equipped with a 7.5-hp electric motor. It draws water from the sedimentation tank sharing the same discharge pipeline as the mixing pump. The sludge pump is manually operated and transfers sludge from the sedimentation tank to the sludge dewatering box. Following pumping, the sludge flow is immediately injected with polymer (AE212P). The same facilities providing polymer prior to the sedimentation tank are also used to provide polymer to the sludge flow. The polymer helps to enhance sludge formation.

Sludge Dewatering Box – The dewatering box is a Flotrend Sludgemate. The sludge flow first enters the box through a PVC pipe equipped with a camlock connection. Water from the dewatering process gravity flows out of the box through bottom outlet ports and is piped back to the backwash receiving basin. The accumulated solids are periodically emptied from the box and are temporarily stored in the nearby concrete, sludge drying bed area. The sludge will be periodically taken to the City's wastewater treatment plant for temporary storage before final disposal.

F. RESERVOIRS AND BOOSTER PUMPS

34,000-Gallon Storage Tank – Post-chlorinated water from Plants A and B flows into the 34,000-gallon underground concrete storage tank. This storage tank was last inspected and cleaned in 2004. Treated water is then pumped into the adjacent two million-gallon above-ground clearwell by three finished-water transfer pumps. Operation of the transfer pumps is triggered based on the water level inside the clearwell. The pumps are equipped with VFDs. The transfer pumps are called to service by SCADA which regulates the water level of the clearwell. There is also a fourth transfer pump at this tank that supplies backwash water at Treatment Plants A and B.

Two-Million Gallon Clearwell – The clearwell reservoir was constructed in 1973. It measures 100 feet in diameter and has a height of 34.5 feet. Proper ventilation is provided at the top center of the clearwell; although it was not inspected at the time of the inspection. **The City will need to provide photo documentation showing the vent screen is intact and in good condition by February 29, 2020.** The clearwell is also equipped with an external overflow line that feeds the storm drain.

Post-chlorinated water enters the two-million-gallon welded-steel clearwell through an internal top feed line. A bottom outlet, located one foot above ground level, connects to a manifold equipped with five booster pumps that feeds the distribution system. The fifth booster pump is engine-driven and is only used during emergencies to meet fire flow demand. The other pumps are high-head electric pumps with a combined capacity of 4,600 gpm. The pumps consist of the following motor power and design flowrate capacities: 30-hp at 600 gpm, 50-hp at 950 gpm, 75-hp at 1,550 gpm, and 75-hp at 1,500 gpm. The two largest pump motors include VFDs that are controlled by the SCADA system.

G. DISTRIBUTION SYSTEM

Water Mains – The pipeline network in the distribution system consists primarily of 4-inch to 8-inch diameter pipe. According to the 2018 eAR, about 60 percent of the distribution system is comprised of asbestos cement that is around 40 years in age. The remaining 40 percent is comprised of C-900 PVC that is about 15 years in age.

One pressure zone exists within the distribution system. System pressure are maintained between 50 and 70 psi. The distribution system is looped except for seven dead-end lines which are flushed annually.

The water mains are in good condition. During the year 2018, no mainline breaks occurred according to the City's 2018 eAR. However, the City did report 24 service connection breaks/leaks in the same annual report. According to the previous sanitary survey, distribution mains are in the streets and the sewers are located in alleys.

Existing mains are repaired by the City personnel or, at times, the work may be contracted out. The City attempts to first repair a main break under pressure but will isolate and de-water the main if the break is too large. All repairs, replacement mains, and new mains are performed in accordance with AWWA Standard specifying disinfection and flushing procedures along with bacteriological sampling.

Valves – A total of 220 valves were reported in the 2018 eAR of which 22 valves were exercised. The valve size ranges from 4-inches to 12-inches in diameter. Valve exercising occurs on an "as needed" basis.

H. WATER QUALITY MONITORING

SOURCE MONITORING

Bacteriological Monitoring – Currently, the City is conducting routine weekly bacteriological monitoring of the source water from the Friant-Kern Canal. This monitoring consists of total coliform, fecal coliform, and *E. coli* bacteria sampling. The raw water samples are reported in MPN/100 ml. A summary of the raw water data is available in the Source Bacteriological Monitoring Report in Appendix B.

Long Term 2-Enhanced Surface Water Treatment Rule – The Federal Long Term 2 Enhanced Surface Water Treatment Rule (LT2ESWTR) was promulgated in January 2006 to

address the health risk from *Cryptosporidium*. For water systems serving less than 10,000 persons (Schedule 4 water systems), the second round of source water monitoring for *E. coli* bacteria was to begin on October 1, 2017. The City submitted their LT2ESWTR Sampling Schedule in August 2017 which was approved by the Fresno District office. The schedule specified which weeks *E. coli* bacteria monitoring would be conducted at two-week intervals. Table 6 provides a summary of the *E. coli* bacteria results from October 2017 through to September 2019.

Table 6 – LT2ESWTR Monitoring Results for *E. coli* Bacteria

Date	<i>E. coli</i> Bacteria Result (MPN/100 mL)	Date	<i>E. coli</i> Bacteria Result (MPN/100 mL)
10/4/2017	<1.8	3/21/2018	4
10/18/2017	4	4/4/2018	27
11/1/2017	2	4/18/18	7.8
11/15/2017	<1.8	5/2/2018	17
12/6/2017	2	5/16/2018	33
12/20/2017	2	6/6/2018	11
1/3/2018	NA	6/22/2018	2
1/17/2018	NA	7/11/2018	11
1/24/2018*	2	7/27/2018	7.8
1/31/2018*	<1.8	8/8/2018	2
2/7/2018	<1.8	8/22/2018	<1.8
2/21/2018	<1.8	9/5/2018	<1.8
3/7/2018	NA	9/19/2018	<1.8
3/16/2019*	<1.8	Annual Mean	5.6

According to Table 6, *E. coli* bacteria results for some scheduled samplings were not available. Dates shown with an asterisk are sample dates closest to a sample date specified in the City's monitoring plan. These values were used to calculate the 12-month annual mean of 5.6 MPN/100 mL. *Cryptosporidium* monitoring is not required for water systems that have an annual mean *E. coli* concentration of less than 10 MPN/100 mL. Because *E. coli* levels are less than this trigger, *Cryptosporidium* monitoring is not required, and the City's bin classification will stay the same.

Source Classification and Data Submittal – The Friant Water Authority operates the Friant-Kern canal, the conveyance system the City utilizes to obtain its source of supply. The City's surface water source is classified as a CLSA (Community, Large, Surface Water, Agricultural).

All source water quality monitoring compliance is based on the sample results found in the Division's Water Quality Inquiry (WQI) database. All chemical water quality monitoring from the surface water source must be submitted to the Division's WQI database by electronic data transfer (EDT). The City must label the samples with the correct primary station code (PS Code) for the laboratory to submit the sample results electronically. A summary report of the City's most recent water quality data available in WQI is provided in Appendix C. The Last Sample Date and Monitoring Schedule report for the City is found in Appendix D.

General Mineral, General Physical and Inorganic Chemicals – Surface water sources are required to be sampled annually for most secondary/general physical (GP) and inorganic (IO) chemicals. Raw water samples collected from the surface water source were last sampled for secondary and inorganic chemicals in March 2019, except for bicarbonate alkalinity, carbonate alkalinity, hydroxide alkalinity which were sampled in September 2019. Asbestos and nitrite monitoring were last sampled in June 2011 and March 2019, respectively. The results for all sampled constituents were in compliance with their respective maximum contaminant levels (MCLs). **The next round of source water sampling for most of the Secondary/GP, and IO chemicals is due to the Division by March 31, 2020.** Please refer to Appendix D for the next due sample dates for each constituent.

Color – A secondary drinking water standard has been established for color. The secondary MCL is 15 Units. Color is typically caused from naturally occurring organic materials found in the source water. In July 2016, March 2017, and March 2019, the City's sample results showed color levels of 15, 30 and 45 units, respectively.

Volatile Organic Chemicals (VOC) Monitoring – The initial monitoring requirement for VOCs requires water systems to collect four quarterly samples. Once initial monitoring requirements have been satisfied, VOC monitoring will be reduced to an annual frequency schedule if results show no VOC detections. However, for the City, VOC monitoring can be further reduced to once every three years for the surface water source. However, a monitoring waiver request must be submitted by the City to the Division for review and approval. The initial monitoring requirement for VOCs has been satisfied. VOC monitoring for all required constituents was last conducted in September 2019. All water quality sample results since the completion of the last sanitary survey inspection showed nondetectable VOC concentrations. **The next round of source water sampling for VOCs is due to the Division by September 30, 2022 by EDT.**

Synthetic Organic Chemicals (SOC) Monitoring – The initial monitoring requirements for SOC requires water systems to collect four consecutive quarterly samples for all required SOC contaminants. Once initial monitoring requirements have been satisfied, SOC monitoring will be reduced to two consecutive quarters every three years, if results show no SOC detections. Only 1,2,3-trichloropropane (1,2,3-TCP), alachlor, atrazine, 2,4-D, endothall and simazine require monitoring. Monitoring for all other SOC constituents has been waived. Once the initial monitoring requirement has been satisfied, monitoring of the six SOC can be reduced to every three years, unless there is a detection. However, a monitoring waiver request must be submitted by the City to the Division for review and approval. The City has satisfied the initial monitoring requirements for all SOC constituents, including 1,2,3-TCP. **The next round of source water sampling of all SOC, except 1,2,3-TCP, is due to the Division by September 30, 2022 by EDT. The next 1,2,3-TCP sample is due to the Division by March 31, 2022.**

1,2,3-Trichloropropane (TCP) - 1,2,3-TCP is a chemical that is not naturally occurring in the environment. It is a manufactured chemical typically found in discharges related to solvent use. In 1999, the Division established a 0.005 µg/L drinking water notification level for 1,2,3-TCP. Notification levels are health-based advisory levels established by the Division for chemicals in drinking water that currently lack MCLs; however, are candidates for future regulation based upon detections in numerous sources, and potential of adverse health effects. 1,2,3-TCP is *reasonably anticipated to be a human*

carcinogen based on sufficient evidence of carcinogenicity from various experimental studies of animals. In December 2017, California established an MCL of 0.000005 mg/L (0.005 µg/L) for 1,2,3-TCP.

Beginning January 1, 2018, water systems were required to begin initial monitoring, consisting of four-consecutive quarterly samples for 1,2,3-TCP at all sources of supply. The City has collected four quarterly samples in which all results yielded nondetectable 1,2,3-TCP concentrations. The monitoring frequency for 1,2,3-TCP has, thereby, been reduced to once every three years.

Radiological Monitoring – The initial monitoring requirements for gross alpha (GA) and radium-228 have been satisfied. Monitoring for uranium, radium-226 and radium-228 is only triggered under the following conditions where analysis of the same GA water sample must be used:

If $GA + (0.84)(\text{Gross Alpha Counting Error}) > 5 \text{ pCi/L}$
then uranium analysis is required

If $GA + (0.84)(\text{Gross Alpha Counting Error}) - U > 5 \text{ pCi/L}$
then radium-226 and radium -228 analysis is required

The on-going monitoring frequency for GA is determined based on the last sample result, prompting either a 3-year, 6-year or 9-year monitoring schedule for GA. The last GA sample collected in March 2017 resulted in a nondetectable concentration, which places the source on a 9-year monitoring frequency for GA. **The next GA sample is due to the Division via EDT by March 31, 2026.**

SURFACE WATER TREATMENT RULE MONITORING COMPLIANCE

The SWTR requires the turbidity and chlorine residual to be measured and recorded for the evaluation of the treatment plant's performance for removal of *Cryptosporidium* and the removal/inactivation of both *Giardia cysts* and viruses. Table 4 provides the filtration credit for microbial removal based on the type of surface water treatment process used.

Effective inactivation for *Giardia* and viruses is determined by chlorine contact time (CT). Filtration performance determines the effective *Giardia*, viruses, and *Cryptosporidium* removal. Each month, the City submits to the Division a "*Monthly Summary of Monitoring for Surface Water Treatment Regulations*" for SWTR compliance. This report includes turbidity and chlorine monitoring data, as well as calculations for CT compliance at the clearwell.

Turbidity Performance Requirements – The Long Term 1 Enhanced Surface Water Treatment Rule (LT1) applies to all public water systems using surface water serving fewer than 10,000 people and requires these water systems to provide at least 2.0-log *Cryptosporidium* removal. Conventional treatment facilities (i.e. Plant A) must achieve a combined filter effluent turbidity level of less than or equal to 0.3 NTU in at least 95 percent of measurements taken each month to receive credit for the required 2-log cryptosporidium removal. Treatment facilities using an alternative filtration technology (i.e. Plant B) must achieve a combined filter effluent turbidity level of less than or equal to 0.2 NTU in at least 95

percent of measurements taken each month to receive credit for the required 2-log cryptosporidium removal. The maximum turbidity level of the combined filter effluent must not exceed 1.0 NTU at any time.

The surface water treatment facility is equipped with the following turbidimeters (not including the unit installed at the backwash reclaim facility): HACH Surface Scatter 6 continuous turbidimeter (Raw Water), eight HACH 1720E turbidimeters. **HACH is discontinuing support of the 1720E turbidimeters and will no longer provide replacement parts nor servicing of units. It is recommended that the City plan for the replacement of these units within the next five years.**

At the time of the inspection, the raw water turbidimeter was giving faulty reads and grab samples were therefore collected. A new raw water turbidimeter was installed in March 2018 and is located on the feed line that directly feeds Plant B.

The surface water treatment facility is equipped with an alarm system operated through the SCADA system software which records individual filter turbidity reading for both Plants A and B, and the combined effluent turbidities at each plant. The SCADA system is connected to an auto-dialer that is activated if turbidity setpoints are exceeded at any plant.

Plant A Filters – There are two filter trains that operate in parallel with two cells each. Each filter cell is equipped with an on-line turbidimeter, HACH 1720E. The combined filter effluent is also equipped with a HACH 1720E turbidimeter. Individual turbidimeter alarms are triggered for values of 0.3 NTU or higher. An alarm is also triggered if the combined filter effluent exceeds 0.3 NTU.

Plant B Filters – There are two filter trains operating in parallel. Each filter is equipped with a HACH 1720E on-line turbidimeter. A HACH 1720E continuous on-line turbidimeter is located on the combined finished water line. Individual turbidimeter alarms are triggered for values of 0.2 NTU or higher. An alarm is also triggered if the combined filter effluent exceeds 0.3 NTUs.

The two treatment plants are operated independent of each other, due to the different turbidity performance standards. Table 7 provides the turbidity standards for each type of filtration technology.

Table 7: Turbidity Performance Standards

Filtration Treatment Technology	Combined Filter Effluent Turbidity (95% Monthly) NTU	Combined Filter Effluent Turbidity (Max) NTU
Plant A - Conventional	0.3	1
Plant B - Alternative	0.2	1

According to the submitted *Monthly Summary Reports*, during 2018 the 95th percentile values for turbidity at Plant A ranged between 0.06 NTU to 0.288 NTU. These values were below the 0.3 NTU performance standard; thereby compliance with the LT1 turbidity performance standards was met. The average percent reduction in turbidity during 2018 ranged between 89.6 percent and 97.8 percent. However, Plant A was taken out of service in February, March, November and December during 2018.

Plant B is credited for 2.5-logs of *Giardia* cysts removal and 2.0-logs of virus removal if the filtered water turbidity is maintained below 0.2 NTU (as calculated using the 95 percentile readings). According to those same submitted *Monthly Summary Reports*, during 2018 the 95th percentile values for turbidity at Plant B ranged between 0.04 NTU and 0.117, meeting compliance with the LT1 turbidity performance standards. The average percent reduction of turbidity during 2018 ranged between 92.2 percent and 98.7 percent.

Disinfection Compliance – The City’s water system is required to achieve a minimum of 0.5-log *Giardia* inactivation through the disinfection process at the SWTP. Log inactivation through disinfection is based on the disinfection residual (C) multiplied by the contact time (T) referred to as “CT”, or “CT achieved” measured as:

$$C \times T = \text{mg/L} * \text{min, delivered dose}$$

Where:

C is the disinfectant residual (mg/L)

T is the exposure or contact time (minutes)

The “CT achieved” value is calculated based on the daily minimum disinfectant (chlorine) residual concentration recorded on the discharge side of the clearwell prior to the first connection and is based on the lowest water level of the clearwell at peak flow. The CT achieved value is compared to the CT required value using the ratio:

$$CT_{\text{Ratio}} = CT_{\text{Achieved}} / CT_{\text{Required}}$$

The “CT required” is calculated based on values obtained from generated tables listing derived CTs using various parameters including chlorine residual, clearwell baffling factor, lowest daily water temperature, and highest daily pH. The CT ratio must be greater than or equal to one (1) in value to show that the CT achieved is greater than or equal to the CT required.

There is a two-million-gallon clearwell tank that provides the required chlorine CT and thus, is an integral part of the SWTP process needed to meet SWTR compliance. The CT calculations provided in the *Monthly Summary Reports* do not account for prechlorination at the 34,000-gallon tank found ahead of the two-million-gallon clearwell.

Table 8 provides a list of the CT parameters:

Table 8: CT Calculation Parameters

Parameter	Value	Description
Flow (gpm)	Q =	Peak daily flowrate in gpm
Clearwell Volume per foot	V = 57,971	Gallons/Ft
Clearwell Baffling Factor	T ₁₀ /T = 0.1	Poor Baffling
Chlorine Residual	C =	measured in mg/L at first customer (min. value)
High pH	pH =	Highest daily treated pH
Low Temperature	T =	°C low temperature daily

The two-million-gallon storage tank is credited with a baffling factor of 0.1. A tracer study has not been conducted and is not needed at this time. However, if improvements are made to the clearwell in the future, a tracer study may be required at that time.

This City is required to achieve a minimum of 0.5-log *Giardia cysts* inactivation through the disinfection process at the SWTP. According to the submitted 2018 monthly surface water treatment reports, chlorine residuals can fluctuate between 0.5 mg/L and 1.9 mg/L. These monthly summary reports also show CT ratios ranging from 6.58 to 46.19.

A HACH CL-17 analyzer continuously monitors the chlorine residual leaving the clearwell. SCADA is used to monitor the treatment plant operations including, but not limited to, water tank elevation levels, pH levels, turbidity levels, and free chlorine residuals. The SCADA system is connected to an automatic phone dialer that is activated following a low-level detection. The low-level chlorine alarm is triggered when a free chlorine of 0.7 mg/L or less is detected at the effluent.

DISTRIBUTION SYSTEM MONITORING

Bacteriological monitoring – The City is required to collect a minimum of three bacteriological samples from the distribution system each week based on population served. Typically, the City has been collecting 16 samples per month. However, the City will collect 20 samples during those months that have five weeks. A bacteriological sample siting plan (BSSP) dated September 15, 2016 is on file with the Fresno District office. The plan provides eight routine site locations along with associated repeat sample site locations found upstream and downstream of the routine sample site. A summary of the distribution monitoring since 2015 is included in Appendix E. The City has complied with the revised total coliform rule maximum contaminant level since the last inspection.

Lead and Copper Rule – The Lead and Copper Rule requires community and nontransient–noncommunity waters systems to monitor lead and copper levels at the consumers' taps. Water systems are required to conduct standard tap samplings for two consecutive six-month periods at a minimum number of sites, based upon water system size. Compliance with the

lead and copper action levels is based on the 90th percentile lead and copper levels. This means that the concentration of lead and copper must be less than or equal to the action level in at least 90 percent of the samples collected. The action levels for lead and copper are 0.015 mg/L and 1.3 mg/L, respectively.

The City is currently placed on a triennial monitoring frequency for lead and copper tap monitoring and is required to collect 20 tap samples. A summary of the historical lead and copper tap sample results is included in Appendix F. The most recent sampling was conducted in September 2018, with concentrations measuring nondetect for lead and 0.15 mg/L for copper. **The next round of lead and copper tap monitoring is due to the Division by September 31, 2021.**

Lead Service Line Inventory Requirement – Existing law requires public water systems (PWS) to take specified actions to test for and remediate certain contaminants in drinking water, including lead and copper. Existing law prohibits the use of any pipe, pipe or plumbing fitting or fixture, solder, or flux that is not "lead free" in the installation or repair of any public water system or any plumbing in a facility providing water for human consumption, except as specified. Senate Bill (SB) 1398 became effective on September 27, 2016 and added Section 116885 to the Health and Safety Code (HSC), which was later amended (SB 427) on September 11, 2017. HSC Section 116885 required Community Water Systems (CWS) to compile an inventory of known lead user service lines in use in its distribution system and identify areas that may have lead user service lines (user service lines whose content cannot be determined) in use in its distribution systems by July 1, 2018. "User service line" means the pipe, tubing, and fittings connecting a water main to an individual water meter or service connection.

HSC Section 116885 requires CWS, after completing the inventory, to provide a timeline for replacement of known lead user service lines in the distribution system to the SWRCB. In addition, by July 1, 2020, CWS with areas that may have lead user service lines in use in its distribution system must either determine the existence or absence of lead user service lines in these areas and provide that information to the SWRCB, or provide a timeline for replacement of the user service lines whose content cannot be determined. The SWRCB must approve the replacement timeline.

According to the 2018 electronic annual report, the City reported that 1,694 service laterals are comprised of high-density polyethylene (HDPE). All service line pipes and fittings within the City's distribution system were determined to be lead-free; where lead-free is defined as a weighted average of 0.25% lead calculated across the wetted surfaces of a pipe, pipe fitting and fixture, and 0.2% lead for solder and flux. The City has complied with the Lead Service Line Inventory Requirement.

Disinfection Byproducts – Beginning on January 1, 2004, the US Environmental Protection Agency's Stage 1 Disinfectants/Disinfection Byproducts (D/DBP) Rule required water systems serving less than 10,000 persons to begin monitoring and reporting disinfection byproduct levels and residual disinfectant levels to the Division. Water Systems serving 10,000 or more persons had to comply by January 1, 2002. The D/DBP Rule applies to any community and nontransient-noncommunity water system that treats their water with a chemical disinfectant in any part of the treatment process or that provides water that contains a chemical disinfectant.

The D/DBP Rule was adopted in California and became effective on June 17, 2006. Prior to this date, any noncompliance issues were referred to the USEPA for enforcement action.

Stage 2 Disinfection Byproduct Rule Monitoring – On June 21, 2012, California adopted the Stage 2 Disinfection Byproduct Rule (ST2DBPR). The S2DBPR builds on the Stage 1 DBPR, and was created to improve on public health protection by increasing compliance monitoring requirements for Total Trihalomethanes (TTHM) and Haloacetic acids 5 (HAA5). The established MCLs for TTHM and HAA5 are 80 µg/L and 60 µg/L, respectively. Compliance with each DBP is based on a running annual average (RAA) of four consecutive quarters of monitoring data.

The PS Codes for the approved ST2DBPR monitoring sites are provided in Table 9. The PS Codes listed are to be used solely for ST2DBPR reporting purposes for each associated sample site. If a monitoring site needs to be changed, approval must first be obtained from the Fresno District office prior to monitoring, as the Division will need to review the request, and also create any new PS Codes. Analyzing laboratories will need to submit all results electronically to the Division's database by EDT. The sample bottle(s) and the chain-of-custody form needs to be correctly labeled using the ST2DBPR Monitoring Site locations for EDT to work properly.

Table 9: Approved ST2DBPR Monitoring Locations and PS Codes

ST2 Monitoring Site	PS Code
ST2DBP – 633 SIXTH STREET	1010023-900
ST2DBP – 1205 ADAMS	1010023-901

The City is required to collect TTHM and HAA5 samples from the distribution system at each ST2DBPR monitoring location once *every quarter*, in accordance with the approved Stage 2 Disinfection Byproduct Monitoring Plan. Tables 10 and 11 provide the last two years of data for TTHM and HAA5 at both monitoring sites.

**Table 10: TTHM and HAA5 Sample Results
1010023-900 S2DBPR – 633 Sixth Street**

Sample Date	TTHM µg/L	TTHM RAA µg/L	HAA5 µg/L	HAA5 RAA µg/L
03/07/2018	33	46	26	31
06/15/2018	64	50	67	41
09/19/2018	33	44	27	38
12/14/2018	35	41	28	37
03/13/2019	41	43	64	47
06/14/2019	36	36	36	39
09/27/2019	30	36	23	38
12/23/2019	21	32	19	36

TTHM MCL = 80 µg/L and HAA5 MCL = 60 µg/L

**Table 11: TTHM and HAA5 Sample Results
1010023-901 S2DBPR – 1205 Adams**

Sample Date	TTHM µg/L	TTHM RAA µg/L	HAA5 µg/L	HAA5 RAA µg/L
03/07/2018	39	56	28	42
06/15/2018	70	55	61	40
09/19/2018	28	46	24	36
12/14/2018	35	43	31	36
03/13/2019	48	45	72	47
06/14/2019	45	39	24	38
09/27/2019	28	39	0	32
12/23/2019	18	35	20	29

TTHM MCL = 80 µg/L and HAA5 MCL = 60 µg/L

According to sample results, TTHM and HAA5 concentrations are below their respective MCLs, with the most recent samples collected in December 2019. **The next samples for TTHM and HAA5 are due to the Division via EDT by March 31, 2020.**

Asbestos – Regulations require tap monitoring within distribution systems vulnerable to asbestos contamination at service connections serviced by an asbestos-cement main pipeline. Distribution system monitoring for asbestos is required if asbestos-cement pipe is used and the water produced by the sources has an aggressive index of less than 11.5. The aggressive index is an indicator of corrosivity, and correlates reasonably well with the release of asbestos fibers caused by dissolution of the cement matrix. The aggressive index (AI) is calculated using the following equation:

$$AI = pH + \log (A \cdot H)$$

Where:

pH = measured pH of the water

A = alkalinity, mg/L as CaCO₃

H = calcium hardness, mg/L as CaCO₃

Aggressive index results less than 11.5 indicates a potential for asbestos contamination in the system. Asbestos monitoring of the distribution system in an area served by asbestos-cement pipe shall be conducted every nine years. The calculated aggressive index of the raw surface water is displayed in Table 12. According to table, the water is considered aggressive to asbestos-cement (AC) pipe.

**Table 12: Aggressive Index of Source Water
for Years 2015-2019**

Sample Date	Lab pH	A	H	Calculated AI	Lab Result AI
3/18/15	7.6	21	17	10.2	10.0
7/6/16	7.4	12	8	9.4	9.3
3/30/17	7.4	15	14	9.7	9.6
3/7/18	7.4	12	8.5	9.4	9.3
3/27/19	7.3	16	14	9.7	9.5

The City currently provides corrosion control treatment using zinc orthophosphate. According to the monthly reports, the City uses about 55 lbs of zinc orthophosphate daily. Each month the City measures the treated water samples weekly from the water treatment plant for pH and zinc orthophosphate measured as phosphorous (as P). The City also measures pH and zinc orthophosphate (as P) from two locations within the distribution, as provided in Table 13. The sites are alternately sampled once every two weeks.

Table 13: Zinc Orthophosphate Monitoring Locations

Location ID
1426 South Avenue
1205 Adams Avenue

Each site listed in Table 13 is located at the furthest point in the distribution system. These sites also serve as bacteriological sampling locations. According to the City's monthly reports submitted to the Division, the concentration of zinc orthophosphate (as P) is maintained at 0.5 mg/L.

MAINTENANCE AND OPERATION

Operator Certification – According to the 2018 Electronic Annual Report, the City's population is 9,780. Based on this service population, the City's water system is classified as a D2 distribution system. The City's Surface Water Treatment Plant is classified as a T3 treatment facility. The minimum chief operator certification requirements for both the City's distribution and treatment systems are provided in Table 14:

Table 14: Minimum Chief Operator Certifications

Facility	Classification
Distribution System	D2
Treatment Classification	T3

According to the 2018 eAR, Mr. Andy Valencia is the Chief Operator and meets the minimum certification requirements for the City's distribution and treatment systems. Table 15 provides a list of the Chief and Shift operators along with their certifications.

Table 15: Operator Certifications

Operator Name	Distribution Certification & Operator Number	Treatment Certification & Operator Number
Andy Valencia, Chief Operator	D3 (No. 19261)	T3 (No. 24013)
David Lopez, Shift Operator	D2 (No. 35011)	T2 (No. 25513)

Operation and maintenance activities for the City's water system are conducted under the supervision of Mr. Andy Valencia, Chief Operator. Bacteriological and chemical samples are typically collected in conformance with required water quality monitoring schedules. The water served complies with the all bacteriological and chemical drinking water standards.

When treatment facilities and distribution facilities are added or modified, the City shall evaluate and update, if necessary, their distribution and treatment classifications. At all times, the Chief and Shift Operators shall meet the minimum certification requirements according to Sections 63766 and 63770 of Chapter 13, Division 4, Title 22.

Cross-Connection Control – Cross connections are defined as actual or potential connections between a potable water supply and a non-potable source, where it is possible for a contaminant to enter the drinking water supply. All community and noncommunity water systems are required to maintain an approved Cross Connection Control Program.

The City has initiated a cross-connection control program, however, does not have a Cross Connection Control Program Coordinator on staff. According to the 2018 eAR, there are a total of 191 backflow prevention assemblies within the distribution system. All assemblies were tested. During testing, there were 25 assemblies that failed. All 25 assemblies were repaired or replaced. There were six assemblies that were installed during 2018. According to the California Drinking Water Regulations, all backflow assemblies/devices must be tested annually. The City has increased in size since the last cross connection control survey was completed in 2001. **It is recommended that the City conduct an updated cross connection control survey to determine if any cross connections exist within the City's service area.**

Emergency Notification Plan (ENP) – The City shall maintain an up-to-date Emergency Notification Plan (ENP) identifying how customers will be notified in the event of a water quality emergency. The City should update their ENP whenever there are changes in emergency personnel and/or their contact information.

An ENP dated November 2006 is on file with the Fresno District office. However, a change in Division staffing has occurred since this submittal. **By February 15, 2020, the City needs to provide the Division with an updated ENP for review and approval.** A blank ENP template is provided in Appendix G. An electronic copy can be provided upon request.

Emergency Response Plan - The City submitted an Emergency Response Plan (ERP) dated December 29, 2004. The ERP needs to be updated to reflect current City personnel. **By April 15, 2020, the City needs to provide an updated ERP to the Fresno District office for review and approval.** For your reference, an ERP template is provided in Appendix H.

Consumer Confidence Report – Every community water system and every nontransient-noncommunity water system is required to prepare and distribute a consumer confidence report (CCR) by July 1st of each year. The CCR provides a summary of water quality information for detected primary and secondary contaminants on an annual basis. A copy of the CCR for the year ending December 31, 2018 was submitted to the Division. The City has also provided the Division with certification of the 2018 CCR delivery. According to the City's certification form, the CCR was distributed in July 2019 to customers. It was also posted on the City's internet website and in public places (City Hall and Orange Cove Library). **As a reminder, the City's 2019 CCR must be distributed to water customers by July 1, 2020. Certification of delivery should be submitted within 10 days following delivery.**

Electronic Annual Report (eAR) – The California Health and Safety Code Section 116530 states that all public water systems shall submit a technical report, as required by the Division,

on an annual basis. The Division requires all water systems to submit the Electronic Annual Report (eAR) to the Drinking Water Program, typically, by March 31st of each year for the previous year, detailing population served and number of service connections, water produced and used status of various monitoring requirements and operator certification, system improvements and other information. The City has submitted their 2018 eAR to the Division via the Division's Drinking Water Information Clearinghouse (DRINC) portal. **As a reminder, the deadline for the 2019 EAR is approaching with a due date of March 31, 2020.**

Complaints – All water suppliers are required to record all water quality and system water outage complaints received, both verbal and written, and corrective action taken. Table 16 provides the number and type of complaints reported in the eARs regarding water system issues for years 2014 through 2018.

Table 16: Complaints Reported during 2014-2018

Type of Complaint	Number of Complaints Reported	Number of Complaints Investigated	Number of Complaints Reported to Division
Taste and Odor	10	10	10
Color			
Turbidity			
Worms and other Visible Organisms			
Pressure (High or Low)	50	50	50
Water Outages			
Illnesses (Waterborne)			
Other			
Total	50	50	50

According to City's EARs, all customer complaints were investigated. The highest volume of complaints involved low water pressure. The City determined the cause to be related to the customer's plumbing. During year 2017, the City received 10 taste and odor related complaints. Operators believed the cause of the issue was due to the surface water source. The City needs to continue recording and reporting all complaints in future EARs.

J. SYSTEM APPRAISAL

The City's water system, specifically Plant A, needs improvement. Plant A is showing corrosion and is incapable of providing reliable redundancy in the event Plant B must be taken out-of-service for maintenance and/or repair. Combined, the two surface water treatment plants have a capacity of 3.0 MGD. The highest year of water production occurred in 2009 with a maximum day demand of 2.88 MG. The plants can meet the City's current maximum day demand with the capacity of the two treatment plants and their 2-MG storage tank. However, the future capability of Plant A to operate without interruption is unlikely. The City has recently received construction funding through the SWRCB's Drinking Water State Revolving Fund financial

assistance program (Proposition 1) to address deficiencies at Plant A and to improve the overall operations of the facility.

Another problem the City faces is source capacity during times when the Friant-Kern Canal must be taken down for maintenance by the Friant Water Authority. The three existing raw water storage basins are unlined and cannot hold water for more than 30 days. This presents a significant problem for the City when canal maintenance is scheduled for longer durations where canal water flow would be low or entirely unavailable. The City was issued a Compliance Order (No. 03_23_17R_001) to address this source capacity deficiency in February 2017. The compliance deadline is March 31, 2020. The City's funding project through Proposition 1 will also include lining the existing basins. As a short-term solution, the City has been awarded funding through Assembly Bill 72 to provide a temporary solution for an upcoming water outage scheduled for Fall 2020. The outage allows the Friant Water Authority to make necessary repairs within the Canal. The outage is expected to take place mid-October 2020 through the beginning of February 2021. However, as a long-term solution, it is recommended that the City construct a fourth raw water storage basin to increase source capacity during times of extended water outages. It is also recommended the City develop another source of supply by either drilling a well outside the City limits, connecting to another public water system, constructing of an alternate pipeline connection from Millerton Lake or installing treatment for groundwater contamination.

The City complies with all primary and secondary drinking water standards. Chemical monitoring is current, and the City adheres to all monitoring schedules. The supervision over the operation and maintenance of the water system is adequate.

K. RECOMMENDATIONS

The City must address the following deficiencies:

1. By February 15, 2020, the City needs to provide the Division with an updated ENP for review and approval. See Appendix G for an ENP template.
2. By February 29, 2020, the City will need to provide the Fresno District office with photo documentation showing the vented screen atop the 2-MG clearwell is intact and in good condition.
3. By March 31, 2020, the City needs to monitor for most of the secondary/general physical, and inorganic chemicals. All sample results must be submitted to the Division through EDT.
4. By March 31, 2020, the City needs to provide the Division with a revised Operations Plan to describe the current operations at the plant which also includes the corrosion control treatment system. See the corrosion control section of this report.
5. By March 31, 2020, the City needs to monitor for TTHM and HAA5 and submit sample results to the Division by EDT.

6. By March 31, 2020, the City must submit the 2019 EAR through the Drinking Water Information Clearinghouse (DRINC Portal website). The draft EAR template will be made available in early February 2020.
7. By April 15, 2020, the City needs to provide an updated ERP to the Fresno District office for review and approval.
8. By July 1, 2020, the City must distribute the 2019 Consumer Confidence Report to all water service customers. A copy of the report must be submitted to the DRINC Portal along with the Certification of Delivery form verifying proof of distribution.
9. It is recommended that the City conduct a cross connection control survey to determine if any cross connections exist within the City's service area since the last survey was conducted in June 2001.
10. It is recommended that the City acquire an increased surface water allotment, as was recommended by the City's engineering consultant.
11. HACH is discontinuing support of the HACH 1720E turbidimeters and will no longer provide replacement parts nor servicing of units. It is recommended that the City plan for the replacement of these units within the next five years.

List of Appendices

- Appendix A – Water System Photographs
- Appendix B – Source Bacteriological Monitoring Report (2015-2019)
- Appendix C – Drinking Water Analyses Results Report
- Appendix D – Last Sample Date and Monitoring Schedule
- Appendix E – Distribution Bacteriological Monitoring Report (2015-2019)
- Appendix F – Lead and Copper Rule Tracking Report
- Appendix G – Emergency Notification Plan Template
- Appendix H – Emergency Response Plan Template

Appendix A

Water System Photographs

Appendix A

City of Orange Cove Water System

Photographs

Friant-Kern Canal Intake

The City's intake structure equipped with a bar screen.



Raw Water Lift Pumps

No.: 3

Type: Vertical Turbine

Power: 20-hp, each

Design flow: 1,050 gpm



Plant A—Upflow Clarifier

Type: Conventional



Appendix A

City of Orange Cove Water System

Photographs

Plant A—Gravity Filters

Type: Conventional Treatment



Plant B—Dual Pacer II (Model P-525)

Type: Alternative

Packaged plant comprised of an upflow clarifier and downflow filtration



Finished Water Clearwell

Type: Welded Steel
Capacity: 2 Million Gallons



Appendix A City of Orange Cove Water System Photographs


Treated Water Booster Pumps

No: 4

Power: 30-hp, 50-hp, 60-hp and 75 hp




Hydropneumatic Tank



Chemical Facilities

Pre- & Post Chlorination chemical metering pumps



Appendix A City of Orange Cove Water System Photographs

Backwash Receiving Basin & Solids Equalization /Sedimentation Tank

Basin dimensions: 40 feet x 25 feet
Basin depth: 11 feet

Tank Type: Bolted Steel
Tank Capacity: 230,000 gallons



Sludge Mixing Pump & Sludge Pump

Sludge Mixing Power: 50 hp

Sludge Pump Power: 7.5 hp



Backwash Recycle Pump

Power : 3 hp



Appendix A
City of Orange Cove Water System
Photographs

Dewatering Box



Solids Handling Chemical Building



Appendix B

Source Bacteriological Monitoring Report

Source Bacteriological Monitoring Report

1010023 Orange Cove, City of

Sample Date	Time	Source	Sample Type	Test Method	T Coli	E Coli	F Coli	HPC	Violation	Comments
1/7/2015	11:15	canal	Surface	MPN	<2		<2			
1/14/2015	11:50	Canal	Surface	MPN	2		<2			
1/21/2015	11:45	Canal	Surface	MPN	<2		<2			
1/28/2015	11:26	Canal	Surface	MPN	<2		<2			
2/6/2015	12:05	Canal	Surface	MPN	7		<2			
2/11/2015	11:20	canal	Surface	MPN	22		4			
2/18/2015	11:41	Canal	Surface	MPN	<2		<2			
2/25/2015	11:10	Canal	Surface	MPN	13		13			
3/4/2015	11:30	Canal	Well	MPN	<2	<2	<2			
3/11/2015	10:10	Canal	Surface	MPN	240	11	17			
3/18/2015	12:00	Canal	Surface	MPN	8	2	2			
3/25/2015	12:17	canal	Surface	MPN	23	<2	2			
4/1/2015	11:50	Canal	Surface	MPN	30		<2			
4/8/2015	11:15	Canal	Surface	MPN	50		13			
4/15/2015	11:45	Canal	Surface	MPN	4	<2	<2			
5/8/2015	11:50	Canal	Surface	MPN	220	70				
5/13/2015	11:40	Canal	Surface	MPN	80		80			
5/20/2015	12:25	Canal	Surface	MPN	13		4			
5/27/2015	11:50	Canal	Surface	MPN	4	<2				
6/3/2015	13:00	Canal	Surface	MPN	30	2	2			
6/12/2015	12:45	canal	Surface	MPN	4	4	4			
6/19/2015	10:45	canal	Surface	MPN	80	7	11			
6/24/2015	10:10	Canal	Surface	MPN	30	2	2			
7/1/2015	12:05	canal	Surface	MPN	23		2			
7/8/2015	11:36	canal	Surface	MPN	30		30			
7/17/2015	11:20	canal	Surface	MPN	300		300			
7/22/2015	11:36	canal	Surface	MPN	300		14			
7/29/2015	10:50	Kern Canal	Surface	MPN	50		8			
8/7/2015	10:59	Lopez	Well	MPN	50	<2	2			
8/14/2015	11:00	Canal	Surface	MPN	80	8	8			
8/19/2015	10:15	Canal	Well	MPN	240	2	2			
8/26/2015	12:55	Canal	Well	MPN	240	13				
9/9/2015	13:00	Canal	Surface	MPN	240	13	13			
9/16/2015	12:10	Canal	Surface	MPN	50	4	4			
9/23/2015	11:29	Canal	Surface	MPN	50	17	17			
9/30/2015	11:54	Canal	Surface	MPN	80		4			
10/7/2015	12:23	Canal	Surface	MPN	<1.8		<1.8			
10/7/2015	12:23	Canal	Surface	MPN	<1.0	<1.0				
10/14/2015	11:56	Canal	Surface	MPN	27		9.3			
10/23/2015	11:45	canal	Surface	MPN	49	17				

1010023 Orange Cove, City of

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
10/28/2015	12:06	canal	Surface	MPN	23		2			
11/6/2015	11:10	Canal	Surface	MPN	23		2			
11/13/2015	11:05	canal	Surface	MPN	4.5		4.5			
11/18/2015	11:30	canal	Surface	MPN	7.8		2			
11/25/2015	13:20	canal	Surface	MPN	49		17			
1/8/2016	11:16	canal	Surface	MPN	>1600		33			
1/15/2016	12:03	canal	Surface	MPN	7		<1.8			
1/20/2016	11:31	Canal	Surface	MPN	>1600	350				
1/27/2016	11:55	canal	Surface	MPN	23	4.6				
2/3/2016	12:11	Canal	Surface	MPN	23	13	13			
2/10/2016	11:20	canal	Surface	MPN	46	13	13			
2/17/2016	10:48	canal	Surface	MPN	9.2	6.8	6.8			
2/24/2016	12:24	canal	Surface	MPN	6.8	2	2			
3/2/2016	12:20	canal	Surface	MPN	22	17	17			
3/9/2016	11:45	canal	Surface	MPN	2	<1.8	<1.8			
3/16/2016	11:45	canal	Surface	MPN	7.8	2	2			
3/24/2016	11:55	canal	Surface	MPN	7.8	7.8	7.8			
3/30/2016	12:15	canal	Surface	MPN	49	23	23			
4/8/2016	11:22	canal	Surface	MPN	27	6.8	6.8			
4/15/2016	11:25	canal	Surface	MPN	79	17	17			
4/20/2016	11:50	canal	Surface	MPN	<1.8	<1.8	<1.8			
4/27/2016	12:01	Canal	Surface	MPN	<1.8	<1.8	<1.8			
5/6/2016	10:57	Kern Canal	Surface	MPN	<1.8	<1.8				
5/13/2016	11:20	Canal	Surface	MPN	350	170	350			
5/18/2016	11:55	Canal	Surface	MPN	49	49	49			
5/25/2016	12:30	canal	Surface	MPN	<1.8	<1.8	<1.8			
6/1/2016	14:00	Canal	Surface	MPN	79	33	33			
6/8/2016	12:38	Canal	Surface	MPN	<1.8	<1.8	<1.8			
6/15/2016	12:40	canal	Surface	MPN	170	170	170			
6/22/2016	12:30	canal	Surface	MPN	23	7.8	7.8			
7/8/2016	12:20	canal	Surface	MPN	11	6.8	6.8			
7/13/2016	12:07	canal	Surface	MPN	49	13	13			
7/20/2016	12:15	Canal	Surface	MPN	49	2	2			
7/29/2016	12:02	Canal	Surface	MPN	70	4.5	4.5			
8/3/2016	12:33	Canal	Surface	MPN	240	14	17			
8/19/2016	11:00	canal	Surface	MPN	22	2	4			
8/26/2016	11:35	Canal	Surface	MPN	13	2	2			
9/2/2016	11:42	Canal	Surface	MPN	130	6.8	6.8			
9/7/2016	11:15	Well 2A	Well	MPN	<1.1	<1.1				
9/9/2016	11:30	canal	Surface	MPN	130	7.8	7.8			
9/14/2016	11:25	well 6	Well	MPN	<1.1	<1.1				
9/14/2016	12:45	Canal	Surface	MPN	79	4.5				

1010023 Orange Cove, City of

Sample Date	Time	Source	Sample Type	Test Method	T Coli	E Coli	F Coli	HPC	Violation	Comments
9/21/2016	10:20	Well 7	Well	MPN	<1.1	<1.1				
9/23/2016	14:35	Canal	Surface	MPN	49	23	23			
9/28/2016	11:30	Well 9A	Well	MPN	<1.1	<1.1				
9/28/2016	12:50	Canal	Surface	MPN	70	7.8	7.8			
10/7/2016	14:45	Canal	Surface	MPN	7.8	4.5	<1.8			
10/12/2016	11:57	Canal	Surface	MPN	<1.8	<1.8	<1.8			
10/21/2016	11:25	Canal	Surface	MPN	33	2	4.5			
10/26/2016	12:00	Canal	Well	MPN	240	<1.8	<1.8			
11/4/2016	11:40	Kern Canal	Well	MPN	49	<1.8	<1.8			
11/9/2016	11:57	canal	Surface	MPN	<1.8	<1.8	<1.8			
11/18/2016	9:50	Canal	Surface	MPN	350	49	79			
11/30/2016	11:20	canal	Surface	MPN	33	<1.8	<1.8			
12/9/2016	11:40	canal	Surface	MPN	130	13	13			
12/14/2016	12:40	canal	Surface	MPN	170	<1.8	<1.8			
12/22/2016	13:28	Canal	Surface	MPN	<1.8	<1.8	<1.8			
12/30/2016	10:20	Kern canal	Surface	MPN	79	49	49			
1/4/2017	12:12	Canal	Surface	MPN	23	<1.8	4.5			
1/11/2017	13:05	Canal	Surface	MPN	920	110	110			
1/20/2017	11:23	Canal	Surface	MPN	920	13	23			
1/27/2017	11:30	Canal	Surface	MPN	<1.8	<1.8	<1.8			
2/8/2017	11:50	Canal	Surface	MPN	<1.8	<1.8	<1.8			
2/17/2017	12:20	Canal	Surface	MPN	110	33	33			
2/24/2017	11:45	Canal	Surface	MPN	14	2	2			
4/5/2017	11:07	Canal	Surface	MPN	22	11	11			
4/13/2017	10:57	Canal	Surface	MPN	<1.8	<1.8	<1.8			
4/19/2017	11:05	Canal	Surface	MPN	33	23	23			
4/26/2017	12:22	Canal	Surface	MPN	7.8	4.5	4.5			
5/3/2017	12:10	Canal	Surface	MPN	17	7.8	13		MR7	Does not have monthly summary
5/10/2017	12:30	Canal	Surface	MPN	33	23	23			
5/17/2017	12:15	Canal	Surface	MPN	<1.8	<1.8	<1.8			
5/24/2017	12:15	canal	Surface	MPN	<1.8	<1.8	<1.8			
5/31/2017	11:30	Canal	Surface	MPN	49	17	33			
6/7/2017	12:10	Canal	Surface	MPN	14	11	11			
6/14/2017	11:20	Canal	Surface	MPN	21	4.5	4.5			
6/23/2017	11:20	Canal	Surface	MPN	33	<1.8	<1.8			
6/28/2017	10:50	Canal	Surface	MPN	7.8	7.8	7.8			
7/19/2017	10:40	Canal	Surface	MPN	33	<1.8	<1.8			
7/26/2017	11:40	Canal	Surface	MPN	130	<1.8	<1.8			
8/2/2017	12:09	Canal	Surface	MPN	240	4.5	4.5			
8/9/2017	12:40	Canal	Surface	MPN	17	2	2			
8/16/2017	11:32	Canal	Surface	MPN	49	<1.8	<1.8			
8/23/2017	12:20	Canal	Surface	MPN	79	<1.8	<1.8			

1010023 Orange Cove, City of

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
8/30/2017	13:17	Canal	Surface	MPN	240	<1.8	<1.8			
9/6/2017	12:05	Canal	Surface	MPN	540	6.8	6.8			
9/13/2017	11:15	Canal	Surface	MPN	79	13	13			
9/20/2017	11:15	Canal	Surface	MPN	13	4.5	7.8			
9/27/2017	11:55	Canal	Surface	MPN	22	17	17			
10/4/2017	12:35	Canal	Surface	MPN	<1.8	<1.8	<1.8			
10/11/2017	12:05	Canal	Surface	MPN	<1.8	<1.8	<1.8			
10/18/2017	13:00	Canal	Surface	MPN	14	4	4			
10/25/2017	11:20	Canal	Surface	MPN	70	7.8	7.8			
11/1/2017	12:08	Canal	Surface	MPN	46	2	2			
11/7/2017	12:03	Canal	Surface	MPN	79	2	2			
11/15/2017	11:58	Canal	Surface	MPN	<1.8	<1.8	<1.8			
11/22/2017	10:25	Canal	Surface	MPN	33	7.8	7.8			
12/6/2017	10:15	Canal	Surface	MPN	31	2	4.5			
12/13/2017	13:35	Canal	Surface	MPN	23	4.5	7.8			
12/20/2017	11:55	Canal	Surface	MPN	4.5	2	2			
12/27/2017	12:00	Canal	Surface	MPN	4.5	<1.8	<1.8			
1/24/2018	13:12	Canal	Surface	MPN	7.8	2	2			
1/31/2018	11:25	Canal	Surface	MPN	<1.8	<1.8	<1.8			
2/7/2018	11:00	Canal	Surface	MPN	<1.8	<1.8	<1.8			
2/14/2018	12:15	Canal	Surface	MPN	2	<1.8	<1.8			
2/21/2018	11:10	Canal	Surface	MPN	<1.8	<1.8	<1.8			
2/28/2018	13:25	Canal	Surface	MPN	<1.8	<1.8	<1.8			
3/16/2018	10:40	Canal	Surface	MPN	4	<1.8	<1.8			
3/21/2018	11:58	Canal	Surface	MPN	49	4	4			
3/27/2018	11:57	Canal	Surface	MPN	13	7.8	7.8			
4/4/2018	11:37	Canal	Surface	MPN	130	27	27			
4/11/2018	11:45	Canal	Surface	MPN	140	70	70			
4/18/2018	11:45	Canal	Surface	MPN	22	7.8	7.8			
4/25/2018	10:30	Canal	Surface	MPN	33	17	17			
5/2/2018	12:33	Canal	Surface	MPN	49	17	17			
5/9/2018	12:10	Canal	Surface	MPN	17	17	17			
5/16/2018	11:55	Canal	Surface	MPN	49	33	33			
5/23/2018	11:30	Canal	Surface	MPN	79	79	79			
6/1/2018	11:20	Canal	Surface	MPN	130	79	79			
6/6/2018	11:00	Canal	Surface	MPN	79	11	11			
6/13/2018	11:20	Canal	Surface	MPN	22	11	11			
6/22/2018	12:50	Canal	Surface	MPN	2	2	2			
6/27/2018	10:00	Canal	Surface	MPN	17	17	17			
7/3/2018	11:57	Canal	Surface	MPN	23	23	23			
7/11/2018	11:35	Canal	Surface	MPN	11	11	11			
7/18/2018	10:50	Canal	Surface	MPN	79	4.5	4.5			

1010023 Orange Cove, City of

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
7/27/2018	12:40	Canal	Surface	MPN	33	7.8	7.8			
8/3/2018	10:58	Canal	Surface	MPN	4.5	<1.8	2			
8/8/2018	13:40	Canal	Surface	MPN	6.8	2	4.5			
8/15/2018	11:45	Canal	Surface	MPN	49	11	11			
8/22/2018	12:40	Canal	Surface	MPN	21	<1.8	<1.8			
8/30/2018	13:00	Canal	Surface	MPN	11	2	2			
9/5/2018	12:00	Canal	Surface	MPN	<1.8	<1.8	<1.8			
9/14/2018	10:25	Canal	Surface	MPN	7.8	7.8	7.8			
9/19/2018	11:50	Canal	Surface	MPN	7.8	<1.8	<1.8			
10/3/2018	12:47	Canal	Surface	MPN	49	13	13			
10/10/2018	11:35	Canal	Surface	MPN	49	13	13			
10/17/2018	11:30	Canal	Surface	MPN	33	4.5	4.5			
10/24/2018	11:10	Canal	Surface	MPN	2	<1.8	<1.8			
11/9/2018	13:55	Canal	Surface	MPN	4	4	4			
11/14/2018	12:00	Canal	Surface	MPN	7.8	2	2			
11/19/2018	11:25	Canal	Surface	MPN	7.8	<1.8	<1.8			
11/28/2018	13:00	Canal	Surface	MPN	49	49	49			
12/5/2018	11:20	Canal	Surface	MPN	9.3	4	4			
12/12/2018	12:15	Canal	Surface	MPN	23	7.8	7.8			
12/19/2018	11:50	Canal	Surface	MPN	<1.8	<1.8	<1.8			
12/26/2018	11:50	Canal	Surface	MPN	23	13	13			
1/2/2019	11:55	Canal	Surface	MPN	<1.8	<1.8	<1.8			
1/11/2019	12:00	Canal	Surface	MPN	<1.8	<1.8	<1.8			
1/16/2019	12:25	Canal	Surface	MPN	<1.8	<1.8	<1.8			
1/23/2019	12:01	Canal	Surface	MPN	2	2	2			
1/30/2019	11:18	Canal	Surface	MPN	6.8	6.8	6.8			
2/6/2019	11:40	Canal	Surface	MPN	13	2	2			
2/15/2019	13:10	Canal	Surface	MPN	<1.8	<1.8	<1.8			
2/20/2019	12:40	Canal	Surface	MPN	<1.8	<1.8	<1.8			
2/27/2019	11:00	Canal	Surface	MPN	7.8	2	2			
3/6/2019	11:29	Canal	Surface	MPN	49	33	33			
3/15/2019	12:25	Canal	Surface	MPN	23	13	13			
3/20/2019	12:05	Canal	Surface	MPN	22	22	22			
3/27/2019	11:15	Canal	Surface	MPN	33	33	33			
4/5/2019	11:59	Canal	Surface	MPN	9.2	6.1	6.1			
4/10/2019	11:22	Canal	Surface	MPN	7.8	7.8	7.8			
4/17/2019	13:13	Canal	Surface	MPN	23	13	13			
4/24/2019	10:10	Canal	Surface	MPN	23	13	13			
5/1/2019	12:10	Canal	Surface	MPN	14	14	14			
5/8/2019	11:30	Canal	Surface	MPN	46	31	31			
5/17/2019	11:29	Canal	Surface	MPN	7.8	2	2			
5/31/2019	14:20	Canal	Surface	MPN	<1.8	<1.8	<1.8			

1010023 Orange Cove, City of

<i>Sample Date</i>	<i>Time</i>	<i>Source</i>	<i>Sample Type</i>	<i>Test Method</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>HPC</i>	<i>Violation</i>	<i>Comments</i>
6/5/2019	11:51	Canal	Surface	MPN	33	13	13			
6/12/2019	11:25	Canal	Surface	MPN	7.8	7.8	7.8			
6/19/2019	11:20	Canal	Surface	MPN	2	<1.8	<1.8			
6/26/2019	12:18	Canal	Surface	MPN	1.8	1.8	4			
8/2/2019	12:39	Canal	Surface	MPN	220	<1.8	<1.8			
8/9/2019	13:25	Canal	Surface	MPN	22	2	2			
8/16/2019	12:20	Canal	Surface	MPN	49	2	2			
8/21/2019	12:40	Canal	Surface	MPN	4.5	2	2			
9/4/2019	12:04	Canal	Surface	MPN	4	<1.89	<1.8			
9/13/2019	11:15	Canal	Surface	MPN	79	7.8	7.8			
10/4/2019	11:25	Canal	Surface	MPN	130	<1.8	<1.8			
10/9/2019	10:15	Canal	Surface	MPN	>1600	<1.8	<1.8			
10/18/2019	11:15	Canal	Surface	MPN	7.8	<1.8	<1.8			
10/30/2019	11:05	Canal	Surface	MPN	49	6.8	6.8			
11/8/2019	11:51	Canal	Surface	MPN	1.8	<1.8	<1.8			
11/13/2019	10:49	Canal	Surface	MPN	<1.8	<1.8	<1.8			
11/22/2019	10:20	Canal	Surface	MPN	23	2	2			
11/25/2019	12:35	Canal	Surface	MPN	17	2	2			

Appendix C

Drinking Water Analyses Result Report

DATE: 1/2/2020

STATE OF CALIFORNIA
DRINKING WATER ANALYSES RESULTS REPORT
LAST SAMPLE FOR ALL CHAPTER 15 CONSTITUENTS - ALL RESULTS
REPORT OF SYSTEM: 1010023

PAGE 1

SYSTEM NO: 1010023 NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 002

NAME: FRIANT KERN CANAL - RAW

CLASS: CLSA

STATUS: A

PSCODE	GROUP/CONSTITUENT IDENTIFICATION	DATE	RESULT *	MCL	DLR	TRIGGER	UNIT
1010023002	1010023 CITY OF ORANGE COVE	002	FRIANT KERN CANAL - RAW				
DB P	DISINFECTION BYPRODUCTS						
32101	BROMODICHLOROMETHANE (THM)	2019/09/27	0	-----	1	-----	UG/L
32104	BROMOFORM (THM)	2019/09/27	0	-----	1	-----	UG/L
32106	CHLOROFORM (THM)	2019/09/27	0	-----	1	-----	UG/L
32105	DIBROMOCHLOROMETHANE (THM)	2019/09/27	0	-----	1	-----	UG/L
82080	TOTAL TRIHALOMETHANES	2019/09/27	0	80	-----	80.000	UG/L
GP	SECONDARY/GP						
82383	AGGRSSIVE INDEX (CORROSIVITY)	2019/03/27	9.5 *	-----	-----	-----	
00440	BICARBONATE ALKALINITY	2019/09/27	9.8 *	-----	-----	-----	MG/L
00916	CALCIUM	2019/03/27	4.3 *	-----	-----	-----	MG/L
00445	CARBONATE ALKALINITY	2019/09/27	0	-----	-----	-----	MG/L
00940	CHLORIDE	2019/03/27	2.8	500	-----	250.000	MG/L
00081	COLOR	2019/03/27	45 *	15	-----	15.000	UNITS
01042	COPPER	2019/03/27	81	1000	50	1000.000	UG/L
38260	FOAMING AGENTS (MBAS)	2019/03/27 < 0000000000		.5	-----	0.500	MG/L
00900	HARDNESS (TOTAL) AS CaCO3	2019/03/27	14.0 *	-----	-----	-----	MG/L
71830	HYDROXIDE ALKALINITY	2019/09/27	0	-----	-----	-----	MG/L
01045	IRON	2019/03/27	220	300	100	300.000	UG/L
00927	MAGNESIUM	2019/03/27	0.88 *	-----	-----	-----	MG/L
01055	MANGANESE	2019/03/27 < 0000000000		50	20	50.000	UG/L
00086	ODOR THRESHOLD @ 60 C	2019/03/27	1.5	3	1	3.000	TON
00403	PH, LABORATORY	2019/03/27	7.3 *	-----	-----	-----	
01077	SILVER	2019/03/27 < 0000000000		100	10	100.000	UG/L
00929	SODIUM	2019/03/27	4.3 *	-----	-----	-----	MG/L
00095	SPECIFIC CONDUCTANCE	2019/03/27	49	1600	-----	900.000	US
00945	SULFATE	2019/03/27	1.3	500	.5	250.000	MG/L
70300	TOTAL DISSOLVED SOLIDS	2019/03/27	42	1000	-----	500.000	MG/L
82079	TURBIDITY, LABORATORY	2019/03/27	9.4 *	5	.1	5.000	NTU

DATE: 1/2/2020

STATE OF CALIFORNIA
DRINKING WATER ANALYSES RESULTS REPORT
LAST SAMPLE FOR ALL CHAPTER 15 CONSTITUENTS - ALL RESULTS
REPORT OF SYSTEM: 1010023

PAGE 2

SYSTEM NO: 1010023

NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 002

NAME: FRIANT KERN CANAL - RAW

CLASS: CLSA

STATUS: A

PSCODE	GROUP/CONSTITUENT IDENTIFICATION	DATE	RESULT *	MCL	DLR	TRIGGER	UNIT
1010023002	GP SECONDARY/GP						
	01092 ZINC	2019/03/27 <	00000000 00	5000	50	5000.000	UG/L
	IO INORGANIC						
	01105 ALUMINIUM	2019/03/27	1800 *	1000	50	200.000	UG/L
	01097 ANTIMONY	2019/03/27 <	00000000 00	6	6	6.000	UG/L
	01002 ARSENIC	2019/03/27	2.2	10	2	5.000	UG/L
	81855 ASBESTOS	2011/06/15 <	.0000	7	.2	7.000	MFL
	01007 BARIUM	2019/03/27 <	00000000 00	1000	100	1000.000	UG/L
	01012 BERYLLIUM	2019/03/27 <	00000000 00	4	1	4.000	UG/L
	01027 CADMIUM	2019/03/27 <	00000000 00	5	1	5.000	UG/L
	A-044 CHROMIUM (TOTAL CR-CRVI SCREEN)	2003/07/18	1.0000 *	-----	1	-----	UG/L
	01034 CHROMIUM (TOTAL)	2019/03/27 <	00000000 00	50	10	50.000	UG/L
	01032 CHROMIUM, HEXVALENT	2001/03/08 <	.0000	-----	1	1.000	UG/L
	01291 CYANIDE	2014/09/03 <	.0000	150	100	150.000	UG/L
	00951 FLUORIDE (F) (NATURAL-SOURCE)	2019/03/27 <	00000000 00	2	.1	2.000	MG/L
	01051 LEAD	2019/03/27 <	00000000 00	-----	5	15.000	UG/L
	71900 MERCURY	2019/03/27 <	00000000 00	2	1	2.000	UG/L
	01067 NICKEL	2019/03/27 <	00000000 00	100	10	100.000	UG/L
	A-031 PERCHLORATE	2019/03/27 <	00000000 00	6	4	4.000	UG/L
	01147 SELENIUM	2019/03/27 <	00000000 00	50	5	50.000	UG/L
	01059 THALLIUM	2019/03/27 <	00000000 00	2	1	2.000	UG/L
	NI NITRATE/NITRITE						
	00618 NITRATE (AS N)	2019/03/27 <	00000000 00	10	.4	5.000	mg/L
	71850 NITRATE (AS NO3)	2015/03/18 <	.0000	45	2	23.000	MG/L
	A-029 NITRATE + NITRITE (AS N)	2019/03/27 <	00000000 00	10	.4	5.000	mg/L
	00620 NITRITE (AS N)	2019/03/27 <	00000000 00	1	.4	0.500	mg/L

DATE: 1/2/2020

STATE OF CALIFORNIA
DRINKING WATER ANALYSES RESULTS REPORT
LAST SAMPLE FOR ALL CHAPTER 15 CONSTITUENTS - ALL RESULTS
REPORT OF SYSTEM: 1010023

PAGE 3

SYSTEM NO: 1010023 NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 002 NAME: FRIANT KERN CANAL - RAW

CLASS: CLSA

STATUS: A

PSCODE	GROUP/CONSTITUENT IDENTIFICATION	DATE	RESULT *	MCL	DLR	TRIGGER	UNIT
1010023002	RA RADIOLOGICAL						
	01501 GROSS ALPHA	2017/03/30	< 00000000 00	15	3	5.000	PCI/L
	01502 GROSS ALPHA COUNTING ERROR	2017/03/30	0.00	-----	-----	-----	PCI/L
	A-072 GROSS ALPHA MDA95	2017/03/30	1.06 *	-----	-----	-----	PCI/L
	11501 RADIUM 228	2017/05/03	1.47 *	-----	1	-----	PCI/L
	11502 RADIUM 228 COUNTING ERROR	2017/05/03	0.35 *	-----	-----	-----	PCI/L
	A-075 RADIUM 228 MDA95	2017/05/03	0.45 *	-----	-----	-----	PCI/L
	S1 REGULATED VOC						
	34506 1,1,1-TRICHLOROETHANE	2019/09/27	0	200	.5	0.500	UG/L
	34516 1,1,2,2-TETRACHLOROETHANE	2019/09/27	0	1	.5	0.500	UG/L
	34511 1,1,2-TRICHLOROETHANE	2019/09/27	0	5	.5	0.500	UG/L
	34496 1,1-DICHLOROETHANE	2019/09/27	0	5	.5	0.500	UG/L
	34501 1,1-DICHLOROETHYLENE	2019/09/27	0	6	.5	0.500	UG/L
	34551 1,2,4-TRICHLOROBENZENE	2019/09/27	0	5	.5	0.500	UG/L
	34536 1,2-DICHLOROBENZENE	2019/09/27	0	600	.5	0.500	UG/L
	34531 1,2-DICHLOROETHANE	2019/09/27	0	.5	.5	0.500	UG/L
	34541 1,2-DICHLOROPROPANE	2019/09/27	0	5	.5	0.500	UG/L
	34561 1,3-DICHLOROPROPENE (TOTAL)	2019/09/27	0	.5	.5	0.500	UG/L
	34571 1,4-DICHLOROBENZENE	2019/09/27	0	5	.5	0.500	UG/L
	34030 BENZENE	2019/09/27	0	1	.5	0.500	UG/L
	32102 CARBON TETRACHLORIDE	2019/09/27	0	.5	.5	0.500	UG/L
	77093 CIS-1,2-DICHLOROETHYLENE	2019/09/27	0	6	.5	0.500	UG/L
	34423 DICHLOROMETHANE	2019/09/27	0	5	.5	0.500	UG/L
	34371 ETHYL BENZENE	2019/09/27	0	300	.5	0.500	UG/L
	46491 METHYL-TERT-BUTYL-ETHER (MTBE)	2019/09/27	0	13	3	3.000	UG/L
	34301 MONOCHLOROBENZENE	2019/09/27	0	70	.5	0.500	UG/L
	77128 STYRENE	2019/09/27	0	100	.5	0.500	UG/L
	34475 TETRACHLOROETHYLENE	2019/09/27	0	5	.5	0.500	UG/L
	34010 TOLUENE	2019/09/27	0	150	.5	0.500	UG/L

DATE: 1/2/2020

STATE OF CALIFORNIA
DRINKING WATER ANALYSES RESULTS REPORT
LAST SAMPLE FOR ALL CHAPTER 15 CONSTITUENTS - ALL RESULTS
REPORT OF SYSTEM: 1010023

PAGE 4

SYSTEM NO: 1010023

NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 002

NAME: FRIANT KERN CANAL - RAW

CLASS: CLSA

STATUS: A

PSCODE	GROUP/CONSTITUENT IDENTIFICATION	DATE	RESULT	*	MCL	DLR	TRIGGER	UNIT
1010023002	S1 REGULATED VOC							
	34546 TRANS-1,2-DICHLOROETHYLENE	2019/09/27	0		10	.5	0.500	UG/L
	39180 TRICHLOROETHYLENE	2019/09/27	0		5	.5	0.500	UG/L
	34488 TRICHLOROFLUOROMETHANE FREON 11	2019/09/27	0		150	5	5.000	UG/L
	81611 TRICHLOROTRIFLUOROETHANE (FREON 113)	2019/09/27	0		1200	10	10.000	UG/L
	39175 VINYL CHLORIDE	2019/09/27	0		.5	.5	0.500	UG/L
	81551 XYLENES (TOTAL)	2019/09/27	0		1750	0.5	1750.000	UG/L
	S2 REGULATED SOC							
	7744X 1,2,3-TRICHLOROPROPANE (1,2,3-TCP)	2009/06/19 <	.5000	*	-----	0.005	0.005	UG/L
	77443 1,2,3-TRICHLOROPROPANE (1,2,3-TCP)	2019/03/13 <	00000000 00		0.005	0.005	0.005	UG/L
	39045 2,4,5-TP (SILVEX)	2016/07/06 <	00000000 00		50	1	1.000	UG/L
	39730 2,4-D	2019/09/27	0		70	10	10.000	UG/L
	77825 ALACHLOR	2019/09/27	0		2	1	1.000	UG/L
	39033 ATRAZINE	2019/09/27	0		1	.5	0.500	UG/L
	38710 BENTAZON	2016/07/06 <	00000000 00		18	2	2.000	UG/L
	34247 BENZO (A) PYRENE	2007/06/01 <	.0000		.2	.1	0.100	UG/L
	39350 CHLORDANE	1998/06/18 <	.0000		.1	.1	0.100	UG/L
	38432 DALAPON	2016/07/06 <	00000000 00		200	10	10.000	UG/L
	A-026 DI(2-ETHYLHEXYL)ADIPATE	2007/06/01 <	.0000		400	5	5.000	UG/L
	39100 DI(2-ETHYLHEXYL)PHTHALATE	2007/06/01 <	.0000		4	3	3.000	UG/L
	38761 DIBROMOCHLOROPROPANE (DBCP)	2016/07/06 <	00000000 00		.2	.01	0.010	UG/L
	81287 DINOSEB	2016/07/06 <	00000000 00		7	2	2.000	UG/L
	38926 ENDOTHALL	2019/09/27	0		100	45	45.000	UG/L
	39390 ENDRIN	1998/06/18 <	.0000		2	.1	0.100	UG/L
	77651 ETHYLENE DIBROMIDE (EDB)	2016/07/06 <	00000000 00		.05	.02	0.020	UG/L
	79743 GLYPHOSATE	2006/12/01 <	.0000		700	25	25.000	UG/L
	39410 HEPTACHLOR	1998/06/18 <	.0000		.01	.01	0.010	UG/L
	39420 HEPTACHLOR EPOXIDE	1998/06/18 <	.0000		.01	.01	0.010	UG/L
	39700 HEXACHLOROBENZENE	1998/06/18 <	.0000		1	.5	0.500	UG/L
	39340 LINDANE	1998/06/18 <	.0000		.2	.2	0.200	UG/L

STATE OF CALIFORNIA
DRINKING WATER ANALYSES RESULTS REPORT
LAST SAMPLE FOR ALL CHAPTER 15 CONSTITUENTS - ALL RESULTS
REPORT OF SYSTEM: 1010023

SYSTEM NO: 1010023

NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 002

NAME: FRIANT KERN CANAL - RAW

CLASS: CLSA

STATUS: A

PSCODE		GROUP/CONSTITUENT IDENTIFICATION	DATE	RESULT	*	MCL	DLR	TRIGGER	UNIT
1010023002	S2	39480	METHOXYCHLOR	1998/06/18 <	.0000	40	10	10.000	UG/L
		82199	MOLINATE	2007/06/01 <	.0000	20	2	2.000	UG/L
		34671	PCB-1016 (AS DECACHLOROBIPHENYL (DCB))	1998/06/18 <	.0000	-----	.5	0.500	UG/L
		39488	PCB-1221 (AS DCB)	1998/06/18 <	.0000	-----	.5	0.500	UG/L
		39492	PCB-1232 (AS DCB)	1998/06/18 <	.0000	-----	.5	0.500	UG/L
		39496	PCB-1242 (AS DCB)	1998/06/18 <	.0000	-----	.5	0.500	UG/L
		39500	PCB-1248 (AS DCB)	1998/06/18 <	.0000	-----	.5	0.500	UG/L
		39504	PCB-1254 (AS DCB)	1998/06/18 <	.0000	-----	.5	0.500	UG/L
		39508	PCB-1260 (AS DCB)	1998/06/18 <	.0000	-----	.5	0.500	UG/L
		39032	PENTACHLOROPHENOL	2016/07/06 < 0000000000		1	.2	0.200	UG/L
		39720	PICLORAM	2016/07/06 < 0000000000		500	1	1.000	UG/L
		39516	POLYCHLORINATED BIPHENYLS, TOTAL, AS DCB	1998/06/18 <	.0000	.5	.5	0.500	UG/L
		39055	SIMAZINE	2019/09/27	0	4	1	1.000	UG/L
		A-001	THIOBENCARB	2007/06/01 <	.0000	70	1	1.000	UG/L
		39400	TOXAPHENE	1998/06/18 <	.0000	3	1	1.000	UG/L
UA STATE UCMR									
		77562	1,1,1,2-TETRACHLOROETHANE	2019/09/27	0	-----	.5	0.500	UG/L
		01020	BORON	2001/02/22 <	.0000	-----	-----	-----	UG/L
		34668	DICHLORODIFLUOROMETHANE (FREON 12)	2019/09/27	0	-----	0.5	1000.000	UG/L
		A-033	ETHYL-TERT-BUTYL ETHER	2019/09/27	0	-----	3	-----	UG/L
		A-034	TERT-AMYL-METHYL ETHER (TAME)	2019/09/27	0	-----	3	-----	UG/L
		01087	VANADIUM	2001/02/22 <	.0000	-----	-----	50.000	UG/L
UB UNREG. TABLE B									
		77222	1,2,4-TRIMETHYLBENZENE	2019/09/27	0	-----	0.5	330.000	UG/L
		38458	DIMETHOATE	2007/06/01 <	10.0000 *	-----	-----	-----	UG/L
		A-011	P-ISOPROPYLTOLUENE	2019/09/27	0	-----	-----	-----	UG/L
UC UNREG. TABLE C									
		38533	PROPACHLOR	2007/06/01 <	.0000	-----	0.5	0.500	UG/L

DATE: 1/2/2020

STATE OF CALIFORNIA
DRINKING WATER ANALYSES RESULTS REPORT
LAST SAMPLE FOR ALL CHAPTER 15 CONSTITUENTS - ALL RESULTS
REPORT OF SYSTEM: 1010023

PAGE 6

SYSTEM NO: 1010023 NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 007

NAME: ORANGE COVE WTP - TREATED

CLASS: OTHR

STATUS: A

PSCODE	GROUP/CONSTITUENT IDENTIFICATION		DATE	RESULT *	MCL	DLR	TRIGGER	UNIT
1010023007	1010023 CITY OF ORANGE COVE		007	ORANGE COVE WTP - TREATED				
	GP SECONDARY/GP							
	01042	COPPER	2002/04/19 <	50.0000	1000	50	1000.000	UG/L
	01045	IRON	2002/04/05 <	50.0000	300	100	300.000	UG/L
	01055	MANGANESE	2002/04/05 <	5.0000	50	20	50.000	UG/L
	IO INORGANIC							
	01051	LEAD	2002/04/19 <	5.0000	-----	5	15.000	UG/L
	NI NITRATE/NITRITE							
	71850	NITRATE (AS NO3)	2013/01/23	32.0000 *	45	2	23.000	MG/L

DATE: 1/2/2020

STATE OF CALIFORNIA
DRINKING WATER ANALYSES RESULTS REPORT
LAST SAMPLE FOR ALL CHAPTER 15 CONSTITUENTS - ALL RESULTS
REPORT OF SYSTEM: 1010023

PAGE 7

SYSTEM NO: 1010023 NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 900 NAME: ST2DBP - 633 SIXTH STREET

CLASS: DBPQ

STATUS: A

PSCODE	GROUP/CONSTITUENT IDENTIFICATION	DATE	RESULT	*	MCL	DLR	TRIGGER	UNIT
1010023900	1010023 CITY OF ORANGE COVE	900	ST2DBP - 633 SIXTH STREET					
DB P	DISINFECTION BYPRODUCTS							
	32101 BROMODICHLOROMETHANE (THM)	2019/09/27	1.2	*	-----	1	-----	UG/L
	32104 BROMOFORM (THM)	2019/09/27	0		-----	1	-----	UG/L
	32106 CHLOROFORM (THM)	2019/09/27	29	*	-----	1	-----	UG/L
	82721 DIBROMOACETIC ACID (DBAA)	2019/09/27	0		-----	1	-----	UG/L
	32105 DIBROMOCHLOROMETHANE (THM)	2019/09/27	0		-----	1	-----	UG/L
	77288 DICHLOROACETIC ACID (DCAA)	2019/09/27	12	*	-----	1	-----	UG/L
	A-049 HALOACETIC ACIDS (5) (HAA5)	2019/09/27	23		60	-----	60.000	UG/L
	A-041 MONOBROMOACETIC ACID (MBAA)	2019/09/27	0		-----	1	-----	UG/L
	A-042 MONOCHLOROACETIC ACID (MCAA)	2019/09/27	0		-----	2	-----	UG/L
	82080 TOTAL TRIHALOMETHANES	2019/09/27	30		80	-----	80.000	UG/L
	82723 TRICHLOROACETIC ACID (TCAA)	2019/09/27	11	*	-----	1	-----	UG/L

DATE: 1/2/2020

STATE OF CALIFORNIA
DRINKING WATER ANALYSES RESULTS REPORT
LAST SAMPLE FOR ALL CHAPTER 15 CONSTITUENTS - ALL RESULTS
REPORT OF SYSTEM: 1010023

PAGE 8

SYSTEM NO: 1010023 NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 901

NAME: ST2DBP - 1205 ADAMS

CLASS: DBPQ

STATUS: A

PSCODE	GROUP/CONSTITUENT IDENTIFICATION	DATE	RESULT *	MCL	DLR	TRIGGER	UNIT
1010023901	1010023 CITY OF ORANGE COVE	901	ST2DBP - 1205 ADAMS				
DB P	DISINFECTION BYPRODUCTS						
32101	BROMODICHLOROMETHANE (THM)	2019/09/27	1.3 *	-----	1	-----	UG/L
32104	BROMOFORM (THM)	2019/09/27	0	-----	1	-----	UG/L
32106	CHLOROFORM (THM)	2019/09/27	27 *	-----	1	-----	UG/L
82721	DIBROMOACETIC ACID (DBAA)	2019/09/27	0	-----	1	-----	UG/L
32105	DIBROMOCHLOROMETHANE (THM)	2019/09/27	0	-----	1	-----	UG/L
77288	DICHLOROACETIC ACID (DCAA)	2019/09/27	0	-----	1	-----	UG/L
A-049	HALOACETIC ACIDS (5) (HAA5)	2019/09/27	0	60	-----	60.000	UG/L
A-041	MONOBROMOACETIC ACID (MBAA)	2019/09/27	0	-----	1	-----	UG/L
A-042	MONOCHLOROACETIC ACID (MCAA)	2019/09/27	0	-----	2	-----	UG/L
82080	TOTAL TRIHALOMETHANES	2019/09/27	28	80	-----	80.000	UG/L
82723	TRICHLOROACETIC ACID (TCAA)	2019/09/27	0	-----	1	-----	UG/L

Appendix D

Last Sample Date and Monitoring Schedule

LAST SAMPLE DATE AND MONITORING SCHEDULE

SYSTEM NO: 1010023

NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 002

NAME: FRIANT KERN CANAL - RAW

CLASS: CLSA

STATUS: Active

PSCODE	GROUP/CONSTITUENT IDENTIFICATION	LAST RESULT	UNITS	MCL	DLR	LAST SAMPLE	COUNT	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
1010023 - 002	CITY OF ORANGE COVE	002	FRIANT KERN CANAL - RAW								
	GP SECONDARY/GP										
	00440 BICARBONATE ALKALINITY		9.8 MG/L	-----	-----	2019/09/27	185	12		2020/09	
	00916 CALCIUM		4.3 MG/L	-----	-----	2019/03/27	20	12		2020/03	
	00445 CARBONATE ALKALINITY		0 MG/L	-----	-----	2019/09/27	185	12		2020/09	
	00940 CHLORIDE		2.8 MG/L	500	-----	2019/03/27	20	12		2020/03	
	00081 COLOR		45 UNITS	15	-----	2019/03/27	18	12		2020/03	
	01042 COPPER		81 UG/L	1000	50	2019/03/27	20	12		2020/03	
	38260 FOAMING AGENTS (MBAS)	<	ND MG/L	.5	-----	2019/03/27	21	12		2020/03	
	00900 HARDNESS (TOTAL) AS CaCO3		14.0 MG/L	-----	-----	2019/03/27	20	12		2020/03	
	71830 HYDROXIDE ALKALINITY		0 MG/L	-----	-----	2019/09/27	185	12		2020/09	
	01045 IRON		220 UG/L	300	100	2019/03/27	20	12		2020/03	
	00927 MAGNESIUM		0.88 MG/L	-----	-----	2019/03/27	20	12		2020/03	
	01055 MANGANESE	<	ND UG/L	50	20	2019/03/27	20	12		2020/03	
	00086 ODOR THRESHOLD @ 60 C		1.5 TON	3	1	2019/03/27	19	12		2020/03	
	00403 PH, LABORATORY		7.3	-----	-----	2019/03/27	21	12		2020/03	
	01077 SILVER	<	ND UG/L	100	10	2019/03/27	21	12		2020/03	
	00929 SODIUM		4.3 MG/L	-----	-----	2019/03/27	20	12		2020/03	
	00095 SPECIFIC CONDUCTANCE		49 US	1600	-----	2019/03/27	21	12		2020/03	
	00945 SULFATE		1.3 MG/L	500	.5	2019/03/27	20	12		2020/03	
	70300 TOTAL DISSOLVED SOLIDS		42 MG/L	1000	-----	2019/03/27	21	12		2020/03	
	82079 TURBIDITY, LABORATORY		9.4 NTU	5	.1	2019/03/27	18	12		2020/03	
	01092 ZINC	<	ND UG/L	5000	50	2019/03/27	20	12		2020/03	
	IO INORGANIC										
	01105 ALUMINUM		1800 UG/L	1000	50	2019/03/27	19	12		2020/03	
	01097 ANTIMONY	<	ND UG/L	6	6	2019/03/27	19	12		2020/03	
	01002 ARSENIC		2.2 UG/L	10	2	2019/03/27	21	12		2020/03	

LAST SAMPLE DATE AND MONITORING SCHEDULE

SYSTEM NO: 1010023

NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO:

NAME: FRIANT KERN CANAL - RAW

CLASS: CLSA

STATUS: Active

PSCODE	GROUP/CONSTITUENT IDENTIFICATION	LAST RESULT	UNITS	MCL	DLR	LAST SAMPLE	COUNT	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
1010023 - IO INORGANIC 002											
81855	ASBESTOS	<	.0000 MFL	7	.2	2011/06/15	2	108		2020/06	
01007	BARIUM	<	ND UG/L	1000	100	2019/03/27	20	12		2020/03	
01012	BERYLLIUM	<	ND UG/L	4	1	2019/03/27	19	12		2020/03	
01027	CADMIUM	<	ND UG/L	5	1	2019/03/27	21	12		2020/03	
01034	CHROMIUM (TOTAL)	<	ND UG/L	50	10	2019/03/27	21	12		2020/03	
00951	FLUORIDE (F) (NATURAL-SOURCE)	<	ND MG/L	2	.1	2019/03/27	20	12		2020/03	
71900	MERCURY	<	ND UG/L	2	1	2019/03/27	20	36		2022/03	
01067	NICKEL	<	ND UG/L	100	10	2019/03/27	19	12		2020/03	
A-031	PERCHLORATE	<	ND UG/L	6	4	2019/03/27	8	12		2020/03	
01147	SELENIUM	<	ND UG/L	50	5	2019/03/27	21	12		2020/03	
01059	THALLIUM	<	ND UG/L	2	1	2019/03/27	19	12		2020/03	
NI NITRATE/NITRITE											
00618	NITRATE (AS N)	<	ND mg/L	10	.4	2019/03/27	20	12		2020/03	
00620	NITRITE (AS N)	<	ND mg/L	1	.4	2019/03/27	17	36		2022/03	
RA RADIOLOGICAL											
01501	GROSS ALPHA	<	ND PCI/L	15	3	2017/03/30	10	108	M	2026/03	
S1 REGULATED VOC											
34506	1,1,1-TRICHLOROETHANE		0 UG/L	200	.5	2019/09/27	21	36		2022/09	
34516	1,1,2,2-TETRACHLOROETHANE		0 UG/L	1	.5	2019/09/27	21	36		2022/09	
34511	1,1,2-TRICHLOROETHANE		0 UG/L	5	.5	2019/09/27	21	36		2022/09	
34496	1,1-DICHLOROETHANE		0 UG/L	5	.5	2019/09/27	21	36		2022/09	
34501	1,1-DICHLOROETHYLENE		0 UG/L	6	.5	2019/09/27	21	36		2022/09	
34551	1,2,4-TRICHLOROBENZENE		0 UG/L	5	.5	2019/09/27	21	36		2022/09	
34536	1,2-DICHLOROBENZENE		0 UG/L	600	.5	2019/09/27	21	36		2022/09	
34531	1,2-DICHLOROETHANE		0 UG/L	.5	.5	2019/09/27	21	36		2022/09	

LAST SAMPLE DATE AND MONITORING SCHEDULE

SYSTEM NO: 1010023			NAME: CITY OF ORANGE COVE				COUNTY: FRESNO				
SOURCE NO:			NAME: FRIANT KERN CANAL - RAW				CLASS: CLSA			STATUS: Active	
1010023 - S1 002	34541	1,2-DICHLOROPROPANE	0 UG/L	5	.5	2019/09/27	21	36	2022/09		
	34561	1,3-DICHLOROPROPENE (TOTAL)	0 UG/L	.5	.5	2019/09/27	21	36	2022/09		
	34571	1,4-DICHLOROBENZENE	0 UG/L	5	.5	2019/09/27	21	36	2022/09		
	34030	BENZENE	0 UG/L	1	.5	2019/09/27	21	36	2022/09		
	32102	CARBON TETRACHLORIDE	0 UG/L	.5	.5	2019/09/27	21	36	2022/09		
	77093	CIS-1,2-DICHLOROETHYLENE	0 UG/L	6	.5	2019/09/27	21	36	2022/09		
	34423	DICHLOROMETHANE	0 UG/L	5	.5	2019/09/27	21	36	2022/09		
	34371	ETHYL BENZENE	0 UG/L	300	.5	2019/09/27	21	36	2022/09		
	46491	METHYL-TERT-BUTYL-ETHER (MTBE)	0 UG/L	13	3	2019/09/27	19	36	2022/09		
	34301	MONOCHLOROBENZENE	0 UG/L	70	.5	2019/09/27	21	36	2022/09		
	77128	STYRENE	0 UG/L	100	.5	2019/09/27	21	36	2022/09		
	34475	TETRACHLOROETHYLENE	0 UG/L	5	.5	2019/09/27	21	36	2022/09		
	34010	TOLUENE	0 UG/L	150	.5	2019/09/27	21	36	2022/09		
	34546	TRANS-1,2-DICHLOROETHYLENE	0 UG/L	10	.5	2019/09/27	21	36	2022/09		
	39180	TRICHLOROETHYLENE	0 UG/L	5	.5	2019/09/27	21	36	2022/09		
	34488	TRICHLOROFLUOROMETHANE FREON 11	0 UG/L	150	5	2019/09/27	21	36	2022/09		
	81611	TRICHLOROTRIFLUOROETHANE (FREON 113)	0 UG/L	1200	10	2019/09/27	21	36	2022/09		
	39175	VINYL CHLORIDE	0 UG/L	.5	.5	2019/09/27	21	36	2022/09		
	81551	XYLENES (TOTAL)	0 UG/L	1750	0.5	2019/09/27	21	36	2022/09		
S2 REGULATED SOC											
	77443	1,2,3-TRICHLOROPROPANE (1,2,3-TCP)	<	ND UG/L	0.005	0.005	2019/03/13	4	36	M	2022/03
	39730	2,4-D		0 UG/L	70	10	2019/09/27	12	36		2022/09
	77825	ALACHLOR		0 UG/L	2	1	2019/09/27	11	36		2022/09
	39033	ATRAZINE		0 UG/L	1	.5	2019/09/27	12	36		2022/09
	38926	ENDOTHALL		0 UG/L	100	45	2019/09/27	10	36		2022/09
	39055	SIMAZINE		0 UG/L	4	1	2019/09/27	11	36		2022/09

LAST SAMPLE DATE AND MONITORING SCHEDULE

SYSTEM NO: 1010023

NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 900

NAME: ST2DBP - 633 SIXTH STREET

CLASS: DBPQ

STATUS: Active

PSCODE	GROUP/CONSTITUENT IDENTIFICATION	LAST RESULT	UNITS	MCL	DLR	LAST SAMPLE	COUNT	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
1010023 - 900	CITY OF ORANGE COVE	900	ST2DBP - 633 SIXTH STREET								
	D BP	DISINFECTION BYPRODUCTS									
	32101	BROMODICHLOROMET HANE (THM)	1.2	UG/L	-----	1	2019/09/27	22	3	2019/12	DUE NOW
	32104	BROMOFORM (THM)	0	UG/L	-----	1	2019/09/27	22	3	2019/12	DUE NOW
	32106	CHLOROFORM (THM)	29	UG/L	-----	1	2019/09/27	22	3	2019/12	DUE NOW
	82721	DIBROMOACETIC ACID (DBAA)	0	UG/L	-----	1	2019/09/27	22	3	2019/12	DUE NOW
	32105	DIBROMOCHLOROMET HANE (THM)	0	UG/L	-----	1	2019/09/27	22	3	2019/12	DUE NOW
	77288	DICHLOROACETIC ACID (DCAA)	12	UG/L	-----	1	2019/09/27	22	3	2019/12	DUE NOW
	A-049	HALOACETIC ACIDS (5) (HAA5)	23	UG/L	60	-----	2019/09/27	22	3	2019/12	DUE NOW
	A-041	MONOBROMOACETIC ACID (MBAA)	0	UG/L	-----	1	2019/09/27	22	3	2019/12	DUE NOW
	A-042	MONOCHLOROACETIC ACID (MCAA)	0	UG/L	-----	2	2019/09/27	22	3	2019/12	DUE NOW
	82080	TOTAL TRIHALOMETHANES	30	UG/L	80	-----	2019/09/27	22	3	2019/12	DUE NOW
	82723	TRICHLOROACETIC ACID (TCAA)	11	UG/L	-----	1	2019/09/27	22	3	2019/12	DUE NOW

LAST SAMPLE DATE AND MONITORING SCHEDULE

SYSTEM NO: 1010023

NAME: CITY OF ORANGE COVE

COUNTY: FRESNO

SOURCE NO: 901

NAME: ST2DBP - 1205 ADAMS

CLASS: DBPQ

STATUS: Active

PSCODE	GROUP / CONSTITUENT IDENTIFICATION	LAST RESULT	UNITS	MCL	DLR	LAST SAMPLE	COUNT	FREQ MON THS	MOD	NEXT SAMPLE DUE	NOTES
1010023 - 901	CITY OF ORANGE COVE	901	ST2DBP - 1205 ADAMS								
D BP	DISINFECTION BYPRODUCTS										
	32101 BROMODICHLOROMET HANE (THM)	1.3 UG/L	-----	1	2019/09/27	22	3			2019/12	DUE NOW
	32104 BROMOFORM (THM)	0 UG/L	-----	1	2019/09/27	22	3			2019/12	DUE NOW
	32106 CHLOROFORM (THM)	27 UG/L	-----	1	2019/09/27	22	3			2019/12	DUE NOW
	82721 DIBROMOACETIC ACID (DBAA)	0 UG/L	-----	1	2019/09/27	22	3			2019/12	DUE NOW
	32105 DIBROMOCHLOROMET HANE (THM)	0 UG/L	-----	1	2019/09/27	22	3			2019/12	DUE NOW
	77288 DICHLOROACETIC ACID (DCAA)	0 UG/L	-----	1	2019/09/27	22	3			2019/12	DUE NOW
	A-049 HALOACETIC ACIDS (5) (HAA5)	0 UG/L	60	-----	2019/09/27	22	3			2019/12	DUE NOW
	A-041 MONOBROMOACETIC ACID (MBAA)	0 UG/L	-----	1	2019/09/27	22	3			2019/12	DUE NOW
	A-042 MONOCHLOROACETIC ACID (MCAA)	0 UG/L	-----	2	2019/09/27	22	3			2019/12	DUE NOW
	82080 TOTAL TRIHALOMETHANES	28 UG/L	80	-----	2019/09/27	22	3			2019/12	DUE NOW
	82723 TRICHLOROACETIC ACID (TCAA)	0 UG/L	-----	1	2019/09/27	22	3			2019/12	DUE NOW

Appendix E

Bacteriological Distribution Monitoring Report

Bacteriological Distribution Monitoring Report

1010023 Orange Cove, City of

Distribution System Freq: 4/W

<i>Sample Date</i>	<i>Time</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>Type</i>	<i>Cl2</i>	<i>Violation</i>	<i>Comment</i>
1/31/2015		16 samples	A	A		Routine	0.95-1.1		
2/28/2015		16 samples	A	A		Routine	0.9-1.1		
3/31/2015		16 samples	A	A		Routine	0.9-1.14		
4/30/2015		20 samples	A	A		Routine	0.90-1.2		
5/31/2015		16 samples	A	A		Routine	1.0-1.2		
6/30/2015		16 samples	A	A		Routine	0.9-1.1		
7/31/2015		20 samples	A	A		Routine	0.9-1.2		
8/31/2015		16 samples	A	A		Routine	0.91-1.3		
9/30/2015		20 samples	A	A		Routine	0.7-1.2		
10/31/2015		16 samples	A	A		Routine	0.8-1.2		
11/30/2015		16 samples	A	A		Routine	1.0-1.5		
12/31/2015		20 samples	A	A		Routine	0.65-1.1		
1/31/2016		16 samples	A	A		Routine	0.85-1.0		
2/29/2016		16 samples	A	A		Routine	0.8-1.5		
3/31/2016		20 samples	A	A		Routine	0.90-1.20		
4/30/2016		16 samples	A	A		Routine	0.90-1.10		
5/31/2016		16 samples	A	A		Routine	1.00-1.10		
6/30/2016		20 samples	A	A		Routine	0.60-1.00		
7/31/2016		16 samples	A	A		Routine	0.10-1.0		
8/31/2016		16 samples	A	A		Routine	0.80-1.10		
9/30/2016		20 samples	A	A		Routine	0.90-1.20		
10/31/2016		16 samples	A	A		Routine	0.80-1.00		
11/30/2016		20 samples	A	A		Routine	0.8-1.10		
12/31/2016		16 samples	A	A		Routine	0.90-1.50		
1/31/2017		16 samples	A	A		Routine	0.80-1.2		
2/28/2017		16 Samples	A	A		Routine	0.9-1.3		
3/31/2017		16 samples	A	A		Routine	0.90-1.20		
4/30/2017		16 Samples	A	A		Routine	0.92-2.0		
5/31/2017		20 Samples	A	A		Routine	0.7-1.50		Missing 4 more samples
6/30/2017		16 samples	A	A		Routine	0.80-1.30		
7/30/2017		16 samples	A	A		Routine	0.90-1.30		
8/30/2017		20 Samples	A	A		Routine	0.8-1.37		
9/30/2017		16 Samples	A	A		Routine	0.9-1.2		
10/31/2017		16 Samples	A	A		Routine	0.8-1.4		
11/30/2017		20 Samples	A	A		Routine	0.81-1.2		
12/31/2017		16 Samples	A	A		Routine	0.80-1.0		
1/31/2018		20 Samples	A	A		Routine	0.8-1.2		
2/28/2018		16 Samples	A	A		Routine	0.8-1.10		
3/31/2018		16 Samples	A	A		Routine	1.03-1.40		
4/30/2018		16 Samples	A	A		Routine	0.90-1.2		
5/31/2018		16 Samples	A	A		Routine	0.7-1.0		
6/30/2018		20 Samples	A	A		Routine	0.80-1.0		
7/31/2018		16 Samples	A	A		Routine	0.80-1.10		
8/31/2018		20 Samples	A	A		Routine	0.80-1.2		
9/30/2018		16 Samples	A	A		Routine	0.9-1.3		
10/31/2018		16 Samples	A	A		Routine	0.9-1.3		
11/30/2018		16 Samples	A	A		Routine	0.90-1.28		
12/31/2018		16 Samples	A	A		Routine	0.9-1.80		
1/30/2019		20 Samples	A	A		Routine	0.9-1.3		
2/28/2019		16 Samples	A	A		Routine	0.8-1.1		
3/31/2019		16 Samples	A	A		Routine	0.80-1.2		

<i>Sample Date</i>	<i>Time</i>	<i>Location</i>	<i>T Coli</i>	<i>E Coli</i>	<i>F Coli</i>	<i>Type</i>	<i>CI2</i>	<i>Violation</i>	<i>Comment</i>
4/30/2019		16 Samples	A	A		Routine	0.70-1.30		
5/31/2019		16 Samples	A	A		Routine	0.7-1.3		
6/30/2019		16 Samples	A	A		Routine	0.90-1.2		
7/31/2019		16 Samples	A	A		Routine	1.00-1.10		
8/30/2019		16 Samples	A	A		Routine	1-1.10		
9/30/2019		16 Samples	A	A		Routine	0.80-1.1		
10/31/2019		20 Samples	A	A		Routine	0.9-1.2		
11/30/2019		16 Samples	A	A		Routine	1.0-1.2		

Violation Key

MCL	Exceeds the maximum contaminant level	MR5	Incorrect number of repeat samples as follow-up to a positive sample
MR1	No monthly sample for the report month	MR6	No source sample
MR2	No quarterly sample for the report month	MR7	No summary report submitted
MR3	Incorrect number of routine samples for the report month	MR8	Other comments and/or info
MR4	Did not collect 5 routine samples for previous month's positive sample	MR9	CI2 not reported

Appendix F

Lead and Copper Rule Tracking Report

Individual System Lead and Copper Rule Tracking Report

1010023 Orange Cove, City of Pop: Eng: CK Lead Action Level: 0.015 mg/L Copper Action Level: 1.3 mg/L

Sample Date Begin/(End)	Monitoring Period	Sample Set ID	Number Required	Number Sampled	Lead 90th % (mg/L)	Copper 90th % (mg/L)	Action Taken	Action Type	Next Due Date	Next Due Freq	Comments
(5/24/1993)	6M1ST-1993	1st 6	40	49	0.0	0.020					Collected 5/24-6/21/93
(6/27/1993)	YR1993	2nd 6	40	47	0.0	0.020					Collected 6/27-7/28/93
(12/22/1997)	YR1997	A1	20	20	0.009	0.0					A1 & A2 not collected in summer
(12/13/2000)	YR2000	A2	40	40	0.0246	0.027					Pb levels caused by inadeq pH adjmt
(6/22/2001)	6M1ST-2001		5	5	<0.005	<0.050					Listed as wells on analytical results
(9/6/2001)	6M2ND-2001	1st 6	17	17	<0.005	<0.050					40 reqd due to exceedance (initial monitoring)
(9/19/2001)	YR2001	1st 6	20	20	<0.005	<0.050			5/31/2002	2nd 6	Monitoring delinquent; 40 samples collected 5/03 awaiting results // akh 6/03
(5/28/2003)	6M1ST-2003	2nd 6	40	40	<0.005	0.055			9/30/2004	A1	Reduced monitoring in 2004 to 20 sample sites.// akh 7/30/03
(9/30/2004)	YR2004	A1	20	20	0.0025	0.025			9/30/2005	A2	Analytical results-still need Form 141 requested email 11/2/04; akh 11/2/04
(9/29/2005)	YR2005	A2	20	20	0.0025	0.051			5/31/2007	1st 6	akh 11/30/05// ah 4/07- Need 40- 1st 6 changed to zinc ortho in 2/07

Legend:

Cit: Citation
EL: Enforcement letter

1st 6: 1st initial 6-mo. round of monitoring
2nd 6: 2nd initial 6-mo. round of monitoring

A1: 1st Annual monitoring
A2: 2nd Annual monitoring

T1: 1st Triennial (3 yr) monitoring
T2: 2nd Triennial (3 yr) monitoring
T3: 3rd Triennial (3 yr) monitoring

1010023

Orange Cove, City of

Pop:

Eng: CK

Lead Action Level: 0.015 mg/L

Copper Action Level: 1.3 mg/L

Sample Date Begin/(End)	Monitoring Period	Sample Set ID	Number Required	Number Sampled	Lead 90th % (mg/L)	Copper 90th % (mg/L)	Action Taken	Action Type	Next Due Date	Next Due Freq	Comments
(3/29/2007)	6M1ST-2007	1st 6	40	40	0.007	0.53			9/30/2008	2nd 6	akh 12/11/07 Need form 141. ah 4/08: 40 sites in 2008 then reduce to 20 sites in 2009 as A1. Other FK users use Zn ortho successfully.
(10/29/2008)	6M2ND-2008	2nd 6	40	40	0.0025	0.086			9/30/2011	T1	entered by MRW 11/24/08. akh 2/8/10: next round June - Sept. 2011 - 20 sites.
8/26/2011 (8/26/2011)	3Y2009-2011	T1	20	20	0.0	0.14			9/30/2014	T2	entered by MRW 9-30-11.
(8/1/2014)	3Y2012-2014	T2	20	20	<0.005	0.074			9/30/2017	T3	
(9/21/2018)	3Y2016-2018	T3	20	20	<0.005	0.150			9/30/2021	T4	

Legend:

Cit: Citation

EL: Enforcement letter

1st 6: 1st initial 6-mo. round of monitoring

2nd 6: 2nd initial 6-mo. round of monitoring

A1: 1st Annual monitoring

A2: 2nd Annual monitoring

T1: 1st Triennial (3 yr) monitoring

T2: 2nd Triennial (3 yr) monitoring

T3: 3rd Triennial (3 yr) monitoring

12/31/2019

Appendix G

Emergency Notification Plan (ENP) Template



GAVIN NEWSOM
GOVERNOR



JARED BLUMENFELD
SECRETARY FOR
ENVIRONMENTAL PROTECTION

State Water Resources Control Board

Division of Drinking Water

WATER QUALITY EMERGENCY NOTIFICATION PLAN

Name of Utility: _____

Physical Location/Address: _____

The following persons have been designated to implement the plan upon notification by the Division of Drinking Water, SWRCB that an imminent danger to the health of the water users exists:

Water Utility: Contact Name & Title	Email Address	Day	Telephone Evening	Cell
1. _____				
2. _____				
3. _____				

The implementation of the plan will be carried out with the following DDW-SWRCB and County Health Department personnel:

DDW-SWRCB & County Health Departments:		Telephone	
Contact Name & Title		Day	Evening
1. José A. Robledo, Fresno District 23 Engineer, SWRCB-DDW		(559) 447-3396	(559) 731-1208
2. Tricia A. Wathen, Central CA Section Chief, SWRCB-DDW		(559) 447-3398	(559) 696-8506
3. Rick Heinrichs, Environmental Health Specialist-Supervisor Fresno County Health Department		(559) 600-3357	(559) 600-3357

If the above personnel cannot be reached, contact:

Office of Emergency Services Warning Center (24 hrs.) (800) 852-7550 or (916) 845-8911
When reporting a water quality emergency to the Warning Center, please ask for the State Water Resources Control Board – Division of Drinking Water Duty Officer.

NOTIFICATION PLAN

Attach a written description of the method or combination of methods to be used (radio, television, door-to-door, sound truck, etc.) to notify customers in an emergency. For each section of your plan give an estimate of the time required, necessary personnel, estimated coverage, etc. Consideration must be given to special organizations (such as schools), non-English speaking groups, and outlying water users. Ensure that the notification procedures you describe are practical and that you will be able to actually implement them in the event of an emergency. Examples of notification plans are attached for large, medium and small communities.

Report prepared by: _____

Signature and Title

Date

E. JOAQUIN ESQUIVEL, CHAIR | EILEEN SOBECK, EXECUTIVE DIRECTOR

265 West Bullard Avenue, Suite 101, Fresno, CA 93704 | www.waterboards.ca.gov

EXAMPLE PLAN I (Medium Community)

During regular working hours our people will contact the news media at television station KXYZ to broadcast the necessary warning. The local radio stations will also be contacted. The television and radio personnel are available at all hours. As a follow-up measure, we will also contact the Daily Bee, a local newspaper that serves both Ourtown and Hometown.

The warnings will be issued in both English and Spanish to cover all members of the community. Outlying areas of the water service area (such as Isolated Canyon and Lonesome Mountain subdivisions) will also be notified by sound truck and/or handbill distributed to their respective areas. Both of these areas are very small and this can be done quite quickly.

A special telephone answering service can also be quickly set up at the utility headquarters (using the regular company numbers) to answer questions that will come in from consumers. Questions are anticipated, especially from the Hometown area, because that area is served by three different water companies. A map will be available to the telephone answering personnel to determine the water company serving the caller.

It is anticipated that the time for notification to the television and radio audiences will be very short. The areas served by handbill and sound truck will also be notified within an hour. For notification to be issued in other than normal hours, the same media will be contacted and an announcement will be scheduled for as long as is necessary. A sound truck(s) will be used in the early morning hours to quickly alert the people not listening to their radio or television.

EXAMPLE PLAN II (Small Community)

Our community is very small and the most efficient means of notification will be both sound truck and handbill. It is estimated that the entire service area can be covered in less than three hours.

EXAMPLE PLAN III (Large Community)

The same plan as implemented in Plan I should be used here with the exceptions noted. All the news media will be contacted in the entire metropolitan area. This includes all television and radio stations and all local and general area newspapers. Maps have been prepared to be distributed to the media to locate the boundaries of the water company. This system is large enough that it may only be necessary to notify some of the water users. This information will be transmitted to the media and an answering service at the water company will respond to consumers' calls. Unless the problems are limited to isolated areas it is unreasonable to assume that contact can be made through sound truck or handbill.

Appendix H

Emergency Response Plan (ERP) Template

This EXAMPLE is for a small water system and represents the minimum information required. The information required for your plan will be based on the complexity of your water system.

Emergency/Disaster Response Plan

To continue minimum service levels and mitigate the public health risks from drinking water contamination that may occur during a disaster or other emergency events and in order to provide reliable water service and minimize public health risks from unsafe drinking water during those events, the _____ water system proposes the following plan that defines how it will respond to emergencies and/or disasters that are likely to affect its operation.

Disasters/emergencies that are likely to occur in the water system's service area that are addressed are: earthquake, major fire emergencies, water outages due to loss of power, localized flooding, water contamination, and acts of sabotage.

- 1) **DESIGNATED RESPONSIBLE PERSONNEL:** For designated responsible personnel and chain of command and identified responsibilities, see the attached "Emergency and Disaster Personnel and Responsibilities".
- 2) **INVENTORY OF RESOURCES:** An inventory of system resources that are used for normal operations and available for emergencies; includes maps and schematic diagrams of the water system, lists of emergency equipment, equipment suppliers, and emergency contract agreements that are kept at the water system office.
- 3) **EMERGENCY OPERATIONS CENTER:** The water system office has been designated as the communication network emergency operations center. Emergency contact information for equipment suppliers is attached. The telephone and FAX will be the primary mode of communication in an emergency. In addition, the local fire department and law enforcement have a radio and we have made arrangements to use it to contact police, fire and other emergency response personnel should telephone communication be lost.

Agency	Address, City	Phone #	FAX #
Water System			
Fire Department			
Law Enforcement			

- 4) **OTHER AGENCY COORDINATION:** Coordination procedures with governmental agencies for health and safety protection; technical, legal, and financial assistance, and public notification procedures are continually being developed and updated through regulation and experience and will be added as necessary to this plan. (See attached sheet.)
- 5) **RESPONSE PROCEDURES:** Personnel will, as quickly as possible, determine the status of other employees, assess damage to water system facilities, provide logistics for emergency repairs, monitor progress of repairs and restoration efforts, communicate with health officials and water users according to the "Emergency Notification Plan" on file with the regulatory agency (i.e., Department of Health Services (DHS) or Local Primacy Agency (LPA)), and document damage and repairs.
- 6) **RESUME NORMAL OPERATIONS:** The steps that will be taken to resume normal operations and to prepare and submit reports to appropriate agencies will include identifying the nature of the emergency (e.g., earthquake-causing water outage/leaks, fire or power outage causing water shortage/outage, sabotage resulting in facility destruction or water contamination).

a. Leaks or service interruption (Result of earthquake, etc.)

- i. Isolate leak. Turn power or flow off, if necessary, to control leak.
- ii. Repair or isolate break to allow service to the maximum system population possible. Disinfect as per attached AWWA Standards; increase system disinfectant residual as precaution, until normal service is resumed.
- iii. Do bacteriological sampling until 3 good consecutive samples are confirmed.
- iv. Reestablish normal service.

b. Low pressure (Result of earthquake, fire, storm)

- i. Increase production, if possible, to provide maximum system output.
- ii. Increase disinfectant residual as precaution to potential contamination.

c. Power outage

- i. Place emergency generator on line to provide minimum water pressure to system.
- ii. Increase disinfectant residual as precaution to potential contamination.

d. Contamination

- i. Identify location and source of contamination.
- ii. If contamination is from system source, isolate or treat source.
- iii. If contamination is an act of sabotage, take appropriate action based on nature of contamination. Immediately contact local law enforcement and your regulatory agency (DHS or LPA). Actions should be taken in consultation with the regulatory agency and could include shutting off water until all contaminants are identified.

e. Physical destruction of facility (sabotage)

- i. Immediately contact local law enforcement and regulatory agency for consultation.

All significant water outages (widespread and lasting more than eight hours) or disinfection failure will be reported to the Department of Health Services (DHS) District Office, or Local Primacy Agency (LPA) by telephone or equally rapid means. All emergencies will be documented along with action taken, and kept in the files of the water system office. Acts of sabotage will be reported to the local law enforcement agency.

Emergency and Disaster Personnel and Responsibilities

Name	Telephone No. (Work)	Role
Title	Telephone No. (Home)	
		Initial contact at office, in charge for all emergencies until replaced by Chairperson or Director
Secretary		
		In charge for all emergencies
Board Chairperson		
Board Member		
Board Member		
Board Member		
Treasurer		
		Emergency assistance and support
Operator		

Additional Mutual Assistance or Emergency Resources

Agency/Department	Telephone No. (Day) Telephone No. (After Hours)
Another Water Agency	
Fire Department	
Local Law Enforcement	
County Office of Emergency Services	
FBI Office (terrorism or sabotage) (Also notify local law enforcement.)	
DHS District Office	
Local Environmental Health Agency	

Water system contact information:

Name:

Address:

City, State, Zip code:

Phone:

FAX:

Emergency Contact Numbers and Operational Practices

A. List of equipment on hand for emergency repairs

1. **Example** (*Miscellaneous pipes and fittings, 2", 4", 6" & 8", approximately 100 count 20 of each.*)

2.

3.

B. List of sources of needed equipment, not on hand

1. (Sources for backhoe, jackhammer, technical support. Sources under contract.)

2. (Sources for electrical and pump repair.)

3. (Sources for emergency generators in case of prolonged power outages.)

4.

C. List of distributors or suppliers of replacement parts for the system

1. (Sources for PVC pipe, valves, and fittings.)

2. (Sources for pumps, pressure tank, and gauges.)

3.

D. List of emergency contact numbers:

	Name	Phone (Day)	Phone (After-hours)
DHS District Office			
Local Environmental Health Agency (LPA)			
Electrician			
Laboratory			
Electric & Pump (repair service)			
Chemical Disinfectant Supplier			
Other Water Agency (equipment support)			
Fire Department			
Law Enforcement			
County Office of Emergency Services			

Appendix N: Ken Schmidt Well Memos

KENNETH D. SCHMIDT AND ASSOCIATES

GROUNDWATER QUALITY CONSULTANTS

600 WEST SHAW AVE., SUITE 250

FRESNO, CALIFORNIA 93704

TELEPHONE (559) 224-4412

August 18, 2016

Mr. Harry Tow
Quad Knopf Inc.
901 East Main Street
Visalia, CA 93292

Re: E. Orosi CSD Test Well

Dear Harry:

During July 20-28, Johnson Drilling Co. of Reedley completed a casing hammer test well to a depth of 590 feet. We logged the drill cuttings and prepared a geologic log, which is attached. Alluvial deposits were encountered to a depth of 588 feet and hardrock was encountered below that depth. The deposits above a depth of 391 feet were primarily brown in color. Blue or gray-green deposits were present from 391 to 421 feet in depth. Gray or brown deposits were present from 421 to 453 feet in depth. Green deposits were predominant below a depth of 453 feet, except for a black sand from 568 to 572 feet in depth. Fine-grained layers that could function as confining beds below a depth of 180 feet were present in the following depth intervals:

181 to 255 feet	333 to 352 feet
265 to 281 feet	421 to 431 feet.

Depth to water ranged from 89 to 100 feet at the time of drilling. Water samples were collected from a total of 10 different depth intervals by airlifting. A submersible pump was installed at two of these intervals (255 to 260 feet and 394 to 400 feet in depth) to allow collection of pumped samples. The water samples were preserved and hand delivered to APPL, Inc. in Clovis for analyses of inorganic and trace organic constituents. Samples for radiological analyses were preserved and shipped to FGL Environmental in Santa Paula.

Total dissolved solids (TDS) concentrations ranged from 236 to 460 mg/l. The lowest TDS concentrations (less than 280 mg/l) were present between 255 and 357 feet and 453 and 496 feet in depth. Nitrate concentrations generally decreased with increasing depth, and were all less than the MCL of 45 mg/l. Nitrate concentrations in samples from below a depth of 255 feet were 15 mg/l or

KENNETH D. SCHMIDT AND ASSOCIATES
GROUNDWATER QUALITY CONSULTANTS


2

less. Iron and arsenic concentrations were well below the respective MCLs of 0.3 mg/l and 10 ppb. Manganese concentrations ranged from less than 0.01 to 0.21 mg/l. Concentrations exceeded the recommended MCL of 0.05 mg/l in samples from 173 to 179 feet, 394 to 458 feet, and for 572 to 577 feet in depth. Alpha activities in all of the samples were less than the MCL. DBCP, EDB, and 1,2,3-TCP concentrations were non-detectable in all of the samples.

A new well can be constructed at the site. I recommend not tapping strata below a depth of 570 feet and between 390 and 430 feet in depth. Blank casing would be installed from the surface to 255 feet, from 390 to 430 feet, and from 570 to 590 feet in depth. Louvered casing would be installed from 255 to 390 feet and 430 to 570 feet in depth. Gravel would be placed from 590 feet up to a depth of 230 feet. A gravel feed tube would be installed from 235 feet in depth to the surface. An annular seal would then be placed from 230 feet to the surface. Sieve analyses of fine sands by Roscoe Moss Co. indicate that a slot size of 0.06 inch and gravel gradation of 8x16 should be used. Such a well would tap about 140 feet of coarse-grained water producing deposits. A properly constructed and developed well should produce about 1,200 to 1,400 gpm.

Please call me if you have any questions.

Sincerely yours,


Kenneth D. Schmidt

KDS/cl

GEOLOGIC LOG FOR EAST OROSI CSD TEST WELL

Depth (feet)	Description
0 - 6	Red-brown sandy silt
6 - 12	Red-brown fine to medium sand
12 - 32	Red-brown sandy clay
32 - 41	Red-brown silty fine sand
41 - 85	Brown silt
85 - 91	Brown silty clay
91 - 101	Brown clay
101 - 138	Red-brown sandy clay
138 - 150	Brown decomposed clayey coarse sand
150 - 158	White and brown clayey decomposed rock
158 - 169	Brown and white clay
169 - 174	Brown clay
174 - 181	Brown clayey medium to coarse sand and gravel
181 - 210	Light brown clay
210 - 255	Brown clayey silt
255 - 257	Brown cemented fine to medium sand
257 - 265	Brown fine to medium sand
265 - 281	Pink dry clay
281 - 292	Pink clay and brown fine to medium sand
292 - 296	Brown cemented fine to medium sand
296 - 301	Brown fine to medium sand
301 - 312	Light brown sandy clay
312 - 318	Brown fine sand
318 - 322	Gray-brown sandy clay
322 - 333	Gray-brown clayey fine sand
333 - 352	Gray and pink dry clay
352 - 361	Brown medium sand
361 - 375	Brown fine to medium sand with clay
375 - 381	Brown clayey medium to coarse sand
381 - 389	Brown clayey coarse sand
389 - 391	Light brown clay
391 - 393	Blue-green clay
393 - 411	Blue-green very fine to fine sand
411 - 419	Gray-green clay
419 - 421	Gray-green silty indurated clay
421 - 429	Gray sandy clay
429 - 431	Light brown clay

Continued:

GEOLOGIC LOG FOR EAST OROSI CSD TEST WELL
(Continued:)

<u>Depth (feet)</u>	<u>Description</u>
431 - 435	White coarse sand
435 - 438	Light brown clay
438 - 445	Brown-green medium to coarse sand
445 - 453	Light brown clay
453 - 468	Brown-green fine to medium sand
468 - 471	Green cemented fine to medium sand
471 - 475	Green medium to coarse sand
475 - 491	Green clayey medium to coarse sand
491 - 511	Brown silty fine sand
511 - 512	Pink and light brown clay
512 - 513	Green clay
513 - 521	Green fine to medium sand
521 - 529	Green clay
529 - 533	Green fine to medium sand
533 - 539	Green clay
539 - 568	Green fine to medium sand
568 - 572	Black cemented fine to medium sand
572 - 588	Green clayey medium to coarse sand
588 - 590	Hard rock

EAST OROSI CSD TEST WELL - WATER QUALITY TABLE

Depth Interval (feet)	Fe (mg/l)	Mn (mg/l)	As (ppb)	NO ₃ (mg/l)	EC umhos/cm	TDS (mg/l)	pH	DBCP (ppb)	EDB (ppb)	1,2,3 TCP (ppt)	Perchlorate (ug/l)	Gross Alpha (pci/l)	SWL (ft)
138-141 A	<0.03	0.031	1.3	41	533	367	8.0	<0.01	<0.01	< 5	1.4	2.1	
173-179 A	<0.03	0.056	1.5	36	506	352	8.1	<0.01	<0.01	< 5	1	2.7	
255-260 A	<0.03	0.062	1.4	15	325	236	8.1	<0.01	<0.01	< 5	1.5	0.4	
255-260 P	<0.03	0.009	1.9	14	330	238	7.6	<0.01	<0.01	< 5	1.7	0.0	89.3
295-300 A	<0.03	0.021	1.4	15	355	243	8.1	0.01	<0.01	< 5	2.2	1.3	
352-357 A	<0.03	0.032	1.2	7	416	279	8.1	<0.01	<0.01	< 5	0.8	1.0	
394-400 A	<0.03	0.138	1.8	1	596	348	8.2	<0.01	<0.01	< 5	<1	0.8	
394-400 P	<0.03	0.211	2.4	<0.5	605	346	7.6	<0.01	<0.01	< 5	<1	1.1	110.3
453-458 A	<0.03	0.057	1.3	7	411	276	8.1	<0.01	<0.01	< 5	<1	0.0	
491-496 A	0.03	0.023	1.8	8	382	260	8.1	<0.01	<0.01	< 5	<1	0.2	
529-534 A	<0.03	0.041	1.7	8	496	326	8.1	<0.01	<0.01	< 5	<1	0.7	
572-577 A	<0.03	0.066	1.2	6	704	460	8	<0.01	<0.01	< 5	<1	0.5	

GROUNDWATER CONDITIONS IN THE MONSON AREA

Draft Report-For Review Purposes Only

prepared for
Provost & Pritchard Consulting Group
Fresno, California

by
Kenneth D. Schmidt & Associates
Groundwater Quality Consultants
Fresno, California

January 30, 2015

January 30, 2015

Mr. Brian Shoener
Provost & Pritchard Consulting Group
286 W. Cromwell
Fresno, CA 93711

Re: Monson Groundwater Evaluation

Dear Brian:

Submitted herewith is our draft report on groundwater conditions in the Monson area. We appreciate the information provided by Self Help Enterprises.

Sincerely yours,

Kenneth D. Schmidt
Geologist No. 1578
Certified Hydrogeologist
No. 176

KDS/td

TABLE OF CONTENTS

	<u>Page</u>
LIST OF ILLUSTRATIONS	ii
INTRODUCTION	1
SUBSURFACE GEOLOGIC CONDITIONS	1
WATER SUPPLY WELLS	4
WATER LEVELS	5
WELL PRODUCTION	5
GROUNDWATER QUALITY	6
Vertical Trends	8
RECOMMENDATIONS	8
REFERENCES	9
APPENDIX A RESULTS OF PRIVATE WELL SAMPLING	

LIST OF ILLUSTRATIONS

<u>No.</u>	<u>Title</u>	<u>Page</u>
1	Location of Deep Holes and Wells in the Monson Area	3

GROUNDWATER CONDITIONS IN THE MONSON AREA

INTRODUCTION

High nitrate concentrations are present in shallow groundwater in the Monson area, a condition that is common in the Dinuba Sultana, Orosi, Cutler, and Sequoia Field areas. Self Help Enterprises has conducted sampling programs for private individual wells at and near Monson. Provost & Pritchard is conducting an evaluation of developing a community water system to serve Monson. This evaluation is intended to provide information on groundwater conditions so that one or more public supply wells producing groundwater without treatment can be developed. Subsurface geologic conditions are discussed first, followed by a discussion of water supply wells and depths. Water levels and well production are then discussed, and then groundwater quality. Lastly, recommendations are provided on the location, depth, and method of construction of a test well in Monson.

SUBSURFACE GEOLOGIC CONDITIONS

The Monson area is located in an interfan area between the Kings and Kaweah Rivers and is thus underlain by primarily fine-grained deposits, particularly below a depth of about 300 feet.

Sand Creek flows through the area just east of Monson, and Cottonwood Creek flows through the area south of Monson. Drillers logs and completion reports for water wells were obtained from the California Department of Water Resources, San Joaquin District. The deepest water wells with records in the Monson area are about 350 to 420 feet deep. In order to evaluate deeper subsurface conditions, lithologic logs and electric logs for deep holes were obtained from the California Division Oil, Gas, and Geothermal Resources website.

Figure 1 shows the location of these deep holes and wells. Three important issues are 1) the depth to the top of the hard-rock, 2) the depth to the top of the reduced (blue-green) deposits, and 3) whether or not salty groundwater is present at depth. Experience in the area is that groundwater in the reduced deposits at depth may be of unusable quality for public supply without treatment. At Hole T16S/R24E-21H, the base of the alluvial deposits was 492 feet deep, and about 40 feet of sands were indicated between 435 and 470 feet in depth. Information on salty groundwater wasn't available. At Hole T16S/R24E-26P, the top of the hardrock was 994 feet deep, and information on salty groundwater was not available. A permeable sand and gravel layer was indicated from 379 to 417 feet in depth. Hole 33H was drilled to a depth of 1,160 feet and salty groundwater




FIGURE 1-LOCATION OF WELLS AND TEST HOLES WITH LOGS

was not indicated. Deposits about a depth of 623 feet were oxidized (not reduced). About 50 feet of sand were indicated between 350 and 775 feet in depth. At Hole 28F, the blue-green deposits were below a depth of 648 feet and the top of the hardrock was 900 feet deep. About 72 feet of sands were indicated between 420 and 630 feet in depth. At Hole 1L, the top of the hardrock was 1,294 feet in depth, and information on salty water wasn't available.

In summary, depth to the top of the hardrock increase to the south in the area, from about 1,000 feet deep near Avenue 392 to 1,250 feet deep near Avenue 380. The top of the blue-green deposits apparently averages about 600 to 650 feet in depth in the vicinity. Salty groundwater wasn't indicated to be present at depth. The most favorable subsurface conditions to develop a public supply well are as far south as is feasible, where the top of the hardrock is deeper.

WATER SUPPLY WELLS

Drillers logs are available for three supply wells in the Monson area that range in depth from 400 to 420 feet, and none encountered the hardrock (Figure 1). The great majority of irrigation wells with logs are less than 300 feet deep. Most domestic wells with logs are less than 200 feet deep. However, two do-

mestic wells were apparently constructed in 2014 to a depth of about 300 feet and produced low nitrate groundwater (discussed later).

WATER LEVELS

Water-level records were obtained from the California Department of Water Resources, San Joaquin District. Long-term records are available for four wells in the Monson area. Water levels in well have been shallow, commonly less than about 30 feet deep. On the long-term, water levels have been stable.

WELL PRODUCTION

Yields of about 1,000 gpm have been reported for some irrigation wells in the Monson area that have perforations or are open extending up to above a depth of about 150 feet. Overall, the shallow strata are more productive than deeper strata. Reported yields of a number of wells that are only perforated below about 190 feet in depth have usually ranged from about 100 to 300 gpm. No information is available on the yields of wells only open or perforated below a depth of about 300 feet. However, yields can be estimated from interpretation of the logs for several deep holes.

GROUNDWATER QUALITY

During May-July 2008, Self Help Enterprises collected water samples from 13 private domestic wells in Monson. Completion reports are only available for only three of these wells. Based on the high nitrate concentrations and other information, all of the sampled wells probably tapped strata above a depth of about 200 feet. Nitrate concentrations in the sampled wells ranged from 46 to 130 mg/l, and all exceeded the maximum contaminant level (MCL) of 45 mg/l. Except for two wells, nitrate concentrations exceeded 75 mg/l. DBCP was detected at concentrations ranging from 0.01 to 0.13 ppb, below the MCL of 0.2 ppb, in water from four of these wells. During 2012-13, Self Help Enterprises collected water samples from 42 private domestic wells in and near Monson. Drillers logs are available for only eight of these wells. All of the sampled wells with records were about 200 feet deep or shallower. Nitrate concentrations in water from these wells ranged from less than 1 to 250 mg/l. Except for one well (No. 28), nitrate concentrations were 130 mg/l or less. The average nitrate concentration in water from the sampled wells in 2012-13 was 64 mg/l, and about 60 percent of the sampled wells had nitrate concentrations exceeding the MCL. Three of the sampled wells (No. 16, 24, and 31) had nitrate concentrations less than 9 mg/l. Wells No. 16 and 24 were located

north of Avenue 388, and No. 31 was located on Simpson Drive. Information on the construction of these wells isn't available.

The source of the high nitrate in the area has not been determined. Nitrogen fertilizers are indicated to be the primary sources in the regional area. However, septic tank effluent is a likely source in Monsoon, and concentrations up to 130 mg/l could be from septic tank effluent. The higher concentration in water from Well No. 28 is likely at least partly associated with nitrogen fertilizer use in the area. Two domestic wells along Monson Drive (Sites 5 and 40) were constructed to a depth of about 300 feet and were sampled in November 2014. Water from these wells had nitrate concentrations ranging from 12 to 13 mg/l. This indicates a trend of lower nitrate concentrations in the deeper groundwater, which is expected. DBCP was not detected in water from either of these wells. 1, 2, 3-TCP was detected at 15 part per trillion (ppt) in water from one of these wells, which is higher than the expected MCL to be developed (5 to 10 ppt). Results of the private well sampling are provided in Appendix A.

Water from the Monson Market well was frequently sampled during 2003-13. The overall trend was increasing nitrate concentrations, from about 55 mg/l in early 2003 to about 80 mg/l

in 2013. Part of this increase may be due to water-level declines during the drought, which results in shallower groundwater (nearer the water level) being pumped from wells.

Groundwater in the deeper reduced deposits may contain high concentrations of arsenic, manganese, iron, and hydrogen sulfide. This needs to be determined by doing a test well (described later).

Vertical Trends

There is a trend in both the local and regional areas that indicates higher nitrate concentrations in the shallow groundwater (above a depth of about 250 feet) and low nitrate concentrations in the deeper groundwater. This has been demonstrated at two lots in Monson (Sites 5 and 40). Nitrate concentrations in water from many shallow wells ranged from 50 to 100 mg/l, whereas for they ranged from only 12 to 13 mg/l in water from the deeper wells (about 300 feet deep). A similar trend is present in Dinuba, Sultana, East Orosi, Orosi, Cutler, and farther south in the Sequoia Field area.

RECOMMENDATIONS

In order to develop one or more public supply wells, the amount and quality of groundwater below a depth of about 300

feet needs to be determined from a test well. Subsurface geologic conditions are indicated to be likely better near the south edge of Monson than elsewhere in Monson. The casing hammer method should be used to drill a test well into the reduced deposits, the top of which is expected to be about 650 feet deep. An 8-inch diameter casing would initially be driven as far as possible, and below that a 6-inch diameter casing would be driven to a total depth of about 900 feet. The most important constituents in the shallow groundwater are indicated to be nitrate, DBCP, and 1, 2, 3-TCP. The most important constituents in the deeper groundwater are likely manganese, arsenic, and possibly iron. Based on the thickness of sands and gravels that have been encountered below a depth of 350 feet at deep holes in the Monson area, well yields of about 400 to 600 gpm may be possible.

REFERENCES

APPENDIX A
RESULTS OF PRIVATE WELL SAMPLING

Monson
Well Water Sampling Results
2012-2013


Site	Samples	Sampling Date	Nitrate PPM	Bacteria P/A
Site 1	1	11/27/2012	85	A
Site 2	2	11/15/2012	39	A
Site 3	3	11/15/2012	100	A
Site 4	4	11/15/2012	56	A
Site 5	5	11/15/2012	50	A
Site 6	6	11/15/2012	110	P
Site 7	7	3/6/2013	100	A
Site 8	8	3/7/2013	81	P
Site 9	9	12/17/2012	37	A
Site 10	10	12/17/2012	100	A
Site 11	11	12/17/2013	92	A
Site 12	12	3/5/2013	66	A
Site 13	13	3/25/2013	120	A
Site 14	14	3/5/2013	34	P
Site 15	15	3/6/2013	41	A
Site 16	16	3/7/2013	8.6	P
Site 17	17	12/17/2012	74	A
Site 18	18	5/1/2013	32	P
Site 19	19	5/1/2013	18	A

Monson
Well Water Sampling Results
2012-2013

Site	Samples	Sampling Date	Nitrate PPM	Bacteria P/A
Site 20	20	5/1/2013	69	A
Site 21	21	3/6/2013	42	A
Site 22	22	5/30/2013	33	A
Site 23	23	5/1/2013	18	A
Site 24	24	3/7/2013	8.6	A
Site 25	25	3/13/2013	67	A
Site 26	26	3/13/2013	67	A
Site 27	27	5/30/2013	33	A
Site 28	28	6/29/2013	250	P
Site 29	29	6/29/2013	63	A
Site 30	30	12/17/2012	130	A
Site 31	31	5/1/2013	0	A
Site 32	32	3/13/2013	81	P
Site 33	33	12/17/2012	43	P
Site 36	34	5/1/2013	14	A
Site 39	35	5/30/2013	80	P
Site 40	36	4/14/2013	100	P
Site 41	37	3/25/2013	18	A
Site 42	38	3/28/2013	71	A

Monson Well Water Sampling Results 2012-2013				
Site	Samples	Sampling Date	Nitrate PPM	Bacteria P/A
		Max	250	N/A
		Min	0	N/A
		Average	64	N/A
		# over MCL	22	10
		% over MCL	58%	26%

: BSK Test Results received



TULARE COUNTY
Monson Water System Feasibility
Project Site

Legend

☐ Parcel (Tulare Co. Assessor)

0 200 400 600 Feet

PROVOST & PRITCHARD
EST. 1988
CONSULTING GROUP
An Employee Owned Company

130 N. Garden Street
Visalia, CA 93291
(559) 636-1166

9/11/2014 : G:\Clients\Tulare County - 1399\13991402-P&E for Monson Community\GIS\Map\site.mxd

MONSON DRINKING WATER WELL SAMPLING, JULY 31 2008

NAME	ADDRESS	PHONE	NO3	DBCP	BACT	PC to rept
1 Clarence & Carol Harms	10524 Ave 388	591-4208	120 ppm	ND	Absent	ok
2 Joel Sanpedro	10507 Ave 388	595-1324	130 ppm	ND	Present*	ok
3 Andrea Gonzalez (Martin)	38668 Monson Dr	595-0912	60 ppm	ND	Absent	na
4 Salvador & Martha Gomez	38660 Monson Dr	591-2332	76 ppm	18 ppt	Present*	ok
5 Modesto Macias	38686 Monson Dr	595-9211	46 ppm	ND	Absent	ok
6 Tony Torres (Lisa)	38734 Monson Dr	591-2491	86 ppm	79 ppt	Absent	na
7 Jorge Luis Colunga (Viadis)	38758 Monson Dr	591-6197	130 ppm	ND	Absent	ok
8 Francisco Javier Salas	38780 Monson Dr	307-6623	120 ppm	14 ppt	Absent	na, lm
9 Ignacio Avila (Christian)	38737 Campbell Dr	595-1753	86 ppm	ND	Absent	ok
10 Terra Pelham	38745 Campbell	397-5946	95 ppm	ND	Absent	na, lm
11 Laura Saldana Garcia (Jose Luis)	38771 Campbell	591-1623	92 ppm	ND	Absent	ok
12 Archuleta Salvador	38785 Campbell Dr	591-7249	96 ppm	130 ppt	Absent	ok
13 Benjamin & Lala Luengas	38795 Campbell	591-4138	120 ppm	ND	Absent	ok

KEY:

NO3 = Nitrate

DBCP = Dibromochloropropane

BACT = Bacteria, by Total Coliform

ND = Non-detect

MCL = Maximum Contaminant Level

ppm = parts per million

ppt = parts per trillion

MCL:

NO3: 45 ppm
DBCP 200 ppt
BACT 0


average:

105 ppm over 12 wells

Sample results in blue were taken 5/16/2008

*While two wells tested in this program came up positive for total coliform bacteria, none were positive for E-coli.

Monson Drinking Water Well Samplings, July 31 2008



KENNETH D. SCHMIDT AND ASSOCIATES

GROUNDWATER QUALITY CONSULTANTS

600 WEST SHAW AVE., SUITE 250

FRESNO, CALIFORNIA 93704

TELEPHONE (559) 224-4412

July 12, 2016

Mr. Brian Shoener
Provost & Pritchard
286 Cromwell
Fresno, CA 93711

Re: Sultana CSD

Following is my updated draft report on groundwater conditions in the Sultana vicinity. In November 1995, I prepared a report on groundwater conditions in the Sultana area. At that time, the District had two active wells (No. 1 and No. 2) that were about 330 feet deep. High nitrate and DBCP concentrations have been common in the shallow groundwater in the Dinuba-Sultana area. Both Wells No. 1 and 2 have relatively shallow perforations and thus tapped such shallow groundwater. Pursuant to that evaluation, a test well was done near where Well No. 3 was later constructed. The top of the hardrock is relatively shallow in the Sultana area. My previous evaluation indicated that the top of the hardrock is deeper to the southeast near Sultana. The test well was completed near Well No. 3 to a depth of 500 feet in March 1996. Although the top of the hardrock wasn't reached, a clay strata was encountered from 460 to 480 feet in depth and the weathered rock (underlying the alluvial deposits) was encountered from 480 to 500 feet in depth. A significant confining bed was indicated between 235 and 268 feet in depth. This same confining bed is indicated to be present from about 215 to 266 feet in depth at CSD Well No. 1. However, perforated casing was placed above this confining bed in both Wells No. 1 and 2. DBCP concentrations, ranging from 0.26 to 0.92 ppb, exceeding the MCL of 0.2 ppb, were present above this confining bed at the test well, as were elevated concentrations of nitrate (26 to 38 mg/l). Well No. 3 was subsequently completed in October 1996. Perforated casing was placed from 260 to 420 feet in depth, and an annular seal was placed from a depth of 250 feet to the surface. A pump test on October 9-10, 1996 indicated a pumping rate of 485 gpm with a drawdown of 128 feet, or a specific capacity of 4 gpm per foot. More recent tests have indicated pumping rates ranging from about 455 to 625 gpm. Specific capacities for this well have reportedly ranged from about 7 to

KENNETH D. SCHMIDT AND ASSOCIATES

GROUNDWATER QUALITY CONSULTANTS

2

10 gpm per foot in recent years. However, these values were apparently based on 5-minute recovery measurements for the static water levels, as opposed to true static levels.

Comprehensive chemical analyses are available for water from Well No. 3 in recent years. Nitrate concentrations have ranged from 10 to 12 mg/l, well below the MCL of 45 mg/l. Arsenic concentrations have been less than 2 ppb, below the MCL of 10 ppb. Iron and manganese concentrations have also been below the recommended MCLs. DBCP concentrations ranged from 0.02 to 0.04 ppb, less than the MCL of 0.2 ppb. The 1,2,3-TCP concentration was determined once, and was less than 0.5 parts per trillion. Although a MCL for 1,2,3-TCP hasn't been developed, it is likely to not be less than 5 ppt.

The driller's reports that we obtained for other wells near Sultana doesn't indicate any other wells tapping alluvial deposits as deep as those tapped by Well No. 3. A suitable location for a new well appears to be somewhere south of Avenue 416 and east of Road 108.

Please call me if you have any questions.

Sincerely Yours,


Kenneth D. Schmidt

ATTACHMENT

GROUNDWATER CONDITIONS REPORT, SULTANA AREA
NOVEMBER 1995

KENNETH D. SCHMIDT AND ASSOCIATES

GROUNDWATER QUALITY CONSULTANTS

1540 EAST MARYLAND, SUITE 100

PHOENIX, ARIZONA 85014

602-279-7033

November 3, 1995

Mr. Richard Ayers, President
Sultana Community Services District
P.O. Box 158
Sultana, CA 93666

Re: New Well

Dear Richard:

Following is my report on groundwater conditions in the Sultana area. Information on the District wells and subsurface geologic conditions in the vicinity is first discussed. Possible sampling of other wells and the potential for developing groundwater with an acceptable DBCP concentration are then discussed. Lastly, recommendations are provided on preferable locations and the estimated depth for a test well.

District Wells

Water Well Drillers Reports indicate that Well No. 1 was drilled in March 1978 to a depth of 358 feet. Casing was installed to a depth of 332 feet, and was perforated from 168 to 322 feet in depth. A 60-foot annular seal was installed from the land surface. Opposite the depth interval perforated in Well No. 1, there was a total of about 50 feet of coarse-grained, water-producing strata. A relatively thick clay layer was reported from 219 to 266 feet in depth at Well No. 1. About 30 feet of coarse-grained water-producing strata were tapped by the well below this clay layer. The well did not encounter bedrock, according to the Water Well Drillers Report.

Well No. 2 was drilled in May 1982 to a depth of 341 feet. Casing was installed to a depth of 340 feet, and was perforated from 150 to 330 feet in depth. A 150-foot conductor and annular seal were installed in this well. In the interval perforated, there was a total of about 65 feet of coarse-grained, water-producing strata. A relatively thick clay layer was reported from 259 to 302 feet in depth. Less than ten feet of coarse-grained water-producing strata below this clay layer were tapped by the

KENNETH D. SCHMIDT AND ASSOCIATES
GROUNDWATER QUALITY CONSULTANTS

2

well. Well No. 2 also did not encounter bedrock, according to the Water Well Drillers Report.

Subsurface Geologic Conditions

Water Well Drillers Reports were obtained for wells in Sections 10, 11, 14, and 15 in T16S/R24E from the California Department of Water Resources in Fresno. Besides the CSD wells, reports were available for eight other alluvial wells about 260 feet deep or deeper. These other wells were all shallower than the CSD wells. Numerous wells near Smith Mountain and "D" Mountain have encountered bedrock. However, none of the wells farther southeast, near Sultana, reportedly encountered bedrock. The area of deepest wells for which records are available includes the south half of Section 11, all of Section 14, and the north half of Section 15. The deepest bedrock in the Sultana CSD is most likely to the southeast, based on existing information.

Possible Water Sampling

The only well for which a Water Well Drillers Report is available that is recommended for sampling is a well at the BASF facility, about one quarter mile west of Road 104. This well is reportedly screened from 183 to 225 feet in depth, and thus has the deepest top of perforations of any of the wells for which records are available. I am in the process of obtaining information on past sampling from them. If no DBCP results are available, we will request to sample the well and do so shortly.

DBCP Concentrations

The highest DBCP concentrations for the CSD wells are usually in the range of 0.5 to 0.7 ppb, compared to the MCL of 0.2 ppb. Experience indicates that prolonged pumping (beyond a few weeks) of each well results in higher DBCP concentrations. Lower, and sometimes non-detectable, DBCP concentrations are usually obtained after long non-operational periods. The existing information indicates that DBCP concentrations are highest in the shallow groundwater. Assuming that the annular seal in Well No. 2 is effective, DBCP concentrations likely exceed the MCL in groundwater below a depth of 150 feet. The thick clay layers (i.e., 219 to 266 feet at Well No. 1) may preclude deeper movement of DBCP to the underlying water-producing strata. The deeper groundwater is likely of suitable quality for public supply.

KENNETH D. SCHMIDT AND ASSOCIATES
GROUNDWATER QUALITY CONSULTANTS

3

Recommendations

My recommendation is to look for well sites either northwest or southeast of Well No. 1, along the 8-inch diameter pipeline. A spacing of at least 500 feet from Well No. 1 is advisable. Also, the locations of nearby irrigation and other large capacity wells should be considered. The new well should be spaced at least 500 feet from these wells also, if possible. Since bedrock has not been reported to a depth of at least 358 feet in the area, I recommend drilling the test well to a depth of 600 feet deep, or to the top of bedrock, whichever is shallower.

I will be providing some additional information after the results of pump tests and the BASF well analyses are obtained, if possible.

Sincerely yours,

A handwritten signature in cursive script, appearing to read "Ken Schmidt".

Kenneth D. Schmidt

KDS/pt

KENNETH D. SCHMIDT AND ASSOCIATES

GROUNDWATER QUALITY CONSULTANTS

600 WEST SHAW, SUITE 250

FRESNO, CALIFORNIA 93704

TELEPHONE (559) 224-4412

May 22, 2013


Mr. Matt Kemp
Provost & Pritchard
286 W. Cromwell
Fresno, CA 93711



Re: Yettem-Seville Area

Dear Matt:

Submitted herewith is our report on groundwater conditions in the Yettem-Seville area.

Sincerely yours,


Kenneth D. Schmidt
Geologist No. 1578
Certified Hydrogeologist
No. 176



HYDROGEOLOGIC CONDITIONS IN
THE YETTEM-SEVILLE AREA

prepared for
Provost and Pritchard
Fresno, California

by
Kenneth D. Schmidt and Associates
Groundwater Quality Consultants
Fresno, California

May 2013

TABLE OF CONTENTS

	<u>Page</u>
LIST OF ILLUSTRATIONS	ii
INTRODUCTION	1
SUBSURFACE GEOLOGIC CONDITIONS	3
WATER LEVELS	8
WELL PRODUCTION	11
GROUNDWATER QUALITY	11
SUMMARY	14
REFERENCES	15
APPENDIX A WATER-LEVEL HYDROGRAPHS	

LIST OF ILLUSTRATIONS

<u>No.</u>	<u>Title</u>	<u>Page</u>
1	Thickness of Alluvial Deposits	2
2	Location of Subsurface Geologic Cross Sections	4
3	Subsurface Geologic Cross Section A-A'	5
4	Subsurface Geologic Cross Section B-B'	7
5	Subsurface Geologic Cross Section C-C'	9
6	Water-Level Elevations and Direction of Groundwater Flow (April 2009)	10
7	Nitrate Concentrations in Shallow Groundwater (1986-89)	13

DRAFT

HYDROGEOLOGIC CONDITIONS IN
THE YETTEM-SEVILLE AREA

INTRODUCTION

Croft and Gordon (1968) described groundwater conditions in the Hanford-Visalia area, which includes Yettem and Seville. The Yettem-Seville area is near the east edge of the valley. Hard-rock outcrops are present north of Seville, and the alluvial deposits are relatively thin in the Yettem-Seville area. The alluvial deposits are underlain by weathered rock and hardrock. Based on well completion reports, a map of the thickness of alluvial deposits was prepared (Figure 1). Logs for some test holes drilled by the mud rotary method cannot be used to clearly determine the depth of the base of the alluvium. Thus more weight was given to logs for wells drilled by other methods, where such a delineation was more evident. The alluvial deposits in the Yettem-Seville area range from less than about 100 feet thick near the Santa Fe Railroad Tracks to more than 500 feet thick southwest of Yettem. Thus these deposits thicken to the southwest. Because of the much thicker alluvium at and near Yettem compared to Seville, the focus of this report is on the Yettem area. The Yettem-Seville area is in what is termed an interfan area, between major streams. The interfan area is underlain predominantly by clay in the alluvial deposits, particularly below a depth of about 200 feet. The largest stream that

probably passed through the south part of the Yettem area in the geologic past was Cottonwood Creek.

SUBSURFACE GEOLOGIC CONDITIONS

As part of this evaluation, three subsurface geologic cross sections were developed (Figure 2). On each cross section, the major water-producing strata are shown. Cross section A-A' extends from the northwest to the southeast, through Yettem Well No. 1. Cross Section B-B' extends from the south to the north and northeast, and passes through Yettem Wells No. 1 and 2 and the Yettem School test hole. Four holes or wells along this section have electric logs, which help delineate subsurface conditions in more detail. Cross Section C-C' extends from the northwest through the Yettem School test hole to the southeast.

Cross Section A-A' (Figure 3) extends from west of Road 136 and south of Avenue 388 on the northwest to near Road 148 and north of Avenue 376 on the southeast. This cross section generally trends perpendicular to the inferred southwesterly dip of the alluvial deposits. Clay and other fine-grained deposits are predominant along the section. The five most southeasterly wells along this section encountered weathered rock. The base of the alluvial deposits was about 360 feet deep at Well 2N, 405 feet deep at Well 3J, 430 deep at 3K, 380 feet deep at Well 3L, and




FIGURE 2 - LOCATION OF SUBSURFACE GEOLOGIC CROSS SECTIONS




FIGURE 3 - SUBSURFACE GEOLOGIC CROSS SECTION A - A'

410 feet deep at Well 3F. The most extensive sands are within the uppermost 200 feet of the deposits, which are considered to be the Quaternary older alluvium of Croft and Gordon (1968). Sands in these deposits are thickest along the central part of the section (at Well 4A and Yettem Well No. 1). The underlying deposits below a depth of about 200 feet are termed the Tertiary-Quaternary continental deposits, and are more fine-grained than the overlying deposits. The thickest sands below a depth of about 270 feet were found along the northwest part of the section at Well 33M. Connate (brackish) groundwater was found in the hardrock (below a depth of about 360 feet) near Well 2N.

Cross Section B-B' (Figure 4) extends from near Avenue 376 and Road 140 to the south to east of Road 144 and north of Avenue 384 to the northeast. This section is generally oriented parallel to the inferred dip of the alluvial deposits. The base of the alluvial deposits was penetrated at Well 4H, the Yettem School test hole, and Well 34N. The base of the alluvial deposits is about 380 feet deep at Well 34N, 450 feet deep at the Yettem School test hole, and about 510 feet deep at Well 4N. The Quaternary older alluvium is also about 200 feet thick along this section and sands are relatively common. The underlying continental deposits are predominantly clay, but significant sands were found at Well 4J below a depth of about 340 feet. Connate




FIGURE 4 - SUBSURFACE GEOLOGIC CROSS SECTION B - B'

groundwater was found in two deep sand layers (below about 400 feet in depth) just above the weathered zone at the Yettem School test hole.

Cross Section C-C' (Figure 5 extends from north of Avenue 388 and east of Road 140 on the north to between Roads 144 and 148 and south of Avenue 384 to the southeast. This cross section is generally oriented perpendicular to the inferred dip of the alluvial deposits. The only well or hole along this section that penetrated the base of the alluvial deposits was the Yettem School test hole. The Quaternary older alluvium is also about 200 feet thick along this section and a laterally extensive, fairly thick sand layer is present at an average depth of about 70 to 90 feet. The underlying continental deposits are primarily clay. The thickest sands in the continental deposits below a depth of about 300 feet along this section were at the Yettem School test hole. As discussed previously, connate groundwater was found below a depth of about 400 feet at this hole.

WATER LEVELS

Water-level measurements for wells in the Yettem-Seville area were obtained from the California Department of Water Resources Website. Figure 6 is a water-level elevation and direction of groundwater flow map for April 2009. Water-level elevations




FIGURE 5- SUBSURFACE GEOLOGIC CROSS SECTION C - C'




FIGURE 6-WATER-LEVEL ELEVATIONS AND DIRECTION OF GROUNDWATER FLOW (APRIL 2009)

ranged from 315 feet above sea level in Seville to less than 300 feet in the southwest part of Yettem.

Water-level hydrographs were prepared for six wells in the area (Appendix A). Water-level are relatively shallow in the area, and the shallowest levels have ranged from about 10 to 15 feet. Water levels have risen and fallen with climatic conditions, and overall have been stable or slightly risen since the 1950's.

WELL PRODUCTION

Pumping rates for most large capacity wells in the Yettem area have ranged from about 60 to 270 gpm. Specific capacity values for most wells range from about 2 to 12 gpm per foot. A sustainable well yield of 200 gpm is thus considered good for irrigation wells in the Yettem-Seville area. The two Yettem community wells had sustainable pumping rates of about 65 gpm and 85 gpm, and specific capacities of 0.8 and 1.3 gpm per foot, respectively, when first tested.

GROUNDWATER QUALITY


Self-Help Enterprises collected water samples from about 50 private wells in the Yettem area during 1986-89. Most of these wells were less than 200 feet deep and thus tapped the older

alluvium. Figure 7 shows nitrate concentrations in the water from these wells. A number of wells that had low nitrate concentrations were along the Button and Sontag Ditches, and the low nitrate concentrations may have been due to canal seepage.

Water samples were collected from different depths at three sites (the Yettem School and Yettem Wells No. 1 and 2). Clay layers normally act to separate differences in constituent concentrations at various depths. Nitrate concentrations are expected to decrease with increasing depth, except near well conduits (wells perforated opposite both shallow and deep groundwater. Moderate nitrate concentrations (31 to 36 mg/l) were found in samples from below a depth of 400 feet at the Yettem School test hole, but this water was indicated to be connate water. Because of the sampling procedures used for the Yettem wells, the reliability of these is uncertain. Nitrate concentrations in water from the Yettem Well No. 1 test hole ranged from 12 to 27 mg/l between depths of 100 and 300 feet. However, the nitrate concentrations from the completed well (perforated from 130 to 260 feet and 270 to 330 feet in depth) was much higher than indicated by the test hole sampling. At the test hole for Yettem Well No. 2, nitrate concentrations ranged from about 7 to 30 mg/l and were lowest in the deepest sample (from 278 to 288 feet). In this case, the nitrate concentration in water from the pumped

FIGURE 7

**NITRATE CONCENTRATIONS IN
SHALLOW GROUNDWATER (1986-89)**



0 500 1,000
Feet

EST. 1968
PROVOST & PRITCHARD
CONSULTING GROUP
An Employee Owned Company

KDSA
Est. 1972

Legend

- Sampled Well and Nitrate Concentration in mg/l
- ▲ High Salinity
- Yettem and Seville public supply wells & Stone Corral School well

- Approximate Area of Nitrate Concentrations > 45 mg/l
- Approximate Area of Nitrate Concentrations < 40 mg/l
- Approximate Area of Nitrate Concentrations < 25 mg/l

NOTES:

1. Locations of water wells and nitrate concentrations sampled by Self-Help Enterprises
2. High salinity 'Well or Test Hole' is from other sources.
3. Most wells shown have a total depth of 200' or less.

FIGURE 7

Nitrate Concentrations in Shallow Groundwater (1986-89)

well (perforated from 120 to 316 feet in depth) agreed with the test hole results. Few wells in the Yettem area have apparently been sampled for 1,2,3-TCP, but this constituent is likely to be present in the shallow groundwater (above a depth of about 200 feet). Perchlorate has also been found in some of the shallow groundwater in the Yettem area.

SUMMARY

Relatively thick and laterally extensive sands are found in the older alluvium above a depth of about 200 feet, in the Yettem area. Sampling of water from numerous relatively shallow wells in and near Yettem was conducted by Self-Help Enterprises in 1986-89. Unfortunately, high nitrate concentrations are widespread in the Quaternary older alluvium. Low nitrate concentrations are present in the shallow groundwater in some areas, particularly near canals. However, this shallow low nitrate groundwater isn't considered a reliable supply, particularly during drought periods. The alluvial deposits are less than 200 feet thick beneath Seville. Because of the shallow depth to the hardrock, the thin sands that are present in the alluvium, and the anticipated low well yield and likely salt water in the hardrock, the Seville area is not considered suitable for developing a new well. In contrast, the alluvial deposits are more than 400 feet

thick beneath Yettem. The best opportunity to obtain good quality groundwater is from the continental deposits located in the area southwest or northwest of Yettem. The key to developing good quality groundwater is to tap sands below a depth of about 250 feet and where the connate groundwater is deeper than about 450 feet or is not present. The casing hammer method is recommended for the test well. The casing could be driven down to the top of the hardrock. If connate water isn't encountered, then the hole could be drilled deeper into the hardrock for further testing, if necessary. The test well should be located at least 600 feet from large capacity wells, so as to minimize possible well interference.

REFERENCES


Croft, M.G., and G. V. Gordon, 1968, "Geology, Hydrology, and Quality of Water in the Hanford-Visalia Area, San Joaquin Valley, California", U.S. Geological Survey Open-File Report.

Boyle Engineering Corporation, 1983, "Domestic Well at Yettem School (Cutler-Orosi Unified School District).


Keller and Wegley Consulting Engineers, 1993, Letter Report of September 14 on Yettem Well No. 1 Test Hole Results.

Keller and Wegley Consulting Engineers, 1994, Data package of October 20, 1994 on Yettem Well No. 2 Test Hole Results.


APPENDIX A
WATER-LEVEL HYDROGRAPHS




WATER-LEVEL HYDROGRAPH FOR WELL T.16S./R.25E.-32C1




WATER-LEVEL HYDROGRAPH FOR WELL T.16S./R.25E.-33A1




WATER-LEVEL HYDROGRAPH FOR WELL T.16S./R.25E.-34D2



WATER-LEVEL HYDROGRAPH FOR WELL T.17S./R.25E.-01D1



WATER-LEVEL HYDROGRAPH FOR WELL T.17S./R.25E.-01P1



WATER-LEVEL HYDROGRAPH FOR WELL T.17S./R.25E.-03B1

Appendix O: Surface Water - Guidelines



Guidelines for Accepting Water into the Friant-Kern Canal

Table of Contents

Guidelines for Accepting Water into the Friant-Kern Canal	1
Overview	1
A. General Requirements for Discharge of Water into the Friant-Kern Canal.....	2
B. Water Quality Monitoring and Reporting Requirements	3
C. Resolution of Disputes	8
D. Water Quality Forecasting and Communications	9
E. Implementation Responsibilities and Costs.....	9
Definitions	11
Tables	12
Attachments.....	12

Guidelines for Accepting Water into the Friant-Kern Canal

Overview

These Guidelines apply to all water introduced into the Friant-Kern Canal (“**FKC**”) other than directly from Millerton Lake to the headworks of the FKC (collectively, “**Non-Millerton water**”).

These Guidelines describe the Friant Water Authority’s (“**FWA**”) application review process, implementation procedures, and the responsibilities of water contractors and other parties authorized to introduce or receive Non-Millerton water into or from the FKC (collectively, “**Contractors**”). These Guidelines define the water quality thresholds and the required mitigation associated with introduced Non-Millerton water and corresponding water quality, as well as the methodologies and tools for monitoring and forecasting water quality in the FKC. These Guidelines are intended to ensure that water quality is protected for sustained domestic and agricultural use.

These Guidelines are applicable to all Non-Millerton water introduced or diverted into the FKC including but not limited to:

- Groundwater pump-ins (e.g., groundwater wells or previously banked water)
- Surface water diversions and pump-ins
- Recaptured and recirculated San Joaquin River Restoration Program Restoration Flows
- Water introduced at the FKC-Cross Valley Canal (“**CVC**”) intertie and delivered via reverse flow on the FKC

A Water Quality Advisory Committee composed of Friant Division long-term contractors (“**Friant Contractors**”) involved in either introducing or receiving Non-Millerton water to or from the FKC has been established to provide recommendations to FWA on operations and monitoring requirements of the FKC. The Water Quality Advisory Committee will operate under an established charter (see Attachment A). The Water Quality Advisory Committee will appoint a Monitoring Subcommittee to assist FWA in the implementation of the Guidelines.

These Guidelines are subject to review and modification by FWA if any of the following conditions occurs:

- A future regulatory cost or equivalent fee is imposed on Friant Contractors and a portion of such fee can reasonably be attributed to the incremental difference of water quality conditions in the FKC.
- When Friant Division Class 1 contract allocation is less than or equal to 25 percent, the Water Quality Advisory Committee will convene as outlined in Attachment A. In these years, mitigation will be accounted for as presented in these Guidelines, but will be deferred to a mutually agreed to later date unless those responsible for the put and take mutually agree to put and take the

mitigation in the critical year. All monitoring requirements will remain as presented in these Guidelines.

- There is a significant, regulatory change or scientifically based justification and three out of the following five Friant Contractors agree and work with the Water Quality Advisory Committee to recommend a change: (1) Arvin-Edison Water Storage District, (2) Shafter Wasco Irrigation District, (3) Delano-Earlimart Irrigation District, (4) South San Joaquin Municipal Utility District, and (5) Kern-Tulare Water District.

The Bureau of Reclamation (**Reclamation**) may also propose and/or require modifications to these Guidelines in coordination with FWA and reserves the right to implement additional water quality requirements as needed to protect water quality within the FKC. FWA will provide written notice of any proposed modification that are relevant to these Guidelines to all Contractors prior to adoption and implementation.

A. General Requirements for Discharge of Water into the Friant-Kern Canal

1. Guidelines Compliance Determination

A Contractor wishing to discharge Non-Millerton water into the FKC must, concurrent with its application for a contract or other applicable approval from Reclamation in such form and contents as may be required by Reclamation, obtain a determination from FWA as to compliance with the Guidelines or demonstrate to FWA and Reclamation that the proposed discharge will be subject to comparable and adequate alternative water quality mitigation measures. The application will not be approved until FWA has provided its determination that the applicant is compliant with the Guidelines or the provision of alternative mitigation measures is adequately demonstrated and incorporated into the proposed discharge project. Figure 1 shows the concurrent process that a Contractor must pursue to obtain these approvals. The Contractor will be responsible for securing all other requisite Federal, State or local permits.




Figure 1. Approval Process Diagram

2. Discharge Facility Approval

The approvals for the erection and maintenance of each discharge facility into the FKC must be approved and documented in the manner required by Reclamation, in coordination with FWA.

3. Other Discharge and Conveyance Requirements

The discharge of Non-Millerton water into the FKC may not in any way limit the ability of either FWA or Reclamation to operate and maintain the FKC for its intended purpose nor may it adversely impact existing water delivery contracts or any other water supply or delivery agreements. The discharge of Non-Millerton water into the FKC will be permissible only when there is capacity in the system as determined by FWA and/or Reclamation.

B. Water Quality Monitoring and Reporting Requirements

1. General Discharge Approval Requirements

Each source of Non-Millerton water discharged into the FKC must be correctly sampled, completely analyzed, and approved by FWA and Reclamation prior to introduction into the FKC. The Contractor must pay the cost of collection and analyses of the water required under these Guidelines. Other costs associated with the implementation of these Guidelines to be paid by the Contractors are described in Section E below.

2. Water Quality Monitoring and Management

The monitoring program requirements are detailed below. In addition, the requirements are summarized in a single table in Attachment B.

(a) Monitoring Requirements for Discharged Water

Prior to introduction to the FKC, all Non-Millerton water discharged into the FKC must be tested at the source (i.e., grab samples at each pump location for groundwater pump-ins or in-prism (i.e., in-situ) grab samples for water being introduced via other conveyances) and sampled by an appropriate party every three years for the complete list of water quality constituents listed in the then current version of Table 1. In addition, all Non-Millerton water discharged into the FKC must be tested and sampled by an appropriate party annually for the short list of water quality constituents listed in Table 4. The analytical laboratory must be a facility with Environmental Laboratory Accreditation Program (ELAP) certification. The laboratory analytical report and summary of water quality analytical results must be reported to FWA and Reclamation's **Contracting Officer** (i.e., the Area Manager for the South-Central California Area Office) for review. All monitoring requirements are summarized in Attachment B.

If analytical results show an exceedance of 80% of the threshold for any water quality constituents, defined in Table 4, discharged Non-Millerton water will be tested weekly for the targeted constituents of concern until four consecutive grab samples show consistent water quality results. The appropriateness of the threshold buffer (i.e., 80% of the threshold) will be evaluated by the Water Quality Advisory Committee.

If the water quality analytical results show exceedance of any constituent above its threshold in Table 1, 3 or 4 (i.e., not the threshold buffer but the threshold itself), at the discretion of Reclamation such water may not be allowed to be introduced into the FKC. FWA will evaluate monitoring requirements on a case-by-case basis and may impose additional requirements including but not limited to monitoring of the discharge source and downstream in prism quality at the cost of the Contractor.

(b) In-Prism Water Quality Monitoring

FWA will cause to be implemented continuous, real-time monitoring of in-prism water quality conditions in the FKC. Conductivity meters (or sondes) will measure and record real-time in-prism electrical conductivity ("EC"), measured as microsiemens per centimeter ($\mu\text{S}/\text{cm}$), every 15 minutes at the FKC check structures and corresponding mileposts shown in Table 2. Collected EC data will be uploaded to FWA's Intellisite Operation System (IOS) in real-time. These continuous, in-prism measurements of EC will provide real-time data on incremental water quality changes and mixing in the canal and will assist in water quality threshold management.

If the Friant Water Quality Model forecasts an in-prism exceedance of 80% of the threshold for any water quality constituents, defined in Table 4, water samples from the FKC will be collected each week by appropriate FWA staff until the sampled concentrations, supported through Friant Water Quality Model forecasted simulations, show four consecutive weeks below the 80% threshold. Each weekly collection will consist of one sample from each downstream check structure shown in Table 2 and where water quality changes are expected, plus one duplicate sample. FWA will deliver the samples to a laboratory

with ELAP certification. FWA expenses for all water quality monitoring and sampling are subject to reimbursement from Contractors through fees and charges. As was the case for the discharged water, the appropriateness of the threshold buffer will be evaluated by the Water Quality Advisory Committee.

Additional water quality sampling and analysis will be performed during specific FKC operations. FWA will cause to be measured EC using hand-held conductivity meters as needed, such as during:

- servicing of real-time monitoring equipment;
- unexpected real-time monitoring equipment outages;
- confirmation of real-time monitoring equipment measurements; and,
- targeted in-prism measurements.

(c) CVC In-Prism Water Quality Monitoring

Upon initiation of reverse-flow, pump-back activities and/or if it is anticipated that operations within the CVC will significantly change mixed water quality conditions (i.e., influence from California Aqueduct, Kern River, Kern Fan), grab samples will be collected by FWA within the CVC near the FKC/CVC Intertie, and provided to a third-party laboratory with ELAP certification for testing of water quality constituents listed in Table 1. In addition, during reverse-flow pump-back operations, weekly water quality sampling will be performed within the CVC near the FKC/CVC Intertie. Grab samples will be collected by FWA and provided to a third-party, ELAP certified laboratory for testing. At a minimum, grab samples collected during reverse-flow pump-back operations will be analyzed for the short list of water quality constituents listed in Table 4.

The Water Quality Advisory Committee will evaluate water quality monitoring, sampling, and analysis requirements on a regular basis and provide recommendations for modification of the described requirements.

(d) In-Prism Water Quality Management

FKC in prism water quality will be managed per the following thresholds. If the below thresholds are exceeded, systematic cessation of pump-in or pump-back operations will occur.

1. Title 22. The Domestic Water Quality and Monitoring Regulations specified by the State of California Health and Safety Code (Sections 116270-116755), and Title 22 of the California Code of Regulations (Sections 6440 et seq.), as amended. In prism water quality constituent concentrations may not exceed the Maximum Contaminant Level (**MCL**) as defined in Table 1, except those constituents listed in Table 3 and Table 4. Current State of California requirements at the time of sampling will prevail over those in the accepted version of this document if MCLs in Table 1 are changed in the future.
2. Water quality thresholds defined in Table 3. Water quality thresholds are representative of constituent thresholds of sensitive crops; leaching requirements; and crop thresholds for regulated

deficit irrigation practices that occur during almond hull split from July 1 through August 31; and flexible thresholds in the second half of the contract year, from September 1 through February 28, depending on observed water quality in the first portion of the contract year.

- i. Table 3 presents alternative water quality thresholds for Period 3 (September 1 – February 28) that are dependent on the measured water quality during Period 1 (March 1 – June 30). If the measured average chloride concentration for Period 1 exceeds 70 milligrams per liter (mg/L), the chloride threshold remains at 102 mg/L for Period 3a. If the measured average chloride concentrations for Period 1 are less than or equal to 70 mg/L, the allowable chloride concentration increases from 102 mg/L to 123 mg/L for Period 3b.
- ii. It is estimated that an average of one week is required for in-prism water quality to turnover. Prior to the onset of the defined hull split period requirements (July 1), current FKC operations and water quality conditions will be evaluated to determine if this one-week period should be adjusted.

If water quality thresholds are exceeded, or based on modeling appear likely to be imminently exceeded, or operations in the FKC need to change per Guidelines requirements, FWA will immediately notify the Water Quality Advisory Committee, which must convene a meeting of the Monitoring Subcommittee within three days of receiving notification from FWA. The Monitoring Subcommittee and FWA will review operations and water quality data and will seek consensus on determining the best management actions to improve water quality; provided, however, the final operational decision will be made by FWA. In addition, the Monitoring Subcommittee will seek 1:1, unleveraged, and cost-neutral exchanges to limit potential Project water impacts. Notwithstanding the foregoing, FWA retains the right to determine and take immediate management actions with respect to groundwater pump-ins in accordance with the applicable approvals, but will work in good faith with the Water Quality Advisory Committee and Monitoring Subcommittee to evaluate options. If required, management actions including any reductions or cessation of pump-in volume must occur within three days of the meeting between FWA and the Monitoring Subcommittee. FWA will order any reduction in pump-in volume in order of greatest mass loading. Finally, the Monitoring Subcommittee will set an appropriate review period to assess if implemented management actions are working and, if not, will agree to reconvene to discuss additional actions necessary to improve water quality.

(e) Uncontrolled Season

Non-Millerton water may not be introduced to the FKC during the Friant Division uncontrolled season as declared by Reclamation unless:

- Deliveries are necessary due to FKC capacity constraints, and if the Non-Millerton water delivered from the CVC remains below the Shafter Check, or
- The Non-Millerton water is below the determined baseline EC threshold of 200 $\mu\text{S}/\text{cm}$ and, therefore, does not require mitigation.
- Introduction of Non-Millerton water does not impact Friant Division flood operations.

3. Water Quality Mitigation


Mitigation for impacted water quality is quantified through use of the Water Quality Mitigation Ledger (“**Ledger**”). The Ledger tracks and accounts for all inflows into and diversions from the FKC in order to determine appropriate mitigation for impacted water quality (attributable to the introduced Non-Millerton water or “**Put**”¹). The volume of additional surface water needed for mitigation, expressed as a percentage of the introduced water, or Put, is determined using an established mitigation rating curve. The mitigation rating curve is based on (1) constituent concentrations, and (2) agronomic principles that focus on leaching requirements to prevent constituent accumulation in the rootzone and resulting impacts on crops. This approach aims to balance concerns related to long-term groundwater quality with a multi-layered assessment of agronomic impacts as a durable solution. The process for developing the agronomic impacts evaluation and mitigation rating curve can be found in *Attachment C– Agronomic Impacts and Mitigation*.

The Ledger quantifies mitigation for Friant Contractors that have an expectation to receive water consistent with quality conditions of Millerton Lake. Specifically, mitigation applies to the “**Take**” (or delivery) of Friant Division Class 1, Class 2, Recovered Water Account (RWA [Paragraph 16b]), and Unreleased Restoration Flows supplies. Friant Contractors and/or other Contractors, including but not limited to third parties, whose supplies are not delivered to the headworks of the FKC are not eligible to receive mitigation.

Mitigation percentage is based on the EC of the Put above the established baseline. The established baseline is based on assumptions of current, minimum leaching practices by water users, or growers, in the region. Consistent with good agricultural practices, it is assumed that growers are currently applying at least a five percent (5%) leaching fraction. Under the mitigation rating curve shown in Figure 2, this corresponds to an approximate EC of 200 $\mu\text{S}/\text{cm}$. It is assumed that growers are already managing the effects of applied water quality conditions up to 200 $\mu\text{S}/\text{cm}$ of EC, and mitigation is only required for water quality conditions with incremental EC that exceed the baseline EC threshold of 200 $\mu\text{S}/\text{cm}$. Note that the mitigation rating curve extends beyond the maximum EC and mitigation percentage shown in Figure 2 (i.e., at 1,000 $\mu\text{S}/\text{cm}$ and 25%) at the same slope of 5% mitigation per 200 $\mu\text{S}/\text{cm}$ of EC.

A mitigation volume is calculated based on the Put volume and corresponding mitigation percentage. Mitigation volumes for each Put are distributed to each Friant Contractor receiving an eligible Take, or “**Taker**,” downstream based on the volumetric proportion of the Take on a weekly basis. Mitigation occurs in real time by the Contractor and offsets a like volume of each Taker’s supply at the end of a reporting period. Additional mitigation is not required to account for the water quality conditions of the mitigation volumes. Water quality conditions and flows are tracked daily. The ledger and required mitigation volumes are balanced weekly and reported and transferred monthly. Accounting and reporting are detailed in *Attachment D – Standard Operating Procedures*.

¹ Existing FKC inlet drains are exempt from providing mitigation.



Key:

µS/cm = microsiemens per centimeter (1 µS/cm = 1 µmhos/cm = 1/1,000 dS/m)

Figure 2. Proposed Mitigation Rating Curve Based on Boron Sensitivity and Normalized to Electrical Conductivity

4. Critical Year Management

When Friant Division Class 1 contract allocation is less than or equal to 25 percent, the Water Quality Advisory Committee will convene as outlined in Attachment A. In these years, mitigation will be accounted for as presented in these Guidelines, but will be deferred to a mutually agreed later date unless those responsible for the Put and Take mutually agree to put and take the mitigation in the critical year. All monitoring requirements will remain as presented in these Guidelines.

C. Resolution of Disputes

In the event a Contractor is dissatisfied with the application or interpretation of these Guidelines by FWA staff or consultants, the following dispute resolution procedures will apply:

1. A Contractor may request FWA refer the dispute to Reclamation's Contracting Officer's Representative for initial review. FWA will prepare and deliver a written summary of the dispute for Reclamation's Contracting Officer's Representative, who will then confer with the parties and issue an advisory opinion regarding the dispute in a timely manner.
2. In addition to or in lieu of the meet and confer process with Reclamation's Contracting Officer's Representative above, a Contractor may submit a written appeal to be heard by the FWA Board of Directors. The written appeal must be submitted to the office of the Chief Executive Officer, who will then place the dispute on the agenda of the Board of Directors for a hearing at a board meeting no later than 60 days from the date of receipt. The decision of the Board of Directors will be final and FWA and the other party(ies) must promptly comply with such decision until the same is stayed, reversed, or modified by a decision of a court of competent jurisdiction.

The Cooperative Agreement between the Contractors and FWA provides additional dispute resolution procedures. In the event of any conflict between the dispute resolution procedures in these Guidelines and the Cooperative Agreement, the provisions in the Cooperative Agreement will control.

D. Water Quality Forecasting and Communications

1. Friant-Kern Canal Water Quality Model

Water quality monitoring and collection of water quality data will be evaluated using the FKC Water Quality Model, a volumetric mass-balance model of the entire FKC. The FKC Water Quality Model will serve as a predictive, water quality forecast tool to assist Friant Contractors and FWA in making real-time operation decisions. The weekly application of this model will require compilation of surface water quality data collected, as described above, as well as forecasts of water orders and periodic model updates.

2. Water quality reporting and communications

IOS will report real-time, continuous FKC in-prism EC measurements. In addition, FWA will cause to be provided a weekly summary report to Friant Contractors and Reclamation on:

- FKC current and forecasted operations;
- FKC current in-prism monitoring and forecasted water quality conditions; and,
- Pertinent pump-in programs' operations and water quality conditions.

E. Implementation Responsibilities and Costs

FWA will be responsible for the following actions:

- Maintain and calibrate conductivity meters
- Perform water quality sampling during pump-in operations
- Coordinate laboratory water quality testing
- Coordinate with Contractors on water quality data monitoring and analysis
- Manage in-prism water quality and manage operations database
- Perform weekly water quality reporting and forecasting using FKC Water Quality Model
- Perform weekly analysis to determine mitigation and distribution to respective Friant Contractors or any other Contractor party(ies) using the FKC Water Quality Mitigation Ledger
- Coordinate with Reclamation's SCCAO on water quality reporting, mitigation, and contractual requirements

- Coordinate and facilitate the work of Water Quality Advisory Committee and the Monitoring Subcommittee.

Costs for implementation and administration of these Guidelines will be initially paid out of the FWA Operation, Maintenance, and Replacement (OM&R) budget, and subsequently will be reimbursed by Contractors. The Contractor will pay a dollar per acre-foot (\$/acre-foot) surcharge (“**Guidelines Surcharge**”) for introduced Non-Millerton water, that will be credited to the FWA OM&R budget. The Guidelines Surcharge will be adopted by the FWA Board of Directors and will be based on an estimate of total annual costs divided by average annual deliveries of pump-in programs into the FKC. The Guidelines Surcharge will be applied to all introduced Non-Millerton water even if mitigation is not required

Annual costs and deliveries will be reassessed every year and compared to estimates provided in Attachment E to determine if any adjustments are required to the Guidelines Surcharge.

Definitions

Contractors: Water contractors and other parties authorized to introduce or receive Non-Millerton water into or from the FKC.

Contracting Officer: The Area Manager of Reclamation's South-Central California Area Office.

Cooperative Agreement: The agreement between FWA and the participating Contractors regarding the establishment, implementation and management of these Guidelines.

CVC: Cross Valley Canal

EC: Salinity measured as electrical conductivity

ELAP: Environmental Laboratory Accreditation Program

Friant Contractors: Friant Division contractors with long-term contracts with Reclamation.

FWA: Friant Water Authority, a California joint powers agency.

Guidelines Surcharge: The surcharge imposed by FWA on Contractors on a per acre feet basis for Non-Millerton water introduced into the FKC to cover the costs of implementing the Guidelines.

IOS: Intellisite Operation System

Ledger: The Water Quality Mitigation Ledger that tracks and accounts for all inflows into and diversions from the FKC in order to determine appropriate mitigation for impacted water quality attributable to the introduced Non-Millerton water.

Maximum Contaminant Level (MCL): Usually reported in milligrams per liter (parts per million) or micrograms per liter (parts per billion).

Non-Millerton water: All water introduced into the Friant-Kern Canal other than directly from Millerton Lake to the headworks of the FKC.

OM&R: Operation, Maintenance and Replacement.

Put: The introduction of Non-Millerton water into the FKC.

Project: The Friant Division of the Central Valley Project, specifically the Friant-Kern Canal.

Reclamation: U.S. Department of the Interior, Bureau of Reclamation.

SCCAO: Reclamation's South-Central California Area Office.

Take: The delivery of Friant Division Class 1, Class 2, Recovered Water Account (RWA [Paragraph 16b]), and Unreleased Restoration Flows supplies.

Taker: A Friant Contractor receiving an eligible Take.

Title 22: The Domestic Water Quality and Monitoring Regulations specified by the State of California Health and Safety Code (Sections 116270-116755), and California Code of Regulations (Sections 6440 et seq.), as amended.

Tables

Table 1. Water Quality Constituents

Table 2. Check Structure Locations for Real-Time Measurements of Electrical Conductivity

Table 3. Friant-Kern Canal In-Prism Water Quality Thresholds

Table 4: Friant-Kern Canal Water Quality Constituents Short List.

Attachments

Attachment A: Water Quality Advisory Committee Charter

Attachment B: Monitoring Program Summary

Attachment C: Agronomic Impacts and Mitigation

Attachment D: Ledger Standard Operating Procedures

Attachment E: FKC Water Quality Guidelines Cost Allocation

The non-Project water discharged into Federal Facilities must comply with the California Drinking Water standards (Title 22)² listed in Table 1. However, selenium thresholds cannot exceed 2 micrograms per liter as defined in Table 4.

Table 1 Title 22 Water Quality Standards

Constituent	Units	MCL	Detection Limit for Reporting	CAS Registry Number	Recommended Analytical Method
Primary					
Aluminum	mg/L	1 ⁽¹⁾	0.05 ⁽²⁾	7429-90-5	EPA 200.7
Antimony	mg/L	0.006 ⁽¹⁾	0.006 ⁽²⁾	7440-36-0	EPA 200.8
Arsenic	mg/L	0.010 ⁽¹⁾	0.002 ⁽²⁾	7440-38-2	EPA 200.8
Asbestos	MFL	7 ⁽¹⁾	0.2 MFL>10µm ⁽²⁾	1332-21-4	EPA 100.2
Barium	mg/L	1 ⁽¹⁾	0.1 ⁽²⁾	7440-39-3	EPA 200.7
Beryllium	mg/L	0.004 ⁽¹⁾	0.001 ⁽²⁾	7440-41-7	EPA 200.7
Cadmium	mg/L	0.005 ⁽¹⁾	0.001 ⁽²⁾	7440-43-9	EPA 200.7
Chromium, total	mg/L	0.05 ⁽¹⁾	0.01 ⁽²⁾	7440-47-3	EPA 200.7
Copper	mg/L	1.3	0.050 ⁽²⁾	7440-50-8	EPA 200.7
Cyanide	mg/L	0.15 ⁽¹⁾	0.1 ⁽²⁾	57-12-5	EPA 335.2
Fluoride	mg/L	2.0 ⁽¹⁾	0.1 ⁽²⁾	16984-48-8	EPA 300.1
Hexavalent Chromium	mg/L	0.010 ⁽¹⁾	0.001 ⁽²⁾	18540-29-9	EPA 218.7
Lead	mg/L	0.015 ⁽⁹⁾	0.005 ⁽²⁾	7439-92-1	EPA 200.8
Mercury	mg/L	0.002 ⁽¹⁾	0.001 ⁽²⁾	7439-97-6	EPA 245.1
Nickel	mg/L	0.1 ⁽¹⁾	0.01 ⁽²⁾	7440-02-0	EPA 200.7
Nitrate (as nitrogen)	mg/L	10 ⁽¹⁾	0.4 ⁽²⁾	7727-37-9	EPA 300.1
Nitrate + Nitrite (sum as nitrogen)	mg/L	10 ⁽¹⁾		14797-55-8	EPA 353.2
Nitrite (as nitrogen)	mg/L	1 ⁽¹⁾	0.4 ⁽²⁾	14797-65-0	EPA 300.1
Perchlorate	mg/L	0.006 ⁽¹⁾	0.004 ⁽²⁾	14797-73-0	EPA 314/331/332
Selenium	mg/L	0.002 ⁽¹⁰⁾	0.001	7782-49-2	EPA 200.8
Thallium	mg/L	0.002 ⁽¹⁾	0.001 ⁽²⁾	7440-28-0	EPA 200.8
Thiobencarb	mg/L	0.07		28249-77-6	EPA 527
Secondary					
Aluminum	mg/L	0.2 ⁽⁶⁾		7429-90-5	EPA 200.7
Chloride	mg/L	500 ⁽⁷⁾		16887-00-6	EPA 300.1
Color	units	15 ⁽⁶⁾			EPA 110
Copper	mg/L	1.0 ⁽⁶⁾	0.050 ⁽⁸⁾	7440-50-8	EPA 200.7
Iron	mg/L	0.3 ⁽⁶⁾		7439-89-6	EPA 200.7
Manganese	mg/L	0.05 ⁽⁶⁾		7439-96-5	EPA 200.7
Methyl-tert-butyl ether (MTBE)	mg/L	0.005 ⁽⁶⁾		1634-04-4	EPA 502.2/524.2
Odor -threshold	units	3 ⁽⁶⁾			SM 2150B
Silver	mg/L	0.1 ⁽⁶⁾		7440-22-4	EPA 200.7
Specific Conductance	µS/cm	1,600 ⁽⁷⁾			SM 2510 B

² California Code of Regulations, Title 22. The Domestic Water Quality and Monitoring Regulations specified by the State of California Health and Safety Code (Sections 4010 4037), and Administrative Code (Sections 64401 et seq.), as amended
https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/documents/lawbook/dw_regulations_2019_03_28.pdf

Constituent	Units	MCL	Detection Limit for Reporting	CAS Registry Number	Recommended Analytical Method
Sulfate	mg/L	500 ⁽⁷⁾		14808-79-8	EPA 300.1
Thiobencarb	mg/L	0.001 ⁽⁶⁾		28249-77-6	EPA 527
Total Dissolved Solids	mg/L	1,000 ⁽⁷⁾			SM 2540 C
Turbidity	units	5 ⁽⁶⁾			EPA 190.1/SM2130B
Zinc	mg/L	5.0 ⁽⁶⁾		7440-66-6	EPA 200.7
Other Required Analyses					
Boron	mg/L	2.0 ⁽¹³⁾		7440-42-8	EPA 200.7
Molybdenum	mg/L	0.01 ⁽¹¹⁾		7439-98-7	EPA 200.7
Sodium	mg/L	200 ⁽¹²⁾		7440-23-5	EPA 200.7
Radioactivity					
Gross alpha*	pCi/L	15 ⁽³⁾			SM 7110C
Organic Chemicals					
<i>(a) Volatile Organic Chemicals (VOCs)</i>					
Benzene	mg/L	0.001 ⁽⁴⁾	0.0005 ⁽⁵⁾	71-43-2	EPA 502.2/524.2
Carbon Tetrachloride	mg/L	0.0005 ⁽⁴⁾	0.0005 ⁽⁵⁾	56-23-5	EPA 502.2/524.2
1,2-Dichlorobenzene.	mg/L	0.6 ⁽⁴⁾	0.0005 ⁽⁵⁾	95-50-1	EPA 502.2/524.2
1,4-Dichlorobenzene.	mg/L	0.005 ⁽⁴⁾	0.0005 ⁽⁵⁾	106-46-7	EPA 502.2/524.2
1,1-Dichloroethane	mg/L	0.005 ⁽⁴⁾	0.0005 ⁽⁵⁾	75-34-3	EPA 502.2/524.2
1,2-Dichloroethane	mg/L	0.0005 ⁽⁴⁾	0.0005 ⁽⁵⁾	107-06-2	EPA 502.2/524.2
1,1-Dichloroethylene	mg/L	0.006 ⁽⁴⁾	0.0005 ⁽⁵⁾	75-35-4	EPA 502.2/524.2
cis-1,2-Dichloroethylene	mg/L	0.006 ⁽⁴⁾	0.0005 ⁽⁵⁾	156-59-2	EPA 502.2/524.2
trans-1,2-Dichloroethylene	mg/L	0.01 ⁽⁴⁾	0.0005 ⁽⁵⁾	156-60-5	EPA 502.2/524.2
Dichloromethane.	mg/L	0.005 ⁽⁴⁾	0.0005 ⁽⁵⁾	75-09-2	EPA 502.2/524.2
1,2-Dichloropropane.	mg/L	0.005 ⁽⁴⁾	0.0005 ⁽⁵⁾	78-87-5	EPA 502.2/524.2
1,3-Dichloropropane.	mg/L	0.0005 ⁽⁴⁾	0.0005 ⁽⁵⁾	542-75-6	EPA 502.2/524.2
Ethylbenzene.	mg/L	0.3 ⁽⁴⁾	0.0005 ⁽⁵⁾	100-41-4	EPA 502.2/524.2
Methyl-tert-butyl ether	mg/L	0.013 ⁽⁴⁾	0.003 ⁽⁵⁾	1634-04-4	EPA 502.2/524.2
Monochlorobenzene	mg/L	0.07 ⁽⁴⁾	0.0005 ⁽⁵⁾	108-90-7	EPA 502.2/524.2
Styrene.	mg/L	0.1 ⁽⁴⁾	0.0005 ⁽⁵⁾	100-42-5	EPA 502.2/524.2
1,1,2,2-Tetrachloroethane	mg/L	0.001 ⁽⁴⁾	0.0005 ⁽⁵⁾	79-34-5	EPA 502.2/524.2
Tetrachloroethylene (PCE)	mg/L	0.005 ⁽⁴⁾	0.0005 ⁽⁵⁾	127-18-4	EPA 502.2/524.2
Toluene	mg/L	0.15 ⁽⁴⁾	0.0005 ⁽⁵⁾	108-88-3	EPA 502.2/524.2
1,2,4-Trichlorobenzene	mg/L	0.005 ⁽⁴⁾	0.0005 ⁽⁵⁾	120-82-1	EPA 502.2/524.2
1,1,1-Trichloroethane	mg/L	0.200 ⁽⁴⁾	0.0005 ⁽⁵⁾	71-55-6	EPA 502.2/524.2
1,1,2-Trichloroethane	mg/L	0.005 ⁽⁴⁾	0.0005 ⁽⁵⁾	79-00-5	EPA 502.2/524.2
Trichloroethylene (TCE)	mg/L	0.005 ⁽⁴⁾	0.0005 ⁽⁵⁾	79-01-6	EPA 502.2/524.2
Trichlorofluoromethane	mg/L	0.15 ⁽⁴⁾	0.005 ⁽⁵⁾	75-69-4	EPA 502.2/524.2
1,1,2-Trichloro-1,2,2-Trifluoroethane	mg/L	1.2 ⁽⁴⁾	0.01 ⁽⁵⁾	76-13-1	SM 6200B
Vinyl Chloride	mg/L	0.0005 ⁽⁴⁾	0.0005 ⁽⁵⁾	75-01-4	EPA 502.2/524.2
Xylenes	mg/L	1.750* ⁽⁴⁾	0.0005 ⁽⁵⁾	1330-20-7	EPA 502.2/524.2
<i>(b) Non-Volatile Synthetic Organic Chemicals (SOCs)</i>					
Alachlor	mg/L	0.002 ⁽⁴⁾	0.001 ⁽⁵⁾	15972-60-8	EPA 505/507/508
Atrazine	mg/L	0.001 ⁽⁴⁾	0.0005 ⁽⁵⁾	1912-24-9	EPA 505/507/508
Bentazon	mg/L	0.018 ⁽⁴⁾	0.002 ⁽⁵⁾	25057-89-0	EPA 515.1
Benzo(a)pyrene	mg/L	0.0002 ⁽⁴⁾	0.0001 ⁽⁵⁾	50-32-8	EPA 525.2
Carbofuran	mg/L	0.018 ⁽⁴⁾	0.005 ⁽⁵⁾	1563-66-2	EPA 531.1
Chlordane	mg/L	0.0001 ⁽⁴⁾	0.0001 ⁽⁵⁾	57-74-9	EPA 505/508
2,4-D	mg/L	0.07 ⁽⁴⁾	0.01 ⁽⁵⁾	94-75-7	EPA 515.1

Constituent	Units	MCL	Detection Limit for Reporting	CAS Registry Number	Recommended Analytical Method
Dalapon	mg/L	0.2 ⁽⁴⁾	0.01 ⁽⁵⁾	75-99-0	EPA 515.1
Dibromochloropropane	mg/L	0.0002 ⁽⁴⁾	0.00001 ⁽⁵⁾	96-12-8	EPA 502.2/504.1
Di(2-ethylhexyl)adipate	mg/L	0.4 ⁽⁴⁾	0.005 ⁽⁵⁾	103-23-1	EPA 506
Di(2-ethylhexyl)phthalate	mg/L	0.004 ⁽⁴⁾	0.003 ⁽⁵⁾	117-81-7	EPA 506
Dinoseb	mg/L	0.007 ⁽⁴⁾	0.002 ⁽⁵⁾	88-85-7	EPA 5151-4
Diquat	mg/L	0.02 ⁽⁴⁾	0.004 ⁽⁵⁾	85-00-7	EPA 549.2
Endothall	mg/L	0.1 ⁽⁴⁾	0.045 ⁽⁵⁾	145-73-3	EPA 548.1
Endrin	mg/L	0.002 ⁽⁴⁾	0.0001 ⁽⁵⁾	72-20-8	EPA 505/508
Ethylene Dibromide	mg/L	0.00005 ⁽⁴⁾	0.00002 ⁽⁵⁾	106-93-4	EPA 502.2/504.1
Glyphosate (Roundup)	mg/L	0.7 ⁽⁴⁾	0.025 ⁽⁵⁾	1071-83-6	EPA 547
Heptachlor.	mg/L	0.00001 ⁽⁴⁾	0.00001 ⁽⁵⁾	76-44-8	EPA 508
Heptachlor Epoxide	mg/L	0.00001 ⁽⁴⁾	0.00001 ⁽⁵⁾	1024-57-3	EPA 508
Hexachlorobenzene	mg/L	0.001 ⁽⁴⁾	0.0005 ⁽⁵⁾	118-74-1	EPA 505/508
Hexachlorocyclopentadiene	mg/L	0.05 ⁽⁴⁾	0.001 ⁽⁵⁾	77-47-4	EPA 505/508
Lindane (gamma-BHC)	mg/L	0.0002 ⁽⁴⁾	0.0002 ⁽⁵⁾	58-89-9	EPA 505/508
Methoxychlor	mg/L	0.03 ⁽⁴⁾	0.01 ⁽⁵⁾	72-43-5	EPA 505/508
Molinate	mg/L	0.02 ⁽⁴⁾	0.002 ⁽⁵⁾	2212-67-1	EPA 525.1
Oxamyl	mg/L	0.05 ⁽⁴⁾	0.02 ⁽⁵⁾	23135-22-0	EPA 531.1
Pentachlorophenol	mg/L	0.001 ⁽⁴⁾	0.0002 ⁽⁵⁾	87-86-5	EPA 515.1-3
Picloram	mg/L	0.5 ⁽⁴⁾	0.001 ⁽⁵⁾	1918-02-1	EPA 515.1-3
Polychlorinated Biphenyls	mg/L	0.0005 ⁽⁴⁾	0.0005 ⁽⁵⁾	1336-36-3	EPA 130.1
Simazine	mg/L	0.004 ⁽⁴⁾	0.001 ⁽⁵⁾	122-34-9	EPA 505
Thiobencarb (Bolero)	mg/L	0.07 ⁽⁴⁾	0.001 ⁽⁵⁾	28249-77-6	EPA 527
Toxaphene	mg/L	0.003 ⁽⁴⁾	0.001 ⁽⁵⁾	8001-35-2	EPA 505
1,2,3-Trichloropropane	mg/L	0.000005 ⁽⁴⁾	0.000005 ⁽⁵⁾	96-18-4	SRL 524M
2,3,7,8-TCDD (Dioxin)	mg/L	3 x 10 ⁻⁸ ⁽⁴⁾	5 x 10 ⁻⁹ ⁽⁵⁾	1746-01-6	EPA 130.3
2,4,5-TP (Silvex)	mg/L	0.05 ⁽⁴⁾	0.001 ⁽⁵⁾	93-72-1	EPA 515.1
<i>Other Organic Chemicals</i>					
Chlorpyrifos	µg/L	0.015 ⁽¹¹⁾		2921-88-2	EPA 8141A
Diazinon	µg/L	0.10 ⁽¹¹⁾		333-41-5	EPA 8141A

Sources:

- Recommended Analytical Methods: <https://www.nemi.gov/home/>
- Maximum Contaminant Levels (MCL): Title 22. The Domestic Water Quality and Monitoring Regulations specified by the State of California Health and Safety Code (Sections 4010-4037), and Administrative Code (Sections 64401 et seq.), as amended.
- (1) Title 22. Table 64431-A Maximum Contaminant Levels, Inorganic Chemicals
- (2) Title 22. Table 64432-A Detection Limits for Reporting (DLRs) for Regulated Inorganic Chemicals
- (3) Title 22. Table 64442 Radionuclide Maximum Contaminant Levels (MCLs) and Detection Levels for Purposes of Reporting (DLRs)
- (4) Title 22. Table 64444-A Maximum Contaminant Levels, Organic Chemicals
- (5) Title 22. Table 64445.1-A Detection Limits for Purposes of Reporting (DLRs) for Regulated Organic Chemicals
- (6) Title 22. Table 64449-A Secondary Maximum Contaminant Levels "Consumer Acceptance Contaminant Levels"
- (7) Title 22. Table 64449-B Secondary Maximum Contaminant Levels "Consumer Acceptance Contaminant Level Ranges"
- (8) Title 22. Table 64678-A DLRs for Lead and Copper
- (9) Title 22. Section 64678 (d) Lead Action level
- https://www.waterboards.ca.gov/drinking_water/certlic/drinkingwater/documents/lawbook/dw_regulations_2019_03_28.pdf
- California Regional Water Quality Control Board, Central Valley Region, Fourth Edition of the Water Quality Control Plan for the Sacramento River and San Joaquin River Basins. Revised June 2015
- (10) Basin Plan, Table III-1 (ug/L) (selenium in Grasslands water supply channels)
- (11) Basin Plan, Table III-2A. 4-day average (chronic) concentrations of chlorpyrifos & diazinon in San Joaquin River from Mendota to Vernalis
- https://www.waterboards.ca.gov/centralvalley/water_issues/tmdl/central_valley_projects/delta_op_pesticide/
- Ayers, R. S. and D. W. Westcot, Water Quality for Agriculture, Food and Agriculture Organization of the United Nations - Irrigation and Drainage Paper No. 29, Rev. 1, Rome (1985).
- (12) Ayers, Table 1 (mg/L) (sodium)
- (13) Ayers, Table 1 (mg/L) (boron)
- <http://www.fao.org/3/T0234E/T0234E00.htm>
- (14) Requested by State Water contractors, no MCL specified.

- California Regional Water Quality Control Board. PFAS Per-and Polyfluoroalkyl Substances.
(15) Testing Methods in California Drinking Water
<https://www.waterboards.ca.gov/pfas/>

Table 2. Check Structure Locations for Real-Time Measurements of Electrical Conductivity

Check Structure	Milepost
Little Dry Creek	5.50
Kings River	28.52
Sand Creek	46.04
Dodge Ave	61.03
Kaweah River	71.29
Rocky Hill	79.25
Fifth Ave	88.22
Tule River	95.67
Deer Creek	102.69
White River	112.90
Reservoir (Woollomes)	121.51
Poso Creek	130.03
Shafter	137.20
Kern River	151.81

Table 3. Friant-Kern Canal In-Prism Water Quality Thresholds

Period	Salinity expressed as EC (μS/cm)	Chloride (mg/L)	Boron (mg/L)¹	Turbidity (NTU)⁶	Total Suspended Solids (ppm)⁶	SAR⁷	Sodium (mg/L)⁷
Period 1 March 1 – June 30	1,000 ²	102 ³	0.4	40	20	3	69
Period 2 July 1 – August 31	500 ⁴	55 ⁴	0.4	40	20	3	69
Period 3a September 1 – February 28	1,000 ²	102 ³	0.4	40	20	3	69
Period 3b September 1 – February 28	1,000 ²	123 ⁵	0.4	40	20	3	69

Notes:

Thresholds adapted from Grieve, C.M., S.R. Grattan and E.V. Maas. 2012. Plant salt tolerance. In. (W.W. Wallender and K.K. Tanji, eds). Agricultural Salinity Assessment and Management (2nd edition). ASCE pp 405-459; and Ayers, R.S. and D.W. Westcot 1985. Water quality for agriculture. FAO Irrigation and Drainage Paper 29 (rev 1). Food and Agriculture Organization of the United Nations. Rome

For addition detail, see Attachment C – Agronomic Impacts and Mitigation.

When Friant-Kern Canal in-prism water quality conditions in this table are exceeded, Friant Division Long-Term Contractors will work together to seek 1:1, unleveraged, and cost-neutral exchanges for pump-in and pump-back programs. This does not apply to spot-market or third-party exchanges.

¹ Grapes are used as a representative crop for boron sensitivity and are prevalent in the Friant Division. They are used as a surrogate for many other sensitive crop types such as apricots, figs, and grapefruits. Threshold assumes conventional irrigation with minimum 20 percent leaching fraction applied.

² Threshold assumes minimum of 20 percent leaching requirement applied and adjusted to account for regulated deficit irrigation during almond hull split period (July 1 – August 31) to not exceed maximum EC_{et}. Almonds on Nemaguard rootstock are used as a representative crop for salinity sensitivity and are prevalent in the Friant Division. They are used as a surrogate for many other sensitive crop types such as apples, cherries, pears, pistachios, and walnuts.

³ Threshold assumes minimum of 20 percent leaching requirement applied and then adjusted to account for regulated deficit irrigation during almond hull split period (July 1 – August 31) to not exceed maximum Cl_{et}. Almonds on Nemaguard rootstock used as a representative crop for chloride sensitivity. They are used as a surrogate for other sensitive crops including cherries, pistachios, and walnuts. If the measured average chloride concentration for Period 1 exceeds 70 mg/L, the chloride threshold remains at 102 mg/L.

⁴ Threshold applies to almond hull split period when regulated deficit irrigation is applied to avoid hull rot. This threshold is used assuming irrigation applications are reduced to 50 percent of the tree water requirement and subsequently thresholds applied for the remainder of the year have been adjusted to account for additional salt accumulation. This threshold was developed with consideration of existing program operations, historical water quality data, and absolute water quality thresholds.

⁵ If the measured average chloride concentration in Period 1 (March 1 – June 30) is less than or equal to 70 mg/L, the allowable chloride threshold for Period 3 (September 1 – February 28) is increased to 123 mg/L.

⁶ Applied TSS and turbidity thresholds from section 3 of the Final Initial Study/Negative Declaration for: Warren Act Contract and License, and Operation and Maintenance Agreement to Introduce Floodwaters from Reclamation District 770 into the Friant-Kern Canal, March 2017. Additional detail provided in Attachment C – Agronomic Impacts and Mitigation

⁷ SAR and Sodium are managed together. If the measured SAR value exceeds 3 AND the measured sodium concentration exceeds a threshold of 69 mg/L, management will be necessary. SAR is derived from Ayers Table 1 and assumes surface irrigation. The sodium threshold is also derived from Ayers Table 1 and suggests that irrigation waters <3 meq/L (69 mg/L) is suitable for crops that are sprinkler irrigated.

Key:

μ S/cm = microsiemens per centimeter (1 μ S/cm = 1 μ hos/cm = 1/1,000 dS/m)

ASCE = American Society of Civil Engineers

Cl_{et} = maximum chloride threshold of the saturated soil paste

EC = electrical conductivity of applied water

EC_{et} = Soil salinity threshold for a given crop

FAO = Food and Agriculture Organization of the United Nations

Friant Division = Friant Division of the Central Valley Project

mg/L = milligrams per liter

SAR = sodium adsorption ratio

TDS = total dissolved solids

Table 4: Friant-Kern Canal Water Quality Constituents Short List

Constituent	Units	Thresholds
1,2,3 TCP	(µg/L)	0.005
Arsenic	(mg/L)	0.010
Bicarbonate	(mg/L)	--
Boron	(mg/L)	See Table 3
Bromide	(mg/L)	--
Calcium	(mg/L)	--
Chloride	(mg/L)	See Table 3
Chromium, total	(mg/L)	0.05
Hexavalent chromium	(mg/L)	0.010
Iron	(µg/L)	300
Magnesium	(mg/L)	--
Manganese	(µg/L)	50
Nitrate	(mg/L)	10
pH		--
SAR		See Table 3
Salinity (as EC)	(µS/cm)	See Table 3
Selenium	(µg/L)	2
Sodium	(mg/L)	See Table 3
Sulfate	(mg/L)	500
TDS	(mg/L)	-- *
Total Organic Carbon	(mg/L)	--
TSS	(ppm)	See Table 3
Turbidity	(NTU)	See Table 3
Gross alpha	pCi/L	15

Notes:

Thresholds are Title 22 MCLs unless otherwise noted.

Constituent with threshold denoted as "--" do not have an established MCL.

Refer to Table 1 and Notes for Table 1 for additional details.

*TDS MCL not listed for the purposes of these Guidelines. TDS and EC are both a measure of salinity and the EC thresholds shown in Table 3 are controlling.

Attachment A. Water Quality Advisory Committee Charter

Background and Objective

The Guidelines for Accepting Water into the Friant-Kern Canal (“Guidelines”) were adopted by the Friant Water Authority (FWA) based on the voluntary consensus of and written agreement with a significant majority of the contractors of the Friant Division of the Central Valley Project (“Friant Division”). The Guidelines address concerns regarding the implementation of programs and projects that could introduce water of a lesser quality to the Friant-Kern Canal (“FKC”), when compared to water quality of historic deliveries from Millerton Lake. The Guidelines include water quality constituent thresholds based on agronomic principles and a ledger mechanism to determine the required mitigation for introducing water of lesser quality into the FKC.

The Guidelines provide that FWA will appoint a Water Quality Advisory Committee (“Committee”) composed of Friant Division long-term contractors (“Friant Contractors”) involved in either introducing water to or receiving water from the FKC. The Committee will provide recommendations to FWA and Reclamation on operations and water quality monitoring requirements of the FKC as well as potential revisions to the Guidelines. This document describes Committee membership and Committee roles and responsibilities.

Water Quality Advisory Committee Membership

The appointed Committee will be composed of Friant Contractors who may either be introducing water to or receiving water from the FKC. Committee membership is described in Table 1. New members in replacement of an existing member or as a new addition to the membership list requires majority approval following notice to and the consent of the FWA Board of Directors.

Table 1. Water Quality Advisory Committee Membership

Members
Arvin-Edison Water Storage District
Delano-Earlimart Irrigation District
Kern-Tulare Water District

Lindsay Strathmore Irrigation District
Lower Tule River Irrigation District
Pixley Irrigation District
Porterville Irrigation District
Saucelito Irrigation District
Shafter Wasco Irrigation District
South San Joaquin Municipal Utility District
Terra Bella Irrigation District

Roles and Responsibilities

The Committee will convene on an annual basis prior to the irrigation season or planned reverse flow operations. The Committee will:

- Evaluate current year operations related to Guidelines implementation including but not limited to Ledger operation modifications, potential schedule changes, and potential changes to mitigation deliveries.
- Review and approve annual monitoring.
- Make recommendations regarding the costs and budgets associated with administering and implementing the Guidelines.

The Committee may also convene on an as needed basis under the following conditions:

- When Friant Division Class 1 contract allocation is less than or equal to 25 percent.
- If a future regulatory cost or equivalent fee is imposed on Friant Contractors and a portion of such fee can reasonably be attributed to the incremental difference of water quality conditions in the FKC.
- If there is a significant, scientifically based justification and three out of the following five water contractors agree that a change to Guideline principles and/or criteria should be discussed: Arvin-Edison Water Storage District, Shafter Wasco Irrigation District, Delano-Earlimart Irrigation District, South San Joaquin Municipal Utility District, or Kern-Tulare Water District.

- If FKC water quality continuously exceeds one or more constituent thresholds and pump-in operations must cease.

The Committee will make recommendations to the FWA Board via consensus decision making. If 100% consensus cannot be reached, a recommendation will be made, and minority viewpoints will also be communicated. The Committee will provide all recommendations to the FWA Board. Single-year modifications to Guidelines implementation, monitoring, and/or pump-in operations will be noticed to all Friant Contractors. Recommendations requiring substantial modifications or updates to the Guidelines will be provided to the FWA Board and the FWA will coordinate with Reclamation to implement recommended changes.

Monitoring Subcommittee

The Committee will appoint at least three and no more than five representatives of its members to serve on a Monitoring Subcommittee that will coordinate with FWA on the implementation of the Guidelines particularly with respect to potential or actual exceedance of the water quality thresholds established under these Guidelines and the implementation of required mitigation, including the reduction of discharges of Non-Millerton water into the FKC. The Subcommittee will make recommendations to FWA in accordance with Section B.2.d above, but the final operational decisions will be made by FWA.

Attachment B. Monitoring Program Summary

Summary of requirements for monitoring campaign specified in the Guidelines for Accepting Water into the Friant-Kern Canal

Sample Source/Type		Trigger	Constituents/Bacterial Organisms	Frequency	Location	Communication
Source of Discharge Water						
1	Non-Millerton Lake Source	Routine sampling.	All in Table 1	Every three years	Discharge Location.	Reported to FWA and Reclamation FKC's Contracting Office for review. FWA will report to Friant contractors.
2	Non-Millerton Lake Source	Routine sampling.	All in Table 4	Annually	Discharge Location.	
3	Non-Millerton Lake Source	If routine sampling of Table 4 water quality constituents shows exceedance of an established threshold buffer. **	Any in Table 4 exceeding the established threshold buffer.	Weekly for targeted constituents of concern, until four consecutive tests show consistent water quality results.	Discharge Location.	
4	Non-Millerton Lake Source	Reclamation on a case-by-case basis per condition of program operations.	Any	Any	Any	
Blended Canal Water						
5	FKC Water	Routine sampling (continuous).	EC	Real-time, Every 15 minutes	Check structures and mile posts in Table 2	Uploaded to FWA's IOS. FWA will regularly calibrate equipment.
6	FKC Water	If Friant Water Quality Model forecasts exceedance of an established threshold buffer. **	Any in Table 4 exceeding the established threshold buffer.	Weekly. Until sampled data, supported through modeling, show four consecutive tests below the established threshold buffer.	Check structures and mile posts in Table 2, where water quality changes are expected.	FWA will deliver to ELAP certified lab. Forecasted and measured in-prism water quality will be communicated by FWA to Friant contractors.
7	FKC Water	Specific operation disruptions (servicing of real-time equipment, unexpected outages, etc.).	EC	Any	Any	
8	CVC	Reverse-flow, and pump-back operations.	All in Table 4	Weekly	CVC, near Intertie	FWA will deliver to ELAP certified lab. Water quality data will be communicated via FWA's IOS.
9	CVC	Initiation of pump-back operations, and/or anticipated that CVC operations will significantly change water quality	All in Table 1 and Table 4	As needed	CVC, near Intertie	FWA will deliver to ELAP certified lab. Water quality data will be communicated via FWA's IOS.

Notes: References to tables above (Table 1, 2, 4) from Friant Water Authority draft Guidelines for Accepting Water into the Friant-Kern Canal.

**Threshold buffers that will trigger continued monitoring are 80% of the thresholds established in Table 4.

Key:

EC = electrical conductivity

CVC = Cross Valley Canal

ELAP = Environmental Laboratory Accreditation Program

FKC = Friant-Kern Canal

IOS = Intellisite Operation System

Reclamation = U.S. Department of the Interior, Bureau of Reclamation

Attachment C. Agronomic Impacts and Mitigation

CONTENTS

BACKGROUND	1
AGRONOMIC EFFECTS	1
Salinity Effects on Crops	3
Toxic Ion Effects	3
Chloride	3
Boron	3
Sodium	4
Infiltration Hazard.....	5
Sodium Adsorption Ratio.....	5
Calcium-Magnesium Ratio.....	6
pH and Bicarbonate Effects	7
Corrosion and Degradation of Materials	8
AGRONOMIC LEACHING REQUIREMENTS.....	9
Leaching Fraction vs Leaching Requirement	9
Limitations to the Steady-state Leaching Concept.....	11
Difference Between Maintenance Leaching and Reclamation Leaching	11
Leaching and Nitrogen Management.....	12
MITIGATION LEACHING REQUIREMENTS	13
Estimating Leaching Requirements for Most Sensitive Crops	13
Developing Mitigation Leaching Curves	15
Leaching Requirement Normalization	17
Normalization Method.....	18
APPLIED AGRONOMIC THRESHOLDS	21
Regulated Deficit Irrigation	23
Hull Rot Control	23
Regulated Deficit Irrigation Analysis	23
Water Quality Thresholds	24
Chloride and Electrical Conductivity Thresholds	24
Chloride Threshold Flexibility	27
Boron Thresholds.....	28
Turbidity and Total Suspended Solids Thresholds	29
SAR and Sodium Thresholds	30
REFERENCES	31

FIGURES

Figure 1. Comparison of Various Water Source Relationship between the Salinity of Applied Irrigation Water and the Adjusted Sodium Adsorption Ratio	6
Figure 2. Relationship Between Soil Salinity (EC_e) and Salinity of the Applied Irrigation Water (EC_w) under a Series of Steady-State Leaching Fractions (0.05 to 0.80) (from Ayers and Westcot, 1985)	9
Figure 3. Reclamation Leaching Function under Sprinkler Irrigation or Intermittent Ponding (Ayers and Westcot, 1985).....	12
Figure 4. Leaching Requirement for Electrical Conductivity.....	16
Figure 5. Leaching Requirement for Chloride	16
Figure 6. Leaching Requirement for Boron	17
Figure 7. Rootzone Leaching Curves for Electrical Conductivity, Chloride, and Boron Normalized to an Electrical Conductivity	18
Figure 8. Proposed Mitigation Rating Curve based on Boron Sensitivity and Normalized to Electrical Conductivity	18
Figure 9. Normalized Leaching Requirement curves for Electrical Conductivity, Chloride, and Boron.....	19
Figure 10. Chloride water quality trends by source water and year type with proposed water quality thresholds.....	28

TABLES

Table 1. Average Concentrations of Various Irrigation Water Quality Constituents 1

Table 2. Average Monthly Electrical Conductivity, Chloride, and Boron Concentrations by Source and Year Type2

Table 3. Critical SAR of Applied Irrigation Water4

Table 4. Seasonal Average SAR for Various Water Sources.....5

Table 5. Seasonal Average Calcium-Magnesium Ratio for Various Water Sources.....7

Table 6. Concentration Factor Values for Conventional and High Frequency Irrigation (adapted from Suarez, 2012).....10

Table 7. Percentage and Area of Sensitive Crop Types within Representative Water Districts.....14

Table 8. Leaching Requirements for Various Sensitive Crops by Water Source and Water Quality Constituent15

Table 9. Constituent Normalization.....20

Table 10. Friant-Kern Canal In-Prism Water Quality Thresholds22

Table 11a. Regulated Deficit Irrigation Analysis for Chloride26

Table 11b. Regulated Deficit Irrigation Analysis for Electrical Conductivity26

Table 12. Boron Tolerance of Various Crops29

ACRONYMS AND ABBREVIATIONS

$\mu\text{mhos/cm}$	micromhos per centimeter ($1 \mu\text{mhos/cm} = 1 \mu\text{S/cm} = 1/1,000 \text{ dS/m}$)
$\mu\text{S/cm}$	microsiemens per centimeter ($1 \mu\text{S/cm} = 1 \mu\text{mhos/cm} = 1/1,000 \text{ dS/m}$)
Ad hoc Committee	Ad hoc Water Quality Committee
AEWSD	Arvin-Edison Water Storage District
ATP	adenosine triphosphate
AW	applied water
B	boron
B_e	boron concentration of the saturated soil paste (rootzone boron)
B_{et}	maximum boron threshold of the saturated soil paste
B_w	boron concentration of applied irrigation water
B_{sw}	boron threshold for soil water concentration
Ca	calcium
Ca^{2+}	calcium ion
CaCO_3	calcite or calcium carbonate
cfs	cubic feet per second
Check 21	Check Structure 21 at milepost 172,40 on the California Aqueduct
Cl^-	chloride ion
Cl_e^-	chloride concentration of the saturated soil paste (rootzone chloride)
Cl_{et}^-	maximum chloride threshold of the saturated soil paste
Cl_w^-	chloride concentration of applied irrigation water
CO_2	carbon dioxide
CO_3^{2-}	carbonate ion
CVC	Cross Valley Canal
DEID	Delano-Earlimart Irrigation District
dS/m	deciSiemens per meter ($1 \text{ dS/m} = 1,000 \mu\text{mhos/cm} = 1,000 \mu\text{S/cm}$)
EC	electrical conductivity
EC_e	electrical conductivity of the saturated soil paste (rootzone salinity)
EC_{dw}	electrical conductivity/salinity of irrigation drainage water
EC_w	electrical conductivity/salinity of applied irrigation water
ET	evapotranspiration
F_c	concentration factor
FKC	Friant-Kern Canal
Friant Division	Friant Division of the Central Valley Project
FWA	Friant Water Authority

HCO_3^-	bicarbonate
Intermediate	Water quality representing the average of California Aqueduct Check 21 and Cross Valley Canal water qualities
KTWD	Kern Tulare Water District
LF	leaching fraction
LR	leaching requirement
Mg^{2+}	magnesium ion
Mg	magnesium
meq/L	milliequivalents per liter
mg/L	milligrams per liter (equivalent to ppm)
Na^+	sodium ion
Na	sodium
pH	Measure of acidity or alkalinity
Policy	Friant-Kern Canal Water Quality Policy
ppm	parts per million (equivalent to mg/L)
RDI	regulated deficit irrigation
SAR	sodium adsorption ratio
SAR_{adj}	adjusted sodium adsorption ratio
SID	Saucelito Irrigation District
SSJMUD	South San Joaquin Municipal Utility District
SWID	Shafter-Wasco Irrigation District
TDS	total dissolved solids

BACKGROUND

The Guidelines for Accepting Water into the Friant-Kern Canal (Guidelines) were developed in response to concerns regarding the implementation of programs and projects that could introduce water of a lesser quality to the Friant-Kern Canal (FKC), when compared to water quality of historic deliveries from Millerton Lake. The Guidelines define requirements for discharging water into the FKC, water quality monitoring and reporting requirements, mitigation requirements, and forecasting and communication protocols. The Guidelines propose a ledger mechanism to determine the required mitigation for introducing water of lesser quality into the FKC. This attachment to the Guidelines provides additional information on agronomic effects, mitigation requirements, and approach for defining maximum water quality thresholds for key constituents. The thresholds are specific to irrigation periods that correspond to the growing season and agricultural management practices during the year.

AGRONOMIC EFFECTS

When assessing the suitability of water for irrigation, three main hazards or “agronomic thresholds” are considered (Ayers and Westcot, 1985): (1) the salinity hazard (electrical conductivity of the applied irrigation water [EC_w]), (2) the hazard posed by specific ions (chloride [Cl⁻], boron [B], and sodium [Na⁺]), and (3) the infiltration hazard (sodium adsorption ratio [SAR] and EC_w). There are other parameters, such as acidity (pH) or alkalinity, sediments and nutrients that can affect calcite (CaCO₃) deposits, emitter clogging, crop development, and corrosion, but these do not fall under “agronomic thresholds.”

The primary source of imported water is proposed to come from the Friant-Kern Canal/Cross Valley Canal Intertie (Intertie) and conveyed via reverse-flow, pump-back operations. Water being introduced at the Intertie might include previously banked groundwater of Kern Fan water quality, Cross Valley Contract supplies, recaptured and recirculated San Joaquin River Restoration Program Restoration Flows, and other colors. Water quality conditions from the Cross Valley Canal (CVC) could range from existing conditions in the Cross Valley Canal (CVC) to that from the California Aqueduct, depending on respective canal operations. For the analysis presented herein, both CVC and California Aqueduct (measured at Check 21) water qualities were used, as well as a weighted average of those two sources (Intermediate) applied to show the range of potential imported water qualities. Source water quality concentrations are shown in Table 1 and Table 2.

Table 1. Average Concentrations of Various Irrigation Water Quality Constituents

LOCATION	WATER QUALITY CONSTITUENTS			
	TDS (/L)	EC _w (µS/cm)	Boron (B) (mg/L)	Chloride (Cl ⁻) (mg/L)
FKC ^{1, 2}	24	40	0.04	1.9
CVC ^{1, 3}	180	340	0.11	45.0
Intermediate ⁴	232	420	0.16	63.2
Check 21 ⁵	283	500	0.21 ⁶	81.3

Note:

¹ Water quality data from AEWS D grab samples lab data from 2010 – 2019. Averages exclude months when mixing occurred.

² Sample taken at terminus of FKC.

³ Sample taken at AEWS D CVC, Pumping Plant 6 or 6B Forebay.

⁴ Weighted average of CVC and Check 21 water quality.

⁵ California Aqueduct measured at Check 21 from 2009-2017.

⁶ Check 21 Boron measurements only available for years 1967 – 1976.

Key:

AEWS D = Arvin Edison Water Storage District

Check 21 = Check Structure 21 at milepost 172.40 on the California Aqueduct

CVC = Cross Valley Canal

µS/cm = microsiemens per centimeter (1 µS/cm = 1 µmhos/cm = 1/1,000 dS/m)

EC_w = electrical conductivity of applied water

FKC = Friant-Kern Canal

Intermediate = Water quality representing the average of California Aqueduct Check 21 and Cross Valley Canal water qualities

mg/L = milligrams per liter

TDS = total dissolved solids

Table 2. Average Monthly Electrical Conductivity, Chloride, and Boron Concentrations by Source and Year Type

MONTH	CVC ¹			CHECK 21 ²		
	Wet ³	Average ⁴	Dry ⁵	Wet ⁶	Average ⁴	Critical ⁷
Average Monthly Electrical Conductivity Concentrations by Source and Year Type (µS/cm)						
January	431	369	287	309	523	598
February	570	433	378	269	551	680
March	261	273	275	248	545	671
April	240	270	277	255	500	616
May	--	306	306	195	479	575
June	385	384	383	174	471	597
July	257	292	307	206	385	542
August	286	308	335	249	425	643
September	323	326	329	247	524	689
October	429	360	315	539	573	628
November	396	356	330	480	529	614
December	368	349	337	532	554	624
Average Monthly Chloride Concentrations by Source and Year Type (mg/L)						
January	74.5	54.4	27.7	34.0	84.5	99.0
February	104.0	63.0	46.6	31.5	87.4	104.3
March	21.0	21.8	22.0	27.5	82.9	104.3
April	19.0	21.4	22.0	33.5	72.1	100.0
May	--	31.4	31.4	25.0	73.0	88.7
June	48.5	46.1	45.2	19.0	73.4	98.3
July	28.5	33.7	35.8	25.5	55.8	84.0
August	39.6	40.7	42.0	31.0	70.3	109.0
September	53.0	48.4	43.8	22.0	92.6	116.7
October	76.0	55.0	41.0	105.5	101.6	106.7
November	68.5	54.8	45.7	90.5	86.8	95.7
December	55.5	46.7	40.8	101.0	95.5	103.0
Average Monthly Boron Concentrations by Source and Year Type (mg/L)⁸						
January	0.12	0.11	0.10	0.23	0.20	0.20
February	0.16	0.15	0.14	0.30	0.26	0.25
March	0.10	0.11	0.11	0.33	0.31	0.30
April	0.11	0.12	0.12	0.30	0.29	0.10
May	--	0.12	0.12	0.27	0.25	0.20
June	0.16	0.15	0.14	0.20	0.18	0.20
July	0.11	0.11	0.12	0.13	0.16	0.20
August	0.09	0.10	0.12	0.10	0.19	0.20
September	0.08	0.09	0.11	0.10	0.16	0.10
October	0.11	0.10	0.09	0.25	0.19	0.15
November	0.11	0.11	0.11	0.20	0.18	0.15
December	0.11	0.11	0.12	0.20	0.19	0.15

Note:

¹ Water quality data from AEWS D grab samples lab data from 2010 – 2019.

² California Aqueduct measured at Check 21 from 2009-2017.

³ CVC wet year averages represent the monthly average for San Joaquin Index year types below normal, above normal, and wet and excludes months where there is mixing.

⁴ Average concentrations shown represent the average of all year types and excludes months where there is mixing.

⁵ CVC dry year averages represent the monthly average for San Joaquin Index year types dry and critical and excludes months where there is mixing.

⁶ Check 21 wet year averages represent the monthly average for San Joaquin Index wet year types only.

⁷ Check 21 critical year averages represent the monthly average for San Joaquin Index critical years only.

⁸ Check 21 Boron measurements represent years 1967 – 1976 per available data.

Key:

-- = no available data. CVC water quality in wet years during May were only mixed water quality.

AEWS D = Arvin-Edison Water Storage District

Check 21 = Check Structure 21 at milepost 172,40 on the California Aqueduct

CVC = Cross Valley Canal

µS/cm = microsiemens per centimeter (1 µS/cm = 1 µmhos/cm = 1/1,000 dS/m)

mg/L = milligrams per liter

SALINITY EFFECTS ON CROPS

The effects of salinity on crops are due to two separate properties in the saline media that can impact the crop individually but more often collectively (Läuchli and Grattan, 2012): (1) Salinity increases the electrical conductivity (EC) of the soil solution which reduces its the osmotic potential and (2) specific ions (i.e. Cl^- , Na^+ and B) in the soil solution can potentially be toxic to certain crops.

Osmotic effects occur when the concentration of salt in the soil solution is too high to allow for normal for crop growth. Dissolved salts reduce the osmotic potential of the soil solution. Plants must adjust osmotically through either the absorption of ions from the soil solution, or the synthesis and/or accumulation of organic solutes in the root cells. The synthesis of compatible organic solutes allows a plant to adjust osmotically and survive, but at the expense of plant growth (Munns and Tester, 2008). The synthesis of organic solutes requires a considerable amount of metabolic energy (i.e., adenosine triphosphate (ATP)) that is used for cell maintenance and osmotic adjustment that could otherwise be used for growth. As a result, salt-stressed plants are stunted, even though they may appear healthy in all other regards. Both processes of adjustment (accumulation of ions and synthesis of organic solutes) occur but the extent by which one process dominates depends on the type of crop and level of salinity (Läuchli and Grattan, 2012). And in a cell, compartmentalization is critical to keep toxic ions away from sensitive metabolic processes in the cytoplasm (Hasegawa et al., 2000). Such compartmentation is controlled by transport processes in the plasma membrane and tonoplast (i.e., vacuolar membrane). The efficiency of ion transport processes, as well as metabolic costs for organic-solute synthesis, differ from crop to crop and even within a species giving rise to different salinity tolerances.

TOXIC ION EFFECTS

Specific ions (i.e., Na^+ , Cl^- , and B) in the soil solution can cause direct injury to crops, causing further crop damage from what occurs from osmotic effects. Typically, toxic ion effects are commonly found in woody perennials, such as tree and vine crops, while most annual row crops remain injury free unless salinity stress is severe. Woody perennial crops have little ability to exclude sodium or chloride from their leaves, and the plants are long-lived; hence, they often suffer toxicities at even moderate soil salinities. Typically, toxic ion effects become more critical to sensitive tree and vine crops over the years.

Chloride

Chloride and sodium toxicity can damage a plant/tree physically, biochemically and physiologically. As sodium and chloride move in the transpiration stream, they are deposited in the leaves. Older leaves have more water transpire from them and consequently have higher concentrations of sodium and chloride. Once accumulated in a leaf, sodium and chloride typically do not remobilize to other tissues. As the concentration in that leaf increases, the salts can physically desiccate cells causing injury in the form of leaf burn. Necrotic leaves no longer photosynthesize and produce carbohydrates for the tree, which in turn, will impact growth and production. But even before salts accumulate in leaves to levels that cause physical injury, those salts can reduce the chlorophyll content in leaves (Dejampour et al., 2012) and interfere with enzymatic activities affecting key metabolic pathways in both respiration and photosynthesis (Munns and Tester, 2008).

Boron

Although not a main “salinizing” constituent in applied irrigation water, boron can also cause injury to the crop. Boron is an essential micronutrient for plants, but the concentration range of plant-available boron in the soil solution optimal for growth for most crops is very narrow. Above this narrow range, toxicity occurs (Grieve et al., 2012). Boron toxicity, including how and where it is expressed in the plant, is related to the mobility of boron in the plant. Boron is thought to be immobile in most species where it accumulates in the margins and tips of the oldest leaves where injury occurs. However, boron can be re-mobilized by some species due to high concentrations of sugar alcohols (polyols) where they bind with boron and carry it to younger tissues (Brown and Shelp, 1997). These boron-mobile plants include almond, apple, grape, and most stone fruits. For these crops, boron concentrations are higher in younger tissue than in older tissue, and injury is expressed in young, developing tissues in the form of twig die back, gum exudation, and reduced

bud formation. Boron-immobile plants such as pistachio, tomato, and walnut do not have high concentrations of polyols, and the boron concentrates in the margins of older leaf tissues. Injury in these crops is expressed as the classical necrosis on leaf tips and margins.

Sodium

Sodium can be problematic to a crop in several ways. It can be directly toxic to the plant, it can interfere with the nutritional status of the plant (e.g., Na⁺-induced calcium [Ca²⁺] deficiency), or it can indirectly affect the crop due to its adverse effect on soil structure. Some trees are very sensitive and can develop Na⁺ toxicity when concentrations of Na⁺ are as low of 5 milliequivalents per liter (meq/L) (115 mg/L) in the soil water. However, this observation was made before scientists realized the importance of adequate Ca²⁺ in the soil water for root membrane stability to maintain their selectivity for ion uptake. With adequate Ca²⁺, such as that provided by gypsum applications, sodium toxicity may never be observed in these sensitive trees at such low sodium concentrations. Therefore, rather than having a threshold for Na⁺ per se, the sodium-calcium ratio in the soil solution is a better indicator of Na⁺ toxicity. The SAR of the applied irrigation water has been used as a surrogate for the sodium-calcium ratio, and the general rule is an SAR < 3 is not problematic.

$$SAR = \frac{Na^+}{\sqrt{\frac{(Ca^{2+} + Mg^{2+})}{2}}}$$

Where Na⁺, Ca²⁺, and magnesium ion (Mg²⁺) concentrations are expressed in meq/L.

This is different when assessing sodium’s indirect effect on soil structural stability (see the Infiltration Hazard section that follows). Table 3 shows critical SAR of the applied irrigation water above which can cause injury or nutritional distress in sensitive crops. Table 4 shows the seasonal average SAR for various water sources.

Table 3. Critical SAR of Applied Irrigation Water

CROP ¹	CRITICAL SAR OF APPLIED IRRIGATION WATER
All Crops	< 3

Note:

¹ Many tree crops are sensitive to Na⁺ toxicity after several years when sapwood converts to heartwood releasing Na⁺ from the root to the shoot. Most annual crops are insensitive to Na⁺ per se provided there is sufficient Ca²⁺ in the soil solution to maintain membrane integrity and ion selectivity. Hence, the ratio of sodium to calcium is more critical (Grattan and Grieve, 1992).

Key

Ca²⁺ = calcium ions

Na⁺ = sodium ions

SAR = sodium adsorption ratio

Table 4. Seasonal Average SAR for Various Water Sources

VALUE ¹	FKC ^{2, 3}	CVC ^{2, 4}	INTERMEDIATE ⁵	CHECK 21 ⁶
Average	0.46	1.68	1.99	2.27
Maximum	0.87	2.04	2.46	2.96
Minimum	0.28	1.10	1.61	1.79

Note:

¹ March through October period.

² Water quality data from AEWS D grab samples lab data from 2011 – 2017.

³ Sample taken at terminus of FKC.

⁴ Sample taken at AEWS D CVC, Pumping Plant 6 or 6B Forebay.

⁵ Weighted average of CVC and Check 21 water quality.

⁶ California Aqueduct measured at Check 21 from 1968-2017.

Key

AEWS D = Arvin Edison Water Storage District

Check 21 = Check Structure 21 at milepost 172,40 on the California Aqueduct

CVC = Cross Valley Canal

FKC = Friant-Kern Canal


Intermediate = Water quality representing the average of California Aqueduct Check 21 and Cross Valley Canal water qualities

SAR = sodium adsorption ratio

INFILTRATION HAZARD

Sodium Adsorption Ratio

The SAR has been the standard used for assessing the infiltration hazard of applied irrigation water (Ayers and Westcot, 1985). But the actual infiltration hazard is assessed by balancing the opposite effects of salinity (EC_w) and sodicity (i.e., SAR) on aggregate stability. High salinity and low SAR are both important in maintaining adequate soil structure, which promotes better infiltration. Even though coarse-textured soils infiltrate faster than fine-textured soils, the hazard exists for all soil types. Typically, the adjusted SAR (SAR_{adj}) is used rather than the SAR as it more accurately accounts for $CaCO_3$, precipitation, and dissolution processes in the soil solution near the soil surface that control the free Ca^{2+} concentration. Figure 1 shows the relationship between the EC_w of the applied irrigation water and the SAR_{adj} as it relates to zones of “likely reductions” in infiltration rates (red), “slight to moderate reductions” in infiltration rates (yellow) and “no reductions” in infiltration rates (blue), adapted from Hanson et al., 2006. The threshold value is, therefore, variable and is considered to be the line that separates the “blue” and “yellow” zones on Figure 1. It is very important to note that low EC_w concentration (i.e., $EC_w < 200 \mu S/cm$) causes a reduction in water infiltration regardless of the SAR. Figure 1 also compares this relationship with various water sources. Note that FKC water falls in the red “severe reduction in infiltration” zone because of its low EC_w concentration, while water from the CVC or mixed with CVC water falls in the yellow “slight to moderate reduction in infiltration” zone. The addition of gypsum to FKC water increases the EC_w concentration, moving the point to the right and away from the “severe reduction in infiltration” zone while slightly reducing the SAR.



Key:
 $\mu\text{S/cm}$ = microsiemens per centimeter
 Check 21 = California Aqueduct Check 21
 CVC = Cross Valley Canal
 FKC = Friant-Kern Canal
 Intermediate = Water quality representing the average of California Aqueduct Check 21 and Cross Valley Canal water qualities

Figure 1. Comparison of Various Water Source Relationship between the Salinity of Applied Irrigation Water and the Adjusted Sodium Adsorption Ratio

Calcium-Magnesium Ratio

Calcium nutrition can be problematic under several conditions. Calcium deficiency can occur under low-saline conditions when the concentration of free calcium $[\text{Ca}^{2+}]$ is $\leq 1\text{-}2$ millimoles/L in the soil solution. Deficiency can also occur under high sodic conditions where the SAR exceeds 10-15 in sensitive plants due to high sodium-calcium ratios or in alkaline conditions where Ca^{2+} precipitates out of the soil solution as it forms CaCO_3 . Due to competition in the plant between calcium and magnesium at the root membrane, calcium nutrition could potentially be compromised when the calcium-magnesium ratio is generally less than 1 (Rhoades, 1992). Table 5 shows the seasonal average calcium-magnesium ratio for various water sources. Note the ratios for both FKC and CVC water are considerably higher than 1, while the ratio at California Aqueduct Check 21 is very close to 1 but will likely increase in the soil solution as the infiltrating water dissolves existing gypsum in the soil from previous amendment use. Therefore, calcium deficiencies, using CVC or Check 21 water or any mixture of the two, are unlikely.

Table 5. Seasonal Average Calcium-Magnesium Ratio for Various Water Sources

VALUE ¹	FKC, ^{2 3}	CVC ^{2, 4}	INTERMEDIATE ⁵	CHECK 21 ⁶
Average	3.54	4.37	1.55	0.92
Maximum	6.16	8.24	2.00	1.00
Minimum	0.17	2.14	1.20	0.77

Note:
 Based on molar or equivalent concentrations.
¹ March through October period.
² Water quality data from AEWSD grab samples lab data from 2011 – 2017.
³ Sample taken at terminus of FKC.
⁴ Sample taken at AEWSD CVC, Pumping Plant 6 or 6B Forebay.
⁵ Weighted average of CVC and Check 21 water quality.
⁶ California Aqueduct measured at Check 21 from 1968-2017.
 Key
 AEWSD = Arvin Edison Water Storage District
 Check 21 = Check Structure 21 at milepost 172,40 on the California Aqueduct
 CVC = Cross Valley Canal
 FKC = Friant-Kern Canal
 Intermediate = Water quality representing the average of California Aqueduct Check 21 and Cross Valley
 Canal water qualities
 SAR = sodium adsorption ratio

BICARBONATE EFFECTS

The pH of both the applied irrigation water and the soil solution are important factors that may affect either the suitability of water for irrigation or its effect on nutrient availability to the crop. And many of the adverse effects of pH are associated with combined high alkalinity (high concentrations of bicarbonate [HCO₃⁻] and carbonate [CO₃²⁻]). In slightly alkaline waters (pH 7- 8.3), the alkalinity is from bicarbonate. Only when the pH exceeds 8.3 does carbonate become present. The pH of the water is an indication of the activity of the hydrogen ion. The numerical pH value is expressed on a negative log scale such that a one-unit increase or decrease corresponds to a ten-fold increase or decrease in the hydrogen ion activity. Therefore, a change of soil pH from 6 to 8 corresponds to a hundred-fold decrease in the hydrogen ion activity.

The pH of applied irrigation water can affect irrigation equipment or cause calcite (i.e. lime) deposits on vegetation. Regarding irrigation equipment, the pH is one of several water quality factors than can influence corrosion of galvanized pipes or other metallic parts. The pH can also influence precipitation of calcite (CaCO₃) at the orifices of drip emitters or minisprinklers which will affect the system's overall performance. This can be problematic if alkaline irrigation water, combined with sufficiently high bicarbonate and calcium concentrations, is used over the long term without periodic acid flushes to reduce scale buildup. Calcite precipitation becomes more problematic if the pH of the applied irrigation water exceeds 8.5. In addition, if such water is sprinkler irrigated above the canopy, it can cause unsightly white deposits that form on leaves and fruit. While these deposits typically do not cause harm to the crop, they nonetheless can affect the aesthetic quality. Acid additions to the irrigation water will not only reduce the pH but will reduce the [HCO₃⁻], reducing the potential for CaCO₃ precipitation. Acid additions convert bicarbonate to carbon dioxide (CO₂) gas.

As the applied irrigation water infiltrates the soil, it interacts with the soil minerals. Therefore, the pH of the infiltrating water will change as it interacts with soil minerals, but soils are typically well buffered, as are soils in the FWA service area. Well buffered soils resist large changes in pH in the soil solution. The seasonal average pH of the irrigation water ranges from 7.1 to 8.4 depending upon the mixture of FKC water and California Aqueduct water. Because of the buffering capacity of the soil, this range in applied irrigation water pH will make little impact of the pH of the soil solution.

The pH of the soil solution has a profound influence on plant nutrient availability, nutrient uptake and ion toxicity to plants. The vast majority of soils that are cultivated for crop production around the world fall within the neutral, slightly acid and slightly basic pH range (i.e. pH 6-8). This is the general range where nutrient availability is optimal. However, there are those soils where the pH falls far from this normal range and these,

if not corrected to an adequate range, can pose adverse effects on crops. Soils that are highly acidic (pH < 5.5) or highly alkaline (pH > 8.5) present a spectrum of challenges for the plant including nutrient availability, ion toxicities, and nutrient imbalances influencing the ion relations and nutrition within the plant itself (Läuchli and Grattan, 2012).

Most nutrients are not equally available to plants across the pH spectrum (Epstein and Bloom, 2005). Several mineral nutrients are severely affected in these non-optimal pH soils, particularly calcium, potassium, phosphorus, and iron. The reactions of plants to these nutrient elements under extreme soil pH conditions can affect plant growth, physiological processes and their morphological development (Läuchli and Grattan, 2012). The majority of the soils irrigated with waters from districts within the FWA, however, fall in the slightly alkaline range with the pH in the rootzone between 7.5 and 8.3 (UC Davis Soilweb <https://casoilresource.lawr.ucdavis.edu/gmap/>). Therefore, these soils are slightly alkaline, based largely on the natural abundance of calcite in the soil, and are at the upper end of the optimal pH range. Depending on the alkalinity of the soil water and $[Ca^{2+}]$, some of the Ca^{2+} can precipitate out as $CaCO_3$ which decreases the calcium-magnesium ratio. Intermittent injection of acids in the applied irrigation water will reduce the pH and, consequently, the alkalinity of the water. Not only is this a maintenance measure to reduce calcite buildup on the orifices of drip emitters and minisprinklers, it drops the pH of the water which decreases bicarbonate, increases the $[Ca^{2+}]$ and availability of other plant nutrients. Most growers in the San Joaquin Valley have some maintenance, acid-injection program in place. However, in Kern county, this may not be common practice in all districts. Acid applications, the residual gypsum in the soil and periodic applications of additional gypsum, are all a means of providing sufficient free Ca^{2+} in soils in Kern country. Moreover, increasing the $[Ca^{2+}]$ in the soil water simultaneously improves the calcium-magnesium ratio.

Sprinkler irrigated fruit and vegetable crops (approximately 20% of studied districts) could be susceptible to formation of white deposits on leaves and fruit, or “white wash,” and reduced marketability if bicarbonate concentrations, or $[HCO_3^-]$, in applied irrigation water are too high (> 1.5 meq/L, leaving a white residue on the crop surface. Bicarbonate concentrations in the California Aqueduct water theoretically could cause “white washing” under sprinkler irrigation, especially during dry and breezy conditions. “White washing” is a concern to some growers and has been seen by growers occasionally in the study area; however, it is not known what the exact cause of the “white washing” was, whether it was from undiluted California Aqueduct water or some other source. Bicarbonate levels of 1.5 meq/L or 92 mg/L and higher may increase formation of white deposits. The seasonal average for $[HCO_3^-]$ of CVC water is 78.5 mg/L. While this concentration is less than 92 mg/L, special management practices may be needed to mitigate or avoid “white wash” impacts during periods of elevated bicarbonate levels. These may include blending with higher quality sources or changing irrigation methods away from sprinklers that wet the foliage (Provost & Pritchard, 2012).

CORROSION AND DEGRADATION OF MATERIALS

The comparison of corrosion potential of California Aqueduct water and FKC water from Millerton Lake was performed by Provost & Pritchard in 2012 on several chemical constituents and calculated indices including: pH, Langelier Index, Ryzner Index, EC, resistivity, sulfates, and chlorides. This comparison generally showed that FKC water has a slight tendency to degrade concrete structures by leaching out minerals, but metallic corrosion will be low. Comparatively, California Aqueduct water will have a lower tendency to leach out minerals from concrete, and will have a more corrosive effect on metals, although there is only a slight difference between the two water sources in either case (Provost and Pritchard, 2012).


Materials such as brass, bronze, PVC, polyethylene, and stainless steel usually have a high corrosion tolerance, and therefore would not likely be affected by the exchange of source waters. The forecasted increase in corrosion from using more California Aqueduct water is likely manageable with the use of special coatings and proper selection of new materials and would likely result in minor increase in O&M costs (Provost and Pritchard, 2012).

AGRONOMIC LEACHING REQUIREMENTS

Agronomic leaching is the application of irrigation water in excess of the soil water holding capacity to neutralize the agronomic effects associated with increased salinity and ion toxicity in the crop rootzone. This approach aims to balance concerns related to long-term groundwater quality with a multi-layered assessment of agronomic impacts as a durable solution. The amount of leaching required, referred herein as maintenance leaching, depends upon the sensitivity of the crop to salinity and the irrigation water salinity. The higher the salinity of the applied irrigation water and the more sensitive the crop is to salinity, the greater the amount of leaching is required. This same leaching concept can also be applied to chloride and boron.

LEACHING FRACTION VS LEACHING REQUIREMENT

Often, leaching fraction (LF) and leaching requirement (LR) are used interchangeably. The two, in fact, are different. The LF is defined as the volume of water that drains below the rootzone divided by the volume of water that infiltrates the soil surface (equivalent to applied irrigation water assuming no surface runoff or evaporation). The LF can also be estimated based on the salinity of the applied irrigation water, or $[EC_w]$, and that of the drainage water, or $[EC_{dw}]$, where $LF = EC_w / EC_{dw}$. The crop roots extract water from the rootzone leaving the salts behind. If the crop rootzone is divided in quarters, typically the top quarter uses 40% of the water, the second quarter 30%, third quarter 20% and bottom quarter 10%. Therefore, the salt concentration increases with soil depth. The lower the LF, the more salts accumulate and concentrate at lower depths. Figure 2 is a representation of this relationship under conventional irrigation. The relationship between irrigation water salinity (EC_w) and soil salinity (EC_e) is linear but the slopes of the relationships are dependent upon the LF. The slopes decrease with increasing LF. The higher the LF, the higher the irrigation water salinity can be to maintain the yield of a crop. In Figure 2, note the dashed lines along the y-axis indicating the general salt tolerant categories as the salinity of the applied irrigation water changes.



Key:
dS/m = deciSiemens per meter ($1 \mu\text{S}/\text{cm} = 1 \mu\text{mhos}/\text{cm} = 1/1,000 \text{ dS}/\text{m}$)
LF = leaching fraction

Figure 2. Relationship Between Soil Salinity (EC_e) and Salinity of the Applied Irrigation Water (EC_w) under a Series of Steady-State Leaching Fractions (0.05 to 0.80) (from Ayers and Westcot, 1985)

The LF concept is attractive in that it allows predictions of average rootzone salinity (EC_e) conditions from the applied irrigation water EC (EC_w) and assumed LF. Knowing the scientifically determined salinity threshold value (EC_{et}) for a particular crop, one can use this relationship to determine the maximum irrigation water salinity (EC_w) for a given LF. The relationship between EC_w , EC_e , and LF also depends on irrigation management. That is, $EC_e = \text{Concentration Factor } (F_c) * EC_w$ where ' F_c ' depends not only on the LF but the type of irrigation method. Applicable F_c values for conventional irrigation methods such as furrow or flood, and high frequency irrigation methods, such as drip and minisprinklers, are provided in Table 6.

Table 6. Concentration Factor Values for Conventional and High Frequency Irrigation (adapted from Suarez, 2012)

LEACHING FRACTION (LF)	CONCENTRATION FACTOR (F_c)	
	Conventional Irrigation	High Frequency Irrigation
0.05	2.79	1.79
0.10	1.88	1.35
0.20	1.29	1.03
0.30	1.03	0.87
0.40	0.87	0.77
0.50	0.77	0.70

The difference in F_c values between conventional and high frequency irrigation is largely based on how crop roots respond to the salinity in the rootzone. Under conventional irrigation, crops typically respond to the average rootzone salinity (i.e. the seasonal average of the four rootzone quarters of salinity). Under high frequency irrigation, crops respond to the water uptake weighted salinity (i.e. the salinity in the top quarter is weighted 40 percent, salinity in the second quarter is weighted 30 percent, and so on). Because the salinity in the top quarter is lower where evapotranspiration (ET) is higher and higher in bottom where ET is lower, the average rootzone salinity is lower under high frequency irrigation.

The LR, on the other hand, is the lowest LF needed to sustain maximum yield given the applied irrigation water salinity concentration, or $[EC_w]$, and yield threshold for the given crop. In other words, it is the minimum leaching needed, given the crop type and water quality, to maintain the salinity (or chloride or boron), at the maximum rootzone concentration in the rootzone that the crop can tolerate. Any increase in rootzone concentration above this maximum level will cause injury or yield reductions. LR is an attractive concept because, given an irrigation water quality and crop sensitivity, the minimum leaching needed to sustain the rootzone salinity EC_e , rootzone chloride (Cl_e), or rootzone boron (B_e) at levels that would avoid or reduce damage or yield losses can be estimated.

LR can be estimated using the following equation (Rhoades and Merrill, 1976; Ayers and Westcot, 1985):

$$LR\% = \frac{EC_w}{5(EC_{et}) - EC_w} \times 100$$

EC_w = Electrical conductivity of irrigation water

EC_{et} = Soil salinity threshold for a given crop

Note that the LR relationship can apply to chloride and boron by substituting their respective irrigation water concentrations (i.e. Cl_w or B_w) and their threshold values (Cl_{et} or B_{et}). The LR equation assumes that crops respond to an average rootzone salinity created by a 40-30-20-10% root water extraction pattern, similar to LF predictions using conventional irrigation. The difference is that LR predicts the minimal LF to achieve maximal yields whereas the LF approach assumes an LF first, then predicts what the EC_e will be given the EC_w of the irrigation water. Both are similar but solve the problem from different directions.

LIMITATIONS TO THE STEADY-STATE LEACHING CONCEPT

The leaching fraction or requirement is an attractive concept but has limitations. First, the leaching concept assumes steady-state conditions and thus has no time element. Therefore, there is no accounting for how long leaching will take, which will differ depending upon the permeability of the soils. Second, the evapotranspiration (ET) of the crop is assumed to be independent of the average rootzone salinity, but it is not (Letey and Feng, 2007). A salt-stressed crop will use less water than a non-stressed crop. Consequently, crop ET will be reduced, and leaching, with the same quantity of applied irrigation water, will be increased. And third, in drip irrigated fields, actual LFs are difficult to quantify because LF, soil salinity, soil water content, and root density all vary with distance and depth from the drip lines.

In light of these limitations, recent studies have shown that the EC_w and EC_e relations described by Ayers and Westcot (1985), which are based on steady-state LF conditions, tend to be too conservative and overestimate soil salinity and, therefore, overestimate yield losses in most cases (Corwin and Grattan, 2018; Letey et al., 2011). Transient-state models may more accurately predict soil salinity, as well as soil chloride, sodium and boron, but they are more complicated and require many more site-specific inputs and assumptions. Therefore, transient models are still too cumbersome and time consuming to replace steady-state models.

The LF and LR concepts are both steady-state, so they assume the amount of irrigation is not limiting. The amount of water needed for irrigation can be estimated as:

$$AW = ET/(1-LR)$$

AW = applied water

ET = evapotranspiration or crop water requirement

LR = leaching requirement

The units for applied water (AW) and ET or crop requirement are typically depths of water (i.e. inches or millimeters). But in many cases, the amount of water is limiting and therefore crops can be under-irrigated and therefore not achieve the required leaching. In this case, the salts in the crop rootzone will increase over time. At some point, depending upon the salinity of the imported water and crop sensitivity, the salt content (or chloride or boron) can exceed the threshold level. Because the threshold values are based on seasonal averages, exceedances above the threshold are allowed to some degree without experiencing a reduction in yield. For example, if the average Cl_e was 100 mg/L for the first 2/3 the season and then reached 200 mg/L for the last 1/3 of the season due to insufficient leaching, almonds on “Nemaguard” rootstock would not be expected to be damaged because the seasonal average Cl_e would be 133 mg/L given the Cl_e threshold is 150 mg/L. Nevertheless, if the required leaching is not achieved, reclamation leaching would be required. Similarly, if the preseason soil salinity is over 150 mg/L and little to no leaching is applied during the season, injury would be expected to develop on almonds on “Nemaguard” rootstock. Therefore, the LR values for various crops and salinities are based on soils where the maintenance leaching fraction is achieved each irrigation. If the pre-existing soil salinity is initially high, then the soil is not at steady-state.

DIFFERENCE BETWEEN MAINTENANCE LEACHING AND RECLAMATION LEACHING

There is a distinct difference between maintenance leaching and reclamation leaching. Maintenance leaching occurs during each irrigation by applying more irrigation water than the soil can hold. This is the leaching fraction or requirement concept described above. Therefore, the AW is higher than the ET to accommodate the necessary leaching (see equation above). Reclamation leaching, on the other hand, occurs at the end of the irrigation season by applying excess irrigation water to flush the salts from the crop rootzone. Ideally, reclamation leaching would not be required if correct maintenance leaching is achieved each irrigation during the irrigation season. However, because some fields may not get the necessary leaching, salts can accumulate, and fields may require reclamation leaching at some time. In addition, low pressure systems such as drip and mini-sprinkler systems produce characteristic salt accumulation patterns in fields, even with sufficient downward leaching. Whether salts are building up in the rootzone or between drippers or

minisprinklers, reclamation leaching is a valuable preventative measure from time to time at the end of the irrigation season.

At the end of the irrigation season, salt can be removed by sprinkler irrigation (i.e equivalent to intermittent ponding). Figure 3 shows the extent of leaching needed to address rootzone salinity. For example, if the average rootzone salinity (ECe) at the end of the season is 3000 $\mu\text{S}/\text{cm}$ and the goal is to reduce the salinity in the soil down to 600 $\mu\text{S}/\text{cm}$ the salinity needs to be reduced to $600/3000 = 0.2$ (y-axis) or 20% of what it was before leaching. Then the amount of sprinkler irrigation water to apply is 0.5 ft (x-axis) for every foot of soil to reclaim. If the goal is to reduce the top 2 feet, then $0.5 \times 2\text{ft} = 1\text{ft}$ of water would be needed. This assumes the combined rainfall and applied reclamation leaching water needed.




Figure 3. Reclamation Leaching Function under Sprinkler Irrigation or Intermittent Ponding (Ayers and Westcot, 1985).

The amount of reclamation leaching can be reduced by the amount of effective rainfall. To take advantage of rainfall, reclamation leaching should ideally take place after the rainfall season but before spring budding and leaf out begins, typically from October/November through March.

LEACHING AND NITROGEN MANAGEMENT

It is also important to address nitrogen management strategies combined with the salt leaching strategies. Unlike salts, nitrogen is very dynamic in the rootzone as it undergoes form changes from organic pools to inorganic fractions (primarily nitrate $[\text{NO}_3^-]$ and ammonium $[\text{NH}_4^+]$). Ammonium, and particularly nitrate, are the forms primarily taken up by plants. Nitrate, being an anion, is relatively mobile in soils and is highly susceptible to leaching below the rootzone. Once nitrate leaches below the rootzone, chemical transformations are less likely to occur, and nitrate commonly continues leaching downward and eventually ends up in the aquifers. A 2002 study conducted by the Lawrence Livermore National Laboratory concluded that nitrate contamination in groundwater is “the number-one contaminant threat to California’s drinking water supply” (LLNL 2002).

Rootzone salinity control and nitrogen management is a conflicting problem. It is necessary to leach salt from the rootzone to avoid damage from salinity or ion toxicity, but nitrates will unavoidably be leaching below the

rootzone as well. If soil salinity is low at the beginning of the irrigation season (see reclamation versus maintenance leaching), then leaching at less than the critical LR is possible to avoid salt damage. Then, salinity in the profile will steadily build up over the season while soil nitrogen will be depleted due to crop uptake. At the end of the irrigation season, salinity will be the highest, and nitrate will be the lowest. Therefore, reclamation leaching can be implemented at the end of the irrigation season, and the process cycle repeats itself.

MITIGATION LEACHING REQUIREMENTS

ESTIMATING LEACHING REQUIREMENTS FOR MOST SENSITIVE CROPS

The most sensitive crops in the Friant Division were used for this analysis. Crops selected were based on their varied sensitivities to salinity, chloride, and boron. By using the most sensitive crops, all crops with higher tolerances should also be protected. The most salt-sensitive crops, or those with the lowest soil salinity threshold (EC_{et}), are beans, carrots, onions (seed), melons, and strawberries. All have an EC_{et} of 1000 $\mu S/cm$. For chloride, the most sensitive crops are almonds and other stone fruits on “Nemaguard” rootstock. The threshold Cl_{et}^1 is estimated to be 150 mg/L. The relationship between boron in the applied irrigation water and the saturated soil paste is more complicated because of boron’s high affinity to adsorb onto the soil. Irrigation water with higher boron concentrations than predicted can be used until the boron saturates the soil adsorption sites. Because of this complexity, Ayers and Westcot (1985) concluded that the “...maximum concentration (of boron) in the irrigation water are approximately equal to these values (boron tolerance reported based on soil water bases) or slightly less,” suggesting that applied irrigation water tolerances would be 0.5 – 0.75 mg/L which would protect the most sensitive crops.. However, over the long term (more than several years), boron will behave similarly to salts and chloride (D. Suarez, US Salinity Laboratory, personal communication). With the boron threshold for soil water ranging from 0.5 – 0.75 mg/L, the B_{et} is equivalent to half of the soil water concentration, or 0.25 – 0.375 mg/L. For more information on conversions from saturated soil paste to soil water concentrations, see Ayers and Westcot (1985). To be conservative, and based on the above tree and vine crop sensitivities, the B_w threshold is assumed to be 0.25 mg/L.

Table 7 shows the acreage and percentage of sensitive crops for representative water districts, and sensitivities to boron, chloride, and EC within each representative water district.

¹ It is important to note that most ‘threshold’ values for chloride and boron reported in literature (e.g. Grieve et al., 2012) are based on the soil water concentration. The saturated soil paste concentration (i.e. Cl_e or B_e) for most mineral soils is about half this value over the long-term (Ayers and Westcot 1985).

Table 7. Percentage and Area of Sensitive Crop Types within Representative Water Districts

CROP TYPE	WATER DISTRICT											
	AEWSD		DEID		KTWD		SID		SSJMUD		SWID	
	%	Acres	%	Acres	%	Acres	%	Acres	%	Acres	%	Acres
Boron Sensitive⁵	15%	18,883	5%	2,842	30%	5,969	6%	1,211	8%	4,629	1%	358
Berries ¹	1%	761	2%	873	1%	200	n/a		<1%	63	n/a	
Cherries	2%	2,196	<1%	228	1%	160	<1%	22	<1%	211	1%	358
Citrus	11%	15,024	2%	1,301	28%	5,609	4%	825	7%	4,355	n/a	
Stone Fruits ⁴	1%	902	1%	440	n/a		2%	364	n/a		n/a	
Chloride Sensitive⁶	6%	7,593	22%	12,399	5%	1,040	17%	3,366	22%	13,577	56%	21,649
Almonds (Nemaguard rootstock)	6%	7,593	22%	12,399	5%	1,040	17%	3,366	22%	13,577	56%	21,649
EC Sensitive⁷	7%	8,490	<1%	175	n/a		<1%	50	1%	375	2%	862
Carrots	3%	3,748	<1%	100	n/a		n/a		<1%	148	2%	784
Melons ²	1%	777	<1%	74	n/a		<1%	50	n/a		<1%	75
Onions ³	3%	3,961	n/a		n/a		n/a		<1%	228	<1%	1
Strawberries	<1%	4	n/a		n/a		n/a		n/a		<1%	2

Source: Data compiled from California Department of Water Resources Land Use Viewer (2017) developed by LandIQ using 2014 land use data. Districts provided updates to 2017 land use data where appropriate. DEID data was provided by the District, and data gaps were filled with LandIQ data.

Notes:

Grape Crops in DEID take up 43% (26,443 ac) of the District's land area.

"n/a" indicates that there is zero amount of a crop type in a district.

¹ Data Source lists Berries as "Bush Berries"

² Data Source groups Melons with Squash and Cucumbers

³ Data Source groups Onions with Garlic

⁴ Stone Fruits include Apricots, Nectarines, Peaches, Plums, and Prunes

⁵ Boron Sensitive Crops include Berries, Citrus, and Stone Fruits

⁶ Chloride Sensitive Crops include Almonds

⁷ EC Sensitive Crops include Carrots, Melons, Onions, and Strawberries

Key:

% = percentage

AEWSD = Arvin-Edison Water Storage District

DEID = Delano-Earlimart Irrigation District

KTWD = Kern-Tulare Water District

n/a = not applicable

SID = Saucelito Irrigation District

SSJMUD = South San Joaquin Municipal Utility District

SWID = Shafter-Wasco Irrigation District

DEVELOPING MITIGATION LEACHING CURVES

This section describes quantification of mitigation based on leaching requirements for sensitive crops. This approach does not directly address the physical characteristics or dynamic nature of the rootzone, but rather is specific to sensitive crop types grown in the region and implementing sufficient leaching volumes to prevent crop injury. In addition, the volumetric mitigation quantified through this approach is not specific to a water district but is representative of all crops grown in the Friant Division.

For salinity, EC_{et} values were used to calculate LR values, as presented in Table 8 in percentages. For chloride or boron the same LR equation is used except irrigation water concentrations (i.e. Cl^-_w and B_w) in mg/L are used in place of EC_w and respective threshold Cl^-_e and B_e are used in place of EC_{et} . At each location, the quantified LR by water quality constituent is based on the most stringent LR, which assumes all water is applied to the most sensitive crop. Analysis shows a long-term LR between 5.2 and 19 percent, using the average, seasonal statistics for EC, chloride, and boron concentrations.

Table 8. Leaching Requirements for Various Sensitive Crops by Water Source and Water Quality Constituent

MOST SENSITIVE CROP	CVC			INTERMEDIATE			CHECK 21		
	EC	Cl^-	B	EC	Cl^-	B	EC	Cl^-	B
Carrots, onions, melons, strawberries	6.7%	-	-	8.6%	-	-	10.6%	-	-
Almonds (Nemaguard rootstock)	-	5.2%	-	-	8.1%	-	-	11.1%	-
Stone fruits, citrus, berries	-	-	8.0%	-	-	13.6%	-	-	19.0%

Key:

B = boron

Check 21 = Check Structure 21 at milepost 172,40 on the California Aqueduct

Cl^- = chloride

CVC = Cross Valley Canal


EC = electrical conductivity

Intermediate = Water quality representing the average of California Aqueduct Check 21 and Cross Valley Canal water qualities

Figures 4 through 6 show mitigation rating curves based on LR percentages, source water quality, and constituents of concern. Each mitigation rating curve was extended to show the maximum observed concentration from historical water quality data for both CVC and California Aqueduct Check 21 sources.

The LR percentages presented in Table 8 and Figures 4 through 6 represent quantified volumetric mitigation that would be applied as maintenance leaching. Maintenance leaching occurs at each irrigation by applying more water than the soil can hold, or in other words, the applied irrigation water is more than the crop requirement to accommodate the necessary leaching. The quantified LR assumes long-term steady-state conditions and does not account for leaching from rain or end-of-season reclamation practices. Any rain or end-of-season leaching will decrease the presented values.

The quantified LR assumes mitigation water is delivered and applied at the same time as surface water delivery is taken. In addition, it assumes mitigation water is of the same water quality as the surface water delivery. Therefore, mitigation is only quantified for water of the same imported quality and not for both reverse flow pump-back and Millerton Lake supplies. If maintenance leaching practices are followed, reclamation leaching is unnecessary, except for in driest of years when surface supply does not meet irrigation demand or to leach salts that have accumulated between drip emitters and mini sprinklers. Using the most stringent LR, it is assumed all mitigation water is applied to the most sensitive crop.



Key:

Check 21 = California Aqueduct Check 21


CVC = Cross Valley Canal

EC = electrical conductivity

µS/cm = microsiemens per centimeter (1 µS/cm = 1 µmhos/cm = 1/1,000 dS/m)

Intermediate = Water quality representing the average of California Aqueduct Check 21 and Cross Valley Canal water qualities

Figure 4. Leaching Requirement for Electrical Conductivity



Key:

Check 21 = California Aqueduct Check 21


CVC = Cross Valley Canal

EC = electrical conductivity

Intermediate = Water quality representing the average of California Aqueduct Check 21 and Cross Valley Canal water qualities

mg/L = milligrams per liter

Figure 5. Leaching Requirement for Chloride




Key:
 Check 21 = California Aqueduct Check 21
 CVC = Cross Valley Canal
 Intermediate = Water quality representing the average of California Aqueduct Check 21 and Cross Valley Canal water qualities
 mg/L = milligrams per liter

Figure 6. Leaching Requirement for Boron


Leaching Requirement Normalization

In order to best understand the LR relationships amongst EC, chloride, and boron and to confirm the dominant constituent trend, individual rating curves were normalized to an EC concentration scale. The EC concentration was used as it can be easily measured in real-time. Figure 7 shows the stacked, normalized mitigation rating curves for all three constituents of concern. Boron is the dominant or driving constituent and has the highest LR, regardless of source water quality. The required leaching based on that curve would be sufficient to prevent crop injury due to increased EC or chloride concentrations in applied irrigation water, and, therefore, the boron curve is the proposed mitigation rating curve for the Water Quality Mitigation Ledger (Figure 8). The method for normalizing each constituent curve is described below.



Key:
 μS/cm = microsiemens per centimeter (1 μS/cm = 1 μmhos/cm = 1/1,000 dS/m)
 EC = electrical conductivity

Figure 7. Rootzone Leaching Curves for Electrical Conductivity, Chloride, and Boron Normalized to an Electrical Conductivity



Key:
 μS/cm = microsiemens per centimeter (1 μS/cm = 1 μmhos/cm = 1/1,000 dS/m)


Figure 8. Proposed Mitigation Rating Curve based on Boron Sensitivity and Normalized to Electrical Conductivity

Normalization Method

As the three constituent curves have differing concentration scales and they do not show direct correlations to each other, the constituents were normalized to a common scale using the below equation.

$$X_{new} = \frac{X - X_{min}}{X_{max} - X_{min}}$$

In the equation, X represents the constituent concentration for EC, chloride, or boron. X_{min} is the minimum average, seasonal, observed concentration for a given constituent from either California Aqueduct Check 21 or CVC water quality data. The maximum observed concentration corresponded with varying leaching requirements for each of the constituents. To ensure that all constituents were normalized to the same scale and the full range of possible constituent concentrations was considered beyond the highest observed concentration for California Aqueduct Check 21 water, X_{max} represents the constituent concentration corresponding to a 25 percent LR. Figure 9 displays the normalized curves, and Table 9 presents the normalized data.



Key:
EC = electrical conductivity

Figure 9. Normalized Leaching Requirement curves for Electrical Conductivity, Chloride, and Boron

Normalized concentration values were then converted back to EC using the equation below, where X_{norm} represents the normalized concentration for chloride or boron. LR curves were then replotted using an EC scale (Figure 7).

$$EC = X_{norm}(EC_{max} - EC_{min}) + EC_{min}$$

Table 9. Constituent Normalization

SOURCE WATER	ELECTRICAL CONDUCTIVITY			CHLORIDE			BORON		
	Observed Concentration (µS/cm)	Normalized Value	Leaching Requirement	Observed Concentration (Seasonal Average) (mg/L)	Normalized Value	Leaching Requirement	Observed Concentration (Seasonal Average) (mg/L)	Normalized Value	Leaching Requirement
CVC	315	0.06	6.7%	37.00	0.12	5.2%	0.10	0.06	8.0%
Intermediate	397	0.17	8.6%	56.00	0.27	8.1%	0.15	0.38	13.6%
Check 21	479	0.29	10.6%	75.00	0.41	11.1%	0.20	0.69	19.0%
Maximum Observed	805	0.73	19.2%	157.00	1.05	26.5%	0.25	1.00	25.0%
Maximum normalization (25% Leaching Requirement)	1000	1.00	25.0%	150.00	1.00	25.0%	0.25	1.00	25.0%

Key:

CVC = Cross Valley Canal

µS/cm = microsiemens per centimeter

mg/L = milligrams per liter

APPLIED AGRONOMIC THRESHOLDS

The Policy includes maximum water quality thresholds for the FKC. Although the mitigation rating curve quantifies mitigation water to account for appropriate maintenance leaching, FKC water quality thresholds for EC, chloride, boron, turbidity, total suspended solids (TSS), and SAR and sodium were developed and are proposed herein. These thresholds aim to (1) balance supply reliability, water quality concerns, and agricultural practices, such as regulated deficit irrigation (RDI); and (2) ensure that the EC_{et} , Cl_{et} , or B_{et} limits are not exceeded for the most prevalent and sensitive crops in the Friant Division. The thresholds are specific to three irrigation periods that correspond to the growing season and agricultural management practices during the year:

- Period one represents the beginning of the growing season (March 1 – June 30);
- Period 2 represents timing of hull split and the duration of RDI practices in the Friant Division (July 1 – August 31); and
- Period 3 is inclusive of the remainder of the growing season and contract year (September 1 – February 28).

Table 10 shows the established water quality constituent thresholds for each period as defined in the Policy. The threshold variations in Period 3, shown as Periods 3a and 3b, are described in more detail in the Threshold Flexibility subsection below.

Sections below describe methods applied to account for annual RDI practices; development of water quality thresholds, including thresholds for RDI; and adjustments to water quality thresholds to accommodate flexibility for water management within the Friant Division.

Table 10. Friant-Kern Canal In-Prism Water Quality Thresholds

Period	Salinity expressed as EC (µS/cm)	Chloride (mg/L)	Boron (mg/L)¹	Turbidity (NTU)⁶	Total Suspended Solids (ppm)	SAR⁷	Sodium (mg/L)⁷
Period 1 March 1 – June 30	1,000 ²	102 ³	0.4	40	20	3	69
Period 2 July 1 – August 31	500 ⁴	55 ⁴	0.4	40	20	3	69
Period 3a September 1 – February 28	1,000 ²	102 ³	0.4	40	20	3	69
Period 3b September 1 – February 28	1,000 ²	123 ⁵	0.4	40	20	3	69

Notes:

Thresholds adapted from Grieve, C.M., S.R. Grattan and E.V. Maas. 2012. Plant salt tolerance. In. (W.W. Wallender and K.K. Tanji, eds). Agricultural Salinity Assessment and Management (2nd edition). ASCE pp 405-459; and Ayers, R.S. and D.W. Westcot 1985. Water quality for agriculture. FAO Irrigation and Drainage Paper 29 (rev 1). Food and Agriculture Organization of the United Nations. Rome

For addition detail, see Attachment C – Agronomic Impacts and Mitigation.

When Friant-Kern Canal in-prism water quality conditions in this table are exceeded, Friant Division Long-Term Contractors will work together to seek 1:1, unleveraged, and cost-neutral exchanges for pump-in and pump-back programs. This does not apply to spot-market or third-party exchanges.

1 Grapes are used as a representative crop for boron sensitivity and are prevalent in the Friant Division. They are used as a surrogate for many other sensitive crop types such as apricots, figs, and grapefruits. Threshold assumes conventional irrigation with minimum 20 percent leaching fraction applied.

2 Threshold assumes minimum of 20 percent leaching requirement applied and adjusted to account for regulated deficit irrigation during almond hull split period (July 1 – August 31) in order to not exceed maximum EC_{et}. Almonds on Nemaguard rootstock are used as a representative crop for salinity sensitivity and are prevalent in the Friant Division. They are used as a surrogate for many other sensitive crop types such as apples, cherries, pears, pistachios, and walnuts.

3 Threshold assumes minimum of 20 percent leaching requirement applied and then adjusted to account for regulated deficit irrigation during almond hull split period (July 1 – August 31) in order to not exceed maximum Cl_{et}. Almonds on Nemaguard rootstock used as a representative crop for chloride sensitivity. They are used as a surrogate for other sensitive crops including cherries, pistachios, and walnuts.

4 Threshold applies to almond hull split period when regulated deficit irrigation is applied to avoid hull rot. This threshold is used assuming irrigation applications are reduced to 50 percent of the tree water requirement and subsequently thresholds applied for the remainder of the year have been adjusted to account for additional salt accumulation. This threshold was developed with consideration of existing program operations, historical water quality data, and absolute water quality thresholds.

5 If the measured average chloride concentration in Period 1 (March 1 – June 30) is less than or equal to 70 mg/L, the allowable chloride threshold for Period 3 (September 1 – February 28) is increased to 123 mg/L.

6. Turbidity threshold is taken from section 3 of the Final Initial Study/Negative Declaration for: Warrant Act Contract(s) and License, and Operation and Maintenance Agreement, to Introduced Floodwaters from Reclamation District 770 into the Friant-Kern Canal, March 2017.

7. SAR and Sodium are managed together. If the measured SAR value exceeds 3 AND the measured sodium concentration exceeds a threshold of 69 mg/L, management will be necessary. SAR value is derived from Ayers Table 1 and the 69 mg/L sodium is derived and converted from the Ayers Table 6.

Key:

µS/cm = microsiemens per centimeter (1 µS/cm = 1 µmhos/cm = 1/1,000 dS/m)

ASCE = American Society of Civil Engineers

Cl_{et} = maximum chloride threshold of the saturated soil paste

EC = electrical conductivity of applied water

EC_{et} = Soil salinity threshold for a given crop

FAO = Food and Agriculture Organization of the United Nations

Friant Division = Friant Division of the Central Valley Project

mg/L = milligrams per liter

SAR = sodium adsorption ratio

TDS = total dissolved solids

REGULATED DEFICIT IRRIGATION

This section describes methods applied to account for annual RDI practices in the Friant Division for EC and chloride agronomic thresholds, specific to almonds. Note, grapes may also be deficit irrigated during the blooming period; however, the deficit irrigation period for grapes is not aligned with that of almonds, and grapes are most prone to boron toxicities. Consequently, a similar RDI analysis and threshold adjustment is unnecessary for grapes. See Boron Thresholds subsection in Water Quality Thresholds section for additional discussion on applied boron thresholds for grapes in the Friant Division.

Hull Rot Control

Hull rot is problematic in almond orchards in the San Joaquin Valley, and trees are particularly sensitive during the hull split period. Hull split is where 1 percent of the almonds exhibit split, and it typically lasts one to two weeks. The initiation of hull split depends on the almond variety, weather conditions, and tree stress. Although variety has the largest influence on hull-split timing, the temperature 90 days after flowering also affects the hull split initiation. Unseasonably cool temperatures delay hull split while unseasonably warm weather accelerates it.

Hull rot occurs due to infestation by one of two types of fungi, *Monilinia fructicola* or *Rhizopus stolonifera* (Holtz, 2009). Some almond varieties, particularly Nonpareil and Monterey, are more susceptible to fungal attack than are other varieties. High nitrogen application to an orchard combined with full irrigation, or irrigation to completely meet tree ET demands, at the time of hull split can make trees considerably more vulnerable to hull rot.

Hull rot can be largely controlled through a combination of nitrogen management, water management, and antifungal sprays. It is best controlled by RDI practices. A 2001 study showed that by cutting back irrigation to 50 percent of the trees' water requirements between June 1 to July 31 (70 percent regulated) or July 1 to July 15 (85 percent regulated), hull rot was substantially reduced as evidenced by fewer dead leaf clusters and fewer dead spurs and branches (Teviotdale et al., 2001). Such mild to moderate water stress results in drier hull conditions, making trees less vulnerable to fungal attack. Many almond growers in the San Joaquin Valley have adopted RDI practices to help synchronize hull split timing and reduce potential for hull rot. To monitor the degree of tree stress, these growers have implemented the University of California recommendation of trying to maintain a stem water potential between -14 to -16 bars using pressure chambers by drying down the soil rootzone (B. Sanden, Personal communication, April 5-6, 2020). The more negative the number, the more stress the tree experiences. It could take between one to six weeks to achieve this stress level, depending on soil type and irrigation systems (B. Lampinen, personal communication, April 7, 2020). Growers should take care to not to stress trees too much because that could compromise kernel size as kernels continue to grow at the onset of hull split (Doll and Shackel, 2015). After almond harvest, irrigation is critical to maximize floral bud development for the subsequent season.

During the RDI period when there is no effective leaching, irrigation application is reduced to 50 percent of the tree water requirement, and some additional salts and chlorides accumulate in the rootzone. Absent leaching, the steady-state model breaks down because the salt content in the applied water would need to be zero to maintain the same rootzone salinity. In this situation, preseason irrigation management should target an adjusted soil salinity to maintain the appropriate soil salinity thresholds and avoid crop injury.

Regulated Deficit Irrigation Analysis

The RDI analysis applied a predictive model based on timing of flowering to estimate hull split for various types of almond varieties in different parts of the Central Valley (UC Fruit & Nut Research & Information Center, 2020). From the model and historical California Irrigation Management Information System (CIMIS) data from the AEWSD weather station, hull split was determined to typically initiate around the end of June or beginning of July and, depending upon the variety, continue through mid-August (B. Sanden, personal communication, April 6, 2020). To account for potential variances in hull split initiation in the Friant Division, an 8-week period (July 1 to August 31) was assumed for this RDI analysis. Determination of water quality

thresholds during the RDI practices period, or Period 2, also considered effective rootzone depth, applied irrigation water quality, soil capacity, and irrigation requirements. The RDI analysis is considered to be conservative because: (1) rainfall was not considered; (2) surface irrigation was assumed, despite the fact that crops under high frequency drip irrigation (typical for most water districts in the Friant Division) are able to tolerate higher salinity for the same assumed LF; and (3) steady-state models typically overestimate rootzone salinity (Corwin and Grattan, 2018).

The RDI analysis was completed for both EC and chloride. Salt accumulation was quantified as a percentage increase, and then rootzone and applied irrigation water thresholds (assuming 20 percent maintenance leaching) were adjusted to maintain maximum EC_{et} or Cl_{et} through the season. Assuming steady-state leaching, the analysis targeted maintenance of rootzone salinity at soil salinity thresholds of 150 mg/L for chloride, and 1,500 $\mu S/cm$ for EC, resulting in adjustments to Cl_w and EC_w thresholds.

The RDI calculation assumed the effective rootzone to be between three and five feet (UC Almond Rootzone Workgroup, 2015). Soil was considered to be at field capacity meaning that volumetric soil moisture content was 25 percent, based on monthly average ET or irrigation water requirements for mature almonds in Kern County during months of July and August, 9.5 inches and 8.8 inches, respectively (Sanden, personal communication, April 6, 2020; Goldhamer 2012). The RDI calculation included soil water concentration thresholds of 300 mg/L for Cl_{sw} , and 3,000 $\mu S/cm$ for EC_{sw} , or twice that of the thresholds expressed on a saturated soil paste basis.

During the RDI period, water was assumed to be applied at 50 percent ET_c . The total amount of irrigation water required for 100 percent irrigation application, in inches, was calculated but then halved to account for 50 percent deficit irrigation. The amount of irrigation water during RDI periods was then multiplied by the irrigation water concentrations of salt and chloride to determine the percentage increase above the salt and chloride concentrations in the rootzone. Calculating the percentage increase of chloride in the rootzone meant first determining irrigation water and soil water amounts.

For example, 50 percent of the total ET for July and August was 9.1 inches, and the total water in the effective rootzone was 15 inches (rootzone depth (5 ft, or 60 inches) * 25 percent water content = 1.25 feet, or 15 inches). The 15 inches of soil water had 300 mg/L chloride at the beginning of the RDI period. After 9.1 inches of water was applied, adding salts to the soil water in the rootzone, the irrigation water concentration was 55 mg/L. The percentage of additional salt was determined by calculating the ratio of the salt added in the deficit irrigation water to that in the soil water, $(9.1 \text{ inches} \times 55 \text{ mg/L}) / (15 \text{ inches} \times 300 \text{ mg/L}) = 11$ percent. If the salt level in the rootzone remained at critical soil threshold levels at the end of the RDI period, the Cl_e at the beginning of RDI period would have needed to be proportionally lower than the critical soil salinity threshold of 150 mg/L, such that the 150 mg/L threshold concentration would be achieved at the end of the season. Thus, the Cl_{et} is reduced to 122 mg/L and the corresponding Cl_w becomes 102 mg/L.

WATER QUALITY THRESHOLDS

This section presents the RDI analysis-based chloride and EC thresholds and proposed flexible thresholds for chloride, boron thresholds, turbidity and TSS thresholds, and SAR and sodium thresholds.

Chloride and Electrical Conductivity Thresholds

Tables 11a and 11b show the RDI analysis for a variety of applied irrigation water qualities for chloride and EC, respectively. In consideration of historical water quality data representative of Kern-Fan or CVC programs that currently introduce water into the FKC, as well as temporal water quality trends, an applied irrigation water threshold for the RDI period was selected to be 55 mg/L Cl_w . The Cl_w value of 55 mg/L during the RDI period correlated to an adjusted Cl_w of 102 mg/L for the remainder of the year, assuming a three-foot (36 inch) effective rootzone – a conservative assumption as the effective rootzone is assumed to be three to five feet (Table 12a).

The same logic described above for Cl_w thresholds was applied to determine RDI EC_w and adjusted EC_w thresholds. The chloride threshold for the RDI period (55 mg/L) was approximately 49 percent greater than

the average historical water quality of representative Kern-Fan programs for all year types during months of July and August (37 mg/L). The average EC_w during July and August for all year types representative of Kern-Fan programs was 300 $\mu S/cm$, and a 49 percent increase is 447 $\mu S/cm$. Rounding up, the RDI threshold for EC_w is 500 $\mu S/cm$, and, in order to maintain an EC_{et} of 1,500 $\mu S/cm$, the adjusted EC_w for the remainder of the year was 1,000 $\mu S/cm$.

Table 11a. Regulated Deficit Irrigation Analysis for Chloride

Cl _w (mg/L)	Effective Rootzone (in)	Sum ET _c Average (in) ¹	RDI %	RDI Water (in)	Rootzone Water (in) ²	% Cl ⁻ Increase	Adjusted Cl _e Needed (mg/L)	Adjusted Cl _w (mg/L)
10	36	18.3	50%	9.2	9	3.4%	145	121
10	60	18.3	50%	9.2	15	2.0%	147	122
20	36	18.3	50%	9.2	9	6.8%	140	117
20	60	18.3	50%	9.2	15	4.1%	144	120
30	36	18.3	50%	9.2	9	10.2%	135	112
30	60	18.3	50%	9.2	15	6.1%	141	117
40	36	18.3	50%	9.2	9	13.6%	130	108
40	60	18.3	50%	9.2	15	8.1%	138	115
50	36	18.3	50%	9.2	9	16.9%	125	104
50	60	18.3	50%	9.2	15	10.2%	135	112
55	36	18.3	50%	9.2	9	18.6%	122	102
55	60	18.3	50%	9.2	15	11.2%	133	111

Notes:

¹ ET_c averages from Sanden and Goldhamer based on water use of mature almond trees in Wasco area for July and August (Goldhamer and Girona 2012).

² Rootzone at field capacity is 25 percent by volume.

Key:

Cl⁻ = chloride

Cl_e = chloride concentration in saturated soil paste or rootzone chloride

Cl_w = chloride concentration in applied irrigation water

ET_c = evapotranspiration or tree water use

in = inches

mg/L = milligrams per liter

RDI = regulated deficit irrigation

Table 11b. Regulated Deficit Irrigation Analysis for Electrical Conductivity

EC _w (μS/cm)	Effective Rootzone (in)	Sum ET _c Average (in) ¹	RDI %	RDI Water (in)	Rootzone Water (in) ²	% EC Increase	Adjusted EC _e Needed (μS/cm)	Adjusted EC _w (μS/cm)
200	36	18.3	50%	9.2	9	6.8%	1,400	1,120
200	60	18.3	50%	9.2	15	4.1%	1,440	1,150
300	36	18.3	50%	9.2	9	10.2%	1,350	1,080
300	60	18.3	50%	9.2	15	6.1%	1,410	1,130
400	36	18.3	50%	9.2	9	13.6%	1,300	1,040
400	60	18.3	50%	9.2	15	8.1%	1,380	1,100
500	36	18.3	50%	9.2	9	16.9%	1,250	1,000
500	60	18.3	50%	9.2	15	10.2%	1,350	1,080
600	36	18.3	50%	9.2	9	20.3%	1,200	960
600	60	18.3	50%	9.2	15	12.2%	1,320	1,050

Notes:

¹ ET_c averages from Sanden and Goldhamer based on water use of mature almond trees in Wasco area for July and August (Goldhamer and Girona 2012).

² Rootzone at field capacity is 25 percent by volume.

Key:

μS/cm = microsiemens per centimeter

EC = electrical conductivity

EC_e = electrical conductivity of saturated soil paste or rootzone salinity

EC_w = electrical conductivity of applied irrigation water

ET_c = evapotranspiration or tree water use

in = inches


RDI = regulated deficit irrigation

By adjusting the Cl_e and EC_e thresholds for non-RDI irrigation periods, LR volumes for the assumed 20 percent leaching were adjusted by default, as LR is a function of the saturated soil paste concentration. Adjusted LR volumes and constituent thresholds affect the mitigation curve slope for each constituent. The adjusted curves for chloride and EC were plotted and were below the governing line, so the mitigation curve remained unchanged and further confirmed the conservative nature of the mitigation curve in ensuring that all constituents would be sufficiently mitigated.

Chloride Threshold Flexibility

In evaluating and comparing the developed, in-prism water quality thresholds with temporal water quality trends during Period 1 (March 1 to June 30), or prior to the RDI period (July 1 to August 31), observed average constituent concentrations were typically below the proposed thresholds. If water with lower constituent concentrations was applied to a crop for the first four months of the growing season, assuming that the rootzone concentration was properly maintained, the rootzone concentration would decrease below the threshold and, even with reductions in irrigation and LFs, could allow the application of higher irrigation water concentrations during the post-RDI period. The period following RDI, or Period 3 (September 1 to February 28), is often used for reclamation leaching; however, it is also the period in which new sources of water may be available for the Friant Division. Thus, having flexibility in the allowable irrigation water quality could be opportune for increasing supply reliability for the region.

Based on the RDI analysis and evaluation of water quality temporal trends, the Guidelines define an alternative water quality threshold for chloride for Period 3 to provide flexibility for irrigation management. Determination of whether the alternative chloride threshold for Period 3 is applied is based on the average chloride concentration of the irrigation water during Period 1. The alternative value was developed considering historical, temporal water quality trends and applying a weighted average calculation to meet the targeted rootzone chloride threshold. If the average measured chloride concentration for Period 1 is less than or equal to 70 mg/L, the allowable chloride concentration threshold increases from 102 mg/L to 123 mg/L for Period 3. If the measured average chloride concentrations for Period 1 exceed 70 mg/L, the chloride threshold remains at 102 mg/L for Period 3. Figure 10 shows the proposed thresholds compared to the chloride water quality trends for CVC and California Aqueduct water sources by year type.



Key:

Average = Average of all San Joaquin Index year types and excludes months where there is mixing.

Cl_w = chloride concentration of applied irrigation water

CVC = Cross Valley Canal

Dry= Monthly average for San Joaquin Index year types dry and critical and excludes months where there is mixing.

mg/L = milligrams per liter

RDI = regulated deficit irrigation

Wet = Monthly average for San Joaquin Index year types below normal, above normal, and wet and excludes months where there is mixing.

Figure 10. Chloride water quality trends by source water and year type with proposed water quality thresholds

Because the average water quality for Kern-Fan or CVC programs for Period 1 (March 1 to June 30) was approximately 30 mg/L (see Table 2), 70 mg/L was chosen as a midpoint between the adjusted Cl_w threshold determined in the RDI analysis and the average historic water quality. Using a weighted average approach, if 70 mg/L water was applied for the four months in Period 1, assuming an LR of 20 percent, the resulting Cl_e would be 84 mg/L. With the target weighted average for Cl_e of 122 mg/L, the necessary Cl_e for Period 3, the six months post-RDI (September 1 – February 28) was determined using the following equation:

$$84 \frac{mg}{L} * .4 + Cl_e * .6 = 122$$

The resulting Cl_e was 147 mg/L, correlating to a Cl_w of 123 mg/L with an assumed 20 percent LR. This approach was conservative in that observed chloride concentrations for Kern-Fan programs were significantly lower than 70 mg/L, and these calculations did not consider rainfall or any reclamation leaching applied in addition to the assumed 20 percent maintenance leaching.

Note that adjusting the Cl_e thresholds for non-RDI irrigation periods (Period 1 and Period 3) would adjust the LR volumes for the assumed 20 percent leaching provided by the mitigation curve. Adjusted curves were plotted and it was confirmed that even with a reduced Cl_e , the established mitigation curve would provide adequate mitigation.

Boron Thresholds

Table 12 shows B_w thresholds for tree and vine crops above which injury occurs under differing irrigation management practices, or LF values of 10 and 20 percent. Grapes have a boron tolerance of 0.4 mg/L when the LF is between 10 to 25 percent (Grattan et al., 2015). The actual boron threshold tolerance range is 0.3-

0.5 mg/L if one considers different combinations of the soil water threshold (B_{sw}) tolerance (0.5 - 0.75 mg/L) and LF (10 - 25%).

The maximum in-prism water quality threshold for boron was set at 0.4 mg/L for all three irrigation periods (Periods 1, 2, and 3). Grapes were used as the representative crop for boron sensitivity because of their prevalence in the Friant Division, serving as a surrogate for other sensitive crop types, such as apricot, fig, and most citrus. The applied threshold assumed conventional irrigation with a LF of 10-25 and was used rather than the LR concept that was used in development of the mitigation curves.

Table 12. Boron Tolerance of Various Crops

CROP	BORON CONCENTRATION OF APPLIED WATER (B_w) (mg/L)	
	Leaching Fraction 10%	Leaching Fraction 25%
Alfalfa	2.0	2.8
Apricot	0.4	0.4
Asparagus	4.8	6.7
Barley	1.4	1.9
Bean (kidney, lima, mung)	0.4	0.6
Bean, snap	0.5	0.6
Beet, red	2.0	2.8
Bluegrass, Kentucky	1.2	1.7
Broccoli	0.5	0.6
Cabbage	1.2	1.7
Carrot	0.7	0.9
Cauliflower	1.6	2.2
Celery	3.8	5.3
Cherry	0.4	0.4
Clover, sweet	1.2	1.7
Corn	1.2	1.7
Cotton	3.1	4.3
Cucumber	0.7	0.9
Fig, Kadota	0.4	0.4
Garlic	1.7	2.4
Grape	0.4	0.4
Grapefruit	0.4	0.4
Lemon	<0.3	<0.4
Lettuce	0.6	0.8

Note: Adapted from data in Grattan, S.R., F.J. Diaz, F. Pedrero and G.A. Vivaldi. 2015. Assessing the suitability of saline waste waters for irrigation of citrus: Emphasis on boron and specific ions interactions. *Agric Water Manag.* 157:48-58.

Key:
mg/L = milligrams per liter

In addition, the applied B_w threshold of 0.4 mg/L was far more conservative than those defined in literature by Ayers and Westcot (1985). This analysis indicated that B_{sw} could be used as protective irrigation water thresholds (B_e) because of the complexities related to boron adsorption and equilibrium concentrations with the soil water. Historical water quality data also indicate that CVC or California Aqueduct water would be below this threshold.

Turbidity and Total Suspended Solids Thresholds

Turbidity and TSS are of concern to water users in the Friant Division. Turbidity and TSS are not agronomic constituents of concern, but elevated levels are problematic for water management infrastructure and facilities, specifically spreading and groundwater recharge basins. TSS and Turbidity are also less of a concern in water supplies introduced via the Intertie and apply more to water being introduced via gravity flow to the FKC during high-flow or flood events.

The precedent for the defined thresholds was established under the environmental compliance documentation Final Initial Study/Negative Declaration for the Warren Act Contract and License and Operation and Maintenance Agreement to Introduce Floodwaters from Reclamation District 770 into the Friant-Kern Canal (DL770 Contract). As part of the agreement, water introduced into the FKC by Delta lands

Reclamation District 770 would not cause in-prism water quality to exceed 40 nephelometric turbidity units (NTU) of turbidity or more than 20 parts per million (ppm) of TSS (Delta Lands Reclamation District 770 2017). These same thresholds are included in the Guidelines.

The TSS and turbidity thresholds defined are based on operational and maintenance practices for spreading and groundwater recharge basins in the region. AEWS has an allowable upper limit for TSS, 25 ppm, for water applied to spreading basins in their district (Bookman-Edmonston Engineering, Inc. 1972). A value of 20 rather than 25 ppm is included in the document to be protective of this upper, allowable limit. Monitoring of TSS requires lab analysis of water quality samples and thus management cannot be done in real time, however turbidity can be measured with a handheld meter and can be done in real time. Although the numerical relationship between turbidity and TSS can be affected by water source location, seasonal timing, and flow velocities (Meozzi 2011), a generalized relationship between the two constituents was developed to facilitate real-time water quality management. The defined turbidity threshold of 40 NTU correlates with the 20 ppm TSS value based on correlation analysis that AEWS performed between 2011 and 2016.

SAR and Sodium Thresholds

The established SAR and sodium thresholds defined in the Guidelines are designed to be managed together. As detailed under the Agronomic Effects section, sodium by itself can be potentially problematic and cause direct toxicity to tree crops. However, because of the importance of adequate Ca^{2+} in the soil water as a means of stabilizing root cell membranes and maintaining selective ion uptake by tree crops, the sodium-calcium ratio in the soil solution is often a better indicator of Na^+ toxicity. Therefore, SAR of the applied irrigation water has been used as a surrogate for the sodium-calcium ratio. The general rule is an SAR less than 3 is not problematic. However an SAR threshold on its own was not acceptable to water managers and water users as there are concerns related to potential acute crop injuries due to observed spikes in sodium concentrations of applied irrigation water. A combination approach to sodium management was developed, where if the measured SAR value exceeds 3 and the measured sodium concentration exceeds 69 mg/L, introduced water would need to be managed. The SAR threshold of 3 is from Ayers and Westcot Table 1 and assumes surface irrigation. The sodium concentration threshold of 69 mg/L is also derived from Ayers and Westcot Table 1 and suggests that irrigation waters $< 3 \text{ meq/L}$ (69 mg/L)² is suitable for crops that are sprinkler irrigated. Crops that are sprinkler irrigated are more susceptible to salt damage than by other irrigation methods as sodium can accumulate in the leaves by direct foliar absorption in addition to root absorption processes. Surface and low-pressure irrigated crops (i.e., drip and mini-sprinklers), on the other hand, can only accumulate sodium in leaves by root absorption and translocation. The defined thresholds are conservative as the assumed sprinkler irrigation and more salt-damaging method is not widely used for crops within the Friant Division, as growers tend to use more efficient, on-the-ground irrigation methods.

The defined thresholds are designed to address sodium toxicities and although SAR is also used to assess the infiltration hazard (described previously), it assumed that given the wide range of observed SAR values relative to water supply source, growers already appropriately manage SAR through the application of gypsum to increase EC and maintain adequate infiltration.

² The value assumes that calcium and magnesium are both at or above 2 meq/L (40 mg/L Ca^{2+} and 24 mg/L Mg^{2+}) where equivalent concentration of Ca^{2+} is greater or equal to Mg^{2+} . It is further assumed that this condition is met as the protection of these divalent constituents is their presence in the rootzone soil water. Nearly all growers in the region apply amendments such as gypsum (CaSO_4), and thus soil water concentrations would meet the criteria. (Maas and Grattan, 1999).

REFERENCES

- Ayers, R.S. and D.W. Westcot. 1985. Water quality for agriculture. FAO Irrigation and Drainage Paper 29 (rev 1). Food and Agriculture Organization of the United Nations. Rome
- Bookman-Edmonston Engineering, Inc. 1972. "Chapter IV Spreading Works." Arvin-Edison Water Storage District Operation and Maintenance Manual. Glendale, California.
- Brown, P.H. and B.J. Shelp. 1997. Boron mobility in plants. *Plant and Soil* 193:85-101.
- California Department of Water Resources. 2017. Land Use Viewer. Available at: <https://gis.water.ca.gov/app/CADWRLandUseViewer/>
- Corwin, D.L and S.R. Grattan. 2018. Are existing irrigation salinity leaching requirement guidelines overly conservative or obsolete? *J Irrig. and Drain. Eng.* ASCE 144(8):02518001.
- Dejampour, J., N. Aliasgharzad, M. Zeinalabedini, M.R. Niya and E. Hervan. 2012. Evaluation of salt tolerance in almond [*Prunus dulcis* (L.) Batsch] rootstocks. *African J of Biotech.* 11(56):11907-11912
- DeJong, T. Almond hull split prediction model. University of California, Davis. Available at: http://fruitsandnuts.ucdavis.edu/Weather_Services/almond_hullsplit_prediction/
- Delta Lands Reclamation District 770. 2017. Final Initial Study/Negative Declaration for Warren Act Contract and License, and Operation and Maintenance Agreement, to Introduce Floodwaters from Reclamation District 770 into the Friant-Kern Canal.
- Doll, D. and Shackel, K. 2015. Drought management for California almonds. UC Drought Tips. University of California Agriculture and Natural Resources (UC ANR) Publication No. 8515
- Epstein, E. and A.J Bloom. 2005. Mineral nutrition of plants: Principles and perspectives. 2nd ed. Sinauer Associates. Sunderland, MA 4
- Goldhamer, D. and Girona, J. 2012. Almond. In *Crop Yield Response to Water*. P. Steduto, T.C. Hsiao, E. Fereres, and D. Raes, eds. FAO Irrigation and Drainage Paper No. 66. Food and Agriculture Organization of the United Nations, Rome, Italy, pp. 246-296.
- Grattan, S.R. and C.M. Grieve. 1992. Mineral element acquisition and growth response of plants grown in saline environments. *Agric., Ecosys. Environ.* 38:275-300.
- Grattan, S.R., F.J. Diaz, F. Pedrero and G.A. Vivaldi. 2015. Assessing the suitability of saline waste waters for irrigation of citrus: Emphasis on boron and specific ions interactions. *Agric Water Manag.* 157:48-58.
- Grieve, C.M., S.R. Grattan and E.V. Maas. 2012. Plant salt tolerance. In (W.W. Wallender and K.K. Tanji, eds). *Agricultural Salinity Assessment and Management* (2nd edition). ASCE pp. 405-459.
- Hanson, B.R., S.R. Grattan, and A. Fulton. 2006. Agricultural salinity and drainage. University of California Agriculture and Natural Resources (UC ANR) Publication No. 3375. University of California, Davis.
- Hasegawa, P.M., Bressan, R.A., Zhu, J.-K and H.J. Bohnert. 2000. Plant cellular and molecular responses to high salinity. *Annu. Rev. Plant Physiology and Molecular Biol.* 51:463-499.
- Holtz, B. 2009. Hull split Part 2: Hull rot of almond. Almond doctor newsletter. University of California Agriculture and Natural Resources (UC ANR). Available at: <http://thealmonddoctor.com/2009/06/30/hull-split-part-2-hull-rot-of-almond/>

- Lauchli, A. and S.R. Grattan. 2012. Plant response to saline and sodic conditions. *Agricultural Salinity Assessment and Management* (W.W. Wallender and K.K. Tanji, eds.). ASCE Manuals and Reports and Engineering Practice No. 71. American Assoc. of Civil Engineers, Reston, VA USA Pp 169-205
- Läuchli, A and S.R. Grattan. 2012. Plant stress under non-optimal soil pH. In: *Plant Stress Physiology*. S. Shabala, ed. CAB International. pp. 194-209.
- Lawrence Livermore National Laboratory (LLNL) Nitrate Working Group. 2002. Nitrate Contamination in California Groundwater: An Integrated Approach to Basin Assessment and Resource Protection. December 10, 2002. Available at: www.swrcb.ca.gov/gama/docs/llnl_nitrate_wp_ucrl-151454.pdf
- Letey, J., G.J. Hoffman, J.W. Hopmans, S.R. Grattan, D. Suarez, D.L. Corwin, J.D. Oster, L. Wu, and C. Amrhein. 2011. Evaluation of soil salinity leaching requirement guidelines. *Agric Water Manag.* 98: pp. 502-506
- Letey, J. and G.L. Feng. 2007. Dynamic versus steady-state approaches to evaluate irrigation management of saline waters. *Agric. Water Manag.* 91: pp. 1-10
- Maas, E. V. and S. R. Grattan. 1999. Crop yields as affected by salinity. In *Agricultural Drainage*. R. W. Skaggs and J. van Schilfgaarde, eds. Agron. Monograph 38. ASA, CSSA, SSA, Madison, WI pp. 55-108.
- Meozzi, Luca. 2011. Relation between turbidity and suspended material at different soils, scales and phosphorous levels. University of Copenhagen.
- Munns, R. and M. Tester. 2008. Mechanisms of salinity tolerance. 2008. *Annu. Rev. Plant Biol.* 59:651-681
- Provost and Pritchard Consulting Group. 2012. Friant Water Authority Evaluation of Impacts from Use of Re-Circulated San Joaquin River Water. Clovis, CA.
- Ragab, R., N. Malash, G. Abdel Gawad, A. Arslan, and A. Ghaibeh. 2005. A holistic generic integrated approach for irrigation, crop and field management: 1. The SALTMed model and its application using field data from Egypt and Syria. *International Journal of Agricultural Water Management*, 78(1-2): pp. 67-88.
- Rhoades, J.D., A. Kandiah, A. and A.M. Marshall. 1992. The use of saline waters for crop production. *FAO Irrigation and Drainage Paper 48*. Food and Agricultural Organization (FAO) of the United Nations. Rome
- Rhoades, J.D. and S.D. Merrill. 1976. Assessing the suitability of water for irrigation: Theoretical and empirical approaches. In: *Prognosis of salinity and alkalinity*. *FAO Soils Bulletin 31*. FAO. Rome pp 69-110.
- Soil Web. 2019. Division of Agriculture and Natural Resources. University of California, Davis. Professor A. O'Geen, Department of LAWR contact person. Available at: <https://casoilresource.lawr.ucdavis.edu/gmap/>
- Suarez, D.L. and J. Simunek. 1997. UNSATCHEM: unsaturated water and solute transport model with equilibrium and kinetic chemistry. *Soil Sci Soc. Am. J* 61: pp. 1633-1646.
- Teviotdale, B.L. Goldhamer, D.A., and Viveros, M. 2001. Effects of deficit irrigation on hull rot disease of almond trees cause by *Monilinia fructicola* and *Rhizopus stolonifera*. *Plant Dis.* 85:399-403.
- University of California Fruit & Nut Research & Information Center. 2020. Available at: <http://fruitsandnuts.ucdavis.edu/>

Attachment D. Ledger Standard Operating Procedures

CONTENTS

PURPOSE..... 1

PROCESS FOR IMPLEMENTING WATER QUALITY GUIDELINES..... 1

 Pump-In Project Approvals 3

 Pump-In Project Water Quality 3

 Mitigation Percentage Determination 3

 Friant-Kern Canal Water Quality Monitoring and Management..... 4

 Pump-In Project Delivery Volumes 4

 Ledger Calculations 4

 Assumptions..... 4

 Preliminary Mitigation Distribution 4

 Ledger Calculations 4

 Assumptions..... 5

 End of Month Water Accounting 5

 Ledger Calculations 5

 Assumptions..... 5

 Final Water Accounting 5

 Water Quality Annual Reporting 5

FIGURES

Figure 1. Water Quality Guidelines Implementation Process..... 3

ACRONYMS AND ABBREVIATIONS

Ad hoc Committee	Ad hoc Water Quality Committee
CVC	Cross Valley Canal
CVP	Central Valley Project
EC	electrical conductivity
FKC	Friant-Kern Canal
Friant Contractor	Friant Division long-term contractor
Friant Division	Friant Division of the Central Valley Project
FWA	Friant Water Authority
Guidelines	Friant-Kern Canal Water Quality Policy Guidelines
Ledger	Friant Kern Canal Water Quality Ledger
Policy	Friant-Kern Canal Water Quality Policy
Pool	Section of the Friant-Kern Canal between Check Structures
Reclamation	U.S. Department of the Interior, Bureau of Reclamation
RWA	Recovered Water Account
SJRRP	San Joaquin River Restoration Program
SOP	Standard Operation Procedures
URF	Unreleased Restoration Flow

PURPOSE

This document describes the proposed standard operating procedures for implementing the Friant-Kern Canal Water Quality Ledger (Ledger) that is associated to the Guidelines for Accepting Water into the Friant-Kern Canal (Guidelines). The concept for the Ledger was developed in late 2019 with the Ad hoc Water Quality Committee's (Ad hoc Committee) Small Workgroup during development of the Guidelines. The Ledger determines the required mitigation for introducing water of lesser quality in the Friant-Kern Canal (FKC). An initial, proof-of-concept version of the Ledger included a calculation of the pump-in mitigation percentage, total volume of mitigation water to be added to the FKC, and distribution of mitigation water to affected water users. As the Guidelines move toward implementation and the Ledger is fully developed, it is important that the defined Ledger process integrates with Friant Water Authority's (FWA) operations and accounting.

This Standard Operating Procedures (SOP) document for implementing the Ledger is intended to serve two purposes:

- 1) Define the complete process for pump-in project operations and agency (i.e., FWA and U.S. Department of the Interior, Bureau of Reclamation (Reclamation)) responsibilities relating to project approval, notification, mitigation water accounting, and reporting.
- 2) Document Ledger calculation assumptions.

PROCESS FOR IMPLEMENTING WATER QUALITY GUIDELINES

The Guidelines identify the need to develop standard operating procedures for a mitigation program and its administration. The processes and procedures for FWA implementation and management of the Guidelines will directly impact Ledger development, including the assumptions and calculations within the Ledger tool itself. The process for the implementation of the Ledger as part of the Guidelines includes:

- Approve pump-in projects.
- Measure, report, and track pump-in water quality.
- Collect pump-in project delivery data.
- Calculate preliminary mitigation water distribution.
- Final water accounting.
- Report volumetric deliveries and balance to Reclamation.




Figure 1. Water Quality Guidelines Implementation Process

PUMP-IN PROJECT APPROVALS

In consideration of the Ledger, a pump-in project (or program) is any project that introduces water into the FKC from a source other than Millerton Lake. Reclamation, with acknowledgement from FWA, provides the final approval for any pump-in project once the Warren Act Contract, other agreements, and environmental documentation is completed. Because the Warren Act Contract and environmental documentation for a pump-in project may have different effective durations, Reclamation will approve the necessary documentation to implement a pump-in project at the appropriate times. Each pump-in project will have a defined duration and maximum volume that can be introduced into the FKC. The pump-in project proponent will identify a point of contact who will work with FWA to coordinate required responsibilities outlined in the Guidelines.

PUMP-IN PROJECT WATER QUALITY

As described in Section B2 of the Guidelines, all waters discharged into the FKC must be tested at least annually. Pump-in projects that introduce a single source water quality and pump-in projects that bring water into the FKC via the Cross Valley Canal (CVC) will have different methods for collecting and reporting water quality data.

Mitigation Percentage Determination

Pump-in project water quality will be an input to the Ledger to determine the required mitigation water percentage and corresponding mitigation volume per pump-in project volume. Groundwater and CVC water quality are input to the Ledger at different frequencies as described below.

Single-Source Pump-In Projects via the FKC – Single-source pump-in projects include projects with Warren Act Contracts that introduce surface water or banked groundwater into the FKC. Before an approved pump-in project begins, FWA will work with the proponent to collect water quality data for the potential introduced surface water or groundwater to determine the required mitigation water percentage to be applied to the volume moved through the FKC. The determination of the required mitigation percentage will be calculated using the Ledger. Collection of the water quality data will follow requirements outlined in the Guidelines for Accepting Water into the FKC.

Pump-In Projects via the CVC - As described in Section B2 of the Guidelines, weekly water quality sampling will be performed by FWA during reverse flow pump-back operations and water quality data will be provided to Reclamation. Mitigation will be based on either the weekly average electrical conductivity (EC) concentrations measured continuously at the terminus of the FKC at the Kern River Check or the weekly grab samples collected from the CVC, whichever is deemed more appropriate by FWA. The CVC water quality conditions may represent multiple pump-in projects and will be updated in the Ledger at a greater frequency than once per year. FWA will coordinate with the pump-in project proponents regarding the required mitigation water percentage as determined by changes in water quality conditions.

The Ledger will document the water quality conditions for all pump-in projects and calculate the required mitigation percentage for each.

Ledger Calculations

As described above, pump-in project water quality data will be input to the Ledger. For each pump-in project, the Ledger will calculate the required mitigation water percentage. FWA will communicate this mitigation percentage to pump-in project proponents prior to operation and introduction.

Assumptions

- Water quality conditions for each pump-in project will be measured at least once per year or at a set frequency agreed to in the Guidelines and/or the Pump-In Project Approval and will determine the required mitigation water percentage.
- The Mitigation Percentage process follows the approach outlined in the Guidelines.

Friant-Kern Canal Water Quality Monitoring and Management

All pump-in projects must adhere to the water quality monitoring requirements stipulated in the Guidelines. FWA will implement continuous, real-time monitoring of in-prism water quality conditions in the FKC and at the FKC/CVC Intertie during reverse flow pump-back operations. Continuous, in situ measurements of EC will provide real-time data on incremental water quality changes and mixing in the FKC and will assist in water quality threshold management. If water quality thresholds are exceeded, FWA shall incrementally direct pump-in project proponents to cease operations of pump-in projects in order of greatest mass loading of the critical water quality constituent until the water quality drops below defined thresholds. Furthermore, if water quality monitoring results show an exceedance of 80% of the threshold for any water quality constituents, weekly monitoring will occur until four consecutive grab samples show consistent water quality results.

PUMP-IN PROJECT DELIVERY VOLUMES

During a contract year in which a pump-in project will be operated, FWA will work with the pump-in project proponent to implement the requirements stipulated in the Guidelines. This includes the addition of mitigation water to the FKC consistent with the pump-in project water quality conditions and quantity delivered. Pump-in project forecasted deliveries, calculated projected mitigation water, and all coordination related to pump-in project operations will be completed on a weekly basis.

Ledger Calculations

FWA will coordinate with pump-in project proponents to obtain an estimated volume of water to be introduced and conveyed in the FKC. The required mitigation water volume for the pump-in project is assumed to be included as part of that estimated volume. FWA will calculate losses, when appropriate, based on the total volume of water to be introduced into the FKC. The mitigation volume will be based on the total volume minus the calculated losses. The Ledger uses the mitigation water percentage for each pump-in project based on measured water quality and the net pump-in project volume to determine the projected mitigation volume requirement.

Assumptions

- Mitigation volumes are calculated based on projected weekly volume of a pump-in project and verified using measured volumes at the end of each month.
- Mitigation volumes are added to the FKC in real time with other pump-in project deliveries.
- FWA will have weekly volume, or weekly average flow, projections from pump-in project proponents.

PRELIMINARY MITIGATION DISTRIBUTION

The Ledger will be used to distribute mitigation water volumes to the impacted Friant Division long-term contractors (Friant Contractors). As described in the Pump-In Project Delivery Volumes section, mitigation water is introduced into the FKC simultaneously with the pump-in project volume introduction. FWA will add weekly water order data to the Ledger to distribute the mitigation volume based on volumetric proportioning. The preliminary, weekly mitigation distribution will be used by the FWA **for communication purposes only** (i.e., as the best available estimate of end-of-month mitigation requirements when communicating internally and with Friant Contractors). The mitigation water distribution will be updated at the end of each calendar month based on quality-controlled delivery data.

Ledger Calculations

The FWA will input water order data into the Ledger to be used in the mitigation water distribution calculations. The Ledger will determine the average weekly mixing interface position based on the weekly volumes for periods during FKC pump-back operations. An option to manually set the mixing interface position will also be available in the Ledger.

Assumptions

- Deliveries will be aggregated by Friant Contractor, and divided into pools, defined as the canal section between check structures.
- The division of deliveries by a Friant Contractor that has turnouts in multiple pools will be based on historical deliveries.
- Only Central Valley Project (CVP) (Class 1, Class 2, 215, and San Joaquin River Restoration Program (SJRRP) Recovered Water Account (RWA) and Unreleased Restoration Flow (URF)) deliveries for the Friant Contractors will be used to calculate the mitigation distribution.
- The interface, or location along the FKC that receives water from both gravity and reverse flow, will be determined using a weekly mass balance. An option will also be included to manually define the interface.
- The FKC Pool with the Interface will be assumed to be fully mixed with gravity and reverse flow.

END OF MONTH WATER ACCOUNTING

At the end of each month that a pump-in project is operating, the preliminary mitigation water distribution will be updated based on quality-controlled delivery data for both the pump-in project and Friant Contractors. The updated mitigation distribution volume will be shared with impacted Friant Contractors and included as part of their normal water accounting. The mitigation volume will be assumed to be the first water taken for their monthly deliveries. For pump-in project proponents that take more water than pump-in project delivery minus the mitigation volume, proponents will be assumed to make up that delivery with their CVP contract supply. For pump-in projects that end with water delivery to a Friant Contractor, adjustments for mitigation volumes are not needed.

For pump-in projects that do not end with delivery to a Friant Contractor, there is potential need for a mitigation volume adjustment. For these pump-in projects, FWA will track pump-in project water introduced into the FKC and deliveries to the non-Friant Contractor. If the volume of mitigation water is not equal to the expected volume, FWA will contact the pump-in project proponent to either increase the mitigation volume or increase their own delivery.

Ledger Calculations

FWA will add quality-controlled data to the Ledger at the end of each calendar month. The Ledger will replace the preliminary data and recalculate the mitigation water distribution to determine the monthly volumes of mitigation delivery, pump-in project delivery, and CVP delivery.

Assumptions

- Mitigation water delivery to impacted Friant Contractors is the first water to be delivered.
- If delivery to a pump-in project proponent exceeds pump-in project input to FKC minus the mitigation volume, the remainder will be accounted for as CVP delivery.

FINAL WATER ACCOUNTING

The end of the month water accounting will be provided to the Friant Contractors for confirmation and their use for accounting with Reclamation. Friant Contractors will clearly show mitigation on their accounting reports as a separate volume of water. As needed, Friant Contractors will work with Reclamation to revise reporting in a timely manner. Mitigation volumes should be rounded and reported as a whole number in acre-feet.

WATER QUALITY ANNUAL REPORTING

The water quality for each year will be maintained in a database by FWA. The mitigation curve developed for the Ledger, as part of the Guidelines, uses relationships between water quality constituents of concern and

in-prism measurements of EC. At the conclusion of each year, the relationships will be updated with new water quality data collected during the year. The updated relationship will be shared with the Friant Contractors. Reclamation may also propose and/or require modifications to the Guidelines in coordination with FWA. Additionally, the Guidelines may be re-evaluated if any of the following conditions occurs:

- A future regulatory cost or equivalent fee is imposed on Friant Contractors and a portion of such fee can reasonably be attributed to the incremental difference of water quality conditions in the FKC.
- When Friant Division Class 1 contract allocation is less than or equal to 25 percent, the Water Quality Advisory Committee will convene as outlined in Attachment A of the Guidelines. In these years, mitigation will be accounted for as presented in these Guidelines, but will be deferred to a mutually agreed to later date unless those responsible for the put and take mutually agree to put and take the mitigation in the critical year. All monitoring requirements will remain as presented in the Guidelines.
- There is a significant, regulatory change or scientifically based justification and three out of the following five Friant Contractors agree and work with the Water Quality Advisory Committee to recommend a change: (1) Arvin-Edison Water Storage District, (2) Shafter Wasco Irrigation District, (3) Delano-Earlimart Irrigation District, (4) South San Joaquin Municipal Utility District, and (5) Kern-Tulare Water District.

Attachment E. FKC Water Quality Guidelines Cost Allocation

**Special Project
Summary Sheet**
Budget Sheet

Project Title: Friant-Kern Canal Water Quality Guidelines

Job Code: 6370

Project Location: Friant-Kern Canal (entire 152 miles)

Project Description: Friant Water Authority implementation and administration of the Friant-Kern Canal (FKC) Water Quality Guidelines (Guidelines). The Guidelines include requirements of discharge of water into the FKC, monitoring and reporting requirements, management, mitigation, communications, and forecasting.

Estimated Annual Project Costs (x1000): \$189.4

Materials and Laboratory

The continuous, real-time sampling of electrical conductivity (EC) at each of the specified check structures requires FWA to install a total of fourteen (14) Seametrics CT2X conductivity meters in the canal, at each structure. Costs for purchase and installation of the real-time water quality monitoring equipment, including integration with IOS, are approximately \$60,477 (\$1,898 per unit cost and total of \$33,905 for installation). It is assumed the useful life of a Seametrics CT2X conductivity meter is about 10 years at an interest rate of 3%. Additionally, FWA staff will maintain two (2) existing handheld Hanna DIST5 conductivity meters. Real-time water quality monitoring equipment and handheld conductivity meters will be calibrated and maintained according to manufacturer recommendations. Costs for maintenance of equipment is estimated to be about 10% of the capital cost (\$6,048 annually, shown as Item 5 in Table 1 below).

Table 1 summarizes the annual materials and lab costs of each monitoring requirement. Specifically, the item numbers in Table 1 refer to the sample source/type item numbers presented in Attachment B – Monitoring Program Summary. Details regarding assumptions are outlined in the narrative following Table 1.

Table 1: Materials and laboratory costs associated with monitoring activities.

Item ¹	Description	Estimated Annual Cost
5	Annual maintenance of equipment for continuous, real-time sampling of electrical conductivity at each specified check structure	\$6,048
6	Estimated exceedance testing	\$936
8	Weekly testing at FKC-CVC Intertie during pump-back operations	\$23,788
9	Testing during initiation of FKC-CVC Intertie pump-back operations	\$11,490
Materials and Lab Testing Subtotal:		\$42,262

¹ Item numbers refer to sample source/type item numbers presented in Attachment B.

Most requirements of the monitoring program (items 6 through 9 in Table 1) require FWA to collect samples and send them to labs for testing. Testing can include a full list of Title 22 constituents in Table 1 of the Guidelines, the short list of constituents in Table 4 of the Guidelines, or single constituents. Testing costs can vary significantly by lab. To be conservative, it was assumed that testing for full Title 22 constituents would be \$5,745, testing for the short list of constituents in Table 4 of the Guidelines would be \$915, and testing for single constituents would be \$59/constituent.

For a given year, it was assumed that single constituents would exceed the thresholds for two months per year and would result in 16 tests annually (4 weekly tests for each month with an exceedance, and 4 weekly tests below the threshold after the exceedance). This results in a total cost of \$936 for testing because of exceedances (item 6 in Table 1). Costs for EC testing during operations outages were not included as this will be done with the handheld units by FWA staff. It was assumed that pump-back operations would occur during 6 months of the year, which would require 26 samples of the full list of constituents in Table 4 of the Guidelines. This results in a total cost of \$23,788 for testing because of pump-back operations (item 8 in Table 1). Finally, it was assumed that full Title 22 testing due to initiation of pump-back operations or anticipated Cross Valley Canal operations that will impact water quality will occur two times per year and will cost \$11,490.

Annualized Capital Install and Replacement of Equipment Subtotal: \$7,090

Annual Materials and Lab Testing Subtotal: \$42,262

Friant Water Authority Staff

For implementation of the Guidelines, the following activities will be required of FWA staff:

- Maintain and calibrate conductivity meters on a bi-weekly basis
- Perform water quality sampling during pump-in operations
- Coordinate laboratory water quality testing
- Coordinate with Friant Division Long-Term Contractors on water quality data monitoring and analysis
- Manage water quality and operations database
- Perform weekly water quality reporting and forecasting using FKC Water Quality Model
- Perform weekly analysis to determine mitigation and distribution to respective Friant Division Long-Term Contractors using the FKC Water Quality Mitigation Ledger
- Coordinate with U.S. Department of the Interior, Bureau of Reclamation's South-Central California Area Office on water quality reporting, mitigation, and contractual requirements
- Coordinate and facilitate FWA committee on water quality

The annual cost for FWA Executive Team and Operations staff is estimated below:

Executive Team (WRM).....	104 hrs @\$111.43/hr	\$11,589
Water Operations (Senior Engineer).....	1664 hrs @\$77.16/hr	\$128,400

Annual Staff Labor Subtotal: \$139,989

General Justification: The Board of Directors, at the request of the Water Quality Ad Hoc Committee requested that staff develop new water quality guidelines for non-Millerton water introduced into the FKC. This plan originally stemmed from the environmental compliance requirements of both the Long-Term Recapture and Recirculation Plan and the FKC Reverse Pump-back Project.

Operating Impact: This estimate assumes implementation of the Guidelines will occur. Although the costs for finalizing the Guidelines, agreements, and environmental compliance will be applied separately, the administration and water quality monitoring outlined in the Guidelines will be applied to 6370. A portion of these costs will be reimbursed through a surcharge applied to those Friant contractors that introduce water into the FKC once the Guidelines are implemented.

Cost Allocation: Costs for implementation and administration of the Policy will be paid initially by the subset of Friant Division Long-Term Contractors who pay for FKC O&M to the FWA and subsequently will be reimbursed by contractors that introduce water (Put) into the FKC (Contributor). The Contributor will pay a dollar per acre-foot (\$/acre-foot[AF]) surcharge, or ‘Guidelines Surcharge,’ that will be credited back to the Friant Division Long-Term Contractors who pay for O&M to the FWA. The Guidelines Surcharge will be calculated by dividing the total annual costs incurred for administration of the Guidelines Program by the total annual deliveries of pump-in programs into the FKC. The Guidelines Surcharge will be applied to all introduced water even if it is not required to provide mitigation as defined in the Guidelines. Surcharge estimates can be provided for budgeting purposes on an annual basis. FWA will bill contractors for reimbursement of Guidelines Program costs based on actual volumes and costs incurred.

Guidelines Surcharge Estimate: Current pump-in programs pump approximately 36.6 thousand acre-feet (TAF) per year into the FKC based on recent 5-year average (2013-2018) as shown in Table 2.

Table 2: Current Pump-In Program 5-year Average (2013-2018)

Source	Annual Average (TAF)	Annual Maximum ¹ (TAF)
Sierra Water	17.8	344
Groundwater	14.7	117
CVC	4.1	149
Total Annual Average	36.6	610

¹ Based on existing compliance and approvals and anticipated renewals.

The potential annual maximum is much greater than the annual average; however, for purposes of setting an initial Guidelines Surcharge, an estimated 40 TAF per year of pump-ins is assumed to occur. This estimate includes the recent average of existing programs and anticipated 10% initial increase due to new programs or greater use of existing programs.

Monitoring and lab costs can be allocated based on location or source of introduced water. It is assumed that all monitoring and lab costs associated with operations at the CVC Intertie will be allocated to a surcharge applied only to water being brought in from the CVC. All other

monitoring and lab costs (e.g., lab costs associated with exceedances) will be allocated to other pump-ins. Other costs (e.g., annual maintenance of equipment, staff time) would be allocated to all pump-ins via a surcharge base.

Based on this approach, the estimated **Guidelines Surcharge would average about \$10.73 per AF for CVC Water and \$3.88 per AF for other pumps ins.** Each surcharge would increase about \$0.70 per AF if the surcharge were to consider recovering CEQA compliance costs over 10 years. The surcharge applied at the end of every year will be based on actual costs and deliveries, and methods for allocation can be reassessed every year by the Water Quality Advisory Committee.

**Extraordinary Maintenance Projects
Cost Summary**

Project Title: Friant Kern Canal Water Quality Program

Project Location and Department: Friant-Kern Canal (entire 152 miles) / Operations
Department

Estimated Total Project Cost (x1000): \$189.4

Estimated Total Material Cost (Including Fuel Costs, x1000): \$49.4

Breakdown of Estimated Costs

*All costs outside of Friant staff costs for CEQA compliance are not covered as part of this program
cost budget.*

Materials and Laboratory

Annualized Capital Install and Replacement of Equipment	\$7,090
Annual Materials and Lab Testing	\$42,246

Subtotal: \$49,336

Regular Labor (Hours and Cost):

Executive Team (WRM)..... 104 hrs @\$111.43/hr	\$11,589
Water Operations (Senior Engineer).....1664 hrs @\$77.16/hr	\$128,400

Subtotal: \$139,989

Total: \$189,325

Guidelines Surcharge (CVC) \$10.73 per AF

Guidelines Surcharge (All other) \$4.58 per AF



Friant-Kern Canal

Conveyance Fees for Non Friant-Kern Canal Contractors

Effective March 1, 2024 - February 28, 2025

Note - These Conveyance rates apply to all classes of water deliveries (Project & Non-Project) that are conveyed on the Friant-Kern Canal on behalf of any non-Long-Term Contractor of the FKC

References	
FY24 FKC OM&R Budget	\$ 12,442,000
MRCCP Phase 1 Budget	\$ 326,600,000
Avg. Last Two Wet Years Class 1, Class 2, & 215 Deliveries (2017 & 2019)	\$ 1,040,622
10-Year Rolling Avg Class 1 Deliveries (FY12 - FY21)	375,643

Numerator:
Denominator:
Rate / AF

215 / Flood Water Conveyance (Non-Long-Term) Routine OM&R Component	
Current OM&R Budget	\$ 12,442,000
Avg W (2017 & 2019)	1,040,622
	\$ 11.96

Numerator:
Denominator:
Rate / AF

215 / Flood Water Conveyance (Non-Long-Term) Replacement Component	
Annual MRCCP Phase 1 SLD	\$10,886,666.67
Avg W (2017 & 2019)	1,040,622
	\$ 10.46

215 / Flood Water Composite Conveyance Rate (FY 2024)	\$ 22.42
--	-----------------

Previous Year: \$21.65

Notes:

- 1/ This conveyance charge is for 215/Flood Water conveyed by a non-long-term Contractor.
- 2/ 215 & Flood Water Conveyance Charge reflects anticipated wet year conveyance and is differentiated from Conveyance of All other Water by NLT FKC Contractors



Numerator:
Denominator:
Rate / AF

Non-215/Flood Water Routine OM&R Conveyance Rate Component	
Current OM&R Budget	\$ 12,442,000
10-Year Rolling Average Class 1	375,643
	\$ 33.12

Notes:

- 1/ Rolling Average of Class 1 is representative of annual use of canal and includes use during dry/critical years
- 2/ Rolling Average of Class 1 approach maintains relatively stable rate from year to year for budgeting purposes

Numerator:
Denominator:
Rate / AF



Non-215/Flood Water Replacement (XM) Conveyance Rate Component	
Annual MRCCP Phase 1 SLD	\$10,886,666.67
10-Year Rolling Average Class 1	375,643
	\$ 28.98

Notes:

- 1/ Used Straight-Line Depreciation of MRCCP Phase 1 Cost over 30 years, no salvage value

Non-215/Flood Water Composite Conveyance Rate (WY 2024)	
	\$ 62.10

Previous Year: \$54.79





Appendix P: Opinions of Probable Construction Costs

PROVOST & PRITCHARD
CONSULTING GROUP

ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST

California State Water Resources Control Board - NORTHEAST TULARE COUNTY REGIONALIZATION FEASIBILITY STUDY

ALTERNATIVE 2 – 2 MGD SWTP, SYSTEM IMPROVEMENTS AND PHYSICAL CONSOLIDATION LOOP

PRELIMINARY

August 21, 2025

Item No.	Item Description	Quantity	Unit	Unit Price	Amount
GENERAL CONDITIONS¹					
1	Mobilization/Demobilization, Bonds and Insurance and Permits (5%)	1	LS	\$ 2,093,000	\$ 2,093,000
2	Worker and Public Protection (2%)	1	LS	\$ 837,000	\$ 837,000
3	Miscellaneous Facilities and Operations (5%)	1	LS	\$ 2,093,000	\$ 2,093,000
4	Traffic Control	1	LS	\$ 132,000	\$ 132,000
5	Dust Control	1	LS	\$ 5,000	\$ 5,000
6	Prepare SWPPP	1	LS	\$ 10,000	\$ 10,000
7	Utility Potholing	1	LS	\$ 66,000	\$ 66,000
8	Clearing and Grubbing	1	LS	\$ 20,000	\$ 20,000
9	Unknown Utility Conflicts	1	LS	\$ 10,000	\$ 10,000
				Subtotal	\$ 5,266,000
FIELD COSTS					
	Surface Water Treatment Plant				
10	18" C900 PVC Raw Water pipeline	18,480	LF	\$ 240	\$ 4,436,000
11	FKC Turnout	1	LS	\$ 700,000	\$ 700,000
12	Raw Water Screening Structure	1	LS	\$ 340,000	\$ 340,000
13	Raw Water Pumping Station	1	LS	\$ 260,000	\$ 260,000
14	Packaged Filtration System	1	LS	\$ 1,500,000	\$ 1,500,000
15	Transfer and Backwash Pumping Station	1	LS	\$ 300,000	\$ 300,000
	Finished Water Storage Tank	1	LS	\$ 475,000	\$ 475,000
	Blending Tank	1	LS	\$ 1,390,000	\$ 1,390,000
16	Chemical Storage Building and Equipment	1	LS	\$ 1,500,000	\$ 1,500,000
17	High Service Pumping Station	1	LS	\$ 640,000	\$ 640,000
18	Operations and Controls Building	1	LS	\$ 625,000	\$ 625,000
19	Washwater Equalization Basin	1	LS	\$ 300,000	\$ 300,000
20	Reclaim Pumping Station	1	LS	\$ 150,000	\$ 150,000
21	Clarifier	1	LS	\$ 500,000	\$ 500,000
22	Sludge Holding Tank	1	LS	\$ 100,000	\$ 100,000
23	Screw Press Skid	1	LS	\$ 500,000	\$ 500,000
	Yard Piping	1	LS	\$ 1,500,000	\$ 1,500,000
	Site Fencing and Access Gates	1	LS	\$ 80,000	\$ 80,000
24	Site Demo, Clearing and Grubbing	1	LS	\$ 60,000	\$ 60,000
25	Site Grading, Paving and Surfacing	1	LS	\$ 600,000	\$ 600,000
26	Site Painting, Coating, and Signage	1	LS	\$ 250,000	\$ 250,000
27	Electrical, Scada & Controls	1	LS	\$ 3,000,000	\$ 3,000,000
28	Emergency Generator	1	LS	\$ 350,000	\$ 350,000
	Water mains				
29	8" C900 PVC Blending piping (Orosi Well 8)	5,000	LF	\$ 160	\$ 800,000
30	8" C900 PVC Blending piping (Orosi Well 10)	1,400	LF	\$ 160	\$ 224,000
31	8" C900 PVC Blending piping (East Orosi Well 3)	1,000	LF	\$ 160	\$ 160,000
32	12" C900 PVC (Yettem to Monson)	26,400	LF	\$ 180	\$ 4,752,000
33	12" C900 PVC (Sultana to Orosi)	18,480	LF	\$ 180	\$ 3,327,000
34	12" C900 PVC (East Orosi to Yettem)	21,120	LF	\$ 180	\$ 3,802,000
35	8" C900 PVC in Railroad ROW (Seville)	10,560	LF	\$ 240	\$ 2,535,000
36	16" C900 PVC Finished Water pipeline	3,000	LF	\$ 210	\$ 630,000
37	Relocate PRV Sultana to Monson	1	LS	\$ 25,000	\$ 25,000
38	Install New PRV at Monson	1	LS	\$ 50,000	\$ 50,000
39	12" Isolation Valves (1/2 mile intervals)	28	EA	\$ 5,000	\$ 140,000
40	Permanent Trench Resurfacing	73,400	LF	\$ 55	\$ 4,037,000
	Site Improvements				
41	Relocate PRV Sultana to Monson	1	LS	\$ 25,000	\$ 25,000
42	Install New PRV at Monson	1	LS	\$ 50,000	\$ 50,000
43	8" C900 PVC Off site piping (Monson)	1,250	LF	\$ 165	\$ 207,000
44	Demo 60,000-gallon bolted Steel Tank and appurtenances	1	LS	\$ 15,000	\$ 15,000
45	Demo 150,000-gallon Bolted Steel Tank and appurtenances	1	LS	\$ 37,500	\$ 38,000
46	Rebowl Monson Well	1	LS	\$ 50,000	\$ 50,000
47	New Monson Well Motor (50 HP)	1	LS	\$ 25,000	\$ 25,000
48	Hydropneumatic Tank	1	LS	\$ 220,000	\$ 220,000
	Electrical and Controls Modification				
49	Well Site Instrumentation and Controls modifications (budgetary)	1	LS	\$ 200,000	\$ 200,000
50	Furnish and Install Back Up Generators (East Orosi)	2	EA	\$ 350,000	\$ 700,000
51	Install new PSV and Site Piping (Tank Fill)	4	EA	\$ 50,000	\$ 200,000
52	Install new Check Valve and Tank Fill modifications	4	EA	\$ 25,000	\$ 100,000
	Well Destruction				
53	Yettem and Seville, Y1, Y2, S1, and S2	4	EA	\$ 50,000	\$ 200,000
				CONSTRUCTION SUBTOTAL	\$ 47,334,000
				CONTINGENCY (30%)	\$ 14,200,000
				CONSTRUCTION TOTAL	\$ 61,534,000
NON-CONSTRUCTION COSTS					
	Non-Construction				
54	Property Costs	4.1	AC	\$ 75,000	\$ 308,000
55	Engineering Design (12%)	1	LS	\$ 7,384,000	\$ 7,384,000
56	Construction Management and Inspection (7%)	1	LS	\$ 4,307,000	\$ 4,307,000
57	Environmental, Legal, and Administration (5%)	1	LS	\$ 3,077,000	\$ 3,077,000
				NON-CONSTRUCTION SUBTOTAL	\$ 15,076,000
				CONTINGENCY (30%)	\$ 4,523,000
				NON-CONSTRUCTION TOTAL	\$ 19,599,000
				GRAND TOTAL	\$ 81,133,000
Notes & Assumptions					
1	This estimate represents the opinion of probable cost based on the engineer's experience with prior projects, recent bid canvasses, and cost sources such as RS Means.				
2	Costs presume work will be publicly bid as a public works project.				
3	Amount totals rounded up to the nearest one-thousand dollars.				
4	Percentages are of the Field Costs.				
5	Construction costs based on current dollars. Construction schedule may impact construction cost.				
6	Construction costs do not include mitigation measures for the biologist or construction observation.				
7	Construction costs do not include PG&E overhead work.				

PROVOST & PRITCHARD
CONSULTING GROUP

ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST

California State Water Resources Control Board - NORTHEAST TULARE COUNTY REGIONALIZATION FEASIBILITY STUDY

ALTERNATIVE 3 – 4.5 MGD SWTP, SYSTEM IMPROVEMENTS AND PHYSICAL CONSOLIDATION LOOP

PRELIMINARY

August 21, 2025

Item No.	Item Description	Quantity	Unit	Unit Price	Amount
GENERAL CONDITIONS*					
1	Mobilization/Demobilization, Bonds and Insurance and Permits (5%)	1	LS	\$ 2,146,000	\$ 2,146,000
2	Worker and Public Protection (2%)	1	LS	\$ 859,000	\$ 859,000
3	Miscellaneous Facilities and Operations (5%)	1	LS	\$ 2,146,000	\$ 2,146,000
4	Traffic Control	1	LS	\$ 100,320	\$ 100,000
5	Dust Control	1	LS	\$ 5,000	\$ 5,000
6	Prepare SWPPP	1	LS	\$ 10,000	\$ 10,000
7	Utility Potholing	1	LS	\$ 50,160	\$ 50,000
8	Clearing and Grubbing	1	LS	\$ 20,000	\$ 20,000
9	Unknown Utility Conflicts	1	LS	\$ 10,000	\$ 10,000
				Subtotal	\$ 5,346,000
FIELD COSTS					
	Surface Water Treatment Plant				
10	18" C900 PVC Raw Water pipeline	18,480	LF	\$ 240	\$ 4,436,000
11	FKC Turnout	1	LS	\$ 700,000	\$ 700,000
12	Raw Water Screening Structure	1	LS	\$ 300,000	\$ 300,000
13	Raw Water Pumping Station	1	LS	\$ 260,000	\$ 260,000
14	Packaged Filtration System	1	LS	\$ 2,800,000	\$ 2,800,000
15	Transfer and Backwash Pumping Station	1	LS	\$ 400,000	\$ 400,000
	Finished Water Storage Tank	1	LS	\$ 475,000	\$ 475,000
	Blending Tank	1	LS	\$ 1,390,000	\$ 1,390,000
16	Chemical Storage Building and Equipment	1	LS	\$ 1,500,000	\$ 1,500,000
17	High Service Pumping Station	1	LS	\$ 840,000	\$ 840,000
18	Operations and Controls Building	1	LS	\$ 625,000	\$ 625,000
19	Washwater Equalization Basin	1	LS	\$ 300,000	\$ 300,000
20	Reclaim Pumping Station	1	LS	\$ 150,000	\$ 150,000
21	Clarifier	1	LS	\$ 500,000	\$ 500,000
22	Sludge Holding Tank	1	LS	\$ 100,000	\$ 100,000
23	Screw Press Skid	1	LS	\$ 500,000	\$ 500,000
	Yard Piping	1	LS	\$ 1,500,000	\$ 1,500,000
	Site Fencing and Access Gates	1	LS	\$ 80,000	\$ 80,000
24	Site Demo, Clearing and Grubbing	1	LS	\$ 60,000	\$ 60,000
25	Site Grading, Paving and Surfacing	1	LS	\$ 600,000	\$ 600,000
26	Site Painting, Coating, and Signage	1	LS	\$ 250,000	\$ 250,000
27	Electrical, Scada & Controls	1	LS	\$ 3,000,000	\$ 3,000,000
28	Emergency Generator	1	LS	\$ 350,000	\$ 350,000
	Water mains				
29	8" C900 PVC Blending piping (Orosi Well 8)	5,000	LF	\$ 160	\$ 800,000
30	8" C900 PVC Blending piping (Orosi Well 10)	1,400	LF	\$ 160	\$ 224,000
31	8" C900 PVC Blending piping (East Orosi Well 3)	1,000	LF	\$ 160	\$ 160,000
32	12" C900 PVC (Yettem to Monson)	26,400	LF	\$ 180	\$ 4,752,000
33	12" C900 PVC (Sultana to Orosi)	18,480	LF	\$ 180	\$ 3,327,000
34	12" C900 PVC (East Orosi to Yettem)	21,120	LF	\$ 180	\$ 3,802,000
35	8" C900 PVC in Railroad ROW (Seville)	10,560	LF	\$ 240	\$ 2,535,000
36	16" C900 PVC Finished Water pipeline	3,000	LF	\$ 210	\$ 630,000
37	Relocate PRV Sultana to Monson	1	LS	\$ 25,000	\$ 25,000
38	Install New PRV at Monson	1	LS	\$ 50,000	\$ 50,000
39	12" Isolation Valves (1/2 mile intervals)	28	EA	\$ 5,000	\$ 140,000
40	Permanent Trench Resurfacing	73,400	LF	\$ 55	\$ 4,037,000
	Site Improvements				
41	Relocate PRV Sultana to Monson	1	LS	\$ 25,000	\$ 25,000
42	Install New PRV at Monson	1	LS	\$ 50,000	\$ 50,000
43	Demo 60,000-gallon bolted Steel Tank and appurtenances	1	LS	\$ 15,000	\$ 15,000
44	Demo 150,000-gallon Bolted Steel Tank and appurtenances	1	LS	\$ 37,500	\$ 38,000
	Electrical and Controls Modification				
45	Well Site Instrumentation and Controls modifications (budgetary)	1	LS	\$ 200,000	\$ 200,000
46	Furnish and Install Back Up Generators (East Orosi)	2	EA	\$ 350,000	\$ 700,000
47	Install new PSV and Site Piping (Tank Fill)	4	EA	\$ 50,000	\$ 200,000
48	Install new Check Valve and Tank Fill modifications	4	EA	\$ 25,000	\$ 100,000
	Well Destruction				
49	Yettem and Seville, Y1, Y2, S1, and S2	4	EA	\$ 50,000	\$ 200,000
				CONSTRUCTION SUBTOTAL	\$ 48,472,000
				CONTINGENCY (30%)	\$ 14,542,000
				CONSTRUCTION TOTAL	\$ 63,014,000
NON-CONSTRUCTION COSTS					
	Non-Construction				
50	Property Costs	4.1	AC	\$ 75,000	\$ 308,000
51	Engineering Design (12%)	1	LS	\$ 7,562,000	\$ 7,562,000
52	Construction Management and Inspection (7%)	1	LS	\$ 4,411,000	\$ 4,411,000
53	Environmental, Legal, and Administration (5%)	1	LS	\$ 3,151,000	\$ 3,151,000
				NON-CONSTRUCTION SUBTOTAL	\$ 15,432,000
				CONTINGENCY (30%)	\$ 4,630,000
				NON-CONSTRUCTION TOTAL	\$ 20,062,000
				GRAND TOTAL	\$ 83,076,000
Notes & Assumptions					
^{1/1}	This estimate represents the opinion of probable cost based on the engineer's experience with prior projects, recent bid canvasses, and cost sources such as RS Means.				
^{1/2}	Costs presume work will be publicly bid as a public works project.				
^{1/3}	Amount totals rounded up to the nearest one-thousand dollars.				
^{1/4}	Percentages are of the Field Costs.				
^{1/5}	Construction costs based on current dollars. Construction schedule may impact construction cost.				
^{1/6}	Construction costs do not include mitigation measures for the biologist or construction observation.				
^{1/7}	Construction costs do not include PG&E overhead work.				

Appendix Q: DDW Letter Re. Governance Term Sheet and Project Alternative Selections



State Water Resources Control Board

Division of Drinking Water

August 7, 2025

Orosi Public Utility District
Cutler Public Utility District
East Orosi Community Services District
Yetttem Water System
Seville Water Company
Monson Water System
Sultana Community Services District

Subject: Governance Term Sheet and Project Alternative Selections

Dear Water Systems:

The State Water Resources Control Board (Board) has funded a draft regional consolidation feasibility study for the Northeast Tulare County (NTC) region. The water systems included in the regional study include Cutler PUD, Orosi PUD, East Orosi CSD, Yetttem, Seville Water Company, Monson, and Sultana CSD. The Board in partnership with local and regional stakeholders, remains committed to supporting a long-term, sustainable drinking water solution to address the ongoing water quality and quantity issues in the region. Your participation in the early stages of this regional project has been instrumental in identifying potential infrastructure and governance alternatives to address ongoing challenges in the region. Furthermore, ongoing commitment to and implementation of a regional governance structure and drinking water infrastructure should allow the region to provide a sustainable source of safe drinking water resilient to future challenges such as changes in climate, water quality and economic conditions.

To consider any further investment in a **regional drinking water project**, the Board requests that each participating utility submit the following two items by **December 19, 2025**:

1. Selected Project Alternative

We request that each water system submit its preferred infrastructure alternative from among those presented in the feasibility study completed by Provost & Pritchard Consulting Group. Alternative 1: Individual System Improvements and Physical

E. JOAQUIN ESQUIVEL, CHAIR | ERIC OPPENHEIMER, EXECUTIVE DIRECTOR

Consolidation Loop, Alternative 2: Regional Surface Water Treatment Plant Partial Supply, and Alternative 3: Regional Surface Water Treatment Plant. The selected alternative should represent a viable solution that addresses your water system's current and projected water service needs, while balancing technical feasibility, financial sustainability, and long-term operational resilience.

2. Joint Governance Term Sheet

We request a draft Governance Term Sheet be developed jointly among all participating water systems. This document should outline the preliminary agreements regarding the governance structure that will support the implementation and long-term management of the regional project. The draft Governance Term Sheet is a collaborative product. We request that each water system individually review and formally sign off on a collaborative draft Governance Term Sheet and submit it to us by December 19th, 2025.

A draft Governance Term Sheet is a non-binding, foundational document that summarizes the key terms, intentions, and proposed structure of a future governance agreement. It typically includes:

- The proposed governance model to be pursued (e.g. MUD, CSD, CSA)
- The preliminary structure for board representation and decision-making
- A general timeline and next steps for implementation (e.g., LAFCO process, legal reviews, public outreach)
- Points of agreement and areas still under discussion

The purpose of the Governance Term Sheet is to ensure mutual understanding, build alignment, and establish a path forward as the water systems move toward formal consolidation.

Governance Recommendation and Principles

The Board believes that the success of a regional project depends not only on physical infrastructure, but also on the establishment of a unified, durable, and inclusive governance structure. Fragmented or temporary governance arrangements present long-term risks to operational stability, financial integrity, and equitable service delivery, particularly for small or disadvantaged communities.

To guide the development of a successful governance proposal for the draft Governance Term Sheet, the Board offers the following principles for sustainable utility governance, aligned with the state's expectations for Technical, Managerial, and Financial (TMF) Capacity:

- **Unified Governance:** A single governing body with clear legal authority to manage infrastructure, oversee finances, and make operational decisions across the service area. This unified structure improves coordination, strengthens technical

oversight, and supports long-term regulatory compliance. It ensures that all parts of a system, from source through the distribution system to customer service, are overseen with equal responsibility, equitable representation, and access to resources.

- **Financial Resilience:** A unified financial structure across the region promotes responsible funding of operations, maintenance, and capital improvements; enables long-term rate stability; and increases access to external funding. While there may be infrastructure improvement areas or zones that have different timebound investment needs for transition projects, ultimately a unified financial structure provides a broad, stable financial foundation to maintain adequate infrastructure and services.
- **Permanence:** The governance structure should be designed for permanence. Long-term operational financial and legal stability are essential to protecting public health, maintaining service continuity, and avoiding the need for future reorganization. A permanent structure promotes regulatory confidence, community trust, and sustained investment.

Recommended Governance Structures

While the specific preferred governance proposal that is chosen to be included in the draft term sheet should be developed collaboratively by the local communities, we want to be clear that there are restrictions and priorities within the Board's funding and permitting that must be accounted for in order to be competitive for any further investment in a regional project. In response to participant feedback from the series of regional discussions thus far, we want to clarify how the governance principles outlined above effectively narrow the governance options that we would consider for further investment.

The Board recommends that any governance proposal included in the draft Governance Term Sheet be **a single, unified, independent special district**. There are a variety of types of special districts that may be appropriate for the region. In the interest of furthering a successful regional project, the board recommends that a draft Governance Term Sheet include the specific type or structure for a single independent special district that is appropriate for the region. To help with that discussion, the following are our recommendations for types of special districts that we believe may be most appropriate for the needs in this region. Each of these are locally governed and able to sustainably provide multiple utility services.

In the State Water Board's experience, the model most likely to provide sustainable and successful governance for the North Tulare County region is a Municipal Water District, followed by a Community Services District and finally a County Water District.

- **Municipal Water District (MWD):** A special district that provides public services, primarily water and wastewater services, to communities. MWDs are governed by

a board of directors, which may be elected or appointed, depending on the district's structure.

- **Community Services District (CSD):** A locally governed special district that can provide water, sewer, street lighting, and other services, with flexible board representation and service zone structures.
- **County Water District (CWD):** A special district that provides water and/or sewer services to areas, typically outside of incorporated cities, within a county. CWDs are governed by an elected board or a similar body that makes decisions about water rates, infrastructure development, and other related matters.

In addition to the required elements, these governance options can ensure that there is equitable representation of all the communities involved and public accountability. They also offer the opportunity for different ways to transition into the final governance form and can ensure fairness in cost distribution. Finally, they offer the greatest access to financing options and structures that would address the need for long-term financial stability.

To proceed with the next phase of the regional project, please submit both the Selected Project Alternative and a draft Governance Term Sheet by December 19, 2025. If no submissions are made, the Board will terminate technical assistance for a regional project under the assumption that the parties are unable to agree on a governance structure or project alternative. We appreciate your continued partnership and look forward to continuing to work with you on the Northeast Tulare County Regional project.

Sincerely,

A handwritten signature in black ink, appearing to read "Andrew Altevogt". The signature is fluid and cursive, with a long horizontal stroke at the end.

Andrew Altevogt, P.E.
Assistant Deputy Director
State Water Resources Control Board, Division of Drinking Water

cc:

Cutler Public Utility District
cutlerpud@sbcglobal.net

Orosi Public Utility District
orosipud@sbcglobal.net

East Orosi CSD Administrator
dengland@tularecounty.ca.gov

Monson Water System & Sultana Community Services District
sultanacsd@gmail.com

Yettem Water System & Seville Water Company
CVPerez@tularecounty.ca.gov

Ben Giuliani
Tulare County LAFCo
bgiuliani@tularecounty.ca.gov

Paige Kadavy
Self-Help Enterprises
paigek@selfhelpenterprises.org

Shawn Demmers
Division of Drinking Water
shawn.demmers@waterboards.ca.gov

James Garrett
Division of Financial Assistance
james.garrett@waterboards.ca.gov

Appendix R: Comment Resolution

No.	RECEIVED FROM	COMMENT	RESPONSE
1	Cutler-Orosi FS Review – SWRCB DFA	There is currently an executed Expedited Drinking Water Grant (EDWG) for the EOCSD – OPUD Consolidation Project	Added this information to Section 1.4.2
2	Cutler-Orosi FS Review – SWRCB DFA	Usage of DDW where SWRCB should be utilized	Replaced some instances of DDW with SWRCB
3	Cutler-Orosi FS Review – SWRCB DFA	The DWSRF IUP restricts eligible contingency to 20%	The Feasibility Study uses 30% contingency as a basis for comparing alternatives at a low level of project definition. For a DWSRF funding application, an Engineering Report will be required where contingency will be reduced to 20% reflecting a better defined project.
4	Cutler-Orosi FS Review – SWRCB DDW	The capacity of Cutler Well 10 needs to be updated.	The estimated capacity of Well C10 has been updated to 750 GPM per the project specifications.
5	Cutler-Orosi FS Review – SWRCB DDW	The CPUD blending tank was constructed in October 2019, but has not been operable because it needs Well 10 to be equipped.	Revised Section 2.1.2.2 to include the construction date of CPUD’s blending tank.
6	Cutler-Orosi FS Review – SWRCB DDW	It is estimated for the CPUD Well 10 Project to be completed in 2026 or early 2027. Cutler PUD anticipates going out to bid for the final portion which includes equipping Well No. 10, installing booster pump station, a hydro tank and appurtenances all before Summer 2025. The Board, Department of Water Resources and Tulare County have provided funding for this project.	Revised Section 2.1.2.1 to reflect the estimated completion date for the CPUD Well 10 Project. Bidding is now anticipated in the Fall 2025.
7	Cutler-Orosi FS Review – SWRCB DDW	The contingency line item for each table should be revised to reflect that only 20% contingency is currently eligible for funding. Contingency should only be included in one line item.	See response to Comment 3. 30% contingency has been consolidated into a single line item.
8	SWRCB DDW	Requested clarification of the plant vs site capacity, accounting for ratio of groundwater and surface water blended at the site and total site output in Alternative 2.	Section 6.2.2 has been revised to clarify Alternative 2 includes production of 1,400 GPM treated surface water. 700 GPM groundwater would be piped to the SWTP for blending with treated surface water. The site would typically provide 2,100

			GPM of the system demand. The remainder of the total 3,150 GPM system demand would be from other existing groundwater wells within the overall system. These would not need to be piped to the SWTP site prior to distribution.
9	CWC NTCRWP Comment Letter	CWC requested inclusion of their efforts to address acute and long-term domestic well needs for properties surrounding Cutler, Orosi, and East Orosi	Included Domestic Well Study in Current Projects (1.4.5).
10	CWC NTCRWP Comment Letter	CWC requested consideration of other domestic well users in a potential regionalization project	Domestic well users are outside the existing service areas, requiring extra territorial service agreements with the existing districts or a boundary change approved by LAFCo. Language has been added to that effect in the governance section indicating that consideration could be given to domestic well owners at formation and in drawing the boundaries of a new Independent Special District. It is beyond the scope of this study to attempt to determine demands, however a surface water alternative would potentially be expandable to accommodate increased demand. Alternative 1 supply is limited by the existing groundwater wells and the ability to drill additional wells in the region.
11	Community Question	Are the rates presented in Table 8-6 total rates or in addition to our current rates?	It is important to note that these are preliminary estimates and will need to be refined as the project becomes better defined. However, the estimated rates are intended to be the total average monthly rates required.
12	Community Question	Is it possible to phase the project?	Yes, the alternatives are set up in a naturally phased approach. Alternative 1 would be the initial phase of interconnecting all of the community systems. Then, Alternative 2 would be construction of a surface water treatment plant to supplement the existing groundwater wells. Alternative 3 could then be implemented to expand the surface water treatment plant.