# State of California CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD LOS ANGELES REGION 320 West 4th Street, Suite 200, Los Angeles

FACT SHEET
WASTE DISCHARGE REQUIREMENTS
FOR
CITY OF FILLMORE

(Sespe Creek Levee Construction Project)
ORDER NO. R4-2003-0111 (SERIES NO. 116)
NPDES NO. CAG994004
CI-9070

# **FACILITY LOCATION**

Sespe Creek near Highway 126 Bridge, Fillmore, CA 93015

### **FACILITY MAILING ADDRESS**

250 Central Avenue Fillmore, CA 93015

#### PROJECT DESCRIPTION

City of Fillmore (The City) proposes to construct a levee along Sespe Creek near Highway 126 Bridge to provide flood protection for a new municipal wastewater treatment plant. Dewatering is anticipated during construction and it will last within six months. The City proposes to discharge approximately 2.5 million gallons per day (mgd) of groundwater. The high rate of discharge is necessary because the construction project is being conducted on the bank of Sespe creek. The groundwater will be pumped into a temporary basin to allow sediment to settle out prior to discharge into Sespe Creek.

## **VOLUME AND DESCRIPTION OF DISCHARGE**

Up to 2.5 mgd of groundwater will be discharged at Latitude 34°23'28", Longitude 118°56'33". The discharge flows to the Sespe Creek, thence to the Santa Clara River, a water of the United States. Should the construction project last past six months. Then the discharge rate will be limited to no greater than 1.0 mgd. The site location is shown as Figure 1.

#### **APPLICABLE EFFLUENT LIMITATIONS**

Based on the information provided in the NPDES Application Supplemental Requirements, the following constituents listed in the Table below have been determined to show reasonable potential to exist in the discharge. The discharge flows to the Santa Clara River between A Street, Fillmore and Freeman Diversion "Dam" near Saticoy. This stream reach of the Santa Clara River is designated as MUN (Existing) beneficial use.

September 19, 2006

The discharge of groundwater satisfies the provisions for creekside construction dewatering opeartions in Order No. R4-2003-0111. Therefore, the discharge limitations in Attachment B.3.f. are not applicable to the discharge except for boron.

This Table lists the specific constituents and effluent limitations applicable to the discharge.

		Discharge Limitations	
Constituents	Units	Daily Maximum	<b>Monthly Average</b>
Total Suspended Solids	mg/L	150	50
Turbidity	NTU	150	50
Oil and Grease	mg/L	15	10
BOD <sub>5</sub> 20°C	mg/L	30	20
Settleable Solids	ml/L	0.3	0.1
Sulfides	mg/L	1.0	
Boron	mg/L	1.5	
Nitrogen*	mg/L	5.0	
Phenols	mg/L	1.0	
Residual Chlorine	mg/L	0.1	
Methylene Blue Active Substances (MBAS)		0.5	

Nitrate nitrogen plus + nitrite nitrogen.

## FREQUENCY OF DISCHARGE


The discharge of groundwater will commence in the Fourth Quarter of 2006. The dewatering phase of the project will last approximately six months.

### **REUSE OF WATER**

It is not feasible to discharge the groundwater to the sanitary sewer system. It is not economically feasible to haul the wastewater for off-site disposal. Therefore, the groundwater will be discharged to the creek in compliance with the requirements of the attached order.

January 2006 Project No. 0502-2471

FIGURE 1





SITE LOCATION MAP

City of Fillmore (Sespe Creek Levee Construction Project) Fact Sheet

CI-9070