STATE OF CALIFORNIA CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD LOS ANGELES REGION 320 West 4th Street, Suite 200, Los Angeles, California 90013

FACT SHEET WASTE DISCHARGE REQUIREMENTS FOR

WORLD SAVINGS CENTER

ORDER NO. R4-2003-0111 NPDES NO. CAG994004, SERIES NO. 215 CI-9221

FACILITY ADDRESS 11601 Wilshire Blvd. Los Angeles, CA 90025

FACILITY MAILING ADDRESS

CarrAmerica 11601 Wilshire Blvd., Suite 102 Los Angeles, CA 90025

PROJECT DESCRIPTION:

World Savings Center proposes to pump and discharge seepage groundwater from its subterranean structure at the above-referenced facility. The groundwater from the building drainage system is collected in a sump and discharged intermittently to a nearby storm drain.

VOLUME AND DESCRIPTION OF DISCHARGE:

Approximately 80,000 gallons per day of groundwater will be discharged into a nearby storm drain (Latitude: 34° 03' 03" and Longitude: 118° 27' 33") thence, to Ballona Creek. The site location map is shown in Figure 1.

APPLICABLE EFFLUENT LIMITATIONS

Based on the information provided in the NPDES Application Supplemental Requirements, the following constituents listed in the Table below have been determined to show reasonable potential to exist in your discharge. The discharge from the project site flows into Ballona Creek. Therefore the limitations in Attachment B of Order No. R4-2003-0111 are not applicable to your discharge.

This Table lists the specific constituents and effluent limitations applicable to the discharge.

	Units	Discharge Limitations	
Constituents		Daily Maximum	Monthly Average
Total Suspended Solids	mg/L	150	50
Turbidity	NTU	150	50
BOD ₅ 20°C	mg/L	30	20
Oil and Grease	mg/L	15	10
Settleable Solids	ml/L	0.3	0.1


		Discharge Limitations	
Constituents	Units	Daily Maximum	Monthly Average
Sulfides	mg/L	1.0	
Phenols	mg/L	1.0	
Residual Chlorine	mg/L	0.1	
Methylene Blue Active Substances (MBAS)	mg/L	0.5	WW.

FREQUENCY OF DISCHARGE:

The discharge of groundwater will be intermitent.

REUSE OF WATER:

It is not economically feasible to haul the groundwater for off-site disposal. Since there are no other feasible reuse options, groundwater generated from the site will be discharged in compliance with the attached Order.



Site Location Figure 1