

California Regional Water Quality Control Board

Los Angeles Region



Recipient of the 2001 Environmental Leadership Award from Keep California Beautiful

Arnold Schwarzenegger Governor

320 W. 4th Street, Suite 200, Los Angeles, California 90013 Phone (213) 576-6600 FAX (213) 576-6640 - Internet Address: http://www.waterboards.ca.gov/losangeles

Jeff Pratt Ventura County Watershed Protection District 800 South Victoria Avenue Ventura, CA, 93009

WATER QUALITY CERTIFICATION FOR PROPOSED HARMON BARRANCA CHANNEL REPAIR PROJECT (Corps' Project No. 2007-477-AJS), HARMON BARRANCA, TRIBUTARY TO SANTA CLARA RIVER, VENTURA COUNTY (File No. 07-059)

Dear Mr. Pratt:

Board staff has reviewed your request on behalf of Ventura County Watershed Protection District (Applicant) for a Clean Water Act Section 401 Water Quality Certification for the above-referenced project. Your application was deemed complete on November 21, 2007.

I hereby issue an order certifying that any discharge from the referenced project will comply with the applicable provisions of sections 301 (Effluent Limitations), 302 (Water Quality Related Effluent Limitations), 303 (Water Quality Standards and Implementation Plans), 306 (National Standards of Performance), and 307 (Toxic and Pretreatment Effluent Standards) of the Clean Water Act, and with other applicable requirements of State law. This discharge is also regulated under State Water Resources Control Board Order No. 2003 - 0017 - DWQ, "General Waste Discharge Requirements for Dredge and Fill Discharges that have received State Water Quality Certification."

The Applicant shall be liable civilly for any violations of this Certification in accordance with the California Water Code. This Certification does not eliminate the Applicant's responsibility to comply with any other applicable laws, requirements and/or permits.

Should you have questions concerning this Certification action, please contact Dana Cole, Section 401 Program, at (213) 576-5733.

[Original Signed By] Tracy J. Egoscue Executive Officer December 26, 2007 Date

California Environmental Protection Agency

DISTRIBUTION LIST

Theresa Stevens Ventura County Watershed Protection District 800 South Victoria Avenue Ventura, CA, 93009

Bill Orme State Water Resources Control Board Division of Water Quality P.O. Box 944213 Sacramento, CA 94244-2130

Natasha Lohmus California Department of Fish and Game Streambed Alteration Team 4949 View Ridge Avenue San Diego, CA 92123

Antal Szijj U.S. Army Corps of Engineers Regulatory Branch, Ventura Field Office 2151 Alessandro Drive, Suite 255 Ventura, CA 93001

Aaron Setran (WTR-8) U.S. Environmental Protection Agency, Region 9 75 Hawthorne Street San Francisco, CA 94105

Dave Smith Supervisor, Wetlands Regulatory Office (WTR-8) US EPA, Region 9 75 Hawthorne San Francisco, CA 94105

Diane Noda U.S. Fish and Wildlife Service 2493 Portola Road, Suite B Ventura, CA 93003

Vicki Clark, Staff Attorney Environmental Defense Center 906 Garden Street Santa Barbara, CA 93101 Jessie Altstatt Santa Barbara Channel Keeper 714 Bond Street Santa Barbara, CA 93103

Peter Brand Coastal Conservancy 1330 Broadway, Suite 1100 Oakland, CA 94612

Project Information File No. 07-059

1. Applicant:	Jeff Pratt Ventura County Watershed Protection District 800 South Victoria Avenue Ventura, CA, 93009		
	Phone: (805) 654-2040	Fax: (805) 654-3350	
2. Applicant's Agent:	Theresa Stevens Ventura County Watershed Protection District 800 South Victoria Avenue Ventura, CA, 93009		
	Phone: (805) 477-7139	Fax: (805) 654-3350	
3. Project Name:	Harmon Barranca Channel Repair		
4. Project Location:	Ventura, Ventura County		
	Longitude	Latitude:	
	119° 11' 42.41"	34° 15' 41.65''	
	119° 11' 42.41 119° 11' 39.67"	34° 15' 42.03"	
	119° 11' 43.85"	34° 15' 47.26"	
	119° 11' 40.85"	34° 15' 48.45"	
	119° 11' 39.30"	34° 15' 53.20"	
	119° 11' 43.25"	34° 16' 01.27"	
	119° 11' 41.59"	34° 16' 06.96"	
	119° 11' 46.13"	34° 16' 27.84"	
5. Type of Project:	Flood control facility repair	ſ	

Project Information File No. 07-059

7. Project Description:	The project involves repair to an existing flood control channel in various locations. The Harmon Barranca is maintained vegetation- free. The project involves repairs to existing rock rip rap, grouted rock, earthen fill areas, culverts and energy dissipaters.	
	Area 1: Repair existing grouted rock only on east bank slope by placing ¹ / ₂ ton grouted rock at a 1.5:1 slope for a distance of 80 linear feet, 960 square feet. No additional grouted rock will be created or added.	
	Area 2: Repair east bank slope by placing 1-ton loose rock for a distance of 50 linear feet, 750 square feet.	
	Area 3: Repair west bank slope by placing 1-ton loose rock for a distance of 30 linear feet, 450 square feet.	
	Area 4: Repair west bank slope by placing 1-ton loose rock for a distance of 30 linear feet, 450 square feet.	
	Area 5: Repair existing 36-inch diameter side drain pipe at base by placing compacted earthen fill for 25 linear feet, 125 square feet.	
	Area 6: Repair 95 linear feet of existing reinforced concrete channel invert and 30 linear feet of existing concrete side wall under Telephone Road, 1,575 square feet.	
	Area 7: Repair west bank slope by placing 1-ton loose rock for a distance of 105 linear feet, 1,575 square feet.	
	Area 8: Repair east bank slope by placing 1-ton loose rock for 120 linear feet, and repair reinforced concrete over-pour by placing with ¹ / ₂ ton grouted rock for 25 linear feet, 2,175 square feet.	
	Area 9: Repair erosion by placing 1-ton loose rock downstream of existing drop structure for 30 linear feet, 600 square feet.	
	Area 10: Repair east bank slope for 150 linear feet with <i>Enviro-Block</i> .	
	Area 11: Repair east bank slope by placing ¹ / ₂ ton grouted rock for 30 linear feet, 360 square feet.	

Project Information File No. 07-059

	Area 12: Repair east bank slope by placing ¹ / ₂ ton grouted rock for 70 linear feet, 840 square feet.	
	Area 13: Repair existing grouted rock channel invert downstream of an existing reinforced concrete box culvert by placing ¹ / ₄ ton grouted rock for 10 linear feet, 100 square feet. No additional grouted rock will be created or added.	
	Area 14: Repair erosion upstream of Telegraph Road by placing ¹ / ₄ ton grouted rock over 5 linear feet, 50 square feet.	
8. Federal Agency/Permit:	U.S. Army Corps of Engineers NWP Nos. 3 & 33 (Permit No. 2007-477-AJS)	
9. Other Required Regulatory Approvals:	California Department of Fish and Game Streambed Alteration Agreement	
10. California Environmental Quality Act Compliance:	The proposed project was determined to be Categorically Exempt from CEQA by the Ventura County Watershed Protection District pursuant to the CEQA Guidelines, Section (e.g., 15301 Existing Facilities), and recorded with the Ventura County Clerk on July 10, 2007.	
11. Receiving Water:	Harmon Barranca tributary to Santa Clara River (Hydrologic Unit No. 403.11)	
12. Designated Beneficial Uses:	MUN*, IND, PROC, AGR, GWR, FRSH, REC-1, REC-2, WARM, COLD, WILD, RARE, MIGR, WET	
	*Conditional beneficial use	
13. Impacted Waters of the United States:	Non-wetland waters: 0.0022 temporary acres (30 linear feet) and 0.2087 permanent acres (780 linear feet).	

Project Information File No. 07-059

14. Dredge Volume:

15. Related Projects Implemented/to be Implemented by the Applicant: The Applicant has not identified any related projects carried out in the last 5 years or planned for implementation in the next 5 years.

16. Avoidance/
Minimization
Activities:The Applicant has proposed to implement several Best
Management Practices, including, but not limited to, the following:

None

- The repairs will be conducted during the dry season between June and December.
- No vegetation will be removed.
- Natural areas will be protected during construction.
- Limits of avoidance will be demarcated with flagging or fencing.
- Watering during construction will be utilized to reduce wind erosion and dust.
- Temporary debris basins, silt fences, straw bale dikes, sand bags, drainage swales, check dams, sediment traps, or temporary earthen dikes will be utilized to prevent sediments from washing downstream.
- Equipment washing and small batch mixing of concrete and other chemicals will be performed in designated upland areas, and will be lined with an impermeable material.
- All waste, including vegetation, clearing, washing, and grubbing material, equipment maintenance material, building materials and sewage will be disposed of in accordance to all applicable federal, state, and local laws, regulations, and ordinances.
- If a spill incident occurs, any spills or excess of toxic materials will be cleaned immediately and disposed of and reported as required by local, state and federal regulations.
- The contractor will protect stockpiles of earth and other
 - 4 of 6

Project Information File No. 07-059

construction-related materials from being transported from the site by wind or water.

- The contractor will properly store and handle fuels, oils, solvents, and other toxic materials so that soil or surface waters are not contaminated.
- The contractor will protect all approved toxic storage containers from weather, clean spills immediately, and properly dispose of cleanup materials.
- Spills shall not be washed into live streams, channels, drains, or other water conveyance facilities.
- The contractor will not wash waste concrete into the public way or any drainage system.
- Concrete wastes will be retained on-site until they can be recycled or taken of to a legal point of disposal.
- The contractor will not allow sediments and other materials to be tracked from the site by vehicle traffic. Construction entrance roadways will be stabilized to inhibit sediments from being deposited onto public ways.
- The contractor will contain non-stormwater runoff from equipment or vehicle washing and any other activity at the work site.
- At completion of the work, the worksite will be cleared of debris and restored to a condition equal to or better than prior to construction.
- 17. Proposed Compensatory Mitigation:

None

18. Required

The Applicant shall provide compensatory mitigation for the

Project Information File No. 07-059

Compensatory Mitigation: proposed permanent and temporary impacts by creating or restoring 0.5803 acres of riparian habitat within the Santa Clara River Watershed. For mitigation ratios not met onsite, the Applicant must provide in-lieu fees to a third party for mitigation within the Santa Clara River Watershed. See *Attachment B, Conditions of Certifications, Additional Conditions* specifically Items 23 through 26 for the required compensatory mitigation.

Conditions of Certification File No. 07-059

STANDARD CONDITIONS

Pursuant to §3860 of Title 23 of the California Code of Regulations (23 CCR), the following three standard conditions shall apply to this project:

- 1. This Certification action is subject to modification or revocation upon administrative or judicial review, including review and amendment pursuant to §13330 of the California Water Code and Article 6 (commencing with 23 CCR §3867).
- 2. This Certification action is not intended and shall not be construed to apply to any activity involving a hydroelectric facility and requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent Certification application was filed pursuant to 23 CCR Subsection 3855(b) and the application specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.
- 3. Certification is conditioned upon total payment of any fee required pursuant to 23 CCR Chapter 28 and owed by the Applicant.

ADDITIONAL CONDITIONS

Pursuant to 23 CCR §3859(a), the Applicant shall comply with the following additional conditions:

- 1. The Applicant shall submit to this Regional Board copies of any other final permits and agreements required for this project, including, but not limited to, the U.S. Army Corps of Engineers' (ACOE) Section 404 Permit and the California Department of Fish and Game's (CDFG) Streambed Alteration Agreement. These documents shall be submitted prior to any discharge to waters of the State.
- 2. The Applicant shall adhere to the most stringent conditions indicated with either this certification, the CDFG's Streambed Alteration Agreement, or the ACOE Section 404 Permit.
- 3. The Applicant shall comply with all water quality objectives, prohibitions, and policies set forth in the *Water Quality Control Plan, Los Angeles Region (1994)*.
- 4. The Avoidance/Minimization activities proposed by the Applicant as described in Attachment A, No. **16**, are incorporated as additional conditions herein.

Conditions of Certification File No. 07-059

- 5. The Applicant and all contractors employed by the Applicant shall have copies of this Certification, the approved maintenance plan, and all other regulatory approvals for this project on site at all times and shall be familiar with all conditions set forth.
- 6. Fueling, lubrication, maintenance, operation, and storage of vehicles and equipment shall not result in a discharge or a threatened discharge to waters of the State. At no time shall the Applicant use any vehicle or equipment which leaks any substance that may impact water quality. Staging and storage areas for vehicles and equipment shall be located outside of waters of the State.
- 7. All excavation, construction, or maintenance activities shall follow best management practices to minimize impacts to water quality and beneficial uses. Dust control activities shall be conducted in such a manner that will not produce downstream runoff.
- 8. No construction material, spoils, debris, or any other substances associated with this project that may adversely impact water quality standards, shall be located in a manner which may result in a discharge or a threatened discharge to waters of the State. Designated spoil and waste areas shall be visually marked prior to any excavation and/or construction activity, and storage of the materials shall be confined to these areas.
- 9. All waste and/or dredged material removed shall be relocated to a legal point of disposal if applicable. A legal point of disposal is defined as one for which Waste Discharge Requirements have been established by a California Regional Water Quality Control Board, and is in full compliance therewith. Please contact Rodney Nelson, Land Disposal Unit, at (213) 620-6119 for further information.
- 10. The Applicant shall implement all necessary control measures to prevent the degradation of water quality from the proposed project in order to maintain compliance with the Basin Plan. The discharge shall meet all effluent limitations and toxic and effluent standards established to comply with the applicable water quality standards and other appropriate requirements, including the provisions of Sections 301, 302, 303, 306, and 307 of the Clean Water Act. This Certification does not authorize the discharge by the applicant for any other activity than specifically described in the 404 Permit.
- 11. The discharge shall not: a) degrade surface water communities and populations including vertebrate, invertebrate, and plant species; b) promote the breeding of mosquitoes, gnats, black flies, midges, or other pests; c) alter the color, create visual contrast with the natural appearance, nor cause aesthetically undesirable discoloration of the receiving waters; d) cause formation of sludge deposits; or e) adversely affect any designated beneficial uses.

Conditions of Certification File No. 07-059

- 12. The Applicant shall allow the Regional Board and its authorized representative entry to the premises, including all mitigation sites, to inspect and undertake any activity to determine compliance with this Certification, or as otherwise authorized by the California Water Code.
- 13. Application of pesticides must be supervised by a certified applicator and be in conformance with manufacturer's specifications for use. Compounds used must be appropriate to the target species and habitat. All pesticides directed toward aquatic species must be approved by the Regional Board. Pesticide utilization shall be in accordance with State Water Resources Control Board Water Quality Order Nos. 2004-0008-DWQ and 2004-0009-DWQ.
- 14. The Applicant shall not conduct any construction activities within waters of the State during a rainfall event. The Applicant shall maintain **a five-day** (**5-day**) **clear weather forecast** before conducting any operations within waters of the State.
- 15. The Applicant shall not conduct any maintenance activities within waters of the State during a rainfall event, or at any period when site conditions would lead to excessive erosion. If any maintenance activities are to be held within five (5) days of a predicted rainfall event, the Applicant shall stage materials necessary to prevent water degradation on site, and shall ensure that all stabilization procedures are completed prior to the rainfall event.
- 16. If rain is predicted after operations have begun, grading activities must cease immediately and the site must be stabilized to prevent impacts to water quality, and minimize erosion and runoff from the site.
- 17. Sediment removal at each phase shall not go beyond the extent as defined in the application packet.
- 18. The grading, stabilization and re-vegetation will be phased to limit the exposed or working face such that the graded area can be stabilized within 24 hours after the first prediction of rain during the 5-day forecast or within 24 hours after final grading of the phased area.
- 19. The Applicant shall utilize the services of a qualified biologist with expertise in riparian assessments during all construction activities where clearing involves areas to be partially cleared (i.e. some vegetation is to remain in the same reach or in an adjacent reach). The biologist shall be available on site during construction activities to ensure that all protected areas are marked properly and ensure that no vegetation outside the specified areas is removed. The biologist shall have the authority to stop the work, as necessary, if instructions are not followed. The biologist shall be available upon request from this Regional Board for consultation within 24 hours of request of consultation.

Conditions of Certification File No. 07-059

- 20. No activities shall involve wet excavations (i.e., no excavations shall occur below the seasonal high water table). A minimum **5-foot** buffer zone shall be maintained above the existing groundwater level. If construction or groundwater dewatering is proposed or anticipated, the Applicant shall file a **Report of Waste Discharge** to this Regional Board and obtain any necessary NPDES permits/Waste Discharge Requirements prior to discharging waste. Sufficient time should be allowed to obtain any such permits (generally 180 days). If groundwater is encountered without the benefit of appropriate permits, the Applicant shall cease all activities in the areas where groundwater is present, file a Report of Waste Discharge to this Regional Board, and obtain any necessary permits prior to discharging waste.
- 21. All project, construction, or maintenance activities not included in this Certification, and which may require a permit, must be reported to the Regional Board for appropriate permitting. Bank stabilization and grading, as well as any other ground disturbances, are subject to restoration and revegetation requirements, and may require additional Certification action.
- 22. All surface waters, including ponded waters, shall be diverted away from areas undergoing grading, construction, excavation, vegetation removal, and/or any other activity which may result in a discharge to the receiving water. If surface water diversions are anticipated, the Applicant shall develop and submit a **Surface Water Diversion Plan** (plan) to this Regional Board. The plan shall include the proposed method and duration of diversion activities, structure configuration, construction materials, equipment, erosion and sediment controls, and a map or drawing indicating the locations of diversion and discharge points. Contingency measures shall be a part of this plan to address various flow discharge rates. The plan shall be submitted prior to any surface water diversions. If surface flows are present, then upstream and downstream monitoring for the following shall be implemented:
 - pH
 - temperature
 - dissolved oxygen
 - turbidity
 - total suspended solids(TSS)
 - Downstream TSS shall be maintained at ambient levels
 - Where natural turbidity is between 0 and 50 Nephelometric Turbidity Units (NTU), increases shall not exceed 20%. Where natural turbidity is greater than 50 NTU, increases shall not exceed 10%.

Analyses must be performed using approved US Environmental Protection Agency methods, where applicable. These constituents shall be monitored for on a daily basis during the first week of diversion and/or dewatering activities, and then on a weekly basis, thereafter, until the in-stream work is complete.

Conditions of Certification File No. 07-059

Results of the analyses shall be submitted to this Regional Board by the 15th day of each subsequent sampling month. A map or drawing indicating the locations of sampling points shall be included with each submittal. Diversion activities shall not result in the degradation of beneficial uses or exceedance of water quality objectives of the receiving waters. Any such violations may result in corrective and/or enforcement actions, including increased monitoring and sample collection.

- 23. The Applicant shall restore the proposed **0.0294 acres** of TEMPORARY IMPACTS to waters of the United States and all other areas of temporary disturbance which could result in a discharge or a threatened discharge to waters of the State. Restoration shall include grading of disturbed areas to pre-project contours. The Applicant shall implement all necessary Best Management Practices to control erosion and runoff from areas associated with this project.
- 24. The Applicant shall provide COMPENSATORY MITIGATION to offset the proposed temporal loss of **0.0294 acres** waters of the United States by creating or restoring riparian habitat at a minimum **1:1** area replacement ratio (**0.0294 acres**). The Applicant shall also provide compensatory mitigation for the proposed permanent impacts to **0.1837 acres** within waters of the United States/Federal jurisdictional wetlands by creating or restoring riparian habitat/Federal jurisdictional wetland habitat at a minimum **3:1** area replacement ratio (**0.5511 acres**). As an alternative, the Applicant may provide adequate funding to a third party organization for the creation or restoration of **0.5803 acres** of riparian habitat within waters of the United States/Federal jurisdictional wetlands.
- 25. If the Applicant proposes funding to a third-party organization for the creation or restoration of a total of **0.5803 acres** of unvegetated streambed riparian habitat within waters of the United States/Federal jurisdictional wetlands, then funding shall apply to mitigation acreage only, exclusive of administrative costs. The mitigation site shall be located within the Santa Clara Watershed unless otherwise approved by this Regional Board. The Applicant shall submit a **Proposed Mitigation Report** which shall include:
 - (a) Documentation from the third party indicating that funds have been used for mitigation acreage only, which do not include administrative costs.
 - (b) The boundary of the mitigation site shall be clearly identified on a map of suitable resolution and quality and shall also be defined by latitude and longitude.
 - (c) The type(s) of mitigation shall be described (e.g., removal of exotics and/or replanting with native species, etc.)
 - (d) Success criteria shall be established.

This information shall be submitted to this Regional Board for approval prior to any disturbance within waters of the United States and shall include copies of all agreements

Conditions of Certification File No. 07-059

made between the Applicant and a third party organization regarding compensatory mitigation efforts.

- 26. All open space and mitigation areas shall be placed within a conservation easement to ensure preservation in perpetuity. Documentation of proper easement placement shall be submitted to the Regional Board within one year.
- 27. The Applicant shall submit to this Regional Board Annual Mitigation Monitoring Reports (Annual Reports) by January 1st of each year for a minimum period of five (5) years following this issuance of 401 Certification or until mitigation success has been achieved and documented. The Annual Reports shall describe in detail all of the project/construction activities performed during the previous year and all restoration and mitigation efforts; including percent survival by plant species and percent cover. The Annual Reports shall describe the status of other agreements (e.g., mitigation banking) or any delays in the mitigation process. At a minimum the Annual Reports shall include the following documentation and answered appropriately whether or not mitigation has been performed:
 - (e) Color photo documentation of the pre- and post-project and mitigation site conditions;
 - (f) Geographical Positioning System (GPS) coordinates in decimal-degrees format outlining the boundary of the project and mitigation areas;
 - (g) The overall status of project including a detailed schedule of work;
 - (h) Copies of all permits revised as required in Additional Condition 1;
 - (i) Water quality monitoring results for each reach (as required) compiled in an easy to interpret format;
 - (j) A certified Statement of "no net loss" of wetlands associated with this project;
 - (k) Discussion of any monitoring activities and exotic plant control efforts; and
 - (1) A certified Statement from the permittee or his/her representative that all conditions of this Certification have been met.
- 28. Prior to any subsequent maintenance activities within the subject drainages, including clearing, maintenance by-hand, and/or the application of pesticides, the Applicant shall submit to this Regional Board a NOTIFICATION of any such activity. Notification shall include: (a) the proposed schedule; (b) a description of the drainage's existing condition; (c) the area of proposed temporary impact within waters of the State; (c) a description of any existing aquatic resources (e.g., wetland/riparian vegetation); and (d) any proposed

Conditions of Certification File No. 07-059

compensatory mitigation. Notifications must be submitted a minimum of **three (3) weeks** prior to commencing work activities.

- 29. All applications, reports, or information submitted to the Regional Board shall be signed:
 - (a) For corporations, by a principal executive officer at least of the level of vice president or his duly authorized representative, if such representative is responsible for the overall operation of the facility from which discharge originates.
 - (b) For a partnership, by a general partner.
 - (c) For a sole proprietorship, by the proprietor.
 - (d) For a municipal, State, or other public facility, by either a principal executive officer, ranking elected official, or other duly authorized employee.
- 30. Each and any report submitted in accordance with this Certification shall contain the following completed declaration:

"I declare under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who managed the system or those directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Executed on the	day of	at	·
			(Signature)
			(Title)"

- 31. All communications regarding this project and submitted to this Regional Board shall identify the Project File Number **07-059**. Submittals shall be sent to the attention of the 401 Certification Unit.
- 32. Any modifications of the proposed project may require submittal of a new Clean Water Act Section 401 Water Quality Certification application and appropriate filing fee.
- 33. The project shall comply with the local regulations associated with the Regional Board's **Municipal Stormwater Permit** issued to Ventura County and co-permittees under NPDES No. CAS004002 and Waste Discharge Requirements Order No. 00-108. This includes the

Conditions of Certification File No. 07-059

Stormwater Quality Urban Impact Mitigation Plan (SQUIMP) and all related implementing local ordinances and regulations for the control of stormwater pollution from new development and redevelopment. The project shall also comply with all requirements of the National Pollutant Discharge Elimination System (NPDES) **General Permit** for Storm Water Discharges Associated with Construction Activity, Order No. 99-08-DWQ. All stormwater treatment systems shall be located outside of any water of the State and shall not be used as a wetland or riparian mitigation credit.

- 34. Coverage under this Certification may be transferred to the extent the underlying federal permit may legally be transferred and further provided that the Applicant notifies the Executive Officer at least 30 days before the proposed transfer date, and the notice includes a written agreement between the existing and new Applicants containing a specific date of coverage, responsibility for compliance with this Certification, and liability between them.
- 35. The Applicant or their agents shall report any noncompliance. Any such information shall be provided verbally to the Executive Officer within 24 hours from the time the Applicant becomes aware of the circumstances. A written submission shall also be provided within five days of the time the Applicant becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected; the anticipated time it is expected to continue and steps taken or planned to reduce, eliminate and prevent recurrence of the noncompliance. The Executive Officer, or an authorized representative, may waive the written report on a case-by-case basis if the oral report has been received within 24 hours.
- 36. *Enforcement*:
 - (a) In the event of any violation or threatened violation of the conditions of this Certification, the violation or threatened violation shall be subject to any remedies, penalties, process or sanctions as provided for under State law. For purposes of section 401(d) of the Clean Water Act, the applicability of any State law authorizing remedies, penalties, process or sanctions for the violation or threatened violation constitutes a limitation necessary to assure compliance with the water quality standards and other pertinent requirements incorporated into this Certification.
 - (b) In response to a suspected violation of any condition of this Certification, the State Water Resources Control Board (SWRCB) or Regional Water Quality Control Board (RWQCB) may require the holder of any permit or license subject to this Certification to furnish, under penalty of perjury, any technical or monitoring reports the SWRCB deems appropriate, provided that the burden, including costs, of the reports shall be a reasonable relationship to the need for the reports and the benefits to be obtained from the reports.

Conditions of Certification File No. 07-059

- (c) In response to any violation of the conditions of this Certification, the SWRCB or RWQCB may add to or modify the conditions of this Certification as appropriate to ensure compliance.
- 37. This Certification shall expire **five (5) years** from date of this Certification. The Applicant shall submit a complete application prior to termination of this Certification if renewal is requested.