**ASSOCIATED LABORATORIES****806 North Batavia - Orange, California 92868 - 714/771-6900****FAX 714/538-1209**

CLIENT Stetson Engineers Inc. (10442)
ATTN: Ken Reich
861 Village Oaks
Suite 100
Covina, CA 91724

LAB REQUEST 228808

REPORTED 02/20/2009

RECEIVED 02/09/2009

PROJECT #2258
Lower SMR Watershed

SUBMITTER Client

COMMENTS

This laboratory request covers the following listed samples which were analyzed for the parameters indicated on the attached Analytical Result Report. All analyses were conducted using the appropriate methods as indicated on the report. This cover letter is an integral part of the final report.

Order No.

969529

969530

Client Sample Identification

#11044350 Sandia Creek

Laboratory Method Blank

Thank you for the opportunity to be of service to your company. Please feel free to call if there are any questions regarding this report or if we can be of further service.

ASSOCIATED LABORATORIES by,

Edward S. Behare, Ph.D.
Vice President

NOTE: Unless notified in writing, all samples will be discarded by appropriate disposal protocol 30 days from date reported.

The reports of the Associated Laboratories are confidential property of our clients and may not be reproduced or used for publication in part or in full without our written permission. This is for the mutual protection of the public, our clients, and ourselves.

TESTING & CONSULTING
Chemical
Microbiological
Environmental

Order #: 969529 Client Sample ID: #11044350 Sandia Creek

Matrix: WATER

Date Sampled: 02/09/2009

Time Sampled: 12:25

Method	Analyte	Result	DF	EQL	MDL	Units	Date/Analyst
10200H	Chlorophyll	10.4	1	1.0		mg/M3	02/10/09 HK
2510B	Specific Conductance	1310	1	1.0	0.86	umhos/c	02/12/09 DV
300.0	Nitrate (as NO3)	17.2	1	0.44	0.07	mg/L	02/10/09 CM
300.0	Nitrite (as NO2)	ND	1	0.33	0.06	mg/L	02/10/09 CM
350.1	Ammonia -N	0.40	1	0.1	0.01	mg/L	02/14/09 TP
351.2	Total Kjeldahl Nitrogen (TKN)	1.24	1	0.4	0.06	mg/L	02/14/09 TP
4500-H+B	pH	7.73	1			NA	02/09/09 DV
4500-P-B.5-E	Total Phosphorus as P	0.40	1	0.02	0.01	mg/L	02/18/09 DK
4500-P-E	Ortho Phosphate as PO4	0.22	1	0.06	0.015	mg/L	02/10/09 DK
5210B	BOD	4	1	3.0	1.5	mg/L	02/10/09 LT

EQL = Estimated Quantitation Limit, MDL = Method detection limit, DF = Dilution Factor
ND = Not detected below indicated MDL, J=Trace, S = Surrogate outside control limits

ASSOCIATED LABORATORIES

Analytical Results Report

Lab Request 228808 results, page 1 of 2



Order #: 969530

Client Sample ID: Laboratory Method Blank

Matrix: WATER

Method	Analyte	Result	DF	EQL	MDL	Units	Date/Analyst
2510B	Specific Conductance	0.52	1	1.0	0.86	umhos/c	02/12/09 DV
300.0	Nitrate (as NO3)	ND	1	0.44	0.07	mg/L	02/10/09 CM
300.0	Nitrite (as NO2)	ND	1	0.33	0.06	mg/L	02/10/09 CM
350.1	Ammonia -N	ND	1	0.1	0.01	mg/L	02/14/09 TP
351.2	Total Kjeldahl Nitrogen (TKN)	ND	1	0.4	0.06	mg/L	02/14/09 TP
4500-H+B	pH	5.25	1			NA	02/09/09 MS
4500-P-B.5-E	Total Phosphorus as P	ND	1	0.02	0.01	mg/L	02/18/09 DK
4500-P-E	Ortho Phosphate as PO4	ND	1	0.06	0.015	mg/L	02/10/09 DK
5210B	BOD	ND	1	3.0	1.5	mg/L	02/10/09 LT

EQL = Estimated Quantitation Limit, MDL = Method detection limit, DF = Dilution Factor
ND = Not detected below indicated MDL, J=Trace, S = Surrogate outside control limits

ASSOCIATED LABORATORIES

Analytical Results Report



ASSOCIATED LABORATORIES
QA REPORT FORM

QC Sample : LR 228793-969450

Matrix: WATER

Prep. Date: 02/10/09

Analysis Date: 02/11/09

Lab ID#'s in Batch: LR 228602, 228793, 228828, 228829, 228804, 228808, 228814, 228818, 228822

MATRIX SPIKE / MATRIX SPIKE DUPLICATE RESULT

Reporting Units = mg/L

Test	Method	Sample Result	Spike Added	Matrix Spike	Matrix Spike Dup	%Rec MS	%Rec MSD	RPD
CL	300.0	ND	200	182	184	91	92	1
SO4	300.0	2	200	197	195	98	96	1
Br ⁻	300.0	ND	100	96	95	96	95	1
NO3	300.0	1.2	100	94.7	92	94	91	3
NO2	300.0	0.1	200	201	198	100	99	1

RPD = Relative Percent Difference of Matrix Spike and Matrix Spike Dup

%REC-MS & MSD = Percent Recovery of Matrix Spike & Matrix Spike Duplicate

%Rec Limits = 80 - 120

RPD Limits = 20

PREPARATION BLANK / LAB CONTROL SAMPLE RESULTS

Test	Method	PREP BLK	LCS				
		Value	Result	True	%Rec	L.Limit	H.Limit
CL	300.0	ND	41	40	103	90%	110%
SO4	300.0	ND	41	40	102	90%	110%
Br ⁻	300.0	ND	20	20	102	90%	110%
NO3	300.0	ND	19.5	20	98	90%	110%
NO2	300.0	ND	9.4	10	94	90%	110%

VALUE = Preparation Blank Value; ND = Not-Detected

LCS = Lab Control Sample Result

TRUE = True Value of LCS

L.LIMIT / H.LIMIT = LCS Control Limits

**ASSOCIATED LABORATORIES
QA REPORT FORM**

QC Sample: 228793-969444

Matrix: WATER

Prep. Date: 02/14/09

Analysis Date: 02/15/09

Lab ID#'s in Batch: 228793, 228808, 228814, 228818, 228822, 228825

MATRIX SPIKE / MATRIX SPIKE DUPLICATE RESULT

Reporting Units = mg/L

Test	Method	Sample Result	Spike Added	Matrix Spike	Matrix Spike Dup	%Rec MS	%Rec MSD	RPD
NH3-N	350.1	1.39	10.00	11.70	11.80	103	104	1

ND = Not Detected

RPD = Relative Percent Difference of Matrix Spike and Matrix Spike Duplicate

%REC-MS & MSD = Percent Recovery of Matrix Spike & Matrix Spike Duplicate

<i>%REC LIMITS = 80 - 120</i>

<i>RPD LIMITS = 20</i>

PREPARATION BLANK / LAB CONTROL SAMPLE RESULTS

PREP BLK	LCS				
Value	Result	True	%Rec	L.Limit	H.Limit
ND	4.84	5.00	97	80%	120%

Value = Preparation Blank Value

LCS Result = Lab Control Sample Result

True = True Value of LCS

L.Limit / H.Limit = LCS Control Limits

ASSOCIATED LABORATORIES QA REPORT FORM

QC Sample: 228799-969478

Matrix: WATER

Prep. Date: 02/14/09

Analysis Date: 02/15/09

Lab ID#'s in Batch: 228799, 228808, 228814, 228818, 228822, 228825, 228804,
228829, 228720, 228722, 229019

MATRIX SPIKE / MATRIX SPIKE DUPLICATE RESULT

Reporting Units = mg/L

Test	Method	Sample Result	Spike Added	Matrix Spike	Matrix Spk. Dup	%Rec MS	%Rec MSD	RPD
TKN	351.2	2.65	25.0	26.3	27.2	95	98	3

ND = Not Detected

RPD = Relative Percent Difference of Matrix Spike and Matrix Spike Duplicate

%REC-MS & MSD = Percent Recovery of Matrix Spike & Matrix Spike Duplicate

%REC LIMITS = 80 - 120

RPD LIMITS = 20

PREPARATION BLANK / LAB CONTROL SAMPLE RESULTS

Test	Method	PREP BLK	LCS				
		Value	Result	True	%Rec	L.Limit	H.Limit
TKN	351.2	ND	2.37	2.50	95	80%	120%

Test	Method	DIG CHK				
		Result	True	%Rec	L.Limit	H.Limit
TKN	351.2	3.12	3.17	98	85%	115%

Value = Preparation Blank Value

LCS Result = Lab Control Sample Result

True = True Value of LCS

L.Limit / H.Limit = LCS Control Limits

**ASSOCIATED LABORATORIES
QA REPORT FORM - INORGANICS**

QC Sample: LR 228804

Matrix: WATER

Prep. Date: 02/10/09

Analysis Date: 02/10/09

Lab ID#'s in Batch: LR 228804, 228808, 228814, 228818, 228822, 228825, 228828, 228829, 228827

MATRIX SPIKE / MATRIX SPIKE DUPLICATE RESULT

Reporting Units = mg/L

Test	Method	Sample Result	Spike Added	Matrix Spike	Matrix Spike Dup	%Rec MS	%Rec MSD	RPD
Ortho-Phosphate (as PO ₄)	4500-P-E	0.53	1.53	2.08	2.07	101	101	0
Ortho-Phosphate (as P)	4500-P-E	0.17	0.50	0.68	0.68	101	101	0

RPD = Relative Percent Difference of Matrix Spike and Matrix Spike Duplicate
 %REC-MS & MSD = Percent Recovery of Matrix Spike & Matrix Spike Duplicate

%REC LIMITS = 75 - 125
RPD LIMITS = 20

PREPARATION BLANK / LAB CONTROL SAMPLE RESULTS

Test	Method	PREP BLK	LCS				
		Value	Result	True	%Rec	L.Limit	H.Limit
Ortho-Phosphate (as PO ₄)	4500-P-E	ND	1.01	1.00	101	80%	120%
Ortho-Phosphate (as P)	4500-P-E	ND	0.33	0.33	101	80%	120%

Value = Preparation Blank Value; ND = Not-Detected
 LCS Result = Lab Control Sample Result
 True = True Value of LCS
 L.Limit / H.Limit = LCS Control Limits

ASSOCIATED LABORATORIES
LCS REPORT FORM

QC Sample: Std. Sol

Matrix: WATER

Prep. Date: February 10, 2009

Analysis Date: February 15, 2009

Lab ID#'s in Batch: 228902, 228844, 228804, 228828, 228825, 228822, 228829, 228818, 228814, 228808

Reporting Units = mg/L

PREPARATION BLANK / LAB CONTROL SAMPLE RESULTS

Test	Method	PREP. BLANK	LCS				
		Value	Result	True	%Rec	L.Limit	H.Limit
BOD	405.1	ND	193	200	97	80%	120%

Value = Preparation Blank Value; ND = Not-Detected

LCS Result = Lab Control Sample Result

True = True Value of LCS


L.Limit / H.Limit = LCS Control Limits

228808

CHAIN OF CUSTODY FOR LOWER SANTA MARGARITA RIVER WATERSHED MONITORING PROGRAM

Client Name/Account #: Stetson Engineers Inc.
 Address: 861 Village Oaks Dr., Suite 100
 City/State/Zip: Covina, CA 91724
 Project Manager: Ken Reich
 Telephone Number: 626-967-6202 Fax No.: 626-331-7065
 Sampler Name: (Print) Joel Barnard / Ken Reich
 Sampler Signature: _____
 Report To: Ken Reich
 Invoice To: Ken Reich
 Quote #: _____
 Project ID: Lower SMR Watershed
 Project #: 2258

Sample ID / Description	Sampling Information				Preservative							Analyses			Reporting/TAT								
	Date Sampled	Time Sampled	No. of Containers Shipped	Grab	Composite	Field Filtered	Ice	HNO ₃	HCl	NaOH	H ₂ SO ₄	None	Other	Conductivity, Nitrate, Nitrite, Ortho Phosphate, pH	BOD5	Chlorophyll a	Total Phosphorous, TKN, Ammonia	RUSH TAT	Standard TAT	Fax Results	Send QC with report		
DAY 4 FEBRUARY 2009 INDEX SAMPLING																							
#11044350 Sandia Creek	2/9	12:25	1	X			X					X		X						X		X	
#11044350 Sandia Creek			1	X			X					X			X					X		X	
#11044350 Sandia Creek			1	X			X					X				X				X		X	
#11044350 Sandia Creek			1	X			X					X					X			X		X	
Special Instructions: 1) Electronic Data Deliverable Required 2) "J" flag results between the MDL and the reporting limit																							
Relinquished by: <i>[Signature]</i>		Date: 2/9/09	Time: 17:21	Received by: <i>[Signature]</i>												Time: 17:17							
Relinquished by:		Date:	Time:	Received by Associated Labs:												Time:							
Laboratory Comments: Temperature Upon Receipt: Y N VOCs Free of Headspace? Y N																							

**ASSOCIATED LABORATORIES**

806 North Batavia – Orange, California 92868 – 714-771-6900

FAX 714-538-1209

SAMPLE ACCEPTANCE CHECKLIST**Section 1**

Client: Stetson
Date Received: 2-9-09
Sample(s) received in cooler: Yes
Shipping Information: _____

Project: _____

Sampler's Name: Yes No

No (Skip Section 2)

Section 2

Was the cooler packed with: Ice Ice Packs Bubble Wrap Styrofoam
Paper None Other _____

Cooler or box temperature: 3.4

(Acceptance range is 2 to 6 Deg. C.)

Section 3

	YES	NO	N/A
Was a COC received?	<u>Yes</u>		
Is it properly completed? (IDs, sampling date and time, signature, test)	<u>Yes</u>		
Were custody seals present?		<u>Yes</u>	
If Yes – were they intact?			<u>Yes</u>
Were all samples sealed in plastic bags?	<u>Yes</u>		
Did all samples arrive intact? If no, indicate below.	<u>Yes</u>		
Did all bottle labels agree with COC? (ID, dates and times)	<u>Yes</u>		
Were correct containers used for the tests required?	<u>Yes</u>		
Was a sufficient amount of sample sent for tests indicated?	<u>Yes</u>		
Was there headspace in VOA vials?			<u>Yes</u>
Were the containers labeled with correct preservatives?	<u>Yes</u>		
Was total residual chlorine measured (Fish Bioassay samples only)? *	<u>Yes</u>		<u>Yes</u>

*: If the answer is no, please inform Fish Bioassay Dept. immediately.

Section 4

Explanations/Comments

Section 5Was Project Manager notified of discrepancies: Y / N N/ACompleted By: [Signature]Date: 2-9-09